INDIANA DEPARTMENT OF TRANSPORTATION
Driving Indiana's Economic Growth

100 North Senate Avenue
Room N925
Indianapolis, Indiana 46204

PHONE: (317) 232-5502
FAX: (317) 234-5133

Mitchell E. Daniels, Jr., Governor
Michael B. Cline, Commissioner

January 31, 2011

CONSTRUCTION MEMORANDUM
11-01

TO: District Deputy Commissioners
District Construction Directors
District Area Engineers
District LPA Coordinators
Field Engineers
Technical Services Directors
Project Engineers/Supervisors

FROM: Mark A. Miller, Director
Division of Construction Management

SUBJECT: Position of staggered barricades

Recently it has been discovered there is a conflict between the Standard Drawing 801-TCDT-02 and the Indiana Manual on Uniform Traffic Control Devices (IMUTCD). The IMUTCD designates the placement of staggered barricades so that the barricade in the lane of approaching traffic is closest to the vehicle. The Standard Drawing will be revised to match the IMUTCD.

Until the revised Standard Drawing is published, staggered barricades should be placed in accordance with the IMUTCD as illustrated in Chapter 6H (http://www.in.gov/dot/div/contracts/design/mutcd/pubs/a15Ch6H(Final2008).pdf)

MAM/JPM