

March 27, 2002

Mr: Chad A. Modesitt, P.E. Project Manager The HNTB Companies 111 Monument Circle Indianapolis, IN 46204-5178

Re: Geotechnical Exploration and Engineering Services INDOT Project No. CM-9945() & STP-N606() Des. No. 0100881 & 0088390 61<sup>st</sup> Avenue Widening and Improvements Hobart, Lake County, Indiana PSI Project No. 016-15159

Dear Mr. Modesitt:

We have completed the geotechnical exploration for the above referenced project. The purpose of the study was to obtain subsurface information from the site and develop recommendations to aid in design of the proposed roadway reconstruction and improvements. This report presents our soil boring logs, laboratory test results, and roadway recommendations.

We appreciate the opportunity to provide geotechnical engineering services for this project. If there are any questions regarding the information contained in this report, please contact us at (317) 216-7131.

Respectfully,

**PROFESSIONAL SERVICE INDUSTRIES, INC.** 

Peter Lee

Peter S. Lee, Ph.D., P.E. Senior Engineer

Élizabeth M. Dwyre, P.E. Regional Engineer



10 pc: Mr. Athar Khan, P.E., INDOT, Materials and Tests Division

# TABLE OF CONTENTS

EX	EXECUTIVE SUMMARY				
SU	; J <b>MI</b> N	MARY	OF GEOTECHNICAL EXPLORATION	i	
1.	IN'	ГROD	DUCTION	1	
		1.1	Project Identification	1	
		1.2	Project Description		
		1.3	Scope of Services and Procedures		
2.	GE	ENER/	AL SITE CONDITIONS	4	
		2.1	General Geology		
		2.2	Topography of the Area	4	
3.	PR	OCEI	DURES		
		3.1	Field Exploration		
		3.2	Laboratory Testing	7	
4.	RE	SULT	ГЅ		
	t i j	4.1	General Subsoil Conditions		
		4.2	Groundwater Conditions Soil Subgrade Investigation Summary		
		4.3	Soil Subgrade Investigation Summary		
5.	ĄN	ALY	SES AND RECOMMENDATIONS		
2.4		5.1	Cut and Fill Sections		
		5.2	Ground Improvements		
		5.3	4-Sided Reinforced Concrete Box Culvert (Structure No. 191)		
		5.4	General Pavement Design Considerations		
		5.5	Recommended CBR Values		
		5.6	Subsurface Drain Recommendations		
6.	CC		RUCTION CONSIDERATIONS		
		6.1	Subgrade Preparation	27	
		6.2	Fill Placement and Compaction		
		6.3	Storm Sewer and Sanitary Sewer Lines		
		6.4	Excavations		
		6.5	Groundwater Control		
7.	RI	EPOR	T LIMITATIONS		

# APPENDIX

### SUMMARY OF GEOTECHNICAL EXPLORATION

### 1. Project Description

The City of Hobart plans a roadway widening and improvements along 61<sup>st</sup> Avenue (from about 200 feet east of Marcella Boulevard to about 750 feet east of Colorado Street), and Colorado Street near the intersection with 61<sup>st</sup> Avenue. We understand this project will include widening the existing two-lane roadway to mostly four lanes with additional left turn lanes at the intersections, resurfacing the existing pavement, storm sewer improvements, and culvert replacement. The western portion of the project (from Station 10+00 to 27+95.56, Line "A") is identified as INDOT Project No. CM-9945() with Designation No. 0100881. The eastern portion of the project (from Station 27+95.56 to Station 62+04, Line "A", and "S-Lines") is identified as Project No. STP-N606() with Designation No. 0088390.

### 2. Subsurface Conditions

Fill materials, such as silty clay and clay loam, were encountered below the surficial pavement materials to depths of about 8 feet (2.4 m) at Boring TB-1-SG. Below the surficial pavement and topsoil, cohesive fill materials or natural clay soils were generally encountered to depths of about 12 to 20 feet (3.7 to 6.1 m), elevation 597 to 622 feet (182.0 to 189.6 m), or to the explored depths of borings at Borings RB-8, RB-10-SG, and RB-11-SG. Below the natural clay soils, intermediate sand and sandy gravel soils were encountered at depths of about 12 to 18 feet to the explored depths of borings RB-1-SG through RB-7-SG and RB-9-SG. However, sand and sandy gravel soils were encountered between depths of about 22 to 42 feet (6.7 to 12.8 m) from existing grade at Borings TB-1-SG, or about 12 to 32 feet (3.7 to 9.8 m) at TB-2, or elevation 597 to 577 feet (182.0 to 175.9 m). Organic clay soils, such as silty clay loam (A-5) and loam (A-4) with little organic matter and trace marl, were encountered below the existing embankment fills near the existing culvert structure to a depth of about 22 feet (6.7 m) at Boring TB-1-SG, or below the surficial topsoil to a depth of about 12 feet (3.7 m) at Boring TB-2.

Based on the moisture state of the retrieved samples, the soil color change from brown to gray, the reported groundwater observations, we estimate the prevailing groundwater level is at or below depths ranging between about 1.5 to 16.5 feet (0.5 to 5.0 m) below existing grade, approximately elevation 609 to 624 feet (185.6 to 190.2 m).

### 3. Ground Improvements near the Proposed Box Culvert Structure

Based on Borings TB-1-SG and TB-2 performed for the proposed precast 4-sided box culvert, the organic clay soils were encountered below the embankment fill to a depth of about 22 feet (6.7 m) at TB-1-SG, and below the surficial topsoil to a depth of about 12 feet (3.7 m) at TB-2. Delineation of clay soils with marl/organic matter is not under our scope of works for this project, therefore, PSI did not perform delineation for cost estimate purposes.

Based on the proposed height of embankment fill and consolidation parameters of clay soils with marl/organic matter, we anticipate primary consolidation settlement up to about 14 inches (356 mm) could develop at Boring TB-2. We anticipate primary consolidation settlement may be achievable within 11<sup>1</sup>/<sub>2</sub> years, after the placement of full-height of embankment fills. Secondary settlement of the these organic clay soils up to 30 years after construction could be in a range of about <sup>1</sup>/<sub>2</sub> to 1 inch (13 to 25 mm).

Therefore, we have considered soil improvements for the embankment and box culvert constructions near the existing creek. The selection of remedies was based on five (5) functions.

i

- Reducing settlement to a tolerable range without a long construction delay.
- Providing adequate embankment slope stability.
- Uniformly supporting the proposed precast 4-sided precast box culvert.
- Providing the support to the existing gas pressure main due to the potential of excessive settlement.
- Providing support to the storm sewer to be installed between Structure No. 187 and 196.

We anticipate excessive settlement could potentially damage the proposed new 4-sided precast concrete box culvert structure and sewers. In addition, 9-year waiting period prior to pavement construction is not practical for this project due to the high traffic volume on existing 61<sup>st</sup> Avenue. Based on the potential quantity of removal and replacement, or required waiting period of about nine years for at least about 93 percent of primary consolidation, or required adequate support to the proposed precast culvert structure and existing gas pressure main, we anticipate vibro-concrete columns (VCC) are likely a feasible alternative for this project.

Vibro Concrete Column (VCC) – To reduce the excessive settlement, to uniformly support the proposed precast 4-sided reinforced concrete box culvert and sewers, and to limit the risk of overstressing the existing gas pressure main, we consider Vibro Concrete Column (VCC) is a relatively fast and feasible scheme.

We anticipate VCC installed at a 6 feet by 6 feet grid may be required. The VCC grid should be adjusted or additional VCC elements added to provide concentric support along the box culvert and storm sewer alignments. The VCC elements below the box culvert and storm sewer must have their top of VCC elements set below the structure invert elevations. Other VCC elements that will support embankment fill could have top of VCC elements established near the existing grades. The VCC elements should also be spaced to avoid the gas main, and a reinforced concrete cap should be constructed to span between VCC elements to support the fill load directly over the gas main. Also, to uniformly support the proposed embankment fill, precast 4-sided reinforced concrete box culvert, and sewer over VCC, we recommend two layers of geogrid reinforced crushed aggregate (one foot for each layer) be placed over the installed VCC underneath the precast box culvert and sewer, and three layers of geogrid reinforced crushed aggregate underneath the proposed embankment fills. We anticipate dewatering by means of wellpoints or deep wells may be necessary along the culvert and storm sewer alignments in order to excavate for the structure and install the granular/geogrid blankets.

N-values of the existing embankment clay fill encountered at Boring TB-1-SG generally ranged from 2 to 11 bpf, with unconfined compressive strength ranging from 1/4 to 11/2 tsf. We anticipate pre-drilling through the existing roadway embankment may be required prior to VCC installation.

The organic soils were generally encountered near the existing ground surface in the widening areas near the creek. (see the attached Summary of Soundings) N-values of the existing organic soils generally ranged from weight of hammer (WHO) to 5 bpf. Therefore, we anticipate a drainage blanket will be required prior to the construction to provide an appropriate working platform and drainage path, and to protect the exposed portions of VCC from construction traffic and freezing temperatures. The working platform should be a granular material with maximum particle size between 1 and 2 inches, and less than 10 percent passing the No. 200 sieve, such as INDOT No. 2. The drainage blanket should be at least a continuous 24 to 36 inches (610 to 915 mm) thick. If the VCC and blanket are placed during the winter months then an additional layer of fill will be required to prevent the ends of the VCC from freezing.

For bidding purposes, the plan limits of VCC along the alignment should be assumed to extend from Station 50+00 to 52+50, Line "A". The actual limits may require revision based on encountered organic soil limits. The plan limits of VCC in width should extend a minimum of 6 feet beyond the toe of the embankment, or greater as determined by the VCC contractor. Plan limits of the VCC also must extend at least to the limits of the box culvert wingwalls.

The VCC contractor should submit a detailed plan for layout and method of installation of the VCC to the design engineer for review. Specific equipment and installation procedures to achieve the specified criteria are the contractor's responsibility. Special provision and recommendations for field inspection for Vibro-compacted concrete columns are included in the Appendix of this report. Specific modifications recommended to tailor the guide specifications to the requirements of this project are marked on the Special Provision. We strongly recommend review of the required contractor submittals be performed by PSI and INDOT Division of Materials and Tests. Full-time quality assurance during construction should be performed by a qualified engineering technician or staff engineer working under the direction of the project geotechnical consultant. We recommend full-time quality assurance during ground improvement construction be performed by PSI or by INDOT Division of Materials and Tests.

# 4. 4-Sided Precast Reinforced Concrete Box Culvert (Structure 191)

We recommend the bridge structure as well as streambed be protected from scouring and erosion with a minimum 1.2 m (4 feet) of riprap at both ends. We have assumed City of Hobart and design consultant, HNTB, will select VCC as the supports for the new culvert structure and roadway embankment. The vibro-concrete columns need to be penetrated the near surface marly soils to the underlying sand or sandy gravel, at about elevation 587 feet. The culvert foundations bearing on the geogrid-reinforced layer placed over the VCC may be proportioned using a net allowable pressure of 3,000 psf. The maximum net allowable soil bearing pressure is that pressure which may be transmitted to the bearing material in excess of the final, minimum surrounding overburden pressure. We estimate total settlement of the culvert structure supported on VCC deep foundation may be about ½ to 1 inch, with differential settlement of about half of the total settlement. In order to uniformly support the proposed culvert structure, we recommend at least two layers (12 inches each) of geogrid-reinforced crushed aggregate, such as INDOT 53, be placed underneath the proposed culvert structure.

We recommend the proposed wingwalls be supported on the same type of VCC deep foundation as the culvert structure. The geogrid-reinforced crushed aggregate should also be placed on top of the VCC to uniformly support the wingwalls. The following additional soil parameters are also provided for wingwall design, as requested in the Memorandum issued on April 12, 1999, by INDOT, Department of Materials and Tests.

- Friction Angle,  $\delta = 30^{\circ}$
- Friction Factor,  $\tan \delta = 0.58$
- Angle of Internal Friction of the geogrid reinforced foundation soil,  $\phi = 32^{\circ}$
- Ultimate adhesion between the foundation soil and concrete footing, C<sub>a</sub> = N/A
- Ultimate cohesion,  $C_{ult} = N/A$

### 5. Storm Sewer and Sanitary Sewer Lines

Based on the soil conditions from borings performed along existing 61<sup>st</sup> Avenue, the soils at the bearing depth of manholes and sewer lines should generally be suitable for support of the structures except within

the area where organic silty clay loam and loam soils were present between Station 50+00 and 52+50, Line "A". Adequate control of groundwater will be necessary to preserve subgrade stability, particularly in the sewer excavations between Station 25+00 and 55+00, Line "A". If loose sand is present at the proposed sewer bearing elevations, we recommend the proposed subgrades be undercut a minimum of 0.5 m (18 inches), and backfilled with compacted INDOT No. 53 crushed aggregate to the proposed pipe invert elevation. The purpose of the undercut and replacement is to aid in bridging the underlying loose sand and providing a stable base for the pipe. The aggregate pad should extend laterally a minimum of 0.5 m (18 inches) from the edge of the pipe for stability. The contractor should support the excavations with appropriate shoring to avoid undermining the soil supporting the roadway and existing utilities.

For the storm sewers located near the existing creek, organic silty clay loam soils are likely to be encountered at the proposed sewer bearing elevations. We recommend the proposed subgrades be undercut a minimum of 2 feet (0.6 m), and backfilled with two layers of geogrid reinforced INDOT No. 53 crushed aggregate to the proposed pipe invert elevation as recommended for the proposed box culvert structure 191.

The INDOT standard drainage structure installation details, Figure 16, is included in the Appendix. "B" Borrow surrounding all pipe structures in the excavated trenches should be compacted to 95 percent of the maximum dry density as determined by AASHTO T-99 (Standard Proctor). The soil in the bottom of the excavations, any bedding material and the engineered fill for structure backfill, should be tested to determine that tested locations comply with this density criterion. If 95 percent of the maximum dry density can not be obtained at the bottom of the excavations, or in the others areas, the Geotechnical Section of INDOT should be contacted for additional recommendations.

When the level of the fill reaches the top of the structure, two lifts, about 150 mm (6 inches) each, should be carefully spread and hand compacted over the structure without the use of heavy equipment. The backfill should be compacted to at least 95 percent of the maximum dry density as determined by AASHTO T-99 except the first 2 lifts above the structure. Mechanical compaction over the sewer structures may commence after the second lift is placed and compacted.

It is important to protect the sewer structures during construction. To avoid imposing concentrated loads far in excess of those the drainage structures would normally carry, heavy construction equipment should not cross the structures until fill placement and compaction is completed. Also, heavy vehicles moving too close to the walls of the structures can create an eccentric loading with potentially harmful results.

### 6. Recommended CBR Values

PSI evaluated the most critical and predominant plastic (cohesive) soil types encountered within the proposed new pavement areas along the proposed 61<sup>st</sup> Avenue alignment for subgrade strength, based on the California Bearing Ratio (CBR) tests. The most predominant plastic soil at subgrade elevations within the proposed pavement area was silty clay loam, with about 77 percent of silt and clay, and plasticity index (PI) of 10. Based on AASHTO classification system, the most predominant cohesive soils within the proposed new pavement area was classified as A-4.

The CBR value of the silty clay loam sample, compacted to 97 percent of the maximum dry density as determined by AASHTO T-99, Standard Proctor Method, are provided in the table below.

Location	Depth (ft)	Soil Type	% Max. Dry Density	Test CBR Value @ 97 %
RB-2	1-3	Silty Clay Loam, A-4(7)	97	3.3

### In the Fill Areas

Based on the INDOT Design Memorandum, Subgrade Treatment Recommendations, dated August 23, 2001, we recommend 24 inches (600 mm) subgrade treatment for the fill areas in this project. Due to the presence of more cohesive silty clay and clay soils (A-7-6) with PI over 20, therefore, we recommend a CBR value of 2.5 be used for pavement design rather than the higher maximum value of 3.3.

### In the Cut Areas

Based on the preliminary Road Plans provided by The HNTB Companies, the projected AADT on existing  $61^{st}$  Avenue ranged from about 11,680 vehicles per day (VPD) in 2003 to 15,650 VPD by 2023. The total subgrade treatment area is more than 10,000 yd<sup>2</sup>. Based on Subgrade Treatment Guidelines prepared by INDOT, we recommend 16 inches (400 mm) chemical modification (or any alternative described in Section 207.04(a).1), with an estimated CBR value of 2.5 for the pavement design.

During the site preparation operations, the subgrade soil should be evaluated by the project geotechnical engineer to verify the soil type meets the design CBR criteria.

The owner/designer should not rely solely on this Executive Summary and must read and evaluate the entire contents of this report prior to utilizing our engineering recommendations in preparation of design/construction documents.

v

Report Prepared By:

Peter S. Lee, Ph.D., P.E. Senior Engineer Report Reviewed By:

Elizabeth M. Dwyre, P.E. Regional Engineer

# 1. INTRODUCTION

### 1.1. Project Identification

The City of Hobart plans a roadway widening and improvements along 61<sup>st</sup> Avenue (from about 200 feet east of Marcella Boulevard to about 750 feet east of Colorado Street), and Colorado Street near the intersection with 61<sup>st</sup> Avenue. We understand this project will include widening the existing two-lane roadway to mostly four lanes with additional left turn lanes at the intersections, resurfacing the existing pavement, storm sewer improvements, and culvert replacement. The western portion of the project (from Station 10+00 to 27+95.56, Line "A") is identified as INDOT Project No. CM-9945() with Designation No. 0100881. The eastern portion of the project (from Station 62+04, Line "A", and "S-Lines") is identified as Project No. STP-N606() with Designation No. 0088390. The extent of the proposed construction is shown on the Site Location Plan included as Figure 1 in the Appendix.

### **1.2 Project Description**

The proposed improvements along 61<sup>st</sup> Avenue begins at Station 10+00, Line "A", about 200 feet east of Marcella Boulevard, and ends at Station 62+04, Line "A", about 750 feet east of Colorado Street. In addition, this project also includes roadway improvements along Colorado Street, from Station 42+54 to Station 50+00, Line "S-4-A", at the intersection with 61<sup>st</sup> Avenue. The side street improvements along Line "A" include Line "S-1-A" (Liverpool Road), "S-2-A" (S. Minnesota Street), "S-3-A" (N. Minnesota Street), and "S-4-A" (Colorado Street). The total length of street improvements is approximately 1.14 mile (1.83 km), including about 0.34 mile (0.54 km) for the western portion of the project (Des. No. 0100881), about 0.65 mile (1.03 km) on the eastern portion of the project (Des. No. 0088390), and about 0.17 mile (0.26 km) on the side streets ("S-Lines").

Based on the provided preliminary Road Plans, the proposed storm sewer trunkline is located to the north of existing 61<sup>st</sup> Avenue, and is generally parallel to existing 61<sup>st</sup> Avenue. The proposed

storm sewer manhole structures are generally founded at depths of about 8.5 to 18.0 feet (2.6 to 5.5 m) below existing grade, with bottom of invert elevation ranging from about 608.52 to 623.66 feet (185.5 to 190.1 m). The proposed sanitary sewer trunkline is also planned at depths of about 7.7 to 15.4 feet (2.3 to 4.7 m) below existing grade between station 14+00 to 28+10, Line "A". We understand the majority of the existing pavement will be removed to allow subgrade regrading within the existing right of ways. An existing 60-inch CMP culvert structure located at Station 51+05, Line "A" will be removed and replaced with a 160 feet long, 16 feet wide by 6 feet high four-sided reinforced concrete box culvert. Based on the provided preliminary Plans and Profiles, up to about 14 feet (4.3 m) of fills and about 4 feet (1.2 m) of cuts are planned within the project limits, with the deeper fills located in the area of the culvert replacement.

The geotechnical recommendations presented in this report are based on the available project information, locations of the proposed roadway widening and culvert structure, and the subsurface conditions described in this report. If any of the above-referenced information is incorrect, please inform PSI in writing so that we may amend the recommendations presented in this report if appropriate and if desired by the client. PSI will not be responsible for the implementation of its recommendations when it is not notified of changes in the project.

### **1.3** Scope of Services and Procedures

The scope of our services for this project included:

- 1. The performance of eleven (11) soil borings to depths of 7<sup>1</sup>/<sub>2</sub> feet (2.3 m) to 25 feet (7.6 m) for the proposed roadway.
- 2. The performance of two (2) structure borings to depths of 40 to 45 feet (12.2 to 13.7 m) for the proposed culvert at Station 51+05, Line "A". In addition, six (4) soundings were performed on each end of the proposed culvert near the existing creek using a hand auger to evaluate the thickness of unsuitable materials.
- 3. The performance of appropriate laboratory tests, including AASHTO visual engineering classification, moisture content, loss on ignition (LOI), grain size analyses, Atterberg Limits, standard Proctor, CBR, and pH tests. One consolidation test was also performed on a Shelby

tube sample obtained from the structure boring, TB-2, which was performed close to the existing toe of the north embankment slope.

- 4. The provision of a written geotechnical report, including the following:
  - Findings and recommendations concerning the subgrade and pavement.
  - A discussion of potential settlement under the proposed embankment fill.
  - Recommended soil improvements for the support of new culvert structure and roadway embankments.
  - Recommended soil parameters for 3-sides box culvert with wing walls.
  - A discussion of the design and construction considerations associated with subgrade treatment.
  - Recommended CBR values for pavement design.
  - Evaluation of the stability of subgrades for support of the sewer line, and bedding and backfill recommendations.
  - Anticipated soil and groundwater related construction problems.
  - General construction considerations for fill placement and construction of the pavements.

The scope of services did not include an environmental assessment for determining the presence or absence of wetlands, or hazardous or toxic materials in the soil, bedrock, surface water, groundwater, or air on or below, or around this site. Any statements in this report or on the boring logs regarding odors, colors, and unusual or suspicious items or conditions are strictly for informational purposes.

# 2. GENERAL SITE CONDITIONS

# 2.1. <u>General Geology</u>

The site is located within the U.S. Geological Survey (USGS) topographic map of Gary, Indiana 7.5-minute quadrangle, dated 1991, which is reproduced as Figure 2 in the Appendix. The general area is drained by Turkey Creek, which is located about ¼ to ½ miles north of the project site. The Turkey Creek stream valley is mapped as swampland in the USGS map, which suggests the potential presence of organic soils. Based on regional geologic mapping, the unconsolidated deposits are generally anticipated to be Lacustrine deposits consisting of clay, silt, and sand of former lake areas. The Lacustrine deposits may associate with older alluvial deposits, which may contain localized organic deposits, based on our past project experience in the area.

Based on the Map of Indiana Showing Thickness of Unconsolidated Deposits, the thickness of the unconsolidated deposits is mapped as ranging from 100 to 150 feet in this area. Based on regional geologic mapping, unconsolidated deposits in the area are underlain by Traverse and Detroit River Formations, which consist of mainly limestone, and dolomite. Based on the regional geologic information, no underground coal mines or solutioned bedrock enlargements are anticipated in the project area.

## 2.2 Topography and Site Conditions

Based on our site visit and review of the preliminary Road Plans prepared by HNTB, the existing grades along the existing  $61^{st}$  Avenue gently slope downward toward the tributary of Turkey Creek, with elevations ranging from 631.9 feet (192.6 m) at Station 10+00, to about 629.7 feet (191.9 m) at the intersection with Liverpool Road, to about 628.3 feet (191.5 m) at the intersection with Minnesota Street, to elevation 615.5 feet (187.6 m) at the existing culvert structure, to about elevation 625.0 feet (190.5 m) at the intersection with Colorado Street, and to elevation 628.7 feet (191.6 m) at the end of  $61^{st}$  Avenue alignment (Station 62+04).

An existing 10-inch gas pressure main is located on the south side of existing 61<sup>st</sup> Avenue, and generally parallel to existing 61<sup>st</sup> Avenue. This existing gas pressure main is about 43 feet (13.1 m) south of the proposed centerline "A" near the existing culvert structure. The depth of gas pressure main was not available at the time this report was prepared. However, based on the proposed top of footing elevation 606 feet, we anticipate the existing gas pressure main could be located close to or below the bottom of the proposed box culvert structure. We also understand City of Hobart plans not to relocate the existing gas pressure main due to the cost and service reasons.

# 3. PROCEDURES

## 3.1. <u>Field Exploration</u>

The exploration program included eleven (11) soil borings to depths of  $7\frac{1}{2}$  feet (2.3 m) to 7.6 m (25 feet) for the proposed roadway and storm sewers. Nine of the eleven roadway borings were performed along the proposed  $61^{st}$  Avenue, and the remaining two (2) roadway borings were performed along Colorado Street. Since these borings were proposed for storm sewer line installation and subgrade investigation, they were generally located at or near the location of sewer manhole structures, and ranged from about 400 to 600 feet on center. The proposed depths of the roadway borings were generally based on the depth of proposed storm sewers along the alignment. We also performed two (2) structure borings to depths of 40 to 45 feet (12.2 to 13.7 m) for the proposed box culvert Structure 191.

The boring and sounding locations were selected by PSI, in conjunction with INDOT, Division of Materials and Tests. Borings and soundings were located in the field by PSI using a calibrated measuring wheel and preliminary Road Plans provided by HNTB, not dated. Boring locations are shown on Figures 3 in the Appendix. Ground surface elevations at the boring locations were estimated from the topographic information shown on available plans and cross sections, and are shown on the boring logs in the Appendix. Sounding locations and estimated ground surface elevations are tabulated together sounding results in the Appendix.

The soil borings were performed with both ATV and truck mounted rotary type drill rigs using continuous flight hollow stem augers to advance the boreholes. Representative soil samples were obtained by means of the split barrel sampling procedures at 2½ feet (0.8 m) intervals in the upper 10 feet (3.1 meters), in general conformance with AASHTO T 206. The number of blows required to drive the sampler 12 inches (305 mm) with a 140 pounds (63.5 kg) hammer falling 30 inches (760 mm), after an initial seating 6 inches (150 mm), is termed the Standard Penetration Test (N) value. A graphical representation of the N-values is shown on the boring logs.

Soundings were performed in or near the existing creek to evaluate the thickness of unsuitable soils at the location of the proposed culvert. The soil soundings were performed by our driller with a hand auger for the purposes of determining the depth through unsuitable deposits in or near the existing tributary of Turkey Creek. Soil sampling was not required during sounding, therefore, soil descriptions on the Summary of Soundings are based solely on the driller; field classification, without further laboratory classification.

During the field operations, the drill crew maintained a log of the subsurface conditions, including changes in stratigraphy and observed groundwater level. After completion of the drilling operations, and observing water levels, the boreholes were backfilled with natural soils and asphalt patch. The soil samples were transported to our laboratory for testing and engineering classification.

# 3.2 Laboratory Testing

The purpose of this laboratory testing program was to evaluate the classification and physical properties of the soils encountered at the project site. The tests performed include loss on ignition (LOI), grain size (sieve and hydrometer) analyses, Atterberg limits, natural moisture content, pH, unconfined compression, standard moisture-density relationship (Standard Proctor), and California Bearing Ratio (CBR) tests. In addition, consolidation test was also performed on relatively undisturbed Shelby-tube samples to evaluate the soil physical properties. The laboratory tests were performed in general accordance with applicable AASHTO standards. The results of the laboratory tests are shown on the logs and in the Appendix.

The recovered soil samples were visually classified by a geotechnical engineer, based upon texture and plasticity in general conformance with the AASHTO classification system. A geotechnical engineer grouped the various soil types into major zones as noted on the boring logs. For more detail regarding the soil conditions at a particular location, refer to the individual boring logs.

## 4. RESULTS

### 4.1 General Subsoil Conditions

Pavement cores were not scheduled for this project, and therefore, were not obtained from the borings performed on the existing pavement. However, the thicknesses of the pavement materials were measured by our driller to provide general information for construction bidding purposes.

The existing roadway pavement encountered at borings consisted of about 3 to 18 inches (75 to 457 mm) of asphaltic concrete surface over 6 to 21 inches (150 to 533 mm) sand and gravel base course. However, Portland concrete cement (PCC) pavement, about 15 inches (381 mm) in thickness, was encountered at ground surface in Boring RB-1-SG. Our driller also reported about 12 inches (304 mm) of clayey topsoil was encountered at the ground surface in Boring RB-8-SG performed within the proposed widening area.

Fill materials, such as silty clay and clay loam, were encountered below the surficial pavement materials to depths of about 8 feet (2.4 m) at Boring TB-1-SG. Below the surficial pavement and topsoil, cohesive fill materials or natural clay soils were generally encountered to depths of about 12 to 20 feet (3.7 to 6.1 m), elevation 597 to 622 feet (182.0 to 189.6 m), or to the explored depths of borings at Borings RB-8, RB-10-SG, and RB-11-SG. Below the natural clay soils, intermediate sand and sandy gravel soils were encountered at depths of about 12 to 18 feet to the explored depths of borings RB-1-SG through RB-7-SG and RB-9-SG. However, sand and sandy gravel soils were encountered at 22 to 42 feet (6.7 to 12.8 m) from existing grade at Borings TB-1-SG, or about 12 to 32 feet (3.7 to 9.8 m) at TB-2, or elevation 597 to 577 feet (182.0 to 175.9 m). Organic clay soils, such as silty clay loam (A-5) and loam (A-4) with little organic matter and trace marl, were encountered below the existing embankment fills near the existing culvert structure to a depth of about 22 feet (6.7 m) at Boring TB-1-SG, or below the surficial topsoil to a depth of about 12 feet (3.7 m) at Boring TB-2.

The in-situ fill materials or natural clay soils, such as clay, silty clay, silty clay loam, clay loam, and silty loam, below the surficial pavement, topsoil, and fill materials at borings ranged from very soft to very stiff, with Standard Penetration Test values (N-values) ranging from 2 to 19 blows per foot (bpf). The moisture content of the in-situ clay soils generally ranged from 10 to 30 percent. Unconfined compressive strengths, as measured by a calibrated pocket penetrometer, ranged from <sup>1</sup>/<sub>4</sub> to over 4<sup>1</sup>/<sub>2</sub> tons per square foot (tsf). Grain size distribution test shows clay soils consists of about 70 to 99 percent fines (material passing a No. 200 mesh sieve). One unconfined compressive strength test was performed on a recovered split-spoon sample obtained at about 9 feet in TB-1-SG, and the strength was 1.68 tsf.

Natural clay soils, such as silty clay, silty clay loam, silty loam, and clay loam, encountered below the pavement and fill materials were generally very soft to very stiff, with N-values ranging from 2 to 29 bpf. Unconfined compressive strengths, as measured by a calibrated pocket penetrometer, ranged from less than 1 to over 4<sup>1</sup>/<sub>2</sub> tsf. Moisture contents of the natural clay soils ranged from 11 to 30 percent

**Organic clay soils with trace to little organic matter and trace marl** were encountered to an elevation about 596 feet (181.7 m) at Borings TB-1-SG and TB-2, with N-values ranging from Weight of Hammer (WOH) to 5 bpf. Moisture contents of the silty clay loam and clay loam soils ranged from 39 to 96 percent, loss on ignition (LOI) was about 7 to 10 percent, and Calcium and Magnesium Carbonate were about 7.6 to 8.1 percent. Unconfined compressive strengths, as measured by a calibrated pocket penetrometer, ranged from less than ¼ to 1 tsf. Three (3) unconfined compressive strength tests were performed on the recovered Shelby-tube samples obtained from Boring TB-2, and their strengths ranged from 0.23 to 0.73 tsf. A consolidation test was also performed on a sample from TB-2, and the results are included in the Appendix. The silty clay loam and clay loam soils were classified as A-5 and A-4, respectively, according to Exhibit "C" issued by INDOT, dated January 1997.

Very soft to soft clay soils, with N-values ranging from 3 to 5 bpf, are listed in the following table:

Boring No.	Depth (feet)	Soil Type	N (bpf)
TB-1-SG	6 - 10	Silty Clay	2 to 5
TB-1-SG	10 - 22	Silty Clay Loam with trace marl/organic matter	2 to 5
TB-2	1 - 8	Silty Clay Loam with trace marl/organic matter	4 to WOH
TB-2	8-12	Clay Loam with trace marl/organic matter	WOH
RB-1-SG	6 - 8	Silty Clay	5
RB-2-SG	2 - 5.5	Silty Clay Loam/Clay	2 to 5
RB-3-SG	5.5 - 8	Silty Clay	5 : .
RB-4-SG	5.5 - 8	Clay	4
RB-7-SG	3 - 5	Silty Clay Loam	4
RB-9-SG	5.5 - 8	Silty Clay	5

The natural granular soils, such as sand and sandy gravel, ranged from loose to medium dense, with N-values ranging from 3 to 19 bpf. The sands were generally moist to wet below about 18 feet, about elevations 596 to 611 feet.

The above subsurface description is of a generalized nature to highlight the major subsurface stratification features and material characteristics. The boring logs included in the appendix should be reviewed for specific information at individual boring locations. These records include soil descriptions, stratifications, penetration resistances, locations of the samples and laboratory test data. The stratifications shown on the boring logs represent the conditions only at the actual boring locations. Variations may occur and should be expected between boring locations. The stratifications represent the approximate boundary between subsurface materials and the actual transition may be gradual. Groundwater information obtained during field operations is also shown on these boring logs. The samples which were not altered by laboratory testing will be retained for 60 days from the date of this report and then will be discarded.

### 4.2 Groundwater Conditions

Water levels were measured in the borings during and at completion of drilling. The driller reported water at the ground surface to depths of about 21 feet (6.4 m) below existing grade, approximately elevation 598 to 612 feet (182.3 to 186.5 m), during drilling at Borings TB-1-SG, TB-2, RB-6-SG, RB-7-SG, and RB-9-SG. The water levels at completion of drilling, following removal of the augers from boreholes, ranged from about 4 to 17 feet (1.2 to 5.2 m) below existing grade, approximately elevation 605 to 614 feet (184.4 to 187.2 m). After 24 hours, groundwater was reported at depths of about 1.5 to 16.5 feet (0.5 to 5.0 m), approximately elevation 609 to 624 feet (185.6 to 190.2 m), in Borings TB-1-SG, RB-6-SG, RB-9-SG, and RB-11-SG. The remaining borings were "dry" during and upon completion of drilling, meaning that no free water was observed in the borehole or on the sampling tools. The "dry" conditions indicate that the continuous groundwater level at the site at the time of the exploration was either below the terminated depths or cave-in depths of the borings, or that the soils encountered were relatively impermeable. Soil cave-in depths were reported at about 5 to 18 feet (182.3 to 189.0 m).

Due to the relatively short period of time the boreholes remained open, and the generally finegrained nature of soils throughout the entire length of shallow soil borings (less than 3 m in depth), the water level observations in the boreholes may not be representative of the groundwater level at the site. In our experience, fine-grained soils oxidize from brown to gray can sometimes be indicative of the long-term groundwater level. At this site, the soil color changes at depths of about 8 to 22 feet (2.4 to 6.7 m) below existing grade, at elevations of about 596 to 617 feet (181.7 to 188.1 m).

Based on the moisture state of the retrieved samples, the soil color change from brown to gray, the reported groundwater observations, we estimate the prevailing groundwater level is at or below depths ranging from about 1.5 to 16.5 feet (0.5 to 5.0 m) below existing grade, approximately elevation 609 to 624 feet (185.6 to 190.2 m). In general, the groundwater levels

appears to follow topography, with the shallower groundwater encountered in the area of proposed box culvert. Limited volumes of perched water will likely be encountered at shallower depths, depending on seasonal conditions.

The prevailing hydrostatic groundwater level, as well as perched water levels and volumes, should be expected to fluctuate throughout the years, based on variations in precipitation, evaporation, surface run-off and other related hydrogeologic factors. The groundwater levels discussed herein, and indicated on the boring log, represent the conditions at the time the measurements were obtained.

### 4.3 Soil Subgrade Investigation Summary

The soil subgrade investigation was performed on eleven (11) of thirteen (13) borings, with suffix "SG" following their boring number. These borings for soil subgrade investigation purposes are RB-1-SG through RB-7-SG, RB-9-SG through RB-11-SG, and TB-1-SG.

The soil subgrade investigation consisted of continuous split spoon sampling below the pavement subbase material, with Shelby tubes pushed adjacent to the split spoon sampling when required based on soil type and Standard Penetration Test (N-values) criteria established by INDOT. A total of eleven (11) Shelby tube samples were obtained in the soil subgrade borings. A minimum of two consecutive split spoon samples were obtained below the pavement subbase material, with a third obtained when required based on N-values from the second. The boring was then terminated unless N-values were less than 5 blows per foot.

CBR and Proctor tests were performed on a bulk sample obtained from Boring RB-2-SG, at a depth of about 1 to 3 feet (0.3 to 0.9 m) below existing grade. The results of the CBR and Proctor tests are summarized below:

Boring No.	Depth (feet)	Soil Type	Opt. Moisture Content, %	Maximum Density, pcf		CBR @ 97 %
RB-2-SG	1.0 - 3.0	Silty Clay Loam A-4(0)	15.5	110	2.2	3.3

We compared the in-place density of the Shelby-tube soil samples to the above Proctor data, and provide a comparison estimate of degree of compaction, as tabulated in the following Summary of Subgrade Soil Conditions Table.

Boring No.	Depth (feet)	Soil Type	Moisture Content (%)	Dry Density (PCF)	Difference to Opt. Moisture Content	% of Max. Dry Density
RB-2-SG	2 - 4	Silty Clay Loam, A-4	24.0	89.4	+9.7	81.3
RB-2-SG	4 - 6	Clay, A-7-6	25.9	95.0	+10.4*	86.4*
RB-4-SG	2 - 4	Silty Clay Loam, A-4	27.5	93.8	+12.0	85.3
RB-5-SG	1.5 - 3	Silty Clay Loam, A-4	26.7	97.2	+11.2	88.4
RB-6-SG	1.5 - 3	Silty Loam, A-4	24.3	98.2	+8.8*	89.3*
RB-7-SG	1.5 –3.5	Silty Clay Loam, A-4	24.5	98.6	+9.0	89.6
RB-7-SG	3.5 –5.5	Silty Clay Loam, A-4	27.5	94.1	+12.0	85.5
RB-9-SG	1.5 - 3.5	Silty Loam, A-4	20.9	102.3	+5.4*	93.0*
RB-10-SG	1-3	Silty Clay, A-6	21.9	105.3	+6.4*	95.7*
RB-11-SG	1 - 3	Silty Loam, A-4	19.4	109.6	+3.9*	99.6*

### **Summary of Subgrade Soil Conditions**

Standard Proctor test was not performed on clay, silty clay, and silty loam soils, therefore, the in-situ
moisture content and dry density were compared to standard Proctor Test data of the most similar
soil – silty clay loam.

We understand INDOT plans bituminous overlay and/or pavement reconstruction in the areas of existing pavement and full depth of bituminous pavement on the widening sections of the proposed roadway. Based on the current and projected Annual Average Daily Traffic (AADT), we anticipate 24-inch (610 mm) subgrade treatment as outlined in Section 5.3 of this report will be required. Compaction of the subgrade soils will be required for 610-mm (24-inch) subgrade treatment. Based on our test data, the moisture contents of in-situ clay soils were generally wetter than the optimum moisture content, up to about 12 percent over optimum. Therefore, we anticipate significant discing, drying and recompaction will be required to improve unstable subgrade conditions. To expedite the roadway construction, we recommend the 16 inch (400 mm) chemical modification method as outlined in Subgrade Treatment Recommendations issued

ŗ

ť

by INDOT, dated August 23, 2001, for this project, instead of conventional 610-mm (24-inch) subgrade preparation for the existing and roadway widening sections.

### 5. ANALYSES AND RECOMMENDATIONS

# 5.1. <u>Cut and Fill Sections</u>

The profile grade along the proposed  $61^{st}$  Avenue alignment within project CM-9945(), varies from about (631.9 feet (192.6 m) at the beginning of construction at Station 10+00, to about 629.7 feet (191.9 m) at the intersection with Liverpool Road, Station 27+95.96, Line "A". The maximum cuts within the project limits were about 2.8 feet (0.85 m), and maximum fills were about 2 feet (0.6 m) located in the existing drainage ditch areas.

Within project STP-N606(), the proposed profile grade varies from about 629.7 feet (191.9 m) at the beginning of construction (Station 27+95.96, Line "A), to about 628.3 feet (191.5 m) at the intersection with Minnesota Street (Station 38+20, Line "A"), to elevation 622.5 feet (189.7 m) at the existing culvert structure (Station 51+20, Line "A"), to about elevation 624.0 feet (190.2 m) at the intersection with Colorado Street (Station , and to elevation 628.7 feet (191.6 m) at the end of 61<sup>st</sup> Avenue alignment (Station 62+04). The maximum cuts within the project limits were about 4.5 feet (1.4 m), and maximum fills were about 14 feet (4.3 m) located near the existing culvert structure (Station 51+50, Line "A").

Embankment slopes of 2½:1 and 3:1 (H:V), as shown in the Typical Pavement Sections, should generally be sufficient to provide stable slopes, provided the subgrade is properly prepared, and the existing slopes are properly benched prior to the placement of the fill. Slope stability are discussed in Section 5.2 of this report, particularly in the vicinity of existing creek where soft organic soils are present. Post-construction settlement is also discussed in Section 5.2.

Surficial organic topsoil, approximately 12 inches (0.3 m) in thickness, was generally encountered at the locations of borings in areas without existing pavement. Based on the soundings performed near the existing creek within the area for the proposed culvert structure, very soft silty clay with organic matter (or peat) and loose sand were generally present below the ground surface to the  $\frac{1}{2}$  to  $\frac{31}{2}$  foot depths of soundings. Due to the presence of organic soils to

significant depths, therefore, soundings were terminated shallower just for organic soil verification purposes. Based on Boring TB-2, which was performed at the toe of the existing slope within the area for the proposed structure, silty clay loam with little organic matter was encountered to a depth of about 12 feet below grade.

The organic topsoil, and loose or soft/loose soils encountered during the subgrade preparation should be removed prior to placing the proposed fill. We do not anticipate removal and replacement of organic soils in the area of the existing creek and proposed culvert is a practical and cost-effective method due to the significant undercut, dewatering, and sheeting/shoring required during construction.

Granular fill should not be used in the drainage ditches, or within 12 inches (305 mm) of the required finished surfaces of slopes, to reduce the risk of erosion. The embankment material should be a non-erodible, environmentally clean soil free from clods, debris, organic matter, and stones. Refer to Section 6.1 for further recommendations regarding subgrade preparation.

5.2 Ground Improvements

Based on the preliminary Road Plans prepared by HNTB, the proposed profile indicates significant embankment fills, about 14 feet (4.3 m) in thickness, will be required for the roadway widening at the existing culvert structure (Station 51+50, Line "A"). In addition, an existing 10-inch gas pressure main is located about 43 feet south of the proposed centerline "A", near the toe of existing south embankment slope. The depth of gas pressure main was not available at the time this report was prepared. However, based on the proposed top of footing elevation 606 feet, we anticipate the existing gas pressure main could be located close to or below the bottom of the proposed box culvert structure. We also understand City of Hobart plans not to relocate the existing gas pressure main due to the cost and service reasons.

Based on the proposed height of embankment fill and consolidation parameters of clay soils with marl/organic matter, we anticipate primary consolidation settlement up to about 14 inches (356

mm) could develop at Boring TB-2. We anticipate primary consolidation settlement may be achievable within 11<sup>1</sup>/<sub>2</sub> years, after the placement of full-height of embankment fills. Secondary settlement of the these organic clay soils up to 30 years after construction could be in a range of about <sup>1</sup>/<sub>2</sub> to 1 inch (13 to 25 mm). For analysis purposes, we have assumed an allowable settlement of the box culvert structure to be 1 inch (25 mm). The time required for within 1 inch (25 mm) allowable post-construction settlement is about 9 years. (see settlement analysis in the Appendix) The above settlement estimate is based on the soil parameters obtained from a consolidation test performed on a relatively undisturbed Shelby tube sample of organic silty clay loam soil from Boring TB-2.

Therefore, we have considered soil improvements for the embankment and box culvert constructions near the existing creek. The selection of remedies was based on five (5) functions.

- Reducing settlement to a tolerable range without a long construction delay.
- Providing adequate embankment slope stability.
- Uniformly supporting the proposed precast 4-sided precast box culvert.
- Providing the support to the existing gas pressure main due to the potential of excessive settlement.
- Providing support to the storm sewer to be installed between Structure No. 187 and 196.

We anticipate excessive settlement could potentially damage the proposed new 4-sided precast concrete box culvert structure and sewers. In addition, 9-year waiting period prior to pavement construction is not practical for this project due to the high traffic volume on existing 61<sup>st</sup> Avenue. Based on the potential quantity of removal and replacement, or required waiting period of about nine years for at least about 93 percent of primary consolidation, or required adequate support to the proposed precast culvert structure and existing gas pressure main, we anticipate vibro-concrete columns (VCC) are likely a feasible alternative for this project. VCC as well as other improvement alternatives considered are discussed below.

(a). Vibro Concrete Column (VCC) – To reduce the excessive settlement, to uniformly support the proposed precast 4-sided reinforced concrete box culvert and sewers, and to limit the risk of overstressing the existing gas pressure main, we consider Vibro Concrete Column (VCC) is a relatively fast and feasible scheme.

The VCC process was first developed in Europe in 1976. Instead of feeding stone to the tip of the vibrator (as is done with stone columns), concrete is pumped through an auxiliary tube to the bottom of the hole. This method can offer the ground improvement advantages of the vibro systems with the load carrying characteristics of a deep foundation.

The VCC process employs a bottom feed depth vibrator that can penetrate the soils to a level suitable for bearing. Concrete is pumped through the vibrator assembly during initial withdrawal. The vibrator then repenetrates the concrete, displacing it into the surrounding soil to form a high-capacity, enlarged column base. The vibrator is then slowly withdrawn as concrete is pumped at maintained pressure to form a continuous shaft of concrete up to ground level. At ground level, a slight mushrooming of the concrete column is constructed to assist the transfer of the applied loading into the VCC.

We anticipate VCC installed at a 6 feet by 6 feet grid may be required. The VCC grid should be adjusted or additional VCC elements added to provide concentric support along the box culvert and storm sewer alignments. The VCC elements below the box culvert and storm sewer must have their top of VCC elements set below the structure invert elevations. Other VCC elements that will support embankment fill could have top of VCC elements established near the existing grades. The VCC elements should also be spaced to avoid the gas main, and a reinforced concrete cap should be constructed to span between VCC elements to support the fill load directly over the gas main. Also, to uniformly support the proposed embankment fill, precast 4-sided reinforced concrete box culvert, and sewer over VCC, we recommend two layers of geogrid reinforced crushed aggregate (one foot for each layer) be placed over the installed VCC underneath the precast box culvert and sewer, and three layers of geogrid reinforced crushed aggregate underneath the proposed embankment fills. We anticipate dewatering by means of wellpoints or deep wells may be necessary along the culvert and storm sewer alignments in order to excavate for the structure and install the granular/geogrid blankets.

N-values of the existing embankment clay fill encountered at Boring TB-1-SG generally ranged from 2 to 11 bpf, with unconfined compressive strength ranging from <sup>1</sup>/<sub>4</sub> to 1<sup>1</sup>/<sub>2</sub> tsf. We anticipate pre-drilling through the existing roadway embankment may be required prior to VCC installation.

The organic soils were generally encountered near the existing ground surface in the widening areas near the creek. (see the attached Summary of Soundings) N-values of the existing organic soils generally ranged from weight of hammer (WHO) to 5 bpf. Therefore, we anticipate a drainage blanket will be required prior to the construction to provide an appropriate working platform and drainage path, and to protect the exposed portions of

VCC from construction traffic and freezing temperatures. The working platform should be a granular material with maximum particle size between 1 and 2 inches, and less than 10 percent passing the No. 200 sieve, such as INDOT No. 2. The drainage blanket should be at least a continuous 24 to 36 inches (610 to 915 mm) thick. If the VCC and blanket are placed during the winter months then an additional layer of fill will be required to prevent the ends of the VCC from freezing.

For bidding purposes, the plan limits of VCC along the alignment should be assumed to extend from Station 50+00 to 52+50, Line "A". The actual limits may require revision based on encountered organic soil limits. The plan limits of VCC in width should extend a minimum of 6 feet beyond the toe of the embankment, or greater as determined by the VCC contractor. Plan limits of the VCC also must extend at least to the limits of the box culvert wingwalls.

The VCC contractor should submit a detailed plan for layout and method of installation of the VCC to the design engineer for review. Specific equipment and installation procedures to achieve the specified criteria are the contractor's responsibility. Special provision and recommendations for field inspection for Vibro-compacted concrete columns are included in the Appendix of this report. Specific modifications recommended to tailor the guide specifications to the requirements of this project are marked on the Special Provision. We strongly recommend review of the required contractor submittals be performed by PSI and INDOT Division of Materials and Tests. Full-time quality assurance during construction should be performed by a qualified engineering technician or staff engineer working under the direction of the project geotechnical consultant. We recommend full-time quality assurance during ground improvement construction be performed by PSI or by INDOT Division of Materials and Tests.

(b). **Complete Removal and Replacement -** The removal and replacement alternate consists of excavating the organic clay soils and replacing the excavated materials with compacted "B" Borrow engineered fill. The existing fill can be removed and stockpiled for reuse. We anticipate the limits of overexcavation are likely within Station 50+00 to 52+50, Line "A". The overexcavation of organic soils could extend to an elevation about 596 feet (181.7 m), or about 12 feet (3.7 m) below the groundwater table. Therefore, for the removal and replacement alternative, wellpoint or multiple deep well dewatering before and during the construction would be necessary. Dewatering for left side of the widening road poses a potential risk of settlement of the existing roadway on the right side, due to an increase in effective stress, which could create pavement distress during the construction period. In order to maintain 61<sup>st</sup> Avenue open for traffic, temporary sheet pile or solider pile and lagging retaining walls with tieback anchors would likely be necessary along the centerline of proposed alignment. Furthermore, since organic soils likely are present below the existing gas main, support or relocation of the gas main would be necessary.

The organic silty clay loam and loam soils should be removed to its full extent under the proposed roadway. From the edge of pavement at the bottom of the excavation, the sides of the excavation could be sloped to the proposed toe of embankment slope. The loose to very loose sand at the bottom of the excavation should be compacted with a vibratory roller prior

to the placement of B Borrow backfill. The on site soils obtained from the culvert excavation or the roadway cuts should be categorized for reuse to facilitate compaction control. The engineered fill should be placed in lifts not exceeding 203 mm (8 inches) in loose thickness and be compacted to the required density as specified in the 1999 INDOT Standard Specifications.

A representative of the project geotechnical engineer must be on-site to observe the removal of organic silty clay loam and loam soils. No waiting period for consolidation is required for this method. Based on the estimated quantities of overexcavation, wellpoints dewatering, and anchored temporary retaining walls and support or relocation of the gas main, we anticipate the complete removal and replacement of in-situ organic soils could be costly and also time consuming.

(c). Expanded Polystyrene (EPS Foam) – EPS Foam is made from polymer in the form of blocks with extremely low unit weight of about 1.35 pounds per cubic feet (pcf). Construction of the roadway embankment with EPS foam could be relatively fast, and only cause minimal post-construction settlement. For a project on a rush basis, EPS foam initially may appear to provide an attractive alternative. However, we understand the existing creek serves as major storm water drainage from 61<sup>st</sup> Avenue to Turkey Creek. The 100-Year elevation at this site is 613.13 feet (186.9 m), which is about 8 feet (2.4 m) above the proposed invert elevations. Due to the potential significant buoyancy conditions under flooding, we do not anticipate EPS foam is a feasible scheme for the roadway embankment construction near the existing creek.

(d). Wick Drains - Wick drains can be best described as prefabricated vertical drains. Their primary use is to accelerate consolidation of soft saturated compressible soils under load. They can greatly decrease the settlement time of embankment over soft soils, and accelerate the rate of strength gain of the in-situ soft soils. Wick drains are generally used in consolidation situations where the soil to be treated is a moderate to highly compressible soil with low permeability and fully saturated in its natural state. The most common use of wick drains is to accelerate consolidation for roadway embankments at bridges or other embankment construction over soft soils, where the total post-construction settlement is not acceptable.

We have performed wick drain analysis for cost comparison purposes. Depending upon the wick drain spacing, we anticipate a minimum waiting time from 3 months to 1 year may be required, with spacing ranging from 1<sup>1</sup>/<sub>4</sub> to 2<sup>1</sup>/<sub>4</sub> feet, respectively, for about 93 percent of primary consolidation. The waiting time could be somewhat reduced or the wick drain spacing increased by placement of a temporary surcharge fill over the alignment. Therefore, as a contingency that City of Hobart is willing to close the road for construction, and accept the responsibility to maintain the roadway pavement annually, wick drains could be a feasible scheme for this project. However, the existing gas pressured main must be properly supported or relocated prior to the installation of wick drains due to the potential differential settlement along the main.

- (e). Compaction Grouting Structural compaction grouting can be used in a wide variety of applications including soil densification, raising of surficial structures, settlement control over tunnels or sinkholes, and for structural underpinning. In general, compaction grouting is effective in loose granular soils, loose unsaturated fine-grained soils, collapsible soils, and in void filling. Based on the test results of grain size distribution, the fines (particles fine than #200 sieve) within the in-situ organic soils generally range from about 58 to 88 percent. Based on the range of applicability of soil grouting techniques (Fig. 26, Ground Improvement Technical Summaries, Volume II, FHWA-SA-98-086), we do not anticipate structural compaction grouting can form structurally sound grout columns to support the box culvert and gas pressure main. The other concern was the high grouting pressure could potentially damage the existing gas pressure main.
- (f). **Geopiers<sup>™</sup>** Geopier<sup>™</sup> elements are installed by drilling 30-inch diameter holes and ramming thin lifts of well-graded aggregate within the holes to form very stiff, high-density aggregate piers. The first lift of aggregate forms a bulb below the bottoms of the piers, thereby pre-stressing and pre-straining the soils to a depth of equal to a depth of equal to at least one-pier diameter below drill depths. Subsequent lifts are typically about 12 inches in thickness. Ramming takes place with a high-energy beveled tamper that densifies the aggregate and forces aggregate laterally into the sidewalls of the hole. This action increases the lateral stress in the surrounding soil; thereby further strengthening and stiffening the composite soil mass.

The depth of conventional Geopier<sup>TM</sup> construction is limited to 22 feet below grade. The depth limitation is controlled by the "reach" of conventional trackhoe mounted tamper. Due to the presence of organic soils to a depth of about 22 feet below the existing pavement grade at Boring TB-1-SG, we anticipate organic soils could be encountered deeper than 22 feet beyond the reach of a conventional trackhoe mounted tamper. Therefore, if this scheme is selected or permitted as a contractor alternate, we recommend further machine soundings be required to evaluate the depths of organic soils prior to bidding.

Considerations regarding arrangement of the elements below the box culvert and sewer, and spanning over the gas main, which applied to VCC also apply to Geopiers<sup>™</sup>. Also, a detailed submitted should be required from the Geopier<sup>™</sup> specialty contractor, for review by PSI and INDOT, Material and Test Division. Protection of the gas main against lateral displacement during geopier<sup>™</sup> installation and tamping will require particular attention.

(g). Vibro-replacement (Stone Column) – Stone columns are a technical and potentially economical alternative capable of improving sufficiently to allow less expensive embankment construction. Stone columns are also more economical than the removal and replacement of deep poor bearing soils, particularly on larger sites where the groundwater is close to the surface. However, stone columns are not a solution for all soft soil problems. Strata of peat, marl, mulch, and other organic soils, very soft clays with a thickness greater than the diameter of the stone column can be inappropriate for stone column construction as they offer inadequate lateral support. When the thickness of the organic layer is greater than 1 to 2 stone column diameters, the ability to develop consistent column diameters

becomes questionable. Therefore, we do not consider stone column to be a feasible scheme for this project.

Based on the proposed 3 (horizontal) to 1 (vertical) embankment slope and VCC installed to a depth of about 18 feet below toe of the slope, or elevation 590 feet, at 6 feet by 6 feet grid, we do not anticipate slope failure is likely to occur. Therefore, we did not perform slope stability analysis near the proposed box culvert structure.

# 5.3 <u>4-Sided Precast Reinforced Concrete Box Culvert (Structure No. 191)</u>

The project also includes replacement of the existing culvert structure at about Station 50+95, Line "A". The existing structure is a 60-inch corrugated metallic pipe (CMP), with a span of about 60 feet (18.3 m) long. We understand, after the removal of the existing culvert structure, a 4-sided precast reinforced concrete box culvert, Structure No. 191, will be constructed at Station 51+10, Line "A". The proposed box culvert is about 160 feet long, with an opening of 16 feet (wide) by 6 feet (height). Two wingwalls are also proposed to be constructed at each end of the proposed culvert structure.

We understand the proposed flow line is about 607.2 to 608.0 feet at the north and south end of culvert, respectively, and the top of the footing elevations will be about 2 feet (0.6 m) below the flow line. Therefore, we anticipate the bottom of footing elevations could be at 603.2 to 604 feet at the north and south end of culvert, respectively.

We recommend the bridge structure as well as streambed be protected from scouring and erosion with a minimum 1.2 m (4 feet) of riprap at both ends. We have assumed City of Hobart and design consultant, HNTB, will select VCC as the supports for the new culvert structure and roadway embankment. The vibro-concrete columns need to be penetrated the near surface marly soils to the underlying sand or sandy gravel, at about elevation 587 feet. The culvert foundations bearing on the geogrid-reinforced layer placed over the VCC may be proportioned using a net allowable pressure of 3,000 psf. The maximum net allowable soil bearing pressure is that pressure which may be transmitted to the bearing material in excess of the final, minimum

surrounding overburden pressure. We estimate total settlement of the culvert structure supported on VCC deep foundation may be about ½ to 1 inch, with differential settlement of about half of the total settlement. In order to uniformly support the proposed culvert structure, we recommend at least two layers (12 inches each) of geogrid-reinforced crushed aggregate, such as INDOT 53, be placed underneath the proposed culvert structure.

We recommend the proposed wingwalls be supported on the same type of VCC deep foundation as the culvert structure. The geogrid-reinforced crushed aggregate should also be placed on top of the VCC to uniformly support the wingwalls. The following additional soil parameters are also provided for wingwall design, as requested in the Memorandum issued on April 12, 1999, by INDOT, Department of Materials and Tests.

- Friction Angle,  $\delta = 30^{\circ}$
- Friction Factor,  $\tan \delta = 0.58$
- Angle of Internal Friction of the geogrid reinforced foundation soil,  $\phi = 32^{\circ}$
- Ultimate adhesion between the foundation soil and concrete footing,  $C_a = N/A$
- Ultimate cohesion,  $C_{ult} = N/A$

# 5.4 General Pavement Design Considerations

For the widening or new roadway sections, the surficial topsoil and/or near-surface clay soils containing trace to little organic matter should be completely undercut with the exception of the areas between Station 50+00 and 52+50, Line "A", which will require VCC for ground improvements. Proofrolling would allow identification and undercutting of areas of weak subgrade soils.

With overlay methods directly over the existing asphalt pavement, no subgrade or drainage improvements are feasible. While pavement design is outside our scope of services for this project, we note that the existing pavement distress decreases the remaining life of the existing pavement to be credited in overlay design, and increases the risk of reflective cracking.

### 5.5 Recommended CBR Values

PSI evaluated the most critical and predominant plastic (cohesive) soil types encountered within the proposed new pavement areas along the proposed 61<sup>st</sup> Avenue alignment for subgrade strength, based on the California Bearing Ratio (CBR) tests. The cohesive soils encountered along the alignment included silty clay loam, silty loam, and silty clay. Two bag samples were obtained near the existing ground surface at Borings RB-2 and RB-8 for CBR tests, the sample from RB-2 was tested. The most predominant plastic soil at subgrade elevations within the proposed pavement area was silty clay loam, with about 77 percent of silt and clay, and plasticity index (PI) of 10. Based on AASHTO classification system, the most predominant cohesive soils within the proposed new pavement area was classified as A-4.

The CBR value of the silty clay loam sample, compacted to 97 percent of the maximum dry density as determined by AASHTO T-99, Standard Proctor Method, are provided in the table below.

Location	Depth (ft)	Soil Type	% Max. Dry Density	Test CBR Value @ 97 %
RB-2	1 – 3	Silty Clay Loam, A-4(7)	97	3.3

### In the Fill Areas

Based on the INDOT Design Memorandum, Subgrade Treatment Recommendations, dated August 23, 2001, we recommend 24 inches (600 mm) subgrade treatment for the fill areas in this project. Due to the presence of more cohesive silty clay and clay soils (A-7-6) with PI over 20, therefore, we recommend a CBR value of 2.5 be used for pavement design rather than the higher maximum value of 3.3.

### In the Cut Areas

Based on the preliminary Road Plans provided by The HNTB Companies, the projected AADT on existing 61<sup>st</sup> Avenue ranged from about 11,680 vehicles per day (VPD) in 2003 to 15,650 VPD by 2023. The total subgrade treatment area is more than 10,000 yd<sup>2</sup>. Based on Subgrade Treatment Guidelines prepared by INDOT, we recommend 16 inches (400 mm) chemical modification (or any alternative described in Section 207.04(a).1), with an estimated CBR value of 2.5 for the pavement design.

During the site preparation operations, the subgrade soil should be evaluated by the project geotechnical engineer to verify the soil type meets the design CBR criteria.

### 5.6 Subsurface Drain Recommendations

Near surface soils generally encountered in borings varied from silty clay loam, silty clay, clay, and silty loam. The predominantly cohesive soils along the proposed alignment generally have poor drainage characteristics. Most of the near surface cohesive soils encountered along the proposed alignments had silt content over 50 percent except clay which had a silt content of 47 percent. If surface water which infiltrates through joints and cracks in the pavement and is allowed to pond on the subgrade, the subgrade will soften and contribute to the formation of frost lenses. The frost lenses will result in further softening during thaw periods with attendant reduction in the pavement life. Removal of infiltrating surface water by means of pavement subsurface drains can help to extend a pavement's useful life.

Current INDOT practice requires the use of geotextile filter fabric around surface drains only when the percentage of silt-size particle (0.074 to 0.002 mm) exceeds50 percent. Subsurface drains are required when soil conditions warrant, and the length of project is over 2,000 feet, and the AADT exceeds 3,000 VPD. Based on the on site soil conditions, length of the project, and provided traffic volume, we recommend that pavement subsurface drains with geotextile filter fabric be used throughout this project.

Subsurface drains should be perforated corrugated plastic pipe meeting the requirements of Section 718 of the INDOT 1999 Standard Specifications, Underdrains. We recommend the pipes be surrounded by a minimum of 150 mm (6 inches) of INDOT No. 8 aggregate, with the aggregate fully encased in a non-woven geotextile filter fabric meeting Section 913.19, Geotextile for Use with Underdrains, of the INDOT 1999 Standard Specifications. The Apparent Opening Size (AOS) should be compatible with the openings in the drain tile and the grain size of the surrounding soils, to reduce the risk of loss of fines into the drainage system and clogging. Outlets should be provided at regular intervals to convey the water collected in the subsurface drains. The subsurface drain outlets should be covered with screen.

The pavement section should be graded to prevent ponding of surface water. Subgrade slopes should follow surface slopes. We recommend a minimum slope of 2 percent, where feasible, to facilitate drainage.

# 6. CONSTRUCTION CONSIDERATIONS

# 6.1. Subgrade Preparation

The recommendations of this section apply to the pavement reconstruction, widening, and new extension areas, with the exception of the areas near the proposed box culvert, which require ground improvements.

In widening areas, all topsoil, wet or soft surface soils, and organic soils within the upper three feet should be stripped from the site within the construction limits prior to construction of the roadway, with the exception of the areas between Station 50+00 and 52+50, Line "A", which will require VCC for ground improvements. In areas where engineered fill will be placed, such as an area undercut due to organics present, proofrolling of the stripped ground surface should be performed in accordance with INDOT Standard Specifications, Section 203.26. All soft, loose, organic or otherwise unsuitable soils encountered during the proofrolling operations should be undercut and replaced with engineered fill.

The majority of the near surface subgrade soils at the site have been characterized as silty clay loam, silty clay, clay, clay loam, and silty loam soils, which will soften when exposed to repeated loadings, thus making grading difficult. If grading is performed during wet times of the year, we anticipate the near-surface soils will be difficult to work, that access may be difficult, and a greater amount of surface repairs will be required to improve soils judged to be unsuitable because of excessive moisture content.

At boring locations performed within the widening lane areas, the natural moisture contents of near surface silty clay loam, silty clay, clay, clay loam, and silty loam soils, generally ranged from 19 to 28 percent, and the majority were generally over the respective optimum moisture contents. Therefore, we anticipate discing, drying and recompaction will be required to improve unstable subgrade conditions. However, if the construction takes place in the hot dry summer season, additional water may need to be added to the soil to increase the moisture content to the

desired optimum. The contractor should have equipment, such as a large non-agricultural disc, on site to allow thorough mixing of the soils and added water, if it becomes necessary.

Near-surface samples containing apparent organic matter (possible buried topsoil) were obtained from about 1 to 4 feet (0.3 to 1.2 m) in Borings RB-4-SG and RB-10-SG. The loss on ignition (LOI) organic content of the first soil sample from these two borings was about 5.8 to 5.9 percent. We recommend subgrade soils which contain organic matter be removed from the zone of seasonal moisture change and replaced with engineered fill. Typically, the zone of seasonal moisture change is approximately the upper 3.5 feet (1.1 m) below final grades.

Provided earthwork proceeds during a warm and dry period, we anticipate only limited areas of subgrade soils would be likely to fail proofrolling. However, if subgrade soils for localized small areas become unstable due to the presence of ponded water, we anticipate they may be stabilized through undercutting a minimum of 305 mm (12 inches) and replacing with compacted "B" Borrow or No. 53 crushed aggregate, in combination with a geogrid if necessary. Alternatively, we anticipate a minimum 406 mm (16 inches) lime kiln dust modification methods may be used, if large areas of wet or disturbed cohesive subgrade soils are encountered during construction.

Due to the presence of very soft organic soils with marl/organic matter, we do not recommend the embankment widening areas near the existing creek be proofrolled. Organic soil delineation was not included in our scope of work for this project, therefore, PSI did not perform marl delineation borings. However, we recommend Station 50+00 to 52+50, Line "A", be used for cost estimate purposes, based on site topography. Actual limits of the organic soils should be established during construction.

It is important the surficial dark brown to black topsoil material or clay soils with marl/organic content <u>not</u> be re-used as backfill. We recommend that a geotechnical field representative observe subgrade preparation and undercutting of organic soils, to evaluate the subgrade soils suitability and adequacy of the undercut.

### 6.2 Fill Placement and Compaction

The recommendations of this section apply to areas of pavement reconstruction or widening areas. Based on the provided preliminary Road Plans, we understand up to about 14 feet (4.3 m) of fills and about 4 feet (1.2 m) of cuts are planned within the project limits, with the deeper fills located in the area of the culvert replacement.

Engineered fill used on the project should be an approved, environmentally clean material, free of lumps, frozen soil, wood, roots, topsoil, or other deleterious material. The engineered fill should meet the requirement of borrow as specified in Section 203.08, INDOT 1999 Standard Specifications. The on site soils obtained from the culvert excavation or the roadway cuts should be categorized for reuse as recommended in Section 5.2, to facilitate compaction control. The engineered fill should be placed in lifts not exceeding 203 mm (8 inches) in loose thickness and be compacted to the required density as specified in the 1999 INDOT Standard Specifications.

Granular soils meeting INDOT specifications for "B" Borrow are suitable for use as engineered fill. On-site inorganic materials, such as silty clay loam and silty loam (A-4) and silty clay (A-6), would generally suitable for the embankment fill. Depending on the time of construction, significant aeration of the on-site fill material may be required before it can be placed as engineered fill according to the INDOT Specifications for fill placement. If may also be necessary to add moisture during extended periods of hot weather should the soil become too dry to achieve compaction.

# 6.3 **Storm Sewer and Sanitary Sewer Lines**

We understand storm and sanitary sewer lines are proposed along existing 61<sup>st</sup> Avenue (Line "A") between the proposed catch basins, manholes, and outlet structures. We understand the proposed inverts of storm and sanitary sewer lines and manholes generally range from about 8.5 to 19 feet (2.6 to 5.8 m) below the existing pavement grade.

We understand the storm sewer to be installed includes 15 to 48 inch (380 to 1200 mm) reinforced concrete pipes (RCP). A 16 feet by 6 feet reinforced concrete box culvert is planned at Station 51+10, Line "A", as discussed in a previous section of this report. The proposed sanitary sewer will include 0.3 to 10 inch PVC pipes. The proposed new sanitary sewer line will be connected the existing sanitary sewer trunkline route running parallel to the S. Liverpool Road.

In general, the placement of the sewer lines within the soil profile does not increase the load on the underlying soil. However, it is important to have proper support, and to maintain proper line and grade of the pipe to prevent the pipe from becoming over-stressed in hoop compression or bending. Also, where new fill causes settlement of soft natural soils, sewer lines also will settle, which can cause problems with flow and potentially can overstress the pipe, depending on the magnitude of different settlement.

Based on the soil conditions from borings performed along existing 61<sup>st</sup> Avenue, the soils at the bearing depth of manholes and sewer lines should generally be suitable for support of the structures except within the area where organic silty clay loam and loam soils were present in the vicinity of Structure No. 187 through 196. The following table shows the type of storm and sanitary sewer pipe structures, approximate locations, and proposed invert elevations, and type of bearing soil at the invert elevations as encountered at the boring locations.

Storm Sewer	From	То	Sewer Invert Elevation, ft	Borings	Bearing Soil at Boring Locations
15 inch	Structure No. 100	Structure No. 111	623.66 to	RB-1-SG &	Medium Stiff Clay to
RCP	(Sta: 11+00, "A")	(Sta. 17+07, "A")	621.20	RB-2-SG	Silty Clay
18 to 24 inch RCP	Structure No. 111 (Sta. 17+07, "A")	Structure No. 136 (Sta. 27+76, "A")	621.10 to 617.24	RB-2-SG RB-3-SG RB-4-SG	Medium Stiff Silty Clay to Medium Dense Sand
30 inch	Structure No. 136	Structure No. 167	617.14 to	RB-5-SG &	Medium Dense to
RCP	(Sta. 27+76, "A")	(Sta. 38+60, "A")	612.84	RB-6-SG	Loose Sand
36 inch RCP	Structure No. 167 (Sta. 38+60, "A")	Structure No. 191 (Sta. 51+23, "A")	612.74 to 608.00	RB-6-SG RB-7-SG TB-1-SG	Medium Dense to Loose Sand to Soft Organic Silty Clay Loam
48 inch RCP	Structure No. 191 (Sta. 51+23, "A")	Structure No. 212 (Sta. 60+98, "A")	607.2 to 614.70	TB-2 RB-8 RB-9-SG	Soft Organic Silty Clay Loam to Medium Stiff Silty Clay or Clay

Sanitary Sewer Type	From	То	Sewer Invert Elevation, ft	Borings	Bearing Soils at Boring Locations
10 inch PVC	Structure No. 300	Structure No. 308	622.75 to 616.73	RB-2-SG RB-3-SG RB-4-SG	Stiff to Soft Silty Clay to Medium Dense Sand

Adequate control of groundwater will be necessary to preserve subgrade stability, particularly in the sewer excavations between Station 25+00 and 55+00, Line "A". If loose sand is present at the proposed sewer bearing elevations, we recommend the proposed subgrades be undercut a minimum of 0.5 m (18 inches), and backfilled with compacted INDOT No. 53 crushed aggregate to the proposed pipe invert elevation. The purpose of the undercut and replacement is to aid in bridging the underlying loose sand and providing a stable base for the pipe. The aggregate pad should extend laterally a minimum of 0.5 m (18 inches) from the edge of the pipe for stability. The contractor should support the excavations with appropriate shoring to avoid undermining the soil supporting the roadway and existing utilities.

For the storm sewers located near the existing creek, organic silty clay loam soils are likely to be encountered at the proposed sewer bearing elevations. We recommend the proposed subgrades be undercut a minimum of 2 feet, and backfilled with two layers of geogrid reinforced INDOT No. 53 crushed aggregate to the proposed pipe invert elevation as recommended for the proposed box culvert structure 191.

The INDOT standard drainage structure installation detail, Figure 16, is included in the Appendix. "B" Borrow surrounding all pipe structures in the excavated trenches should be compacted to 95 percent of the maximum dry density as determined by AASHTO T-99 (Standard Proctor). The soil in the bottom of the excavations, any bedding material and the engineered fill for structure backfill, should be tested to determine that tested locations comply with this density criterion. If 95 percent of the maximum dry density can not be obtained at the bottom of the excavations, or in the others areas, the Geotechnical Section of INDOT should be contacted for additional recommendations.

When the level of the fill reaches the top of the structure, two lifts, about 150 mm (6 inches) each, should be carefully spread and hand compacted over the structure without the use of heavy equipment. The backfill should be compacted to at least 95 percent of the maximum dry density as determined by AASHTO T-99 except the first 2 lifts above the structure. Mechanical compaction over the sewer structures may commence after the second lift is placed and compacted.

It is important to protect the sewer structures during construction. To avoid imposing concentrated loads far in excess of those the drainage structures would normally carry, heavy construction equipment should not cross the structures until fill placement and compaction is completed. Also, heavy vehicles moving too close to the walls of the structures can create an eccentric loading with potentially harmful results.

# 6.4 Excavations

In Federal Register, Volume 54, No. 209 (October 1989), the United States Department of Labor, Occupational Safety and Health Administration (OSHA) amended its "Construction Standards for Excavations, 29 CFR, part 1926, Subpart P". This document was issued to better provide for the safety of workers entering trenches or excavations. This federal regulation mandates that excavations, whether they be utility trenches, basement excavation or footing excavations, be constructed in accordance with the OSHA guidelines. It is our understanding that these regulations are being strictly enforced and if they are not closely followed, the owner and the contractor could be liable for substantial penalties.

The contractor is solely responsible for designing and constructing stable, temporary excavations and should shore, slope, or bench the sides of the excavations as required to maintain stability of both the excavation sides and bottom. The contractor's "responsible person", as defined in 29 CFR Part 1926, should evaluate the soil exposed in the excavations as part of the contractor's safety procedures. In no case should slope height, slope inclination, or excavation depth,

including utility trench excavation depth, exceed those specified in local, state, and federal safety regulations.

We are providing this information solely as a service to our client. PSI does not assume responsibility for construction site safety or the contractor's or other parties compliance with local, state, and federal safety or other regulations.

# 6.5 Groundwater Control

Fill placement for the roadway in areas, which are undercut due to organics or stabilization, must be performed in the dry. The Contractor should be prepared to control groundwater and surface water in order to perform all construction in the dry.

Based on the results from the subsurface exploration, we anticipate groundwater is likely to be encountered in the trench excavations at or below about 18 to 20 feet, or about elevation 609 feet to 612 feet (185.6 to 186.5 m). However, localized zones of apparent perched water were observed at about 6 feet (1.8 m) in boring RB-8, and may be present elsewhere at shallower depths depending on seasonal conditions. For the majority of the sewer excavation alignment, we anticipate infiltrating perched and trapped water and runoff can likely be handled with conventional sump and pump techniques.

However, portions of the sewer alignment extend deeper than about 18 to 20 feet below existing grade. Due to the presence of wet loose sand encountered at the storm sewer bearing elevation in the vicinity of Borings RB-6-SG and RB-7-SG, we anticipate shallow sumps will not be sufficient to control water seepage in this area. We anticipate water seepage can then be controlled using a dewatering system such as wellpoints or deep wells with a proper casing and filter system. We anticipate that water will need to be removed constantly during the entire period of construction. Failure to adequately control groundwater will result in severe subgrade instability in the loose sand.

The groundwater levels were encountered near the existing toe of slope near the proposed box culvert, at elevation about 609 feet (185.6 m). Therefore, we anticipate dewatering by means of wellpoints or deep wells will be necessary during the construction of the proposed culvert and storm sewers in order to excavate for the structures and install the granular/geogrid blankets. We

The contractor should plan appropriate site drainage prior to commencing any excavation. Proper site drainage of surface runoff water will help to alleviate unwanted intrusion into the excavation during the construction process.

## **REPORT LIMITATIONS**


The recommendations submitted, in this report, are based on the available subsurface information obtained by PSI and design details furnished by The HNTB Companies for the proposed project. If there are any revisions to the plans for this project, or if deviations from the subsurface conditions noted in this report are encountered during construction, PSI should be notified immediately to determine if changes in the foundation recommendations are required. If PSI is not notified of such changes, PSI will not be responsible for the impact of those changes on the project.


The geotechnical engineer warrants that the findings, recommendations, specifications, or professional advice contained herein have been made in accordance with generally accepted professional geotechnical engineering practices in the local area. No other warranties are implied or expressed.


After the plans and specifications are more complete, the geotechnical engineer should be retained and provided the opportunity to review the final design plans and specifications to check that our engineering recommendations have been properly incorporated into the design documents. At this time, it may be necessary to submit supplementary recommendations. PSI will perform this review using the INDOT Geotechnical Review of Final Check Prints form. This report has been prepared for the exclusive use of The HNTB Companies for the specific application to the proposed 61<sup>st</sup> Avenue widening and improvements project in Hobart, Indiana.

# APPENDIX

- 1. Figure 1, General Site Plan
- 2. Figure 2, Site Vicinity Map USGS Topographic Map
- 3. Figures 3a and 3b, Soil Boring Location Plans
- 4. Boring Logs (RB-1-SG through RB-11-SG, TB-1-SG, and TB-2)
- 5. General Notes (AASHTO/INDOT)
- 6. Summary of Soundings (1)
- 7. Summary of Classification Test Results
- 8. Summary of Special Laboratory Test Results (5)
- 9. Figures 4 through 12, Particle Size Distribution Test Reports
- 10. Figure 13, Consolidation Test (TB-2, 2/ST)
- 11. Consolidation Test (TB-2, 2/ST)
- 12. Unconfined Compression Strength Tests (4)
- 13. Figure 14, Proctor Test Report (RB-2, 1/BS)
- 14. Summary of CBR Test Results (RB-2, 1/BS)
- 15. Figure 15, CBR Test Curve (RB-2, 1/BS)
- 16. Settlement Analyses (at Station 51+50, Line "A") (4)
- 17. Wick Drain Analysis
- 18. Bearing Capacity Analysis for Vibro-Concrete Column (VCC)
- 19. Figure 16, Drainage Structure Installation Details
- 20. Special Provision for Vibro-Compacted Concrete Columns








 $\overline{O}$ 8

30+00 N BEGIN PROJECT P.J. STA. 27+95.56 LINE "A" JOSE & CHRISTINA EL!ZONDO PETE GLEGOROVICH psi PI. STA. 27:95.56 "A" (NO CURVE RUN) A = 0:07/25 LT. = PJ. STA. 50:00.00 "S-HA" (NO CURVE RUN) A = 3'35/34 RT. 7225 Georgetown Road Indianapolis, IN 46268 (317) 216 - 7131 RB-5-SG 30+00 Project: 61st Avenue Improvements Client: HNTB, Inc. Location: Lake County, Indiana PSI Job No.: 016-15159 Date: 3/02 Project No.: STP-N606( ) & CM-9945( ) Date: 1"=200'± DES No.: 0088390 & 0100881 6' Lt."A" 40 EASEMENT FOR GAS PIPELINE 2 3 4 5 6 0 **B** 9 LOT 2 LOT 3 LOT 4 LOT 5 LOT 6 LOT 7 LOT 8 LOT MERRILLVILLE HEIGHTS SUBDIVISION PJ. STA. 48+29.10 "S-1-A" (NO CURVE RUN) Δ= 3'30'09" LT. P.O.T. STA. 47+50.00 "S-+-A" MERRILLYILLE HEIGHT'S SUBDIVISION OWNER LOT NO. JANES & BETTY HARRINGTON DAVID ROSAS JOSEPTH & PHYLLIS Majedward SHEILIA GREENBURG JOSEPH & MARILYN HENDRICKSON SIGISMUND & PHYLLIS STEFANKIEWICZ 6 BUDDY & IRENE RAMSEY FRANK & FILOMENA MERVA 8 ANDY JACOB 9 soil boring location plan Figure 3A



PJ. STA. 61+00.00 "A" (NO CURVE RUN) Δ = 3\*25'23" END PROJECT P.J. STA. 62+04.00 LINE "A" (NO CURVE RUN) A= 477'08" SECTION LINE-LINE "A" L GIST AVENUE **psi** RB-9-SG 62+00 7225 Georgetown Road 6' Lt."A" Indianapolis, IN 46268 (317) 216 - 7131 STP-N606( ) & CM-9945( ) S No.: 0088390 & 0100881 DES No.: Project: 61st Avenue Improvements Client: HNTB, Inc. Location: Lake County, Indiana PSI Job No.: 016-15159 Date: 3/02 Project No.: STI Scale: 1"=200'± DES No soil boring location plan Figure 3B

		Proj. #: 016-15	159	Boring Lo	o dia		
Client: The HNTE	3 Companies	Sheet: 1 of	1	Number:	-		fessional
Project: DES No.: 0088;	P-N606()/CM-9945() 390/0100881 ening & Improvements	Location.		Lt. "A" Inty, India	na		Service stries, Inc.
t) Ape	PCF Indicates Sample Dry Pounds Per Cubi	Unit Weight in c Foot	ers)	⊗ "N" Blows	s Per Foot oisture Content	Strength	d Hand
Sample No./Type Sample Distance Recovery Depth (feet)	Description Of	Material	Depth (meters)	 P.L.% 0	•• [] L.L.%	· · ·	neter (TSF) d Shear Strength 4 6
	Surface Elevation (USC & GS			Scale: 40/	inch	Scale: 4	/inch
	iller reported 15" CONCRE GRAVEL SUBGRADE (visu						
	LTY CLAY LOAM - stiff - n ab No. 8395SL			\$3,5,6			
2/33	LTY CLAY - with interbedo medium stiff to soft - moist elow 6' - brown & gray A-6	to very moist		\$3,4,3			
3/33	LAY - medium stiff - moist			\$1,3,2			
	o. 8397SL		3	\$3,4,5	,		
	ILTY CLAY - very stiff - mc ab No. 8399SL	ist - brown A-7-6,	4				
5/SS	AND - medium dense - moi o. 8398SL	st - brown A-3, Lab		<b>●</b> ⊗6,	9,10		
	ND OF BORING 15'						
	**Cave-in @ 11 1/2' follov augers. Dry to cave-in de Weather: Cloudy.	pth of 11 1/2'.					
Note: The stratificat	ion lines indicated herein						
Water Level C		ng Started: 11-21			Drawn By: SV		proved: FAL
Dry **	at completion		-21-0		Office: India		e: 15159
	@ hrs. after					Benton	to d
	completion Not	te: Boring backfille	ed witl	n soil cuttin	gs unless otl	nerwise no	πεα.

Client:			<del>تستعممي</del> .		Proj. #: 016-	15159	9		oring umbo	Log er:		-2-8	20		Pro	fes	sior	nal	٦
		Th	e HN	ITB Companies	Sheet: 1	of <b>1</b>				ा - इ.स. ह	nD D	-2-0					/ice		
Project: 61s	DE	S No	o.: 00	STP-N606()/CM-9945() 88390/0100881 /idening & Improvements	Location.	62,6 Lake C				liana	a				ndu	stri	es,	Inc	;.
be	ee			PCF Indicates Sample Dry Pounds Per Cubic	Unit Weight in c Foot		le l	0			er Foo			Stre	confin ength ibrate netrom	(TSF)		sive	
No./Ty	Distan	Recovery	Depth (feet)	Description Of N	Vaterial	Douth (meterc)	ווומום	<u>ک</u>	<u> </u>	<b>6</b>	sture (	-0		XUn	draine		(TSF) ear Str	ength	<u>,</u>
Sample No./Type	Sample Distance	Rec	Deptl			4+000	nebru	P.L 0	20	+	40	L.L.%	60		2	<u> </u>	4		6
Ю				Surface Elevation (USC & GS				Sca	le: 4	10/in	ch			Sca	le: 4	/inch			_
			 	Driller reported 15" ASPHAL GRAVEL SUBGRADE (visual)	T over 9" SAND		TTTTT								*				
1/SS			  	SILTY CLAY LOAM - soft - m A-4(7), Lab No. 8395SL			1	<b>⊗</b> 1,2	2,3	24 <u>A</u> -	34 <del> </del> ]	89.4							
2/SS				CLAY - very soft - most - gra 8397SL			1111	\$1,1,	,1	•		95.0	Opcf		$\leq$	<u> </u>			
3/SS				SILTY CLAY - stiff to mediun A-6(21), Lab No. 8396SL	n stiff - moist - g	gray E	2		04,5		_					Q			
4/SS								\$	19 ⊿ 3,3,0	<u> </u>	[]						×		
.,			= 10 • -				3												
				] - SAND - loose - very moist - l - 8398SL	brown A-3, Lab	No.	4					_							
5/SS			- 	END OF BORING 15'		Ē		\$2	,3,3										
													:						
				1/ST 2'-4' Recovery = 50% MC = 24.0%, Dry Density	5 = 89.4pcf														
				Lab No. 8473SL 2/ST 4'-6' Recovery = 100 MC = 25.9%, Dry Density	% = 95.0pcf														
				Lab No. 8474SL 1/BS pH = 7.86															
				<b>4/SS</b> pH = 8.65				,											
•																			
				**Cave-in @ 13' following Dry to cave-in depth of 1 Weather: Cloudy.	removal of auge 3'.	ers.													
Note	: Th	e st	ratifi	cation lines indicated herein	are approxima	te; In-s	itu	the t	tran	sitio	n be	twee	en s	oil ty	/pes	may	be	grad	ual
					ing Started: 11						)rawn	By:	SW		· Aj	oprov	/ed:	P4,	r
_		Dry	<u> </u>		ing Completed:	11-2	1-0	1	<u> </u>	C	Office	: In	diar	na	Fi	le:	151	59	در ا
-		**		at completion @Rig:	CME-55 (	Truck)				ſ	Driller		<b>S</b> .	Bent	on			<del></del>	-
				@ hrs. after completion Not	te: Boring bac	kfilled v	with	n soil	cut	tting	is un	less	oth	erwi	se n	oted	، ، ا		

Client:					Proj. #: 016-15	159	Boring Numbe		3-3-SG	Pr	ofess	sional
				TB Companies	Sheet: <b>1</b> of	1					Serv	ice
Project:	DES	No	.: 008	STP-N606()/CM-9945() 38390/0100881 dening & Improvements	Location	4, 6' L e Cou	t. "A" Inty, Indi	ana				es, Inc.
/pe	e			PCF Indicates Sample Dry Pounds Per Cubic	Unit Weight in 5 Foot	rs)	⊗ "N" Blov			( <sup>*</sup> Calibra	h (TSF) ted Hand	1
Sample No./Type	Sample Distance	Recovery	Depth (feet)	Description Of N	Material	Depth (meters)	● Natural  P.L.% 0 20		- [] L.L.%	× Undrair (KSF)	ometer (1 ned Shea 2	rSF) r Strength 4 6
Sai	Sa			Surface Elevation (USC & GS	): 631.6'		Scale: 40	D/inch		Scale:	4/inch	
				Driller reported 15" ASPHALT GRAVEL SUBGRADE (visual)	Fover 9" SAND &						÷	
1/SS			·	SILTY CLAY LOAM - stiff - m Lab No. 8395SL	oist - brown A-4,		<b>⊗3,5,6</b>				σ	
2/SS			•	SILTY CLAY - soft to very sti A-6, Lab No. 8396SL	ff - moist - brown		\$3,5,3					
3/SS		-	• =- • •			2	\$2,3,2					
4/SS			  - 10 -			3	\$3,3,5	•		¢*		
								1				
5/SS				SAND - medium dense - very Lab No. 8398SL	v moist - brown A-3	4		5,9,10			<u>.</u>	
				Lad No. 63963L		5						
.6/SS			 			6	Ø4,5	6				
			<b>=</b> 20 <b>=</b>	END OF BORING 20'								
				NOTE: Two attempts were r without recovery.	nake @ 2/SS							
				**Cave-in @ 17' following Dry to cave-in depth of 1 Weather: Cloudy.	removal of augers. 7'.							
Note:	The	e str	atific	ation lines indicated herein	are approximate;	n-situ	the transi	ition be	tween s	oil type:	s may	
	_				ng Started: 11-21				n By: <b>SW</b>		Approve	~ / .
		Dry		while drilling Bori	ng Completed: 11	-21-0	1	Office	: Indiar	na F	ile: <b>1</b>	5159
[		* *		at completion Rig:	CME-55 (Tru	ck)		Driller	: S.	Benton		
				hrs. after completion Not	e: Boring backfill	ed with	n soil cutt	ings un	less oth	erwise ı	noted.	

Ą

Olivert.				Proj. #: 016-15	159	Boring	Loa				_	
Client:	٦	۔ he H	NTB Companies	Sheet: <b>1</b> of	1	Numbe		B-4-S	G	Profe		
Project: 61s	DES	No.: 00	STP-N606()/CM-9945() 088390/0100881 Videning & Improvemen	Looution.		Lt. "A" unty, Indi	iana	化的过去式	In	Ser ndustr	rvice ries,	
e d	e S		PCF Indicates Sampl Pounds Per	e Dry Unit Weight in Cubic Foot	() ()	⊗ "N" Blo	ws Per F	oot	Stre	confined C ength (TSI	F)	sive
Sample No./Type	Sample Distance	Depth (feet)	Description	Of Material	Depth (meters)	● Natural		[] L.L.%	Pen	ibrated Ha netrometer drained Sh SF) 2	r (TSF)	ngth
Sa	Š		Surface Elevation (USC	& GS): 633.8'		Scale: 40	0/inch		Scal	e: 4/incl	} h	
1/SS			Driller reported 9" ASPH AGGREGATE over 10" S COURSE (visual) SILTY CLAY LOAM - wi	SAND & GRAVEL BASE		\$2,3,3 I		93.8p	cf	9		
2/SS		5	medium stiff - moist - da below 2.5' A-4, Lab No. CLAY - medium stiff to A-7-6(22), Lab No. 839	. 8395SL soft - moist - brown		19 \$2,3,4	,	44 †⊡				
3/SS			- - - -		2	\$2,2,2						
4/SS		10	SILTY CLAY - medium s A-7-6, Lab No. 8399SL	tiff - moist - brown	3	\$1,3,3	•			0		
5/SS		- - - - - - - - - -	SAND - medium dense - Lab No. 8398SL	very moist - brown A-3	4	\$4,7	,7					
6/SS			END OF BORING 20'		6	\$3,5,	7					
·			1/ST 2'-4' Recovery = MC = 27.5%, Dry Den Lab No. 8475SL LOI = 5.8% 2/SS pH = 8.22									
			**Cave-in @ 17' follow Dry to cave-in depth Weather: Cloudy.									
Note:	The s	tratific	ation lines indicated her	ein are approximate; I	n-situ 1	the transit	ion be	tween s	soil typ	es may	be gra	adua
			el Observation	Boring Started: 11-21-	01		Drawr	n By: <b>SV</b>	v	Approv	ed: }	Xı
<del></del>	<u>Dr</u>			Boring Completed: 11	21-01	1	Office	India	na	File:	15159	)
<b></b> .	**	-	at completion @hrs. after	Rig: CME-55 (Truc	k)		Driller	: S.	Bento	n		

Client:			Proj. #: 016-15	159	Boring Numb		RB-5	.56		Pro	fes	sior	nal
		TB Companies	Sheet: <b>1</b> of	1			mb-5-	50		S	Serv	/ice	
Project: DES N	lo.: 008	STP-N606()/CM-9945() 38390/0100881 idening & Improvements	Location.		.t. "A" unty, Ind	liana			lr	ndu	stri	es,	Inc.
e e		PCF Indicates Sample I Pounds Per C		s)	⊗ "N" Blo	ws Pe	er Foot		Stre	ength	(TSF)		sive
No./Type Diŝtance overy	feet)			leter	Natural	Moist	ure Conte	ent [	( <sup>*</sup> Cal Per	ibrate letron	d Har neter	d (TSF)	
Sample No./Type Sample Distance Recovery	Depth (feet)	Description C	f Material	Depth (meters)	∆ P.L.%	•	[] L.L.		X Und (KS		d She	ar Stre	ngth
Sample Sample Reco	l õ			Dep	0 20	1	40	60		2		4	6
		Surface Elevation (USC & Driller reported 9" ASPHA			Scale: 4	0/inc	h		Scal	e: 4	/inch :		
777 6 5 5 5	+ +	GRAVEL BASE COURSE (	visual)					2pcf			<u></u>		
1/SS		SILTY CLAY LOAM - med moist - brown A-4, Lab No			⊗2,3,3		57	zpei					
2/SS	+ -				●3,4,5	þ					Ì,		
2,00		SILTY CLAY - medium stil	f - moist - brown A-6,			-1							
3/SS		Lab No. 8396SL		2	\$2,3,4	•					Ø.		
		SILTY CLAY - medium stit	f - moist - brown							/	<u>/</u> *		
4/SS		A-7-6, Lab No. 8399SL			\$3,2,4	•				Ŭ,			
777		SAND - medium dense - v	ery moist - brown A-3	4									
5/SS		Lab No. 8398SL			\$7,0	5,8							
			·				1						
					⊗3,5,	6							
6/SS	20 -	END OF BORING 20'		6	00,0								
		1/ST 1.5'-3.5' Recovery											
		MC = 26.7%, Dry Densit Lab No. 8467SL	y = 97.2pcf										
		**Cave-in @ 17' followir	ng removal of augers.										
		Dry to cave-in depth or Weather: Cloudy.											
Note: The st	rotifica	ation lines indicated here	in are annrovimato: l		the trans	tion	hetwee	i n so	il tyr		nav	i be ar	adual
}			oring Started: 11-20-				wn By:		cyl			d: D	
Dry				·20-0'	1		ice: In			File		5159	
**		at completion	ig: CME-55 (Truc		•	Dril		S. B	_				
Dry		@ 24 hrs. after	ote: Boring backfille	_	soil cutt						ted		
I		completion N	ote. During Dackrille		Son out	ingo	011033	0.118		- 10			

Å

Client:					Proj. #: 016-15		Boring		B-6-S	G	Pro	fess	iona	
				TB Companies	Sheet: <b>1</b> of	1						Servi	ce	
Project:	DE	ŚNa	.: 00	STP-N606()/CM-9945() 88390/0100881 idening & Improvements	<sub>Location:</sub> 36+0 Lak		.t. "A" Inty, Ind	iana			Indu	strie	s, In	с.
ype	ce		~	PCF Indicates Sample Dry Pounds Per Cubic	Unit Weight in c Foot	rs)	⊗ "N" Blo				Unconfir Strength Calibrate	(TSF)		e
Sample No./Type	Sample Distance	Recovery	th (feet)	Description Of N	Viaterial	Depth (meters)	Natural A P.L.%				Penetror Undraine (KSF)	neter (TS		th
Sample	Sample	Re	Depth (	Surface Elevation (USC & GS	N. 629 0'	Depth	0 20 Scale: 4	<del></del>		000	2 	/inch	4 <del>  </del>	6
				Driller reported 12" ASPHALT			Scale, 4	Omen				:		
1/00	777		•	GRAVEL BASE COURSE (visu SILTY LOAM - soft - moist - I	Jal)		<b>\$3,2,3</b>	•	98,2p	ocf		\$		
1/SS				8401SL			00,2,0							
2/SS			5	SILTY CLAY - medium stiff - Lab No. 8396SL	moist - brown A-6,		\$2,3,4				Q		X	
3/SS			 	SILTY CLAY - medium stiff - A-7-6, Lab No. 8399SL	moist - brown	2	\$4,4,5	•					<b>A</b> 4	.5+
4/SS			 				\$3,3,4	•				ð		
			10											
			 	SAND - medium dense to loc	ose - very moist to	4					-			
5/SS			15	wet below 18' - brown A-3,	Lab No. 8298SL		\$5,5	,8						
						5								
6/SS							\$3,4,5							
			- 20 -	END OF BORING 20'		<u> </u>								
				1/ST 1.5'-3.5' Recovery = 1 MC = 24.3%, Dry Density	50% = 98.2pcf									
				Lab No. 8477SL 5/SS pH = 8.51										
					1.									
ļ														
				**Cave-in @ 17' following Dry to cave-in depth of 1 Weather: Cloudy.										
Note:	The	e str	atific	ation lines indicated herein	are approximate; lr	n-situ	the transi	tion be	etween	soil	types	may be	e grac	lual
	١	Nate	er Leve	el Observation Borir	ng Started: 11-20-	01		Draw	n By: <b>S</b>	W	Ap	proved	P4	L
	19	1/: * *	2'		ng Completed: 11-	20-0	1	Office	e: India	ana	Fil	e: 15	159	
	16	<u>* *</u> ; 1/:	2'	at completion @ <b>24</b> hrs. after	CME-55 (Truc			Drille			nton	· · · · ·		
				completion Not	e: Boring backfille	d with	soil cutt	ings ur	nless ot	herv	wise no	ted.		

h

Client:	Proj. #: 016-1	Nu	oring Log umber: <b>RB-7-S(</b>	G Professional
The HNTB Compani				Service
Project No.: STP-N606()/CN Project: DES No.: 0088390/010088 61st Avenue Widening & Imp	1 Location:	40, 27' Lt. "A ke County,		Industries, Inc.
PCF Indica	tes Sample Dry Unit Weight in ounds Per Cubic Foot	-	" Blows Per Foot	O Unconfined Compressive Strength (TSF)
o./Ty istan feet)		na ● Na	tural Moisture Content	O <sup>*</sup> Calibrated Hand Penetrometer (TSF)
Sample No./Type Sample Distance Recovery Depth (feet)	scription Of Material	Depth (meters) → 0 → 1 → 0 → 0 → 1 → 0 → 1 → 1 → 1 → 1 → 1 → 1 → 1 → 1		X Undrained Shear Strength (KSF)
Sample No./Type Sample Distance Recovery Depth (feet)			····	
Surface Eleva	tion (USC & GS): 629.1' 1 3" ASPHALT over 15" SAND &		e: 40/inch	Scale: 4/inch
GRAVEL BASE	E COURSE (visual)		98,6p	→ <b>F</b> ()
	OAM - medium stiff to soft - A-4, Lab No. 8395SL	₩ 3,3	3,3 \	
2/SS			,2 i 94.1p	
			1	
	medium stiff - moist - brown to ?' A-7-6, Lab No. 8399SL	2 33,	.3,4	
	A-7-0, Lab NO. 03993L			
4/SS			3,4,5 i	Ϋ
			1	
				<b>*</b>
5/SS			8,4,4	Ŷ
	um dense - wet - brown A-3, Lab			
6/SS		6	\$5,9,10	
7/SS			\$6,7,9	
25 END OF BORI	NG 25'			
1/ST 1.5'-3.5 MC = 24.5%	5' Recovery = 100% 6, Dry Density = 98.2pcf			
Lab No. 8478	3SL 5' Recovery = 100%			
MC = 27.5%	6, Dry Density = 94.1pcf			
Lab No. 8479	JSL			
	16' following removal of augers.			
Weather: Clo				
Note: The stratification lines ind	icated herein are approximate;	In-situ the tr	ansition between	soil types may be gradual
Water Level Observation	Boring Started: 11-28	3-01	Drawn By: S	
<u>18 1/2'</u> while dril	Bornig Completed:	1-28-01	Office: India	na File: 15159
	Rig: CME-55 (Tru	ick)	Driller: S.	Benton
	mpletion Note: Boring backfil	led with soil o	cuttings unless ot	nerwise noted.

ŕ.

Client:					Proj. #: 016-151	59	Boring Lo			Duefe	
Client:		Tł	ne HN	ITB Companies	Sheet: 1 of	1	Number:	F	RB-8		ssion
Project: 61s	DE	ŚN	o.: 00	STP-N606()/CM-9945() 88390/0100881 /idening & Improvements	Location: 57+00		Lt. "A" nty, India	na		Se Indust	rvice ries, lı
ed	ce			PCF Indicates Sample Dry Pounds Per Cubic	Unit Weight in Foot	(s)	⊗ "N" Blows			Unconfined Strength (TS Calibrated H	\$F)
Sample No./Type	Sample Distance	Recovery	Depth (feet)	Description Of N	Naterial	Depth (meters)	● Natural M  P.L.% 0 20	•	- [] L.L.%	Penetromete X Undrained S (KSF)	r (TSF)
Sar	Sa			Surface Elevation (USC & GS	): 625.0'		Scale: 40/	inch		Scale: 4/inc	<u>⊦</u> :h
				Driller reported 12" brown CL		= =					*
1/SS 2/SS	H			(visual) SILTY LOAM - medium stiff - A-4(1), Lab No. 8401SL	moist - brown		©3,4,54 ©3,4,4	5	104 9pcf	, de	φ
3/SS			5	SILTY CLAY - stiff to medium wet below 12' - brown to gra Lab No. 8399SL	n stiff - moist to ay below 8' A-7-6,	2	\$4,7,£	3		4	*
4/SS			10				\$3,5,7 \				/
5/SS			   		na National National		\$3,3,4			¢*	
6/SS						0 11111111	\$2,3,3			ď*	
			- <b></b> 20 <b>*</b>	END OF BORING 20'							
•				1/ST 1'-2.5' Recovery = 67 MC = 21.6%, Dry Density = Lab No. 8480SL 1/BS pH = 8.46							
				**Cave-in @ 9' following re Dry to cave-in depth of 9' Weather: Cloudy.							
Note:	Th	e st	ratific	cation lines indicated herein a	are approximate; In	-situ t	he transiti	on bet	ween so	il types ma	y be gra
			er Lev	el Observation Borin	ng Started: 11-28-0	)1		Drawn	By: <b>SW</b>		ved: R
					Boring Completed: 11-28-01				Indiana	a File:	15159
	<u> </u>	**		- at completion Rig:	CME-55 (Truc	k)		Driller:	S. B	enton	
1 —				hrs. after completion Note	e: Boring backfilled	l with	soil cuttin	as unl	ess othe	rwise noter	

Client:						Proj. #: 016-			Boring	-	RB-9	.SG		Pro	fes	ssio	nal	٦
		The	e HN	TB Companies		Sheet: 1	of <b>1</b>	-					4	ç	Ser	vice	е	
Project:	DE	S No.	.: 008	STP-N606()/CM-9945() 38390/0100881 idening & Improvemei	nts	Location.	2+00, 6 Lake Co		t. "A" inty, Ind	iana	I			ndu	stri	ies,	Ind	
ed	e			PCF Indicates Samp Pounds Pe	le Dry U r Cubic I	nit Weight in Foot	(S		⊗ "N" Blo			1		nconfir rength alibrate			ssive	
Sample No./Type	Sample Distance	Recovery	Depth (feet)	Description	n Of M	aterial	Depth (meters)		● Natural  P.L.% 0 20	•	ture Conto 		Pe ×Ur (K	netron ndraine SF) 2	neter	(TSF)		ר 6
လိ	ů			Surface Elevation (USC	: & GS):	628.7'		ſ	Scale: 4	, 0/inc	h		Sca	ale: 4	, /inch	•		
				Driller reported 18" ASI	PHALT	(visual)	=	-										
1/SS 2/SS			- 5 -	SILTY LOAM - medium gray A-4, Lab No. 8401		noist - brown 8			\$3,4,4 \$2,3,4		102	3pcf		¢	Ø			
3/SS 4/SS	[]]] []]			SILTY CLAY - with trac medium stiff - moist - b No. 8396SL	ce organ prown &	ic matter - sof ≀ black A-6, La	t to 2 b		\$2,2,3 \$2,3,3	• • •				Ĵ ¢				
1,00			10 <b>-</b>	CLAY - medium stiff - r No. 8397SL	moist -	gray A-7-6, La	b 4			1 1 1								
5/SS			•15 <b>-</b>				5		\$3,4,5	•				Ф <b>,</b>				
6/SS			•20	SAND - medium dense \8398SL END OF BORING 20'	- wet -	gray A-3, Lab	No. <u>6</u>		\$7	,8,9								
			•	1/ST 1.5'-3.5' Recove MC = 20.9%, Dry Der Lab No. 8481SL 3/SS LOI = 4.4%														
				**Cave-in @ 18' follo Dry to cave-in depth Weather: Cloudy.			ſS.											-
Note:	The	stra	atifica	ation lines indicated he	erein ar	e approximat	e; In-situ	u t	he transi	tion	betwee	en so	oil ty	pes i	may	be g	gradi	Jal
	' N	Vater	Leve	l Observation	Boring	Started: 11-	19-01			Dra	wn By:	sw		Ap	prov	ed:	p41	_
		<b>7</b>		while drilling	Boring	Completed:	11-19-	01		Of	ice: In	dian	а	File	e: <b>*</b>	151	59	
	17	7'**		at completion	Rig:	CME-55 (T				Dri	ller:	S. E	Bent	on				
	5	1/2'	r 	@ 24 hrs. after completion		Boring back		th	soil cutti					_	ted			
			-	completion		Doning Duok												

ņ

Client:					Proj. #: 016-15159 Bori									
		Ił	ne Hľ	NTB Companies	Sheet: <b>1</b> of	1	Nu	mber:	RB	·10-S	G			ional
roject:	DE	ŚΝ	o.: 00	STP-N606()/CM-9945() 88390/0100881 /idening & Improvements	Looddon		Rt. "S-4 unty,		na				ervi strie:	ce s, Inc
ype	nce			PCF Indicates Sample I Pounds Per C	Dry Unit Weight in Tubic Foot	rs)		' Blows			S	Inconfine trength (	TSF)	
Sample No./Type	Sample Diŝtance	Recovery	Depth (feet)	Description C	of Material	Depth (meters)	● Nat  P.L. 0		D	- [] L.L.%	Xu	alibrated enetrome Indrained (SF) 2		SF) Strength
S	0)			Surface Elevation (USC &	GS): 625.0'		Scale	: 40/ir	nch '		Sc	ale: 4/i	nch	
1/SS				Driller reported 12" ASPH SILTY CLAY - with trace of medium stiff - moist - blac	organic matter -		Ø3,3	,4		105 3pc	f			Q <sup>*</sup> 4.5+
2/SS				8396SL SILTY CLAY - medium stil gray A-7-6, Lab No. 8399			¢3,	4,5 \			-			0 4.5+
3/SS				END OF BORING 7.5'		2	 ⊗3,3	8,4					ð	
				END OF BORING 7.5										
											-			
•			·	1/SS LOI = 5.9% 1/ST 1'-3' Recovery = 10 MC = 21.9%, Dry Densit Lab No. 8482SL										
				**Cave-in @ 5' following Dry to cave-in depth of Weather: Cloudy.										
lote: T	he	str	atifica	ation lines indicated herei	n are approximate; In	-situ t	he trar	nsition	betw	/een so	oil ty	pes ma	iy be	gradual
	V	/ate	Level	Observation Bo	oring Started: 11-19-0	)1		Dr	awn B	y: SW		Appro	oved:	PM
			ring Completed: 11-	19-01		Of	fice:	Indian	а	File:	151	59		
		ry		at completion @ 24 hrs. after completion No	g: CME-55 (Truck ote: Boring backfilled				iller:	S.E				

.

Client:						Proj. #: <b>016-</b> 1	5159		oring L				Dr	ofoe	siona	
		Th	ne HN	ITB Companies		Sheet: <b>1</b> c	of 1		lumber:	RB	-11-S	G				וג
Project	Pro	ject	No.:	STP-N606()/CM-9945() 88390/0100881		Location: 49	+ 30, 8'	Rt. "S	5-4-A"					Serv		
				idening & Improveme	ents		ake Co	unty,	, India	na			Indu	Istri	es, Ir	nc.
				PCF Indicates Sam				⊗"	N" Blow	s Per Fo	ot		Jnconfi Strengtl		mpressiv	/e
Гуре	ance		et)	Pounds Pe	er Cubic	Foot	ers)	<b>N</b>	atural M	oisture	Content		Calibrat Penetro		±t	
No.7	Dist	Recovery	(feet)	Descriptio		atorial	met	-	∆	· <b>.</b>	- []				ISF) ar Streng	
Sample No./Type	Sample Distance	Rec	Depth	Description		atenai	Depth (meters)		%	•	L.L.%	(	KSF)		a Streng	J.(1) -
San	San			Surface Elevation (US		62E 01	De	0	20	-    	0 60	0	2 ++ cale: 4		4	6
		_		Driller reported 12" AS	-				ile: 40/		:	30		F/INCIT i		
1/00				SILTY LOAM - medium			- <u>E</u>				109:6pc	;f			¥.	
1/SS		7777		A-4, Lab No. 8401SL			ĒĒ		3,5,41 19	4	1					
2/SS				SILTY CLAY - stiff - m Lab No. 8399SL	oist - bro	own A-7-6(22),			3,5,6						<u> </u>	
		7111	- 5 -	Lab NO. 83993L			Ē									
							È,								J*4	ŧ.5+
3/SS							2		\$4,8,6						Ţ	
		////		CLAY - stiff to medium											\$	
4/SS			- = 10 =	gray below 13' A-7-6,	Lab No.	83975L	3		\$3,5,8						/	
							Ē									
									1							
							4						(7	¢ .		
5/SS			 - 15 -				EE	Ø	3,4,5							
				END OF BORING 15'												
							-					ľ				
				<b>1/ST</b> 1'-3' Recovery = MC = 19.4%, Dry De		109.6pcf										
				Lab No. 8483SL	,	·										
				<b>2/SS</b> pH = 8.42												
				- -												
	1			**Cave-in @ 12' follo Dry to cave-in dept			4 -					-				
				Weather: Cloudy.	10112.											
Note:	The	str	atifica	ation lines indicated h	erein are	e approximate:	In-situ 1	the tr	ansitio	n betv	veen s	oil ty	/pes r	nav b	e grad	lual
<u> </u>	_			Observation		Started: 11-19					By: <b>S</b> M		-	proved		
		ry		while drilling			1-19-01	)			Indiar		File		<u>· ٢/</u> 5159	
		*		at completion	_											
	1	.5'		@ <b>24</b> hrs. after	Rig:	CME-55 (Tru	•••			oriller:		Bent				
				completion	Note:	Boring backfil	led with	soil c	cutting	s unle	ss oth	erwi	se no	ted.		

/+ ;						ور میں میں ا								والمتركب المتراف
Client: The HN	TB Companies		Proj. #: 0 Sheet:		159 2	Borin Numl	g Log ber:	TB-1	-SG	1. AND 10	Prof	essi	ona	зI
Project No.: S <sup>Project:</sup> DES No.: 008	TP-N606()/CM-9945()		Location:	51+1	0, 11'	Rt. "A" unty, In	diana		60 y 1 720.	In		ervio tries		۱c.
be	PCF Indicates Samp Pounds Pe	ole Dry U r Cubic F	nit Weight <sup>=</sup> oot	in	s)	⊗ "N" B	iows Pe	er Foot		Stre	ngth (		ressiv	/e
Sample No./Type Sample Distance Recovery Depth (feet)	Descriptior	n Of Ma	aterial		Depth (meters)	● Natura △ P.L.% 0 2	0	ure Cont [] L.L. 40	]	Pen × Und (KS	rained	Hand ter (TS Shear		3th 6
	Surface Elevation (USC					Scale:	40/inc	h		Scale	e: 4/ir	nch		
	Driller reported 6" ASPI SAND & GRAVEL Base	Course	(visual)								ų			
2/SS	CLAY LOAM FILL - stiff black & brown (visual)					\$2,6 \$3,3,4	5				Ρ			
	SILTY CLAY - soft to ve moist - brown & gray (g 8396SL				2		<b>9</b> 3 <b>9</b>	06	2	¢*				
	SILTY CLAY LOAM - w organic matter - soft to A-5, Lab No. 8412SL					\$WOH,2		96 \ \ \	3pcf		0			
5/SS						\$2,2,3								
	SAND - loose to mediur	m dense	- wet - gr	ay A-3,	6	\$1,1,1			•	<u>*</u>				
7/SS	Lab No. 8398SL					\$1,2,5								
8/SS					9 9		7,8,10							
9/SS	SANDY GRAVEL - med A-1-a, Lab No. 8400SL	-			10	\$7,								
and the second	ion lines indicated he					he transi	tion b	etwee	n soil	type	es ma	y be	grad	ual
Water Level C	and the shafting a		Started: 1					vn By:			Appro		P4	$\mathcal{L}$
<u>20 1/2'</u> 10 1/2'**	at completion		Completed:		0-01			e: Inc			File:	151	59	
4.01	@ 24 hrs. after		CME-55 Boring ba			soil cutti	Drille Das u		S. Be			4		
<u>L:</u>	completion			JANEU	***									

Client:				<u></u>	Proj. #: 016-15	159		Boring	g Log	en nationa	3) (S <sup>1</sup> 69)			_		
Client:		TI	ne Hľ	NTB Companies	Sheet: <b>2</b> of	2		Numb		TB-1	-SG					onal
Project: 61s	DE	ŜΝ	o.: 00	STP-N606()/CM-9945() 088390/0100881 /idening & Improvements	Location: 51+1 Lak	0, 11' e Cou			diana	) ·				Sei Jstr		;e , Inc
ype	nce		(	PCF Indicates Sample Dry Pounds Per Cubic	Unit Weight in : Foot	(s)	Ũ			er Foot		St	rengt	h (TS	F)	ressive
Sample No./Type	Sample Diŝtance	Recovery	Depth (feet)	Description Of N	Naterial	Depth (meters)	_	Natura  .L.% 29	0	ture Con [ L.L. 40	]	×υι (K		ted Ha ometer ned Sh		=) Strength
Sa	ŝ			Surface Elevation (USC & GS)			Sc	ale: 4	40/inc	:h	4	Sca	ale:	4/incl	h	}
			 	SANDY GRAVEL - medium de A-1-a, Lab No. 8400SL	ense - wet - gray											
10/SS			40 =			12		\$6	,8,8	-						
11/SS				SILTY CLAY - medium stiff - r Lab No. 8399SL	moist - gray A-7-6,	13	1	3,4,3	•				ď			
11/33			<b>4</b> 5 <b>-</b>	END OF BORING 45'		<u> </u>		0,4,0			<u> </u>					
				1/ST 8'-10' Recovery = 29% 5/SS LOI = 9.5% 6/SS LOI = 7.7%, CA & MG 10/SS pH = 7.95												
				NOTE: Two attempts were m & 8/SS with no recove	ade on 2/SS, 5/SS ery @ 2/SS.											
				**Cave-in @ 16 1/2' followin augers. Weather: Cloudy. ation lines indicated herein a						1					L.	

Client:		Proj.	#: <b>0</b> *	16-15 <sup>-</sup>	159		ng Log		an in the second se		Profe			.1
The HI	NTB Companies	Shee	et: <b>1</b>	of	2	Nur	nber:	T	B-2			rvic		11
Project: DES No.: 00	STP-N606()/CM-9945() 088390/0100881 Videning & Improvemer		tion:			Lt. "A' unty, l		a		In	dusti			ıc.
d de	PCF Indicates Samp Pounds Per	le Dry Unit We r Cubic Foot	eight i	n	s)	⊗ "N"	Blows I	Per Foot			igth (TS	iF)	essiv	е
Sample No./Type Sample Distance Recovery Depth (feet)	Description	Of Materia	al		Depth (meters)	● Natu  P.L.% 0	(	-	ontent .L. % 60	× Undr (KSF	tromete ained Sl	r (TSF		th 6
S N	Surface Elevation (USC	& GS): 609.1	1'			Scale:	40/in	ich		Scale	4/inc	h		
	Driller reported 12" darl	k gray CLAYE	Υ ΤΟ	PSOIL	= =					~*				
1/SS	SILTY CLAY LOAM - w					\$2,2,2			61.5 84-4pcf 70:7pcf	¥.				
	organic matter - soft to brown to black A-5(6),			arĸ	1					¢ ¢<0.2	5			
2/SS						∮woh		3741	68.0pcf					
3/SS					2	эмон		ΆÐ	95.5	0*<0.2	5			
4/SS	LOAM - with trace marl soft - wet - dark brown					рмон		•		Q*<0.2	5			
10-					3				61.7 <b>6</b>					
	SAND - very loose - we 8398SL	t - gray A-3,	Lab N	0.	4									
5/SS						\$1,1,2								
					5									
6/SS					6	\$1,2,3	3							
	- SANDY GRAVEL - medi		loose	- wet										
7/SS	- gray A-1-a, Lab No. 84 -	400SL				\$2	3,8							2
					8									
			- -											
8/SS					9	\$4,4	,4							
	SILTY CLAY - medium moist - gray A-7-6, Lab			very	10					*				
9/SS						\$4,3	,5 / / /							
Note: The stratifica	ation lines indicated he	rein are appr	roxim	ate; In-	situ t	he tran	sition	betw	een so	il type	s may	be ç	iradi	ual
1	l Observation	Boring Starte	d: 1'	1-29-0	1		Dra	awn By	: SW		Approv	ed:	PS1	Ċ
Surface 4'**	while drilling	Boring Compl	eted:	11-2	9-01		Of	fice: I	ndiana		ile:	151	59	
	_ at completion hrs. after	Rig: CME	-55	(Truck	)		Dri	iller:	S. B	enton				
	completion	Note: Borin	ig ba	ckfilled	with	soil cu	ttings	unles	s other	rwise I	noted.			

ę

Client:					Proj. #:	016-15	159		Boring	, Log		20 (* 10	17		_				
Client.		Tł	ne HN	ITB Companies	Sheet:	<b>2</b> of	2		Numb	er:		TB-	2					ona	[
Project: 61s	DE	ŚΝ	o.: 00	STP-N606()/CM-9945() 88390/0100881 /idening & Improvements	Location		0, 24 e Co			liana	a					Ser Jstr		e, In	c.
Type	ance	. ,	et)	PCF Indicates Sample Dry I Pounds Per Cubic	Jnit Weight Foot	t in	ers)	Ĩ	"N" Blo Natural				ent	Ξ S <sup>.</sup>	trengt	ined C h (TSi ted Ha ometer	F)	essive	9
Sample No./Type	Sample Diŝtance	Recovery	Depth (feet)	Description Of M	laterial		Depth (meters)	P.	 .L.%	•	,	- 🗆 L.L.9	%	×u (k	ndrair (SF)	ned Sh		trengt	th
San	Sar			Surface Elevation (USC & GS)	: 609.1'		ď	0 Sc	20    ale: 4		4)   ch		60		ŀ	2 ┝───-  4/incl	—î h		
				SILTY CLAY - medium stiff to moist - gray A-7-6, Lab No. 83		- very			$\left[ \right]$	;			-		$\left  \right\rangle$				
10/SS							12		e		8,11	,18			Į	D*			
			<b>-</b> 40 <b>-</b>	END OF BORING 40'	,														
		-		1/ST 1'-2.5' Recovery = 100 MC = 49.7%, Dry Density = Qu = 0.73 tsf		×													
				LOI = 8.0% 2/ST 5'-7' Recovery = 100% MC = 60.0%, Dry Density = Qu = 0.25 tsf LOI = 7.3%, CA & MG = 8.1	68.0pcf														
				3/ST 10'-11.5' Recovery = 2 Qu = 0.23 tsf 2/SS LOI = 10.0% 4/SS Qu = 1.68 tsf LOI = 4.5%, CA & MG = 8.1															•
					-														· .
•																			
													-						
-																			
				**Cave-in @ 11 1/2' followir augers. Weather: Cloudy.	ng removal	of													

# General Notes - AASHTO/INDOT



# **DRILLING & SAMPLING SYMBOLS**

SS	Split Spoon – 1 3/8" I.D., 2" O.D. except where noted	HA	Hand Auger Boring
ST	Shelby Tube – 3" O.D., except where noted	BS	Bag Sample
PA	Power Auger	RC	Rock Core with Diamond Bit, NX size, except where noted
PS	Piston Sample – 3" diameter	RB	Roller Bit
WB	Wash Boring	N/A	Not applicable or available
WS	Wash Sample		

Standard Penetration Test "N" Value - Blows per foot after an initial 6" seating of a 140 pound hammer falling 30" on a 2" O.D. split spoon, except where noted.

# Water Level Measurement Notations & Symbols

### Particle Sizes

First	When noted during drilling or	Boulder	Greater than 6" (>152.4mm)
	sampling process	Cobbles	3" to 6" (76.2mm to 152.4mm)
Completion	After all drilling tools are removed from borehole	Gravel	#10 to 3" (2.0mm to 76.2mm)
HR	Number of hours after completion	Coarse Sand	#40 to #10 (0.425mm to 2.0mm)
N/R	Not Recorded	Fine Sand	#200 to #40 (0.074mm to 0.425mm)
Dry	No measurable water level found in borehole	Silt/Clay	Minus #200 The term "silty" is applied to fine material boying a placticity index of
	ndicated on the boring logs are the ed in the boring at the time indicated.		material having a plasticity index of 1.0 or less and the term "clayey" is applied to fine material having a

The accurate determination of ground water levels may not be possible with short term observations, especially in impervious soils. The levels shown may fluctuate throughout the year with variations in precipitation, evaporation, runoff, and other hydrogeologic factors.

Minus #200
The term "silty" is applied to fine
material having a plasticity index of
1.0 or less and the term "clayey" is
applied to fine material having a
plasticity index of 11 or greater.

### **CLASSIFICATION**

	Cohesionle	ess Soil		<u>Coh</u>	esive Soil	
Relative Density		<u>"N" Value (Blows/ft)</u>	Consistenc	v	"N" Va	alue (Blows/ft)
Very Loose	<u>-</u>	0-5	Very Soft	-	0-3	<b>_</b>
Loose	-	6-10	Soft	-	4-5	
Medium Dense	_	11-30	Medium	-	6-10	
Dense	-	31-50	Stiff	_	11-15	
Very Dense	-	51 or more	Very Stiff	-	16-30	
<u> </u>			Hard	<u>-</u> '	31 or 1	more
Soils are classifie	ed in	Classification System for	or Organic Soils	Classif	ication Sy	stem for Marly Soils
accordance with		With trace organic matter	1% to 6%	With tra	ace marl	1% to 9%
M145. The Class		With little organic matter	7% to 12%	With lit	tle marl	10% to 17%
Soils and Soil Ag	gregate-	With some organic matter	<sup>-</sup> 13% to 18%	With so	ome marl	18% to 25%
Mixtures for high	way	Organic soil (Ā-8)	19% to 30%		oil (A-8)	26% to 40%
construction purp	oses.	Peat (A-8)	More than 30%	Mari (A	• • •	More than 40%

Professional Service Industries, Inc. Geotechnical, Environmental & Material Consultants Summary of Soundings



ľ

ł.

CLIENT: The HNTB Companies PROJECT: 61<sup>st</sup> Avenue Widening and Improvements PROJECT NO.: CM-9945() & STP-N606() DESIGNATION NO.: 0100881 & 0088390 LOCATION: Hobart, Lake County, Indiana

÷											1	
Page 1 of 1												
Pag												
	DESCRIPTION* (Field Observation)	arl	narl	narl			narl					
	DESCRIPTION* (Field Observation)	Loose Dark Gray Sand/marl	Clay with organic matter/marl	Clay with organic matter/marl			Clay with organic matter/marl					
	ESCF eld O	ay Sa	nic ma	nic m			nic ma					
	D (F	ırk Gr	ı orga	ı orga			orga					
		se Da	y with	y with	Peat/marl	Peat/marl	y with					
		Loc	Cla	Cla	Pea	Pea	Cla					
	EPTH (ft)	0 – 2.0	0 - 0.5	0 – 3.5	0 – 3.0	0 – 2.0	0 - 1.0					
	DEPTH (ft)	- 0	- 0	- 0	- 0	- 0	- 0					1 2
	ACE								• .			
	APPROX, SURFACE ELEV. (ft)	+1	-1-1	-1-1	-+1	+1	-+-1					
	KOX. SURI ELEV. (ft)	∓609	<b>∓</b> 609	年609	<del>1</del> 609	<del>1</del> 609	<b>∓</b> 609					2
	PPR( E		·						· · ·		-	1
	A									·		
	ET	Rt. "A"	Rt. "A"	Rt. "A"	Lt. "A"	Lt. "A"	Lt. "A"					44 12 1
	OFFSET	55' Rt.		40' Rt.	40' Lt.		50' Lt.					
		5;	45'	4(	4(	47'	2(					
	STATION	-65	06	00	50	60	20					
	STAT	50+65	50+90	51+00	51+50	51+60	51+70					
	And a state						· .					- <u></u>
	SOUNDING NUMBER	S-1	S-2	S-3	S-4	S-5	S-6					
	SOUNDING											
		ıger	ıger	ıger	ıger	ıger	ıger					
	AUGER METHOD	Hand Auger	Hand Auger	Hand Auger	Hand Auger	Hand Auger	Hand Auger					
	dia an	Ha	Ha	Ha	Ha	Ha	Ha	 				
	AUGER DATE	11/29/01	11/29/01	11/29/01	11/29/01	11/29/01	11/29/01					
	AU Di	11/2	11/2	11/2	11/2	11/2	11/2					

7226 Georgetown Road Indianapolis, Indiana 46268 (317) 216-7131 **Engineering • Consultion** 

í

ļ

# Summary of Classification Test Results

PSI PROJECT NO.: 016-15159 CLJIENT: The HNTB Companies PROJECT: 61<sup>st</sup> Avenue Widening and Improvements LOCATION: Lake County, Indiana PROJECT NO.: CM-9945() & STP-N606() DESIGNATION NO.: 0100881 & 0088390

DESIG	NATIO	N NO.:	DESIGNATION NO.: UIUUSSI & UVSSUU	06688									-							Page 1 of	1 of 1
				-	Sample	Classification		% Passing	gu	% Gravel	% Sand	% Silt	% Clay		<u> </u>				Max. C	~	CBR
Lab No.	Boring No.	Station	Offset	Sample No.		Textural AASHTO	No.10	) No.40	No.200	76.2 - 2.0 mm	2.00 - 0.074 mm	0.074 - 0.002 mm	Below 0.002 mm	Hd		PL P	PI Mo	Moist.( De %) (p		@ 93%	@ 97%
8395SL	RB-2-SG	16+62	6' Lt. Line "A"	1/BS	1.0-3.0	Silty Clay Loam A-4 (7)	r) 92.8	88.9	76.7	7.2	16.1	55.4	21.3	7.86	34	24 1	10	15.5 11	11-0.0	2.2	3.3
8396SL	RB-2-SG	16+62	6' Lt. Line "A"	4/SS	8.5-10.0	Silty Clay A-6 (21)	6.99 (	7.66	99.3	0.1	0.6	59.6	39.7	8.65	39	19 2	20			,	
8397SL	RB-4-SG	25+40	6' Lt. Line "A"	2/SS	4.0-5.5	Clay A-7-6 (22)	99.1	94.8	86.7	0.9	12.4	47.0	39.7	8.22	44	19 2	25			-	,
8398SL	RB-6-SG	36+00	6' Lt. Line "A"	5/SS	13.5-15.0	Sand A-3	3 99.8	83.0	5.0	0.2	94.8	5.0		8.51	đ	A A V	đN				.
8401SL	RB-8	57+00	22' Lt. Line "A"	1/BS	2.0-3.0	Silty Loam A-4 (1)	) 99.4	96.2	70.3	0.6	29.1	56.7	13.6	8.46	26	22	4				•
TS66E8	RB-11-SG	49+30	8' Rt. Line "S-4-A"	2/SS	3.0-4.5	Silty Clay A-7-6 (22)	2) 99.4	97.4	95.2	0.6	4.2	60.3	34.9	8.42	41	19 2	22			· · ·	,
8400SL	TB-1	51+10	11' Rt. Line "A"	10/SS	38.5-40	Sandy Gravel A-1-a	-a 45.6	18.4	6.2	54.4	39.4	6.2		7.95	đ	Z dN	dN				•
8412SL	TB-2	51+40	24' Lt. Line "A"	2/ST	5.0-7.0	Silty Clay Loam w/little organic matter & trace marl A-5(6)	99.3	97.8	87.5	0.7	11.8	66.5	21.0	8.03	41	37 '	4				
8415SL	TB-2	51+40	24' Lt. Line "A"	3/ST	10.0 - 11.5	Loam w/little organic matter & trace marl A-4(1)	1) 98.4	95.0	58.4	1.6	40.0	40.0	18.4	7.94	25	20	5	1			•

7225 Georgetown Road Indianapolis, IN 46268-4126 (317) 216-7131

Project: 61st Avenue Widening & Improvements Client: The HNTB Companies Location: Lake County, Indiana Project No.: CM-9945()/STP-N606() Designation No.: 0100881/0088390 PSI Project No.: 016-15159

<u>Laboratory</u> <u>Number</u>	<u>Boring</u> Number	<u>Sample</u> Number	<u>Depth</u> (ft)	<u>Moisture</u> <u>Content</u>	pH Value	LOI	<u>Dry Density</u> (pcf)	
8414SL	RB-1-SG	1/ SS	3.00 - 4.50	19.4				
8414SL	RB-1-SG	2/ SS	4.50 - 6.00	23.2				
8414SL	RB-1-SG	3/ SS	6.00 - 7.50	25.3				
8414SL	RB-1-SG	4/ SS	8.50 - 10.00	24.9				
8414SL	RB-1-SG	5/ SS	13.50 - 15.00	22.6				
8395SL	RB-2-SG	1/ BS	1.00 - 3.00		7.86			
8414SL	RB-2-SG	1/ SS	2.00 - 3.50	25.2				
8473SL	RB-2-SG	1/ ST	2.00 - 4.00	24.0			89.4	
8414SL	RB-2-SG	2/ SS	4.00 - 5.50	26.1				
8474SL	RB-2-SG	2/ ST	4.00 - 6.00	25.9			95.0	
8414SL	RB-2-SG	3/ SS	6.00 - 7.50	24.5				
8396SL	RB-2-SG	4/ SS	8.50 - 10.00	21.9	8.65			
8414SL	RB-3-SG	1/ SS	2.00 - 3.50	22.9				
8414SL	RB-3-SG	3/ SS	6.00 - 7.50	21.9				
8414SL	RB-3-SG	4/ SS	8.50 - 10.00	24.3				
8414SL	RB-3-SG	5/ SS	13.50 - 15.00	24.9				
8414SL	RB-4-SG	1/ SS	2.00 - 3.50	22.3				•
8475SL	RB-4-SG	1/ ST	2.00 - 4.00	27.5		5.8	93.8	

Project: 61st Avenue Widening & Improvements Client: The HNTB Companies Location: Lake County, Indiana Project No.: CM-9945()/STP-N606() Designation No.: 0100881/0088390 PSI Project No.: 016-15159

Ļ,

<u>Laboratory</u> <u>Number</u>	<u>Boring</u> Number	<u>Sample</u> Number	<u>Depth</u> (ft)	<u>Moisture</u> <u>Content</u>	<u>pH Value</u>	<u>LOI</u>	<u>Dry Density</u> (pcf)
8414SL	RB-4-SG	2/ SS	4.00 - 5.50	22.9	8.22		
8414SL	RB-4-SG	3/ SS	6.00 - 7.50	29.2			
8414SL	RB-4-SG	4/ SS	8.50 - 10.00	28.0			
8414SL	RB-5-SG	1/ SS	1.50 - 3.00	21.6			
8476SL	RB-5-SG	1/ ST	1.50 - 3.50	26.7			97.2
8414SL	RB-5-SG	2/ SS	3.50 - 5.00	27.2			
8414SL	RB-5-SG	3/ SS	6.00 - 7.50	24.9		•	
8414SL	RB-5-SG	4/ SS	8.50 - 10.00	26.8			· •
8414SL	RB-6-SG	1/ SS	1.50 - 3.00	27.3			
8477SL	RB-6-SG	1/ ST	1.50 - 3.50	24.3			98.2
8414SL	RB-6-SG	2/ SS	3.50 - 5.00	25.8			
8414SL	RB-6-SG	3/ SS	6.00 - 7.50	24.3			
8414SL	RB-6-SG	4/ SS	8.50 - 10.00	24.6			
8398SL	RB-6-SG	5/ SS	13.50 - 15.00		8.51		
8414SL	RB-7-SG	1/ SS	1.50 - 3.00	22.0			
8478SL	RB-7-SG	1/ ST	1.50 - 3.50	24.5			98.6
8414SL	RB-7-SG	2/ SS	3.00 - 4.50	25.6			
8479SL	RB-7-SG	2/ ST	3.50 - 5.50	27.5			94.1

Project: 61st Avenue Widening & Improvements Client: The HNTB Companies Location: Lake County, Indiana Project No.: CM-9945()/STP-N606() Designation No.: 0100881/0088390 PSI Project No.: 016-15159

ŗ

<u>Laboratory</u> <u>Number</u>	<u>Boring</u> Number	<u>Sample</u> <u>Number</u>	<u>Depth</u> <u>(ft)</u>	<u>Moisture</u> <u>Content</u>	<u>pH Value</u>	<u>L01</u>	Dry Density (pcf)
8414SL	RB-7-SG	3/ SS	6.00 - 7.50	24.1			
8414SL	RB-7-SG	4/ SS	8.50 - 10.00	24.6			
8414SL	RB-7-SG	5/ SS	13.50 - 15.00	25.5			
8414SL	RB-8-SG	1/ SS	1.00 - 2.50	21.7			
8401SL	RB-8-SG	1/ BS	2.00 - 3.00		8.46		
8480SL	RB-8-SG	1/ ST	1.00 - 2.50	21.6			104.9
8414SL	RB-8-SG	2/ SS	2.50 - 4.00	24.2	. · · ·		
8414SL	RB-8-SG	3/ SS	6.00 - 7.50	25.4			
8414SL	RB-8-SG	4/ SS	8.50 - 10.00	24.0			
8414SL	RB-8-SG	5/ SS	13.50 - 15.00	26.6			
8414SL	RB-8-SG	6/ SS	18.50 - 20.00	27.4			
8414SL	RB-9-SG	1/ SS	1.50 - 3.00	19.0			
8481SL	RB-9-SG	1/ ST	1.50 - 3.50	20.9			102.3
8414SL	RB-9-SG	2/ SS	3.50 - 5.00	22.9			
8405SL	RB-9-SG	3/ SS	6.00 - 7.50	26.4		4.4	
8414SL	RB-9-SG	4/ SS	8.50 - 10.00	26.7			•
8414SL	RB-9-SG	5/ SS	13.50 - 15.00	25.1			
8414SL	RB-9-SG	6/ SS	18.50 - 20.00	30.3			

Project: 61st Avenue Widening & Improvements Client: The HNTB Companies Location: Lake County, Indiana Project No.: CM-9945()/STP-N606() Designation No.: 0100881/0088390 PSI Project No.: 016-15159


6


<u>Laboratory</u> <u>Number</u>	<u>Boring</u> <u>Number</u>	<u>Sample</u> Number	<u>Depth</u> (ft)	<u>Moisture</u> <u>Content</u>	<u>pH Value</u>	<u>LOI</u>	<u>Dry Density</u> (pcf)
8406SL	RB-10-SG	1/ SS	1.00 - 2.50	14.8	,	5.9	
8482SL	RB-10-SG	1/ ST	1.00 - 3.00	21.9			105.3
8414SL	RB-10-SG	2/ SS	3.00 - 4.50	22.9			
8414SL	RB-10-SG	3/ SS	6.00 - 7.50	26.2			
8414SL	RB-11-SG	1/ SS	1.00 - 2.50	22.0			
8483SL	RB-11-SG	1/ ST	1.00 - 3.00	19.4			109.6
8399SL	RB-11-SG	2/ SS	3.00 - 4.50	22.2	8.42		
8414SL	RB-11-SG	3/ SS	6.00 - 7.50	19.7			
8414SL	RB-11-SG	4/ SS	8.50 - 10.00	22.2			
8414SL	RB-11-SG	5/ SS	13.50 - 15.00	21.6			
8414SL	TB-1-SG	1/ SS	2.00 - 3.50	12.3			
8414SL	TB-1-SG	3/ SS	6.00 - 7.50	23.4			
8414SL	TB-1-SG	4/ SS	8.50 - 10.00	26.2			
8407SL	TB-1-SG	5/ SS	13.50 - 15.00	39.0		9.5	
8408SL	TB-1-SG	6/ SS	18.50 - 20.00	55.1		7.7	
8400SL	TB-1-SG	10/ SS	38.50 - 40.00		7.95		
8414SL	TB-1-SG	11/ SS	43.50 - 45.00	24.7			
8414SL	TB-2	1/ SS	1.00 - 2.50	61.5			


Project: 61st Avenue Widening & Improvements Client: The HNTB Companies Location: Lake County, Indiana Project No.: CM-9945()/STP-N606() Designation No.: 0100881/0088390 PSI Project No.: 016-15159


1


Ī	<u>aboratory</u> <u>Number</u>	<u>Boring</u> Number	<u>Sample</u> Number	<u>Depth</u> <u>(ft)</u>	<u>Moisture</u> <u>Content</u>	<u>pH Value</u>	LOI	<u>Dry Density</u> (pcf)
	8402SL	TB-2	1/ ST	1.00 - 3.00	49.7		8.0	70.7
	8410SL	TB-2	2/ SS	3.50 - 5.00	77.8		10.0	
	8412SL	TB-2	2/ ST	5.00 - 7.00	60.0	8.03	7.3	68.0
	8414SL	TB-2	3/ SS	6.00 - 7.50	95.5			
	8411SL	TB-2	4/ SS	8.50 - 10.00	33.8		4.5	
	8415SL	TB-2	3/ ST	10.00 - 11.50	61.7		· .	59.5
	8414SL	TB-2	9/ SS	33.50 - 35.00	25.6			
	8414SL	TB-2	10/ SS	38.50 - 40.00	20.2			


























## **CONSOLIDATION TEST**

			CONSU	UIDAI.	ION IES.	L			
CLIENT: HNTB Companies							DATE TE		2/25/02
PROJECT: 61st Street Improvements				_			TESTED		WC
	016-15159		SAMPLE N	0.:	2/ST		REVIEW	ED BY:	PSL
BORING NO.									
DEPTH ft:	6.0-6.1		011. O1 T						
DESCRIPTIO					ttle organic m			770 · 1	
SAMPLE HT	.:	0.748		SPEC. GF		2.59		Tested	
RING AREA:		4.8305			ERG LIMITS:		41	PI -	
KING AKEA.			m 2 cm^2	DRY DEN	NSIT I :	71.90			
		51.10					kg/m^3 tial		nal
Cup No.		1-HR		Wt Ding	+ Soil Wet	177.66		167.4	
Wt. Cup $+$ So	oil Wet	85.70			+ Soil Dry	142.30		142.30	
Wt. Cup + So $Wt$ . Cup + So		61.20		Wt. Ring		74.15		74.15	
Wt Water	on Dij	24.50		Wt. Soil (	Wet)	103.51		93.25	
Wt. of Cup         13.90					68.15				
Wt. Dry Soil 47.30				0.332		0.332			
Initial Moisture (%) 51.80%		0	Void Ratio		1.249				
			· ·						
APPLIED	APPLIED	CUMULAT.	CHANGE	VOID					
PRESSURE	PRESSURE	DISPLACE.	V. RATIO	RATIO	STRAIN	н	T90	Cv *	. •
(tsf)	(psf)	(in.)	(delta e)	(e)	(%)	(in.)	(min.)	(in^2/min)	
0	0	0	0	1.249	0	0.748			
0.0625	125	0.0042	0.0127	1.236	0.56	0.744	37.2	0.0032	
0.125	250	0.0127	0.0383	1.211	1.70	0.735	59.3	0.0019	
0.25	500	0.0293	0.0883	1.161	3.92	0.719	53.3	0.0021	
0.5	1000	0.05725	0.1725	1.076	7.65	0.691	85.6	0.0012	
1	2000	0.0905	0.2727	0.976	12.10	0.658	94.1	0.0010	
2	4000	0.1358	0.4092	0.840	18.16	0.612	86.5	0.0009	
4	8000	0.1814	0.5466	0.702	24.25	0.567	98	0.0007	
2	4000	0.17745	0.5347	0.714	23.72	0.571			
1	2000	0.171	0.5153	0.734	22.86	0.577			
0.5	1000	0.16415	0.4946	.0.754	21.95	0.584			
0.25	500	0.155	0.4671	0.782	20.72	0.593			
0.125	250	0.1467	0.4421	0.807	19.61	0.601			
* Cv values a	re based on o	our interpretati	ion of the plo	tted data.					· · · ·


### **UNCONFINED COMPRESSION STRENGTH**


Project: 61st Ave. Widening & Improv. Client: The HNTB Companies

4

Date Tested: 12/02/01 Project No.: 016-15159


Soil Description:	Silty Clay				Tested By:	WC
	TB-1-SG	Sample No.:	47/SS		<b>Reviewed By:</b>	AJM
Depth (ft): 9		(2.7)	meters		• -	
LAB NO.:	8403SL	Height:	2.80	inches	70.99	mm
Qp(tsf):	0.75	Diameter:	1.41	inches	35.81	mm
Wet Weight(g):	138.8	Moisture	Content:	25.7%	Saturation (%):	95.2
Load Cell Cal	ib <b>ration</b>	HtDiame	ter Ratio -	1.98	Specific Gravity:	2.65
Pounds/mVolt	14.55	Dry Density:	96.3	pcf	1542.3	$kg/m^3$
	DEFOR-	TRANS-	[	1	CORRECTED	AXIAL
READING	MATION	DUCER	LOAD	STRAIN	AREA	STRESS
NUMBER	(in.)	READING	(lbs)	(%)	^(in <sup>2</sup> )	(tsf)
0	0.000	0.1	0.0	0.00	1.561	0.00
1	0.010	0.2	2.9	0.36	1.567	0.13
2	0.020	0.3	4.4	0.72	1.573	0.20
3	0.030	0.5	7.3	1.07	1.578	0.33
4	0.040	0.7	10.2	1.43	1.584	0.46
5	0.060	1.0	14.6	2.15	1.596	0.66
6	0.080	1.3	18.9	2.86	1.607	0.85
7	0.100	1.5	21.8	3.58	1.619	0.97 ·
8	0.120	1.7	24.7	4.29	1.631	1.09
9	0.140	1.9	27.6	5.01	1.644	1.21
10	0.160	2.0	29.1	5.72	1.656	1.27
11	0.180	2.1	30.6	6.44	1.669	1.32
12	0.200	2.2	32.0	7.16	1.682	1.37
13	0.220	2.3	33.5	7.87	1.695	1.42
. 14	0.240	2.4	34.9	8.59	1.708	1.47
15	0.280	2.5	36.4	10.02	1.735	1.51
16	0.300	2.6	37.8	10.73	1.749	1.56
17	0.340	2.7	39.3	12.16	1.778	1.59
18	0.360	2.8	40.7	12.88	1.792	1.64
19	0.380	2.9	42.2	13.60	1.807	1.68
20	0.440	3.1	45.1	15.74	1.853	1.75
Qu =	1.68	tsf	160.98	kPa Strair	ı 15.00%	







Documents\Unconfin Comp\[15159tb2,4ss.xls]A بريس.


UNC	CONFIN	NED CO	MPRE	SSION	STRENGT	H
Project: Client:	61st Ave. Widening & Improv. The HNTB Companies				Date Tested: Project No.:	12/02/01
Boring #: TB-2		oam with little organic matter Sample No.: 1/ST			Tested By: Reviewed By:	
Depth (ft): LAB NO.:			meters			
		Height:	5.56	inches	141.22	
Qp(tsf):		Diameter:	2.82	inches	71.63	
Wet Weight(g):		Moisture		49.7%	Saturation (%):	97.8
Load Cell Cal		HtDiamet		1.97	Specific Gravity:	2.65
Pounds/mVolt	14.55	Dry Density:	70.7	pcf	1132.4	kg/m³
	DEFOR-	TRANS-			CORRECTED	AXIAL
READING	MATION	DUCER	LOAD	STRAIN	AREA	STRESS
NUMBER	(in.)	READING	(lbs)	(%)	^(in <sup>2</sup> )	(tsf)
0	0.020	0.4	0.0	0.36	6.268	0.00
1	0.040	0.7	10.2	0.72	6.291	0.12
2	0.060	0.9	13.1	1.08	6.314	0.15
3	0.080	1.2	17.5	1.44	6.337	0.20
4	0.120	1.6	23.3	2.16	6.384	0.26
5	0.160	2.1	30.6	2.88	6.431	0.34
6	0.200	2.5	36.4	3.60	6.479	0:40
7	0.240	2.9	42.2	4.32	6.528	0.47
8	0.280	3.2	46.6	5.04	6.577	0.51
9	0.320	3.5	50.9	5.76	6.627	0.55
10	0.360	3.7	53.8	6.47	6.678	0.58
11	0.400	4.0	58.2	7.19	6.730	0.62
12	0.440	4.2	61.1	7.91	6.783	0.65
13	0.480	4.3	62.6	8.63	6.836	0.66
14	0.520	4.5	65.5	9.35	6.890	0.68
15	0.560	4.6	66.9	10.07	6.945	0.69
16	0.600	4.8	69.8	10.79	7.001	0.72
17	0.640	4.9	71.3	11.51	7.058	0.73
18	0.720	5.0	72.8	12.95	7.175	0.73
19	0.800	5.1	74.2	14.39	7.296	0.73
20	0.840	5.1	74.2	15.11	7.357	0.73
Qu =	0.73	tsf	70.13	kPa Strai	15.00%	







UNC	CONFI	<b>NED CO</b>	MPRE	SSION S	TRENGTH	I
Project: Client:	61st Ave.	Widening & B Companie	Improv.		Date Tested: Project No.:	02/02/02
Soil Description: Boring #: Depth (ft):	TB-2	oam w/ little organic matter & trace marl Sample No.: 2/ST			Tested By: Reviewed By:	
LAB NO.:		(1.8) Height:	meters 5.76	inches	146.00	
Qp(tsf):		Diameter:	2.73	inches	<u> </u>	
Wet Weight(g):		Moisture		60.0%	09.04	
Load Cell Cal					Saturation (%):	110.6
		HtDiame		2.11	Specific Gravity:	2.65
Pounds/mVolt	6.73	Dry Density:	68.0	pct	1089.5	
READING	DEFOR- MATION	TRANS- DUCER	LOAD	STRAIN	CORRECTED AREA	AXIAL STRESS
NUMBER	(in.)	READING	(lbs)	(%)	^(in <sup>2</sup> )	(tsf)
0	0.020	0.5	0.0	0.35	5.874	0.00
1	0.040	0.6	4.0	0.69	5.894	0.05
2	0.060	0.7	4.7	1.04	5.915	0.06
3	0.080	0.8	5.4	1.39	5.936	0.07
4	0.120	1.0	6.7	2.08	5.978	0.08
5	0.160	1.2	8.1	2.78	6.021	0.10
6	0.200	1.5	10.1	3.47	6.064	0:12
7	0.240	1.7	11.4	4.17	6.108	0.13
8	0.280	1.9	12.8	4.86	6.153	0.15
9	0.320	2.1	14.1	5.56	6.198	0.16
10	0.360	2.3	15.5	6.25	6.244	0.18
11	0.400	2.5	16.8	6.94	6.290	0.19
12	0.440	2.6	17.5	7.64	6.338	0.20
13	0.480	2.8	18.8	8.33	6.386	0.21
14	0.520	2.9	19.5	9.03	6.434	0.22
15	0.560	3.0	20.2	9.72	6.484	0.22
16	0.600	3.1	20.9	10.42	6.534	0.23
17	0.640	3.3	22.2	11.11	6.585	0.24
18	0.720	3.4	22.9	12.50	6.690	0.25
19	0.800	3.5	23.6	13.89	6.798	0.25
20	0.840	3.5	23.6	14.58	6.853	0.25
Qu =	0.25	tsf	23.89	kPa Strain	13.89%	






" TING	ONFI	NED CO	MDDF	SSION	STDENCT	Ω.
UNCONFINED COProject:61st Ave. Widening & The HNTB Companies			Improv.	5510N	Date Tested: Project No.:	12/02/01
Soil Description: Boring #: Depth (ft):	with little orga Sample No.: (3.4)			Tested By: Reviewed By:	WC AJM	
LAB NO.:		Height:	5.65	inches	143.51	mm
Qp(tsf):		Diameter:	2.85	inches	72.39	
Wet Weight(g):		Moisture		61.7%	Saturation (%):	91.5
Load Cell Ca		HtDiame	ter Ratio -	1.98	Specific Gravity:	2.65
Pounds/mVolt	14.55	Dry Density:	59.5	pcf	953.3	kg/m³
	DEFOR-	TRANS-	A		CORRECTED	AXIAL
READING	MATION	DUCER	LOAD	STRAIN	AREA	STRESS
NUMBER	(in.)	READING	(lbs)	(%)	^(in <sup>2</sup> )	(tsf)
0	0.020	0.1	0.0	0.35	6.402	0.00
1	0.040	0.2	2.9	0.71	6.425	0.03
2	0.060	0.3	4.4	1.06	6.448	0.05
3	0.080	0.4	5.8	1.42	6.471	0.06
4	0.120	0.6	8.7	2.12	6.518	0.10
5	0.160	0.8	11.6	2.83	6.565	0.13
6	0.200	0.9	13.1	3.54	6.614	0.14
7	0.240	1.1	16.0	4.25	6.662	0.17
8	0.280	1.2	17.5	4.96	6.712	0.19
9	0.320	1.3	18.9	5.66	6.762	0.20
10	0.360	1.3	18.9	6.37	6.814	0.20
11	0.400	1.4	20.4	7.08	6.865	0.21
12	0.440	1.4	20.4	7.79	6.918	0.21
13	0.480	1.5	21.8	8.50	6.972	0.23
14	0.520	1.5	21.8	9.20	7.026	0.22
15	0.560	1.5	21.8	9.91	7.081	0.22
16	0.600	1.5	21.8	10.62	7.137	0.22
17	0.640	1.5	21.8	11.33	7.194	0.22
18	0.720	1.5	21.8	12.74	7.311	0.21
19	0.800	1.5	21.8	14.16	7.432	0.21
$\frac{20}{Qu} =$	0.840	1.5 tsf	21.8 21.58	14.87 kPa Strai	7.493 5.66%	0.21







Information	To Build On	<b>Consulting • Testing</b>
		Engineering • Co

Summary of CBR Test Results


ŗ

		,
ent		CBR, % (0.2" PEN 4.0 3.8 3.8 2.7 2.7 2.7 0.8 0.8 0.8
STP-N 606( ) 61 <sup>st</sup> Ave. Widening and Improvement Hobart, Indiana		CBR, % <u>@ 0.1" PEN.</u> 3.6 3.3 2.6 1.2 1.0 1.0 2.2 2.8 3.3 3.3 3.3
STP-N 606( 61 <sup>st</sup> Ave. Wid Hobart, India		<u>SWELL, %</u> 0.96 0.92 0.94 0.96
Project No.: Project: Location:		MAXIMUM DRY DENSITY 98.9 95.1 94.0 85.7 85.7 85.7 Y DENSITY
im A-4 (0)		INITIAL DRY DENSITY MAXIM (pcf) (pcf) <u>DRY DEI</u> 108.0 98.1 104.6 95.0 98.1 94.0 94.0 86.4 94.3 85.1 94.3 85.1 94.0 86.4 94.0 91.0 95 95
RB-2 1.0'-3.0' Silty Clay Loam A-4 (0) 110 15.5 25	Average Water Content, %	AFTER SOAKING 18.5 19.7 20.6 20.9 23.6 24.6 24.6
cf: ent, %: aaking, lbs.:	Ave	AS MOLDED 15.4 15.1 15.6 15.9 15.6 15.7 7 (pcf)
Boring No.: Sample Depth, ft: Soil Description: Maximum Dry Density, pcf: Optimum Moisture Content, %: Surcharge Weight for Soaking, lbs.:		BLOWS/ A LAYER MOLI 64 15 64 15 64 15 20 15 20 15 20 15 20 15 102.3 102.3 104.5 106.7
Boring No.: Sample Depth, ft: Soil Description: Maximum Dry Der Optimum Moisture Surcharge Weight		Ω Ш N N N N N N N N N N N N N N N N N N N

## **CBR Test Curve**



ŗ



Dry Density pcf

Professional Service Industries, Inc. 7225 Georgetown Road Indianapolis, Indiana 46268

**Figure Number 15** 

SUBJECT: Suffement Analysis **Information** PROJECT: 61st Ale. Widening & Improv. 'Io Ruild ( In PROJECT NO. STP-N606 ()/CM-9945() Engineering • Consulting • Testing CALC. BY: <u>PSL</u> DATE: <u>2/12/02</u> Sheet \_\_\_\_\_ of \_\_\_\_\_ CHECKED. BY: 4MD DATE: 3/11/02 Settlement Analysis @ Station 51+50, Line "A" (Max Fill) - Existing Ground HeV : 609 ft. - Boring used for analysis: TB-2 & TB-1 - Max fiel = 14 feet. (on the north side) - Compressible organic soils located from o' to 12' at TB-2, or about 10' to 22' at TB-1-5G. <1> Consolication Parameters for silty day loam w/little organic matter  $CR = \frac{C_c}{1+e_-} = 0.202$   $C_c = CR \times (1+e_0) = 0.454$  $RR = \frac{C_{s}}{1+P_{s}} = 0.031 \qquad C_{s} = RRX(1+P_{o}) = 0.0697$  $OCR = \frac{P_c}{P_o} = \frac{0.74105f}{0.65 \text{ ksf}} = 1.14 \quad \frac{C_s/c_c}{c_c} = \frac{0.157}{0.157}$  $\Delta P = 125 \times 14 = 1750 \text{ psf}$   $e_0 = 1.249$  $22 \xrightarrow{\text{Post-Const.}} \xrightarrow{\text{primary Settlement}} S_{c} = RR(1+) \log\left(\frac{650 \times 1.14}{650}\right) + CR(1+) \log\left(\frac{650 \times 1.14}{650 \times 1.14}\right)$  $= 0.031(144) \log \left(\frac{740}{650} + 0.202(144) \log \left(\frac{2150}{740}\right)\right)$  $= 0.25'' + 13.47'' = 13.72'' \Rightarrow Say 14''$ 

.

SUBJECT: Settlement Analysis **T**Information PROJECT: 615+ Ave Widening & Zuppov. l'Io Build On PROJECT NO. <u>STP-N606()/CM-9945(</u>) Engineering • Consulting • Testing CALC. BY: <u>\$56</u> DATE: <u>2/22/02</u> CHECKED. BY: 410 DATE: 3/11/02 Sheet \_\_\_\_\_ of 4 (3) Seconday SetAlement. For organic soils, Secondary settlement load ke Significant. Based on the consolidation data,  $C_{\chi} = 0.014$ ,  $C_{v} = 0.0011$  in/min. Required trab for primary consolidation = 165 mm in the lab test under 0.5 tst. (1 kst) There fore, the required time to reach the end of primary consolidation in the field, trield =  $\frac{T_{lab}}{T_{field}} = \frac{|T_{dr}(lab)|}{|H_{ar}(field)|} = \frac{\left(\frac{0.748}{2}\right)^2}{\left(\frac{144}{2}\right)^2}$  $t_{\text{field}} = \frac{(72)}{(0.374)^2} t_{1ab} = 37061.4 (165 \text{ min})$ = 11,6 years.  $T_{\text{field}} = \frac{C_{V} \cdot t_{\text{field}}}{|t_{d_{V}}|^{2}} = \frac{0.0011 \cdot 6115131}{72^{2}} = 1.298$ U do = 98.3 do (Regree of Consol. for primary).

SUBJECT: Settlement Analysis **T**Information PROJECT: 6/St Ave Widening & Improv. To Build On PROJECT NO. <u>STP-N606()/CM-9945()</u> Engineering • Consulting • Testing CALC. BY: \_\_\_\_\_\_\_ DATE: 2/22/02 Sheet 3 of 4CHECKED BY: MM DATE: 2/4/02 <4> Secondary Settlement to 30 years. CX = 0.014. (secondary Compression Index).  $S_{S} = \frac{c_{\alpha}}{1+e_{n}} \cdot H \cdot \log\left(\frac{t_{2}}{t_{1}}\right)$ where ep = void ratio at the end of primary consolidation lo - Deprimary = Deprimary = (s log ( - Pc ) + C log ( Potap ) = 0,0697 log (-140) + 0,454. log (-740+1750) = 0,243Therefore, ep = 1.249-0.243 = 1.006  $S_{S}(30 \, year) = \frac{0.014}{1+1.006} \cdot 144 \cdot \log(\frac{30}{11.6})$ = 0,4" A-300-9 (Indy)

SUBJECT: Settlement Analysis Information PROJECT: <u>61 St Ave Widowing & 2mpsv.</u> To Build On Engineering • Consulting • Testing PROJECT NO. <u>Stp-N606()/CM-9945()</u> CALC. BY: \_\_\_\_\_\_ DATE: \_\_\_/22/02\_ CHECKED. BY: MD DATE: 3/11/02 Sheet  $\underline{4}$  of  $\underline{4}$ <57 Conclusions: O primary consolidation settlement = 13.7", Say 14" @ It will take about 11.6 years to reach the end of primary lonsolidation. 3 Secondary settlement is about 0,4" to 30 years 3 2f Say allowable primary settlement is 1",  $U_{0} = \frac{13.72 - 1}{13.72} \times 100 = 92.7 ofo$ The time required to have primary consolidation within 1" T9310= 0,993  $t_{a_{3,0}} = \frac{T_{a_{3,0}}}{C_{v}} \cdot H_{dr}$  $= \frac{0.993}{0.0011} \cdot 72^2 = 8.9 \text{ years}$ 

### Wick Drain Design

Project Name: 61st Ave. Widening & Improvements

INDOT Project No.: STP-N606()/CM-9945()

Client: HNTB Corporation

Project Location: Hobart, Indiana

Soil Borings: TB-2 & TB-1-SG

1. Units:

month  $\equiv 3\theta \cdot day$ 

2. Design Parameters:

H\_surcharge :=  $14 \cdot ft$ 

WD\_surcharge :=  $125 \cdot \frac{lb}{ft^3}$ 

q := H\_surcharge · WD\_surcharge

slope := 3.0

 $a := slope \cdot H$  surcharge

 $\mathbf{b} := 42 \cdot \mathbf{ft}$ 

 $t := 12 \cdot month$ 

 $\mathbf{D} := 2.2 \cdot \mathbf{ft} \qquad \mathbf{de} := 1.05 \cdot \mathbf{D}$ 

3. Soil Parameters & Drain Length for Each Layer, I: (Input)

$$i := 1$$
 layer := 1

$$h_{layer} := 12 \cdot ft$$

$$SD_{layer} := 109 \cdot \frac{lb}{ft^3}$$

WD<sub>layer</sub> := 
$$62.4 \cdot \frac{\text{lb}}{\text{ft}^3}$$

$$l_{layer} := 6 \cdot ft$$

61st Ave - Wick Drains.mcd

(This analysis is based on Ployfelt TS Design and Practice Technical Manual)

PSI Project No.: 016-05017

Designation No.: 9300360

H<sub>surcharge</sub>: Height of surcharge

WD<sub>surcharge</sub>: Wet density of the surcharge soil

q: Embankment Surcharge Pressure

slope: Design slope of surcharge embankment

a: Horizontal distance between the toe and top of slope

b: Horizontal distance between crest and centerline

t: Estimated time to reach 90% consolidation

D: Design actual distance of wick drains

 $d_e$ : Equivalent drain distance, = 1.05 \* D for triangular pattern = 1.13 \* D for square pattern

i: No. of compressible soil layers

h: Thickness of compressible soil layers

SD: Unit Density of Soils (Wet)

WD: Unit Density of Water

l = (1/2)\*h for drains penetrated into a lower permeable layer = h for drains only drain to the top 4. Influence Factor of Soil Layers: (Based on "Advanced Soil Mechnics" by Das, Fig. 3. 15, p. 188)

$$Z(layer) := h_{layer} - \frac{h_{layer}}{2}$$
Z: Depths to the middle of each layer

$$\alpha 2_{\text{layer}} := \operatorname{atan}\left(\frac{b}{Z(\text{layer})}\right)$$
  $\alpha 2_{\text{layer}} = 1.43$ 

$$\alpha 1_{layer} := atan \left( \frac{a+b}{Z(layer)} \right) - \alpha 2_{layer}$$

$$\mathbf{I}_{\text{layer}} := \frac{1}{\pi} \cdot \left[ \left( \frac{\mathbf{a} + \mathbf{b}}{\mathbf{a}} \right) \cdot \left( \alpha \mathbf{1}_{\text{layer}} + \alpha \mathbf{2}_{\text{layer}} \right) - \frac{\mathbf{b}}{\mathbf{a}} \cdot \alpha \mathbf{2}_{\text{layer}} \right] \qquad \qquad \mathbf{I}_{\text{layer}} = \mathbf{0}$$

5. Overburden Pressure, Horizontal Coefficient of Consolidation, and Horizontal Soil Condictivity in Each Soil Layer:

$$\mathbf{OP}(\mathbf{layer}) := \left[\sum_{j=I}^{i} \left(\mathbf{SD}_{j} - \mathbf{WD}_{j}\right) \cdot \mathbf{h}_{j} \cdot (j \leq \mathbf{layer})\right] - \left(\mathbf{SD}_{\mathbf{layer}} - \mathbf{WD}_{\mathbf{layer}}\right) \cdot \frac{\mathbf{h}_{\mathbf{layer}}}{2} + \left(2 \cdot \mathbf{I}_{\mathbf{layer}}\right) \cdot \mathbf{q}$$

(Input)

$$OP(1) = 2.03 \times 10^3 \frac{1b}{ft^2}$$

$$Cv_{layer} := 1.83 \cdot 10^{-5} \cdot \frac{in^2}{sec}$$
 (input)

$$\operatorname{Kh}_{\operatorname{layer}} := 1.0 \cdot 10^{-7} \cdot \frac{\operatorname{cm}}{\operatorname{sec}}$$

Kh: Horizontal soil permeability coefficient

 $\alpha 1_{\text{layer}} = 7.06 \times 10^{-2}$ 

5

Select  $C_v$  for each soil layer according to the overburden pressure in each soil layer and type of soil.

Assumed Horizontal Consolidation Coefficient,  $C_h$ , is about 1.2 to 1.5 times of the Vertical Consolidation Coefficient  $C_v$ , which is obtained from the consolidation tests.

Assume: 
$$Ch_{laver} := 1.5 \cdot Cv_{laver}$$

6. Equivalent Drain Diameter, d<sub>w</sub>:

Select Drain Width  $\mathbf{b} := \mathbf{4} \cdot \mathbf{in}$ 

$$dw := \frac{b}{2}$$

dw = diameter for round drain or half of the drain width for the flat section

ļ

#### 7. Transmissivity q.: Assume TYPE 2 Polyfelt

 $qw_{layer} := 0.01 \cdot \frac{gal}{min}$  (Input)

The Transmissivity  $q_w$  of each soils is a function of the overburden pressure and are taken according to table VD-1 of Polyfelt TS Design & Practice manual

Diameter of the Smear Zone, d<sub>r</sub>:

 $dr := 2 \cdot dw$ 

Diameter of the smear zone is approximately 1.5 to 3 of Equivalent Drain Diameter

61st Ave - Wick Drains.mcd

2

#### 8. Permeability Coefficient of the disturbed soil, Kr:

Assumed 
$$Kr_{laver} := 0.35 \cdot Kh_{laver}$$
 Generally,  $K_h/K_r \sim 2 \text{ to } 8$ 

9. Determination of Factor F:

1

$$\mathbf{F}_{\text{layer}} \coloneqq \ln\left(\frac{d\mathbf{e}}{d\mathbf{r}}\right) - \mathbf{0.75} + \mathbf{0.64} \cdot \pi \cdot \left(\mathbf{l}_{\text{layer}}\right)^2 \cdot \left(\frac{\mathbf{Kh}_{\text{layer}}}{\mathbf{qw}_{\text{layer}}}\right) + \left(\frac{\mathbf{Kh}_{\text{layer}}}{\mathbf{Kr}_{\text{layer}}}\right) \cdot \ln\left(\frac{d\mathbf{r}}{d\mathbf{w}}\right)$$

F<sub>layer</sub> = 3.18

#### 10. Degree of Consolidation, U<sub>h</sub>:

$$\mathbf{Uh}_{\text{layer}} := \mathbf{1} - \exp\left(\frac{-\mathbf{\delta} \cdot \mathbf{Ch}_{\text{layer}} \cdot \mathbf{t}}{\mathrm{de}^2 \cdot \mathbf{F}_{\text{layer}}}\right) \qquad \qquad \mathbf{Uh}_{\text{layer}} = \mathbf{0.94}$$

#### 11. Average of Consolidation, U<sub>b</sub>:

$$Avg\_Uh := \frac{\underset{layer = I}{\overset{i}{\sum}} Uh_{layer} \cdot h_{layer}}{\underset{layer = I}{\overset{i}{\sum}} h_{layer}}$$

Avg\_Uh = 93.9 % > The minimum required 92.7 % of primary settlement (within 1" of primary settlement)


Or 15" spacing for 3 month waiting time.

SUBJECT: Bearing Capacity Analysis for VCC **Information** PROJECT: \_6/ st. Alenne Widening Io Build On PROJECT NO. <u>STP-N 606()/CM-9945()</u> Engineering • Consulting • Testing DATE: 2/28/02 CALC. BY: PSL CHECKED. BY: MM DATE: 3/11/02 3 Sheet / of Bearing Capacity Analysis for VCC - min 2 layers Geogrid Rehatored B' THEV 618 ± Utell Clay Loans \$ min 2 layers Geograd Silty day fill NReinforced B Borrow J= 120 PCF. Text Grade Her 608 t SILTY Clay Loam \$17" \$17" W/ little Mone/Peat. 61ev 596 V loose to loose Said mm -30 Ċ \$=28° (prior to Vibro-Compaction Whin. 0  $\varphi = 33$ 1 after Vibro-- Compaction. Recommend Usig & (Transverse) X & (Lowitrdinal) grid.  $\mathcal{O}$ 2 Vibrator will densify the underlying sand to > 800/0 Dr Based on empinical values for &, Dr, and unit weight of granular 3 Soil; we assume  $\phi = 34^{\circ}$  for estimate of allowable bearing pressure.

SUBJECT: Bearing Capa City Analysis for VCC Information PROJECT: 61 st. Avenue Widening lo Build On PROJECT NO. <u>SCP-N606() / CM-9945()</u> Engineering • Consulting • Testing CALC. BY: PSL DATE: 2/28/02 CHECKED BY: MUD DATE: 3/11/02 Sheet Z of 3 (D Bearing Capacity (based on \$= 34°) <1> Terzaghi bearing Capacity Ba = Quit = AP (L' 2 Ng + 0.4 8B Nr)  $Ap = 2\left(\frac{2.5}{2}\right)^2 = 4.91 \text{ ft}^2$ For shorter VCL -> L' = 18' (limit to 15B = 15×1.42 = 21)  $\mathcal{F} = 120 \text{ pcf} (after Vibro-Compaction}), \mathcal{F} = 120-62.4$ = 57.6 pcf  $N_{q} = 36.5 \ (\phi = 34^{\circ})$  $N_{g} = 36 \ (\phi = 34^{\circ})$ Thereforce, Allowable VCC Capacity  $R_{a} = \frac{4.91}{3} (18 \times 57.6 \times 36.5 + 0.4 \times 57.6 \times 2.5 \times 36)$ = 65 kips /vcc East = 13,000 psf with the Column tip

;

SUBJECT: Bearing Capacity Analysis & VCC Design **T**Information PROJECT: <u>61 ST Avenue Widening</u> To Build Engineering • Consulting • Testing PROJECT NO. \_STP-N 606()/CM-9945() CALC. BY: \_\_\_\_\_ DATE: \_\_\_\_2/28/02 CHECKED. BY:\_\_\_\_\_ DATE: FOR 14' OF fill. (Assumed 125 pcf) Overburden pressure =  $120 \times 14 = 1680 \text{ Psf} + 200 \text{ Psf} (+nffre)$ Max area/Vcc = 65000/1880 = 34,6 ft²/vcc => 5.9' spacing use 6' => use 6' × 6' grid for vcc installation A-300-9 (Indy)



#### SPECIAL PROVISION FOR VIBRO-COMPACTED CONCRETE COLUMNS

#### 1.0 Introduction

- 1.1 Vibro-compacted concrete columns are to be constructed using Vibro Compaction equipment. Vibro Compaction is a technique utilizing specially developed depth vibrators to direct compactive energy to the required improvement depth. This compactive energy results from electrically driven eccentric weight assemblies to apply a radial energy in the horizontal plane to the surrounding soil materials. Improvement is achieved by increasing the mass in-situ density, increasing the mass shear strength and reinforcing the subsurface materials with a prepared backfill. When concrete is used for the prepared backfill a compacted concrete column is produced. This item is explicitly associated with Alternate (a) for the 61<sup>st</sup> Avenue Improvements project.
- 1.2 The installation sequence initially inserting the probe to the required depth using a combination of water jetting, vibration and the dead weight of the equipment followed by repeated cycles of raising and lowering the probe while concrete is pumped into the hole created by the probe. The initial insertion of the probe causes particle re-arrangement and densification in the soil within 2.0 to 4.0 feet of the probe. Concrete is pumped out the bottom of the probe while it is withdrawn. Periodically the probe is re-penetrated to densify the concrete and expand it outward. The resulting concrete column is about 17.0 inches in diameter surround by a zone of highly compact soil.

#### 2.0 Scope of Work

- 2.1 Specialty contractor shall provide all supervision, labor, material, equipment and related services necessary to perform all concrete column installation and soil improvement by the Vibro-concrete technique as indicated on the drawings or specified herein.
- 2.1.1 Alternates or exceptions to the plans or specification should only be considered when submitted in writing. All acceptances of alternates or exceptions will be provided in writing. In the absence of written response no acceptance should be assumed.
- 2.2 The work includes subsurface soil improvement by Vibro-Compaction and delivery and placement of all concrete as necessary to the improvement process.
- 2.3 Soil improvement by the Vibro-compacted concrete column method is specified for the roads, culvert, and sewer structures, and retaining wall subgrades.
- 2.4 The owner or owner's representative shall locate and stake all concrete column locations by providing a piling location at the centerline of the roadway. The Contractor will be responsible for locating the remainder of the piling based on the location of the piling at the centerline.
- 2.5 Specialty contractor shall contact IUPPS at 1-800-382-5544 three business days prior to the start of work and meet with utility representatives (particularly from NIPSCO for the existing gas main) as necessary to determine the location of utilities.

#### **Special Provision for Vibro-compacted Concrete Columns**

- 2.6 Specialty contractor shall install all concrete columns and perform compaction at the locations and to the elevations indicated on the plans.
- 2.7 Specialty contractor shall maintain the grades at the scheduled top of concrete column elevation. B-Borrow shall be placed over the site as needed to recover the soil volume lost due to compaction.
- 2.8 Specialty contractor shall cooperate and provide material to the Owner's representatives as necessary for them to complete inspection and testing requirements.
- 2.9 The Contractor shall hand dig all existing utilities to ensure that piling are not installed directly through existing utilities. The Contractor shall be responsible for the repair of other utilities that are damaged by the piling operations.
- 2.10 Top of column elevations shall be adjusted at locations where proposed utilities are to be installed and there is a conflict between the two. Top of column elevation shall be reduced so that there is a 18' to 24' separation between the outside diameter of the proposed utility and the top of the columns.
- 2.11 The Contractor shall ensure a firm base on which heavy equipment can be operated without platform maintenance. The Contractor will be responsible for water diversion and containment.

#### 3.0 Owners Responsibilities

- 3.1 The owner shall provide access and egress into the site for the Specialty Contractors' equipment, work force, and delivery of material.
- 3.2 The general contractor at the owners direction shall perform additional densification with a vibratory roller at the top of column grade after the installation of columns is complete. This compaction may be necessary due to the large vibration produced by the Vibro-Compaction equipment and the absence of confinement at the surface. This compaction in no way relieves the specialty contractor of any responsibilities or requirements for compaction of the existing soft or placement of columns.
- 3.3 The owner shall supply a source of water at the existing fire hydrants for the contractor's use. The volumes required will vary with technique, and could range from several thousand g.p.h to in excess of 5,000 g.p.h.

#### 4.0 Applicable Documents

- 4.1 All Vibro-concrete columns bid work should be based upon the following: plans, specifications and geotechnical report.
- 4.2 The subsurface conditions are described in PSI Geotechnical Report, dated March 18, 2002.

Special Provision for Vibro-compacted Concrete Columns

# **4.3** The following documents are referenced elsewhere in this specification.

- 4.3.1 ASTM D 1586 "Penetration Test and Split Barrel Sampling of Soil"
  4.3.2 ASTM D 3441 "Deep Oracle Control of Soil"
- 4.3.2 ASTM D 3441 "Deep, Quasi-Static, Cone & Friction-Cone Penetration Tests of Soil"
- 4.4.3 ASTM D 1143 "Axial Static Load Testing of Piles"

# 4.4 The following documents may be referenced for design and analysis:

- 4.4.1 Aboshi, H.; lehimoto, E; Harada, K.; and Enoki, M; "the composer, a Method to Improve Characteristics of soft clays by Inclusion of Large Diameter Sand Columns. It's design and practical applications," International Conference on Soil Reinforcement, Paris, March 20-22, 1979
- 4.4.2 Barksdale, R.D.; and Bachus, R.C.; "Design and Construction of Stone Column Volume 1", Federal Highway Administration Report No; FHWAIRD-831026, February 1983
- 4.4.3 Bell, F.G. (editor) 1975 Method of Treatment of Unstable Ground, Chapter II, Vibro Floatation; Rational for design and Practices. London, Awnes-Butterworths, pp. 189 209
- 4.4.4 DiMaggio, J.A., "Stone Columns for Highway Construction", Report No.: FHWA-DP-46-1, Department of Transportation, Federal Highway Administration, June 1978.
- 4.4.5 Greenwood, D.A., "Mechanical Improvement of Soils Below Ground Surface," Proceedings of Conference on Ground Engineering, ICE, London, 1970.
- 4.4.6 Greenwood, D.A., and Kirsch, K., "Specialist Ground Treatment by Vibratory and Dynamic Methods,: Piling and Ground Treatment for Foundations", Thomas Telford, London, 1983.
- 4.4.7 Mitchell, J.K. and Huber, J.R., "Performance of a stone column foundation", ASCE Journal of Geotechnical Engineering, Vol. 111, NO. 2, February 1985.

#### 5.0 Qualifications

5.1 The Specialty Contractor performing the Vibro-Compacted Concrete columns shall be one who can provide a minimum of five (5) years of experience record documenting five (5) recent successful projects completed with specific application to these site conditions and improvement criteria. References asserting this documentation shall be provided upon request.

## 6.0 Vibro-Compaction Requirements

6.1 The Specialty Contractor shall use a down hole vibratory capable of providing at least 80 hp and 15 tons of force. The minimum diameter of the probe tip excluding guides shall be 16.0 inches.

**Special Provision for Vibro-compacted Concrete Columns** 

- 6.2 After penetration to the specified column tip elevation the vibrator should slowly retrieved in 12 to 18 inch increments to allow concrete placement.
- 6.3 The vibrator should be re-driven through each increment into the recently placed concrete. Amperage buildup shall be noted.
- 6.4 Amperage buildup and concrete quantities shall be established based on the type of vibratory, concrete slump, soil conditions required to meet the requirements in this section. The established amperage buildup shall be maintained throughout the project.
- 6.5 The concrete shall have a twenty-eight day strength of 3,000 psf. The concrete shall be placed at a slump of 1.0 inches or less.
- 6.6 The concrete should be tested at the rate of one test per half day of production. Each test should consist of one set of three test cylinders 6.0 inches in diameter. One cylinder should be tested at seven days and two cylinders should be tested at twenty-eight days. The cost of the testing to be by the owner.
- 6.7 One column shall be load tested in accordance with ASTM D 1883. The column shall be loaded using the "Quick Load' procedure. The column shaft be loaded to a capacity of 40 tons (80 kips). The column shall be considered acceptable of the settlement at a load of 20 tons (40 kips) is less than 0.5 inches and is less than 2.0 inches at a load of 40 tons (80 kips). A production column may be used for the column load test. The project/ geotechnical engineer shall specify the test column location.

#### 7.0 Tolerances and Acceptance Criteria

- 7.1 Columns shall be located with an accuracy of 3.0 inches of the scheduled location. Piles shall be constructed within 1.5 degrees of vertical.
- 7.2 The concrete column shall be a continuous column of concrete between the top and tip elevations without voids or soil inclusions. The minimum diameter of each column shall be 17.0 inches. The concrete volume shall exceed 115 percent of the theoretical volume of an 18.0 inch diameter column of the specified length.
- 7.3 The zone of soil within 2.0 feet of the face of the concrete column shall be compacted to the following criteria:

'N" Value	10 blows/foot or greater
<b>CPT</b> Resistance	50 t.s.f. or greater
<b>Relative Density</b>	55 percent or greater

7.3.1 Should the minimum "N" values, CPT Resistance or Relative Density not be met, the Vibro contractor will place additional probes to attain the soil improvement criteria at no <u>additional cost to the owner.</u>

#### 8.0 <u>Restrictions</u>

- 8.1 The Specialty Contractor shall obtain all state and municipal permits and conform to all state and local regulations.
- 8.2 Presently no known restrictions exist on handling of the soil at this site. However, Protection Level D should be assumed due to the known industrial nature of the existing fill.
- 8.3 Utility restrictions should be determined by contacting IUPPS and individual utilities as required.
- 8.4 The Contractor shall provide a detailed copy of it's equipment performance specifications for review **prior to award of Contract.**

#### 9.0 **Quality Assurance / Testing and Inspection**

- 9.1 All testing to determine specification compliance will be provided by an independent testing agency and will consist of standard penetration testing per ASTM D 1586, static cone penetration testing per ASTM D 3441 and pile load tests per ASTM D 1883.
- 9.2 Five to ten locations will be established by the geotechnical engineer within the treatment area. CPT and SPT test locations should be located to provide an average of the subsurface improvement.
- 9.3 The geotechnical engineer will provide site inspection to insure performance of the Vibro-Compacted Concrete Column Installation. The inspection may include any specialty Contractor's procedures, recording of concrete quantities and recording of ammeter information.

#### **10.0** Documentation

- 10.1 A daily log shall be submitted to the owner by the Specialty Contractor to include: recording of probe number, start/finished time of probe, depth of treatment, approximate concrete quantities and indication of relative ammeter increases.
- 10.2 Any change in the predetermined vibro program necessitated by a change in the subsurface conditions will be immediately reported and submitted to the engineers.

#### **<u>11.0</u>** Measurement & Payment

- 11.1 Specialty contractor shall provide a lump sum price which shall include all costs for mobilization, demobilization, concrete column layout, concrete column installation and materials, fill incidental to maintaining grade and one concrete column load test.
- 11.2 Unit price for additional concrete columns of specified length.
- 11.3 Unit price for increasing length of scheduled concrete columns.
- 11.4 Unit price for decreasing length of scheduled concrete columns.
- 11.5 Unit price for deletion of scheduled concrete columns.
- 11.6 Unit price for additional load tests.
- 11.7 Unit price for piling reinforcement.
- 11.8 Concrete columns damaged due to negligence of specialty contractor shall be replaced at no cost to owner.

December 4, 2003



Mr. Chad A. Modesitt, P.E. Project Manager The HNTB Companies 111 Monument Circle Indianapolis, IN 46204-5178

Re: MSE Wall Recommendations INDOT Project No.: STP-N606() Des. No.: 0088390 61<sup>st</sup> Avenue Widening and Improvements Hobart, Lake County, Indiana PSI Project No. 016-15159

Dear Mr. Modesitt:

We have completed the analysis and recommendations for 61<sup>st</sup> Avenue widening and improvements project. The purpose of the study was to evaluate the external stability and develop recommendations to aid in design of the proposed MSE walls over the VCC reinforced soils. This report presents our MSE wall analysis and construction considerations.

Based on the preliminary Road Plans prepared by HNTB, the proposed profile indicates significant embankment fills, up to about 14 feet (4.3 m) in thickness, will be required for the roadway widening at the existing culvert structure. To reduce the excessive settlement due to the presence of underlying organic soils, to uniformly support the proposed precast 4-sided reinforced concrete box culvert and sewers, and to limit the risk of overstressing the existing gas pressure main, HNTB has elected Vibro Concrete Column (VCC) from a list of alternatives provided by PSI in the geotechnical report, dated March 27, 2002, for soil remediation.

We understand VCC installed at a 6 feet by 6 feet grid will be required. The VCC grid should be adjusted or additional VCC elements added to provide concentric support along the box culvert, storm sewer alignments, and MSE walls. Also, to uniformly support the proposed embankment fill, precast 4-sided reinforced concrete box culvert, and sewer over VCC, we recommend two layers of biaxial geogrid reinforced crushed aggregate (one foot for each layer) be placed over the installed VCC underneath the precast box culvert and sewer, and three layers of geogrid reinforced crushed aggregate underneath the proposed MSE walls and embankment fills. For further construction considerations for VCC, please refer to PSI geotechnical report, dated March 27, 2002.

Due to the limited space for the roadway widening and embankment slope construction near the proposed culvert structure, south and north MSE walls are planned between Station 50+01 and 51+65, and between Station 50+55 and 52+40, Line "A", respectively.

We have selected a most critical cross section at Station 51+50, Line "A", for the MSE wall analysis. MSE wall design involves the use of controlled soil backfill and thin metallic strips, mesh, or geosynthetic reinforcement mesh (geogrids) to form a gravity mass capable of supporting or restraining large imposed loads. We recommend that the MSE walls be designed by a contractor/manufacturer based on their knowledge and experience in the practice of MSE walls construction of this type.

The MSE walls must be designed for internal and external stability. The design of MSE walls for internal stability is typically the contractor/manufacturer's responsibility. For external stability, a vertical MSE wall must satisfy the same external design criteria as a conventional retaining wall. That is, it must resist forces that can cause sliding as a rigid body at or below the base, overturning, bearing capacity failure, and rotation slip-surface failure (i.e., an unsafe failure surface around the entire embankment). PSI has evaluated sliding, overturning, bearing capacity and rotational failure for the MSE walls supported on VCC. The contractor/manufacturer should be required to submit shop drawings and detailed calculations for final review by INDOT, HNTB, and PSI.

The vertical MSE walls must be designed to resist lateral earth pressures and surcharge pressures transferred from the roadway. The design of this type of system requires that the skin friction between reinforcements should resist the soil pressure from the backfill layer, that the reinforcement length be great enough to support the skin friction and provide a stable mass, and that the reinforcement be strong enough to resist the tension applied. For overall stability, a minimum top width of 0.7 times the overall height of MSE walls is recommended. The length of reinforcements must be extended beyond the zone of Rankine failure. We recommend granular "B" Borrow be used behind the vertical MSE walls and must be compacted to at least 95 percent of the maximum dry density as determined by AASHTO T-99.

The following values are recommended for the design parameters for the MSE retaining walls:

(1). Granular "B" Borrow in MSE fill

$$\gamma_s = 125 \text{ pcf}$$
  
 $\phi = 34^\circ$ 

(2). Retained Compacted Granular Engineered Fill ("B" Borrow)

 $\phi = 32^{\circ}$   $K_a = 0.31$   $K_p = 3.26$  $\gamma_s = 125 \text{ pcf}$  61<sup>st</sup> Avenue Widening and Improvements – MSE Wall Analysis Hobart, Indiana Project No.: STP-N606 () Des. No.: 0088390

(3). Foundation Soils

1. Natural Soft to Very Soft Silty Clay Loam

 $\begin{array}{ll} K_p &= 1.0 \\ c &= 200 \; psf \end{array}$ 

 $\gamma_s = 100 \text{ pcf}$ 

- $\phi = 0^{\circ}$
- 2. Vibro Concrete Column (VCC)
  - $K_{p} = 1.0$
  - c = 5,000 psf (assumed hard soils throughout)
  - $\gamma_s = 150 \text{ pcf}$
  - $\phi = 0^{\circ}$

Allowable bearing pressure = 3,500 psf on the biaxial geogrid reinforced crushed aggregate be placed over the VCC.

The stability analysis was performed by using STABL for WINDOWS two-dimensional, limit equilibrium slope stability program, originally developed at Purdue University. The factor of safety was determined using the modified Bishop method for circular shaped failure surfaces. The minimum factor of safety for overall stability, under the short term (undrained) condition, must meet or exceed the recommendation of 1.5 for external slope stability, static loading recommended for MSE walls in Reinforced Soil Structures, Volume I, Design and Construction Guidelines, Publication No. FHWA-RD-89-043, dated November 1990. The calculated factor of safety for overall stability was 2.0 for the MSE wall. The analyses are reported and summarized in the Appendix.

A minimum factor of safety of 1.5 is recommended for a MSE wall against sliding. The factor of safety against sliding with a 250 psf surcharge was calculated as 2.1 for the MSE wall.

A minimum factor of safety of 2.0 is recommended for a MSE wall against overturning. The factor of safety against overturning with a 250 psf surcharge was calculated as 2.7 for the MSE wall.

A minimum factor of safety of 2.5 is recommended for a MSE wall against bearing failure. Bearing capacity failure governs the VCC spacing design. The VCC spacing of 6 feet was selected to provide a factor of safety of 2.6 against bearing failure with a 250 psf surcharge. However, due to the stress concentration near the face of MSE walls, we recommend a maximum spacing of 5 feet be used between the first and second VCC from the face of MSE walls.

A summary of calculated factors of safety against sliding, bearing failure, overturning, and overall stability (or rotation slip-surface) failure is presented below.

Failure Mode ①②	Sliding	Overturning	Bearing	Overall Stability
Minimum Required Factor of Safety	1.5	2.0	2.5	1.5
MSE Wall Station 51+50, Line "A" (TB-2)	2.1	2.7	2.6	1.9

① Analysis for the proposed MSE walls, with 250 psf surcharge.

<sup>(2)</sup> Assumed length of horizontal reinforcements extended about 0.7 time the height of the proposed MSE walls.

We appreciate the opportunity to provide geotechnical engineering services for this project. If there are any questions regarding the information contained in this report, please contact us at (317) 216-7131.

Respectfully,

### **PROFESSIONAL SERVICE INDUSTRIES, INC.**


Peter Lee

Peter S. Lee, Ph.D., P.E. Senior Engineer

Elizabeth Durgset

Elizabeth M. Dwyre, P.E. Regional Engineer

Attachment: MSE wall analysis




SUBJECT: USE Well Analysi= Information PROJECT: 61st Ave Reconstruction PROJECT NO. STP - N 606 ( ), les Engineering • Consulting • Testing CALC. BY: PSL DATE: 1/19/03 Sheet \_\_\_\_\_ of \_\_\_\_\_ CHECKED. BY: FEMID DATE: 11/30/03 MSE WALL ANALTSIS @ Stadion. 51+50, Line "A" - Height of MSE Wall (from top of geogrid to bottom of loping)= ATE | CRIPTIONS) 611.3 <u>♥ 608,5</u>' IB WATER 596 ONSI - Existing Ground Surface FLev. = 608.7' - Top of Geogrid = 6/1.3" - Rottorn of Coping: 621.3' - Top of pavement: 626.0' - Thick we sof geophia = 2' - Height of Coping, hs: (626'-621.3') + 2' = 6.7' ("/Traffic load of 250 psf) - Height of MSE walk = 621.3'- 6/1.3' = 10


A-300-9 (Indy)

Subject: <u>MSE W</u>	all External	<u>Stabilty Analy</u>	sis		<b>The I</b> Information			
Project: <u>61st Av</u>	Checked by: <u>Emd</u> Date: <u>11/20/03</u> Page <u>2</u> of <u>6</u>							
Project No.:	<u>STP-N 606( )</u>	) Design	ation No.:	<u> 2088390</u>				
Checked by:	Emd	Date: _	11/20/0	3	Page _ 2 of _ 6			
<u>Units</u>	Ih	11-	16					
kip := 1000 ·lb	$plf := \frac{ID}{ft}$	$psf := \frac{10}{ft^2}$	$pcf := \frac{1D}{ft^3}$	ksi := $\frac{\kappa p}{\ln^2}$				
	klf := $\frac{\text{kip}}{\text{ft}}$	ksf := $\frac{\text{kip}}{\text{ft}^2}$	$kcf := \frac{kip}{ft^3}$					

Typical Cross Section of MSE Wall (Top of Levelling Pad Elev. = 610.3")



(I). Soil and MS	E Wall Properties at TB-1-SG & TB	- <u>-2</u> B :=	240-ft B: Length of MSE Wall
γs := 125 ·pcf	$\gamma_{\rm s}$ : Unit Weight of Surcharge Soil	hs := 6.7 ⋅ft	h <sub>s</sub> : Weight of Surcharge (soil+Traffic)
γr := 125 ·pcf	$\gamma_{r}$ . Unit Weight of Reinforced Soil	φr:= 34 deg	$\phi_r$ : Friction Angle of Reinforced Soil
γf := 125 ⋅pcf	$\gamma_{f}$ Unit Weight of Foundation Soil	φf := 34 ⋅ deg	$\phi_{f}$ : Friction Angle of Foundation Soil
cf := 0 ⋅ psf	c <sub>f</sub> : Cohesion of Foundation Soil	Df := 3.5 ⋅ ft	$D_{f}$ : Depth of MSE Wall Leveling Pad
$Kp := \frac{1 + \sin(\phi f)}{1 - \sin(\phi f)}$	K <sub>p</sub> : Coefficient of Passive Earth Pres	sure	Kp = 3.537
γb := 125 ·pcf	$\gamma_{b}$ : Unit Weight of Backfill	φb:=32∙deg	$\boldsymbol{\varphi}_{b}$ : Friction Angle of Backfill
H := 11.0·ft	H: Height of MSE Wall	L := 0.7·H	L: Width of MSE Wall
$\mu := tan(\phi b)$	$\mu = (\text{Select}) \text{ Minimum of } \tan \phi_{r_{r}} \tan \phi_{f}$ , c	or tanq <sub>b</sub>	μ = 0.625



 $Pb := 0.5 \cdot Kab \cdot \gamma b \cdot H^2$ 


Pq := Kab·γs·hs·H

 $FS\_sliding := \frac{(Vq + W) \cdot \mu}{Pb + Pq}$ 

FS\_sliding = 2.1 >1.5, O.K.

Subject: <u>MSE Wall External Stab</u>	ilty Analysis	<b>Information</b>
Project: <u>61st Avenue Widening,</u>	Culvert @ Station 50+95, Line "A"	Information To Build On Engineering • Consulting • Testing
Project No.: <u>STP-N 606( )</u>	_ Designation No.: <u>0088390</u>	
Calculated by:PSL	Date: <u>11/17/03</u>	
Checked by: <u>Emd</u>	Date: <u>11/20/03</u>	Page <u>4</u> of <u>6</u>

(III). Factor of Safety against Overturning



Vq := γs ⋅hs ⋅L

 $W := \gamma r \cdot H \cdot L$ 


 $\mathsf{Kab} := \tan\!\left(\frac{\pi}{4} - \frac{\phi \mathsf{b}}{2}\right)^2$ 

 $Pb := 0.5 \cdot Kab \cdot \gamma b \cdot H^2$ 

Pq := Kab<sub>`</sub>γs ⋅hs ⋅H

FS\_overturning := 
$$\frac{(Vq + W) \cdot \left(\frac{L}{2}\right)}{Pb \cdot \left(\frac{H}{3}\right) + Pq \cdot \left(\frac{H}{2}\right)}$$

 $FS_overturning = 2.7 >= 2.0, O.K.$ 



γ<sub>b</sub>, φ<sub>b</sub>

K., 9

P.

emax = 1.3 ft

K<sub>e,b</sub> Y<sub>b</sub>H

<u>н</u> 3

O.K.

2

(2). The magnitude of the Vertical Stress,  $\sigma_{vmax}$ :  $\sigma_{vmax} := \frac{(Vq + W)}{L - 2 \cdot e}$   $\sigma_{vmax} = 3497 \text{ psf}$ 

W

16.

L-2e 12e

7r. 9r.

71.91

(1). The Eccentricity, e, of the resultant loads:

 $e := \frac{Pb \cdot \left(\frac{H}{3}\right) + Pq \cdot \left(\frac{H}{2}\right)}{W + Vq} \qquad e = 1.4 \text{ ft} \quad \le \text{ emax} := \frac{L}{6}$ 

(3) soits below the base of vibro concrete column (VCC) are indicated to be loose to very loose sand, W/N = 3 - 7 bpf,  $\phi = 28^{\circ}$ .

(5) Unit Wt. of overlying silty day loam with organics  

$$Y_{s} = 109 \text{ pcf}$$
 based on cosolidations data  
 $T_{d} = 72 \text{ pcf}$ 

(6) Allowable bearing Capacity at base of VCC  

$$Q_{p} = A_{p} g_{p} = A_{p} g' N_{g}^{*} = 4.9 \times (25\times2+109\times2.8+)$$

$$(109-62.4) \times (2.5) \times 40 = 4.9 \times 1138 \times 40 = 223 \text{ kips.}$$


$$Q_{p_{all}} = 223/2.5 = 89 \text{ Kips.}$$

SUBJECT: <u>MSZ Wall Analysis</u> PROJECT: <u>61st Ave Reconstruction</u> PROJECT NO. <u>STP - N 606 ()</u> CALC. BY: <u>PSL</u> DATE: <u>11/19/03</u> CHECKED. BY: <u>BMD</u> DATE: <u>u/36/63</u>



(7) FOR VCC pattern of 6'x6' Max Load on each VCC = ( hs+1++ gogrig reinforced mait) × 125 × 6×6 = (6.7+10+ 2) × 125 × 6×6 = 84 Kips = Qpall = 89 Kp General VCC pattern of 6'×6' is considered appropriate -except in the area near MSE face where phaximum. Stress is concentrated. (8) Hax spacing under MSE wall.  $S = \frac{\beta p_{all}}{\nabla v_{max}} = \sqrt{\frac{89}{3.5}} = 5.0'$ Therefore, the spacing between the first and second VCC from the face of MSE will should be 5' max. (V) Global Stability Failune See the attached slope stability analysis using the Composite soil parameters after VCC improvements

A-300-9 (Indy)



61st Avenue Widening - STP-N606() - FS Min = 1.888



9715 KENNEDY AVENUE • HIGHLAND, INDIANA 46322 (219) 924-5231 • (773) 734-5900 • FAX (219) 924-5271

July 25, 2006

www.kandsengineers.com • ksengineers@sbcglobal.net

HNTB Corporation 111 Monument Circle Suite 1200 Indianapolis, IN 46204-5178

- Attn: David W. McDougall, P.E., Structures Department Manager
- RE: Designation No.0088390
   Project No. STP-N606()
   Subsurface Conditions for MSE Wall Design 61<sup>st</sup> Avenue Widening and Improvements
   Hobart, Lake County, Indiana
   K & S Project No. 7998

Dear Mr. McDougall:

We are herewith submitting for your review and approval a draft copy of a report for the Subsurface Conditions for MSE Wall Design, 61<sup>st</sup> Avenue Widening and Improvements, Hobart, Lake County, Indiana. This report presents the field and laboratory data obtained, together with our conclusions and recommendations concerning the influence of the subsurface conditions on the proposed design and construction.

We are looking forward to receiving your comments. If you have any questions or need additional information, please do not hesitate to call us at (219) 924-5231.

Very truly yours, K & S Engineers, Inc.

Dibakar Sundi, P.E.. Senior Engineer

Padmakar Srivastava, Ph.D., P.E. Project Engineer

	DATE RECEIVED
	HNTB INDIANAPOLIS
JOB	NO
FILE	

Attachment: One draft copy of the geotechnical report

DS:PS/dp

JUL 3 1 2006

ROUTE-TO:

Geotechnical and Environmental Consultants

### **REPORT**

### SUBSURFACE CONDITIONS FOR MSE WALL DESIGN PROJECT NO. STP-N606() DESIGNATION NO. 0088390 61<sup>st</sup> AVENUE WIDENING AND IMPROVEMENTS HOBART, LAKE COUNTY, INDIANA K & S PROJECT NO. 7998

HNTB Corporation 111 Monument Circle Suite 1200 Indianapolis, IN 46204-5178

Attn: David W. McDougall, P.E. Structures Department Manager

K₄S

### **EXECUTIVE SUMMARY**

A summary of the conclusions and recommendations of this report is given below.

<u>Project Description</u>: City of Hobart, Lake County, Indiana is planning widening and improvements of 61<sup>st</sup> Avenue from approximately 200 feet east of Marcella Boulevard to approximately 750 east of Colorado Street. The eastern portion of the project, where the roadway would be supported on a MSE wall, is identified as Project No. STP-N606() with Designation No. 0088390.

It is reported that compressible organic materials are present underlying the 61<sup>st</sup> Avenue from approximately Station 50+00 to 52+50, a distance of approximately 250 feet. It was proposed to improve the ground by using Vibro Concrete Columns. Later, based on the unsatisfactory performance of the Vibro Concrete Column system on some projects, it was decided not to use such system on the present project.

It is proposed to install sheeting along the limits of the proposed roadway, excavate the unsuitable material between the sheet piles down to suitable foundation material and construct MSE walls within the excavation up to the proposed roadway profile.

The purpose of the present geotechnical exploration was to establish a subsurface profile and delineate the organic materials along 61<sup>st</sup> Avenue between the proposed limits.

<u>Subsurface Conditions:</u> Underlying approximately 0.8-foot to 3.5-foot-thick layer of asphalt and crushed stone at the surface, the borings encountered silty clay loam and silty clay extending to depths ranging from 9 feet in Boring RB-4 to 18.5 feet in Borings RB-1 and RB-6 through RB-8.

Very soft to soft organic materials and peat were observed in Borings RB-4 (extending from a depth of 9 feet to 16 feet) and RB-5 (extending from a depth of 13.5 feet to 23.5 feet).

Organic materials were not observed in Borings RB-1 through RB-3 and RB-6 through RB-8.

Underlying the organic materials in Borings RB-4 and RB-5 and below silty clay loam/silty clay in the remainder borings, stratum of loose to medium dense sand was observed.

The borings were terminated in the stratum of loose to medium dense sand at depths ranging from 20 feet to 30 feet.

Groundwater levels were observed at depths ranging from 6 feet to 16 feet after 24 hours of completion of the boreholes.

Do not consider this summary separate from the entire text of this report, with all the conclusions and qualifications mentioned herein. Details of our analysis and recommendations are discussed in the following sections and in the Appendix of this report.



### TABLE OF CONTENTS

			PAGE
1.	INT	RODUCTION	1
	1.1	Project Identification	1
	1.2	Scope of Services and Procedures	1
2.	GEN	<ul> <li>1.2 Scope of Services and Procedures</li> <li>GENERAL SITE CONDITIONS</li> <li>2.1 General Geology</li> <li>INVESTIGATION PROCEDURES</li> <li>3.1 Field Investigation</li> <li>3.2 Laboratory Testing</li> <li>RESULTS OF FIELD INVESTIGATION</li> <li>4.1 General Subsurface Conditions</li> <li>4.2 Groundwater Conditions</li> <li>4.2 Groundwater Conditions</li> <li>5.1 MSE Wall Design</li> <li>CONSTRUCTION CONSIDERATIONS</li> <li>6.1 Fill Placement and Compaction</li> </ul>	3
	2.1	General Geology	3
3.	INV	ESTIGATION PROCEDURES	4
	3.1	Field Investigation	4
	3.2	Laboratory Testing	4
4.	RES	<b>SULTS OF FIELD INVESTIGATION</b>	5
	4.1	General Subsurface Conditions	5
	4.2	Groundwater Conditions	5
5.	ANA	ALYSES AND RECOMMENDATIONS	6
	5.1	MSE Wall Design	6
6.	CON	STRUCTION CONSIDERATIONS	ditions5s5HENDATIONS666ERATIONS7
	6.1	Fill Placement and Compaction	7
	6.2	Excavations	7
7.	LIM	ITATIONS	9

K₄S

# 1. INTRODUCTION

# 1.1 <u>Project Identification and Description</u>

We understand that the City of Hobart, Lake County, Indiana is planning widening and improvements of 61<sup>st</sup> Avenue from approximately 200 feet east of Marcella Boulevard to approximately 750 east of Colorado Street. The eastern portion of the project, where the roadway would be supported on a MSE wall, is identified as Project No. STP-N606() with Designation No. 0088390.

A geotechnical exploration was performed and report was submitted by PSI of Indianapolis, Indiana on March 27, 2002. It was observed that compressible organic materials are present underlying the 61<sup>st</sup> Avenue from approximately Station 50+00 to 52+50, a distance of approximately 250 feet. The depth of the organic materials is as much as 22 feet. It was proposed to improve the ground by using Vibro Concrete Columns. Later, based on the unsatisfactory performance of the Vibro Concrete Column system on some projects, it was decided not to use such system on the present project.

It is proposed to install sheeting along the limits of the proposed roadway, excavate the unsuitable material between the sheet piles down to suitable foundation material and construct MSE walls within the excavation up to the proposed roadway profile. Therefore, a better understanding of the limits of the unsuitable material is required.

The purpose of the present geotechnical exploration was to establish a subsurface profile and delineate the organic materials along 61<sup>st</sup> Avenue between proposed limits.

# 1.2 <u>Scope of Service and Procedures</u>

The general purpose of the geotechnical exploration was to develop recommendations with regard to the soil and groundwater conditions to aid in the design of the MSE wall. The scope of our services for this project was as follows:

1. A review of available geologic information for the project area.

2. A section beginning from Station 48+75 to 53+50 along 61<sup>st</sup> Avenue was considered.

- 3. Perform a total of 8 borings, ranging in depth from 20 feet to 30 feet. The Roadway Borings are referred to with a Prefix 'RB.' Obtain soil samples according to INDOT specifications.
- 4. Observe groundwater level during and 24 hr after drilling.
- 5. Perform appropriate laboratory tests and visual classification according to current INDOT specifications.
- 6. Prepare a report which provides our recommendations with regard to cut and fill requirements and pavement design as well as potential groundwater problems.

The scope of services did not include an environmental assessment for determining the presence or absence of wetlands or hazardous or toxic materials in the soil, bedrock, surface water, groundwater, or air on or below, or around this site. Any statement in this report or on the boring logs regarding odors, colors, and unusual or suspicious items or conditions are strictly for the informational purposes.

### 2. GENERAL SITE CONDITIONS

### 2.1 <u>General Geology</u>

Soils within the project area are characterized as unconsolidated glacial deposits overlying sedimentary bedrock sequences. The unconsolidated sediments were deposited during the Late Wisconsian Age as lakebottom and near shore deposits of glacial Lake Chicago. As fluctuations in lake levels occurred, cycles of sand, gravel and lake bottom deposits of silt and clay occurred as the lake shore line receded northward. The northward movement of the shore line resulted in the deposition interstratified lake and terrestrial (surface erosion deposition of sand dune) deposits which are indistinguishable from one another.

Within the project area the unconsolidated deposits are classified as belonging to the dune or lacustrine facies of the Atherton Formation of northwestern Indiana and form the Calumet Lacustrine Plain. The Calumet Lacustrine Plain forms the principal shallow groundwater aquifer or the Calumet Aquifer. The Calumet Aquifer is a water-bearing unconfined aquifer ranging from about 5 to 75 feet (1.5 to 23 meters) in thickness. Beneath the aquifer is a relatively impermeable clay till overlying the sedimentary bedrock sequences. The estimated depth to the sedimentary bedrock sequences within the project area is approximately 100 to 150 feet (30 to 46 meters) below the ground surface. Bedrock within the site consist of limestone and dolomite deposits of Silurian age.

# 3. INVESTIGATION PROCEDURES

### 3.1 <u>Field Investigation</u>

A K & S field engineer/senior foreman was on site during drilling operations to assist in logging the boring. Traffic control was observed to provide a safe working environment for our field crews during our field operations. Upon completion of drilling, the borings were either covered with cones, or a screened PVC pipe was installed for observing 24-hour water level readings. The borings were backfilled subsequently.

The borings included split-spoon sampling in general accordance with ASTM Standard D 1586/AASHTO T-206. Results of the boring data showing the materials encountered, natural moisture content of cohesive soils, groundwater level readings and other pertinent observations made during the drilling operations are included on the boring logs in the Appendix.

### 3.2 Laboratory Testing

The purpose of the laboratory investigation was to determine the classification and physical properties of the soils encountered on the project. The classification tests included grain-size analyses, Atterberg Limit and Loss on Ignition tests. In addition to these tests, natural moisture content tests were performed on all cohesive soil samples. A summary of the classification tests is presented in Table 1 and the results of all laboratory tests are presented in Table 2 in the appendix.

### 4. RESULTS OF FIELD INVESTIGATION

### 4.1 <u>General Subsurface Conditions</u>

At the surface approximately 0.8-foot to 3.5-foot-thick layer of asphalt and crushed stone was observed.

Underlying asphalt and crushed stone at the surface, the borings encountered silty clay loam and silty clay extending to depths ranging from 9 feet in Boring RB-4 to 18.5 feet in Borings RB-1 and RB-6 through RB-8. The standard penetration resistance (SPR) N-values in silty clay loam and silty clay ranged from approximately 3 blows per foot (bpf) to 24 bpf.

Very soft to soft organic materials and peat were observed in Borings RB-4 (extending from a depth of 9 feet to 16 feet) and RB-5 (extending from a depth of 13.5 feet to 23.5 feet). The SPR values in the organic materials ranged from 2 bpf to 4 bpf with pocket penetrometer resistance (PPR) values ranging from 0 tons per square foot (tsf) to 1.25 tsf. The moisture content in the organic materials ranged from 19 percent to 163 percent, with organic content ranging from 3 percent to 74 percent.

Organic materials were not observed in Borings RB-1 through RB-3 and RB-6 through RB-8.

Underlying the organic materials in Borings RB-4 and RB-5 and below silty clay loam/silty clay in the remainder borings, stratum of sand was observed. The SPR values in the stratum of sand ranged from approximately 7 bpf tp 29 bpf, indicating a loose to medium dense consistency.

The borings were terminated in the stratum of loose to medium dense sand at depths ranging from 20 feet to 30 feet.

### 4.2 Groundwater Conditions

Groundwater levels were observed at depths ranging from 6 feet to 16 feet after 24 hours of completion of the boreholes. It should be noted that the groundwater levels are subject to seasonal and long-term variations in response to climatic conditions and man-made influences.



### 5. ANALYSES AND RECOMMENDATIONS

### 5.1 MSE Wall Design

It is understood that the design of the sheet-pile and MSE walls would be performed by others. The MSE wall should analyzed for the external stability, including: Sliding, Overturning, Bearing Capacity and Global stability. It is believed that the internal stability would be performed by the MSE Wall manufacturer.

Following Factors of Safety (FOS) are recommended for the analysis.

Sliding	≥ 1.5	
Overturning	≥ 2.0	
Bearing	≥ 2.5	
Slope Stability	≥ 1.5	(Static conditions)

A 2 feet of surcharge should also used to reflect FHWA HS 20 loading.

For estimating bearing capacity, factor of safety for sliding, overturning and global stability, following parameters are recommended:

Specified Backfill:	c = 0
(Reinforced Soil Zone)	$\Phi = 32^{\circ}$
	$\gamma = 120 \text{ pcf}$
In-situ Foundation Soils	c = 0
(Sand)	$\phi = 32^{\circ}$ to $34^{\circ}$
	$\gamma = 120 \text{ pcf}$



### 6. CONSTRUCTION CONSIDERATIONS

### 6.1 Fill Placement and Compaction

Engineered fill used on this project should be approved, environmentally clean material, free of lumps, frozen soil, wood, roots, topsoil, or other deleterious material. The engineered fill should meet the requirement of borrow as specified in Section 203.08, INDOT 1999 Standard Specifications. On-site materials such as silty clay loam are not expected to meet the requirement for "B" borrow material. Depending on the time of construction, some aeration, or moisture conditioning of the fill material may be required.

Fill materials should be placed in lift thicknesses (loose) not to exceed 8 inches (20 centimeters), and compacted to the required density as specified in the latest INDOT Standard Specifications. A vibratory roller should be used to compact the granular soils.

### 6.2 <u>Excavations</u>

The Contractor is solely responsible for designing and constructing stable, temporary excavations and should shore, slope or bench the sides of all the excavations as required to maintain the stability of the excavation sides and bottom. All excavations should comply with applicable local, state and federal regulations including the current OSHA Excavation and Trench Safety Standards. Construction site safety generally is the sole responsibility of the Contractor, who shall also be responsible for the means, methods and sequencing of construction operations. We are providing this information solely as a service to our client. Under no circumstances should the information provided herein be interpreted to mean that K & S Engineers, Inc., is assuming responsibility for construction site safety or the contractor's activities; such responsibility is not being implied and should not be inferred.

In no case should slope height, slope inclination or excavation depth, including utility trench excavation depth exceed those specified in local, state and federal safety regulations. Specifically, the current OSHA Health and Safety Standards for Excavations, 29 CFR Part 1926 should be followed. We understand these regulations are being strictly enforced and if they are not closely followed, the Owner and Contractor could be liable for substantial penalties.



### 7. LIMITATIONS

The conclusions and recommendations presented in this report are based upon the assumption that the subsurface conditions do not deviate appreciably from those disclosed by the borings. These conclusions and recommendations are also based upon the premise of competent field engineering, monitoring and testing during construction.

If, during construction, subsurface conditions different from those encountered in the exploratory borings are observed or appear to be present beneath excavations, we should be advised at once so that we can review these conditions and reconsider our recommendations where necessary.

This report was prepared for the exclusive use of the owner, architect, and engineer for evaluating the design of the project as it relates to the geotechnical aspects discussed herein.

### APPENDIX

- 1. Exhibit 1: Inferred Subsurface Profile
- 2. Exhibits 2 through 9: Boring Logs
- 3. Summary of Classification Test Results
- 4. Summary of Special Laboratory Test Results
- 5. Figures 1 through 5, Grain Size Distribution Curves




EXHIBIT 2 Sheet 1 of 1

										S	neet	<u>1 of 1</u>		
CLIENT	Th	e HNTB Companies			LOG	OF B	ORIN	NG NUME	BER	DES. NO.				
PROJE	CT NA	ME 61st Avenue Wide	ening & Impro	ovement		F	RB	-1		PROJECT NO	).			
SITE LO	CATIO	ON 61st Avenue, Hot	art, Indiana	·		STRUCTURE NUMBER				STATION 48+78	5, A	OFFSE	r 10' R	t
BORING		1-31-06	RIG	Diedrich D-50		ILE N	UMB	ER	$\oplus$	CALIBRATED P		DMETER,	TONS/F	T <sup>2</sup>
BORING	3	1-31-06	FOREMAN	Ruben Perez	-	7998		0	UNCONFINED C TONS/FT <sup>2</sup>	OMPRE	ESSIVE S	TRENG	TH,	
	SUF	RFACE ELEVATION ft	(m) USC & 0	S			SAM	PLE	0	1 2	3	4	5	6
(METERS) STRATA DEPTH (FEET)	TEXTURAL ASSIFICATION				FC	5	~	т )	•	WATER CONTE	NT, %	·		
(METERS) RATA DEP (FEFT)		DESCF		ATERIAL	DEPTH (FEET)	N PE	NUMBER	DRY UNIT WEIGHT pcf (kg/m <sup>3</sup> )	0 L	10 20	30 1	40 I	50	60 
STR		2				TYPE RECOVERN	NN	DR) VE	Δ	BLOW COUNTS				
	ರ *****	Asphalt, 13 inches	over 2 inche	es of crushed					0	10 20	30	40	50	60
<u> </u>	3	<u>stone, visual</u> Brown, damp, very			$\perp$		1							
		LOAM, Lab No. 79	98-1, A-6(9)		- 2.5 -	Н	,			5,7,9				
							2							
					- 5.0 -	$\mathbb{A}$	2			6,7,9				
-2							3							
					- 7.5 -	$\mathbf{k}$	J			3 5,9				
E 8.	9//// +/+/	Gray, damp, mediu	m stiff, Silty	Clay, Lab. No.		$ \mathcal{H} $	4							
-3		7998-2, A-6(13)			-10.0-		4			3,57	₽			
	+++						5							
Ē		-12.5-					0			3,5 7 0				
- <sup>4</sup>							6							
					- 15.0-	4	0		:	3,5,5				
-5	++++													
È					-17.5-									
- 18.4 -	54.24	Brown, wet, loose,	Sand, Lab.	No. 7998-3,	Z	+	7							
6 20.0	0	A-3(0) END OF BO			20.0-	44	1		3,4	4,4				
				5.03 EE1										
								ſ						
,										<u> </u>	<u> </u>			
·		LEVEL WHILE DRILLING					RE	MARKS						
¥ v	VATER	LEVEL 16.0 FEET 24 HC	OURS AFTER (	COMPLETION										
	IT 90/				W OODE				<u> </u>					
			E MI AUGE QUID LIMIT	R ⊠ROC Xa-UNITDRY	X CORE		:			K&SEN	IGINE	ERS,	INC.	
11						.	1		Ľ					11

EXHIBIT 3 Sheet 1 of 1

LIENT The HNTB Companies         ROJECT NAME 61st Avenue Widening & Improvement         ITE LOCATION       61st Avenue, Hobart, Indiana         ORING       1-18-06       RIG       Diedrich D-120         ORING       1-18-06       FOREMAN       Carlos Santana         OMPLETED       1-18-06       FOREMAN       Carlos Santana         T       SURFACE ELEVATION       ft (m) USC & GS		RB		BER	DES. NO.	1.0	<u>1 of 1</u>	I <u></u>	
ITE LOCATION 61st Avenue, Hobart, Indiana ORING 1-18-06 RIG Diedrich D-120 ORING 1-18-06 FOREMAN Carlos Santana	STRUCTUR		-2						
ORING TARTED     1-18-06     RIG     Diedrich D-120       ORING OMPLETED     1-18-06     FOREMAN     Carlos Santana				PROJECT NO.					
TARTED     1-18-06     Rig     Diedrich D-120       ORING     OMPLETED     1-18-06     FOREMAN     Carlos Santana       SUBFACE ELEVATION     ff (m) USC # CS		STRUCTURE NUMBER FILE NUMBER			STATION 49+40, OFF			FSET 10' Lt	
OMPLETED 1-18-06 FUREMAN Carlos Santana	FILEN				CALIBRATE	D PENETR			
T SURFACE ELEVATION ft ( m) USC & GS	7	998		0	UNCONFINI TONS/FT <sup>2</sup>	ED COMPF	RESSIVE S	TRENG	
		SAM	PLE	0 L	1 2	23	4	5 J	
ACTINE AC	EE A	Ľ Ľ	EF5	-	WATER CO				
	DEPTH (FEET) TYPE RECOVERV	NUMBER	DRY UNIT WEIGHT pcf (kg/m <sup>3</sup> )		10 2 	<u>1</u>	40	50 	
		ž	RG≥pa	∆ ₀	BLOW COU 10 2		40	50	
0.8 Asphalt, 6 inches over 4 inches of crushed									
Stone, visual Brown to gray, moist, stiff to very stiff, Silty Cla	¥ ==7	] 1				Ð			
LOAM, Lab. No. 7998-4, A-6(9)	- 2.5				3,66				
		2					 ⊕		
	- 5.0 -				5,10	,74			
		3				⊕⊕			
	- 7.5				3,6,9				
		4							
	-10.0-				5,8,12	- Ţ. •		.	
		5							
	- 12.5				3,57				
14.0 Brown, wet, medium dense, Sand, Lab. No.		6							
7998-3, A-3	- 15.0-7					5,13,16			
	-17.5-					/			
	-20.0	7			3,6,10				
					4.0,10				
	-22.5-								
	-25.0	8			4,10,12				
END OF BORING @ 25.0 FEET									
		<u>.                                    </u>							
WATER LEVEL WHILE DRILLING 14.0 FEET		RE	MARKS						
	CK CORE		6			,			
PL-PLASTIC LIMIT + LL - LIQUID LIMIT 1/2 - UNIT DR				$\mathbb{D}$	K & S	ENGIN	EERS, I	NC.	

**EXHIBIT 4** 




EXHIBIT 5 Sheet 1 of 1

								XHIBIT heet 1			
CLIENT Th	e HNTB Companies		LOGO	FBOR	RING NUME	BER	DES, NO.			<u></u>	
PROJECT NA	ME 61st Avenue Wi	dening & Improvement	1	RE	3-4		PROJECT NO.				
SITE LOCATIC	DN 61st Avenue, Ho	obart, Indiana	STRUCT			STATION 50+68, Line A OFFSET 10' Lt					
BORING STARTED	1-18-06	RIG Diedrich D-120	FILI	E NUM	IBER	-	CALIBRATED P	ENETRON			
BORING COMPLETED	1-18-06	FOREMAN Carlos Santana	<u> </u>	7998		0	UNCONFINED ( TONS/FT <sup>2</sup>	COMPRES	SIVE STI	RENGTH,	
	RFACE ELEVATION		SA 	MPLE			3	4 I	5 		
(METERS) RATA DEPT (FEET) STURAL SIFICATION			DEPTH (FEET) VDE			٥	WATER CONTE	30	40	50 e	
e H K	DESC	RIPTION OF MATERIAL		RECOVERY NI IMBER	DRY UNIT WEIGHT pcf (kg/m <sup>3</sup> )		BLOW COUNTS	 ;	1		
	Asphalt 8 inchas	over 6 inches of crushed	+			0	10 20	30	40	50 1	
1.2	<u>stone, visual</u>	ay, moist, medium stiff, Silty		日.							
	Clay LOAM, Lab.	No. 7998-1, A-6	- 2.5	1		3,3,3	$\mathbf{P}_{\mathbf{v}}$				
				七 2							
			- 5.0 -			3,3,		P 			
2				囗 3	;			θ			
			- 7.5 -			3,3,	·				
3	Dark gray to black	, wet, very soft Peat with Lab. No. 7998-5, A-7-5	- 10.0	∕∐ ₄		Į∉.	··				
	LOI= 73.9%	_db. No. 7880-3, A-7-3	<u>10.0</u>								
	201 10.070		-12.5	5						16:	
	LOI= 3.4%			+ 6							
16.0	LUI= 3.4%		- 15.0-	┦╹		2 1.3		•		1	
5	Gray and brown, v No. 7998-3, A-3	vet, very loose, Sand, Lab.						17			
	110.1000 0,710		-17.5-					ľ			
6				7		$\mathbf{k}$					
			-20.0-			$\left \right\rangle$					
			22.5			`					
7 23.5	Gray and brown, v	vet, medium dense to dense,									
	Sand, Lab. No. 79	98-3, A-3	-25.0	8			8,8,8				
8			· · · · · · · · · · · · · · · · · · ·								
			-27.5-								
9 30.0	END OF B	ORING @ 30.0 FEET	=7	9							
	LEVEL WHILE DRILLIN	G 9.5 FEET	and a second	R	EMARKS		<u>l</u>	7,15,21	. <u> </u>	17 / Mar 1	
VATER	LEVEL 8.0 FEET 24 HC	OURS AFTER COMPLETION									
						~					
_ SPLIT SPO + PL - PLASTI		BE 🛛 AUGER 🛛 ROC IQUID LIMIT 🍾 - UNIT DRY	K CORE			$\mathbf{F}$	K & S EN	IGINEE	RS, IN	IC.	
						<u> </u>	· · · · · · · · · · · · · · · · · · ·				





EXHIBIT 7 Sheet 1 of 1

r									Sheet	<u>1 of </u>	1	
CLIENT The H	INTB Companies			LOG	OF BC	ORIN	IG NUME	BER	DES. NO.			
PROJECT NAME	61st Avenue Wid	ening & Impro	ovement	1	F	RB-	-6		PROJECT NO.			
SITE LOCATION	61st Avenue, Hol	bart, Indiana		STRU				STATION 51+96, OFFSET 10' Lt				
BORING STARTED	1-18-06	RIG	Diedrich D-120		ILE NL	IMB	ER					-2
BORING COMPLETED	1-18-06	FOREMAN	Carlos Santana	7998				0	UNCONFINED COMPE TONS/FT <sup>2</sup>	RESSIVE	STRENGT	H,
SLIDEA	CE ELEVATION ft	(m) USC & C	SS		5	SAMPLE		0 L	1 2 3	4	5	6
(METERS) STRATA DEPTH (FEET) TEXTURAL ASSIFICATION				1 FF	7	<b>m</b>	⊢∟∩	•	WATER CONTENT, %	,		
(METERS) RATA DEP (FEET) STURAL SIFICATION	DESC	RIPTION OF M/	ATERIAL	DEPTH (FEET)	TYPE RECOVER	NUMBER	DRY UNIT WEIGHT pof (kg/m <sup>3</sup> )	0 L	10 20 30	40 	50 	60 
() STR TEV LASS						N	Ę <sub>,</sub> Я	∆ ₀	BLOW COUNTS 10 20 30		50	
	sphalt, 11 inches	over 4 inche	es of crushed							40	50	60
1.3 s	tone, visual Gray-brown to gray OAM, Lab. No. 79	y, moist, stiff	, Silty Clay		П	1						
	.OAM, Lab. No. 79	998-1, A-6		- 2.5 -	H			ł	4,3,8			
Ē					IЛ	2						
				- 5.0 -	H				4 5,g			
-2			·			3						
				- 7.5 -	H				5,6,7			
						4						
				-10.0-					46.7			
			Ţ		$\square$	5						
				- 12.5-	H				56,8			
						6						
				- 15.0-					4,5,6			
5												
18.5			7	- 17.5-								
	Gray-brown, wet, m lo. 7998-3, A-3	nedium dens	se, Sand, Lab.		$\overline{\Lambda}$	7						
	0.7000-0,740			-20.0-					4,5,6			
7				-22.5-								
						8						
				-25.0	41				7,10,16			
8												
				-27.5-			Í					
- - 9 30.0	END OF BO	DRING @ 30	0.0 FEET		$\pi$	9						
· / · · · · · · · · · · · · · · · · · ·	VEL WHILE DRILLING			<u> </u>		REN	MARKS	<u> </u>	<u> </u>	<u> </u>		╧
•	VEL 11.0 FEET 24 HC		OMPLETION									
i	<u> </u>											
SPLIT SPOON	SHELBY TUB		R 🛛 ROC	K CORE			A	$\mathbb{P}$	K & S ENGIN		INC	
+ PL - PLASTIC		QUID LIMIT		WEIGHT			U	V	NO SENGIN	LERO,	INC.	



									Sne	<u>et 1 c</u>	Я 1	_
CLIENT The	HNTB Companies			LOG OF B	ORIN	ig nume	3ER	DES. NO	).			
PROJECT NAM	AE 61st Avenue Wid	ening & Impr	ovement		RB	-8		PROJEC	T NO.			
SITE LOCATIO	N 61st Avenue, Hol	bart, Indiana		STRUCTUR NUMBER	E	-	S		3+50, ine A	OF	- Set 1	0'Lt
BORING STARTED	1-18-06	RIG	Diedrich D-120	FILE N	UMBI	ER		CALIBRAT				
BORING COMPLETED	1-18-06	FOREMAN	Carlos Santana	79	998		0	UNCONFII TONS/FT <sup>2</sup>	NED CON	MPRESS	VE STRI	ENGTH,
E SUR	FACE ELEVATION ft	(m) USC & (	<u>3</u> S		SAM	PLE	0 1	1	2	3	4 : I	5 6 L1
(METERS) STRATA DEPTH (FEET) TEXTURAL CLASSIFICATION	DESCR Asphalt, 10 inches	RIPTION OF M		CEPTH (FEET) TYPE RECOVERY	NUMBER	DRY UNIT WEIGHT pcf (kg/m <sup>3</sup> )		BLOW CO	20 1 UNTS	30 4	L	
1.2 -1 -2 -3 11.0 +++ ++++ ++++ +++++ +++++ +++++++	stone, visual Brown, moist, stiff Lab No. 7998-1, A Gray-brown, moist, Lab No. 7998-2, A Brown, wet, loose,	to very stiff, -6 , medium st -6 Sand, Lab. DRING @ 2	Silty Clay LOAM, ff, Silty Clay, ▼ No. 7998-3, A-3		1 2 3 4 5 6 7 7	MARKS						
	LEVEL VHILE DRILLING		COMPLETION			## 11 XI XO						
SPLIT SPOO	—			1			D	K&\$	6 ENG	INEER	s, inc	<b>)</b> .

EXHIBIT 9

# TABLE 1. SUMMARY OF CLASSIFICATION TEST RESULTS

Lab. No.	Lab. No. Boring No.	Station	Offset	Depth	Classification	ion		% Passing	60	%	%	%	%			
	Sample No.									Gravel	Sand	Silt	Clay		Atterberg Limits	mits
	, ,			(Ft)			No. 10	No. 10 No. 40 No. 200	No. 200					TT	PL	Id
7998-1	RB-1; SS-2	48+75	10 ft Rt., Line A		3.5-5.0 Silty Clay Loam	A-6 (9)	81.7	79.3	73.0	18.3	8.7	50.1	22.8	31	15	16
7998-2	RB-1; SS-4	48+75	10 ft Rt., Line A		8.5-10.0 Silty Clay	A-6 (13)	96.3	93.4	90.2	3.7	6.1	57.9	32.3	32	16	16
7998-3	RB-1; SS-7	48+75	10 ft Rt., Line A	18.5-20.0	Sand	A-3 (0)	98.6	95.9	0.08	1.4	98.5	0	0.1	đX	đ	Êž
7998-4	RB-2; SS-1	49+40	10 ft Lt., Line A	1.0-2.5	Silty Clay Loam	A-6 (9)	99.5	98.8	97.2	0.5	2.3	71.3	25.9	26	15	11
7998-5	RB-5; SS-6	51+32	10 ft Rt., Line A	13.5-15.0	51+3210 ft Rt.,13.5-15.0Peat (Organic Silty Loam)Line AA	am) A-7-5 (19)	5.99	97.0	74.1	0.5	25.4	64.8	9.3	54	30	24

Lab No:		SUMN	1ARY	OF LAI	BOR	ATOR	Y TES	r resu	LTS
	Boring No. Sample No.	Depth (Ft)	NATURAL WATER CONTENT	Uncon Comp Strength ([sf)	pH	ORGANIC CONTENT (%)	UNIT DRY WEIGHT pcf		ROCTOR RESULTS
			(%)					Opt. Moisture	Max Dry Density
	RB-1								
7998-RB1S1	SS-1	1.0-2.5	12.5						
7998-1	SS-2	3.5-5.0	24.2						
7998-RB1S3	SS-3	6.0-7.5	23.3						
7998-2	SS-4	8.5-1.0	24.7						
7998-RB1S5	SS-5	11.0-12.5	25.2						
7998-RB1S6	SS-6	13.5-15.0	26.4						
	RB-2					<u> </u>	I <u> </u>	,	· · · · · · · · · · · · · · · · · · ·
7998-4	SS-1	1.0-2.5	19.7						
7998-RB2S2	SS-2	3.5-5.0	21.2				-		
7998-RB2S3	SS-3	6.0-7.5	26.4						·
7998-RB2S4	SS-4	8.5-10.0	23.7						
7998-RB2S5	SS-5	11.5-12.5	24.6						·····
7998-RB2S6	SS-6	13.5-15.0	26.3						
	RB-3		I						
7998-RB3S1	SS-1	1.0-2.5	5.8						III
7998-RB3S2	SS-2	3.5-5.0	23.2					 	
7998-RB3S3	SS-3	6.0-7.5	23.6						
7998-RB3S4	SS-4	8.5-10.0	24.7	~ *				`	
7998-RB3S5	SS-5	11.5-12.5	25.0					2 11	
	RB-4	<u> </u>	<u></u>				. <u>.</u>	A Allan	
7998-RB4S1		1.0-2.5	10.0					<u></u>	

# TABLE 2. SUMMARY OF LABORATORY TEST RESULTS

Table 2, Sheet 1

Lab No.		SUMN	<b>IARY</b>	OF LAI	BOR	ATOR	Y TES	T RESU	LTS
	Boring No. Sample No.	Depth (Ft)	NATURAL WATER CONTENT (%)	Uncon Comp Strength (tst)	pH	ORGANIC CONTENT (%)	UNIT DRY WEIGHT pef	STANDARD PI	ROCTOR RESULTS
7998-RB4S2	SS-2	3.5-5.0	18.7				, and the second second		
7998-RB4S3	SS-3	6.0-7.5	20.7			·			
7998-RB4S4	SS-4	8.5-10.0	19.2						
7998-RB4S5	SS-5	11.5-12.5	162.5			73.9	·		
7998-RB4S6	SS-6	13.5-15.0	33.1			3.4			
	RB-5		·	·	ı	<sub>.</sub>	<u> </u>	I	J
7998-RB5S2	SS-2	3.5-5.0	21.6				- ** <u>-</u>		
7998-RB5S3	SS-3	6.0-7.5	20.4						
7998-RB5S4	SS-4	8.5-10.0	21.3			· · ·			
7998-RB5S5	SS-5	11.5-12.5	26.0						
7998-5	SS-6	13.5-15.0	42.5			9.6			
7998-RB5S7	SS-7	18.5-20.0	35.5			3.0		-	
	RB-6	······································			<u> </u>				
7998-RB6S1	SS-1	1.0-2.5	20.7						· · · · · · · · · · · · · · · · · · ·
7998-RB6S2	SS-2	3.5-5.0	16.6						
7998-RB6S3	SS-3	6.0-7.5	26.6						
7998-RB6S4	SS-4	8.5-10.0	26.3						
7998-RB6S5	SS-5	11.5-12.5	24.7			- <u></u>			
7998-RB6S6	SS-6	13.5-15.0	27.0						
	RB-7		······································		4				
7998-RB7S2	SS-2	3.5-5.0	19.4						
7998-RB7S3	SS-3	6.0-7.5	12.5						·
7998-RB7S4	SS-4	8.5-10.0	22.9			· · · · · · · · · · · · · · · · · · ·	Nertes I I I Na a s		
7998-RB7S5	SS-5	11.5-12.5	26.1						

Lab No		SUMN	1ARY	OF LAH	BOR	ATOR	Y TEST	r resui	TS
<ul> <li>Marine and States an</li></ul>	Boring No. Sample No.	Depth (Ft)	NATURAL WATER	Uncon Comp Strength	pH	ORGANIC CONTENT	UNIT DRY WEIGHT	STANDARD PR	OCTOR RESULTS.
			CONTENT (%)	(121) (121)		(%)	pcf	Opt: Moisture	Max Dry Density
7998-RB7S6	SS-6	13.5-15.0	29.3						
	RB-8						<u></u>		
7998-RB8S1	SS-1	1.0-2.5	19.6						
7998-RB8S2	SS-2	3.5-5.0	23.0						
7998-RB8S3	SS-3	6.0-7.5	23.7						
7998-RB8S4	SS-4	8.5-10.0	23.0						
7998-RB8S5	SS-5	11.5-12.5	23.9						
7998-RB8S6	SS-6	13.5-15.0	26.3						


and a second second


· · ·

Please see grain-size distribution curves


×


Table 2, Sheet 3





(		U.:	s. SI	EVE C 6	PE 4	Ni 3							23	] 8/8	3	4		6									ER 5		<sub>70</sub> 1	00	14(	02	 .00				ŀ	IYC	R	DM	ET	ER					
10	00								1		l				+			╊╎	-1			•				ļ			ł	Г														····			
g	90																										$\left  \right $																_				
8	30-												_															•														-	-				
P E_													-		_																																
PER7 CEN	0						-				-		+																																		
T6 F	0																									:			-													-					
N E5 R	i0-															+			<b></b>															_													
в Ү4	0						~																																								
W E G 3 H	╞																			******																											
Т	0-																										-	•																			
																											-																				
1	0																																														
	oL		[	1	00	) )							10	)		1				<u>}</u>		1		1		:					<u> </u>	] 1						0.0	)   D1							0.0	)0 <sup>.</sup>
	٢					T							1.07				GR	All	NE		EI	NF	VIIL				R8 D	<u> </u>																			I
				BLES					1		G	- A	.VE		•							:02						f	ine	2							S									AY	
s •		cim RB-		ldent		at 20.		1								(					atio 3 (0										N	1C	%	+			Pl			P			C		+	Cu	
			- 1																	<b>-</b>		<u>"</u>													NP		NI			NF			0.8	<b>39</b>		1.7	
																																					·						<u> </u>				
S				ldenti							)1C					D						03						910			%			vel			San	d		%	6Si				%C	lay	!
•	F	RB-	1		2	20.	0			1	2.7	0				0.2	28				0	.20	)3			(	).1	62	25			1	1.4			9	8.5					<u> </u>	0.	1			
			* •																	·										~ 7																	
F	PR	DJE	CT		: A\	/ei	nue	· V	Vid		ng	& I	mp	ого	ove	em	en	t -	61	st	A١	/er	านอ	<del>)</del> ,						 NC I. N								JC D/			Э.		'99 '/25	8			
																G	iF	٢A		) <b>/</b>	\T	10	DÌ	N	С	:	JF	٢V	Έ	S	_		(		Ð		ĸ٤	& S	Ε	N	GII	NE	E	RS	, IN	۱C.	





Ms	ijor Divk	slons	Group symbol			Laboratory classification	ı criteria
 ,	5	avels 0 fines)	GW	Well-grades gravels, gravel-sand mixtures, little or no fines	raincd	$C_{ij} = \frac{D_{ik}}{D_{ij}}$ greater than 6: 0	$C_{\rm c} = \frac{(D_{11})^1}{D_{10} \times D_{14}}$ between 1 and 3
ize)	is coarse fracti 4 sieve size)	Clean gravels (Little of no fines)	GP	Poorly graded gravels, gravel- sand mixtures, little or no fines	ce). coarse-grained P C requiring dual	Not meeting all gradation re	quirements for GW
. 200 sieve si	Gravels (More than half of coarse fraction larger than No. 4 sieve size)	h fines amount s) .	GM d	Silty gravels, gravel-sand-silt mixtures	In No. 200 sieve size), coarse-grain In No. 200 sieve size), coarse-grain GW, GP, SW, SP GM, GC, SM, SC Borderline cases requiring dual wmbols	Atterberg limits below "A" line or P.I. less than 4	Above "A" line with P.I. between 4 and 7 are bor-
(More than half of matcrial is <i>larger</i> than No. 200 sieve size)	(More t large	Gravels with fincs (Appreciable amount of fines)	൳	Claycy gravels, gravel-sand-clay mixtures	Determine percentages of sand and gravel from grain-size curve. Depending on percentages of fines (fraction smaller than No. 200 sieve size), soils are classified as follows: Less than 5 per cent	Atterberg limits above "A" fine with P.1, greater than 7	derline cases requiring use of dual symbols
material is <i>la</i>	tion ce)	ands 10 (inc.)	sw	Well-graded sands, gravely sands, little or no fines	l gravel from (Fraction sma	$C_{ij} = \frac{D_{ij}}{D_{ij}}$ greater than 4; $C_{ij}$	$= \frac{(D_{\rm ta})^2}{D_{\rm te} x D_{\rm te}}$ between 1 and 3
than half of	Sands (More than half of coarse fraction is smaller than No. 4 sieve size)	Clean sands (Little or no fines)	SP	Poorly graded sands, gravelly sands, little or no fines	of sand and age of fines ( ollows: t	Not meeting all gradation re	equirements for SW
(Mare	Sands e than half of c naller than No.	Sands with fines (Appreciable amount of fines)	SM d u	Silty sunds, sand-silt mixtures	termine percentages of pending on percentages is are classified as folio Less than 5 per cent More than 12 per cent 5 to 12 per cent	Atterberg limits below "A" line or P.I. less than 4	Limits plotting in hatched zone with P.I. between 4 and 7 are <i>borderline</i> cases
	(More is si	Sands with fines (Appreciable amou of fines)	SC	Clayey sands, sand-clay mix- tures	Determin Dependin Soils are o Less th More 5 to 12	Atterberg limits above "A" line with P.I. greater than 7	requiring use of dual synt- bols
	<b>-</b>	2	· мі.	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity	soils and	sification of fine-grained	
vc)	Silts and clays	(Liquid limit less than 50)	cı.	Inorganic clays of low to me- dium plasticity, gravelly clays, sandy clays, silty clays, lean clays	40 intelect	rg Limits plotting in	
n No. 200 sie	Silts	(Liquid lim	OL	Organic silts and organic silty clays of low plasticity	20 Equation PT = 0. Equation PT = 0. PT = 0.	of A-line: 73 (I.I 20)	
s smaller tha		en 50)	мн	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, clastic silts		· · · · · · · · · · · · · · · · · · ·	- Olf and MII
intoit that of matchal is smaller than No. 200 sicve)	Silts and clays	(Luquid limit greater than 50)		inorganic clays of high plas- licity, fat clays	10 7 4	MI, and OL.	
		רומחום וונ	OH H	Organic clays of medium to ligh plasticity, organic silts	0 10 21	0 30 <u>40</u> 50 60	70 80 90 100
	Highly organic	3105		eat and other highly organic oils	· · · · · ·	Liquid Limit Plasticity Chart	

K & S TESTING AND ENGINEERING, INC. 9715 Kennedy Avenue Highland, IN Phone: (219) 924-5231

# GENERAL QUALIFICATIONS

This report has been prepared in order to aid in the evaluation of this property and to assist the architect and/or engineer in the design of this project. The scope is limited to the specific project and location described herein. In the event that any changes in the design or location of the building as outlined in this report are planned, we should be informed so that changes can be reviewed and the conclusions of this report modified as necessary. We recommend that we be authorized to review the project plans and specifications within our scope of work to confirm that the recommendations contained in this report have been interpreted in accordance with our intent. Without this review, we will not be responsible for misinterpretation of our data, our analysis, and/or our recommendations, nor how these are incorporated into the final design.

The analysis and recommendations submitted in this report are based upon the data obtained from the soil borings performed at the locations indicated on the location diagram and from any other information discussed in this report. This report does not reflect any variations which may occur between these borings. In the performance of subsurface explorations, specific information is obtained at specific locations at specific times. However, it is a well-known fact that variations in soil and rock conditions exist on most sites between boring locations and also such situations as groundwater levels vary from time to time. The nature and extent of variations may not become evident until the course of construction. If variations then appear evident, it will be necessary for a re-evaluation of the recommendations of this report after performing on-site observations during construction period and noting the characteristics of any variations. 9715 Kennedy Ave. Highland, Indiana Phone: (219) 924-5231

K & S Testing and Engineering Inc.

GENERAL NOTES

IN ORDER TO PROVIDE UNIFORMITY THROUGHOUT OUR PROJECTS, THE FOLLOWING SYSTEM HAS BEEN ADOPTED TO DESCRIBE EACH SOIL SAMPLE. ROCK, SHALE AND OTHER MATERIALS WILL BE DESCRIBED IN DETAIL AS ENCOUNTERED.

CONSISTENCY OF CO	HESIVE SOILS	RELATIVE DENS	SITY OF GRANULAR SOILS
UNCONFINED COMPRESSIV STRENGTH, Qu, TSF	E CONSISTENCY	"N" VALUE *	RELATIVE DENSITY
< 0.25	VERY SOFT	0 - 3	VERY LOOSE
0.25 - 0.49	SOFT	4 - 9	LOOSE
0.50 - 0.99	MEDIUM	10 - 29	MEDIUM
1.00 - 1.99	STIFF	30 - 49	DENSE
2.00 - 3.99	VERY STIFF	50 - >	VERY DENSE
4.00 - `>	HARD		
		l .	

ローン 第117 JMBER OF BLOWS PER FODT REQUIRED TO DRIVE A 2" O.D. SPLIT-SPOON SAMPLER USING A 140 LB, WEIGHT FALLING FREE FOR 30",

- COLOR - AS DETERMINED ON THE FRESH MOIST SAMPL	ETERMINED ON THE FRESH MOIST SAMPL	FRESH MOIST	FRESH	THE	TERMINED ON	AS I	<u>COLOR -</u>
--	------------------------------------	-------------	-------	-----	-------------	------	----------------

PREDOMIN	ATE COLORS	SHADES	MODIFYING ADJECTIVES
BLACK	YELLOW	LIGHT	VARI-COLORED
BROWN	RED .	DARK	STREAKED
GRAY	BLUE		MOTTLED

### SOIL IDENTIFICATION TERMINOLOGY

	GRANULAR SOILS	COHESIVE SOILS	
COMPONENTS	SIZE RANGE	DESCRIPTIVE TERM	PLASTICITY
BOULDERS	OVER B INCHES	CLAY OR ORGANIC CLAY	30
COBBLES	8 INCHES TO 3 INCHES	SILTY CLAY OR ORGANIC SILTY CLAY	8-30
GRAVEL	3 IN. TO <sup>#</sup> 4 SIEVE (4.75 mm)	INTERNEDIATE SOILS	·
SAND	$^{\#}4$ sieve to $^{\#}200$ sieve (0.075 mm)	CLAYEY SILT	4 - 7
SILT	PASSING #200 SIEVE (0.075mm)	SILT	0 - 3

ESTIMATED				

1 - 10
10 - 20
20 - 35
35 - 50