

| Pavement Treatment → | Prvnt. Maint. | Func- tional | Struc- tural |
|---|------------------|-----------------|-----------------|
| <i>Culverts,</i> | | | |
| Extend | B | B | A |
| Modify | B | B | A |
| Place New | C | C | C |
| Repair and Clean | B | B | A |
| Replace | B | B | A |
| Headwalls, Remove | C | B | A |
| <i>Eroded Areas,</i> Grade and Seed or Sod | B | B | A |
| <i>Guardrail End Treatments,</i> | | | |
| Repair Damaged | A | A | A |
| Replace product not on appvd. list with appvd. prod. | B | B | B |
| Replace type I with type MS or OS as req'd. | B | A | A |
| <i>Highway Signs,</i> Replace | C | C | B |
| <i>Impact Attenuators,</i> | | | |
| Repair Damaged | A | A | A |
| Replace product not on appvd. list with appvd. prod. | B | B | B |
| <i>Linear Grading</i> | C | C | B |
| <i>Mailboxes,</i> Replace with Current Standard | C | B | B |
| <i>Obstruction-Free Zone Clearance,</i> Remove Fixed Objects > 4 in. Above Grd. ³ | C | B | B |
| <i>Pavement Markings and Delineation,</i> | | | |
| Pavement Markings, Place | A | A | A |
| Roadside Delineators, Place or Replace | B | B | B |
| Raised Pavement Markers, Place | C | B | B |
| Raised Pavement Markers, Replace | B | B | B |
| <i>Side Ditches,</i> Reshape or Riprap | B | B | B |

Key to work incidental to paving is shown at the end of the table.

PARTIAL 3R WORK
Roadside, Culverts, and Traffic Considerations

Figure 56-4F

| Pavement Treatment → | Prvnt. Maint. | Func- tional | Struc- tural |
|--|------------------|-----------------|-----------------|
| <i>Side Slopes,</i> Flatten to Traversable Levels | C | C | B |
| <i>Sidewalks,</i> Repair or Replace | C | C | C |
| <i>Sidewalk Curb Ramps at Intersections,</i> Repair existing | B | A | A |
| Upgrade existing to ADA requirements | A | A | A |
| Place in exist. sdwks. per ADA requirements | A | A | A |
| <i>Traffic Barriers,</i> Bridge Railing, Upgrade to Current Standards | C | C | C |
| Guardrail, Repair or Replace Damaged | A | A | A |
| Guardrail, Replace Obsolete ¹ or Weathered | C | B | B |
| Guardrail, Place or Lengthen to Current Standards ² | C | B | B |
| Guardrail to Bridge Railing, Connect | C | A | A |
| Guardrail Transition, Upgrade to Current Standards | C | C | C |
| <i>Traffic Signals,</i> Add or Upgrade | C | C | B |
| Detector Loops or Handholes, Perpetuate | A | A | A |

Key to work incidental to paving:

A = Item should be included as part of the project.

B = Item may be included.

C = Item should not be included. If it is considered, it should be programmed separately as a spot improvement.

Notes:

¹ Obsolete guardrail should be treated as shown in Section 49-4.02.

² Treat as described in Section 55-5.04.

³ For example, trees, bushes, posts, rocks, private signs, etc. See Section 55-5.02 for obstruction-free-zone information.

PARTIAL 3R WORK Roadside, Culverts, and Traffic Considerations

Figure 56-4F (Continued)