

STATEMENTS ABOUT EXISTING CONDITIONS OF UTILITIES,
ADDITIONAL RIGHT-OF-WAY, AND ENCROACHMENTS

The Standard Specifications are revised as follows:

SECTION 107, AFTER LINE 597, INSERT AS FOLLOWS:

107.25 Existing Conditions of Utilities, Additional Right-of-Way, and Encroachments.
Such existing conditions are as described below.

(a) Utilities. *The status of all utility companies and organizations potentially involved with the work to be performed are described below.*

The facilities of Spartan Water Co. exist within the project limits, but are not expected to be affected by the proposed construction. The utility has a 150-mm water-line crossing under SR 1001 at Station 2+000. If questions arise, Dan Tanna of the utility company shall be contacted at 800-555-1111.

The facilities of Hawkeye Pipeline Co. exist within the project limits. Their facilities have been adjusted to accommodate construction. The utility has a 300-mm product pipeline crossing SR 1001 at Station 3+000 which has been lowered in place to eliminate any conflict with the construction of the underdrains. If questions arise, Thurston Howell III of the utility company shall be contacted at 800-555-2222.

The facilities of Golden Gopher Sewer Co. exist within the project limits. The utility has a 300-mm sewer main running parallel to SR 1001 on the east side of the road for the entire length of the project. This sewer main will be relocated to within 2 m of the new east right-of-way line for the entire length of the project. It is anticipated that the utility company will adjust its facilities for construction on or before March 31, 2008. This date is dependent on the utility receiving its environmental permit prior to March 1, 2008. If questions arise, Jamie Sommers of the utility company shall be contacted at 800-555-3333.

The facilities of Boilermaker Electric Co. exist within the project limits. The utility company has power poles along the existing east right-of-way line for the entire length of the project. The utility company will relocate its facilities to the new east right-of-way line for the entire length of the project except from Station 4+500 to Station 5+000 where the poles will remain in place. The utility company will support such poles when the Contractor places the storm sewer in this area. It is anticipated that the utility company will take approximately 20 work days to adjust its facilities once the Contractor has staked and cleared the right of way along the east side of SR 1001. If questions arise, Norm Petersen of the utility company shall be contacted at 800-555-4444.

107-R-169

1 of 2

SAMPLE UTILITIES SPECIAL PROVISION**Figure 10-2A**

The facilities of Nittany Lion Gas Co. exist within the project limits. The utility has a 400-mm gas line outside of the existing right of way on the south side of SR 1001 for the entire length of the project. The gas line will be relocated as follows:

- *From Station 1+000 to Station 3+000, the line will remain in place.*
- *From Station 3+000 to Station 4+000, the line will be relocated to within 1 m of the new west right-of-way line.*
- *From Station 4+000 to Station 5+000, the line will remain in place. In the areas where drainage structures shall be placed, the utility company will locate and expose its main. The gas main shall not be disturbed during the placement of these structures.*

Once the contractor has staked and cleared the right-of-way between Station 1+000 and Station 5+000 along the south side of SR 1001 and placed Structure No. 10, the utility company will take approximately 30 work days to adjust its facilities. This line cannot be worked on until after May 1 and anytime the temperature is below freezing. The utility company's schedule is also dependent on the availability of 400-mm steel gas line. Supply of this is scarce and may not be able to be delivered to the site until May 15. If questions arise, Mary Richards of WJM Contract Services shall be contacted at 800-555-5555.

The facilities of Bearcat Communications exist within the project limits. The utility company has two fiber optic cables on poles owned by Boilermaker Electric Co. The utility company will be relocating its facilities on the new power poles to be placed by Boilermaker Electric Co. The utility company cannot begin its relocation until Boilermaker Electric Co. has completed the majority of its work. It is anticipated that the utility company will take approximately 10 work days to complete its relocation. Once the utility company completes such, it will work with Boilermaker Electric Co. to remove the existing poles. This will take approximately an additional 3 work days. If questions arise, Herb Tarlick of the utility company shall be contacted at 800-555-6666.

=====

SAMPLE UTILITIES SPECIAL PROVISION

Figure 10-2A (Continued)