

- (X1) Construction Sign, Type B
- (X2) Construction Sign, Type _____
- (Y) Barricade, Type _____
- (Y1) Barricade, Type _____
- (1) 33 in. Concrete Barrier
- (2) 45 in. Concrete Barrier
- (2A) Modified Concrete Barrier
- (3) Longitudinal Joint
- (5) Butt Joint
- (6) Construction Joint
- (7) Keyway Joint
- (8) 1 in. Expansion Joint with Load Transfer
- (9) (width) in. Preformed Joint Filler
- (12) Impact Attenuator, Type _____
- (13) Concrete Curb
- (14) Integral Concrete Curb
- (15) Concrete Curb and Gutter
- (16) Concrete Curb Type B
- (18) Integral Concrete Curb and Gutter, Type _____
- (20) Contraction Joint, Type _____
- (21) Longitudinal Construction Joint
- (22) Concrete Center Curb, Type _____
- (23) Asphalt Curb
- (24) Ear Construction, Type A
- (25) Ear Construction, Type B
- (26) Sodding

- (27) Cement Concrete Header, Type _____
- (28) Retrofitted Tie Bar
- (31) Temporary Concrete Barrier
- (32) Impact Attenuator, CZ, Type _____
- (33) Snowplowable Raised Pavement Marker
- (34) (width) in. Solid White Paint Line
- (35) (width) in. Solid Yellow Paint Line
-  Concrete Curb Ramp
(Type is indicated by letter inside hexagon)
- (36) (message) Preformed Plastic Pavement Message Marking
- (37) (message) Thermoplastic Pavement Message Marking
- (38) (width) in. (type) (color) Thermoplastic Transverse Marking
- (39) (width) in. (type) (color) Preformed Plastic Transverse Marking
- (40) (width) in. Solid White Preformed Plastic Line
- (41) (width) in. Solid Yellow Preformed Plastic Line
- (42) (width) in. Broken White Preformed Plastic Line
- (43) (width) in. Broken Yellow Preformed Plastic Line
- (44) 24 in. Solid White Preformed Plastic Line
- (45) 24 in. White Stop Line, Preformed Plastic
- (46) (width) in. Solid White Thermoplastic Line
- (47) (width) in. Solid Yellow Thermoplastic Line
- (48) (width) in. Broken White Thermoplastic Line
- (49) (width) in. Broken Yellow Thermoplastic Line
- (50) No Change Required to Existing Sign and Supports
- (51) Remove Existing Panel Sign from Ground Mounted Supports
- (52) Remove Existing Sheet Sign from Supports
- (53) Remove Existing Panel Sign from Overhead Sign Structure

- (54) Remove Existing Sheet Sign from Overhead Sign Structure
- (55) Remove Existing Sign Foundation
- (56) Remove Existing Sheet Sign and Supports
- (57) Remove Existing Ground Mounted Panel Sign, Supports and Foundations
- (58) Remove Existing Overhead Sign, Supports and Foundations
- (59) Existing Sheet Sign on New Supports
- (60) Existing Panel Sign on New Supports
- (61) Existing Panel Sign on New Overhead Structure

RECOMMENDED PLANS LEGENDS

Figure 14-3A