

- 1 The extrusion and plate assemblies with anchors shall be miter cut and shop spliced at this location. A miter cut, vulcanized shop spliced will be required in the strip seal at the location.
- 2 The extrusion and plate assemblies with anchors shall be shop prepared for field welding at this location. A miter cut, vulcanized shop splice will be required in the strip seal at this location.

All dimensions are in mm unless otherwise specified.

INDIANA DEPARTMENT OF TRANSPORTATION

EXPANSION JOINTS CLASS SS

SEPTEMBER 1994

STANDARD DRAWING NO. 724-BSSJ-07



/s/Anthony L. Uremovich 9/30/94

/s/Donald W. Lucas 9/30/94

Source Sheet:

SS-2

SIGN STANDARDS ENGINEE

CHIEF HIGHWAY ENGINEER