



INDIANA DEPARTMENT OF TRANSPORTATION

Driving Indiana's Economic Growth

Design Memorandum No. 08-12 Technical Advisory

May 29, 2008

TO: All Design, Operations, and District Personnel, and Consultants

FROM: /s/ Anthony L. Uremovich
Anthony L. Uremovich
Design Resources Engineer
Production Management Division

SUBJECT: Stable Construction Entrances

REVISES: *Indiana Design Manual Section 37-2.0*

EFFECTIVE: September 4, 2008, Letting

Most construction projects will require the contractor to have temporary entrance points from off-road locations on to public roads. Recurring Special Provision 108-C-192 requires the contractor to install stable construction entrances at these points in order to control movement of sediment off the project site by construction traffic. This special provision is required in each contract except for a mowing or herbicide contract. If the special provision is required, the designer should include an undistributed quantity of 100 tons (100 Mg) of No. 2 stone in the preliminary estimate of quantities and cost estimate. This minimum quantity should be sufficient to provide two stable construction entrances. If the designer anticipates that additional entrances will be required, the quantity should be adjusted accordingly. The locations of such entrances should not be shown on the plans.

Recurring Special Provision 108-C-192 is attached herewith.

alu