

BASIS FOR USE
OF RECURRING SPECIAL PROVISIONS
AND RECURRING PLAN DETAILS

CODE Date	Description BASIS FOR USE
100-C-146 R 3-07-00	Payment of Predetermined Minimum Wage (Davis-Bacon) IN010001 ALL PROJECTS IN LAKE, LAPORTE, PORTER, AND ST. JOSEPH COUNTIES EXCEPT BUILDING CONSTRUCTION.
100-C-147 R 3-07-00	Payment of Predetermined Minimum Wage (Davis-Bacon) IN010006 ALL PROJECTS IN COUNTIES OTHER THAN LAKE, LAPORTE, PORTER, AND ST. JOSEPH EXCEPT BUILDING CONSTRUCTION.
100-C-148 A 6-06-97	Payment of Predetermined Minimum Wage (Davis-Bacon) _____ ALL BUILDING CONSTRUCTION - DETERMINED BY CENTRAL OFFICE PERSONNEL
100-C-151 R11-01-99	Federally Funded Contract with DBE AS DETERMINED BY CONTRACTS SECTION
100-C-152 R 1-04-99	Federally Funded Contract without DBE AS DETERMINED BY CONTRACTS SECTION
100-C-166 A 2-19-01	As Built Plans ALL CONTRACTS WITH PERMANENT TRAFFIC SIGNAL INSTALLATIONS
101-B-042 R 9-1-93	Structure Numbers for Pay Items MORE THAN ONE BRIDGE FILE NUMBER IN CONTRACT, AND LUMP SUM PAY ITEMS SHOWN TO BE REQUIRED FOR EACH SUCH BRIDGE FILE
102-C-082 R 1-04-99	Schedule of Pay Items for Alternate Bids PAY ITEMS IN CONTRACT WHICH REQUIRE ALTERNATE BIDS
102-C-145 R 1-04-99	Toll Road Special Provisions ALL TOLL ROAD CONTRACTS
102-C-170 A 1-16-02	Prequalification BUILDING CONSTRUCTION
103-C-036 R 9-22-99	Owners' and Contractors' Protective Liability Insurance Coverage for Operations of the Designated Contractor ALL FEDERAL AID LOCAL PUBLIC AGENCY CONTRACTS
103-C-159 A 9-13-99	Wage Stipulations 100% STATE FUNDED CONTRACTS
104-C-112 R 6-06-03	Traffic Control Changes and On-Call Maintenance of Traffic Control Devices TRAFFIC BEING MAINTAINED ON PRESENT ROADWAY WITH NO WATCHMAN REQUIRED
104-C-139 A 9-19-95	Geotechnical Evaluation Report GEOTECHNICAL REPORT HAS BEEN DEVELOPED AND APPROVED

104-R-168 R 6-06-03	Schedule of Operations and Traffic Control for Undersealing, Concrete Patching, Placing Underdrains, and Resurfacing PAVEMENT UNDERSEALING, PATCHING, SHOULDER DRAIN PLACEMENT, AND RESURFACING SPECIFIED
105-C-056 R 4-25-03	Engineer Application Personal Computer ALL CONTRACTS WITH FIELD OFFICE
105-C-071b R 5-01-03	Fax Machine in Field Office (Advanced Features) AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
105-C-176 A 5-22-03	Field Office Windows PAY ITEM: FIELD OFFICE
105-R-305 R 1-04-99	Pipe Structure Pay Items ALL CONTRACTS WITH PIPE STRUCTURE PAY ITEMS
106-C-074 R 1-04-99	Basis for Use of Approved or Prequalified Materials ALL CONTRACTS
107-B-040 R 1-04-99	Environmental Restrictions AS DETERMINED BY PROJECT DESIGNER
107-C-029 R 7-14-98	Equal Employment Opportunity Trainees AS DETERMINED BY CONTRACT SERVICES
107-C-051 R10-17-00	Environmental Permits AS DETERMINED BY PROJECT DESIGNER
107-C-169 A12-13-01	Traffic Control Device Report ALL CONTRACTS
107-C-169d A12-13-01	Traffic Control Device Report Form ALL CONTRACTS
107-R-042a R 1-04-99	Railroad Information HIGHWAY OVER OR UNDER RAILWAY
107-R-042b R10-08-96	Protection of Railway Interest AS DETERMINED BY UTILITIES SECTION
107-R-169 R 1-04-99	Statements About Existing Conditions of Utilities, Additional Right-of-Way, and Encroachments ALL CONTRACTS
108-C-043 R12-05-01	Incentive or Disincentive for Opening Project to Traffic Ahead of Schedule AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-078 R10-25-99	Partnering Overhead AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
108-C-089 R 1-04-99	Percentage of Work Required of Prime Contractor AS DETERMINED BY CONTRACT SERVICES PERSONNEL WHO WILL PROCESS CONTRACTS SHORTLY BEFORE LETTING
108-C-090 R 1-04-00	Latest Date to Begin Work DELAYED START OF WORK DESIRED

108-C-091 R 1-04-99	Failure to Complete on Time for Restriction-One Structure LANE RESTRICTIONS ON ONE LANE, PHASE, OR DIRECTION
108-C-092 R 1-04-99	Failure to Complete on Time for Restriction-Two or More Structures LANE RESTRICTIONS ON MORE THAN ONE STRUCTURE, PHASE, OR DIRECTION
108-C-093 R 1-04-99	Failure to Complete on Time for Road Closure AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT WHICH INCLUDES DETOUR
108-C-094 R 1-04-99	Failure to Complete on Time for Intermediate Completion Date AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT IN WHICH A CERTAIN PORTION OF THE WORK IS TO BE COMPLETED BEFORE THE ENTIRE CONTRACT IS
108-C-095 R 6-06-03	Failure to Complete on Time for Calendar Completion Date AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-096 R 6-06-03	Failure to Complete on Time for Work Days AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-127 R 1-04-00	Earliest Date To Begin Work AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
108-L-001 R 1-04-99	Notice to Proceed With Demolition Work PAY ITEMS: 202-03000 HOUSES AND BUILDINGS PARCEL NO. _____ REMOVE
108-L-012 A 12-1-93	Specialty Pay Items PAY ITEM: 202-01261 TESTING FOR ASBESTOS REMOVAL
108-R-148 R 1-04-99	Construction Equipment in Park Areas PARK CONTRACT
109-B-148 A 3-21-01	Cost Reduction Incentive ALL PROJECTS WITH A BRIDGE
112-C-122 R 1-04-99	State Funded Contract with Davis-Bacon Wage Rates AS DETERMINED BY CONTRACTS SECTION
200-R-401 R 5-29-03	Recyclable Spent Foundry Sand Application PAY ITEMS OF BORROW OR B BORROW (REQUIRES 200-R-402 ALSO)
200-R-402 A 4-03-01	INDOT Microtox™ Test Method & Acceptance TO BE USED IN CONJUNCTION WITH 200-R-401 ONLY
201-C-052 R 1-04-99	Clearing Right-of-Way PAY ITEMS FOR CLEARING RIGHT-OF-WAY
201-M-030 R 1-04-99	Debris Removal at Bridge Structures DEBRIS REMOVAL MAINTENANCE CONTRACT
201-R-021 R 2-21-90	Burning of Natural Growth Permitted IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING OF NATURAL GROWTH

201-R-179 R 2-21-90	Air-Curtained Open-Pit Incineration of Natural Growth Required IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING BY MEANS OF AIR-CURTAINED OPEN-PIT INCINERATOR
202-C-175 A 5-20-03	Demolition/Renovation Notification To IDEM ALL CONTRACTS EXCEPT MOWING, HERBICIDE, T CONTRACTS, LIGHTING, SIGNING, STRIPING, AND BRIDGE PAINTING
202-L-013 A 6-06-03	Inspection and Testing for Asbestos Material AS DETERMINED BY PRE-ENGINEERING AND ENVIRONMENT
203-B-025 R 1-04-99	Marion County Borrow Pits PROJECT LIMITS IN MARION COUNTY, PAY ITEM: 203-02070
203-R-121 R 1-04-99	Borrow Pit Wetland Enhancement BORROW PIT EXCAVATION EXPECTED TO REACH WATER TABLE
203-R-155 R 5-22-02	Rock Backfill PAY ITEM: 202-92634 ROCK BACKFILL
203-R-260 R 1-04-99	Linear Grading PAY ITEM: 203-90014 OR 203-02080 LINEAR GRADING. EARTH WEDGING AT OUTSIDE EDGE OF SHOULDER OR BEHIND GUARDRAIL, OR MEDIAN EARTH FILLING
203-R-360 A 4-08-98	Embankments Constructed of Coal Combustion By-Products PAY ITEM OF 3800 CUBIC METERS (5000 CYS) OR MORE OF BORROW
204-R-049 R 1-04-99	Piezometers PAY ITEM: 204-02295 PIEZOMETER
206-B-026 R 1-04-99	Steel Sheet Piling at Railroad Grade Separation STEEL SHEET PILING REQUIRED, RAILWAY WITHIN PROJECT LIMITS
206-B-113 R 6-06-03	General Bridge Requirements BRIDGE REPLACEMENT OR NEW BRIDGE CONSTRUCTION
207-R-430 R 6-06-03	Recycling Existing Concrete Pavement WHEN DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
208-R-111 R 1-04-99	Gore Area Treatment PAY ITEM: 203-02046 GRADING OF GORE AREA
211-R-415 A 2-12-02	Crushed Glass as Bedding Material AS DETERMINED BY MATERIALS AND TESTS DIVISION
213-R-446 A 3-13-03	Flowable Backfill PAY ITEM: FLOWABLE MORTAR OR FLOWABLE BACKFILL
305-R-431 R 5-22-02	Cement Concrete Pavement Cracking and Seating PAY ITEM: CONCRETE PAVEMENT CRACKING AND SEATING
400-R-448d A 3-14-03	Termination of Mainline Pavement Treatment AS DETERMINED BY PROJECT DESIGNER
400-R-449d A 3-14-03	Pavement Wedge Limits AS DETERMINED BY PROJECT DESIGNER

400-R-450d A 3-14-03	Public Road Approach Paving AS DETERMINED BY PROJECT DESIGNER
400-R-451 A 6-16-03	Revisions for HMA 2004 HMA PAY ITEMS
410-R-432 R 5-22-02	Warranted Micro-Surfacing PAY ITEM OF MICRO-SURFACING
500-R-452 A 5-22-03	Revisions for PCCP 2004 PCCP PAY ITEMS
601-R-016 R10-03-01	Construction Zone Energy Absorbing Terminal, CZ PAY ITEM: ENERGY ABSORBING TERMINAL, CZ
601-R-146 R 1-04-99	Removal of Guardrail REMOVED GUARDRAIL TO BECOME PROPERTY OF DEPARTMENT
601-R-237 R 1-04-99	Spare Parts Package for Guardrail End Treatment AS DETERMINED BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
601-R-338 R 4-16-03	Guardrail Blockouts PAY ITEM FOR GUARDRAIL
602-R-388d A11-16-00	Concrete Barrier AS DETERMINED BY DESIGN DIVISION
603-R-109 R 9-1-95	Gate Barricade PAY ITEM: GATE BARRICADE
603-R-414 R 12-1-02	Vinyl Coated Chain Link Fence PAY ITEM: VINYL COATED CHAIN LINK FENCE
603-R-447 A 3-13-03	Fences PAY ITEM FENCE OR FENCE GATE
605-R-453 A 5-22-03	Curbing PAY ITEM: CURB
609-R-443 A 5-22-03	Reinforced Concrete Bridge Approaches PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH
609-BRJT-01 A 2-13-03	Type 1-A Joint PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH
609-RCBA-01 A 2-13-03	Reinforced Concrete Bridge Approach for Use With Asphalt Pavement PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH WHEN MAINLINE IS HMA
609-RCBA-02 A 2-13-03	Reinforced Concrete Bridge Approach & Terminal Joint For PCCP PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH WHEN MAINLINE IS PCCP
609-RCBA-03 A 2-13-03	Reinforced Concrete Bridge Approach PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH
609-RCBA-04 A 2-13-03	Reinforced Concrete Bridge Approach PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH
609-RCBA-05 A 2-13-03	Reinforced Concrete Bridge Approach PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH

609-RCBA-06 A 2-13-03	Reinforced Concrete Bridge Approach PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH
609-RCBA-07 A 2-13-03	Pavement Ledge Details PAY ITEM: REINFORCED CONCRETE BRIDGE APPROACH
610-M-008d R 3-1-85	Typical Approach Details DRAWING FOR RESURFACE CONTRACT WHICH INCLUDES DRIVE APPROACHES
610-R-100 R 6-06-03	Median Crossovers MEDIAN CROSSEOVERS REQUIRED AS SHOWN ON PLANS
610-R-444 A 3-13-03	Approaches and Crossovers ALL ROAD, BRIDGE, AND TRAFFIC CONTRACTS
611-R-445 A 3-13-03	Mailbox Installation PAY ITEM: MAILBOX ASSEMBLY
615-R-020 R 1-04-99	Wood Post Parking Barriers PAY ITEM: PARKING BARRIER WOOD POST
616-R-102 R 9-1-95	Gabion Revet Mattress PAY ITEM: 616-02305 GABIONS
621-R-398 3-21-01	Capping Cut and Fill Slopes Steeper Than 3:1 AS DETERMINED BY PROJECT ENGINEER
622-R-209 A 5-13-91	Wildlife Habitat Species and Spacing PAY ITEM: 621-91786 SEEDLING; SPECIES AND SPACING NOT SHOWN ON PLANS
623-M-025 R 3-01-02	Roadside Mowing MAINTENANCE CONTRACT FOR MOWING
623-M-039 R 6-06-03	Mowing Cycles, Starting Dates, and Failure to Complete Mowing on Time MAINTENANCE CONTRACT FOR MOWING
624-M-024 R 3-01-02	Herbicide Treatment MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT
624-M-040 R 6-06-03	Herbicide Formula and Application Period MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT
625-R-194 R5-22-02	Gabions PAY ITEM: 616-02305 GABIONS
626-R-165 R 3-01-02	Modified Section Concrete Median Barrier CONCRETE MEDIAN BARRIER REQUIRED OF OTHER THAN STANDARD SHAPE
701-B-068 R 9-01-95	Bitumen Coating for Piles BITUMEN COATED PILES
701-B-078 R 5-22-02	Oversized Predrilled Pile Holes for Integral End Bent Structures PAY ITEM: 701-93633 PILE HOLE PREDRILLED (REQUIRES 211-R-357)
701-B-101d R11-05-99	Pile Driving and Equipment Data Form PAY ITEMS FOR PILES

701-B-132 R 3-05-99	Pile Driving AS DETERMINED BY THE PROJECT DESIGNER
701-B-154 A12-06-01	Oversized Predrilled Pile Holes for Reduction of Pile Downdrag AS DETERMINED BY PROJECT DESIGNER
703-C-138 A 1-04-99	Reinforcing Bars PROJECTS DESIGNED WITH HARD METRIC REINFORCING STEEL
706-B-140d R 7-01-01	Bridge Railing Type TS-1 & Guardrail Transition Type TGS-1 PAY ITEM: BRIDGE RAILING TYPE TS-1
707-B-013 R 6-06-03	High Range Water Reducers in Precast Prestressed Concrete Structural Members PAY ITEMS FOR STRUCTURAL MEMBERS CONCRETE
707-B-085 R 5-01-03	Alternate Prestressed Precast Concrete I-Beam to Standard AASHTO Type IV Prestressed Precast Concrete I-Beam ALTERNATE BEAM SECTION PERMITTED IN LOCAL AGENCY PROJECT
707-B-158 A 3-13-03	Precast and Prestressed Concrete Structural Members PAY ITEM: STRUCTURAL MEMBER CONCRETE
709-B-070 R 9-1-93	Tinted Epoxy Penetrating Sealer PAY ITEMS FOR SURFACE SEAL TINTED
709-M-019 R 1-04-99	Surface Seal for Steel Bridge to be Painted PAY ITEMS: CLEAN STEEL BRIDGE, PAINT STEEL BRIDGE
713-B-076 R 1-04-99	Temporary Pipe TEMPORARY PIPE SPECIFIED ON PLANS IN LIEU OF TEMPORARY BRIDGE
714-R-437 A 6-02-03	Oversize Precast Reinforced Concrete Box Culvert PRECAST REINFORCED CONCRETE BOX CULVERT WITH SPANS GREATER THAN 3.65 M (12')
715-R-342 A 9-04-97	Pipe Backfill Methods METRIC PROJECTS REFERRING TO PIPES BY GROUPS, EXCEPT GROUP K
715-R-361 A 9-1-98	Pipe Material Abbreviations PAY ITEMS FOR PIPE
715-R-442 R 6-03-03	PIPE JOINTS ANY PIPE PAY ITEM
717-R-152 R 5-22-02	Alternates to Structural Plate Structures PAY ITEMS FOR PIPE STRUCTURAL PLATE
718-R-397 2-26-01	Underdrain Outlet Protectors PAY ITEM FOR TYPE 1 OR TYPE 2 OUTLET PROTECTORS
718-R-397d 2-26-01	Precast Outlet Protector Type 1 or Type 2 718-R-397
720-M-021 R 9-1-95	Extension of Cast Iron Floor Drains PAY ITEM: DRAIN EXTENSION CAST IRON
720-R-104 R 6-06-03	Capped Inlet PAY ITEM: 720-44296 CAP INLET

720-T-021 R 11-1-92	Drainage Structures TRAFFIC CONTRACT - DRAINAGE STRUCTURES REQUIRED
722-B-159 A 3-13-03	Latex Modified Concrete Bridge Deck Overlays ANY 722 PAY ITEMS
722-B-160 A 3-17-03	Curing Structural Concrete ANY 702 PAY ITEM
723-R-282 R 6-02-03	Precast Reinforced Concrete 3-Sided Drainage Structure PAY ITEMS FOR CULVERT PRECAST 3 SIDED
723-R-282f R 6-02-03	Precast Reinforced Concrete 3-Sided Flat-Topped Drainage Structure AS DETERMINED BY THE DESIGNER
724-B-046 R 5-22-02	Modular Expansion Joints PAY ITEM: 724-51927 MODULAR EXPANSION JOINT
724-B-086 R 6-14-01	Approved Expansion Joint SS Devices PAY ITEM: 724-51925 EXPANSION JOINT SS
724-B-131 R 1-27-98	Polymer Modified Asphalt Joint System PAY ITEM: 501-02221 EXPANSION JOINT POLYMER MODIFIED ASPHALT
724-B-131d R 7-14-97	Polymer Modified Asphalt Joint System Details ACCOMPANIES 501-R-281
724-B-145 R 6-05-03	Expansion Joint Sealing System PAY ITEM: EXPANSION JOINT SEALING SYSTEM
724-B-147d A 1-22-01	Alternate SS Joint AS CALLED FOR BY INDOT BRIDGE REHAB SECTION
726-B-044 R 1-04-99	Bearing Assemblies PAY ITEM: 707-95870 BEARING ASSEMBLY
727-B-012 R 1-04-99	Concrete Repair by Epoxy Injection PAY ITEMS FOR EPOXY INJECTION EQUIPMENT, CRACK PREPARATION, EPOXY MATERIAL
728-B-039 R 3-01-01	Masonry Coating PAY ITEMS FOR MASONRY COATING; MASONRY COATING SPECIFIED WITHOUT PAYMENT
729-B-009 R 3-28-96	Concrete for Patching Bridge Structures PAY ITEM: CONCRETE, A, PATCHING
730-B-157 R 9-02-02	QC/QA Superstructure Concrete PAY ITEM: CONCRETE, QC/QA, SUPERSTRUCTURE
731-R-202 R 5-01-03	Mechanically Stabilized Earth Retaining Walls DETAILS FOR PROPRIETARY MECHANICALLY STABILIZED EARTH WALL SYSTEMS INCLUDED IN PLANS
732-R-310r R 9-02-22	Modular Concrete Block Retaining Walls With Ground Reinforcing AS DETERMINED BY PROJECT DESIGNER
732-R-310u R 9-02-22	Modular Concrete Block Retaining Walls Without Ground Reinforcing AS DETERMINED BY PROJECT DESIGNER

732-R-433 R 5-22-02	Bin-Type Retaining Wall PAY ITEMS FOR RETAINING WALL BIN TYPE _____ DESIGN _____
733-B-104 R 9-02-02	Silica Fume Modified Structural Concrete Bridge Deck Overlay PAY ITEM: 722-51842 BRIDGE DECK OVERLAY; MICROSILICA ADMIXTURE SPECIFIED
801-C-157 R 1-21-03	Certification of Temporary Traffic Control Devices PAY ITEM: MAINTENANCE OF TRAFFIC
801-M-006 R 6-06-03	Maintaining Traffic for Maintenance or Resurface Work MAINTENANCE OR RESURFACE CONTRACT, PAY ITEMS FOR MAINTAINING TRAFFIC
801-R-030 R 6-06-03	Temporary U-Turns for Contractor's Vehicles AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
801-R-253 A 1-14-93	Mobile Construction Signs PAY ITEM: 801-92448 CONSTRUCTION SIGNS, MOBILE
801-R-420 A 5-06-02	Worksite Speed Limit Signs PAY ITEM: WORKSITE SPEED LIMIT SIGNS
801-T-089 R 7-8-99	Maintaining Existing Traffic Signal Installation PAY ITEM: TEMPORARY TRAFFIC SIGNAL INSTALL AND MAINTAIN
801-T-142 A 5-22-03	Temporary Mounted Construction signs ALL CONTRACTS
802-T-143 A 5-22-03	Structural Frames 802 PAY ITEMS
802-SNGP-01 A 5-22-03	Sign Placement PAY ITEM: SIGN POST, WIDE FLANGE
802-SNGE-04 A 5-22-03	Sign Details PAY ITEM: SIGN POST, WIDE FLANGE
802-SNGP-06 A 5-22-03	Sign Data Tables PAY ITEM: SIGN POST, WIDE FLANGE
802-SNGP-07 A 5-22-03	Wide Flange Sign Post Support Foundation Data PAY ITEM: SIGN POST, WIDE FLANGE
802-SNGS-10 A 5-22-03	Steel Sign Posts PAY ITEM: SIGN POST, SQUARE, TYPE _____, REINFORCED ANCHOR BASE SIGN POST, SQUARE, TYPE _____, UNREINFORCED ANCHOR BASE
802-SNGS-12 A 5-22-03	Wide Flange Post Selection Table PAY ITEM: SIGN POST, WIDE FLANGE
802-SNOB-01 A 5-22-03	Overhead Sign Bridge Spans PAY ITEM: OVERHEAD SIGN STRUCTURE, BRIDGE
802-SNOC-01 A 5-22-03	Overhead Cantilever Signs PAY ITEM: OVERHEAD SIGN STRUCTURE, CANTILEVER, SINGLE ARM

802-SHOC-02 A 5-22-03	Overhead Cantilever Sign Details 802-SNOC-01
802-SNOC-03 A 5-22-03	Single Arm Cantilever Table 802-SNOC-01
802-SNOC-04 A 5-22-03	Double Arm Cantilever Table PAY ITEM: OVERHEAD SIGN STRUCTURE, CANTILEVER, DOUBLE ARM
802-SNOC-05 A 5-22-03	Overhead Sign Details PAY ITEM: OVERHEAD SIGN STRUCTURE, ALL TYPES
802-SNOH-01 A 2-13-03	Sign Structure Truss Aluminum Details PAY ITEM: OVERHEAD SIGN STRUCTURE, TRUSS
802-SNOH-04 A 2-13-03	Sign Structure Truss Schedules PAY ITEM: OVERHEAD SIGN STRUCTURE, TRUSS
802-SNOH-06 A 5-22-03	Aluminum Structure Bolt Details PAY ITEM: OVERHEAD SIGN STRUCTURE, TRUSS
802-SNOH-15 A 2-13-03	Sign Structure Truss Aluminum Details (120' & 130') PAY ITEM: OVERHEAD SIGN STRUCTURE, TRUSS 120' OR 130' SPANS
802-SNOH-16 A 2-13-03	Sign Structure Truss Schedules (120' & 130') PAY ITEM: OVERHEAD SIGN STRUCTURE, TRUSS 120' OR 130' SPANS
805-T-035 R11-07-02	Delay Amplifiers CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-036 R 7-01-95	Department Furnished Materials CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-039d A 3-16-93	Loop Testing Table PAY ITEM: 805-01439 MICROLOOP DETECTOR
805-T-041 R 7-1-95	Miscellaneous Equipment CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-069 A 2-27-89	Traffic Signalization Locations AT LEAST 2 LOCATIONS TO BE SIGNALIZED
805-T-075 R 1-04-99	Saw Cut Requirement PAY ITEMS FOR LOOP DETECTORS
805-T-076 R 1-04-99	Solid State Controllers PAY ITEMS FOR CONTROLLER SOLID STATE PRE-TIMED
805-T-078 A 8-22-90	Electrical Insulation Sealant CONTRACT WITH TRAFFIC SIGNAL OR LIGHTING INSTALLATIONS
805-T-083 R 1-04-99	Traffic Signal Equipment Salvaged by the Contractor TRAFFIC SIGNAL EQUIPMENT TO BECOME PROPERTY OF CONTRACTOR
805-T-084 R 1-04-99	Traffic Signal Equipment Salvaged by the Department PAY ITEM: 202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS

805-T-085 R 7-01-95	Signal Bulb Replacement, Aerial Inspection, and Loop Replacement TRAFFIC MAINTENANCE CONTRACT FOR SIGNAL BULB REPLACEMENT
805-T-086 R 7-1-95	Traffic Signal Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR NON-BULB SIGNAL MAINTENANCE
805-T-093 A 2-2-93	Detector Card Rack and Detector Modules PAY ITEM: DETECTOR MODULE
805-T-095 R 4-16-01	Signal Controllers PAY ITEMS FOR CONTROLLER AND CABINET
805-T-105 A 7-1-95	Conversion of Metric Standards ENGLISH DESIGNED CONTRACTS; PAY ITEMS FOR TRAFFIC SIGNAL
805-T-123 A11-20-00	Video Vehicle Detector System PAY ITEM: VIDEO VEHICLE DETECTOR SYSTEM
805-T-124 A11-20-00	Integrated Video Vehicle Detector System PAY ITEM: INTEGRATED VIDEO VEHICLE DETECTOR SYSTEM
805-T-133 A12-21-01	LED Traffic Signal Indicators AS DETERMINED BY DESIGNER
805-T-144 A 6-13-03	Traffic Vehicle Detection Loop Shape PAY ITEM: SAW CUT FOR ROADWAY LOOP AND SEALANT
807-T-087 R 7-1-95	Highway Illumination Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR LIGHTING MAINTENANCE
808-B-114 R 1-04-99	Repainting No-Passing Zone Pavement Markings BRIDGE CONTRACT; PAY ITEM FOR LINE SOLID YELLOW 4 IN. USED AS NO-PASSING ZONE MARKING
808-T-116 A 1-03-00	Snowplowable Raised Pavement Markers PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKERS
808-T-141 R 6-06-03	Removal of Snowplowable Raised Pavement Markers PAY ITEM: SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE
902-R-454 A 5-22-03	Asphalt Materials HMA PAY ITEMS
904-R-455 A 5-22-03	Aggregates ALL CONTRACTS EXCEPT MOWING AND HERBICIDE
904-R-456 A 5-22-03	Uniform Riprap PAY ITEM: UNIFORM RIPRAP
913-T-117 A 1-12-00	Encapsulated Lens High Intensity Reflective Sheeting PAY ITEM FOR SIGN, SHEET
913-T-120 R 6-13-01	Reflective Lenses for Snowplowable Raised Pavement Markers PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKER
913-T-137 A 2-11-03	Traffic Signal Controllers, Cabinets, and Structures AS DETERMINED BY DISTRICT TRAFFIC ENGINEER

913-T-139	Galvanized Steel Lighting Standards
A 3-17-03	807 PAY ITEMS

913-T-140	Roadway Loop Wire For Signals
A 3-17-03	805 OR 806 PAY ITEMS