

REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT

The following existing traffic signal installations shall be removed. The removal shall be in accordance with 105.03 and shall include the partial removal of existing traffic signal foundations in accordance with 805.03 that are not to be utilized in the finished project.

LOCATIONS

The following existing traffic signal installations shall be partially removed. The removal shall be in accordance with 105.03 and shall include the partial removal of existing traffic signal foundations in accordance with 805.03 that are not to be utilized in the finished project.

LOCATION:EQUIPMENT TO BE REMOVED:

This work will be measured per each existing traffic signal installation that is to be removed or partially removed. This work will be paid for at the contract unit price per each for traffic signal and equipment, remove.

NOTE: If there are no installations that are to be partially removed, delete the material above that deals with a partial removal of an installation