

TEMPORARY REVETMENT RIPRAP CHECK DAMS

The Standard Specifications are revised as follows:

SECTION 205, BEGIN LINE 134, INSERT AS FOLLOWS:

205.06 Method of Measurement

Silt fence and straw bale check dams will be measured by the linear foot (meter). *Straw bale check dams will be measured once per dam parallel to the dam and at the widest point.* Sediment basins will be measured by the units installed complete in place. Revetment riprap check dams, sediment traps, and splashpads will be measured by the ton (megagram). *The measurement of temporary revetment riprap check dams will include the revetment riprap and the No. 5 stone.* Measurement of sediment traps will include the riprap and the No. 8 filter stone. Temporary mulching will be measured by the ton (megagram).

SECTION 205, BEGIN LINE 184, DELETE AND INSERT AS FOLLOWS:

The cost of geotextile fabric shall be included in the cost of ~~the~~ temporary check dam or sediment trap.

The cost of geotextile fabric, trenching, backfilling, posts, fencing, and all necessary incidentals shall be included in the cost of silt fence.

The cost of No. 5 stone required for temporary revetment riprap check dams shall be included in the cost of temporary check dam, revetment riprap.

SECTION 205, AFTER LINE 201, INSERT AS FOLLOWS:

The cost of maintenance, except for the removal of sediments, and removal of temporary erosion and sediment control items shall be included in the cost of the respective items in this section.
