

QC/QA PCCP AIR CONTENT

The Standard Specifications are revised as follows:

SECTION 501, BEGIN LINE 522, DELETE AND INSERT AS FOLLOWS:

(b) Air Content

When test results for air content exceed the allowable tolerance or range, a pay factor will be assessed as follows:

1. Lots

Lot Average Air Content	
Percent %	Pay Factors
> 10.0 9.9	*
10.0 9.7 – 9.8	0.80
9.7 9.9	0.85
9.5 – 9.6	0.91 0.90
9.3 – 9.4	0.96 0.95
9.0 – 9.2	0.98 0.99
5.7 – 8.9	1.00
5.0 5.6	0.99 0.93
4.7 4.9	0.98
4.6 5.5	0.88 0.90
4.5 5.4	0.80 0.85
< 4.5 5.3	* 0.79
< 5.3	*

- * The PCCP will be adjudicated as a failed material in accordance with normal Department practice as listed in 105.03. The PCCP may be subject to removal and replacement or left in place with reduced or no payment.

Lot Range for Air Content	
Percent %	Pay Factors
0.0 – 2.5	1.00
2.6 – 3.0	0.99
3.1 – 3.5	0.97
> 3.5	*

- * The PCCP will be adjudicated as a failed material in accordance with normal Department practice as listed in 105.03. The PCCP may be subject to removal and replacement or left in place with reduced or no payment.

2. Sublots

If a subplot value is less than ~~4.0~~ 5.0% or greater than 10.0%, the PCCP will be adjudicated as a failed material in accordance with normal Department practice in accordance with 105.03. For a subplot completely removed, the subplot test value from the replacement subplot will replace the original test value.