

CONSTRUCTION ZONE ENERGY ABSORBING TERMINALS, CZ

The Standard Specifications are revised as follows:

SECTION 801, BEGIN LINE 823, INSERT AS FOLLOWS:

Construction zone energy absorbing terminals, *cz*, *used on type 1 and type 3 temporary traffic barriers* will be measured by the number of terminals placed.

SECTION 801, BEGIN LINE 887, INSERT AS FOLLOWS:

Construction zone energy absorbing terminal, *cz when used with type 1 or type 3 temporary traffic barriers* will be paid for at the contract unit price per each for energy absorbing terminal, *cz*, of the test level placed. Each unit will be paid for only once regardless of how many times it is moved. *Construction zone energy absorbing terminal, cz when used with type 2 or type 4 temporary traffic barriers will be paid for at the contract unit price per linear foot (meter) of type 2 or type 4 temporary traffic barrier.* Back-up units will be paid for as energy absorbing terminal, *cz*, of the test level placed, if they are placed in service due to non-repairable damage to the units already in service. Due to the nature of the TRACC-350 unit, the Engineer must agree that the in-service unit has been damaged to the extent that it is non-repairable before a standby TRACC-350 unit will be considered for payment.
