

BASIS FOR USE
OF RECURRING SPECIAL PROVISIONS
AND RECURRING PLAN DETAILS

CODE Date	Description BASIS FOR USE
100-C-146 R10-26-06	Payment of Predetermined Minimum Wage (Davis-Bacon) IN030001 ALL PROJECTS IN LAKE, LAPORTE, PORTER, AND ST. JOSEPH COUNTIES EXCEPT BUILDING CONSTRUCTION.
100-C-147 R10-26-06	Payment of Predetermined Minimum Wage (Davis-Bacon) IN030006 ALL PROJECTS IN COUNTIES OTHER THAN LAKE, LAPORTE, PORTER, AND ST. JOSEPH EXCEPT BUILDING CONSTRUCTION.
100-C-148 A10-26-06	Payment of Predetermined Minimum Wage (Davis-Bacon) _____ ALL BUILDING CONSTRUCTION - DETERMINED BY CENTRAL OFFICE PERSONNEL
100-C-151 R12-07-06	Federally Funded Contract with DBE AS DETERMINED BY CONTRACTS SECTION
100-C-152 R 3-09-06	Federally Funded Contract without DBE AS DETERMINED BY CONTRACTS SECTION
100-C-166 A 9-01-05	As Built Plans ALL CONTRACTS WITH PERMANENT TRAFFIC SIGNAL INSTALLATIONS
100-C-188 A 7-08-05	2006 Standard Specifications ALL CONTRACTS
100-C-201 A12-15-06	MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) ALL CONTRACTS
101-B-042 R 9-01-05	Structure Numbers for Pay Items MORE THAN ONE BRIDGE FILE NUMBER IN CONTRACT, AND LUMP SUM PAY ITEMS SHOWN TO BE REQUIRED FOR EACH SUCH BRIDGE FILE
102-C-082 R 9-01-05	Schedule of Pay Items for Alternate Bids PAY ITEMS IN CONTRACT WHICH REQUIRE ALTERNATE BIDS
102-C-145 R 9-01-05	Toll Road Special Provisions - Contact for Questions Regarding Contract Documents ALL TOLL ROAD CONTRACTS
102-C-170 A 9-01-05	Prequalification BUILDING CONSTRUCTION
103-C-036 R 3-09-06	Owners' and Contractors' Protective Liability Insurance Coverage for Operations of the Designated Contractor ALL FEDERAL AID LOCAL PUBLIC AGENCY CONTRACTS
103-C-159 R12-05-06	Wage Stipulations 100% STATE FUNDED CONTRACTS
104-C-112 R 9-01-05	Traffic Control Changes and On-Call Maintenance of Traffic Control Devices TRAFFIC BEING MAINTAINED ON PRESENT ROADWAY WITH NO WATCHMAN REQUIRED

104-C-139	Geotechnical Evaluation Report
A 9-01-05	GEOTECHNICAL REPORT HAS BEEN DEVELOPED AND APPROVED
104-R-168	Schedule of Operations and Traffic Control for Undersealing,
R 9-01-05	Concrete Patching, Placing Underdrains, and Resurfacing
	PAVEMENT UNDERSEALING, PATCHING, SHOULDER DRAIN PLACEMENT,
	AND RESURFACING SPECIFIED
105-C-056	Engineer Application Personal Computer
R 9-01-05	ALL CONTRACTS WITH FIELD OFFICE
105-C-071b	Fax Machine in Field Office (Advanced Features)
R 9-01-05	AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
105-C-164	Cellular Telephones/Radios
A 1-30-06	AS DETERMINED BY DISTRICT CONSTRUCTION
105-C-191	Field Office Internet Service
A 8-22-06	PAY ITEM: FIELD OFFICE
105-R-305	Pipe Structure Pay Items
R 9-01-05	ALL CONTRACTS WITH PIPE STRUCTURE PAY ITEMS
107-B-040	Environmental Restrictions
R 9-01-05	AS DETERMINED BY PROJECT DESIGNER
107-C-029	Equal Employment Opportunity Trainees
R 9-01-05	AS DETERMINED BY CONTRACT SERVICES
107-C-193	Drug Testing Plan Implementation
R 9-21-06	ALL CONTRACTS
107-R-042a	Railroad Information
R 9-01-05	HIGHWAY OVER OR UNDER RAILWAY
107-R-042b	Railroad Information
R 11-18-05	AS DETERMINED BY UTILITIES SECTION
107-R-169	Statements About Existing Conditions of Utilities, Additional
R11-18-05	Right-of-Way, and Encroachments
	ALL CONTRACTS
108-C-043	Incentive for Opening Project to Traffic
R 9-01-05	Ahead of Schedule
	AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET
	CONTRACT TIME
108-C-078	Partnering Overhead
R 9-01-05	AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
108-C-089	Percentage of Work Required of Prime Contractor
R 9-01-05	AS DETERMINED BY CONTRACT SERVICES PERSONNEL WHO WILL PROCESS
	CONTRACTS SHORTLY BEFORE LETTING
108-C-090	Latest Date to Begin Work
R 9-01-05	DELAYED START OF WORK DESIRED
108-C-091	Failure to Complete on Time for Restriction-One Structure
R 8-21-06	LANE RESTRICTIONS ON ONE LANE, PHASE, OR DIRECTION

108-C-092 R 8-21-06	Failure to Complete on Time for Restriction-Two or More Structures LANE RESTRICTIONS ON MORE THAN ONE STRUCTURE, PHASE, OR DIRECTION
108-C-093 R 8-21-06	Failure to Complete on Time for Road Closure AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT WHICH INCLUDES DETOUR
108-C-094 R 9-01-05	Failure to Complete on Time for Intermediate Completion Date AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT IN WHICH A CERTAIN PORTION OF THE WORK IS TO BE COMPLETED BEFORE THE ENTIRE CONTRACT IS
108-C-095 R 9-01-05	Failure to Complete on Time for Calendar Completion Date AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-127 R 9-01-05	Earliest Date To Begin Work AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
108-C-192 A 9-27-06	Temporary Erosion Control Measures ALL CONTRACTS EXCEPT MOWING AND HERBICIDE
108-C-200 A11-16-06	Determination and Extension of Contract Time ALL CONTRACTS
108-C-202 A 2-07-07	Working Restrictions Memorial Day, July Fourth, Labor Day - Ft. Wayne ALL FORT WAYNE CONTRACTS
108-L-001 R 9-01-05	Notice to Proceed With Demolition Work PAY ITEMS: 202-03000 HOUSES AND BUILDINGS PARCEL NO. ____ REMOVE
108-L-012 A 9-01-05	Specialty Pay Items PAY ITEM: 202-01261 TESTING FOR ASBESTOS REMOVAL
108-R-148 R 9-01-05	Construction Equipment in Park Areas PARK CONTRACT
109-B-148 A 9-01-05	Cost Reduction Incentive ALL PROJECTS WITH A BRIDGE
111-C-178 A 9-01-05	Stockpiled Materials ALL CONTRACTS EXCEPT MOWING, HERBICIDE, AND PAINTING
112-C-122 R 9-01-05	State Funded Contract with Davis-Bacon Wage Rates AS DETERMINED BY CONTRACTS SECTION
200-R-401 R 1-12-07	Recycled Foundry Sand PAY ITEMS OF BORROW OR B BORROW
201-C-052 R 9-01-05	Clearing Right-of-Way PAY ITEMS FOR CLEARING RIGHT-OF-WAY
201-M-030 R 9-01-05	Debris Removal at Bridge Structures DEBRIS REMOVAL MAINTENANCE CONTRACT

201-R-021 R 9-01-05	Open Burning of Natural Growth Permitted IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING OF NATURAL GROWTH
201-R-179 R 9-01-05	Air-Curtained Open-Pit Incineration of Natural Growth Required IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING BY MEANS OF AIR-CURTAINED OPEN-PIT INCINERATOR
202-C-190 A 3-16-06	Demolition/Renovation Notification to IDEM ALL CONTRACTS WITH BRIDGE REMOVAL OR BUILDING DEMOLITION
202-L-013 R 9-01-05	Inspection and Testing for Asbestos Material AS DETERMINED BY PRE-ENGINEERING AND ENVIRONMENT
202-R-430 R 9-01-05	Recycling Existing Concrete Pavement WHEN DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
202-T-161 A11-30-06	Removal of Existing Traffic Signal Equipment CONTRACTS WHERE EXISTING TRAFFIC SIGNAL EQUIPMENT IS TO BE COMPLETELY/PARTIALLY REMOVED
203-B-025 R 9-01-05	Marion County Borrow Areas PROJECT LIMITS IN MARION COUNTY, PAY ITEM: 203-02070
203-R-121 R 9-01-05	Borrow Area Wetland Enhancement BORROW PIT EXCAVATION EXPECTED TO REACH WATER TABLE
203-R-260 R 4-12-06	Linear Grading PAY ITEM: 203-90014 OR 203-02080 LINEAR GRADING. EARTH WEDGING AT OUTSIDE EDGE OF SHOULDER OR BEHIND GUARDRAIL, OR MEDIAN EARTH FILLING
203-R-360 R 9-01-05	Embankments Constructed of Coal Combustion By-Products PAY ITEM OF 5000 CYS (3800 CUBIC METERS) OR MORE OF BORROW
205-R-528 A 9-21-06	Temporary Revetment Riprap Check Dam PAY ITEMS: TEMPORARY CHECK DAM, REVETMENT RIP OR TEMPORARY CHECK DAM, STRAW BALES
205-R-528d A 9-21-06	Temporary Check Dam, Revetment Riprap 205-R-528
206-B-026 R 9-01-05	Steel Sheet Piling at Railroad Grade Separation STEEL SHEET PILING REQUIRED, RAILWAY WITHIN PROJECT LIMITS
206-B-113 R 9-01-05	General Bridge Requirements BRIDGE REPLACEMENT OR NEW BRIDGE CONSTRUCTION
206-R-512 A 2-16-06	Excavation for Retaining Walls PAY ITEM: CONCRETE, (<u>CLASS</u>), STRUCTURES WHERE CONCRETE IS FOR RETAINING WALLS
208-R-111 R 9-01-05	Gore Area Treatment PAY ITEM: 203-02046 GRADING OF GORE AREA
211-R-415 A 9-01-05	Crushed Glass as Bedding Material AS DETERMINED BY MATERIALS AND TESTS DIVISION

211-R-534 A11-16-06	B Borrow and Structure Backfill PAY ITEMS B BORROW OR STRUCTURE BACKFILL
213-R-446 R 9-01-05	Flowable Fill PAY ITEM: FLOWABLE BACKFILL
215-R-523 A 5-09-06	Compaction PAY ITEM 215-07043, CHEMICAL MODIFICATION, SOILS
305-R-431 R 7-20-06	Cement Concrete Pavement Cracking and Seating PAY ITEM: CONCRETE PAVEMENT CRACKING AND SEATING
306-R-524 A 6-15-06	Transition Milling PAY ITEM: TRANSITION MILLING
306-R-524d A 6-15-06	HMA Pavement Wedging and Transition Milling USE IN CONJUNCTION WITH 306-R-524
400-R-500 A 7-19-05	Volumetric Mix Design ANY HMA PAY ITEM
400-R-520 A 4-03-06	Moisture Test For HMA and SMA ANY HMA OR SMA PAY ITEM
400-R-525 A10-26-06	HMA Smoothness PAY ITEM: QC/QA - HMA
411-R-432 R 7-20-06	Warranted Micro-Surfacing PAY ITEM OF MICRO-SURFACING
500-R-515 A 6-22-06	Concrete Mix Design ALL CONTRACTS EXCEPT BRIDGE PAINTING, MOWING, AND HERBICIDE
500-R-529 A10-26-06	PCCP Smoothness PAY ITEM: QC/QA - PCCP
500-R-530 A 9-21-06	Sawing, Cleaning, and Sealing PCCP Joints ANY PCCP PAY ITEM
501-R-540 A 1-05-07	QC/QA PCCP Air Content ALL CONTRACTS WITH A 501 PAY ITEM
503-R-516 A 3-24-06	PCCP Stitching AS DETERMINED BY PAVEMENT ENGINEERING SECTION
503-R-516d A 3-24-06	PCCP Stitching AS DETERMINED BY PAVEMENT ENGINEERING SECTION
503-R-518 A 3-16-06	Retrofitted Tie Bars PAY ITEM: RETROFITTED TIE BARS
601-R-146 A 9-01-05	Removal of Guardrail REMOVED GUARDRAIL TO BECOME PROPERTY OF DEPARTMENT
601-R-237 R 1-01-06	Spare Parts Package for Guardrail End Treatment AS DETERMINED BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
601-R-237d A May-06	Spare Parts Package for Guardrail End Treatment PAY ITEM FOR SPARE PARTS PACKAGE FOR GUARDRAIL END TREATMENT

601-R-338 R 9-01-05	Guardrail Blockouts PAY ITEM FOR GUARDRAIL
601-R-497 A 1-01-06	Spare Parts Package for Impact Attenuators PAY ITEM: IMPACT ATTENUATOR SPARE PARTS PACKAGE
601-R-497d A 1-01-06	Spare Parts Package for Impact Attenuators PAY ITEM FOR SPARE PARTS PACKAGE FOR IMPACT ATTENUATORS
602-R-388d A11-16-00	Concrete Barrier AS DETERMINED BY DESIGN DIVISION
603-R-109 R 9-01-05	Gate Barricade PAY ITEM: GATE BARRICADE
603-R-414 R12-08-06	Polyvinyl Chloride Coated Chain Link Fence PAY ITEM: VINYL COATED CHAIN LINK FENCE
604-R-531 A 9-21-06	Detectable Warning Devices ANY 604 PAY ITEM
610-R-100 R 9-01-05	Median Crossovers MEDIAN CROSSEOVERS REQUIRED AS SHOWN ON PLANS
610-R-502 A 2-16-06	Approaches ANY 610 PAY ITEM
615-R-020 R 9-01-05	Wood Post Parking Barrier PAY ITEM: PARKING BARRIER WOOD POST
616-R-102 R 9-01-05	Gabion Revet Mattress PAY ITEM: GABION REVET MATTRESS
620-R-483 R 6-15-06	Sound Barrier Systems ANY 620 PAY ITEM
620-R-483a A 6-15-06	Sound Barrier Systems USE IN CONJUNCTION WITH 620-R-483
621-R-398 A 9-01-05	Capping Cut and Fill Slopes Steeper Than 3:1 AS DETERMINED BY PROJECT ENGINEER
621-R-517 A 3-28-06	Laying Sod PAY ITEMS FOR SOD AND SODDING, NURSERY
622-R-209 A 9-01-05	Wildlife Habitat Species and Spacing PAY ITEM: 622-91786 SEEDLING; SPECIES AND SPACING NOT SHOWN ON PLANS
623-M-025 R 9-01-05	Roadside Mowing MAINTENANCE CONTRACT FOR MOWING
623-M-039 R 9-01-05	Mowing Cycles, Starting Dates, and Failure to Complete Mowing on Time MAINTENANCE CONTRACT FOR MOWING
624-M-024 R 9-01-05	Herbicide Treatment MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT

624-M-040 R 9-01-05	Herbicide Formula and Application Period MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT
625-R-194 R 9-01-05	Gabions PAY ITEM: 616-02305 GABIONS
626-R-165 R 9-01-05	Modified Section Concrete Median Barrier CONCRETE MEDIAN BARRIER REQUIRED OF OTHER THAN STANDARD SHAPE
701-B-068 R 9-01-05	Bitumen Coating for Piles BITUMEN COATED PILES
701-B-078 R 9-01-05	Oversized Predrilled Pile Holes for Integral End Bent Structures PAY ITEM: 701-93633 PILE HOLE PREDRILLED
701-B-101d R11-05-99	Pile Driving and Equipment Data Form PAY ITEMS FOR PILES
701-B-132 R 9-01-05	Pile Driving AS DETERMINED BY THE PROJECT DESIGNER
701-B-154 A 9-01-05	Oversized Predrilled Pile Holes and Bentonite Grout for Reduction of Pile Downdrag AS DETERMINED BY PROJECT DESIGNER
703-C-138 A 9-01-05	Reinforcing Bars PROJECTS DESIGNED WITH HARD METRIC REINFORCING STEEL
706-B-140d R 7-01-01	Bridge Railing Type TS-1 & Guardrail Transition Type TGS-1 PAY ITEM: BRIDGE RAILING TYPE TS-S
707-B-085 R 9-01-05	Alternate Prestressed Precast Concrete I-Beam to Standard AASHTO Type IV Prestressed Precast Concrete I-Beam ALTERNATE BEAM SECTION PERMITTED IN LOCAL AGENCY PROJECT
707-B-171 A 7-19-06	Alternative Interior Diaphragms AS DETERMINED BY THE DESIGN ENGINEER
707-B-172 A 5-24-06	Interior Diaphragms AS DETERMINED BY THE DESIGN ENGINEER
707-B-173 A 7-19-06	Structural Steel Intermediate Diaphragms AS DETERMINED BY THE DESIGN ENGINEER
707-B-173d A 7-19-06	Structural Steel Intermediate Diaphragms 707-B-173
709-B-070 R 9-01-05	Tinted Epoxy Penetrating Sealer PAY ITEMS FOR SURFACE SEAL TINTED
709-M-019 R 9-01-05	Surface Seal for Steel Bridge to be Painted PAY ITEMS: CLEAN STEEL BRIDGE, PAINT STEEL BRIDGE
711-B-165 A 7-19-06	High Performance Steel AS DETERMINED BY THE DESIGN ENGINEER
713-B-076 R 9-01-05	Temporary Pipe TEMPORARY PIPE SPECIFIED ON PLANS IN LIEU OF TEMPORARY BRIDGE

714-R-437 A11-01-06	Oversize Precast Reinforced Concrete Box Culvert PRECAST REINFORCED CONCRETE BOX CULVERT WITH SPANS GREATER THAN 12' (3.65 M)
714-R-535 A11-16-06	Concrete Culverts and Retaining Walls ANY 714 PAY ITEM
715-R-532 A 9-21-06	Metal Pipe ANY 715 PAY ITEM
715-R-536 A11-16-06	Pipe Culverts and Storm and Sanitary Sewers ANY 715 PAY ITEM
715-R-536d A11-16-06	Pipe Culverts and Storm and Sanitary Sewers 715-R-536
717-R-152 R11-01-06	Alternates to Structural Plate Structures PAY ITEMS FOR PIPE STRUCTURAL PLATE
717-R-537 A11-16-06	Structural Plate Pipe, Pipe-Arches, and Arches ANY 717 PAY ITEM
720-M-021 R 9-01-05	Extension of Cast Iron Floor Drains PAY ITEM: DRAIN EXTENSION CAST IRON
720-R-104 R 9-01-05	Capped Inlet PAY ITEM: 720-44296 CAP INLET
720-T-021 R 9-01-05	Drainage Structures TRAFFIC CONTRACT - DRAINAGE STRUCTURES REQUIRED
722-B-170d A 6-15-06	HMA Pavement Wedge at RCBA PAY ITEM FOR TRANSITION MILLING
723-R-282 R11-01-06	Precast Reinforced Concrete 3-Sided Drainage Structures PAY ITEMS FOR CULVERT PRECAST 3 SIDED
723-R-282f R11-01-06	Precast Reinforced Concrete 3-Sided Flat-Topped Drainage Structures AS DETERMINED BY THE DESIGNER
724-B-046 R10-19-06	Modular Expansion Joints PAY ITEM: 724-51927 MODULAR EXPANSION JOINT
724-B-086 R 3-21-06	Approved Expansion Joint SS Devices PAY ITEM: 724-51925 EXPANSION JOINT SS
724-B-145 R 7-14-06	Expansion Joint Sealing System PAY ITEM: EXPANSION JOINT SEALING SYSTEM
724-B-147d A 1-22-01	Alternate SS Joint AS CALLED FOR BY INDOT BRIDGE REHAB SECTION
726-B-044 R 9-01-05	Bearing Assemblies PAY ITEM: 707-95870 BEARING ASSEMBLY
727-B-012 R 9-01-05	Concrete Repair by Epoxy Injection PAY ITEMS FOR EPOXY INJECTION EQUIPMENT, CRACK PREPARATION, EPOXY MATERIAL

728-B-039 R 9-01-05	Masonry Coating PAY ITEMS FOR MASONRY COATING; MASONRY COATING SPECIFIED WITHOUT PAYMENT
729-B-009 R 9-01-05	Concrete for Patching Bridge Structures PAY ITEM: CONCRETE, A, PATCHING
730-B-157 R 1-01-06	QC/QA Superstructure Concrete PAY ITEM: CONCRETE, QC/QA, SUPERSTRUCTURE
731-R-202 R 2-06-07	Mechanically Stabilized Earth Retaining Walls DETAILS FOR PROPRIETARY MECHANICALLY STABILIZED EARTH WALL SYSTEMS INCLUDED IN PLANS
732-R-310 R 2-16-06	Modular Concrete Block Retaining Walls AS DETERMINED BY PROJECT DESIGNER
732-R-433 R 2-16-06	Metal Bin-Type Retaining Wall PAY ITEMS FOR RETAINING WALL BIN TYPE _____ DESIGN _____
733-B-104 R 4-06-06	Silica Fume Modified Structural Concrete Bridge Deck Overlay AS DETERMINED BY INDOT BRIDGE REHAB SECTION
735-R-468 A 9-01-05	Wingwalls and Headwalls for Precast Concrete Box Culverts PAY ITEMS: CULVERT, PRECAST REINFORCED CONCRETE BOX AND CONCRETE CULVERT EXTENSION, PRECAST REINFORCED CONCRETE BOX SECTION
801-C-157 R 9-01-05	Certification of Temporary Traffic Control Devices PAY ITEM: MAINTENANCE OF TRAFFIC
801-M-006 R 9-01-05	Maintaining Traffic for Maintenance or Resurface Work MAINTENANCE OR RESURFACE CONTRACT, PAY ITEMS FOR MAINTAINING TRAFFIC
801-R-030 R 9-01-05	Temporary U-Turns for Contractor's Vehicles AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
801-R-253 A 9-01-05	Mobile Construction Signs PAY ITEM: 801-92448 CONSTRUCTION SIGNS, MOBILE
801-R-471 A 9-01-05	Material Used for Temporary Ingress/Egress to Properties AS CALLED FOR BY DISTRICT CONSTRUCTION ENGINEER
801-R-519 A 3-16-06	Maintenance of Traffic ALL CONTRACTS WITH TEMPORARY TRAFFIC CONTROL DEVICES
801-T-089 R 9-01-05	Maintaining Existing Traffic Signal Installation PAY ITEM: TEMPORARY TRAFFIC SIGNAL INSTALL AND MAINTAIN
801-T-150d A 9-01-05	Traffic Control Device Report ALL CONTRACTS
801-T-154 A 2-16-06	Construction Zone Energy Absorbing Terminals, CZ PAY ITEM FOR ENERGY ABSORBING TERMINAL, CZ

801-T-157 A 7-14-06	Temporary Pavement Marking Materials 801 PAY ITEMS FOR TEMPORARY PAVEMENT MARKINGS AND TEMPORARY RAISED PAVEMENT MARKER
801-T-158 A 7-20-06	Worksite Speed Limit Sign Assembly/Reduced Speed Ahead Sign Assembly PAY ITEM FOR TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY
801-T-158d A 7-20-06	Worksite Speed Limit Sign Assembly 801-T-158
801-T-163 A12-18-06	Temporary Concrete Traffic Barriers ALL CONTRACTS WITH TEMPORARY TRAFFIC BARRIER, TYPE 1, 2, OR 3
805-T-035 R 9-01-05	Delay Amplifiers CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-036 R 9-27-05	Department Furnished Materials AS DETERMINED BY TRAFFIC DESIGN
805-T-039d A 9-01-05	Loop Testing Table PAY ITEM: 805-01439 MICROLOOP DETECTOR
805-T-041 R 9-01-05	Miscellaneous Equipment CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-076 R 9-01-05	Solid State Controllers PAY ITEMS FOR CONTROLLER SOLID STATE PRE-TIMED
805-T-078 A 9-01-05	Electrical Insulation Sealant CONTRACT WITH TRAFFIC SIGNAL OR LIGHTING INSTALLATIONS
805-T-083 R 9-01-05	Traffic Signal Equipment Salvaged by the Contractor TRAFFIC SIGNAL EQUIPMENT TO BECOME PROPERTY OF CONTRACTOR
805-T-084 R 4-12-06	Traffic Signal Equipment Salvaged by the Department PAY ITEM: 202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS
805-T-085 R 1-13-06	Signal Bulb Replacement, Aerial Inspection, and Loop Replacement TRAFFIC MAINTENANCE CONTRACT FOR SIGNAL BULB REPLACEMENT
805-T-086 R 9-01-05	Traffic Signal Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR NON-BULB SIGNAL MAINTENANCE
805-T-093 A 9-01-05	Detector Card Rack and Detector Modules PAY ITEM: DETECTOR MODULE
805-T-095 R 2-06-06	Signal Controllers PAY ITEMS FOR CONTROLLER AND CABINET
805-T-105 A 9-01-05	Conversion of Metric Standards ENGLISH DESIGNED CONTRACTS; PAY ITEMS FOR TRAFFIC SIGNAL
805-T-123 A 9-01-05	Video Vehicle Detector System PAY ITEM: VIDEO VEHICLE DETECTOR SYSTEM
805-T-124 A 9-01-05	Integrated Video Vehicle Detector System PAY ITEM: INTEGRATED VIDEO VEHICLE DETECTOR SYSTEM

805-T-144 A 1-11-06	Traffic Vehicle Detection Loop Shape PAY ITEM: SAW CUT FOR ROADWAY LOOP AND SEALANT
805-T-156d A 4-13-06	Pedestal Mounted Signal Indications PAY ITEM: PEDESTRIAN PUSH BUTTON
807-T-087 R 9-01-05	Highway Illumination Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR LIGHTING MAINTENANCE
808-B-114 R 9-01-05	Repainting No-Passing Zone Pavement Markings BRIDGE CONTRACT; PAY ITEM FOR LINE SOLID YELLOW 4 IN. USED AS NO-PASSING ZONE MARKING
808-T-116 A 9-01-05	Snowplowable Raised Pavement Markers PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKERS
808-T-141 R 9-01-05	Removal of Snowplowable Raised Pavement Markers PAY ITEM: SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE
808-T-151 A 9-29-05	Refurbished Snowplowable Raised Pavement Marker Castings AS DETERMINED BY PROJECT MANAGER
904-R-538 A11-16-06	Structure Backfill PAY ITEMS B BORROW OR STRUCTURE BACKFILL
911-R-526 A 7-05-06	Wood Conditioning ALL CONTRACTS EXCEPT MOWING, HERBICIDE, AND PAINTING
913-T-117 A 9-01-05	Encapsulated Lens High Intensity Reflective Sheeting PAY ITEM FOR SIGN, SHEET
913-T-120 R 9-01-05	Reflective Lenses for Snowplowable Raised Pavement Markers PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKER
914-R-509 A 2-07-06	Grass and Legume Seed PAY ITEMS MULCHED SEEDING OR SEED MIXTURE
918-R-533 A 9-21-06	Geotextile Material Properties PAY ITEMS FOR RIPRAP OR UNDERDRAINS
920-T-162 A12-06-06	High Mast Poles PAY ITEM: LIGHT POLE, HIGH MAST, (EFFECTIVE MOUNTING HEIGHT)
922-T-137 R12-11-06	Traffic Signal Materials and Equipment ANY 805 PAY ITEM
923-T-155 A 2-16-06	Acceptance of Temporary Traffic Control Devices ALL CONTRACTS