

100-C-166 AS-BUILT TRAFFIC SIGNAL PLANS

(Revised 08-15-07)

The Contractor shall prepare two sets of as-built plans for the traffic signal portion of the contract. The as-built traffic signal plans shall be submitted to the Engineer no later than the date the signal is placed into operation.

Traffic signal as-built plans shall include a copy of the project title sheet and the plan sheets that show the traffic signal related work. The plans shall indicate the as-built location of steel strain poles, signal cantilevers, electrical service, signal controller, loop detectors, conduit runs, and traffic signal handholes.

The cost of as-built traffic signal plans shall be included in the cost of the traffic signal items.
