

111-C-178 STOCKPILED MATERIALS

(Adopted 09-01-05)

The Standard Specifications are revised as follows:

SECTION 111, BEGIN LINE 9, DELETE AND INSERT AS FOLLOWS:

be incorporated into the work and delivered in the vicinity of the project, or stored in approved storage facilities. Such materials shall be limited to structural steel, concrete structural members, ~~pavement~~ reinforcing steel, pavement contraction joints, granular base and subbase materials, aggregates for HMA and concrete pavements, and structural supports for signals, signs, and luminaires.

In addition to the aforementioned, the Department will consider the stockpiling of other steel products, such as guardrail, culvert pipe, etc if it has been determined that a critical shortage of material would cause delay to the project.

SECTION 111, BEGIN LINE 115, DELETE AS FOLLOWS:

Approval of partial payment for stockpiled materials will not constitute final acceptance of such materials for use in completing the work. Structural steel members and ~~pavement~~ reinforcing steel may be subjected to additional inspection and testing prior to final acceptance and incorporation into the work. All other stockpiled pay items will be subjected to additional inspection and testing prior to final acceptance and incorporation into the work.
