

## 603-R-109 GATE BARRICADE

*(Revised 09-01-05)*

This work shall consist of furnishing and placing a wooden gate barricade as shown on the plans or as otherwise directed.

The posts, bracing, and beam shall be fabricated from No. 2 dense stress rated grade yellow pine and pressure treated with pentachlorophenol in accordance with 911. The wood preservative shall be applied at a rate of 0.40 pounds per cubic foot (6.4 kg per cubic meter). Posts, bracing, and beam shall be rough sawed timber cut and shaped as shown on the plans. Fasteners shall be galvanized with two washers per bolt. The steel collars shall have a corrosion resistant coating. The 10 ft (3 m) chain shall be made from galvanized steel.

This work will be measured per each. This work will be paid for at the contract unit price per each for gate barricade. The costs of all labor, equipment, and necessary materials shall be included in the cost of this work.

---