

723-R-568 THREE-SIDED SCOUR PROTECTION

(Revised 04-15-10)

The Standard Specifications are revised as follows:

SECTION 723, BEGIN LINE 366, DELETE AND INSERT AS FOLLOWS:

723.17 Scour Protection

Scour protection shall be installed as shown on the plans.

When riprap is specified, geotextile shall first be placed on the in-situ soil in accordance with 616.11. Riprap shall then be placed in accordance with 616.

For concrete base slabs, concrete shall be placed in accordance with 702.

723.18 Method of Measurement

Structures and wingwalls will not be measured. The accepted quantities for payment will be the quantities shown on the plans.

Structure backfill will be measured in accordance with 211.09. Flowable backfill will be measured in accordance with 213.08. ~~Geotextile and riprap will be measured in accordance with 616.12.~~

723.19 Basis of Payment

The accepted quantities of structure will be paid for at the contract unit price per linear foot (meter) for structure, precast three-sided, of the span and rise specified. The accepted quantities of wingwalls will be paid for at the contract unit price per square foot (square meter) for wingwalls. Structure backfill will be paid for in accordance with 211.10. Flowable backfill will be paid for in accordance with 213.09. ~~Geotextiles and riprap will be paid for in accordance with 616.13.~~

SECTION 723, BEGIN LINE 401, INSERT AS FOLLOWS:

The cost of designing, coring, testing, pedestals or extended legs, reinforcement, excavation, *scour protection*, repairs, plugging core and handling holes, mortar, sealer, and necessary incidentals shall be included in the cost of the structure.
