

725-R-649 REMOVAL AND DISPOSAL OF DEBRIS AND FOREIGN MATERIAL FROM THE
EXISTING PIPE

(Adopted 10-20-16)

The Standard Specifications are revised as follows:

SECTION 725, BEGIN LINE 202, INSERT AS FOLLOWS:

725.08 Liner Pipe Installation

Prior to commencing the liner pipe installation, all jagged existing pipe edges or other deformities shall be repaired. All debris and foreign material shall be removed from the existing pipe *and disposed of in accordance with 203.08*. A visual walk-through inspection shall be performed after all debris and foreign material has been removed from the existing pipe in order to assess the current condition of the pipe. If visual inspection is not possible, a video inspection of the existing pipe shall be performed. A copy of the video inspection shall be provided to the Engineer. If, upon completion of the inspection of the existing pipe, the Contractor believes that they cannot proceed with the work as shown on the plans, the Engineer shall be notified.

SECTION 725, BEGIN LINE 261, INSERT AS FOLLOWS:

No measurement will be made for debris removal *and disposal*, filling existing voids, or trimming, cutting, jacking, or other corrective measures performed on jagged edges or other deformities of the existing pipe in order to facilitate installation of the liner pipe. No measurement will be made for visual or video inspection of the existing pipe.

SECTION 725, BEGIN LINE 285, DELETE AND INSERT AS FOLLOWS:

The cost of repairing, trimming, or cutting jagged edges or deformities to existing pipe, filling cavities around the existing pipe with cellular concrete grout, acquisition and restoration of right-of-entry areas, acquiring all necessary new permits or amendments to existing permits to work in areas accessible via Contractor-obtained right-of-entry, erection, maintenance, and removal of temporary fence, ~~removing~~ *removal and disposal of debris and foreign material from the existing pipe, visual or video inspection of the existing pipe, deforming a circular liner pipe, supplying and constructing the bulkheads, grouting the annular space between the existing pipe and the liner pipe, and other incidentals* will not be paid separately, but shall be included in the cost of the pay items in this section.
