801-T-238 TEMPORARY ACCESSIBLE PEDESTRIAN PATH

(Adopted 02-15-24)

Description

This work shall consist of installing temporary surfaces for temporary pedestrian access in accordance with 105.03.

Material Requirements

Materials shall be in accordance with 604.02 or selected from the Department's QPL of ADA Compliant Work Zone Devices and as follows:

The temporary surface shall be a minimum of 48 in. wide. The temporary surface shall not be made of plywood. The temporary surface shall have a firm and stable slip resistant surface.

Construction Requirements

The Contractor shall place temporary surfaces to provide ADA compliant temporary access for pedestrians in accordance with 107.08, 604, 801 and as shown on the plans.

Prior to placement of the temporary surface, the existing ground shall be cleared of any removable debris to provide a level surface. The maximum cross slope shall be 2.0%. The existing ground shall be cleared or excavated of natural vegetation as needed for temporary surface construction.

The temporary accessible pedestrian path shall be kept free of any obstructions or trip hazards including debris, mud, construction equipment, and stored materials.

If the temporary surface is less than 60 in. wide a 60 in. by 60 in. passing space shall be provided every 200 ft.

The final layout of the temporary pedestrian access path at each location shall be as approved by the Engineer prior to closing any existing sidewalk.

Method of Measurement

Temporary surfaces for temporary pedestrian access will be measured by the square yard.

Basis of Payment

The accepted quantity of temporary surfaces for temporary pedestrian access will be paid for at the contract unit price per square yard.

Payment will be made under:

Pay Item

Pay Unit Symbol

Temporary Accessible Pedestrian PathSYS

The cost of all labor, materials, equipment, railing, handrail, excavation or removal of existing vegetation, in-kind replacement of existing vegetation and all necessary incidentals required to place the temporary surfaces during construction operations and removal of the temporary surfaces after construction is complete shall be included in the cost of the pay item.