

REVISION TO 2006 STANDARD SPECIFICATIONS

SECTION 801, BEGIN LINE 771, DELETE AND INSERT AS FOLLOWS:

*Temporary ~~concrete~~ traffic barrier and anchored temporary ~~concrete~~ traffic barrier will be paid for at the contract unit price per meter (linear foot) per the type specified. Payment will be made only once, regardless of the number of times the barrier is moved to accommodate different phases of traffic maintenance or construction operations as shown in the contract. Construction zone impact attenuators, cz when used on a type 2 or type 4 temporary traffic barrier will be paid for as part of the wall.*

SECTION 801, BEGIN LINE 852, DELETE AND INSERT AS FOLLOWS:

*Temporary ~~Concrete~~ Traffic Barrier, \_\_\_\_\_ m (LFT)  
type  
 Temporary ~~Concrete~~ Traffic Barrier, Anchored, \_\_\_\_\_ m (LFT)  
Type*

SECTION 801, AFTER LINE 889, DELETE AND INSERT AS FOLLOWS:

*The cost of end treatments and impact attenuators for type 2 and type 4 temporary traffic barriers shall be included in the cost of the barrier.*

*The cost of delineation of temporary ~~concrete~~ traffic barrier shall be included in the cost of temporary ~~concrete~~ traffic barrier.*

Other sections containing specific cross references:	General Instructions to Field Employees Update Required? Y____ N____ By - Additional or Revision
408.08, Pg 438SS	Frequency Manual
713.09, Pg 518	Update Required? Y____ N____ By - Addition or Revision
Recurring Special Provisions potentially affected:	Standard Sheets potentially affected:
NONE	NONE
Motion: Mr.	Action: Passed as submitted; revised
Second: Mr.	Effective - _____ Letting
Ayes:	_____ Supplementals
Nays:	Withdrawn. Resubmit? _____
	Received FHWA Approval? _____