



Indiana Department of Environmental Management
Office of Water Quality
Wetlands Section

Publication Date:

March 24, 2010

IDEM ID Number:

2010-113-74-JPS-A

Closing Date:

April 14, 2010

Corps of Engineers ID Number:

LRL-2009-645-lcl

PUBLIC NOTICE

To all interested parties:

This letter shall serve as a formal notice of the receipt of an application for **Section 401 Water Quality Certification** by the Indiana Department of Environmental Management (IDEM). The purpose of the notice is to inform the public of active applications submitted for water quality certification under Section 401 of the Clean Water Act (33 U.S.C. § 1341) and to solicit comments and information on any impacts to water quality related to the proposed project. IDEM will evaluate whether the project complies with Indiana's water quality standards as set forth at 327 IAC 2.

- | | | | |
|----------------------|--|------------------|--|
| 1. Applicant: | Ms. Laura Hilden
Indiana Department of Transportation
100 North Senate Avenue, Room N642
Indianapolis, IN 46204 | 2. Agent: | Mr. Mark Williams
Indiana Department of Transportation
3650 S. US Hwy 41 N.
Vincennes, IN 47591 |
|----------------------|--|------------------|--|
- 3. Project location:** NW ¼ of Section 13, Township 7 South, Range 8 West, Yankeetown USGS Map
On SR 66, 3.67 miles East of SR 61, Spencer County
- 4. Affected waterbody:** Unnamed Tributary to Baker Creek
- 5. Project Description:** The applicant is requesting after-the-fact authorization for the emergency culvert replacement. The applicant proposes to remove the failing 120 inch by 350 feet long corrugated metal culvert that currently carries SR 66 over an Unnamed Tributary to Baker Creek. The failing structure is proposed to be replaced with a 350 feet long 12 feet wide by 8 feet tall concrete box structure that is to be sumped 12 inches in depth. 0.039 acre of wetland is proposed to be temporarily disturbed during construction. Once construction is complete the temporary fill will be removed from the wetland. As compensatory mitigation, the disturbed wetland areas will be returned to original grade and seeded with a wetland seed mix.

Comment period: Any person or entity who wishes to submit comments or information relevant to the aforementioned project may do so by the closing date noted above. Only comments or information related to water quality or potential impacts of the project on water quality can be considered by IDEM in the water quality certification review process.

Public Hearing: Any person may submit a written request that a public hearing be held to consider issues related to water quality in connection with the project detailed in this notice. The request for a hearing should be submitted within the comment period to be considered timely. The request should also state the reason for the public hearing as specifically as possible to assist IDEM in determining whether a public hearing is warranted.

Questions? Additional information may be obtained from Mr. Jared Sanders, Project Manager, at 317-234-6352. Please address all correspondence to the project manager and reference the IDEM project identification number listed on this notice. Indicate if you wish to receive a copy of IDEM's final decision. Written comments and inquiries may be forwarded to -

Indiana Department of Environmental Management
100 North Senate Avenue
MC65-42 WQS IGCN 1255
Indianapolis, Indiana 46204-2251
FAX: 317/232-8406

INDIANA DEPARTMENT OF TRANSPORTATION

ROAD PLANS
PROJECT NO. 0800794

PROJECT DESCRIPTION
STRUCTURE REPLACEMENT

PROJECT LOCATION
S.R. 66, 3.67 MILES E. OF S.R. 61 IN SPENCER COUNTY.



Gross Length mi.
Net Length mi.

LONGITUDE: 87° 15' 36"
LATITUDE: 37° 54' 56"

PLANS PREPARED BY:
Mark C. Williams

PROJECT LOCATION
Spencer

DES. NO. 0800794




CERTIFIED BY:

APPROVED FOR LETTING:


Mark C. Williams



John W. Cunniff



(NOT TO SCALE)

BOX CULVERT FLOWLINE DETAIL



-  STRUCTURE BACKFILL
-  HMA FOR STRUCTURE INSTALLATION

L = LONGITUDINAL PAY LIMITS OF PAVEMENT REMOVAL AND PAVEMENT REPLACEMENT (FT)

12'x8' CONCRETE BOX

RP 45+27

S.R. 66