

PROPOSAL
TO THE
INDIANA DEPARTMENT OF TRANSPORTATION

DATE OF LETTING: August 10, 2016

TIME OF LETTING: 10:00 AM EASTERN DAYLIGHT SAVING TIME

LOCATION OF LETTING: N725 CONF RM, GOVERNMENT CENTER NORTH
100 N. SENATE AVENUE
INDIANAPOLIS, INDIANA 46204

LOCATION OF DEPOSIT: N725 GOVERNMENT CENTER NORTH
100 N. SENATE AVENUE
INDIANAPOLIS, INDIANA 46204

***** STATE CERTIFIED *****

CONTRACT NUMBER: R -32502-A

PROJECT NUMBER(S): 0400039

STRUCTURE NUMBER(S):

ROUTE:

LOCATION: ON 5TH STREET FROM MAIN STREET TO VINE STREET IN THE CITY OF
ROCKPORT

DESCRIPTION: ROAD RECONSTRUCTION

VINCENNES DISTRICT

COUNTY : SPENCER

CONTRACT COMPLETION INFORMATION

CONTRACT COMPLETION DATE:

November 01, 2017

INTERMEDIATE COMPLETION DATE

June 01, 2017

DBE GOAL: A contract provision goal of 12 percent of the contract bid price has been established as the minimum amount for contracting to disadvantaged business enterprises.

THE FOLLOWING DOCUMENTS ARE INCLUDED IN THE CONTRACT:

2016 STANDARD SPECIFICATIONS EFFECTIVE

LIST OF APPROVED OR PREQUALIFIED MATERIALS

STANDARD DRAWINGS LISTED ON STANDARD DRAWING INDEX EFFECTIVE 9-1-15

ADDITIONAL REFERENCE MATERIAL MAY BE AVAILABLE ON THE INDOT WEBSITE. THE REFERENCE MATERIAL MAY INCLUDE, BUT IS NOT LIMITED TO PERMITS, ASBESTOS REPORTS, GEOTECHNICAL REPORTS, AND PRE-BID QUESTIONS AND ANSWERS. THE CONTRACTOR SHALL CONSIDER THE AVAILABLE ADDITIONAL REFERENCE MATERIAL IN PREPARATION OF THE PROPOSAL BID.

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 1

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016

REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE DOLLARS CTS | BID AMOUNT DOLLARS CTS |
|------------|---------------------|----------------------------------|-----------------------------|-----------------------------|
|------------|---------------------|----------------------------------|-----------------------------|-----------------------------|

SECTION 0001 ROAD RECONSTRUCTION

| | | | | |
|------|--|--------------|---------|------|
| 0001 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP | . |
| 0002 | 109-08359 LIQUIDATED DAMAGES | 1.000 DOL | 1.00000 | 1.00 |
| 0003 | 109-08360 CONTRACT LIENS | 1.000 DOL | 1.00000 | 1.00 |
| 0004 | 109-08440 QUALITY ADJUSTMENTS, HMA | 1.000 DOL | 1.00000 | 1.00 |
| 0005 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 DOL | 1.00000 | 1.00 |
| 0006 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 DOL | 1.00000 | 1.00 |
| 0007 | 109-09489 PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.000 DOL | 1.00000 | 1.00 |
| 0008 | 109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.000 DOL | 1.00000 | 1.00 |
| 0009 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP | . |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 2

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016

REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|---------|--|----------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0010 | 201-02260 TREE 30 IN., REMOVE | 1.000 EACH | . | | . | |
| 0011 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP | | . | |
| 0012 | 202-02637 PIPE ABANDON AND GROUT FILL | 71.000 LFT | . | | . | |
| 0013 | 203-02000 EXCAVATION, COMMON | 650.000 CYS | . | | . | |
| 0014 | 203-02070 BORROW | 1071.000 CYS | . | | . | |
| 0015 | 205-06933 TEMPORARY INLET PROTECTION | 29.000 EACH | . | | . | |
| 0016 | 205-06937 TEMPORARY SILT FENCE | 3306.000 LFT | . | | . | |
| 0017 | 205-11584 TEMPORARY CHECK DAM, TRAVERSABLE | 150.000 LFT | . | | . | |
| 0018 | 211-09265 STRUCTURE BACKFILL, TYPE 2 | 1462.000 CYS | . | | . | |
| 0019 | 303-01180 COMPACTED AGGREGATE NO. 53 | 830.000 TON | . | | . | |
| 0020 | 303-08210 COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS | 141.000 TON | . | | . | |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 3

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016
REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|---------|---|----------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0021 | 304-07490 HMA PATCHING, TYPE B | 67.000 TON | . | | . | |
| 0022 | 306-08034 MILLING, ASPHALT, 1 1/2 IN. | 4543.000 SYS | . | | . | |
| 0023 | 306-08041 MILLING, PCCP, VARIOUS DEPTH | 1135.000 SYS | . | | . | |
| 0024 | 306-08432 MILLING, APPROACH | 830.000 SYS | . | | . | |
| 0025 | 306-10163 MILLING ASPHALT, 2 1/2 IN | 3646.000 SYS | . | | . | |
| 0026 | 401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm | 726.000 TON | . | | . | |
| 0027 | 401-07356 QC/QA-HMA, 2, 64, INTERMEDIATE, 9.5 mm | 436.000 TON | . | | . | |
| 0028 | 401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm | 502.000 TON | . | | . | |
| 0029 | 401-10258 JOINT ADHESIVE, SURFACE | 5539.000 LFT | . | | . | |
| 0030 | 401-10259 JOINT ADHESIVE, INTERMEDIATE | 5200.000 LFT | . | | . | |
| 0031 | 401-11785 LIQUID ASPHALT SEALANT | 5200.000 LFT | . | | . | |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 4

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016

REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|---------|---|----------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0032 | 406-05520 ASPHALT FOR TACK COAT | 6.000 TON | . | | . | |
| 0033 | 506-06333 PCCP PATCHING, FULL DEPTH | 326.000 SYS | . | | . | |
| 0034 | 604-06070 SIDEWALK, CONCRETE | 3031.000 SYS | . | | . | |
| 0035 | 604-07897 CURB RAMP, CONCRETE, C | 365.000 SYS | . | | . | |
| 0036 | 604-07899 CURB RAMP, CONCRETE, E | 637.000 SYS | . | | . | |
| 0037 | 604-07901 CURB RAMP, CONCRETE, G | 603.000 SYS | . | | . | |
| 0038 | 605-06140 CURB AND GUTTER, CONCRETE | 5171.000 LFT | . | | . | |
| 0039 | 610-08446 PCCP FOR APPROACHES, 6 IN. | 112.000 SYS | . | | . | |
| 0040 | 610-09108 PCCP FOR APPROACHES, 9 IN. | 780.000 SYS | . | | . | |
| 0041 | 615-01469 MONUMENT SECTION CORNER INSTALL | 1.000 EACH | . | | . | |
| 0042 | 615-06500 MONUMENT, A | 1.000 EACH | . | | . | |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 5

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016

REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|---------|---|----------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0043 | 616-05688 RIPRAP, CLASS 1 | 3.000 TON | . | | . | |
| 0044 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 EACH | . | | . | |
| 0045 | 621-06560 MULCHED SEEDING U | 6011.000 SYS | . | | . | |
| 0046 | 715-04987 CONNECTION , 30" STORM SEWER | 4.000 EACH | . | | . | |
| 0047 | 715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN. | 78.000 LFT | . | | . | |
| 0048 | 715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN. | 607.000 LFT | . | | . | |
| 0049 | 715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN. | 228.000 LFT | . | | . | |
| 0050 | 715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN. | 601.000 LFT | . | | . | |
| 0051 | 715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN. | 505.000 LFT | . | | . | |
| 0052 | 715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN. | 57.000 LFT | . | | . | |
| 0053 | 715-09064 VIDEO INSPECTION FOR PIPE | 991.000 LFT | . | | . | |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 6

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016
REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|---------|--|----------------------------|------------|-----|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0054 | 715-46015 PIPE END SECTION, DIAMETER 21 IN. | 1.000 EACH | . | | . | |
| 0055 | 715-46020 PIPE END SECTION, DIAMETER 24 IN. | 1.000 EACH | . | | . | |
| 0056 | 715-92543 WATER MAIN, 8 IN., RELOCATE | 70.000 LFT | . | | . | |
| 0057 | 720-02442 PIPE PLUG EXISTING | 4.000 EACH | . | | . | |
| 0058 | 720-44000 CASTING, ADJUST TO GRADE , VARIOUS UTILITY | 23.000 EACH | . | | . | |
| 0059 | 720-45030 INLET, E7 | 7.000 EACH | . | | . | |
| 0060 | 720-45045 INLET, J10 | 19.000 EACH | . | | . | |
| 0061 | 720-45240 CATCH BASIN, J10 | 1.000 EACH | . | | . | |
| 0062 | 720-45410 MANHOLE, C4 | 2.000 EACH | . | | . | |
| 0063 | 720-90105 INLET, REPAIR | 1.000 EACH | . | | . | |
| 0064 | 720-98136 FIRE HYDRANT, RESET | 6.000 EACH | . | | . | |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 7

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016
REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE | | BID AMOUNT | |
|---------|---|----------------------------|------------|------|------------|-----|
| | | | DOLLARS | CTS | DOLLARS | CTS |
| 0065 | 801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 5200.000 LFT | . | | . | |
| 0066 | 801-06640 CONSTRUCTION SIGN, A | 32.000 EACH | . | | . | |
| 0067 | 801-06645 CONSTRUCTION SIGN, B | 20.000 EACH | . | | . | |
| 0068 | 801-06775 MAINTAINING TRAFFIC | LUMP | | LUMP | | . |
| 0069 | 802-91122 SIGN GROUND MOUNTED RESET | 4.000 EACH | . | | . | |
| 0070 | 805-92951 SIGNAL DETECTOR HOUSING ADJUST TO GRADE | 2.000 EACH | . | | . | |
| 0071 | 808-05929 TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN. | 956.000 LFT | . | | . | |
| 0072 | 808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN. | 1843.000 LFT | . | | . | |
| 0073 | 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN. | 4541.000 LFT | . | | . | |
| 0074 | 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN. | 1005.000 LFT | . | | . | |

INDIANA DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PAY ITEMS

PAGE: 8

CONTRACT ID: R -32502-A

LETTING DATE: August 10, 2016
REVISED:

CONTRACTOR : _____

| LINE NO | ITEM DESCRIPTION | APPROX. QUANTITY AND UNITS | UNIT PRICE DOLLARS CTS | BID AMOUNT DOLLARS CTS |
|------------|---|----------------------------------|-----------------------------|-----------------------------|
| 0075 | 808-75256 TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 8 IN. | 174.000 LFT | . | . |
| 0076 | 808-75297 TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 162.000 LFT | . | . |
| 0077 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW | 1.000 EACH | . | . |
| | SECTION 0001 TOTAL | | | . |
| | TOTAL BID | | | . |