## INDIANA DEPARTMENT OF TRANSPORTATION OFFICE OF MATERIALS MANAGEMENT

## PORTLAND CEMENT CONCRETE PLANT INSPECTION ITM No. 405-08P

#### 1.0 SCOPE.

- 1.1 This procedure covers the field inspection of PCC plants. The inspection will identify the materials used in concrete production and the procedure for the storage and sampling of aggregates, cement, pozzolans, and admixtures. The inspection also covers scale and meter verification.
- 1.2 The values stated in either acceptable English or SI metric units are to be regarded separately as standard, as appropriate for a specification with which this ITM is used. Within the text, SI metric units are shown in parenthesis. The values stated in each system may not be exact equivalents; therefore, each system shall be used independently of the other, without combining values in any way.
- 1.3 This ITM may involve hazardous materials, operations, and equipment and may not address all of the safety problems associated with the use of the test method. The user of the ITM is responsible for establishing appropriate safety and health practices and determining the applicability of regulatory limitations prior to use.
- **TERMINOLOGY**. Definitions for terms and abbreviations shall be in accordance with the Department's Standard Specifications, Section 101.
- **3.0 SIGNIFICANCE AND USE.** This ITM is used to ensure that PCC plants are capable of producing concrete in accordance with applicable Department Standard Specifications.

#### 4.0 APPARATUS.

- **4.1** Certified weights (masses)
- **4.2** Tanks and scales

#### 5.0 PROCEDURE.

- **5.1** The PCC supplier shall request a Department inspection of the PCC plant.
- **5.2** The inspection date and time shall be mutually agreed upon.
- 5.3 The PCC supplier shall ensure that the required apparatus are on site.

**5.4** The PCC plant will be inspected in accordance with the following procedures and the results recorded on the form in Appendix A.

- **5.4.1** Record the plant identification data
- **5.4.2** Inspect the aggregate storage
- **5.4.3** Inspect the aggregate conveying system
- **5.4.4** Inspect the storage and conveying system
- **5.4.5** Review the admixture control systems
- **5.4.6** Check all gates to confirm non-leakage by charging material into each bin and then into the weigh hopper
- **5.4.7** Locate the cementitious weigh hopper
- **5.4.8** Locate the aggregate weight hopper
- **5.4.9** Locate the cementitious sampling ports
- **5.4.10** Review the batching method
- **5.4.11** Examine the discharge boot
- **5.4.12** Determine if the scales zero prior to charging
- **5.4.13** Determine if a moisture probe is present
- **5.4.14** Determine where the admixtures are introduced
- **5.4.15** Determine the type of scales
- **5.4.16** Determine the method of addition and source of water
- **5.4.17** Verify that the supplier has checked the blades for wear
- **5.4.18** Locate the automatic timing device
- **5.4.19** Locate the automatic discharge locking device
- **5.4.20** Review the cold weather concreting procedure, if applicable
- **5.4.21** Have the supplier certify the admixture metering and proportioning systems

5.5 The aggregate, cementitious, and water scales will be checked in accordance with 508.02(b) and recorded on the form in Appendix A.

- **5.5.1** Record the scale identification data
- **5.5.2** Ensure that all weigh hoppers are clean and empty prior to calibration
- **5.5.3** Apply the necessary calibration equipment such as chains or platforms
- **5.5.4** Tare the scales
- **5.5.5** Load the first increment of weight (mass)
- **5.5.6** Compare to the known weight (mass) for variance
- **5.5.7** Repeat 5.5.5 and 5.5.6 in a cumulative manner throughout the working capacity of the scales, plus 10 percent. Calibration will include a minimum of four points.
- 5.6 The meters will be checked in accordance with 508.02(b) and recorded on the form in Appendix A.
  - **5.6.1** Record the meter identification data
  - **5.6.2** Instruct the plant operator to pump the first increment of volume into a tared container
  - **5.6.3** Calculate the weight (mass) of the volume in the tared container
  - **5.6.4** Measure the weight (mass) of the volume in the tared container
  - **5.6.5** Compare the measured weight (mass) to the calculated weight (mass) for variance
  - **5.6.6** Repeat 5.6.2 through and 5.6.5 in a cumulative manner throughout the working range of the meter, plus 10 percent
  - **5.6.7** The calibration will include a minimum of three consecutive passing test results.

#### 6.0 CRITICAL ELEMENTS.

6.1 The PCC plant will not be approved if the following critical elements of the plant operations are not met.

#### 6.2 Cementitious.

- **6.2.1** There is a system to prevent contamination within the silos or bins.
- **6.2.2** The conveying system prevents contamination.

#### 6.3 Weigh Hopper.

- **6.3.1** The coarse and fine aggregate gates are tight and not leaking.
- **6.3.2** The cementitious gates are tight and not leaking.
- **6.3.3** There are cementitious sampling ports.

#### 6.4 Batching.

- **6.4.1** The scales are zero prior to charging.
- **6.4.2** The water is potable or documentation is supplied indicating the water is potable in accordance with 913.01.

#### 6.5 Mixing.

- **6.5.1** The blades are in accordance with the manufacturer's recommendations.
- **6.5.2** The mixer is equipped with a timing device.
- **6.5.3** The mixer is equipped with an automatic locking device.

#### 6.6 Certification.

- **6.6.1** The supplier can certify the admixture metering system.
- **6.6.2** The supplier can certify the accuracy of the proportioning system.

### 6.7 Scales and Meters.

6.7.1 The difference between the scale reading and the actual weight (mass) applied is less than or equal to one half percent.

**6.7.2** The difference between the meter reading and the actual volume is less than or equal to one percent.

### 7.0 REPORT.

**7.1** Report Appendix A

## ITM 405 PORTLAND CEMENT CONCRETE PLANT INSPECTION

PLANT OWNERS NAME PLANT CAPAC			CITY			PLANT NUMBER	
OWNER'S HOME OFFICE ADDRESS		PLANT MANU	ER		MANUFACTURED DATE		
PLANT LOCATION AND ADDRESS			TYPE OF PLANT  □ CENTRAL			MODEL NUMBER	
PLANT AREA CODE AND PHONE NUMBER			□ SHRINK □ TRANSIT			INSPECTION DATE	
AGGREGATES CHECK SOURCES OF ALL AGGREGATES OF					GH TICKET	S FOR ALI	AGGREGATES
INTENDED FOR INDOT USE. (IDENTIFY N SIZE/TYPE SOURCE NAME AND		GREGATES AS "C	APPROVA		CLASS/ I	LEDGE	INDOT APPROVED
		<del></del>					
COMMENTS:							
CEMENTITIOUS MATERIALS CHECK SOURCES OF ALL CEMENTITIOUS FLY ASH, AND SILICA FUME. REVIEW COL							
"COMMERCIAL ONLY").  MATERIAL  TYL	PE/CLASS	SOURCE NAME	E AND NUM	BER		APPE	POVAL#
COMMENTS:							
COMMENTS.							
CHEMICAL ADMIXTURES CHECK SOURCES OF ALL ADMIXTURES F			PLANT. REV	VIEW COPIES	OF MOST I	RECENT D	ELIVERY TICKETS.
(IDENTIFY NON-INDOT MATERIALS AS "C   NAME			AND NUME	<u>BER</u>		APPE	ROVAL#
COMMENTS:		<u> </u>					

## ITM 405 PORTLAND CEMENT CONCRETE PLANT INSPECTION

AGGREGATE STORAGE YES NO  BY STOCKPILING ARE AGGREGATES KEPT FROM INTERMIXING  CORRECTIVE ACTIONS:  AGGREGATE CONVEYING SYSTEM BELT BUCKET ELEVATOR OTHER IF OTHER, EXPLAIN:	BATCHING YES NO    S BATCHING CONDUCTED MANUALLY   S BATCHING CONDUCTED AUTOMATICALLY   S BATCHING CONDUCTED AUTOMATICALLY   S DISCHARGE BOOT CLEAN AND FUNCTIONING PROPERLY   DO SCALES ZERO PRIOR TO CHARGING   S THERE A MOISTURE PROBE IN THE COARSE AGGREGATE   S THERE A MOISTURE PROBE IN THE FINE AGGREGATE  ARE BATCH TICKETS PRINTED AUTOMATICALLY MANUALLY  WHERE AND WHEN IS ADMIXTURE INTRODUCED
CEMENTITIOUS YES NO  IS THERE A SYSTEM TO PREVENT CONTAMINATION WITHIN SILOS OR BINS DOES THE CONVEYING SYSTEM PREVENT CONTAMINATION CORRECTIVE ACTIONS:	SCALES  DIAL DOAD CELL OTHER  IF OTHER, EXPLAIN:
ADMIXTURES YES NO CONTROLLED BY VOLUME CONTROLLED BY WEIGHT (MASS) ADDED MANUALLY ADDED AUTOMATICALLY	
BINS/HOPPER YES NO  ARE COARSE AND FINE AGGREGATE GATES TIGHT AND NON-LEAKING  ARE CEMENTITIOUS GATES TIGHT AND NON-LEAKING  ARE WEIGH HOPPER GATES TIGHT AND NON-LEAKING  IS THE CEMENTITIOUS WEIGHT HOPPER SEPARATE FROM THE AGGREGATE WEIGH HOPPER  IS THERE A CEMENT SAMPLING PORT IN THE SILO  IS THERE A CEMENT SAMPLING PORT IN THE WEIGH HOPPER  IS THERE A SYSTEM TO PREVENT OVERLOADS  CORRECTIVE ACTIONS:	IS WATER ADDED BY  VOLUME/METERED WEIGHT (MASS)  IS SOURCE OF WATER  COMMERCIAL OTHER  IF OTHER, EXPLAIN:  CORRECTIVE ACTIONS:

## ITM 405 PORTLAND CEMENT CONCRETE PLANT INSPECTION

MIXING YES NO  HAS THE SUPPLIER CHECKED THE BLADES FOR WEAR IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS  DATE CHECKED  STATE MIXER EQUIPPED WITH A TIMING DEVICE  STATE MIXER EQUIPPED WITH AN AUTOMATIC DISCHARGE LOCKING DEVICE  CORRECTIVE ACTIONS:	COLD WEATHER PRODUCTION YES NO  SET IS THE PLANT CAPABLE OF PROWEATHER CONCRETE SET IS THERE A SYSTEM FOR MONITOR TEMPERATURE SET CAN THE WATER BE HEATED STEAM DRY OTH	ORING
CERTIFIC	CATION	
I CERTIFY THAT THE ADMIXTURE METERING SYSTEM IS ACCUAND ONE HALF PERCENT, IF BY WEIGHT.  I ALSO CERTIFY THAT THE ACCURACY OF THE PROPORTIONIN FOLLOWING:		
ADMIXTURE	DATE	
REMARKS		
DEDARTMENT CICNATURE CUAC	CHEICA TION	DATE SIGNED
DEPARTMENT SIGNATURE CLASS	SIFICATION	DATE SIGNED
DISTRICT TESTING OFFICE TELEPHONE NUMBER		
THIS IS TO CERTIFY THAT I HAVE ACCOMPANIED THE DEPART CONCRETE PLANT AND HAVE GIVEN ALL INFORMATION, TRUI UNDERSTAND THAT ONLY INDOT APPROVED MATERIALS MAY AND PURCHASE ORDERS. I WILL CONTACT THE INDOT TESTING CHANGE ANY SOURCE, SUPPLIER, OR MATERIAL.	E AND COMPLETE, TO THE BEST OF MY Y BE INCORPATED INTO CONCRETE FOR	KNOWLEDGE. I . INDOT CONTRACTS
SUPPLIER'S SIGNATURE		DATE SIGNED
DISTRIBUTION: MATERIALS MANAGEMENT DIVISION DISTRICT TESTING ENGINEER SUPPLIER		

## ITM 405 PORTLAND CEMENT CONCRETE PLANT INSPECTION

INSPECTION OF SCALES AND METERS FOR CONCRETE PLANT								
PRODUCER PLANT LOCATION								
PLANT NO Scales and meters will be checked to the maximum capacity for which they will be used. The allowable difference between the scale reading and the actual weight applied shall be one half percent or less. Meter variation shall also be one percent or less. Scales will be checked cumulatively throughout the working capacity plus approximately ten percent. At least three points within the working range for meters will be checked.								
+ GCDEG +	THE GOLD CHECK	NT.7						
	TE SCALE CHEC		NO		CAPACITY			
WAKE		SERIAL	. NO		CALACIT I			
LOAD APPLIED								
SCALE READING								
ERROR, LBS (KG)								
PERCENT ERROR								
CEMENT S	SCALE CHECK							
MAKE		SERIAL	NO		_ CAPACITY _			
LOAD APPLIED								
SCALE READING								
ERROR, LBS (KG)								
PERCENT								
ERROR								
WATER SO	CALE CHECK							
MAKE		SERIAL	NO		_ CAPACITY			
GALLON (LITER)								
WEIGHT (MASS)								
APPLIED								
SCALE READING				_				
ERROR,								
LBS (KG)								
PERCENT ERROR								
REMARKS								

# ITM 405 A PORTLAND CEMENT CONCRETE PLANT INSPECTION

PLANT NO									
WATER SCALE CHECK (CON'T)									
		SCALE							
GALLON (LITER)									
WEIGHT (MASS) APPLIED									
SCALE READING									
ERROR, LBS (KG)									
PERCENT ERROR									
ERROR									
SCALE									
GALLON (LITER)									
WEIGHT (MASS) APPLIED									
SCALE READING									
ERROR, LBS (KG)									
PERCENT ERROR									
		SCALE							
GALLON (LITER)									
WEIGHT (MASS)									
APPLIED SCALE									
READING ERROR, LBS									
(KG) PERCENT									
ERROR									
SCALE									
GALLON (LITER)		SCALE							
WEIGHT (MASS)									
APPLIED SCALE									
READING ERROR, LBS									
(KG) PERCENT									
ERROR	<u> </u>			<u> </u>	<u> </u>	<u> </u>			