# INDIANA DEPARTMENT OF TRANSPORTATION OFFICE OF MATERIALS MANAGEMENT

# PROCEDURE FOR BENCH TESTING, FIELD TESTING, AND APPROVAL LIST REQUIREMENTS FOR ITS ETHERNET SWITCHES ITM No. 950-15P

#### 1.0 SCOPE.

- 1.1 This test procedure covers the methods that an ITS Ethernet Switch is evaluated in the field, and is placed, maintained, or removed from an approval list.
- 1.2 This ITM may involve hazardous materials, operations, and equipment and may not address all of the safety problems associated with the use of the test method. The user of the ITM is responsible for establishing appropriate safety and health practices and determining the applicability of regulatory limitations prior to use.

#### 2.0 REFERENCES.

#### 2.1 Indiana Standards.

806 Approval List Requirements

### 2.2 NTCIP Standards.

1103 NTCIP Transportation Management Protocol (TMP) 9012 NTCIP Testing Guide for Users

- **TERMINOLOGY.** Definitions for terms and abbreviations shall be in accordance with the Department's Standard Specifications, Section 101 and NEMA TS-2 Section 1.
- **4.0 SIGNIFICANCE AND USE.** This ITM is used to evaluate, approve, maintain approval, and remove from the approval listing an ITS Ethernet Switch which is placed on the Department's List of Approved Traffic Signal and ITS Control Equipment. Each model of the ITS Ethernet Switch will be bench tested and field tested separately.

#### 5.0 APPARATUS.

**5.1** Complete ITS fully functional system

ITM 950-15P 6-16-15

**6.0 SAMPLING.** The manufacturer shall furnish, at no cost to the Department, one randomly selected production-run ITS Ethernet Switch of each model for bench testing and field testing.

## 7.0 PROCEDURE.

- 7.1 The manufacturer of the material shall submit the Preliminary Product Material Evaluation Form (Appendix A) for each model type of the ITS Ethernet Switch which the manufacturer is requesting to be added to the listing.
- **7.2** The manufacturer of the material shall submit with the Evaluation Form the following:
  - **7.2.1** An invoice showing an initial zero dollar amount (\$0.00) for the use of the evaluation sample material during the evaluation. The invoice shall also list the deferred cost of the material that the Department would pay if the material is purchased the instead of returned upon the successful completion of the evaluation.
  - 7.2.2 A certification of environmental testing shall be furnished with each major unit approval request indicating the unit has been tested and is in accordance with the environmental requirements from NTCIP. The certification shall specify the model and serial number of the ITS Ethernet Switch tested. A complete log of each test shall be provided to the Department and will be maintained by the Department. The log shall show which, if any, component failed during the test, when the component failed, and what steps were taken to repair the AFP. The log shall include the date of testing, name and title of person conducting the tests, a record of conditions throughout the tests, and a temperature and humidity verses time chart. The maximum report interval of any chart shall be 24 h. The chart shall be from a recording machine used to monitor the status of the environmental chamber during testing.
  - **7.2.3** Operation and Maintenance Manual(s), including theory of operation, schematics and components parts listing
  - **7.2.4** One randomly selected production run ITS Ethernet Switch for bench testing and field testing
  - **7.2.5** List of required software and any additional items required to realize the full potential of the product
- **8.0 SUBMITTAL REVIEW.** The documentation, including the environmental testing, will be reviewed for usability of the ITS Ethernet Switch with Department approved NTCIP based ITS system in Indiana. The manufacturer's recommended schedule and extent of maintenance will be reviewed for acceptability.

ITM 950-15P 6-16-15

**9.0 BENCH TESTING.** The ITS Ethernet Switch will be bench tested for compatibility with all ITS equipment assemblies used by the Department. The ITS Ethernet Switch will be verified for full NTCIP functionality and full manufacturer's claimed optional functionality.

- **10.0 FIELD TESTING.** The field testing of the ITS Ethernet Switch will consist of installing the ITS Ethernet Switch in an actual ITS cabinet for a period of up to 12 months to monitor the following:.
  - **10.1** A log of any failures for the ITS Ethernet Switch
  - **10.2** The relative ease of use for the field personnel
  - 10.3 Overall build quality and expected lifecycle of the ITS Ethernet Switch. The build quality and expected life shall be comparable with existing ITS Ethernet Switches.
- **11.0 REPORT.** A final report will include the notations and findings from the electronic bench test and field testing results and documentation.

#### 12.0 APPROVAL LIST.

- **12.1 Approval of ITS Ethernet Switch.** The ITS Ethernet Switch model may be placed on the approval list when the following conditions are met:
  - **12.1.1** A potential net benefit to the Department is realized by inclusion of the item on the list.
  - **12.1.2** The unit passes the NTCIP environmental requirements
  - **12.1.3** The required documentation is submitted.
  - **12.1.4** The bench and field testing are completed with satisfactory results.
  - **12.1.5** No excessive amount of routine or periodic maintenance is required.
  - **12.1.6** There are no failures with any of the different types of ITS assemblies or individual components used by the Department.
  - **12.1.7** All manuals, documents, and required software to realize the full potential of the Aries Field Processor are submitted.
  - **12.1.8** Only minimal maintenance operations were necessary during the field testing.

ITM 950-15P 6-16-15

# 12.2 Maintaining Approval.

**12.2.1** The ITS Technology Deployment Division of TMBU shall be notified each time any update or revision is made and an explanation of the benefits of the change shall be submitted. Operations Support Division will determine if and to what extent a revision is to be placed into field operation and may fully re-evaluate the ITS Ethernet Switch with the revision.

- 12.2.2 If the manufacturer makes any changes to an approved model to correct a non-NTCIP compliant or safety issue, the Department shall be notified immediately. The manufacturer shall correct all existing equipment purchased by the Department either directly, by contract, or through agreement prior to the change being incorporated at the manufacturer's production level.
- **12.2.3** A design change to an approved model shall require a submittal of documented changes. At the discretion of the Department, resubmission of the model for testing, and evaluation may be required. Permanent addition or removals of component parts or wires, printed circuit board modifications, or revisions to memory or processor software, are examples of items that are considered to be design changes.
- **12.3 Removal from Approval List.** ITS Ethernet Switch will be removed from an approval list for, but not limited to, the following reasons:
  - **12.3.1** Changes in the ITS Ethernet Switch components or production process that fail testing and/or evaluation
  - **12.3.2** If three consecutive years elapse without furnishing the ITS Ethernet Switch
  - **12.3.3** Performance of the ITS Ethernet Switch no longer meets the intended purpose
  - **12.3.4** Recurring similar product failures indicate a manufacturer's defect

# INDIANA DEPARTMENT OF TRANSPORTATION DIVISION OF OPERATIONS SUPPORT PRELIMINARY INFORMATION FOR PRODUCT MATERIAL EVALUATION

Trade Name		Date	
Manufacturer	Patented? Yes _	No	Applied for
Address			
Street No (P. O. Box)	City	State	Zip Code
Representative		Phone No	0 ( )
Address			
Street No (P. O. Box)	City	State	Zip Code
Product Information			
Materials Composition			
** Is this product considered HAZA surplus materials? Yes N		L when disposi	ng of non-used or
** What is the shelf life of this mater	ial? Years	Months	N/A
Recommended Use-Primary			
Recommended Use-Alternate			

Advantages an	d/or Benefits		
literature, test is submitted with	results, guarantee, ha this form. In the cas	zardous material data sh se of electronic devices t	eration manual, maintenance manual, eets, plan, picture or sketch must be the schematic diagram, parts list, and cuit board within the device.
Meets following	ng specifications:		
AASHTO		_	
ASTM			
Use by highwa	y authorities or simil	lar agencies in other state	es.
Agency	Years Used		Remarks
** Has produc	t ever been evaluated	by and rejected for use	by a governmental agency?
Yes	_ No If	yes, by what agency and	for what reason?
		/es No	
Availability: \$	Seasonal	_ Nonseasonal	Delivery at site
After receipt o	f order, are quantities	s limited? Yes	No

** Will FREE SAMPLES be furnished? Yes No If yes, Quantity Furnished
** If the sample is salvageable, do you desire to have it returned Yes No
(Desired return of salvageable samples will be at the supplier's expense.) (The manufacturer agrees upon the return of salvageable samples, such samples may be damaged or non-operable. Normal care will be taken that the samples, when returned, are in operable condition; INDOT, however, does not guarantee that the returned samples are operable.)
Will laboratory analysis be furnished? Yes No
** Approximate cost Royalty Cost
When was the product introduced to the market?
This product is an alternate for what product?
Will warranty be provided? Yes No If yes, for how long?
Background of company, including principal products
What offices of the Indiana Department of Transportation have been contacted?
Additional Information
(Attach additional sheets as necessary)

6-16-15

Person fu	rnishing information			
	_	Name	Т	itle
Address				
	Street No (P. O. Box)	City	State	Zip Code

Items marked \*\* <u>MUST BE RESPONDED TO</u> or further consideration may not be given for this product.

Please mail this form to: Manager, Office of Traffic Engineering

100 N. Senate Ave., Room N925 Indianapolis, IN 46204-2249

If INDOT elects to evaluate your product/material - traffic signal equipment will be shipped to:

Electronic Technician 1 Indiana Department of Transportation 7701 East Melton Street Gary, IN 46403

While all other materials to be evaluated will be shipped to:

ITS Field Engineer Indiana Department of Transportation 8620 East 21<sup>st</sup> Street Indianapolis, IN 46219