

**INDIANA DEPARTMENT OF TRANSPORTATION
OFFICE OF MATERIALS MANAGEMENT**

**PORTLAND CEMENT CONCRETE PLANT INSPECTION
ITM No. 405-06P**

1.0 SCOPE.

- 1.1** This procedure covers the field inspection of PCC plants. The inspection will identify the materials used in concrete production and the procedure for the storage and sampling of aggregates, cement, pozzolans, and admixtures. The inspection also covers scale and meter verification.
- 1.2** The values stated in either acceptable English or SI metric units are to be regarded separately as standard, as appropriate for a specification with which this ITM is used. Within the text, SI metric units are shown in parenthesis. The values stated in each system may not be exact equivalents; therefore each system shall be used independently of the other, without combining values in any way.
- 1.3** This procedure may involve hazardous materials, operations, and equipment. This ITM may not address all of the safety problems associated with the use of the test method. The user of the ITM is responsible for establishing the appropriate safety and health practices and determining the applicability of regulatory limitations prior to use.

2.0 TERMINOLOGY

- 2.1 Terms and Abbreviations.** Definitions for terms and abbreviations shall be in accordance with the Department's Standard Specifications, Section 101.

3.0 SIGNIFICANCE AND USE. This ITM is used to ensure that PCC plants are capable of producing concrete in accordance with applicable Department Standard Specifications.

4.0 APPARATUS.

- 4.1** Certified weights (masses)
- 4.2** Tanks and scales

5.0 PROCEDURE.

- 5.1** The PCC supplier shall request a Department inspection of the PCC plant in accordance with 106.03 and 508.02.
- 5.2** The inspection date and time will be mutually agreed upon.
- 5.3** The PCC supplier shall ensure that the required apparatus are on site.

- 5.4** The PCC plant will be inspected in accordance with the following procedures and the results recorded on the form in APPENDIX A.
- 5.4.1** Record the plant identification data
 - 5.4.2** Inspect the aggregate storage
 - 5.4.3** Inspect the aggregate conveying system
 - 5.4.4** Inspect the storage and conveying system
 - 5.4.5** Review the admixture control systems
 - 5.4.6** Check all gates to confirm non-leakage by charging material into each bin and then into the weigh hopper
 - 5.4.7** Locate the cementitious weigh hopper
 - 5.4.8** Locate the aggregate weight hopper
 - 5.4.9** Locate the cementitious sampling ports
 - 5.4.10** Review the batching method
 - 5.4.11** Examine the discharge boot
 - 5.4.12** Determine if the scales zero prior to charging
 - 5.4.13** Determine if a moisture probe is present
 - 5.4.14** Determine where the admixtures are introduced
 - 5.4.15** Determine the type of scales
 - 5.4.16** Determine the method of addition and source of water
 - 5.4.17** Verify that the supplier has checked the blades for wear
 - 5.4.18** Locate the automatic timing device
 - 5.4.19** Locate the automatic discharge locking device
 - 5.4.20** Review the cold weather concreting procedure,if applicable
 - 5.4.21** Have the supplier certify the admixture metering and proportioning systems

5.5 The aggregate, cementitious, and water scales will be checked in accordance with 508.02(b) and recorded on the form in APPENDIX A.

5.5.1 Record the scale identification data

5.5.2 Ensure that all weigh hoppers are clean and empty prior to calibration

5.5.3 Apply the necessary calibration equipment; chains, platforms, and etc.

5.5.4 Tare the scales

5.5.5 Load the first increment of weight (mass)

5.5.6 Compare to the known weight (mass) for variance

5.5.7 Repeat 6.5.5 and 6.5.6 in a cumulative manner throughout the working capacity of the scales, plus ten percent. Calibration will include a minimum of four points.

5.6 The meters will be checked in accordance with 508.02(b) and recorded on the form in Appendix A.

5.6.1 Record the meter identification data

5.6.2 Instruct the plant operator to pump the first increment of volume into a tared container

5.6.3 Calculate the weight (mass) of the volume in the tared container

5.6.4 Measure the weight (mass) of the volume in the tared container

5.6.5 Compare the measured weight (mass) to the calculated weight (mass) of for variance

5.6.6 Repeat 6.6.2 through and 6.6.5 in a cumulative manner throughout the working range of the meter, plus ten percent

5.6.7 The calibration will include a minimum of three consecutive passing test results.

6.0 CRITICAL ELEMENTS.

6.1 The PCC plant will not be approved if the following critical elements of the plant operations are not met.

6.2 Cementitious Critical Elements

6.2.1 There is a system to prevent contamination within the silos or bins.

6.2.2 The conveying system prevents contamination.

6.3 Weigh Hopper Critical Elements

6.3.1 The coarse and fine aggregate gates are tight and not leaking.

6.3.2 The cementitious gates are tight and not leaking.

6.3.3 There are cementitious sampling ports.

6.4 Batching Critical Elements

6.4.1 The scales are zero prior to charging.

6.4.2 The water is potable or documentation is supplied indicating the water is potable in accordance with 913.01.

6.5 Mixing Critical Elements

6.5.1 The blades are in accordance with manufacturer's recommendations.

6.5.2 The mixer is equipped with a timing device.

6.5.3 The mixer is equipped with an automatic locking device.

6.6 Certification Critical Elements

6.6.1 The supplier can certify the admixture metering system.

6.6.2 The supplier can certify the accuracy of the proportioning system.

6.7 Scales and Meters Critical Elements

6.7.1 The difference between the scale reading and the actual weight (mass) applied is less than or equal to one half percent.

6.7.2 The difference between the meter reading and the actual volume is less than or equal to one percent.

7.0 **REPORT.**

7.1 Report APPENDIX A.

7.2 Distributed as identified.

ITM 405
APPENDIX A
PORTLAND CEMENT CONCRETE PLANT INSPECTION

PLANT OWNERS NAME		PLANT CAPACITY		PLANT NUMBER	
OWNER'S HOME OFFICE ADDRESS		PLANT MANUFACTURER		MANUFACTURED DATE	
PLANT LOCATION AND ADDRESS			TYPE OF PLANT <input type="checkbox"/> CENTRAL <input type="checkbox"/> SHRINK <input type="checkbox"/> TRANSIT	MODEL NUMBER	
PLANT AREA CODE AND PHONE NUMBER				INSPECTION DATE	
<u>AGGREGATES</u> CHECK SOURCES OF ALL AGGREGATES USED AT PLANT. REVIEW COPIES OF MOST RECENT WEIGH TICKETS FOR ALL AGGREGATES INTENDED FOR INDOT USE. (IDENTIFY NON-INDOT AGGREGATES AS "COMMERCIAL ONLY").					
<u>SIZE/TYPE</u>	<u>SOURCE NAME AND NUMBER</u>	<u>APPROVAL (Q#)</u>	<u>CLASS/LEDGE</u>	<u>INDOT APPROVED</u>	
_____	_____	_____	_____	_____	
_____	_____	_____	_____	_____	
_____	_____	_____	_____	_____	
_____	_____	_____	_____	_____	
COMMENTS: _____					
<u>CEMENTITIOUS MATERIALS</u> CHECK SOURCES OF ALL CEMENTITIOUS MATERIALS POTENTIALLY UTILIZED AT THE PLANT. THIS WILL INCLUDE CEMENT, GGBFS, FLY ASH, AND SILICA FUME. REVIEW COPIES OF MOST RECENT BILLS OF LADING. (IDENTIFY NON-INDOT MATERIALS AS "COMMERCIAL ONLY").					
<u>MATERIAL</u>	<u>TYPE/CLASS</u>	<u>SOURCE NAME AND NUMBER</u>	<u>APPROVAL #</u>		
_____	_____	_____	_____		
_____	_____	_____	_____		
_____	_____	_____	_____		
_____	_____	_____	_____		
COMMENTS: _____					
<u>CHEMICAL ADMIXTURES</u> CHECK SOURCES OF ALL ADMIXTURES POTENTIALLY UTILIZED AT THE PLANT. REVIEW COPIES OF MOST RECENT DELIVERY TICKETS. (IDENTIFY NON-INDOT MATERIALS AS "COMMERCIAL ONLY").					
<u>NAME</u>	<u>TYPE</u>	<u>SOURCE NAME AND NUMBER</u>	<u>APPROVAL #</u>		
_____	_____	_____	_____		
_____	_____	_____	_____		
_____	_____	_____	_____		
_____	_____	_____	_____		
COMMENTS: _____					

ITM 405
APPENDIX A
PORTLAND CEMENT CONCRETE PLANT INSPECTION

<p>AGGREGATE STORAGE YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> BY STOCKPILING <input type="checkbox"/> <input type="checkbox"/> IN BINS <input type="checkbox"/> <input type="checkbox"/> ARE AGGREGATES KEPT FROM INTERMIXING</p> <p>CORRECTIVE ACTIONS: _____ _____ _____</p> <p>AGGREGATE CONVEYING SYSTEM <input type="checkbox"/> BELT <input type="checkbox"/> BUCKET ELEVATOR <input type="checkbox"/> OTHER IF OTHER, EXPLAIN: _____ _____ _____</p>	<p>BATCHING YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> IS BATCHING CONDUCTED MANUALLY <input type="checkbox"/> <input type="checkbox"/> IS BATCHING CONDUCTED AUTOMATICALLY <input type="checkbox"/> <input type="checkbox"/> IS DISCHARGE BOOT CLEAN AND FUNCTIONING PROPERLY <input type="checkbox"/> <input type="checkbox"/> DO SCALES ZERO PRIOR TO CHARGING <input type="checkbox"/> <input type="checkbox"/> IS THERE A MOISTURE PROBE IN THE COARSE AGGREGATE <input type="checkbox"/> <input type="checkbox"/> IS THERE A MOISTURE PROBE IN THE FINE AGGREGATE</p> <p>ARE BATCH TICKETS PRINTED <input type="checkbox"/> AUTOMATICALLY <input type="checkbox"/> MANUALLY</p> <p>WHERE AND WHEN IS ADMIXTURE INTRODUCED _____ _____ _____</p> <p>SCALES <input type="checkbox"/> DIAL <input type="checkbox"/> LOAD CELL <input type="checkbox"/> OTHER</p> <p>IF OTHER, EXPLAIN: _____ _____ _____ _____ _____ _____</p>
<p>CEMENTITIOUS YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> IS THERE A SYSTEM TO PREVENT CONTAMINATION WITHIN SILOS OR BINS <input type="checkbox"/> <input type="checkbox"/> DOES THE CONVEYING SYSTEM PREVENT CONTAMINATION</p> <p>CORRECTIVE ACTIONS: _____ _____ _____</p>	<p>_____</p> <p>_____</p> <p>_____</p>
<p>ADMIXTURES YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> CONTROLLED BY VOLUME <input type="checkbox"/> <input type="checkbox"/> CONTROLLED BY WEIGHT (MASS) <input type="checkbox"/> <input type="checkbox"/> ADDED MANUALLY <input type="checkbox"/> <input type="checkbox"/> ADDED AUTOMATICALLY</p>	<p>_____</p> <p>_____</p> <p>_____</p> <p>_____</p> <p>_____</p>
<p>BINS/HOPPER YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> ARE COARSE AND FINE AGGREGATE GATES TIGHT AND NON-LEAKING <input type="checkbox"/> <input type="checkbox"/> ARE CEMENTITIOUS GATES TIGHT AND NON-LEAKING <input type="checkbox"/> <input type="checkbox"/> ARE WEIGH HOPPER GATES TIGHT AND NON-LEAKING <input type="checkbox"/> <input type="checkbox"/> IS THE CEMENTITIOUS WEIGHT HOPPER SEPARATE FROM THE AGGREGATE WEIGH HOPPER <input type="checkbox"/> <input type="checkbox"/> IS THERE A CEMENT SAMPLING PORT IN THE SILO <input type="checkbox"/> <input type="checkbox"/> IS THERE A CEMENT SAMPLING PORT IN THE WEIGH HOPPER <input type="checkbox"/> <input type="checkbox"/> IS THERE A SYSTEM TO PREVENT OVERLOADS</p> <p>CORRECTIVE ACTIONS: _____ _____ _____</p>	<p>IS WATER ADDED BY <input type="checkbox"/> VOLUME/METERED <input type="checkbox"/> WEIGHT (MASS)</p> <p>IS SOURCE OF WATER <input type="checkbox"/> COMMERCIAL <input type="checkbox"/> OTHER</p> <p>IF OTHER, EXPLAIN: _____ _____ _____</p> <p>CORRECTIVE ACTIONS: _____ _____ _____ _____ _____ _____</p>

ITM 405
APPENDIX A
PORTLAND CEMENT CONCRETE PLANT INSPECTION

<p>MIXING YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> HAS THE SUPPLIER CHECKED THE BLADES FOR WEAR IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS</p> <p>DATE CHECKED _____</p> <p><input type="checkbox"/> <input type="checkbox"/> IS THE MIXER EQUIPPED WITH A TIMING DEVICE</p> <p><input type="checkbox"/> <input type="checkbox"/> IS THE MIXER EQUIPPED WITH AN AUTOMATIC DISCHARGE LOCKING DEVICE</p> <p>CORRECTIVE ACTIONS: _____</p> <p>_____</p> <p>_____</p> <p>_____</p>	<p>COLD WEATHER PRODUCTION YES NO</p> <p><input type="checkbox"/> <input type="checkbox"/> IS THE PLANT CAPABLE OF PRODUCING COLD WEATHER CONCRETE</p> <p><input type="checkbox"/> <input type="checkbox"/> IS THERE A SYSTEM FOR MONITORING TEMPERATURE</p> <p><input type="checkbox"/> <input type="checkbox"/> CAN THE WATER BE HEATED</p> <p><input type="checkbox"/> <input type="checkbox"/> CAN THE AGGREGATES BE HEATED</p> <p style="padding-left: 40px;"><input type="checkbox"/> STEAM <input type="checkbox"/> DRY <input type="checkbox"/> OTHER</p>						
<p>CERTIFICATION</p> <p>I CERTIFY THAT THE ADMIXTURE METERING SYSTEM IS ACCURATE AND MAINTAINED TO ONE PERCENT, IF BY VOLUME AND ONE HALF PERCENT, IF BY WEIGHT.</p> <p>I ALSO CERTIFY THAT THE ACCURACY OF THE PROPORTIONING SYSTEM IS MAINTAINED IN ACCORDANCE WITH THE FOLLOWING:</p> <p style="padding-left: 40px;">ADMIXTURE.....±3 %</p> <p style="padding-left: 40px;">AGGREGATES.....± 2 %</p> <p style="padding-left: 40px;">CEMENTITIOUS MATERIALS.....± 1 %</p> <p style="padding-left: 40px;">WATER.....± 1 %</p>							
<table style="width: 100%; border: none;"> <tr> <td style="border: none; width: 33%; text-align: center;">_____</td> <td style="border: none; width: 33%; text-align: center;">_____</td> <td style="border: none; width: 33%; text-align: center;">_____</td> </tr> <tr> <td style="border: none; text-align: center;">SUPPLIER'S SIGNATURE</td> <td style="border: none; text-align: center;">TITLE</td> <td style="border: none; text-align: center;">DATE</td> </tr> </table>		_____	_____	_____	SUPPLIER'S SIGNATURE	TITLE	DATE
_____	_____	_____					
SUPPLIER'S SIGNATURE	TITLE	DATE					
<p>REMARKS</p> <p>_____</p> <p>_____</p> <p>_____</p>							
DEPARTMENT SIGNATURE	CLASSIFICATION	DATE SIGNED					
DISTRICT TESTING OFFICE TELEPHONE NUMBER							
<p>THIS IS TO CERTIFY THAT I HAVE ACCOMPANIED THE DEPARTMENT ON THIS INSPECTION FOR THE ABOVE NAMED CONCRETE PLANT AND HAVE GIVEN ALL INFORMATION, TRUE AND COMPLETE, TO THE BEST OF MY KNOWLEDGE. I UNDERSTAND THAT ONLY INDOT APPROVED MATERIALS MAY BE INCORPORATED INTO CONCRETE FOR INDOT CONTRACTS AND PURCHASE ORDERS. I WILL CONTACT THE INDOT TESTING OFFICE TO UPDATE THIS MATERIAL APPROVAL LIST IF WE CHANGE ANY SOURCE, SUPPLIER, OR MATERIAL.</p>							
SUPPLIER'S SIGNATURE		DATE SIGNED					
<p>DISTRIBUTION:</p> <p>MATERIALS MANAGEMENT DIVISION</p> <p>DISTRICT TESTING ENGINEER</p> <p>SUPPLIER</p>							

ITM 405
APPENDIX A
PORTLAND CEMENT CONCRETE PLANT INSPECTION
INSPECTION OF SCALES AND METERS FOR CONCRETE PLANT

PRODUCER _____ PLANT LOCATION _____
PLANT NO. _____

Scales and meters will be checked to the maximum capacity for which they will be used. The allowable difference between the scale reading and the actual weight applied shall be one half percent or less. Meter variation shall also be one percent or less. Scales will be checked cumulatively throughout the working capacity plus approximately ten percent. At least three points within the working range for meters will be checked.

AGGREGATE SCALE CHECK

MAKE _____ SERIAL NO. _____ CAPACITY _____

LOAD APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							

CEMENT SCALE CHECK

MAKE _____ SERIAL NO. _____ CAPACITY _____

LOAD APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							

WATER SCALE CHECK

MAKE _____ SERIAL NO. _____ CAPACITY _____

GALLON (LITER)							
WEIGHT (MASS) APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							

REMARKS

ITM 405 A
APPENDIX A
PORTLAND CEMENT CONCRETE PLANT INSPECTION

PLANT NO _____							
WATER SCALE CHECK (CON'T)							
_____ SCALE							
GALLON (LITER)							
WEIGHT (MASS) APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							
_____ SCALE							
GALLON (LITER)							
WEIGHT (MASS) APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							
_____ SCALE							
GALLON (LITER)							
WEIGHT (MASS) APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							
_____ SCALE							
GALLON (LITER)							
WEIGHT (MASS) APPLIED							
SCALE READING							
ERROR, LBS (KG)							
PERCENT ERROR							

