

Summer 2001 Outlook

Introduction

Summer Supply Resources

Demand Forecast

Transmission System Performance

Communication Plan

Generation Capacity Planning

Concerns

Conclusion



Summer Supply Status

Summer Supply Resources


- Historically High Unit Availability
- Focused Maintenance Activities
- Availability Goals
- Energy Purchases



COAL FIRED STEAM SYSTEM

<u>Historical</u> perating Availability

Summer Supply Resources






COAL FIRED STEAM SYSTEM

Availability at Summer Peak Hour

Summer Supply Resources



VECTREN System Capacity

Summer Supply Resources

Coal Generation 1056 MW

Combustion Turbine 215 MW

Purchased Capacity 79 MW

Total 1350 MW

Interruptible DLC Capabilities

Summer Supply Resources

Interruptible

DLC, normal

DLC, emergency

65 MW


30 MW

50 MW

COAL FIRED STEAM SYSTEM

Summer Peak Load

Demand Forecast



Meet the Peak Summary

Demand Forecast

System Capability 1350 MW

Interruptible 65 MW

DLC <u>50 MW</u>

Total Capability 1465 MW

2001 Projected Peak 1260 MW

<u>System Margin (16.4)%</u> <u>205 MW</u>

Special Provisions

Demand Forecast

•	Voluntary	Capacity	Releases	75 MW
---	-----------	----------	----------	-------

- Internal Use Reduction Plans 10 MW
- Conservation Request 30 MW
- ECAR ARS
- Guaranteed generation purchase
- Emergency Load Reduction Plan



Transmission System Performance

Internal Operations

Under normal and single contingency conditions, system capacity is adequate to serve native load.

Under certain conditions select transformers outside of our system overload and reduce our import capability.



Transmission System Performance

External Operations

Under heavy north to south regional flows, with loss of certain transmission lines at Big Rivers, VECTREN Z82 interconnection to LG&E can become overloaded.



Communication Plan

June / July Bill Insert


Conservation Appeal

- News Release
- Key Accounts Phone Appeal
- Media Spots



Generation Capacity Plan

- Co-generation project has been cancelled.
- IRP calls for 80 MW of new capacity by 2002.
- Filed petition to install 80 MW Peaking Unit. Plan to have in service by June, 2002.
- Current review of IRP indicates need for second block of capacity in 2004.



<u>Concerns</u>

Summer Supply Resources/Demand Forecast

- Contractual Reliability
- Transmission Constraints
- Extended Heat Wave
- Environmental Impacts
- Drought



Conclusion

Based upon forecasted demand for electricity and historical reliability of system generating and transmission capacity, VECTREN anticipates it will be able to provide reliable service to firm native load customers including an adequate margin.

However, unforeseen system generation outages or significant disturbances in the eastern interconnection could effect that capability.

