## ARTICLE 2. GENERAL PROVISIONS

### **Rule 1. Definitions**

#### 135 IAC 2-1-1 Definitions

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 1. The following definitions apply throughout this article unless the context indicates another or different meaning or intent:

- (1) "Aircraft" means any contrivance used or designed for navigation of or flight in the air.
- (2) "Authority" means the Indiana finance authority.
- (3) "Automatic lane" means those entry or exit lanes located at toll plazas that are:
  - (A) generally unattended by toll attendants; and
  - (B) equipped with automatic:
    - (i) ticket dispensers; or
    - (ii) coin receptacles;

for the collection of specified tolls.

- (4) "Axle" means the common axis of rotation of one (1) or more wheels:
  - (A) whether power driven or freely rotating;
  - (B) whether in one (1) or more segments; and
  - (C) regardless of the number of wheels carried thereon.
- (5) "Axle weight" means the total weight concentrated on one (1) or more axles spaced less than forty (40) inches from center to center.
- (6) "Bicycle" means any vehicle irrespective of the number of wheels in contact with the ground that has the possibility of being foot propelled.
- (7) "Bus" means any vehicle designed for the transportation of sixteen (16) or more persons.
- (8) "Concessionaire" means the operator of the toll road as designated by the governor on March 29, 2006 under IC 8-15.5-4-11(b).
- (9) "Control devices and signals" means all:
  - (A) signs;
  - (B) signals;
  - (C) markings; and
  - (D) devices:

placed or erected on the toll road, as defined in this section, for the purpose of regulating, warning, or guiding traffic.

- (10) "Converter dolly" means a one (1) or two (2) axle vehicle:
  - (A) designed to convert a semitrailer into a trailer; and
  - (B) usually coupled to a semitrailer for the purpose of making up a tandem trailer combination.
- (11) "Cross-over" means a paved area in the median strip provided for the use of authorized vehicles to cross the median strip.
- (12) "Deceleration lanes and acceleration lanes" means speed change lanes provided for vehicles entering and exiting service areas or interchanges adjacent to the outer traffic lanes.
- (13) "Department" means the Indiana department of transportation.
- (14) "Disabled vehicle" means any vehicle temporarily incapable of movement.
- (15) "Electronic tolling system" means an electronic tolling system to be implemented by the concessionaire pursuant to a public-private agreement pursuant to IC 8-15.5.
- (16) "Emergency vehicle" means the following:
  - (A) Fire and police vehicles.
  - (B) Ambulances.
  - (C) Other vehicles authorized by the authority.
- (17) "Gross weight" means the total weight of a vehicle or combination of vehicles, including the weight of the following:

- (A) The vehicle or vehicles.
- (B) Loads.
- (C) Drivers.
- (D) Fuel.
- (E) Spare tire.
- (18) "Interchange" means that portion of the toll road:
  - (A) beginning at the point where entrance and exit roads join:
    - (i) federal;
    - (ii) state;
    - (iii) county; or
    - (iv) city;

highways or streets;

- (B) ending at the point where the toll road traffic lanes join the deceleration and acceleration lanes, as defined in this section; and
- (C) including all:
  - (i) bridges;
  - (ii) underpasses;
  - (iii) overpasses;
  - (iv) toll plazas; or
  - (v) parking areas;

located between the points referenced in clauses (A) and (B).

- (19) "LCV double" means an LCV consisting of a:
  - (A) truck-tractor;
  - (B) semitrailer;
  - (C) converter dolly; and
  - (D) second semitrailer:

complying with the requirements in 135 IAC 2-7-2.

- (20) "LCV triple" means a combination of vehicles consisting of:
  - (A) a truck-tractor;
  - (B) a semitrailer; and
  - (C) two (2) trailers;

complying with the requirements in 135 IAC 2-7-2.

- (21) "Longer combination vehicle" or "LCV" means an LCV double or LCV triple combination.
- (22) "Median strips" means the area between the inner traffic lane for westbound traffic and the inner traffic lane for eastbound traffic, including the following:
  - (A) Concrete barriers.
  - (B) Grassy areas.
  - (C) Inner shoulders.
- (23) "Michigan trains" means a combination of three (3) vehicles consisting of a:
  - (A) truck-tractor;
  - (B) semitrailer; and
  - (C) trailer;

complying with the requirements of 135 IAC 2-8-2 hereafter, that exceeds ninety thousand (90,000) pounds.

- (24) "Motorcycle" means every vehicle designed to travel on not more than three (3) wheels in contact with the ground.
- (25) "Operator" means every person who:
  - (A) drives or is in actual physical control of a vehicle upon the toll road; or
  - (B) is exercising control over or steering a vehicle being towed or pushed by another vehicle.
- (26) "Oversize or unusual vehicle" means those vehicles exceeding the allowable dimensions set forth in 135 IAC 2-4-1 hereafter.

- (27) "Parking" means the stopping or standing of a vehicle whether occupied or not. A vehicle shall not be deemed to be parked if stopped temporarily for any of the following reasons:
  - (A) Because its movement is obstructed.
  - (B) While waiting to enter or exit a toll booth lane.
  - (C) In obedience to:
    - (i) the direction of a police officer, toll attendant, or other toll road employee assigned to traffic control work; or
    - (ii) an official sign, signal, marking, or device.
  - (D) Because it is disabled.
- (28) "Pedestrian" means any natural person afoot.
- (29) "Permitted company" means a company as described in 135 IAC 2-7-21.
- (30) "Person" means any of the following:
  - (A) A natural person.
  - (B) A firm.
  - (C) A copartnership.
  - (D) An association.
  - (E) A corporation.
  - (F) A legal entity.
- (31) "Police officer" means all officers of the Indiana state police assigned to duty on the toll road by the superintendent of state police.
- (32) "Public police officer" means peace officers of:
  - (A) the United States; or
  - (B) Indiana or its political subdivisions;

while in discharge of their official duties.

- (33) "Radioactive material" means any material, or combination of materials, that spontaneously emits ionizing radiation, excepting only those specifically exempted from control by the hazardous materials regulations of the United States Department of Transportation, Federal Highway Administration.
- (34) "Semitrailer" means every vehicle without motive power:
  - (A) designed for:
    - (i) carrying persons or property;
    - (ii) being drawn by another vehicle;
  - (B) constructed so that some part of its weight and load:
    - (i) rests upon; or
    - (ii) is carried by;

another vehicle.

- (35) "Shoulders" means the paved strips adjoining the following:
  - (A) Traffic lanes.
  - (B) Acceleration and deceleration lanes.
  - (C) Interchange ramps.
- (36) "Tandem axle group" means two (2) or more axles spaced:
  - (A) more than forty (40) inches; and
  - (B) less than ninety-six (96) inches.
- (37) "Toll" means the fees collected by the concessionaire for the use of the toll road and includes all revenues charged by or on behalf of the concessionaire in respect of vehicles using the toll road during the term of any public-private agreement entered into in accordance with IC 8-15.5-4, including revenues collected through an electronic tolling system.
- (38) "Toll attendant" means a toll road employee assigned to and on duty at a toll plaza for the purpose of:
  - (A) collecting tolls; or
  - (B) issuing toll tickets.
- (39) "Toll plaza" means the portion of the toll road:

- (A) beginning where the pavement widens on the approach to the toll booths;
- (B) ending at the point where the pavement narrows to the normal width of roadway after passing the toll booths; and
- (C) including all booths and buildings located thereon.
- (40) "Toll road" means all:
  - (A) traffic lanes:
  - (B) acceleration lanes:
  - (C) deceleration lanes;
  - (D) shoulders;
  - (E) median strips;
  - (F) bridges;
  - (G) overpasses;
  - (H) underpasses;
  - (I) interchanges;
  - (J) approaches;
  - (K) entrance and exit ramps;
  - (L) toll plazas;
  - (M) travel plazas;
  - (N) maintenance areas; and
  - (O) other areas adjacent thereto;

comprising a part of the Indiana east-west toll road.

- (41) "Toll road employee" means each person in the official employ of the concessionaire.
- (42) "Traffic" means vehicles, either singly or together, using any portion of the toll road for the purpose of travel.
- (43) "Traffic control signal" means any device, whether:
  - (A) manually;
  - (B) electrically; or
  - (C) mechanically;

operated, by which traffic on the toll road is regulated.

- (44) "Traffic lanes" means the four (4) or six (6) continuous traffic lanes (each for a single line of vehicles) extending between the eastern and western termini of the toll road. These four (4) or six (6) traffic lanes are in two (2) or three (3) lanes, which lanes are separated by the median strip. The lanes that lie generally to the north of the median strip are for westbound traffic, and the lanes that lie generally to the south of the median strip are for eastbound traffic.
- (45) "Trailer" means a vehicle without motive power designed for carrying property.
- (46) "Travel plaza" means the portion of the toll road right-of-way occupied by the:
  - (A) restaurant buildings:
  - (B) fuel stations; and
  - (C) parking and seeded areas adjacent thereto;

including the deceleration lanes and acceleration lanes provided for entering and exiting the areas.

- (47) "Truck-tractor" means every vehicle:
  - (A) designed and used primarily for drawing other vehicles; and
  - (B) constructed so as not to carry a load other than a part of the weight of the vehicle and load so drawn.

Nothing in this section prohibits the transportation of motor vehicles on part of the truck-tractor.

(48) "Vehicle" means every device (motorized or nonmotorized) in, upon, or by which any person or property is or may be transported or drawn upon a highway.

(Indiana Finance Authority; 135 IAC 2-1-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 321; errata, 7 IR 1054; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2899; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3397; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## Rule 2. Operation of Vehicles on the Toll Road

#### 135 IAC 2-2-1 Speed regulations

Authority: IC 8-15-2-17; IC 8-15-2-17.2 Affected: IC 8-15-2; IC 9-21-5-11

Sec. 1. The following are speed regulation requirements:

- (1) No person shall drive a vehicle as follows:
  - (A) On the toll road at a speed greater than is reasonable and prudent under the conditions and having regard for the actual and potential hazards then existing.
  - (B) On the traffic lanes of the toll road at a speed greater than that posted. At no location on the toll road shall the rate of speed of any vehicle exceed that permitted by IC 9-21-5.
- (2) No person shall operate a vehicle at a speed in excess of the following:
  - (A) That posted on any interchange.
  - (B) Twenty (20) miles per hour within any travel plaza, except on the acceleration and deceleration lanes thereof.
- (3) No person shall drive a vehicle at such a low speed as to impede or block the normal and reasonable movement of traffic or at a speed lower than forty-five (45) miles per hour on the traffic lanes on the toll road, except when:
  - (A) a reduced speed is necessary for safe operation;
  - (B) ordered to do so by a police officer; or
  - (C) posted at a lower speed.
- (4) No operator of a vehicle shall suddenly decrease the speed of a vehicle without first giving a clearly visible and conventional signal to traffic immediately to the rear.
- (5) In construction zones, vehicles shall comply with IC 9-21-5-11.

(Indiana Finance Authority; 135 IAC 2-2-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 323; filed Aug 5, 1987, 4:15 p.m.: 11 IR 6; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2901; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-2-2 One-way traffic

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 2. All traffic lanes, deceleration lanes, acceleration lanes and shoulders on the toll road are hereby designated as one-way lanes. No person shall operate any vehicle on any of such lanes in any direction other than forward and generally parallel to and to the right of the median strip. (*Indiana Finance Authority; 135 IAC 2-2-2; filed Dec 6, 1983, 1:52 pm: 7 IR 323; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)* 

## 135 IAC 2-2-3 Entering traffic lanes

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

- Sec. 3. Upon entering a traffic lane from a travel plaza, interchange, shoulder, or entrance ramp, the operator of a vehicle shall do the following:
  - (1) Use the acceleration lane or shoulder.
  - (2) Enter the outer traffic lane with caution so as not to interfere with or endanger traffic.
  - (3) Yield the right-of-way to vehicles already on the traffic lanes.

(Indiana Finance Authority; 135 IAC 2-2-3; filed Dec 6, 1983, 1:52 p.m.: 7 IR 323; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2901; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-2-4 Crossing median strip prohibited

Authority: IC 8-15-2-14; IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-7; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 4. No operator of a vehicle shall drive his vehicle across or upon the median strip. The use of designated cross-over areas is prohibited to all except emergency vehicles, vehicles owned or operated by the concessionaire, authorized non-revenue vehicles (described in 135 IAC 2-5-5), and others in emergency situations when directed by a police officer. The operator of a vehicle authorized to cross the median strip at designated crossovers shall yield the right-of-way to all traffic on the traffic lanes. (*Indiana Finance Authority*; 135 IAC 2-2-4; filed Dec 6, 1983, 1:52 p.m.: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3399; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-2-5 U-turns prohibited

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 5. No person operating a vehicle shall make a U-turn at any point on the toll road, except as directed to do so by a police officer. (Indiana Finance Authority; 135 IAC 2-2-5; filed Dec 6, 1983, 1:52 p.m.: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2901; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3400; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-2-6 Passing prohibited in certain lanes and ramps

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 6. No operator of a vehicle, while on a deceleration lane, acceleration lane, or interchange ramp shall overtake and pass another vehicle which is in motion thereon, or attempt to do so. (*Indiana Finance Authority*; 135 IAC 2-2-6; filed Dec 6, 1983, 1:52 pm: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-2-7 Driving on shoulders prohibited

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 7. No person shall operate a vehicle on the shoulders, except in the case of an emergency or when so directed by a police officer. This section shall not preclude the use of the outer shoulder for emergency stopping, parking, or standing as provided in 135 IAC 2-2-8. (*Indiana Finance Authority*; 135 IAC 2-2-7; filed Dec 6, 1983, 1:52 pm: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## 135 IAC 2-2-8 Stopping, parking, or standing of vehicles

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 8. No person shall stop, park or leave standing any vehicle, whether attended or unattended, upon the traffic lanes, acceleration lanes, deceleration lanes, bridges, entrance or exit ramps, median strip or at any place where a "NO PARKING" sign is posted. In case of an emergency, but not otherwise, a vehicle may be stopped and parked on the shoulder, adjacent to outer traffic lanes in the designated direction of traffic, provided that all wheels and projecting parts of the vehicle or its load shall be completely clear of the traffic lanes. In the event that it is necessary for the operator of any vehicle to leave such vehicle on any portion of the

toll road unattended, the operator must obtain authorization for parking from a police officer before leaving his vehicle. The provisions of this section shall not apply to emergency vehicles or vehicles owned or operated by the concessionaire. (Indiana Finance Authority; 135 IAC 2-2-8; filed Dec 6, 1983, 1:52 p.m.: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3400; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## 135 IAC 2-2-9 Impoundment of vehicles

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 9. Any vehicle which is parked or abandoned on any portion of the toll road, without first obtaining permission from a police officer shall be towed off the toll road and impounded. Such vehicle may not be removed from the place where it is impounded without first obtaining the proper release from the police and the payment of all towing, storage and other costs and charges. (Indiana Finance Authority; 135 IAC 2-2-9; filed Dec 6, 1983, 1:52 pm: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## 135 IAC 2-2-10 Traffic control signals

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 10. All traffic approaching toll plazas shall comply with the signals of the lights indicating the following:

- (1) For a toll plaza, the following:
  - (A) A green light indicates that:
    - (i) the traffic lane over which the light is displayed is open to traffic; or
    - (ii) in the case of automatic lanes, the vehicle activating the green light may proceed.
  - (B) A red light indicates that:
    - (i) the traffic lane over which the light is displayed is closed to traffic; or
    - (ii) in the case of automatic lanes, the vehicle failing to activate the green light shall not proceed.
- (2) For a highway, a flashing yellow light indicates that all traffic shall do the following:
  - (A) Reduce speed.
  - (B) Proceed with caution.
  - (C) Comply with all supplemental and related traffic signs.

(Indiana Finance Authority; 135 IAC 2-2-10; filed Dec 6, 1983, 1:52 p.m.: 7 IR 324; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2902; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-2-11 Compliance with orders and traffic control devices

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 11. No person shall fail, neglect or refuse to comply with any lawful order or direction of toll attendants at toll booths, flagmen of the maintenance forces and such other uniformed police officers as may be employed by the concessionaire for such purposes. No person shall fail, neglect or refuse to comply with any traffic control sign, signal or device erected or displayed on the toll road, unless directed otherwise by a police officer or toll road employee. (Indiana Finance Authority; 135 IAC 2-2-11; filed Dec 6, 1983, 1:52 p.m.: 7 IR 325; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3400; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-2-12 Stops at toll collection facilities

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 12. (a) The operator of a vehicle shall make a complete stop at all manual and automatic toll collection facilities when entering and exiting the toll road if the:

- (1) procurement of a ticket; or
- (2) payment of a toll;

is required.

- (b) In any facility with unstaffed toll collection capabilities, the operator of a vehicle shall comply with all signs with respect to the following:
  - (1) Operating speed.
  - (2) Stopping of vehicles.
  - (3) The procession subsequent to a reduction in speed or a stop.

(Indiana Finance Authority; 135 IAC 2-2-12; filed Dec 6, 1983, 1:52 p.m.: 7 IR 325; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2902; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## 135 IAC 2-2-13 Entry and exit restrictions

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 13. No operator of a vehicle shall enter or leave the toll road except through the toll lanes, except in case of any emergency, and in such case the entrance or exit may be made only under the control and supervision of a police officer or toll attendant. (Indiana Finance Authority; 135 IAC 2-2-13; filed Dec 6, 1983, 1:52 pm: 7 IR 325; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### **135 IAC 2-2-14 Accidents**

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 14. In addition to the provisions of the motor vehicle laws of the state of Indiana, the operator of a vehicle involved in an accident on the toll road resulting in injury or death to any person or damage to any property, real or personal, shall immediately stop such vehicle at the scene of the accident, and give his name, address, license and registration numbers to the person injured, or to the person sustaining the damage, and to a police officer. (*Indiana Finance Authority*; 135 IAC 2-2-14; filed Dec 6, 1983, 1:52 pm: 7 IR 325; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## Rule 3. Limitation of Use of the Toll Road

#### 135 IAC 2-3-1 Pedestrians and certain vehicles prohibited

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 1. The following shall not travel on the toll road under any circumstances:

- (1) Pedestrians.
- (2) Bicycles.
- (3) Motorcycles with less than one hundred twenty-five (125) cubic centimeters displacement.
- (4) Vehicles drawn by animals.

- (5) Aircraft.
- (6) Vehicles with improperly secured loads.
- (7) Vehicles with any of the following:
  - (A) Metal tires.
  - (B) Solid tires.
  - (C) Deflated pneumatic tires.
  - (D) Caterpillar treads.
- (8) Vehicles towing another vehicle that does not have the following:
  - (A) A proper tow bar.
  - (B) Safety chains.
- (9) Vehicles that are deemed, in the opinion of a police officer, to be as follows:
  - (A) Unsafe.
  - (B) Such as to create a hazard upon the toll road.

(Indiana Finance Authority; 135 IAC 2-3-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 325; errata, 7 IR 1054; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2902; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## 135 IAC 2-3-2 Hitchhiking and loitering prohibited

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 2. The following are prohibited on any portion of the toll road, including all toll plazas and travel plazas:

- (1) The solicitation of a ride, commonly known as hitchhiking.
- (2) Stopping any vehicle for the purpose of picking up or discharging a hitchhiker.
- (3) Loitering.

(Indiana Finance Authority; 135 IAC 2-3-2; filed Dec 6, 1983, 1:52 p.m.: 7 IR 325; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2902; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## 135 IAC 2-3-3 Commercial activity

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 3. No person shall offer or display goods or services for sale, or post, distribute or display signs, advertisements, circulars, written or printed matter, or operate mobile or stationary public address equipment on the toll road unless the authority shall have granted permission therefor; provided, however, that this section shall not apply to the display of customary warning, identifying, advertising or like signs on a vehicle ordinarily and customarily carrying such signs. (*Indiana Finance Authority*; 135 IAC 2-3-3; filed Dec 6, 1983, 1:52 p.m.: 7 IR 325; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3400; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

## Rule 4. Dimension and Weight Limitations; Special Hauling Permits

# 135 IAC 2-4-1 Allowable dimensions without toll attendant authorization

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 1. The dimensions in this section shall be the maximum allowable dimensions for vehicles permitted to operate on the toll road without toll attendant authorization under section 2 of this rule or a permit under section 4 of this rule, 135 IAC 2-7, or 135 IAC 2-8. Vehicles not exceeding the following dimensions shall, for toll collection purposes, be classified by axle count and the toll assessed accordingly:

#### **GENERAL PROVISIONS**

FACTOR	LIMITS
Width	8' 6"
Height	13' 6"
Length for single vehicle under own motive power (other than buses)	36' 0"
Buses	40' 0"
Semitrailer in a truck tractor-semitrailer combination	53' 0"

Provided, however, that a semitrailer longer than forty-eight (48) feet, six (6) inches shall not be operated on the toll road when the distance between the kingpin and the rearmost axle of the semitrailer exceeds forty (40) feet, six (6) inches. (Indiana Finance Authority; 135 IAC 2-4-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 326; filed Aug 5, 1987, 4:15 p.m.: 11 IR 6; errata, 11 IR 96; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2903; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-4-2 Dimensions requiring toll attendant authorization

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 2. The operator or operators of any vehicle exceeding any of the dimensions set forth in section 1 of this rule, except where permits are required under section 4 of this rule, 135 IAC 2-7, or 135 IAC 2-8, shall, upon entering the toll road, state to the toll attendant on duty the facts relative to any excessive dimension or dimensions. The toll attendant, so advised, may at that time allow the vehicle to travel on the toll road, after having classified the vehicle by axle count and the toll assessed accordingly, if it should fall within the following dimensions:

Width \*Over 8' 6" to and including 12' 0" Height Over 13' 6" to and including 14' 6"

Length:

Single vehicles To 65' 0"
Buses To 65' 0"

(Indiana Finance Authority; 135 IAC 2-4-2; filed Dec 6, 1983, 1:52 p.m.: 7 IR 326; errata, 7 IR 1054; filed Aug 5, 1987, 4:15 p.m.: 11 IR 6; errata, 11 IR 96; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2903; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-4-3 Allowable weights not requiring permit

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 3. The following shall be the maximum allowable weight limits permitted on the toll road without a special hauling permit, or as specifically provided in the case of authorized trailer combinations and Michigan train combinations.

Factor Limits
Maximum single axle weight 22,400 lbs.
Maximum tandem axle weight per 18,000 lbs.

axle

Maximum gross weight 90,000 lbs.

(Indiana Finance Authority; 135 IAC 2-4-3; filed Dec 6, 1983, 1:52 pm: 7 IR 326; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

<sup>\*</sup>Vehicles exceeding 10' 0" in width are not allowed to travel during hours of darkness.

#### 135 IAC 2-4-4 Special hauling permits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 4. (a) A special hauling permit for a vehicle exceeding the dimensions or weights set forth in sections 2 and 3 of this rule, providing the load is nondivisible, may be issued by the department of state revenue. The permit is issued on a one-trip basis. The permit fee is as follows:

- (1) Five dollars (\$5) for oversized dimension loads.
- (2) Fifty dollars (\$50) for loads ninety thousand (90,000) to one hundred twenty thousand (120,000) pounds.
- (3) Seventy-five dollars (\$75) for loads one hundred twenty thousand one (120,001) to two hundred thousand (200,000) pounds.
- (4) One hundred dollars (\$100) for loads over two hundred thousand (200,000) pounds.
- (b) The operator of the vehicle shall have a copy of the permit to present to the toll attendant upon entry. (*Indiana Finance Authority; 135 IAC 2-4-4; filed Dec 6, 1983, 1:52 p.m.: 7 IR 326; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2903; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)*

### Rule 5. Vehicle Classification and Related Toll Rules

#### 135 IAC 2-5-1 Classification of vehicles

Authority: IC 8-15-2-14; IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 1. For purposes of the toll payable under the toll schedule adopted by the authority for use of the Indiana toll road, the following classifications shall apply:

- (1) Class 2. Any vehicle with two (2) axles, including motorcycles.
- (2) Class 3. Any vehicle or combination with three (3) axles.
- (3) Class 4. Any vehicle or combination with four (4) axles.
- (4) Class 5. Any vehicle or combination with five (5) axles.
- (5) Class 6. Any vehicle or combination with six (6) axles.
- (6) Class 7. Any vehicle or combination with seven (7) or more axles and all LCVs.
- (7) Class 8. Commuters. [NOTE: 135 IAC 2-5-1(7) is repealed on the freeze termination date (as defined in LSA Document #06-186(E), printed at 29 IR 3389) and the corresponding chart for class 8 in 135 IAC 2-5-2.1 is removed.]

(Indiana Finance Authority; 135 IAC 2-5-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 326; filed Mar 5, 1985, 9:10 a.m.: 8 IR 748, eff on the date of the commencement of the operation of the new combination ticket/barrier system of toll collection; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2903; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-5-2 Payment of toll (Repealed)

Sec. 2. (Repealed by Indiana Finance Authority; filed May 4, 2006, 12:55 p.m.: 29 IR 2943)

### 135 IAC 2-5-2.1 Payment of tolls

Authority: IC 8-15-2-14; IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-9.5-8-6; IC 8-15-2

Sec. 2.1. (a) Every operator of a vehicle using the toll road shall pay the toll prescribed by the authority (unless a lease exists between the authority and the department under IC 8-9.5-8-6, in which case the tolls are fixed by the department under 105 IAC 14), except when the use shall have been exempted from the payment by the authority.

(b) All persons driving vehicles upon the toll road, except as provided in section 5 of this rule, are required to pay the

## **GENERAL PROVISIONS**

prescribed toll at each toll plaza encountered while using the toll road. Tolls may be paid by:

- (1) currency or change presented to a toll attendant; or
- (2) correct change deposited in the automatic coin machine.
- (c) In the event that no lease exists between the authority (or its successor) and the department under IC 8-9.5-8-6, the following toll rates are effective on the toll road:

[See following pages for Indiana Toll Road Toll Structure and Rate Schedule.]

					Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Barrier System (Toll will be charged at inclined below enty upon entry and esta)	Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Barrier System oll will be charged at inclinated below only upon entry and sai	(H				
		Direction of Travel	Entry or Exit	Glass 2 Twe Axle Vehicles and Motoreyeles	Class 3 Three Axle Vehicks or Combination	Chass 4 Four Axle Vehicles or Combination	Class 5 Five Axle Vehicles or Combination	Class 6 Six Axie Vehicles or Combination	Class 7 Seven or More Arle Vehicles or Continuities	Class 8A	Class 8B (1)
ا <del>حما</del> م	West Point	W.TB	EX:T BNTRY	\$0.50	\$1.50 1.50	\$2.25 2.25	\$2.75 2.75	\$3.25	02'9 00'9\$	\$030	\$0.35
Plaza 5	Calumet Ave	WB	EXIT	0.25	1,25	L.75 27.1	2.25	250	00.8	0.10	0.15
Plaza 10	Cline Ave	WB EB	EXIT	0.25	0.75 0.75	1.25	57.1 27.1	200	3.75 3.75	0.10	0.15
Plaza 17	1-65/Gary East	W/B	ENTRY	0.15	050	0.75 0.75	1.25	1.25	2.50	0.05	0.05
Place 21	Lake Station/1-94	WB	ENTRY	0.30	050 050	0.75 0.75	1.25	1.25	2.50	0.15	0.15
Plaza 23	Willow Creek Rd	WR EB	ENTRY EXIT	0.30	05.0 05.0	0.75	1.25	1.25	2.50	0.15 0.15	0.15

Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System Class 2 (Two Axle Vehicles and Motorcycles)

153 East Point 144 Angola 121 Howe-LaGrange 0.75 107 Middlebury 1.10 0.45 101 Bristol-Goshen 1.30 0.65 96 Elkhart-East 0.35 0.75 1.45 92 Elkhart 0.40 0.90 1.65 83 Mishawaka 1.10 1.80 0,40 0.55 0.75 0.50 77 South Bend-ND 0.35 09.0 0.70 0.95 0.55 1,30 72 South Bend-West 0.35 1.10 1.55 0.45 2.20 49 LaPorte 0.65 1.10 2.10 1.65 39 Michigan City 31 Valparaiso-Chesterton 2.65 24 Portage Barrier 3.05 101 121 144 153 107 39 49 72 17 83 92 96

121 Howe-LaGrange 1.50 107 Middlebury 0.75 2.00 101 Bristol-Goshen 0.50 1.25 2.50 Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System 96 Elkhart-East 1.50 3.00 1.75 3.00 77 South Bend-ND 72 South Bend-West 0.50 0.50 1.25 1.50 1.75 2.00 3.00 4.25 49 LaPorte 1.75 2.00 2.50 3.00 4.25 39 Michigan City 31 Valparaiso-Chesterton 0.50 2.25 2.50 3.25 3.25 Class 3 (Three Axle Vehicles or Combination) 0.50 1.25 2.25 3.50 4.25 5.25 24 Portage Barrier

72

11 83 92 96 101 107 121 144

Indiana Administrative Code 2014 Edition

153 East Point

144 Angola

121 Howe-LaGrange 2.25

1.25 3.00

1.75 3.75

2.50 4.25

3.50 5.00

3.75 6.00

4.25 6.50

8.50 10.25

101 107 121 4

92 96

77

49 72 8.00

4.25 2.25

107 Middlebury 101 Bristol-Goshen Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System 96 Elkhart-East 0.75 0.75 1.25 2.25 1.25 1.75 77 South Bend-ND 2,50 1.25 1.75 2.25 72 South Bend-West 0.75 1.75 2.25 2.50 3.00 49 LaPorte 2.25 3.75 39 Michigan City 31 Valparaiso-Chesterton Class 4 (Four Axle Vehicles or Combination) 24 Portage Barrier 0.75 2.25 4.25 1.25 9.00

Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System

Class 5 (Five Axle Vehicles or Combination)

153 East Point 144 Angola 121 Howe-LaGrange 2.75 107 Middlebury 1.75 4.00 101 Bristol-Goshen 5.00 1.25 225 96 Elkhart-East 5.75 2.75 92 Elkhart 5.75 1.25 1.25 83 Mishawaka 6.75 1.25 2.25 4.50 77 South Bend-ND 1.25 1.75 2.25 2.75 3.50 5.00 8.00 72 South Bend-West 3,50 1.25 1.25 2.25 2.75 4.00 5.75 8.50 49 LaPorte 10.75 3.50 4.00 5.00 5.75 6.75 8.50 39 Michigan City 31 Valparaiso-Chesterton 1.25 6.75 1.25 4.50 5.00 5.75 6.75 8.00 7.25 24 Portage Barrier 1.25 101 107 121 144 153 2 5 83 92 49 96

Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System

Class 6 (Six Axle Vehicles or Combination)

153 East Point 144 Angola 121 Howe-LaGrange 3,25 107 Middlebury 2.00 4.50 101 Bristol-Goshen 1.25 2.50 90.9 96 Elkhart-East 1.25 3.25 6.50 1.25 92 Elkhart 4.00 2.00 6.50 83 Mishawaka 1.25 2.00 2.50 3.25 5.25 7.75 77 South Bend-ND 1.25 2.50 3.25 4.00 6.00 9.25 72 South Bend-West 1.25 3.25 4.50 9.75 11.25 4.00 49 LaPorte 4.00 39 Michigan City 31 Valparaiso-Chesterton 24 Portage Barrier 1.25 11.25 15.75 101 107 121 144 72 7 83 96

Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System

Class 7 (Seven or More Axle Vehicles or Combination)

153 East Point 144 Angola 121 Howe-LaGrange 00.9 107 Middlebury 3.75 8.50 101 Bristol-Goshen 11.00 5.00 96 Elkhart-East 6.00 12.25 2.50 2.50 92 Elkhart 3.75 7.25 12.25 14.75 00.9 9.75 18.25 5.00 77 South Bend-ND 7.25 17.00 2.50 3.75 5.00 6.00 72 South Bend-West 12.25 18.25 5.00 00'9 7.25 8.50 49 LaPorte 23.25 11,00 14.75 18.25 6.00 7.25 8.50 11.00 12.25 39 Michigan City 31 Valparaiso-Chesterton 20.75 25.75 13.50 17.00 2.50 8.50 9.75 22.00 28.00 5.00 24 Portage Barrier 29.25 2.50 101 107 121 144 49 72 11 83 92 96 31

153 East Point 144 Angola 121 Howe-LaGrange 0.45 107 Middlebury 0.70 101 Bristol-Goshen 0.40 0.80 96 Elkhart-East 0.20 0.95 0.20 0.50 92 Elkhart 0.55 0.30 1.05 0.20 0,45 0.70 0.25 0.30 1.15 77 South Bend-ND 0.20 0.30 0.35 09.0 0.80 1,30 72 South Bend-West 0.20 0.40 1.00 1.40 49 LaPorte 0.55 08.0 1.80 0.70 1.35 39 Michigan City 31 Valparaiso-Chesterton 0.20 09.0 24 Portage Barrier Class 8 (Commuters) 0.25 107 121 144 72 83 32 96 101 4

Indiana Toll Road Toll Structure and Rate Schedule Effective through March 31, 2007 Ticket System


-		Direction of Travel	Entry or Exit	Class 2 Two Axle Vehicles and Motomyodes	Class 3 Three Ask Vehieles or Combination	Class 4 Pour Axle Vehicles or Combination	Class 5 Five Aule Vehicles or Combination	Class 6 Six Ash Vehicles or Combination	Class 7 Seven or More Ask Vehicles or Combination	Class 8A (1) Commuters	Class 8B (1) Commuted	
Plaza 1	West Point	WB	EXIT	05'0\$	\$1.50	\$2.75	\$3.50	\$4.25	\$7.75	\$0.30	\$0.35	
		68	ENTRY	0.50	1.50	et (2)	3.50	4.25	7.75	0.50	0.35	
Plaza 5	Calumet Ave	W/B	EXIT	0.25	1.25	2.25	2.75	3.25	\$279	0.10	0.15	
		EB	ENTRY	6.25	<del>57</del> 11	22.25	2.75	3.25	6.25	0.10	0.15	
Plaza 10	Oline Ave	W/B	EXIT	0.25	. 001	1.75	2.60	2.50	150	010	0.15	
		EB EB	ENTRY	0.25	1,000	1.75	2,00	2.50	4.50	0.10	0.15	
Plaza 17	L65/Gary Fast	WB	ENTRY	0.15	0.75	1.60	1.50	1.75	3.00	0.05	0.05	
		EB	EXIT	6.15	, 50.0	1.66	1.50	1,75	3.00	0.05	0.05	
Plaza 21	Lake Station/L-94	WB	ENTRY	0.30	6.75	1:00	1.50	1.75	3,00	0.15	0.15	
		8.6	EXIT	0.36	6.75	1.00	1.50	1.75	3.00	0.15	0.15	
Plaza 23	Willow Creek Rd.	MA.	ENTRY	0.30	0.75	1.06	1.50	1.75	3,00	0.15	. 0.15	
		63	EXIT	0.30	0.75	1.00	1.50	57.1	3.00	0.15	0.15	
								and the second s				

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System Class 2 (Two Axle Vehicles and Motorcycles)

153 East Point 144 Angola 0.45 121 Howe-LaGrange 0.75 107 Middlebury 1.10 101 Bristol-Goshen 0.65 0.35 1.30 96 Elkhart-East 0.35 0.75 1.45 92 Elkhart 0.35 0.55 0.90 1.65 83 Mishawaka 0.75 08.1 77 South Bend-ND 0.35 0.55 09.0 0.95 1.30 2.00 72 South Bend-West 1.55 2.20 0.35 1.10 49 LaPorte 2.75 0.65 1.50 1.65 39 Michigan City 31 Valparaiso-Chesterton 2.05 24 Portage Barrier 101 107 121 144 72 83 92 96


Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System

Class 3 (Three Axle Vehicles or Combination)




Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System

Class 4 (Four Axle Vehicles or Combination)




Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System

Class 5 (Five Axle Vehicles or Combination)



Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System

Class 6 (Six Axle Vehicles or Combination)



Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System

Class 7 (Seven or More Axle Vehicles or Combination)

153 East Point 144 Angola 121 Howe-LaGrange 7.75 107 Middlebury 10,75 101 Bristol-Goshen 3.00 6.25 96 Elkhart-East 7.75 15.50 18.50 3.00 3,00 9.25 15.50 3.00 4.50 3.00 83 Mishawaka 12.25 7.75 18.50 3.00 4.50 6.25 77 South Bend-ND 6.25 7.75 13.75 72 South Bend-West 9.25 10.75 15,50 23.00 3.00 6.25 7.75 3.00 49 LaPorte 10.75 13.75 13.75 29.25 7.75 9.25 39 Michigan City 31 Valparaiso-Chesterton 26.25 32,25 3,00 3.00 6.25 24 Portage Barrier 37.00 3.00 7.75 101 121 107 144 49 72 11 83 6 96

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2007 through March 31, 2008 Ticket System

Class 8 (Commuters)


153 East Point 121 Howe-LaGrange 0.45 107 Middlebury 0.25 0.70 101 Bristol-Goshen 0.20 08.0 96 Elkhart-East 0.20 0.20 0.50 0.95 0.55 1.05 83 Mishawaka 1.15 77 South Bend-ND 1.30 72 South Bend-West 0.20 0.25 0.40 1.40 0.40 0.70 1.35 08.0 1.05 39 Michigan City 31 Valparaiso-Chesterton 0.20 1.30 1.60 0.20 1.10 1.20 1.35 1.70 101 107 121 44 39 49 72 83 92 96

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Barrier System ("bit will be charged as indicated believ only upon entry and exit.)

				Class 2	Class 3	Chass 4	Class 5	Class 6	Class 7	Class 8A (1)	Class 8B (1)
		Direction of Travel	Entry or Exit	Two Axie Vehicles and Morotrycles	Three Axle Vehicles or Combination	Four Arke Vehicles or Corribination	Five Axle Vehicles or Combination	Six Axle Vehicles or Combination	Seven or Mone Axle Vehicles or Combination	Commuters	Соттите
Plaza i	West Point	WB	EXIT	\$0.50	\$1.75	\$3.25	\$4.25	\$5.00	\$9.25	50.30	\$0.35
		6	ENTRY	0.50	1.75	3.25	4.25	5.00	92.5	0.30	0.35
Plaza S	Calumet Ave	WB	EXIT	0.25	1.25	2,75	3,50	4.30	7.50	0.10	0.15
		EB	ENTRY	0.25	1.25	2.75	3.50	4.30	7.50	0.10	0.15
Plaza 10	Cline Ave	W.B	EXIT	0.25	1.00	2.60	2.50	3.00	5.50	0.10	0.15
		EB	ENTRY	0.25	1.00	2.00	2.50	3,80	5.50	0.10	0.15
Plaza 17	L65/Gary Fast	WB	ENTRY	0.15	0.75	1.25	1.75	2.00	3,75	0.05	900
		<b>1</b>	EXIT	0.15	0.75	1.25	1.75	2.70	3.75	0.05	0.05
Pleza 21	Lake Station/1-94	WB	ENTRY	030	0.75	1.25	1,75	2.00	3,75	0.15	0.15
		EB	EXIT	0730	0.75	1.25	1.75	2.00	3,75	0.15	0.15
Plaza 23	Willow Creek Rd.	W.B	ENTRY	0.30	0.75	1.25	1.75	2.00	3.75	0.15	0.15
		EB	EXIT	0.30	0.75	1.25	1.75	2.00	3.75	0.15	0.15
(I) 8 A con	(1) & A commuser pay on exit or entry, but not both; § B commuters pay on	ar not both; 8	B commuters pay on a	entry and exit or have a trip that	entry and exit or have a trip that includes an entry or exit in the licket system.	: sicket system.					


Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Ticket System

Class 2 (Two Axle Vehicles and Motorcycles)



Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Ticket System

Class 3 (Three Axle Vehicles or Combination)



Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Ticket System

Class 4 (Four Axle Vehicles or Combination)

144 Angola 121 Howe-LaGrange 3.25 2.00 4.50 101 Bristol-Goshen 1.25 2.75 9.00 96 Elkhart-East 1.25 1,25 3.25 6.50 8.00 92 Elkhart 1.25 2.00 4.00 6.50 8.50 83 Mishawaka 1.25 2.00 2.75 3.25 5.25 8.00 77 South Bend-ND 1.25 3.25 9.25 2.00 2.75 4.00 6.00 72 South Bend-West 1.25 1.25 2.75 6.50 9.75 49 LaPorte 39 Michigan City 31 Valparaiso-Chesterton 11.25 13.75 1.25 5.25 6.00 7.25 7.25 8.00 9.25 11.75 15.00 1.25 2.75 8.00 8.50 9.25 9.75 5.25 24 Portage Barrier 15.75 11,25 13.25 1.25 3.25 8.00 9.25 9.75 107 121 144 153 49 72 11 83 96 101

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Ticket System

Class 5 (Five Axle Vehicles or Combination)

153 East Point 144 Angola 121 Howe-LaGrange 4.25 2.50 6.00 101 Bristol-Goshen 3.50 7.75 96 Elkhart-East 1.75 4.25 8,50 1.75 2.50 8.50 5.25 83 Mishawaka 1.75 4.25 10.25 2.50 3.50 6.75 South Bend-ND 12.00 1.75 4.25 5.25 7.75 72 South Bend-West 1.75 49 LaPorte 39 Michigan City Valparaiso-Chesterton 18.00 1.75 00'9 6.75 12.00 1.75 2.50 101 107 121 144 153 92 11 83

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Ticket System

Class 6 (Six Axle Vehicles or Combination)

144 Angola 121 Howe-LaGrange 9.00 107 Middlebury 3.00 7.00 101 Bristol-Goshen 2.00 4.00 9.00 5.00 10.00 2.00 92 Elkhart 2.00 3.00 00'9 10,00 2.00 83 Mishawaka 4.00 8.00 12.00 77 South Bend-ND 2.00 5.00 72 South Bend-West 2.00 49 LaPort 39 Michigan City 31 Valparaiso-Chesterton 14.00 15.00 18.00 23.00 24 Portage Barrier 10.00 11.00 12.00 14.00 2.00 5.00 92 96 101 107 121 77

Indiana Toll Road Toll Structure and Rate Schedule Effective Ápril 1, 2008 through March 31, 2009 Ticket System

Class 7 (Seven or More Axle Vehicles or Combination)

153 East Point 144 Angola 121 Howe-LaGrange 9.25 107 Middlebury 13.00 5.50 101 Bristol-Goshen 16.75 3,75 7.50 96 Elkhart-East 18.75 9.25 3.75 92 Elkhart 11.25 18.75 3.75 3.75 5.50 83 Mishawaka 15.00 22.25 3.75 5.50 7.50 9.25 77 South Bend-ND 16.75 26.00 3.75 11.25 5.50 7.50 9.25 72 South Bend-West 18.75 3.75 3.75 49 LaPorte 22.25 28.00 9.25 39 Michigan City 31 Valparaiso-Chesterton 26.00 3.75 15.00 18.75 22.25 24.25 26.00 28.00 33,50 42.75 3.75 7.50 24 Portage Barrier 31.75 37.25 44.75 101 107 121 144 49 27 77 83 98

153 East Point

144 Angola 121 Howe-LaGrange 0.45 107 Middlebury 0.25 0.70 101 Bristol-Goshen 0.20 0.40 08'0 Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2008 through March 31, 2009 Ticket System 96 Elkhart-East 0.20 0.95 92 Elkhart 0.30 0.20 0.55 1.05 0.20 83 Mishawaka 0.20 1.15 0.25 0.30 0.45 77 South Bend-ND 0.20 0.30 0.35 0.40 09.0 0.80 30 72 South Bend-West 0.20 0.25 0,40 0,45 0.70 1.00 1.40 0.55 49 LaPorte 0.40 0.55 0.70 1.05 1.35 1.80 0.95 39 Michigan City 31 Valparaiso-Chesterton 0.20 24 Portage Barrier Class 8 (Commuters) 0.25 2.40

49 72 7 83 92 96 101

107 121 144


Indiana Administrative Code 2014 Edition

indians Toil Road Toil Structure and Rate Schedule
Effective April 1, 2019
Barrier System
(Toll will be charged as substanted leave only spare entry and exis)

		Direction of Travel	Entry or Exit	Class 2 Two Axis Vehicles and Morocycles	Class 3 Three Axle Vehicles or Combination	Class 4 Four Axle Vehicles or Combination	Class 5 Five Axie Vehicles or Combination	Class 6 Six Azie Vehieles or Combination	Class 7 Sevra or Nore Ask Vehicles or Combination	Ciass 8A (1) Commuters	Class 8B (1) Commuters
Plaza 1	West Point	WB	EXIT	\$0.50	\$1.75	\$3.75	\$5.00	\$5.75	001134	\$0.30	\$0.35
		EB	ENTRY	0.50	1.75	3.75	5.40	5.75	11.00	0.30	0.35
Plaza 5	Calumet Ave	WB	EXIT	0.25	1.50	3.00	4.00	4.75	8.75	0.10	0.15
		EB	ENTRY	6.25	1.50	3.00	4.00	4.75	8.75	0.10	0.15
Plaza t0	Pleza 10 Cline Ave	EA)	ЕХІТ	57.0	1.03	2.25	3.00	5.50	05:99	0.10	0.15
		89	BNTRY	0.25	1.00	223	3.00	3.50	6.50	0.10	0.15
Plaza 17	Plaza 17 1-65/Gary Fast	WB	ENTRY	0.15	24.0	1.50	2.00	2.25	4.25 .	900	0.05
		89	EXIT	0.15	0.75	1.50	2.00	22.	4.25	0.05	0.05
Plaza 21	Plaza 21 Lake Station/1-94	W.B	ENTRY	0.30	ST:0	1.50	2.00	225	4.25	0.15	0.15
		<b>89</b>	FXIT	0.0	52.0	1.50	700	88.5	4.25	0.15	0.15
Plaza 23	Piaza 23 Willow Creek Rd.	E/A	ENTRY	0.30	0.75	1.50	200	2.25	4.25	0.15	0.15
		EB	EXIT	0.30	0.75	1.50	700	577	52.4	0.15	0.15

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2009 Ticket System

Class 2 (Two Axle Vehicles and Motorcycles)



144 Angola 121 Howe-LaGrange 1.75 107 Middlebury 00'1 2.50 101 Bristol-Goshen 3.25 0.75 1.50 Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2009 Ticket System 96 Elkhart-East 3.75 92 Elkhart 3.75 1.00 2.25 1.50 4.50 1.00 77 South Bend-ND 72 South Bend-West 3.25 3.25 3.75 5,50 7.00 39 Michigan City 31 Valparaiso-Chesterton 6.25 Class 3 (Three Axle Vehicles or Combination) 5.25 24 Portage Barrier 0.75 101 107 121 144 153 49 27 77 77 88 83 84

Indiana Administrative Code 2014 Edition


Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2009 Ticket System

Class 4 (Four Axle Vehicles or Combination)

153 East Point 144 Angols 121 Howe-LaGrange 3.75 107 Middlebury 2.25 5.50 101 Bristol-Goshen 1.50 3.00 7.00 96 Elkhart-East 1.50 3.75 7.75 9.25 92 Elkhari 1.50 2.25 4.75 7.75 1.50 2.25 3.00 3.75 6.25 9.25 77 South Bend-ND 7.00 1.50 2.25 3.00 3.75 4.75 72 South Bend-West 1.50 1.50 3.75 49 LaPorte 39 Michigan City 31 Valparaiso-Chesterton 1.50 6.25 24 Portage Barrier 1.50 11.50 13.25 2.25 7.75 8,50 9.25 83 92 96 101 107 121 144 49 77

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2009 Ticket System

Class 5 (Five Axle Vehicles or Combination)



Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2009 Ticket System

Class 6 (Six Axle Vehicles or Combination)

144 Angola 121 Howe-LaGrange 5.75 8.25 107 Middlebury 8.25 101 Bristol-Goshen 2,25 4.75 96 Elkhart-East 2.25 11.75 2.25 5.75 14.00 11.75 15.25 2.25 3.50 2,25 83 Mishawaka 14.00 17.50 2.25 3.50 4.75 5.75 77 South Bend-ND 16.50 2.25 4.75 5.75 7.00 72 South Bend-West 2.25 5.75 7.00 8.25 2.25 4.75 49 LaPorte 39 Michigan City 31 Valparaiso-Chesterton 14.00 2.25 9.50 15.25 16.50 17.50 21,00 27.00 2.25 4.75 24 Portage Barrier 28.25 2.25 101 107 121 96 49 83 6


Indiana Toll Road Toll Structure and Rate Schedulc Effective April 1, 2009 Ticket System

Class 7 (Seven or More Axle Vehicles or Combination)

153 East Point 121 Howe-LaGrange 11.00 107 Middlebury 6.50 15.25 101 Bristol-Goshen 4.25 8.75 96 Elkhart-East 4.25 11.00 21.75 4.25 21.75 4.25 13.00 4.25 6.50 83 Mishawaka 4.25 17.50 6.50 8.75 77 South Bend-ND 30.30 72 South Bend-West 4.25 4.25 15.25 21.75 32.75 49 LaPorte 39 Michigan City 31 Valparaiso-Chesterton 4.25 4.25 24 Portage Barrier 4.25 11.00 52.25 101 107 121 31 39 49 72 83 92 96

Indiana Toll Road Toll Structure and Rate Schedule Effective April 1, 2009 Ticket System

Class 8 (Commuters)



(Indiana Finance Authority; 135 IAC 2-5-2.1; filed May 4, 2006, 12:55 p.m.: 29 IR 2904; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA) NOTE: 135 IAC 2-5-1(7) is repealed on the freeze termination date (as defined in LSA Document #06-186(E), printed at 29 IR 3389) and the corresponding chart for class 8 in 135 IAC 2-5-2.1 is removed.

#### 135 IAC 2-5-3 Loss of toll ticket; excessive time on toll road

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 3. The operator of any vehicle who, for any reason:

- (1) does not have a toll ticket upon reaching the exit toll plaza at which he or she seeks to leave the toll road; or
- (2) presents a toll ticket that was issued at entry fourteen (14) hours or more before exiting from the toll road; shall be charged the highest toll chargeable for the applicable vehicle classification from either terminus of the toll road. (*Indiana Finance Authority*; 135 IAC 2-5-3; filed Dec 6, 1983, 1:52 p.m.: 7 IR 327; errata, 7 IR 1054; readopted filed Nov 6, 2002, 10:33

a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2937; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-5-4 Exit of vehicle at point of entry; disabled vehicle in tow

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 4. The presentation of a toll ticket, by the operator of any vehicle, for payment at the same toll plaza at which such toll ticket was issued shall be prima facie evidence of violation of 135 IAC 2-2-4 and/or 135 IAC 2-2-5. Therefore, said operator shall be charged the highest toll chargeable for the appropriate vehicle classification from either terminus of the toll road.

A disabled vehicle in tow by an authorized emergency service vehicle on the toll road shall not be charged toll if it is necessary, under 135 IAC 2, for the particular vehicle to leave the toll road at the same plaza at which it entered. (*Indiana Finance Authority*; 135 IAC 2-5-4; filed Dec 6, 1983, 1:52 pm: 7 IR 327; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-5-5 Toll-free travel

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 5. No free vehicular passage will be permitted over any part of the toll road except to the following:

- (1) Vehicles owned or operated by the state or any department or agency thereof.
- (2) Police officers of:
  - (A) the United States; or
  - (B) Indiana or its political subdivisions;

while in discharge of their official duties.

- (3) Fire or other authorized emergency vehicles entering the toll road:
  - (A) for the purpose of performing emergency services; or
  - (B) as authorized by the authority.
- (4) Vehicles bearing diplomatic plates.

(Indiana Finance Authority; 135 IAC 2-5-5; filed Dec 6, 1983, 1:52 p.m.: 7 IR 327; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2937; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3400; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# Rule 6. Protection of Property

# 135 IAC 2-6-1 Damage to property

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 1. Any person who defaces, destroys or damages any property or equipment owned by, or under the jurisdiction or control of the department, shall be liable to the department for such destruction or damage. (*Indiana Finance Authority; 135 IAC 2-6-1; filed Dec 6, 1983, 1:52 pm: 7 IR 327; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)* 

# **Rule 7. Longer Combination Vehicle Operations**

# 135 IAC 2-7-1 Permit required

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 1. LCVs may operate on the toll road:

- (1) only under an permit issued by the department or the authority under section 21 of this rule; and
- (2) subject to compliance by the permitted company with this rule.

(Indiana Finance Authority; 135 IAC 2-7-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 327; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2937; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3401; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-2 Definitions; length and axle limits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 2. (a) An LCV double shall consist of a:

- (1) truck-tractor;
- (2) semitrailer; and
- (3) trailer.

Neither the semitrailer nor the trailer shall be longer than forty-eight (48) feet, six (6) inches in length. The permissible number of axles on an LCV double combination shall be a minimum of five (5) and a maximum of nine (9).

- (b) An LCV triple shall consist of:
- (1) a truck-tractor;
- (2) a semitrailer; and
- (3) two (2) trailers.

Neither the semitrailer nor either of the two (2) trailers shall be longer than twenty-eight (28) feet, six (6) inches in length. The permissible number of axles of an LCV triple combination shall be a minimum of seven (7) and a maximum of nine (9). (Indiana Finance Authority; 135 IAC 2-7-2; filed Dec 6, 1983, 1:52 p.m.: 7 IR 327; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2937; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-3 Weight limits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 3. The maximum gross weight for an LCV shall be governed by the formula ninety thousand (90,000) pounds plus one thousand seventy (1,070) pounds per foot for each foot of combination length (front bumper to end of combination) in excess of sixty (60) feet. However, any LCV shall not exceed a total maximum gross weight of one hundred twenty-seven thousand four hundred (127,400) pounds. The gross load of an LCV shall not exceed the sum of allowable gross loads on the axles, which are

as follows:

- (1) The maximum gross weight on any one (1) axle: twenty-two thousand four hundred (22,400) pounds. Axles measuring less than forty (40) inches between axle centers are considered one (1) axle.
- (2) The maximum combined axle load of any two (2) successive axles, spaced more than forty (40) inches apart but less than nine (9) feet apart: thirty-six thousand (36,000) pounds.

No LCV will be permitted to leave the toll road for travel as combinations upon the state highways of Indiana without a permit from the department of state revenue. The maximum gross weight and axle weight of vehicles leaving the toll road as singles to travel upon the public highways of Indiana must comply with Indiana state law. (*Indiana Finance Authority*; 135 IAC 2-7-3; filed Dec 6, 1983, 1:52 p.m.: 7 IR 328; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2937; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-7-4 Other dimensions

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 4. All other maximum dimensions of 135 IAC 2 for the control and regulation of traffic on the toll road shall apply. (Indiana Finance Authority; 135 IAC 2-7-4; filed Dec 6, 1983, 1:52 pm: 7 IR 328; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-5 Classification for toll collection purposes

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 5. Qualified LCVs shall be charged a rate indicator 7 toll. (Indiana Finance Authority; 135 IAC 2-7-5; filed Dec 6, 1983, 1:52 p.m.: 7 IR 328; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2938; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-6 Safety and performance requirements

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 6. A responsible officer of the applicant shall certify to the department or the authority, before the start of operations, that the vehicles and equipment proposed to be furnished and used for LCV operations will comply with and meet all minimum safety and performance factors required by IC 8-2.1-24. (*Indiana Finance Authority*; 135 IAC 2-7-6; filed Dec 6, 1983, 1:52 p.m.: 7 IR 328; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2938; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3401; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-7 Emergency equipment

Authority: IC 8-15-2-17; IC 8-15-2-17.2 Affected: IC 8-2.1-24; IC 8-15-2; IC 9-19

Sec. 7. Each truck-tractor used in LCV operations shall be equipped at a minimum with emergency equipment as required by IC 8-2.1-24. (*Indiana Finance Authority*; 135 IAC 2-7-7; filed Dec 6, 1983, 1:52 p.m.: 7 IR 328; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2938; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-7-8 Structural strength

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 8. Every vehicle used for towing other vehicles in LCV operations shall have sufficient structural strength to ensure the safe and secure attachment of any coupling device used to tow other vehicles. (Indiana Finance Authority; 135 IAC 2-7-8; filed Dec 6, 1983, 1:52 p.m.: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2938; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-7-9 Safety chains

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 9. Every converter dolly shall be coupled with a safety chain or chains (stay chains or cables) directly to the frame of the semi-trailer by which it is to be towed. Attachment to the pintle hook will not meet this requirement. No more slack shall be left in safety chains or cables than shall be necessary to permit proper turning. Chains or cables shall be so connected to the dolly and towing vehicle and to the tow-bar as to prevent the tow-bar from dropping to the ground in the event the tow-bar fails. The means of attachment in both the towing and towed vehicles shall be capable of developing the full capacity of the safety chains or cables. Each chain or cable shall have an ultimate strength at least equal to the gross weight of the dolly and trailer being towed. (Indiana Finance Authority; 135 IAC 2-7-9; filed Dec 6, 1983, 1:52 pm: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-7-10 Distance between units

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 10. The distance between trailers coupled in combination shall not exceed nine (9) feet. (*Indiana Finance Authority*; 135 IAC 2-7-10; filed Dec 6, 1983, 1:52 pm: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-11 Lights and reflectors

Authority: IC 8-15-2-17; IC 8-15-2-17.2 Affected: IC 8-2.1-24; IC 8-15-2

Sec. 11. Each unit in an LCV shall be equipped at a minimum with:

- (1) electric lights; and
- (2) reflectors;

mounted on the vehicle as required by IC 8-2.1-24. (*Indiana Finance Authority*; 135 IAC 2-7-11; filed Dec 6, 1983, 1:52 p.m.: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2939; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-12 Coupling devices

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 12. Coupling devices shall be designed, constructed, and installed and the vehicles in an LCV shall be designed and constructed as to ensure that any LCV traveling on a level, smooth, paved surface will follow in the path of the towing vehicle without shifting or swerving from side to side over three (3) inches to each side of the path of the towing vehicle when the towing

vehicle is moving in a straight line. (Indiana Finance Authority; 135 IAC 2-7-12; filed Dec 6, 1983, 1:52 p.m.: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2939; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-7-13 Assembly of LCVs

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 13. In the assembly of LCVs before their operation on the Indiana toll road, the permitted company shall do the following:

- (1) Ascertain the total gross weight of each trailer of the proposed combination.
- (2) Couple them according to their gross weights with the:
  - (A) heaviest trailer coupled to the tractor; and
  - (B) lightest trailer in the rear.

(Indiana Finance Authority; 135 IAC 2-7-13; filed Dec 6, 1983, 1:52 p.m.: 7 IR 329; errata, 7 IR 1054; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2939; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-14 Police inspection

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 14. LCVs are subject to inspection by a police officer before initial movement by any newly permitted company. The inspection is designed to do the following:

- (1) Instruct drivers in the proper use of assembly areas.
- (2) Satisfy the department or the authority that the equipment meets the qualifications set forth in this section.

Spot checks of LCVs may be made periodically at the discretion of any police officer. (Indiana Finance Authority; 135 IAC 2-7-14; filed Dec 6, 1983, 1:52 p.m.: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2939; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3401; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-15 Assembly areas

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 15. LCVs shall be made up and broken up only in special assembly areas designated for this purpose by the department or the authority. All movements across traffic while entering or leaving an assembly area shall be properly safeguarded. (*Indiana Finance Authority*; 135 IAC 2-7-15; filed Dec 6, 1983, 1:52 p.m.: 7 IR 329; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2939; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3401; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# **135 IAC 2-7-16 Speed limits**

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 16. LCVs shall comply with existing speed regulations. A minimum speed of forty-five (45) miles per hour must be maintained on the toll road under normal conditions, except on entry and exit ramps (135 IAC 2-2-1). (*Indiana Finance Authority*; 135 IAC 2-7-16; filed Dec 6, 1983, 1:52 p.m.: 7 IR 330; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2939; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-7-17 Minimum distances between LCVs and other vehicles

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 17. A minimum distance of five hundred (500) feet shall be maintained under normal conditions between:

- (1) LCVs; and
- (2) a vehicle traveling in front of the LCV in the same travel lane;

except when passing occurs. (Indiana Finance Authority; 135 IAC 2-7-17; filed Dec 6, 1983, 1:52 p.m.: 7 IR 330; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2940; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-18 Passing

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 18. (a) LCVs may pass another vehicle traveling in the same direction only if the speed differential will allow the LCV to:

- (1) complete the maneuver; and
- (2) return to the normal driving lane;

within a distance of one (1) mile.

(b) LCVs shall not pass another vehicle traveling the same direction within one (1) mile of any travel plaza or interchange. (Indiana Finance Authority; 135 IAC 2-7-18; filed Dec 6, 1983, 1:52 p.m.: 7 IR 330; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2940; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-19 Equipment identification

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 19. LCVs shall be identified visually as follows:

- (1) An identification number issued by the department or the authority shall be stenciled as follows:
  - (A) In three (3) inch high block letters.
  - (B) In a contrasting color to that of the truck-tractor.
  - (C) On the left side of the vehicle.
  - (D) In a location where it can be seen by the toll attendant in the booth.

The number shall identify the company as a permitted company to operate LCVs on the toll road.

- (2) Permitted companies shall do the following:
  - (A) Maintain current lists of all stenciled and active truck-tractors used in LCV operations on the toll road.
  - (B) Provide these lists to the department or the authority upon request.

(Indiana Finance Authority; 135 IAC 2-7-19; filed Dec 6, 1983, 1:52 p.m.: 7 IR 330; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2940; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3401; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-20 Driver requirements

Authority: IC 8-15-2-17; IC 8-15-2-17.2 Affected: IC 8-2.1-24; IC 8-15-2

Sec. 20. (a) Drivers shall possess the minimum qualifications as required by the state for drivers operating vehicles within the state, and drivers must do the following:

(1) Comply with all applicable requirements of IC 8-2.1-24.

- (2) Possess a valid Class A commercial driver's license (CDL) with appropriate endorsements for operation of LCVs.
- (b) Drivers of LCVs on the toll road:
- (1) must be:
  - (A) not less than twenty-six (26) years of age; and
  - (B) in good health; and
- (2) shall have not less than five (5) years of provable experience in driving:
  - (A) semitrailer; or
  - (B) tandem trailer type;

motor vehicles throughout the four (4) seasons.

- (c) A permitted company's application for a driver permit under section 21 of this rule will be rejected by the department if the driver's license has been:
  - (1) revoked more than once in the past ten (10) years; or
  - (2) suspended more than once in the past five (5) years.

(Indiana Finance Authority; 135 IAC 2-7-20; filed Dec 6, 1983, 1:52 p.m.: 7 IR 330; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2940; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-21 Driver permits

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 21. (a) A permitted company shall make application on a form provided by the department or the authority that includes the applicant's driving employment history. The application must be accompanied by the following:

- (1) An official abstract of the applicant's driving record.
- (2) A photocopy of the applicant's current CDL.
- (b) Upon approval by the department or the authority, an identification card bearing a permit number will be issued to the permitted company. The driver must carry the card with him or her at all times while operating LCVs on the toll road for presentation upon request by:
  - (1) toll road personnel; or
  - (2) a police officer.
  - (c) The driver identification card is valid only for the operation of tractors:
  - (1) owned by; or
  - (2) under the control of;

the permitted company to which the driver permit is issued.

- (d) Neither the department nor the authority will accept driver applications from individuals. Applications are accepted only from permitted companies. All correspondence in connection therewith shall be handled through the companies, not the drivers.
- (e) The accuracy of the information in a driver application must be attested to by an officer of the company, who, in doing so, assumes sole responsibility for the representation made to the department or the authority.
  - (f) Permitted companies shall do the following:
  - (1) Maintain current lists of all active permitted drivers for LCV operations on the toll road.
  - (2) Provide these lists to the department or the authority upon request.

(Indiana Finance Authority; 135 IAC 2-7-21; filed Dec 6, 1983, 1:52 p.m.: 7 IR 330; errata, 7 IR 1054; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2941; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3401; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-7-22 Temporary suspension of LCV permits

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 22. Permission to operate LCVs on the toll road may be temporarily suspended by the department or the authority at

any time due to any of the following:

- (1) Weather conditions.
- (2) Unfavorable road conditions.
- (3) Holiday traffic.
- (4) Any other emergency conditions.

(Indiana Finance Authority; 135 IAC 2-7-22; filed Dec 6, 1983, 1:52 p.m.: 7 IR 331; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2941; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3402; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-7-23 Insurance coverage

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 23. An applicant an LCV operating permit shall furnish to the department or the authority a certificate attesting to the fact that there has been secured by the applicant public liability insurance affording coverages of not less than the following:

- (1) Five hundred thousand dollars/one million dollars (\$500,000/\$1,000,000) for all damages arising from bodily injury, including death.
- (2) One hundred thousand dollars/five hundred thousand dollars (\$100,000/\$500,000) for property damage, including damage to toll road property and facilities.

The named insured thereon shall include the department or the authority and their respective officers, agents, and employees, and the certificate shall indicate that the policy contains an endorsement that reads, "The inclusion of the Indiana department of transportation or the Indiana finance authority as an additional named insured shall not exclude coverage of liability of the named insured for damage of property of the additional named insured, or for injury to or death of any person working with or for the additional named insured." The certificate shall also provide that the coverage under the policy may not be canceled without thirty (30) days prior notice to the department or the authority. (Indiana Finance Authority; 135 IAC 2-7-23; filed Dec 6, 1983, 1:52 p.m.: 7 IR 331; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2941; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3402; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-7-24 Applicability of other rules

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 24. Except as noted herein and in the LCV operations permit, all rules for the control and regulation of traffic on the toll road shall apply to the operation of LCVs on the toll road. (*Indiana Finance Authority*; 135 IAC 2-7-24; filed Dec 6, 1983, 1:52 p.m.: 7 IR 331; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2942; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# **Rule 8. Michigan Train Operations**

# 135 IAC 2-8-1 Permit required

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 1. Michigan trains may operate on the toll road:

- (1) only under a Michigan train single trip permit issued by the department of state revenue; and
- (2) subject to compliance by the permittee with this rule.

(Indiana Finance Authority; 135 IAC 2-8-1; filed Dec 6, 1983, 1:52 p.m.: 7 IR 331; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2942; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-8-2 Definitions; length and axle limits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 2. A Michigan train shall consist of a truck-tractor, semi-trailer and trailer. Neither the semi-trailer nor the trailer shall exceed 28' 6" in length. The permissible number of axles of a Michigan train shall be a minimum of eight (8) and a maximum of eleven (11). (Indiana Finance Authority; 135 IAC 2-8-2; filed Dec 6, 1983, 1:52 pm: 7 IR 331; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-8-3 Weight limits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

- Sec. 3. (a) The maximum gross weight for a Michigan train shall be one hundred twenty-seven thousand four hundred (127,400) pounds. Gross weight on any one (1) axle shall be twenty-two thousand four hundred (22,400) pounds. Axles measuring less than forty (40) inches between centers are considered one (1) axle.
- (b) The maximum combined axle loads of any two (2) successive axles spaced more than forty (40) inches apart but less than nine (9) feet apart shall be thirty-six thousand (36,000) pounds. No such combination will be permitted to leave the toll road for travel upon the state highways of Indiana without a permit from the department of state revenue. The maximum gross weight and axle weights of vehicles leaving the toll road as singles to travel the public highways of Indiana must comply with Indiana state law. (Indiana Finance Authority; 135 IAC 2-8-3; filed Dec 6, 1983, 1:52 p.m.: 7 IR 331; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2942; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-8-4 Other dimensions

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 4. All other maximum dimensions of 135 IAC 2 for the control and regulation of traffic on the toll road shall apply. (Indiana Finance Authority; 135 IAC 2-8-4; filed Dec 6, 1983, 1:52 pm: 7 IR 332; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-8-5 Permits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 5. Michigan train permits for specified one-way movements may be obtained from the department of state revenue. The permits do not include the rate indicator 7 toll, which must be paid as provided in the rules. For information regarding Michigan train permits, contact the department of state revenue. (*Indiana Finance Authority; 135 IAC 2-8-5; filed Dec 6, 1983, 1:52 p.m.: 7 IR 332; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2942; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)* 

### 135 IAC 2-8-6 Safety and performance requirements

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 6. A responsible officer of the applicant shall certify to the department or the authority, prior to the approval of truck-tractor, that the vehicle proposed to be furnished and used for specified gross loads will comply with and meet all minimum safety

and performance factors of the department or the authority. If it is determined, after the truck-tractor is engaged in the Michigan train operation, that the vehicle cannot meet such requirements, the truck-tractor shall not be used in trailer combination on the toll road until corrective measures are taken to comply with the requirements of the department or the authority. (*Indiana Finance Authority*; 135 IAC 2-8-6; filed Dec 6, 1983, 1:52 p.m.: 7 IR 332; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3402; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-7 Emergency equipment

Authority: IC 8-15-2-17; IC 8-15-2-17.2 Affected: IC 8-2.1-24; IC 8-15-2; IC 9-19

Sec. 7. Each truck-tractor used in the Michigan train operation shall be equipped at a minimum with emergency equipment as required by IC 8-2.1-24. (*Indiana Finance Authority; 135 IAC 2-8-7; filed Dec 6, 1983, 1:52 p.m.: 7 IR 332; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2942; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA*)

# 135 IAC 2-8-8 Structural strength

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 8. Every vehicle used for towing other vehicles in trailer combinations shall have sufficient structural strength to insure the safe and secure attachment of any coupling device used to tow other vehicles. (Indiana Finance Authority; 135 IAC 2-8-8; filed Dec 6, 1983, 1:52 pm: 7 IR 332; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-9 Safety chains

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 9. Every converter dolly shall be coupled with safety chain or chains (stay chains or cables) directly to the frame of the semi-trailer by which it is to be towed. Attachment to the pintle hook will not meet this requirement. No more slack shall be left in safety chains or cables than shall be necessary to permit proper turning. Chains or cables shall be so connected to the dolly and towing vehicle and to the tow-bar as to prevent the tow-bar from dropping to the ground in the event the tow-bar fails. The means of attachment to both the towing and towed vehicles shall be capable of developing the full capacity of the safety chains or cables. Each chain or cable shall have an ultimate strength at least equal to the gross weight of the dolly and trailer being towed. (*Indiana Finance Authority*; 135 IAC 2-8-9; filed Dec 6, 1983, 1:52 pm: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-10 Distance between units

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 10. The distance between the rear of the first semi-trailer and the front of the second trailer as coupled in combination shall not exceed nine (9) feet. (*Indiana Finance Authority*; 135 IAC 2-8-10; filed Dec 6, 1983, 1:52 pm: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-8-11 Lights and reflectors

Authority: IC 8-15-2-17; IC 8-15-2-17.2 Affected: IC 8-2.1-24; IC 8-15-2; IC 9-19-6

Sec. 11. Each unit in a Michigan train combination shall be equipped at a minimum with:

(1) electric lights; and

(2) reflectors;

mounted on the vehicle as required by IC 8-2.1-24 and IC 9-19-6. (*Indiana Finance Authority*; 135 IAC 2-8-11; filed Dec 6, 1983, 1:52 p.m.: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2943; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-12 Coupling devices

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 12. Coupling devices shall be so designed, constructed and installed, and the vehicles in a Michigan train combination shall be so designed and constructed as to insure that any such combination traveling on a level, smooth, paved surface will follow in the path of the towing vehicle without shifting or swerving from side to side over three (3) inches to each side of the path of the towing vehicle when it is moving in a straight line. (*Indiana Finance Authority; 135 IAC 2-8-12; filed Dec 6, 1983, 1:52 pm: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)* 

### 135 IAC 2-8-13 Assembly of combinations

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 13. In the assembly of the Michigan train combinations prior to their operation on the Indiana toll road, the permittee shall ascertain the total gross weight of each trailer of the proposed combination. The permittee shall couple them according to their gross weights with the heaviest trailer coupled to the tractor and the lightest trailer in the rear. (*Indiana Finance Authority*; 135 IAC 2-8-13; filed Dec 6, 1983, 1:52 pm: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-14 Police inspection

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 14. Michigan train combinations are subject to inspection by a police officer prior to initial movement by any newly authorized company. The inspection is designed to instruct drivers in the proper use of make-up and break-up areas and to satisfy the department or the authority that the equipment meets the qualifications set forth in this section. Spot checks of Michigan train combinations may be made periodically at the discretion of any police officer. (*Indiana Finance Authority*; 135 IAC 2-8-14; filed Dec 6, 1983, 1:52 p.m.: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3403; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-8-15 Assembly areas

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 15. Michigan train combinations shall be made up and broken up on the toll road only in special assembly areas designated for this purpose by the department or the authority. All movements across traffic while entering or leaving a make-

up/break-up area shall be properly safeguarded. (*Indiana Finance Authority*; 135 IAC 2-8-15; filed Dec 6, 1983, 1:52 p.m.: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3403; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-16 Speed limits

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 16. Michigan train combinations shall comply with all existing speed regulations. A minimum speed of forty-five (45) miles per hour must be maintained on the toll road under normal conditions, except on entry and exit ramps (135 IAC 2-2-1). (Indiana Finance Authority; 135 IAC 2-8-16; filed Dec 6, 1983, 1:52 pm: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

#### 135 IAC 2-8-17 Assured clear distance

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 17. A minimum distance of five hundred (500) feet shall be maintained under normal conditions between Michigan train combinations and a vehicle traveling in front of it in the same travel lane, except when passing occurs. (*Indiana Finance Authority*; 135 IAC 2-8-17; filed Dec 6, 1983, 1:52 pm: 7 IR 333; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

### 135 IAC 2-8-18 Passing

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 18. (a) Michigan train combinations may pass another vehicle traveling in the same direction only if the speed differential will allow the Michigan train combination to complete the maneuver and return to the normal driving lane within a distance of one (1) mile.

(b) Michigan train combinations shall not pass another vehicle traveling the same direction within one (1) mile of any service area or interchange. (Indiana Finance Authority; 135 IAC 2-8-18; filed Dec 6, 1983, 1:52 pm: 7 IR 334; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-19 Temporary suspension of Michigan train permits

Authority: IC 8-15-2-17; IC 8-15-2-17.2; IC 8-15.5-10

Affected: IC 8-15-2; IC 8-15.5

Sec. 19. Permission to operate Michigan train combinations on the toll road may be temporarily suspended by the department or the authority at any time due to weather conditions, unfavorable road conditions, holiday traffic, and any other emergency conditions. (Indiana Finance Authority; 135 IAC 2-8-19; filed Dec 6, 1983, 1:52 p.m.: 7 IR 334; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; emergency rule filed Jun 14, 2006, 10:50 a.m.: 29 IR 3403; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-8-20 Applicability of other rules and regulations

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 20. Except as noted herein and in the Michigan train operation permit, all rules and regulations for the control and regulation of traffic on the toll road shall apply to the operation of trailer combinations on the toll road. (*Indiana Finance Authority*; 135 IAC 2-8-20; filed Dec 6, 1983, 1:52 pm: 7 IR 334; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# Rule 9. Indiana Motor Vehicle Laws

# 135 IAC 2-9-1 Motor vehicle laws applicable

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

Sec. 1. Except as such may have been modified or amplified by 135 IAC 2, the terms and provisions of the motor vehicle laws of the state of Indiana shall apply to the operator of a vehicle on the toll road the same as if said operator was operating a vehicle on the public highways of the state of Indiana. (*Indiana Finance Authority*; 135 IAC 2-9-1; filed Dec 6, 1983, 1:52 pm: 7 IR 334; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# Rule 10. Penalties; Severability; Savings

# 135 IAC 2-10-1 Penalties (Repealed)

Sec. 1. (Repealed by Indiana Finance Authority; filed May 4, 2006, 12:55 p.m.: 29 IR 2943)

# 135 IAC 2-10-2 Severability provision

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2

- Sec. 2. If any rule or application of any rule is held invalid or void, the invalidity or voidness affects the remainder of the authority's rules only to the extent that the remainder is:
  - (1) so essentially and inseparately connected with, and so dependent on, the invalid or void provision or application that it cannot be presumed that the remainder would have been issued without the invalid or void provision or application; or
- (2) incomplete and incapable of being executed without the invalid or void provision or application.

(Indiana Finance Authority; 135 IAC 2-10-2; filed Dec 6, 1983, 1:52 p.m.: 7 IR 334; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; filed May 4, 2006, 12:55 p.m.: 29 IR 2943; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

# 135 IAC 2-10-3 Savings provision

Authority: IC 8-15-2-17; IC 8-15-2-17.2

Affected: IC 8-15-2-17.2

Sec. 3. Unless the authority expressly states to the contrary, a rule issued by the authority does not affect:

- (1) rights or liabilities accrued;
- (2) penalties incurred;
- (3) crimes committed; or
- (4) proceedings begun;

before the effective date of such rule. Those rights, liabilities, penalties, crimes and proceedings continue, shall be imposed and shall be enforced as if such rule had not been issued. (Indiana Finance Authority; 135 IAC 2-10-3; filed Dec 6, 1983, 1:52 pm: 7 IR 335; readopted filed Nov 6, 2002, 10:33 a.m.: 26 IR 882; readopted filed Sep 17, 2008, 11:47 a.m.: 20081001-IR-135080542RFA; readopted filed Sep 20, 2012, 12:24 p.m.: 20121017-IR-135120378RFA)

\*