

INDIANA

DEPARTMENT OF TRANSPORTATION

STANDARD SPECIFICATIONS

EFFECTIVE
FOR LETTINGS ON OR AFTER JANUARY 1, 1998

Includes August 14-15, 1997 Minutes

1995

For copies of these Standard Specifications contact:

Contract Engineer
Indiana Department of Transportation
Room N855, Indiana Government Center North
100 North Senate Avenue
Indianapolis, Indiana 46204-2217

Price \$15.00

FRANK O'BANNON
GOVERNOR

INDIANA
DEPARTMENT OF TRANSPORTATION

Curtis A. Wiley
COMMISSIONER

DEPUTY COMMISSIONERS

Donald W. Lucas
CHIEF HIGHWAY ENGINEER

Dennis E. Faulkenberg
CHIEF FINANCIAL OFFICER

Debbie Simmons-Wilson
INTERMODAL TRANSPORTATION
AND PLANNING

Phil Schermerhorn
PUBLIC AND LEGISLATIVE AFFAIRS

SPECIFICATION COMMITTEE

CHAIRMAN
Firooz Zandi, Deputy Chief Highway Engineer

MEMBERS
John P. Bellinger, Materials and Tests Division
Robert D. Cales, Technical Services Division
Thomas W. Caplinger, Design Division
Jack Fischbacher, LaPorte District Construction Engineer
Dennis A. Kuchler, Operations Support Field Engineer
Janice Osadczuk, Pre-Engineering and Environment Division

SECRETARY
Dannie L. Smith, Specifications Manager

METRICS

The first 2 paragraphs of 109.01, Measurement of Quantities reads as follows:

(a) General Requirements. All work completed under the contract will be measured according to the metric system, now known as the International System of Units, or SI, unless otherwise specified.

The standard measures shown in this publication are mostly in the International System of Units such as meters, kilograms, liters, and hectares. The Department is converting to the International System. In this text where the standard measure is given in the International System, the English, or inch pound system, equivalents are shown in parentheses. The measures shown in parentheses are intended only for those contracts in which they are specified. No guarantee is provided, explicit or implicit, that the units are accurate conversions. Work included in the contract will be accepted on the basis of measures shown in parentheses only when such measures are specified.

In addition to the english equivalents shown in the text, the following general notes and table are provided to assist you in becoming familiar with the metric system.

SI UNITS AND CONVERSION FACTORS

MEASUREMENT	ENGLISH UNIT	ENGLISH UNIT SYMBOL	MULTIPLIER FOR CONVERSION FROM ENGLISH UNIT TO SI UNIT (*)	SI UNIT	SI SYMBOL
Acceleration	foot per second squared mile per hour squared	ft/sec ² mi/h ²	0.304 8 exactly 1.0609 3	meter per second squared kilometer per second squared	m/s ² km/h ²
Area	square inch square foot square yard acre square mile	in ² ft ² yd ² ac mi ²	645.16 exactly 0.092 9 0.836 1 0.404 7 2.59	square millimeter square meter square meter hectare square kilometer	mm ² m ² m ² ha km ²
Density	pound per cubic foot	lb/ft ³	16.018 46	kilogram per cubic meter	kg/m ³
Energy	foot-pound force kilowatt hour	ft lbf kW h	1.355 8 3 600 000. exactly	joule joule	J J
Force/Weight (Gravity of Force)	pound force kilopound force ton	lbf kip t	4.448 2 4.448 2 8.896 4	newton kilonewton kilonewton	N kN kN
Length	inch foot yard mile	in. ft yd mi	25.4 exactly 0.304 8 exactly 0.914 4 exactly 1.609 3	millimeter meter meter kilometer	mm m m km

MEASUREMENT	ENGLISH UNIT	ENGLISH UNIT SYMBOL	MULTIPLIER FOR CONVERSION FROM ENGLISH UNIT TO SI UNIT (*)	SI UNIT	SI SYMBOL
Mass	ounce pound mass ton mass	oz lbm t	28.349 5 0.453 6 0.907 2	gram kilogram megagram	g kg Mg
Power	horsepower (550 ft·lbf/s)	hp	745.699 9	watt	W
Pressure/Stress	pound per square inch pound per square foot kilopound per square inch	lb/in ² lb/ft ² kip/in ²	6.894 8 0.047 88 6.894 8	kilopascal kilopascal megapascal	kPa kPa MPa
Speed/Velocity	foot per second mile per hour	ft/s mi/h	0.304 8 exactly 1.609 3	meter per second kilometer per hour	m/s km/h
Temperature	degree Fahrenheit	°F	(°F - 32)/1.8(**) exactly	degree Celsius	°C
Volume, Fluid	cubic inch fluid ounce gallon 1000 gallons	in ³ fl oz gal. M.G.	16.387 1 29.573 4 3.785 4 3.785 4	milliliter milliliter liter kiloliter	mL mL L kL
Volume, Solid	cubic inch cubic foot bushel cubic yard 1000 feet board measure	in ³ ft ³ bu yd ³ MFBM	16 387.06 exactly 0.028 32 0.035 24 0.764 6 2.359 7	cubic millimeter cubic meter cubic meter cubic meter cubic meter	mm ³ m ³ m ³ m ³ m ³

(*) Conversion from SI unit to English unit may be made by dividing the SI unit by the conversion factor shown in this column.

(**) This is a formula, and not a multiplier. The Fahrenheit temperature is substituted for °F in the formula to attain the Celsius temperature. Conversion from Celsius temperature to Fahrenheit temperature may be made by substituting the Celsius temperature for °C in the formula $1.8 \times ^\circ\text{C} - 32$. This is an exact conversion.

Angles will continue to be measured in degrees, minutes, and seconds instead of radians.

GENERAL NOTES

1. The SI unit of millimeter should be used to covert inches to millimeters.
2. The SI unit of Mass is the Kilogram (Kg) which should be used for smaller masses expressed in pounds. The megagram (Mg) should be used for larger masses expressed in tons.
3. All units peculiar to the various cgs systems (measurement systems constructed by using the centimeter, gram and second as base units) are to be avoided.
4. In commercial and everyday use, the term weight nearly always means mass; thus, when one speaks of a person's weight, the quantity referred to is mass. In Science and Technology, the term weight of a body has usually meant the force that, if applied to the body, would give it an acceleration equal to the local acceleration of free fall g (acceleration of gravity). When the term is used, it is important to know whether mass or force is intended and to use SI Units properly, by using Kilograms for Mass or Newtons for Force. The use of force of gravity (mass times acceleration of gravity) instead of weight with this meaning is recommended. Because of the dual use of the term weight as a quantity, this term should be avoided in technical practice except under circumstances in which its meaning is completely clear.
5. The term load means either mass or force, depending on its use. A load that produces a vertically downward force because of the influence of gravity acting on a mass may be expressed in mass units. Any other load is expressed in force units.
6. A quantity stated as limits, such as "not more than" or "maximum", must be handled so that the stated limit is not violated.
7. Conversion of quantities should be handled with careful regard to the implied correspondence between the accuracy of the data and the given number of digits. In all conversions, the number of significant digits retained should be such that accuracy is neither sacrificed nor exaggerated. For example, a length of 125 ft converts exactly to 38.1 m. If however, the 125-ft length has ben obtained by rounding to the nearest 5 ft, the conversion should be given as 38 m. The proper conversion procedure is to multiply a value by a conversion factor that is more accurate than is required, the result is then rounded to the appropriate number of significant digits.
8. The rule for addition and subtraction is that the answer shall contain no significant digits farther to the right than occur in the least precise number. The rule for multiplication and division is that the product or quotient shall contain no more significant digits than are contained in the number with the fewest significant digits used in the multiplication.

9. When a figure is to be rounded to fewer digits than the total number available, the procedure should be as follows: a. When the first digit discarded is less than 5, the last digit retained should not be changed. For example, 3.46325, if rounded to four digits, would be 3.463; if rounded to three digits, 3.46. b. When the first digit discarded is greater than 5, or if it is a 5 followed by at least one digit other than 0, the last digit retained should be increased by one unit. For example, 8.37652, if rounded to four digits, would be 8.377; if rounded to three digits, 8.38. c. When the first digit discarded is exactly 5 followed by zeros, the last digit retained should be rounded upward if it is an odd number, but no adjustment made if it is an even number. For example, 4.365 when rounded to three digits, becomes 4.36. The number 4.355 would also round to the same value, 4.36, if rounded to three digits.
10. Refer to ASTM E 380 Standard Practice For Use of International System of Units (SI) for other conversion factors.

TABLE OF CONTENTS

Section	Title
---------	-------

SECTION 100 -- GENERAL PROVISIONS

101 --	DEFINITIONS AND TERMS
101.01	Abbreviations
101.02	Above Normal Rainfall
101.03	Blank
101.04	Bid Bond
101.05	Bidder
101.06	Bridge
(a)	Length
(b)	Roadway Width
101.07	Calendar Day
101.08	Blank
101.09	Change Order
101.10	Construction Limits
101.11	Contract
101.12	Contract Information Book
101.13	Contract Item (Pay Item)
101.14	Contract Time
101.15	Contractor
101.16	Culvert
101.17	Department
(a)	Division of Materials and Tests
(b)	Contract Services Section
(c)	Procurement and Distribution Division
101.18	Commissioner
101.19	Engineer
101.20	Equipment
101.21	Extra Work
101.22	Force Account Work
101.22.1	Frequency Manual
101.23	Holidays
101.24	Invitation for Bids
101.25	Itemized Proposal
101.26	Laboratory
101.27	Major and Minor Contract Items
101.28	Materials
101.29	Notice to Proceed
101.30	Open to Unrestricted Traffic
101.31	Pavement Structure
101.32	Performance Bond
101.33	Plans
101.33.1	Professional Engineer
101.34	Profile Grade
101.35	Project
101.36	Proposal
101.37	Proposal Book
101.38	Reasonably Close Conformance
101.39	Right-of-Way
101.40	Road
101.41	Roadbed
101.42	Roadside
101.43	Roadside Development
101.44	Roadway

TABLE OF CONTENTS

Section	Title
---------	-------

101.45	Schedule of Pay Items
101.46	Shoulder
101.47	Sidewalk
101.48	Special Provisions
101.49	Specifications
101.50	Specified Completion Date
101.51	State
101.52	Street
101.53	Structures
101.53.1	Substantial Completion
101.54	Blank
101.55	Subcontractor
101.56	Subgrade
101.57	Substructure
101.58	Superintendent
101.59	Superstructure
101.60	Supplemental Specifications
101.61	Surety
101.62	Technician or Inspector
101.63	Titles (Headings)
101.64	Township, Town, City
101.65	Traveled Way
101.66	Work
101.67	Work Day
101.68	Working Drawings
102	-- BIDDING REQUIREMENTS AND CONDITIONS
102.01	Prequalification and Bidding
102.02	Certification Regarding Lobbying for Contracts, Grants, Loans, and Cooperative Agreements
103	-- AWARD AND EXECUTION OF CONTRACT
103.01	Disadvantaged Business Enterprise Program
(a)	General Requirements
(b)	Definitions
1.	DBE
2.	Small Business Concern
3.	Socially and Economically Disadvantaged Individuals
4.	Certified DBE
(c)	Goal
1.	DBE Joint Venture Type A
2.	DBE Joint Venture Type B
(d)	Affirmative Actions
(e)	Guidelines for Determining Good Faith Efforts
(f)	Affirmative Action Certification
(g)	Subcontracts
(h)	Leases and Rentals
(i)	Records and Reports
103.02	Specific Equal Employment Opportunity Responsibilities
103.03	Blank
103.04	Insurance
(a)	Contractor's Comprehensive General Liability
(b)	Comprehensive Automobile Liability
(c)	Railroad's Protective Public Liability and Property Damage Liability
(d)	Blank
(e)	Owners' and Contractors' Protective Liability Insurance Coverage for Operations of Designated Contractor
(f)	Basis of Payment

TABLE OF CONTENTS

Section	Title
103.05	Waiver of Damages
103.06	Wage and Labor Requirements
(a)	Nondiscrimination of Employees
(b)	Affidavits and Payrolls
(c)	Wage Stipulations
1.	General Decision Included in Contract Information Book
2.	General Decision Not Included in Contract Information Book
103.07	Accident Prevention and Safety
104 --	SCOPE OF WORK
104.01	Intent of Contract
104.02	Differing Site Conditions, Suspension of Work and Significant Changes in the Character of Work
(a)	Differing Site Conditions
(b)	Suspensions of Work Ordered by the Engineer
(c)	Significant Changes in the Character of Work
(d)	Pre-established Remedies to Changed Conditions
104.03	Extra Work
104.04	Maintenance of Traffic
(a)	Special Detours
(b)	Maintenance Directed by the Engineer
(c)	Blank
(d)	Traffic Control for Patching on a 2-Lane Roadway
104.05	Removal and Disposal of Structures and Obstructions
104.06	Removal and Disposal of Regulated Materials
(a)	For Such Materials which are Identified in the Proposal Book as Being Present on the Project Site
(b)	For Such Materials which are not Identified in the Proposal Book as Being Present on the Project Site
104.07	Rights in and Use of Materials Found in the Project Site
104.08	Final Clean-Up
105 --	CONTROL OF WORK
105.01	Authority of the Engineer
105.02	Plans and Working Drawings
105.03	Conformance with Plans and Specifications
105.04	Coordination of Plans, Standard Specifications, Supplemental Specifications, and Special Provisions
105.05	Cooperation by Contractor
105.06	Cooperation with Utilities
105.07	Cooperation Between Contractors
105.08	Construction Stakes, Lines, and Grades
(a)	Construction Engineering by the State
(b)	Construction Engineering by the Contractor
(c)	Production Staking by the Contractor
105.09	Duties of Technician and Inspector
105.10	Inspection of Work
105.11	Removal of Unacceptable and Unauthorized Work
105.12	Load Restrictions
105.13	Maintenance During Construction
105.14	Failure to Maintain Roadway, Structures, Barricades, and Construction Signs
105.15	Acceptance and Final Inspection
(a)	Partial Acceptance
(b)	Final Acceptance
105.16	Claims for Adjustment and Disputes
105.17	Field Office
105.18	Method of Measurement
105.19	Basis of Payment
106 --	CONTROL OF MATERIAL

TABLE OF CONTENTS

Section	Title
106.01	Source of Supply and Quality Requirements
(a)	Approved or Prequalified Materials
(b)	Material Records
1.	Documentation of Material Delivery
2.	Delivery Ticket Information
3.	Payment Procedures
(c)	Buy American Requirement
106.02	Samples, Tests, Cited Specifications
106.03	Plant Inspection
106.04	Field Laboratory
106.05	Storage of Materials
106.06	Handling Materials
106.07	Unacceptable Materials
106.08	Hazard Communication Program
106.09	Department Furnished Materials
106.10	Proportioning Materials
106.11	Sample Asbestos Exclusion Letter
107 --	LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC
107.01	Laws to be Observed
107.02	Permits, Licenses, and Taxes
107.03	Patented Devices, Materials, and Processes
107.04	Restoration of Surfaces Opened by Permit
107.05	Federal Aid Provisions
107.06	Equal Employment Opportunity Trainees
107.07	Sanitary Conditions Requirements
107.08	Public Convenience and Safety
(a)	Employee Safety
(b)	Dust and Air Pollution
(c)	Protection to Traffic
(d)	Notice to Local Public Officials
(e)	Convenience to Traffic and Property Owners
107.09	Railroad-Highway Requirements
(a)	Protection of Track Ballast
(b)	Hold Harmless Clause
107.10	Blank
107.11	Bridges over Navigable Waters
107.12	Traffic Control Devices
107.13	Use of Explosives
107.14	Protection and Restoration of Property and Landscape
107.14.1	Erosion Control Plan and Proof of Publication
107.15	Forest Protection
107.16	Responsibility for Damage Claims
107.17	Opening Sections of Project to Traffic
107.18	Contractor's Responsibility for Work
107.19	Contractor's Responsibility for Utility Property and Services
107.20	Furnishing Right-of-Way
107.21	Personal Liability of Public Officials
107.22	Waiver of Legal Rights
107.23	Governing Law
107.24	Severability
108 --	PROSECUTION AND PROGRESS
108.01	Subletting of Contract
108.02	Notice to Proceed
108.03	Prosecution of the Work

TABLE OF CONTENTS

Section	Title
108.04	Prephase Site Construction Meetings
108.05	Limitation of Operations
108.06	Character of Workers, Methods, and Equipment
108.07	Determination and Extension of Contract Time
108.08	Failure to Complete on Time
108.09	Default and Termination of Contract
108.10	Termination of Contractor's Responsibility
108.11	Contract Documentation
109 --	MEASUREMENT AND PAYMENT
109.01	Measurement of Quantities
(a)	General Requirements
(b)	Scales and Measurement by Mass (Weight
(c)	Measurement by Volume
(d)	Measurement of Asphalt Materials
(e)	Measurement of Portland Cement Concrete
(f)	Measurement of Aggregates
(g)	Measurement of Timber or Lumber
(h)	Rental of Equipment
(i)	Manufactured Materials
109.02	Scope of Payment
109.03	Compensation for Altered Quantities
109.04	Cost Reduction Incentive
(a)	Cost Reduction Incentive Proposal Requirements
(b)	Approval of Proposal
(c)	Method of Measurement
(d)	Basis of Payment
109.05	Extra Work and Force Account Work
(a)	Labor Costs
(b)	Bond and Insurance
(c)	Materials
(d)	Equipment
(e)	Miscellaneous
(f)	Subcontracting
(g)	Compensation
(h)	Statements
(i)	Cost Breakdown
109.06	Eliminated Pay Items
109.07	Partial Payments
109.08	Final Payment
110 --	MOBILIZATION AND DEMOBILIZATION
110.01	Description
110.02	Limitations
110.03	Method of Measurement
110.04	Basis of Payment
111 --	STOCKPILED MATERIALS
111.01	Description
111.02	General Requirements
111.03	Structural Steel and Concrete Structural Members
(a)	Delivered to the Job Site
(b)	Acceptably Stored at the Fabricator's or Manufacturer's Storage Facilities
111.04	Dowel Bar Assemblies
111.05	Granular Base, Subbase Materials, and Aggregates for HMA and Concrete Pavements
111.06	Bridge Expansion Joints

TABLE OF CONTENTS

Section Title

- (a) Type SS
- (b) Type M
- 111.07 Structural Supports for Signals, Signs and Luminaries
- 111.08 Precast Concrete Median Barrier
- 111.09 Additional Requirements
- 111.10 Method of Measurement
- 111.11 Basis of Payment

SECTION 200 -- EARTHWORK

201 -- CLEARING AND GRUBBING

- 201.01 Description
- 201.02 General
- 201.03 Clearing and Grubbing
- 201.04 Scalping
- 201.05 Hedge Removal
- 201.06 Method of Measurement
 - (a) Area Basis
 - (b) Lump Sum Basis
 - (c) Linear Basis
 - (d) Individual Unit Basis
- 201.07 Basis of Payment
 - (a) Area Basis
 - (b) Lump Sum Basis
 - (c) Linear Basis
 - (d) Individual Unit Basis
 - (e) Clearing Right-of-Way
 - (f) Exclusions

202 -- REMOVAL OF STRUCTURES AND OBSTRUCTIONS

- 202.01 Description
- 202.02 General Requirements
 - (a) Type X Waste
 - (b) Type Y Waste
 - (c) Type Z Waste
- 202.03 Removal of Bridges, Culverts, and Other Drainage Structures
 - (a) Complete
 - (b) Portions
 - (c) Disposal of Concrete
- 202.04 Removal of Pipe and Tile Drains
- 202.05 Removal of Pavement, Sidewalks, Curbs, Surface, Surface Milling, etc
- 202.06 Removal of Houses and Buildings
- 202.06.1 Inspection and Removal of Asbestos
- 202.07 Removal of Underground Storage Tanks Containing Petroleum Products or Other Hazardous Chemicals
 - (a) Type A Waste
 - (b) Type B Waste
 - (c) Type C Waste
- 202.08 Remediation of Contaminated Soil and Groundwater
- 202.09 Remediation of Other Regulated Materials
- 202.10 Transportation and Disposal of Regulated Materials
- 202.11 Blank
- 202.12 Method of Measurement
- 202.13 Basis of Payment

203 -- EXCAVATION AND EMBANKMENT

- 203.01 Description

TABLE OF CONTENTS

Section	Title
203.02	Common Excavation
203.03	Rock Excavation
203.04	Unclassified Excavation
203.05	Peat Excavation
203.06	Waterway Excavation
203.07	Class Y Excavation
203.08	Borrow or Disposal
203.09	General Requirements
203.10	Disposal of Excavated Material (Except Waterway and Peat Excavation)
203.11	Disposal of Waterway Excavation
203.12	Disposal of Peat
203.13	Slides
203.14	Drainage
203.15	Excavating Rock
203.16	Peat Deposit Treatment
(a)	Treatment of Existing Fills
(b)	Treatment by Removal
(c)	Treatment by Displacement
203.17	Cased Test Holes
203.18	Embankment Construction
203.19	Embankment Over and Around Structures
203.20	Rock and Shale Embankment
(a)	Rock Embankment
(b)	Shale, Shale and Soft Rock Mixtures, or Soft Rock
(c)	Shale and Thinly Layered Limestone
203.21	Embankment on Hillsides or Slopes
203.22	Embankment Over Existing Roadbeds
203.23	Embankment Other Than Rock and Shale, With Density Control
203.24	Method of Making Density Tests
(a)	Laboratory
(b)	Field
203.25	Embankment Without Density Control
203.26	Proofrolling
203.27	Method of Measurement
(a)	Contract Quantity
(b)	Measured Quantities
(c)	Measurement on a Linear Basis
(d)	Measurement of Excavation Items on a Weight Basis
(e)	Measurement of Embankments
(f)	Measurement of Borrow
(g)	Measurement of Subgrade Treatment
(h)	Measurement of Water for Shale, Shale and Soft Rock Mixtures, or Soft Rock
(i)	Lump Sum
(j)	Measurement of Exploratory Cores
203.28	Basis of Payment
204 --	GEOTECHNICAL INSTRUMENTATION
204.01	Description
204.02	Materials
204.03	Settlement Plates
(a)	Installation of Settlement Plates
(b)	Instrument Readings and Settlement Period
204.04	Method of Measurement
204.05	Basis of Payment
205 --	TEMPORARY EROSION AND SEDIMENT CONTROL

TABLE OF CONTENTS

Section	Title
205.01	Description
205.02	Materials
205.03	Temporary Perimeter Protection
(a)	Straw Bales
(b)	Silt Fence
205.04	Temporary Slope Protection
205.05	Sediment Control in Side Ditches
205.06	Sediment Basin
205.06.1	Fish Pool and Sediment Trap
205.07	Temporary Inlet Protection
205.08	Maintenance of Erosion and Sediment Control Measures
205.09	Removal of Temporary Erosion and Sediment Control Measures
205.10	Method of Measurement
205.11	Basis of Payment
206 --	STRUCTURE EXCAVATION
206.01	Description
206.02	Class X Excavation
(a)	General Excavation
(b)	Excavation for Foundations of Traffic Support Structures
206.03	Wet Excavation
206.04	Dry Excavation
206.05	Foundation Excavation, Unclassified
206.06	General Requirements
206.07	Disposal of Excavated Material
206.08	Preparation of Foundation Surfaces
206.09	Cofferdams and Temporary Construction Dikes
206.10	Method of Measurement
206.11	Basis of Payment
(a)	Culverts and Retaining Walls
(b)	Bridges
(c)	Traffic Structure Supports
207 --	SUBGRADE
207.01	Description
207.02	General Requirements
207.03	Subgrade for HMA Base Courses
207.04	Subgrade for Approaches
207.05	Subgrade for Cement Concrete Base and Pavement
207.06	Special Subgrade Treatment
207.07	Method of Measurement
207.08	Basis of Payment
208 --	FINISHING SHOULDERS, DITCHES, AND SLOPES
208.01	Description
208.02	Finishing Shoulders
208.03	Finishing Ditches
208.04	Finishing Slopes
208.05	Blank
208.06	Finishing at Contract Drainage Structures
208.07	Method of Measurement
208.08	Basis of Payment
209 --	FINISHING EARTH GRADED ROADS
209.01	Description
209.02	Construction Requirements
209.03	Method of Measurement

TABLE OF CONTENTS

Section	Title
209.04	Basis of Payment
210 --	FINAL TRIMMING AND CLEANING
210.01	Description
210.02	Construction Requirements
210.03	Method of Measurement
210.04	Basis of Payment
211 --	B BORROW FILL AND BACKFILL
211.01	Description
211.02	Materials
(a)	Gradation for Structure Backfill
(b)	Gradations for Other Types of Backfill
(c)	Flowable Mortar Substitution
211.03	General Requirements
211.04	Mechanical Compaction
211.05	Blank
211.06	Embankment for Bridges
211.07	B Borrow Around Bents
211.08	Spandrel Filling
211.09	Method of Measurement
211.10	Basis of Payment
212 --	STOCKPILED SELECTED MATERIALS
212.01	Description
212.02	Materials
212.03	Construction Requirements
212.04	Method of Measurement
212.05	Basis of Payment
213 --	FLOWABLE MORTAR
213.01	Description
213.02	Materials
213.03	Proportioning
213.04	Mix
(a)	Flow
(b)	Average Penetration Resistance
(c)	Mixing Equipment
(d)	Placement
(e)	Limitation of Operations
213.05	Blank
213.06	Method of Measurement
213.07	Basis of Payment
214 --	DETENTION PONDS
214.01	Description
214.02	Materials
214.03	Construction Requirements
214.04	Method of Measurement
214.05	Basis of Payment

SECTION 300 -- BASES

301 --	Blank
302 --	Blank

TABLE OF CONTENTS

Section	Title
303 --	COMPACTED AGGREGATE BASE, SURFACE, OR SHOULDERS
303.01	Description
(a)	Type O Mix
(b)	Type P Mix
303.02	Materials
303.03	Preparation of Type P Mixture
(a)	Mixer Unit
(b)	Conveyors and Feeders
(c)	Water Pump and Meter
(d)	Mixing
303.04	Calcium Chloride
303.05	Preparation of Subgrade or Subbase
303.06	Handling and Transporting Mixtures
303.07	Spreading Mixtures
303.08	Control of Width
303.09	Compacting Aggregate
303.10	Checking and Correcting Surface
303.11	Temperature Limitations
303.12	Priming Compacted Aggregate Base
303.13	Blank
303.14	Protection of Surface
303.15	Method of Measurement
303.16	Basis of Payment
304 --	SUBBASE
304.01	Description
304.02	Materials
304.03	Subgrade Preparation
304.04	Spreading
304.05	Compacting
304.06	Surface Requirements
304.07	Method of Measurement
304.08	Basis of Payment
305 --	RECONDITIONING
305.01	Description
305.02	Materials
305.03	Repairing
305.04	Blank
305.05	Patching Asphalt Pavement
305.06	Patching Rigid Pavement or Rigid Base
(a)	Patching with Portland Cement Concrete
(b)	Patching with HMA Mixture
305.07	Blank
305.08	Sealing Cracks and Joints in Asphalt Pavement
305.09	Filling Cracks and Joints in Concrete Pavement
305.10	Widening
(a)	Widening with HMA Mixture
(b)	Widening with Cement Concrete
(c)	Widening with Compacted Aggregate
305.11	Method of Measurement
305.12	Basis of Payment
306 --	Blank
307 --	PORTLAND CEMENT CONCRETE BASE
307.01	Description

TABLE OF CONTENTS

Section Title

307.02	Materials
307.03	General Requirements
307.04	Joints
307.05	Placing Steel
307.06	Final Finish
307.07	Curing
307.08	Monolithic Curb
307.09	Method of Measurement
307.10	Basis of Payment
308 --	Blank
309 --	Blank
310 --	CEMENT CONCRETE PAVEMENT PATCHING
310.01	Description
310.02	Materials
310.03	Proportioning
310.04	Concrete Removal
(a)	Partial Depth Removal
(b)	Full Depth Removal
310.05	Cleaning
310.06	Patching
(a)	Partial Depth Patching
(b)	Full Depth Patching
310.07	Method of Measurement
310.08	Basis of Payment

SECTION 400 -- ASPHALT PAVEMENTS

401 --	QUALITY CONTROL/QUALITY ASSURANCE, QC/QA, HOT MIX ASPHALT, HMA, PAVEMENT
401.01	Description
401.02	Quality Control
401.03	Materials
401.04	Design Mix Formula
401.05	Volumetric Mix Design
(a)	Gradation Table for Design ESAL Equal To or Greater Than 10,000,000
(b)	Gradation Table for Design ESAL Less Than 10,000,000
401.06	Recycled Materials
401.07	Lots and Sublots
401.08	Job Mix Formula
401.09	Acceptance of Mixtures
401.10	General
401.11	Preparation of Surfaces to be Overlaid
401.12	Process Control
401.13	Weather Limitations
401.14	Spreading and Finishing
401.15	Joints
401.16	Density
(a)	Mainline ESAL Equal To or Greater Than 10,000,000
(b)	Mainline ESAL Equal To or Greater Than 1,000,000 and Less Than 10,000,000
(c)	Mainline ESAL Less Than 1,000,000
401.17	Shoulder Corrugations
(a)	Formed Corrugations
(b)	Milled Corrugations

TABLE OF CONTENTS

Section	Title
401.18	Pavement Smoothness
401.19	Adjustment Points
(a)	Mixture
(b)	Density
1.	Mainline ESAL Equal To or Greater Than 10,000,000
2.	Mainline ESAL Equal To or Greater Than 1,000,000 and Less Than 10,000,000
(c)	Smoothness
401.20	Appeals
(a)	Mixture
(b)	Density
1.	Mainline ESAL Equal To or Greater Than 10,000,000
2.	Mainline ESAL Equal To or Greater Than 1,000,000 and Less Than 10,000,000
401.21	Method of Measurement
401.22	Basis of Payment
402 --	HOT MIX ASPHALT, HMA, PAVEMENT
402.01	Description
402.02	Materials
402.03	Job Mix Formula
402.04	Mix Design Criteria
(a)	Composition Limits for Base Mixtures
(b)	Composition Limits for Intermediate Mixtures
(c)	Composition Limits for Surface Mixtures
(d)	Composition Limits for HMA Rumble Strip Mixtures
(e)	Composition Limits for HMA Wedge and Leveling Mixtures
402.05	Recycled Materials
402.06	Acceptance of Mixtures
402.07	Preparation of Mixtures
402.08	General
402.09	Preparation of Surfaces to be Overlayed
402.10	Weather Limitations
402.11	Spreading and Finishing
402.12	Joints
402.13	Compaction
402.14	Low Temperature Density Requirements
402.15	Shoulder Corrugations
(a)	Formed Corrugations
(b)	Milled Corrugations
402.16	Pavement Smoothness
402.17	Method of Measurement
402.18	Basis of Payment
403 --	COLD MIXED ASPHALT, CMA, PAVEMENT
403.01	Description
403.02	Materials
403.03	Weather Limitations
403.04	Equipment
403.05	Preparation of Mixtures
403.06	Preparation of Subgrade or Base
403.07	Spreading Mixture
403.08	Curing
403.09	Compaction
403.10	Surface Tolerances
403.11	Method of Measurement
403.12	Basis of Payment

TABLE OF CONTENTS

Section	Title
404 -- SEAL COAT	
404.01	Description
404.02	Asphalt Material
404.03	Cover Aggregate
404.04	Weather Limitations
404.05	Equipment
404.06	Preparation of Surface
404.07	Applying Asphalt Material
404.08	Application of Cover Aggregate
404.09	Method of Measurement
404.10	Basis of Payment
405 -- PRIME COAT	
405.01	Description
405.02	Asphalt Material
405.03	Cover Aggregate
405.04	Weather Limitations
405.05	Equipment
405.06	Preparation of Surface
405.07	Application of Asphalt Material
405.08	Cover Aggregate
405.09	Method of Measurement
405.10	Basis of Payment
406 -- TACK COAT	
406.01	Description
406.02	Asphalt Material
406.03	Equipment
406.04	Preparation of Surface
406.05	Application of Asphalt Material
406.06	Method of Measurement
406.07	Basis of Payment
407 -- DUST PALATIVE	
407.01	Description
407.02	Asphalt Material
407.03	Weather Limitations
407.04	Equipment
407.05	Preparation of Surface
407.06	Application of Asphalt Material
407.07	Method of Measurement
407.08	Basis of Payment
408 -- EQUIPMENT	
408.01	Production, Transportation, and Laydown of Asphalt Mixtures
408.02	Mixing Plant
(a)	HMA Mixing Plant
1.	Plant Inspection
2.	Proportioning Systems
3.	Material Storage
a.	Aggregates
b.	Asphalt
4.	Aggregate Feed System
5.	Drier Unit
6.	Dust Collector
7.	Mixing Unit
8.	Mix Load-out Scales

TABLE OF CONTENTS

Section	Title
	9. Hot Surge Bins
	10. Sampling Point Requirements
	(b) CMA Mixing Plant
408.03	HMA Laydown Operations
	(a) Distributor
	(b) Hauling Equipment
	(c) Laydown Equipment
	1. Paver
	2. Widener
	3. Other Mechanical Devices
	(d) Compaction Equipment
	1. Tandem Roller
	2. Three Wheel Roller
	3. Pneumatic Tire Roller
	4. Vibratory Roller
	5. Trench Roller
	6. Speciality Roller/Compactor
	(e) Miscellaneous Equipment
	1. Aggregate Spreader
	2. Rotary Power Broom
	(f) Smoothness Equipment
	1. Profilograph
	2. Straightedge - 4.9 m (16 ft)
	3. Straightedge - 3 m (10 ft)
409 --	Blank.
410 --	Blank

SECTION 500 -- RIGID PAVEMENT

501 --	PORTLAND CEMENT CONCRETE PAVEMENT
501.01	Description
501.02	Materials
501.03	Proportioning
	(a) Composition of Concrete
	1. Blank
	2. Exceptions to AASHTO T 23 Making and Curing Concrete Specimens in the Field
	3. Exceptions to AASHTO T 97 for Flexural Test
	4. Exceptions to AASHTO T 121 for Determining the Relative Yield
	(b) Methods of Entraining Air
	(c) High Early Strength Pavement
501.04	Equipment
	(a) Batching Plant and Equipment
	1. General
	2. Bins and Hoppers
	3. Scales
	4. Automatic Weighing Device
	(b) Mixers
	1. Truck Mixers and Truck Agitators
	2. Non-Agitator Trucks
	(c) Finishing Equipment
	1. Finishing Machine
	2. Vibrators
	(d) Concrete Saw

TABLE OF CONTENTS

Section	Title
	(e) Forms
501.05	Preparation of Grade
501.06	Setting Forms
	(a) Base Support
	(b) Form Setting
	(c) Grade and Alignment
501.07	Conditioning of Subgrade or Base Course
501.08	Handling, Measuring, and Batching Materials
501.09	Mixing Concrete
501.10	Limitations of Mixing
501.11	Placing Concrete
501.12	Test Specimens
501.13	Strike-off of Concrete and Placement of Reinforcement
501.14	Joints
	(a) General Requirements
	(b) Sawed Longitudinal Joints
	(c) Expansion Joints
	(d) Sawed Contraction Joints
	(e) Transverse Sawed Construction Joints
	(f) Dowel Bars and Assemblies
	(g) Retrofitted Tie-Bars for Pavement Joints
	(h) Terminal Joints
501.15	Final Strike-Off, Consolidation, and Finishing
	(a) Consolidation and Strike-Off
	(b) Floating
	(c) Checking and Surface Correction
	(d) Final Finishing
	1. Method 1-Brooming
	2. Method 2-Tining
	(e) Edging at Forms and Joints
501.16	Pavement Smoothness
501.17	Curing
	(a) Double Burlap
	(b) Straw
	(c) Waterproof Blankets
	(d) Ponding
	(e) White Membrane
	(f) Curing in Cities and Towns
501.18	Removing Forms
501.19	Sealing Cracks and Joints
501.20	Inspection for Pavement Cracking
501.21	Protection of Pavement
501.22	Opening to Traffic
501.23	Concrete Pavement, Slip-Form Method
	(a) General Requirements
	(b) Grade
	(c) Placing Concrete
	(d) Finishing
	(e) Curing
	(f) Joints
	(g) Protection Against Rain
501.24	Tolerance In Pavement Thickness.
	(a) General Requirements
	(b) Taking Cores
	(c) Measuring the Cores

TABLE OF CONTENTS

Section Title

(d) Determination of Average Thickness	
(e) Pavement Removal and Replacement for Core Thickness Deficiency of Greater than 25 mm (1.0 in.).	
(f) Reinforcing Steel Requirements for Reinforced Concrete Pavement	
(g) Measuring the Reinforcing Steel Placement in Concrete Pavement	
(h) Removal Limits for Deficiency in Steel Placement	
501.25 Method of Measurement	
501.26 Basis of Payment	
(a) Adjusted Payment for Deficient Pavement Thickness	
(b) Reduced Payment for Deficient Reinforcing Steel Placement in Concrete Pavement	
(c) Non-payment or Removal of Pavement for Core Thickness Deficiencies of more than 13 mm (0.5 in.) to 25 mm (1.0 in.)	
502 -- QUALITY ASSURANCE FOR PORTLAND CEMENT CONCRETE PAVEMENT	
502.01 Description	
502.02 Quality Control Plan	
(a) General Requirements	
(b) Origin and Sampling of Materials	
(c) Trial Batch Demonstration	
(d) Concrete Batching and Hauling	
(e) Concrete Placement	
(f) Concrete Finishing, Texturing, and Curing	
(g) Production Testing	
502.03 Materials	
502.04 Concrete Mixture and Mix Design	
502.05 Production Control and Acceptance Testing	
502.06 Facilities and Equipment for Production Control and Acceptance Testing	
502.07 Test Methods and Procedures	
(a) Exceptions to AASHTO T 141	
(b) Exceptions to AASHTO T 23	
(c) Exceptions to AASHTO T 97	
(d) Exceptions to AASHTO T 121	
(e) Exceptions to AASHTO T 152	
502.08 Trial Batch Demonstration	
502.09 Lots and Sublots, and Selection of Test Locations	
502.10 Equipment	
502.11 Preparation of Grade	
502.12 Setting Forms	
502.13 Conditioning of Subgrade or Base Course	
502.14 Handling, Measuring, and Batching Materials	
502.15 Mixing Concrete	
502.16 Natural Light and Weather Limitations	
502.17 Placing Concrete	
502.18 Test Specimens	
502.19 Placement of Reinforcement and Strike-off of Concrete	
502.20 Joints	
502.21 Final Consolidation, Strike-Off, and Finishing	
502.22 Curing	
502.23 Removing Forms	
502.24 Sealing Cracks and Joints	
502.26 Protection of Pavement	
502.27 Opening to Traffic	
502.28 Concrete Pavement, Slip-Form Method	
502.29 Substandard Work Produced During Concrete Paving Operations	
502.30 Acceptance Testing and Approval of Concrete Pavement Properties	
(a) Plastic Unit Weight Acceptance Test.	
(b) Water/Cementitious Ratio Acceptance Determination	

TABLE OF CONTENTS

Section Title

- (c) Flexural Strength Acceptance Test
- (d) Air Content Acceptance Test
- 502.31 Pavement Smoothness and Surface Tolerances
- 502.32 Tolerance in Pavement Thickness
- 502.33 Appeal Procedure for Air Content and Flexural Strength Acceptance Test Results
 - (a) Pavement Cores
 - (b) Air Content Appeal
 - (c) Flexural Strength Appeal
- 502.34 Method of Measurement
- 502.35 Basis of Payment
 - (a) Payment for Other Pavement Components
 - (b) Price Adjustment for Flexural Strength and Air Content
 - 1. Flexural Strength Price Adjustment
 - 2. Air Content Price Adjustment
 - (c) Smoothness Price Adjustment
 - (d) Pavement Thickness and Reinforcing Steel Price Adjustment

SECTION 600 -- INCIDENTAL CONSTRUCTION

601 -- GUARDRAIL

- 601.01 Description
- 601.02 Materials
- 601.03 General Requirements
- 601.04 Guardrail Erection
- 601.05 Curved W-Beam Guardrail Systems
- 601.06 Guardrail Transitions
- 601.07 Guardrail End Treatments
- 601.08 Extension of Existing Guardrail
- 601.09 Removal of Existing Guardrail
- 601.10 Adjusting Existing Guardrail Height
- 601.11 Resetting Guardrail
- 601.12 Method of Measurement
- 601.13 Basis of Payment

602 -- CONCRETE BARRIER

- 602.01 Description
- 602.02 Materials
- 602.03 Concrete Barrier and Concrete Glare Screen
 - (a) Precast Concrete Barrier and Concrete Glare Screen
 - (b) Cast-in-Place Concrete Barrier and Concrete Glare Screen
 - (c) Finishing
 - (d) Sealing
 - (e) Joints
 - (f) Reflectorization
- 602.04 Temporary Concrete Barrier
 - (a) Placement
 - (b) Connection
 - (c) Anchorage
 - (d) Delineation
- 602.05 Method of Measurement
- 602.06 Basis of Payment

603 -- FENCES

- 603.01 Description
- 603.02 Materials

TABLE OF CONTENTS

Section	Title
603.03	General Requirements
603.04	Setting Posts
603.05	Placing Barbed and Tension Wire and Fabric
603.06	Resetting Fence
603.07	Method of Measurement
603.08	Basis of Payment
604 --	SIDEWALKS, CURB RAMPS AND STEPS
604.01	Description
604.02	Materials
604.03	Portland Cement Concrete Sidewalks and Curb Ramps
(a)	General Requirements
(b)	Excavation
(c)	Forms
(d)	Placing Concrete
(e)	Finishing
(f)	Joints
(g)	Curing
604.04	Portland Cement Concrete Steps
604.05	Reconstructed Portland Cement Concrete Sidewalk
604.06	Re-Laid Portland Cement Concrete Sidewalk
604.07	HMA Sidewalk
(a)	Excavation and Forms
(b)	Bed Course
(c)	Placing HMA Sidewalk
604.08	Backfilling and Finishing Shoulders and Slopes
604.09	Method of Measurement
604.10	Basis of Payment
605 --	CURBING
605.01	Description
605.02	Materials
605.03	Precast Cement Concrete Curbing
(a)	Excavation
(b)	Installation
(c)	Joints
(d)	Backfilling
605.04	Cast in Place Cement Concrete Curbing
(a)	Excavation
(b)	Forms
(c)	Proportioning and Placing
(d)	Curb Turnouts and Combined Concrete Curb and Gutter Turnouts
(e)	Joints
(f)	Curing
(g)	Backfilling
(h)	Curb Machine
(i)	Integral Curb Walk
605.05	Reflecting Cement Concrete Curbing
605.06	Cement Concrete Center Curbing
605.07	HMA Curbing
(a)	Excavation
(b)	Preparation of Bed
(c)	Mixture
(d)	Placing
(e)	Painting and Sealing
605.08	Resetting Curbing

TABLE OF CONTENTS

Section	Title
	(a) Salvage of Curbing
	(b) Curb Removal
	(c) Excavation
	(d) Resetting
	(e) Backfilling
605.09	Method of Measurement
605.10	Basis of Payment
606 --	Blank
607 --	PAVED SIDE DITCH OR CONCRETE GUTTER
607.01	Description
607.02	Materials
607.03	General Requirements
607.04	Cement Concrete Gutter and Turnout
607.05	Method of Measurement
607.06	Basis of Payment
608 --	SHOULDER DRAINS
608.01	Description
608.02	Materials
608.03	General Requirements
608.04	Method of Measurement
608.05	Basis of Payment
609 --	Blank
610 --	SURFACES FOR APPROACHES
610.01	Description
610.02	Materials
610.03	General Requirements
610.04	Existing Approaches and Crossovers
610.05	Cement Concrete Bridge Approach Pavement
	(a) Machine Method
	(b) Hand Method
610.06	Method of Measurement
610.07	Basis of Payment
611 --	CROSSOVERS, DRIVEWAYS AND MAILBOX INSTALLATIONS
611.01	Description
611.02	Materials
611.03	General Requirements
611.04	Temporary Crossovers
611.05	Mailbox Assembly
611.06	Method of Measurement
611.07	Basis of Payment
612 --	UNDERSEALING
612.01	Description
612.02	Materials
612.03	Shoulders
612.04	Drilled Holes
612.05	Pumping Asphalt
612.06	Method of Measurement
612.07	Basis of Payment
613 --	SALVAGED ROAD MATERIALS
613.01	Description
613.02	Materials

TABLE OF CONTENTS

Section	Title
613.03	Construction Requirements
613.04	Method of Measurement
613.05	Basis of Payment
614 --	CONCRETE HEADER
614.01	Description
614.02	Materials
614.03	Cement Concrete Header
614.04	Reconstructed Cement Concrete Header
614.05	Method of Measurement
614.06	Basis of Payment
615 --	MONUMENTS, MARKERS AND PARKING BARRIERS
615.01	Description
615.02	Materials
615.03	Reinforced Cement Concrete Right-of-Way Markers
615.04	Monuments
615.05	Bench Mark Posts
615.06	Parking Barriers
615.07	Setting Right-of-Way Markers
615.08	Resetting Right-of-Way Markers
615.09	Setting Monuments
615.10	Re-Established Monuments
615.11	Setting Bench Mark Posts and Tablets
615.12	Reset Bench Mark Posts
615.13	Method of Measurement
615.14	Basis of Payment
616 --	RIPRAP AND SLOPEWALL
616.01	Description
616.02	Materials
(a)	Dumped Riprap
(b)	Revetment Riprap
(c)	Hand Laid Riprap
(d)	Grouted Riprap
(e)	Precast Cement Concrete Riprap
(f)	Uniform Riprap
616.03	Placing Dumped Riprap
616.04	Placing Revetment Riprap
616.05	Placing Uniform Riprap
616.06	Placing Hand Laid Riprap
616.07	Placing Grouted Riprap
616.08	Placing Precast Cement Concrete Riprap
616.09	Sloped wall
616.09.1	Undermined Paved Side Ditch
616.10	Installation of Geotextile Under Riprap
616.11	Method of Measurement
616.12	Basis of Payment
617 --	Blank
618 --	Blank
619 --	PAINTING
619.01	Description
619.02	Materials
619.03	General Requirements
619.04	Inspection Access to Bridges

TABLE OF CONTENTS

Section	Title
619.05	Surface Preparation
(a)	Pressure Washing
(b)	Solvent Cleaning
(c)	Near-White Blast Cleaning
(d)	Commercial Blast Cleaning
(e)	Hand Tool Cleaning
(f)	Brush-Off Blast Cleaning
(g)	Special Cleaning Methods
619.06	Pollution Control
619.07	Paint Systems
(a)	Paint System No. 1
(b)	Paint System No. 2
(c)	Paint System No. 3
619.08	Painting
(a)	General Requirements
(b)	Maintaining Traffic
(c)	Prosecution of Work
(d)	Claims
(e)	Responsibility for Damage
(f)	Paint Mixing
(g)	Paint Thinning
(h)	Paint Application
619.09	Shop Painting
619.10	Field Painting New Steel Bridges
619.11	Painting Existing Steel Bridges
619.12	Encapsulation of Existing Steel Bridges
(a)	Rust Penetration Sealer
(b)	Spot Priming
(c)	Topcoating
(d)	Application Limitations
619.13	Quality Assurance Inspection of Blasting and Painting
(a)	Definitions
1.	Lot
2.	Acceptance of One Lot
3.	Rejection of One Lot
4.	Series
5.	Phase
(b)	Testing Procedure
619.14	Environmental Requirements
(a)	Laws to be Observed
(b)	Requirements
1.	Written Training Program
2.	Hazardous Waste Contingency Plan
3.	Marking of Spent Material Containers
4.	Protective Equipment
5.	Health and Safety Plan
(c)	Instructions
619.15	Method of Measurement
619.16	Basis of Payment
620 --	Blank
621 --	SEEDING AND SODDING
621.01	Description
621.02	Materials
621.03	Preparation of Ground Before Seeding

TABLE OF CONTENTS

Section Title

621.04 Preparation of Ground Before Applying Erosion Control Blankets

621.05 Applying Fertilizer, Seed, and Mulch

(a) Fertilizer

(b) Seed

(c) Mulch

1. Method A

2. Method B

3. Method C

4. Method D

5. Method E

(d) Excelsior Blankets

(e) Paper Mat

(f) Straw Mat

(g) Wood Cellulose Fiber Mulch

621.06 Seed Mixtures

(a) Seed Mixture R

(b) Seed Mixture U

(c) Seed Mixture P

(d) Seed Mixture CV

(e) Seed Mixture D

(f) Seed Mixture T

1. Conventional Mix

2. Color Mix

(g) Seed Mixture Grass

1. Type 1

2. Type 2

(h) Seed Mixture Legume

1. Type 1

2. Type 2

621.07 Mulched Seeding

621.08 Preparation of Ground Before Sodding

621.09 Laying Sod

621.10 Watering Sod

621.11 Seasonal Limitations

621.12 Method of Measurement

621.13 Basis of Payment

(a) Warranty Bond

(b) Changed Fertilizer

(c) Mulching

622 -- PLANTING TREES, SHRUBS, AND VINES

622.01 Description

622.02 Materials

622.03 Care and Handling of Plants

(a) Bare Rooted Plants

(b) Balled and Burlapped Plants and Container Grown Plants

622.04 Collected Plants

622.05 Excavation for Plant Holes

622.06 Planting Season

622.07 Pruning

622.08 Planting, Backfilling, and Watering

(a) Plants with Bare Roots

(b) Balled and Burlapped Plants

(c) Seedlings for Wildlife Habitat

622.09 Liquid Fertilizer Application

TABLE OF CONTENTS

Section Title

- 622.10 Mulching
- 622.11 Guying and Staking
- 622.12 Plant Protection
 - (a) Borer Control Coatings
 - (b) Wrapping for Rodent Protection
- 622.13 Retaining Walls and Tree Wells
- 622.14 Tree Root Protection
- 622.15 Pipe Underdrains
- 622.16 Damage to Plants
- 622.17 Grass and Weed Control
- 622.18 Care, Inspection, and Replacement
 - (a) Care
 - (b) Inspection and Replacement
- 622.19 Crown Vetch Plants and Seedlings
- 622.20 "Do Not Mow or Spray" Signs and "Do Not Disturb" Signs
- 622.21 Method of Measurement
- 622.22 Basis of Payment

SECTION 700 -- STRUCTURES

- 701 -- DRIVEN PILING
- 701.01 Description
- 701.02 Materials
- 701.03 Handling of Epoxy Coated Piles
- 701.04 Equipment for Driving Piles
 - (a) Approval of Pile Driving Equipment
 - 1. Wave Equation Analysis Method
 - 2. Alternate Method
 - (b) Pile Hammers
 - 1. Gravity Hammers
 - 2. Steam and Air Hammers
 - 3. Diesel Hammers
 - 4. Pile Driving Aids
 - (c) Pile Driving Appurtenance
 - 1. Hammer Cushion
 - 2. Pile Drive Head
 - 3. Pile Cushion
 - 4. Leads
 - 5. Followers
 - 6. Jets
- 701.05 Test Piles
- 701.06 Driven Pile Capacity
 - (a) Wave Equation Analysis Program, or WEAP
 - (b) Dynamic Formula
 - (c) Dynamic Pile Load Test
 - (d) Static Load Test
 - 1. Load Test Procedure
 - 2. Hydraulic Jacks and Load Gages
 - 3. General Requirements
- 701.07 Piling Length
- 701.08 Required Bearing Capacity
- 701.09 Preparation and Driving
 - (a) Pilot Holes
 - (b) Location and Alignment Tolerance

TABLE OF CONTENTS

Section	Title
	(c) Heaved Piles
	(d) Installation Sequence
	(e) Inspection
	(f) Pouring Concrete
701.10	Unsatisfactory Piles
701.11	Splicing Piles
	(a) Precast Prestressed Concrete Piles
	(b) Steel Piles and Steel Shells for Cast-in-Place Concrete Piles
701.12	Steel H Pile Tips
701.13	Cut-Off Lengths
701.14	Method of Measurement
701.15	Basis of Payment
	(a) Timber Piles Furnished
	(b) Timber Piles Driven
	(c) Epoxy Coated Piles
	(d) Prestressed Concrete Piles
702 --	STRUCTURAL CONCRETE
702.01	Description
702.02	Classes of Concrete
702.03	Materials
702.04	Shipping and Storage
702.05	Proportioning
702.06	Batching
	(a) Portland Cement
	(b) Water
	(c) Aggregates
	(d) Bins and Scales
	(e) Batching
702.07	Mixing
702.08	Mixing at Site of Work
702.09	Ready-Mixed Concrete
	(a) General Requirements
	(b) Mixers and Agitators
	(c) Mixing and Delivery
	(d) Non-Agitating Equipment
702.10	Pumping Concrete
702.11	Cold Weather Concrete
702.12	Consistency
702.13	Forms
	(a) Construction
	(b) Ties
	(c) Walls
	(d) Surface Treatment
	(e) Metal Forms
	1. Removable
	2. Permanent
	a. General
	b. Construction Requirements
	(f) Removal and Re-Use of Forms
	(g) Test Beams
702.14	Falsework and Centering
	(a) Design and Construction
	(b) Removal
702.15	Joints

TABLE OF CONTENTS

Section	Title
	(a) Construction Joints
	(b) Expansion Joints
	(c) Folded Metal Joints
	(d) Sliding Joints
702.16	Drainage Pipes Through Concrete Masonry
702.17	Incased Pipes and Conduits
702.18	Roadway Surface Drainage
702.19	Pouring Bent Caps
702.20	Placing Concrete
	(a) General Requirements
	(b) Chutes and Troughs
	(c) Vibrating
	(d) Depositing Concrete Under Water
	(e) Placing Footing Concrete
	(f) Concrete Foundation Seal
702.21	Finishing Concrete Surfaces
	(a) Class 1 Finish
	(b) Class 2 Finish
	(c) Class 3 Finish
702.22	Curing Concrete
	(a) Protective Covering Curing Methods
	(b) Membrane Forming Curing Compound
	(c) Curing-Sealing Materials
702.23	Waterproofing
702.24	Application of Loads to and Acceptance of New Concrete
702.25	Field Drilled Holes in Concrete
702.26	Artificial Lighting
702.27	Method of Measurement
702.28	Basis of Payment
703 --	REINFORCING STEEL
703.01	Description
703.02	Materials
703.03	Bar List
703.04	Protection of Materials
703.05	Bending
703.06	Placing and Fastening
703.07	Method of Measurement
	(a) Hard Metric Table
	(b) Soft Metric Table
	(c) English Table
703.08	Basis of Payment
704 --	CONCRETE FLOOR SLABS
704.01	Description
704.02	Materials
704.03	Forms
704.04	Placing Reinforcement and Concrete
704.05	Finishing Concrete
704.06	Curing
704.07	Method of Measurement
704.08	Basis of Payment
705 --	SIDEWALKS ON STRUCTURES
705.01	Description
705.02	Materials

TABLE OF CONTENTS

Section	Title
705.03	Construction Requirements
705.04	Method of Measurement
705.05	Basis of Payment
706 --	RAILINGS
706.01	Description
706.02	Materials
706.03	Concrete Railing
706.04	Pipe Railing
706.05	Aluminum and Steel Railings
706.06	Method of Measurement
706.07	Basis of Payment
707 --	PRECAST AND PRESTRESSED CONCRETE STRUCTURAL MEMBERS
707.01	Description
707.02	Materials
707.03	General Requirements
707.04	Steel and Concrete Requirements
(a)	Reinforcing Steel
(b)	Welding Reinforcing Steel
(c)	Concrete
707.05	Forms
707.06	Placing and Finishing Cement Concrete
707.07	Removal of Forms and Curing
707.08	Handling and Shipping
707.09	Placing Structural Members
707.10	Method of Measurement
707.11	Basis of Payment
708 --	PNEUMATICALLY PLACED MORTAR
708.01	Description
708.02	Materials
708.03	Preparing Surface
708.04	Reinforcement
708.05	Proportioning and Mixing
708.06	Placing Mortar
708.07	Finishing
708.08	Method of Measurement
708.09	Basis of Payment
709 --	PORTLAND CEMENT CONCRETE SEALERS
709.01	Description
709.02	Materials
709.03	Surface Preparation
709.04	Environmental Requirements
(a)	General Requirements
(b)	Epoxy Penetrating Sealers
(c)	Other Portland Cement Concrete Sealers
(d)	Low Temperature Epoxy Penetrating Sealer
709.05	Sealer Application
(a)	General Requirements
(b)	Epoxy Penetrating Sealer
(c)	Other Portland Cement Concrete Sealers
(d)	Clear Sealers
(e)	Alternate To Concrete Sealers
709.06	Safety Precautions
709.07	Method of Measurement

TABLE OF CONTENTS

Section	Title
709.08	Basis of Payment
710 --	REPOINTING MASONRY IN STRUCTURES
710.01	Description
710.02	Materials
710.03	Repointing Concrete Masonry
710.04	Repointing Rubble Masonry
710.05	Repointing Dressed Stone and Brick Masonry
710.06	Method of Measurement
710.07	Basis of Payment
711 --	STEEL STRUCTURES
711.01	Description
711.02	Materials
711.03	General Requirements
711.04	Certification of Fabricators
711.05	Shop Drawings
711.06	Storage of Materials
711.07	Mill Orders and Shipping Statements
711.08	Mill Test Reports
711.09	Notice of Beginning Work
711.10	Facilities for Inspection
711.11	Straightening Material
711.12	Finish
711.13	Flame Cutting
711.14	Edge Planing
711.15	Abutting Joints
711.16	End Connection Angles
711.17	Blank
711.18	Blank
711.19	Bent Plates
711.20	Fit of Stiffeners
711.21	Bolt Holes
	(a) High Tensile Strength Bolts, and Unfinished Bolts
	(b) Ribbed Bolts, Turned Bolts, or other Approved Bearing-Type Bolts
711.22	Punched Holes
711.23	Reamed or Drilled Holes
711.24	Subpunching and Reaming of Field Connections
711.25	Accuracy of Punched or Subdrilled Holes
711.26	Accuracy of Reamed Holes and Holes Drilled Full Size
711.27	Fitting for Bolting
711.28	Filler Plates
711.29	Toothed Expansion Plates
711.30	Blank
711.31	Blank
711.32	Welds
	(a) AWS Requirements
	(b) Edge Blocks
711.33	Stud Shear Connectors
711.34	Annealing and Stress Relieving
711.35	Eyebars
711.36	Facing of Bearing Surfaces
711.37	Pins and Rollers
711.38	Boring Pin Holes
711.39	Pin Clearances
711.40	Threads for Bolts and Pins

TABLE OF CONTENTS

Section	Title
711.41	Pilot and Driving Nuts
711.42	Finishing Cast Steel
711.43	Finished Members
711.44	Shop Assembling
(a)	Full Truss or Girder Assembly
(b)	Progressive Beam or Girder Assembly
(c)	Full Chord Assembly
(d)	Progressive Chord Assembly
(e)	Special Complete Structure Assembly
711.45	Drifting of Holes
711.46	Match Marking
711.47	Shop Cleaning and Painting
711.48	Furnishing Bolts
711.49	Weighing of Members
711.50	Full Size Tests
711.51	Acceptance
711.52	Shipping
711.53	General Requirements
711.54	Delivery of Materials
711.55	Handling and Storing
711.56	Falsework
711.57	Bearings and Anchorages
711.58	Field Straightening Material
711.59	Field Assembly of Steel
711.60	Misfits
711.61	Pin Connections
711.62	Blank
711.62.1	Diaphragm Connections
711.63	Bolted Connections Using High Strength Bolts
(a)	General
(b)	Bolts, Nuts, and Washers
(c)	Bolted Parts
(d)	Installation
1.	Bolt Tension
2.	Washers
3.	Calibrated Wrench Tightening
4.	Turn-of-Nut Tightening
(e)	Inspection
711.64	Bolted Connections Using Other Than High Strength Bolts
711.65	Final Clean-Up
711.66	Structural Steel Cutting, Rivet and Bolt Removal, and Drilled Bolt Holes in Repair Projects
711.67	Jacking and Supporting Beams
711.68	Painting
711.69	Method of Measurement
711.70	Basis of Payment
(a)	Lump Sum Basis
(b)	Unit Weight Basis
712 --	TIMBER STRUCTURES
712.01	Description
712.02	Materials
712.03	General Requirements
712.04	Caps
712.05	Stringers
712.06	Bents

TABLE OF CONTENTS

Section	Title
712.07	Wheel Guards and Railings
712.08	Painting
712.09	Single-Ply Plank Floors
712.10	Two-Ply Plank Floors
712.11	Method of Measurement
712.12	Basis of Payment
713 --	TEMPORARY BRIDGES AND APPROACHES
713.01	Description
713.02	Materials
713.03	General Requirements
713.04	Temporary Bridge
713.05	Temporary Approaches
713.06	Maintenance
713.07	Removal
713.08	Method of Measurement
713.09	Basis of Payment
714 --	CONCRETE CULVERTS AND RETAINING WALLS
714.01	Description
714.02	Materials
714.03	General Requirements
714.04	Extension of Existing Culverts
	(a) Precast Concrete Box Sections Extension
	(b) Cast-In-Place Concrete Culvert Extension
714.05	Sealing Existing Culverts
714.06	Method of Measurement
714.07	Basis of Payment
715 --	PIPE CULVERTS, AND STORM AND SANITARY SEWERS
715.01	Description
715.02	Materials
	(a) Type 1 Pipe
	(b) Type 2 Pipe
	(c) Type 3 Pipe
	(d) Type 4 Pipe
	(e) Type 5 Pipe
	(f) Slotted Drain Pipe
	(g) Slotted Vane Drain Pipe
	(h) End Bent Drain Pipe
	(i) Underdrain Outlet Pipe
715.02.1	General Requirements
715.03	Excavation
715.04	Laying Pipe
715.05	Joining Pipe
715.06	Tee and Stub-Tee Connections
715.07	Blank
715.08	Backfilling
715.09	Pipe End Sections and Anchors
715.10	Re-Laid Pipe
715.11	Method of Measurement
715.12	Basis of Payment
716 --	JACKED PIPE
716.01	Description
716.02	Materials
716.03	General Requirements

TABLE OF CONTENTS

Section	Title
	(a) Jacking
	(b) Boring
716.04	Jacking Steel Pipe
716.05	Jacking Concrete Pipe
716.06	Method of Measurement
716.07	Basis of Payment
717 --	STRUCTURAL PLATE PIPE, PIPE-ARCHES, AND ARCHES
717.01	Description
717.02	Materials
717.03	General Requirements
717.04	Backfill
717.05	Re-Laid Pipe and Pipe-Arch
717.06	Blank
717.07	Concrete Paved Inverts
717.08	Method of Measurement
717.09	Basis of Payment
718 --	UNDERDRAINS
718.01	Description
718.02	Materials
718.03	Pipe Installation
718.04	Geotextile
718.05	Underdrain Outlets
718.06	Underdrain Outlet Protectors
718.07	Method of Measurement
718.08	Basis of Payment
719 --	TILE DRAINS
719.01	Description
719.02	Materials
719.03	Trench Excavation
719.04	Laying Tile
719.05	Backfilling
719.06	Blank
719.07	Method of Measurement
719.08	Basis of Payment
720 --	MANHOLES, INLETS, AND CATCH BASINS
720.01	Description
720.02	Materials
720.03	General Requirements
720.04	Grade Adjustment of Existing Structures
720.05	Method of Measurement
720.06	Basis of Payment
721 --	AUTOMATIC DRAINAGE GATES
721.01	Description
721.02	Materials
721.03	Construction Requirements
721.04	Method of Measurement
721.05	Basis of Payment
722 --	LATEX MODIFIED CONCRETE BRIDGE DECK OVERLAYS
722.01	Description
722.02	Materials
722.03	Storage and Handling of Materials
722.04	Proportioning

TABLE OF CONTENTS

Section	Title
722.05	Preparation of the Bridge Floor
(a)	Concrete Removal
1.	Deck Surface
2.	Bridge Floor
(b)	Cleaning
722.06	Patching of the Bridge Floor
(a)	Full Depth Patching
1.	Patching with Bridge Deck Patching Concrete
2.	Patching with Latex Modified Concrete
(b)	Partial Depth Patching
1.	Patching with Bridge Deck Patching Concrete
2.	Patching with Latex Modified Concrete
722.06.1	Overlay Dam
722.07	Mixing
722.08	Placing and Finishing
722.09	Texturing
722.10	Curing
722.11	Calibration of Continuous Mixers
(a)	Frequency
(b)	Equipment
(c)	Pre-calibration
(d)	Calibration
1.	Cement Meter
2.	Water Flow Meter
3.	Aggregate Bin Gates
4.	Latex Throttling Valve
5.	Admixture Dispensers
722.12	Patching an Existing Bridge Deck Overlay
(a)	Materials
(b)	Storage and Handling of Materials
(c)	Proportioning
(d)	Preparation of the Bridge Floor
(e)	Patching
(f)	Mixing
(g)	Placing and Finishing
(h)	Texturing
(i)	Curing
(j)	Calibration of Continuous Mixers
722.13	Method of Measurement
722.14	Basis of Payment
723 --	DENSE CONCRETE BRIDGE DECK OVERLAYS
723.01	Description
723.02	Materials
723.03	Storage and Handling of Materials
723.04	Proportioning
723.05	Preparation of the Bridge Floor
(a)	Concrete Removal
1.	Deck Surface
2.	Bridge Floor
(b)	Cleaning
723.06	Patching of the Bridge Floor
(a)	Full Depth Patching
(b)	Partial Depth Patching
1.	Patching with Bridge Deck Patching Concrete

TABLE OF CONTENTS

Section	Title
---------	-------

	2. Patching with Dense Concrete
723.07	Mixing
723.08	Placing and Finishing
723.09	Texturing
723.10	Curing
723.11	Calibration of Continuous Mixers
723.12	Patching an Existing Bridge Deck Overlay
	(a) Materials
	(b) Storage and Handling of Materials
	(c) Proportioning
	(d) Preparation of the Bridge Floor
	(e) Patching
	(f) Mixing
	(g) Placing and Finishing
	(h) Texturing
	(i) Curing
	(j) Calibration of Continuous Mixers
723.13	Method of Measurement
723.14	Basis of Payment
724 --	STRUCTURAL EXPANSION JOINTS
724.01	Description
	(a) Structural Expansion Joint
	(b) Replacement of Existing Structural Expansion Joint
	(c) Replacement of Existing Structural Expansion Joint Seal
724.02	Materials
	(a) Expansion Joint SS
	(b) Expansion Joint M
724.03	General Requirements
	(a) Expansion Joint SS
	(b) Expansion Joint BS
	(c) Expansion Joint M
	(d) Replacement of Existing Structural Expansion Joint
	(e) Replacement of Existing Structural Expansion Joint Seal
724.04	Method of Measurement
724.05	Basis of Payment
725 --	Blank
726 --	Blank
727 --	Blank
728 --	Blank
729 --	Blank
730 --	GRATED BOX END SECTIONS
730.01	Description
730.02	Materials
730.03	Construction Requirements
730.04	Method of Measurement
730.05	Basis of Payment

SECTION 800 -- TRAFFIC CONTROL DEVICES AND LIGHTING

801 -- TRAFFIC CONTROLS FOR CONSTRUCTION AND MAINTENANCE OPERATIONS

TABLE OF CONTENTS

Section	Title
---------	-------

801.01	Description
801.02	Materials
801.02.1	General Requirements
801.03	Construction Signs
801.04	Temporary Worksite Speed Limit Sign Assemblies
801.05	Detour Route Marker Assembly
801.05.1	Road Closure Sign Assembly
801.06	Vehicle Warning Lights
801.07	Barricades
(a)	Type III-A Barricade
(b)	Permanent Type III-A Barricade
(c)	Type III-B Barricade
801.08	Cones and Tubular Markers
801.09	Temporary HMA Divider
801.10	Drums
801.11	Temporary Illumination
801.12	Construction Warning Lights
(a)	Type A
(b)	Type B
(c)	Type C
801.13	Flashing Arrow Sign
801.14	Temporary Pavement Marking
(a)	Types of Temporary Pavement Markings
1.	Painted Lines
2.	Temporary Pavement Marking Tape
a.	Type I
b.	Type II
3.	Temporary Raised Pavement Marker
4.	Buzz Strips
(b)	Marking Method On Two-Lane Pavements
(c)	Marking Method On Multi-Lane Pavements
1.	Lane Line Markings
a.	Base Course
b.	Intermediate Course
c.	Surface
2.	Gore Area Markings
a.	Base Course
b.	Intermediate Course
c.	Surface
3.	Acceleration, Deceleration, and Ramp Area Markings
a.	Base Course
b.	Intermediate Course
c.	Surface
4.	Narrow Bridge Markings
a.	Base Course
b.	Intermediate Course
c.	Surface
5.	Time of Installation
801.15	Traffic Control for Temporary Traffic Stoppage
(a)	On Multi-Lane Divided Highways
(b)	On Non-Divided Highways
801.16	Maintenance of Traffic for Snowplowable Marker or Reflector Installation
801.17	Method of Measurement
801.18	Basis of Payment

TABLE OF CONTENTS

Section	Title
802 --	GROUND MOUNTED SIGNS
802.01	Description
802.02	Materials
802.03	Location of Signs
802.04	Excavation
802.05	Installing Posts and Signs
802.06	Removal or Relocation of Signs or Support Assemblies
802.07	Remove and Reset Roadway and Bridge Reference Signs
802.08	Shop Drawings of Signs and Sign Structures
802.09	Final Clean-Up
802.10	Method of Measurement
802.11	Basis of Payment
803 --	OVERHEAD SIGN STRUCTURES
803.01	Description
803.02	Materials
803.03	Shop Drawings
803.04	Excavation
803.05	Placing Concrete
803.06	Erection
	(a) Under Traffic
	(b) Trusses
	(c) Monotube
	(d) Cantilever
	(e) Bridge Brackets
803.07	Welding Aluminum Alloys for Highway Structures
	(a) Base Metals
	(b) Welding Processes
	(c) Filler Metal
	(d) Shielding Gases
	(e) Preparation of Materials
	(f) Welding Procedure
	(g) Weld Quality
	(h) Inspection
	(i) Corrections
	(j) Qualification of Procedures, Welders, and Welding Operators
803.08	Removal of Overhead Signs and Sign Structures
803.09	Final Clean-Up
803.10	Method of Measurement
803.11	Basis of Payment
804 --	DELINEATORS
804.01	Description
804.02	Materials
804.03	Delineators and Barrier Delineators
804.04	Posts
804.05	Flexible Delineator Posts
804.06	Method of Measurement
804.07	Basis of Payment
805 --	TRAFFIC SIGNALS
805.01	Description
805.02	Materials
805.03	General Requirements
805.04	Pole Installation
805.05	Placing Signal Heads

TABLE OF CONTENTS

Section	Title
805.06	Grounding
805.07	Wire and Cable Installations
805.08	Controller Cabinet, Signal Service, and Detector Housing Installation
805.09	Loop Wire Detector Installation
	(a) Megohm Test Before Splice is Made at Detector Housing for Loop Wire
	(b) Megohm Test Before Splice is Made at Detector Housing for Lead-in Cable
	(c) Megohm Test After Splice is Completed at Cabinet
	(d) Vehicle Simulator Test
	(e) Acceptance Criteria
805.10	Magnetometer and Microloop Detectors
805.11	Steel Conduit
805.12	PVC Conduit
805.13	Foundations
805.14	Final Clean-Up
805.15	Method of Measurement
805.16	Basis of Payment
806 --	TEMPORARY TRAFFIC SIGNALS
806.01	Description
806.02	Materials
806.03	General Requirements
806.04	Pole Installation
806.05	Signal Heads
806.06	Grounding
806.07	Wire and Cable Installations
806.08	Controller
806.09	Controller Cabinet, Signal Service, and Detector Housing Installation
806.10	Loop Detector Installation
806.11	Conduit
806.12	Final Clean-Up
806.13	Method of Measurement
806.14	Basis of Payment
807 --	HIGHWAY ILLUMINATION
807.01	Description
807.02	Maintenance of Highway Illumination
807.03	Materials
807.04	Excavation
	(a) Trench Excavation
	(b) Foundation Excavation
	(c) Landscape Replacement
807.05	Backfilling
807.06	Placing Conduit
807.07	Connections in Base of Lighting Standards
807.08	Placing Wire and Cable
	(a) Underground Through Cable-duct
	1. Cable-duct
	2. Cable Markers
	(b) Underground Through Conduit
	1. Cable-duct
	2. Cable Markers
	(c) In Conduit Risers
	(d) Through Conduit in Bridge Copping
	(e) Aerial Cable
807.09	Lighting Handholes
807.10	Concrete Foundations For Lighting Standards

TABLE OF CONTENTS

Section	Title
	(a) Cast-in-Place Foundations
	(b) Precast Foundations
	(c) Grading of Foundations
807.11	Placing Lighting Standards
	(a) Lighting Standards Under 24 m (80 ft) in Height
	(b) High Mast Lighting Standards of 24 m (80 ft) Height and Over
807.12	Grounding
807.13	Luminaire Installation
	(a) Roadway Luminaires
	(b) Sign Luminaires
	(c) Underpass Luminaires
	(d) High Mast Luminaires
807.14	Sign, Underpass, Roadway, and High Mast Lighting Location Identification
807.15	Service Point Power Entry
	(a) Types of Service Points
	1. Type I Service Point
	2. Type II Service Point
	(b) Sign and Underpass Circuits
	(c) Multiple Relay Switches
807.16	Testing of Highway Lighting System
	(a) Testing Lighting Circuitry
	(b) Testing and Inspecting Luminaires
807.17	Pay Item and Installation Summary Sheets
807.18	Method of Measurement
	(a) From the Face of the Concrete Foundation to the Center of the Handhole or Face of the Next Concrete Foundation
	(b) From Lighting Standard Bases or Handholes to Switch Boxes at Underpasses
	(c) From End to End of the Conduit when the Cable is in Conduit under a Roadway Surface or Shoulder
807.19	Basis of Payment
808 --	PAVEMENT TRAFFIC MARKINGS
808.01	Description
808.02	Materials
808.03	General Requirements
808.04	Longitudinal Markings
	(a) Center Lines
	(b) Lane Lines
	(c) Edge Lines
	(d) Barrier Lines
808.05	Transverse Markings
808.05.1	Curb Markings
808.06	Pavement Marking Material Application and Equipment
	(a) Traffic Paint
	1. Application
	2. Equipment
	(b) Durable Pavement Marking Material
	1. Thermoplastic
	a. Application
	b. Equipment
	2. Preformed Plastic
	a. Application
	b. Equipment
	3. Epoxy
	a. Application
	b. Equipment
808.07	Marking Protection and Maintenance of Traffic

TABLE OF CONTENTS

Section Title

- (a) Vehicle Signs
- (b) Vehicle Warning Lights
- (c) Cones
- (d) Front Escort Vehicles
- (e) Marking Application Vehicles
- (f) Rear Escort Vehicles
- 808.08 Warranty for Durable Pavement Marking Material
- 808.09 Removal of Pavement Markings
- 808.10 Snowplowable Raised Pavement Markers
 - (a) Surface Preparation
 - (b) Location
 - (c) Reflector Color
 - (d) Installation
 - (e) Removal of Markers
 - (f) Replacement of Prismatic Reflectors
- 808.11 Method of Measurement
- 808.12 Basis of Payment

SECTION 900 -- MATERIALS DETAILS

- 901 -- HYDRAULIC CEMENT AND POZZOLANS
- 901.01 Hydraulic Cement
 - (a) General
 - (b) Portland Cement
 - 1. Requirements
 - 2. Acceptance Criteria
 - a. General Requirements
 - b. Requirements for Domestic Source Qualification
 - c. Requirements for Foreign Source Qualification
 - d. Certification
 - (c) Masonry Cement
- 901.02 Fly Ash Used as a Pozzolan
 - (a) General
 - (b) Acceptance Criteria
 - 1. Requirements
 - 2. Test and Calibration Procedure
 - 3. Documentation
- 901.03 Ground Granulated Blast Furnace Slag Used as a Pozzolan
 - (a) General
 - (b) Acceptance Criteria
 - 1. Requirements
 - 2. Test and Calibration Procedure
 - 3. Documentation
- 901.04 Microsilica Used As a Pozzolan Mineral Admixture
 - (a) General
 - (b) Acceptance Criteria
 - 1. Requirements
 - 2. Frequency of Testing
 - 3. Test and Calibration Procedure
 - 4. Documentation
- 902 -- ASPHALT MATERIALS
- 902.01 Asphalt
 - (a) Performance Graded Asphalt Binders

TABLE OF CONTENTS

Section	Title
---------	-------

	(b) Asphalt Emulsions
	(c) Cutback Asphalts
	1. Medium Curing Asphalts With and Without Additives
	2. Slow Curing Asphalts With and Without Additives
	(d) Utility Asphalt
	(e) Asphalt for Coating Corrugated Metal Pipe
902.02	Sampling and Testing Asphalt Materials
902.03	Application Temperatures
903 --	CLASSIFICATION OF SOILS
903.01	Definitions
903.02	Soils Having 0 to 19 Percent Retained on 2.00 mm (No. 10) Sieve
903.03	Soils Having 20 Percent or More Retained on 2.00 mm (No. 10) Sieve and More Than 20 Percent Passing 75 μ m (No. 200) Sieve
903.04	Soils Having 20 Percent or More Retained on 2.00 mm (No. 10) Sieve and Less Than 20 Percent Passing 75 μ m (No. 200) Sieve
903.05	Organic Soils
903.06	Marly Soils
904 --	AGGREGATES
904.01	Fine Aggregates
	(a) For Portland Cement Concrete
	(b) For HMA Mixtures
	(c) For Pneumatic Placement
	(d) For Mortar
	(e) Mineral Filler
	(f) Snow and Ice Abrasives
	(g) Sizes of Fine Aggregates
	(h) Sampling and Testing
904.02	Coarse Aggregates
	(a) General Requirements
	(b) Classification of Aggregates
	(c) Coarse Aggregate Angularity
	(d) Surface Aggregate Requirements
	(e) Sizes of Coarse Aggregates
	(f) Sampling and Testing
904.03	Exceptions to AASHTO Standard Methods
	(a) Exceptions to AASHTO T 2
	(b) Exceptions to AASHTO T 11, T 27, and T 37
	(c) Exceptions to AASHTO T 27 for Coarse Aggregates
	(d) Blank
	(e) Exceptions to AASHTO T 103 and T 104
	(f) Exceptions to AASHTO T 85
905 --	MASONRY UNITS
905.01	Clay or Shale Brick
	(a) Sewer Brick
	(b) Manhole Brick
	(c) Building Brick
905.02	Concrete Brick
905.03	Concrete Masonry Blocks
906 --	JOINT MATERIALS
906.01	Joint Fillers
906.02	Joint Sealing Materials

TABLE OF CONTENTS

Section	Title
(a)	Joint Sealers
1.	Silicone Joint Sealants
a.	Physical Requirements
b.	Field Evaluation
c.	Specific Requirements for Installation of Silicone Joint Sealant
d.	Certification
2.	Hot Poured Joint Sealant
a.	General Requirements
b.	Packaging and Marking
c.	Requirements for Installation
d.	Sampling and Testing
3.	Preformed Elastomeric Joint Seals
(b)	Backer Rod
1.	Requirements
2.	Certification
906.03	Joint Mortar
906.04	Rubber Type Gaskets
906.05	Bituminous Mastic Pipe Joint Sealer
(a)	General Requirements
(b)	Detail Requirements
(c)	Certification
906.06	Bridge Expansion Joints
(a)	Type SS
(b)	Type BS2, BS6, BS8, BS9, BS11, and 1-A
(c)	Type M
907 --	CONCRETE, CLAY, AND PLASTIC DRAINAGE COMPONENTS
907.01	Non-Reinforced Concrete Pipe
907.02	Reinforced Concrete Pipe
907.03	Reinforced Concrete Horizontal Elliptical Pipe
907.04	Precast Concrete Manholes, Inlets, and Catch Basins
907.05	Precast Reinforced Concrete Box Sections
907.06	Blank
907.07	Blank
907.08	Clay Pipe
907.09	Perforated Clay Pipe
907.10	Blank
907.11	Drain Tile
907.12	Blank
907.13	Blank
907.14	Blank
907.15	Blank
907.16	Plastic Pipe Manufacturer Requirements
907.17	Corrugated Polyethylene Drainage Tubing
907.18	Perforated Polyvinyl Chloride Semicircular Pipe
907.19	Corrugated Polyethylene Pipe
907.20	Ribbed Polyethylene Pipe
907.21	Smooth Wall Polyethylene Pipe
907.22	Profile Wall Polyvinyl Chloride Pipe
907.23	Smooth Wall Polyvinyl Chloride Pipe
907.24	Smooth Wall Pipe for Outlets
(a)	Type PSM Polyvinyl Chloride Pipe and Fittings
(b)	Schedule 40 Polyvinyl Chloride Pipe
907.25	Solvent Cements for Polyvinyl Chloride Pipe and Pipe Fittings
907.26	Elastomeric Seals

TABLE OF CONTENTS

Section	Title
908 --	METAL PIPE
908.01	Blank
908.02	Corrugated Steel Pipe and Pipe-Arches
908.03	Blank
908.04	Corrugated Aluminum Alloy Pipe and Pipe-Arches
908.05	Blank
908.06	Metal End Sections
908.07	Fiber Bonded Fully Bituminous Coated Corrugated Steel Culvert Pipe and Pipe-Arches
908.08	Polymer Precoated Galvanized Corrugated Steel Culvert Pipe and Pipe-Arches
908.09	Structural Plate Pipe, Pipe-Arches, and Arches
	(a) Steel
	(b) Aluminum Alloy
908.10	Cast Iron Soil Pipe
908.11	Steel Pipe
908.12	Straps, Hook Bolts and Nuts Used in Anchors
909 --	PAINT AND LIQUID EPOXY
909.01	General Requirements
909.02	For Metal
	(a) Zinc Primers
	1. Two Component and Multi-Component Inorganic Zinc Silicate Primer
	2. Single Package Inorganic Zinc Silicate Primer
	3. Organic Zinc Primer
	4. Approval of Formulation
	5. Reapproval of Formulation
	(b) Vinyl Finish Paint
	1. Vehicle Component
	2. Pigment Component
	3. Mixed Paint Properties
	4. Color
	5. Storage Life
	6. Application
	(c) Waterborne Finish Paint
	1. Vehicle Component
	2. Pigment Component
	3. Mixed Paint Properties
	4. Approval of Formulation
909.03	Encapsulation Bridge Paint System
909.04	For Wood or Metal
	(a) Primer for Field Paint
	(b) White Field Paint, Finish Coat
909.05	White and Yellow Traffic Paint
	(a) Standard Traffic Paint
	1. General Requirements
	2. Specific Requirements
	(b) Fast Dry Traffic Paint
	1. General Requirements
	2. Specific Requirements
	(c) White and Yellow Waterborne Traffic Paint
	1. Composition Requirements
	2. Specific Requirements
	3. Formulation Approval
	4. Formulation Reapproval
909.06	Blank
909.07	Miscellaneous Paints and Ingredients

TABLE OF CONTENTS

Section	Title
	(a) Stencil Paint
	(b) Zinc Chromate Paint
909.08	Blank
909.09	Epoxy Penetrating Sealers
	(a) Polysulfide Type
	(b) Unmodified Type
	(c) Specific Requirements
	(d) Low Temperature Epoxy Penetrating Sealer
	(e) Packaging and Marking
	(f) Approval of Formulation
909.10	Proprietary Portland Cement Concrete Sealers
909.11	Epoxy-Resin-Base System for Bonding Plastic Concrete to Hardened Concrete
910 --	METAL MATERIALS
910.01	Reinforcing Steel and Dowel Bars
	(a) General
	(b) Specific Requirements
	1. Billet Steel Bars
	2. Rail Steel Bars
	3. Axle Steel Bars
	4. Steel Bar Mats for Continuously Reinforced Concrete Pavement
	5. Welded Steel Wire Fabric for Concrete Reinforcement
	6. Welded Deformed Steel Wire Fabric for Concrete Reinforcement
	7. Uncoated 7 Wire Strand for Prestressed Concrete
	8. Steel Spiral Reinforcement
	9. Epoxy Coated Reinforcing Steel
	10. Dowel Bars
	(c) Inspection, Sampling, and Testing
910.02	Structural Steel
	(a) Structural Steel
	(b) High Strength Structural Steel
	(c) Charpy V-Notch Toughness Tests
	(d) Mill Test Reports
	(e) High Strength Bolts, Nuts, and Washers
	1. General Use
	2. Assembly of Structural Steel in Bridges
	a. Bolts
	b. Nuts
	c. Tests
	(1) Rotational Capacity
	(2) Proof Loads
	(3) Wedge Tension Test
	d. Certification
	(f) Bolts other than High Strength Bolts
	1. General
	2. Unfinished Bolts
	3. Turned Bolts
	4. Ribbed Bolts
910.03	Permanent Metal Forms
910.04	Steel Forgings and Steel Shafting
	(a) Carbon Steel Forgings
	(b) Cold Finished Carbon Steel Shafting
	(c) Alloy Steel Forgings
	(d) Certification
910.05	Castings

TABLE OF CONTENTS

Section	Title
(a)	Steel Castings
1.	Steel Castings for Highway Bridges
2.	Chromium Alloy Steel Castings
(b)	Iron Castings
(c)	Ductile Iron Castings
(d)	Malleable Castings
(e)	Carbon Steel Castings
910.06	Bronze and Copper Alloy
(a)	Bronze Castings
(b)	Copper Alloy Plates
910.07	Steel Drain Pipe
910.08	Miscellaneous
(a)	Sheet Lead
(b)	Sheet Zinc
910.09	Guardrail
(a)	Steel Beam Rail
(b)	Aluminum Rail
910.10	Guardrail Posts
(a)	Steel Guardrail Posts
	Aluminum Guardrail Posts
(c)	Wood Guardrail Posts
910.11	Guardrail Accessories, Fittings, and Hardware
(a)	For Steel Beam Guardrail
(b)	For Aluminum Guardrail
(c)	For Steel Tube Guardrail
910.12	Samples and Certification of Guardrail, Posts, Accessories, Fittings, and Hardware
(a)	Control Procedure for Furnishing Steel Beam Guardrail and Accessories
(b)	Aluminum Guardrail
910.13	Steel Fence Posts
(a)	Tubular Steel Fence Posts
1.	Group 1
2.	Group 2
(b)	Fence Fastenings
910.14	Sign Posts
(a)	Steel, Flanged, Channel Posts
1.	General Requirements
2.	Deflection Test Requirements
3.	Type of Posts
(b)	Wide Flange Posts
(c)	Structural Steel Posts
(d)	Structural Aluminum Posts
(e)	Square Steel Posts
1.	Steel
2.	Fabrication
3.	Protective coating
910.15	Delineator Posts
910.16	Copper Flashing
910.17	Bronze or Copper Alloy Plates
910.18	Fence, Fittings, and Gates
(a)	Farm Field or Woven Wire Fence
(b)	Steel Fabric Chain Link Fence
1.	Tension Wire
2.	Stretcher Bars, Truss Rods, and Turnbuckles
3.	Braces
4.	Barbed Wire

TABLE OF CONTENTS

Section	Title
	(c) Aluminum Fabric Chain Link Fence
	(d) Gates
	1. Steel Gates
	2. Aluminum Gates
	(e) Control Procedures for Furnishing Fence and Accessories
	1. General Requirements
	2. Suppliers of Pretested Approved Stockpiled Material
	3. Suppliers Not Furnishing Pretested Approved Stockpiling Material
910.19	Overhead Sign Structures
	(a) Aluminum Overhead Sign Structures, Box Truss and Bridge Attached
	(b) Steel Overhead Sign Structures, Box Truss, Cantilever, Monotube, and Bridge Attached
910.20	Blank
910.21	Steel Sheet Piling
911 --	WOOD MATERIALS
911.01	Untreated Lumber
	(a) General
	1. Boards
	2. Dimension Lumber
	3. Structural Lumber
	4. Timbers
	5. Timbers, Round
	6. Yard Lumber
	7. Surfaced or Dressed Lumber
	8. Rough Lumber
	(b) Species and Grade
	(c) Inspection
	(d) Tolerances
	(e) Untreated Piling
911.02	Treated Lumber
	(a) General
	(b) Bridge Lumber
	(c) Piling
	(d) Guardrail Posts, Braces, and Battens
	(e) Sign Posts
	(f) Sawed Timber Posts and Blocks for Thrie-Beam and W-Beam Guardrail
	1. Species and Grades
	2. Department Grade GRP
	a. Splits
	b. Checks
	c. Shakes
	d. Stains
	e. Slope of Grain
	f. Wane
	g. Knots
	3. Department Grade GRB
	a. Splits
	b. Checks
	c. Shakes
	d. Stains
	e. Wane
	f. Knots
	4. General Requirements
	a. Decay
	b. Unsound Wood

TABLE OF CONTENTS

Section	Title
---------	-------

- | | |
|-----|---------------------------------------|
| | c. Crook or Bow |
| | d. Dimensional Tolerances |
| 5. | Pressure Treating Posts and Blocks |
| a. | Machining |
| b. | Incising |
| c. | Inspection Before Treatment |
| d. | Test for Moisture Content |
| e. | Preservative Treatment |
| f. | Material for Preservative Treatments |
| g. | Treatment Methods |
| h. | Sorting and Spacing |
| i. | Conditioning |
| j. | Treatment |
| k. | Inspection During Treatment |
| l. | Retentions |
| m. | Penetration |
| n. | Inspection After Treatment |
| o. | Branding |
| p. | Conformance |
| q. | Records |
| r. | Independent Inspections |
| 6. | Field Treatment of Posts and Blocks |
| 7. | Rejection for Degrade After Treatment |
| (g) | Preservatives |
| 1. | Waterborne Preservatives |

912 -- CONCRETE CURING MATERIALS AND ADMIXTURES

912.01 Curing Materials

- (a) Burlap Cloth made from Jute or Kenaf
- (b) Waterproof Paper Blankets
- (c) White Polyethylene Sheeting, Film
- (d) White Burlap Polyethylene Sheet
- (e) Liquid Membrane Forming Compounds

912.02 Curing-Sealing Materials

912.03 Admixtures for Use in Concrete

- (a) Air Entraining Admixtures
- (b) Chemical Admixtures for Concrete
 - 1. Type A
 - 2. Type B
 - 3. Type C
 - 4. Type D
 - 5. Type E
 - 6. Type F
 - 7. Type G
 - 8. High Range Water Reducing and High Range Water Reducing and Retarding Admixture Systems
- (c) Certification
- (d) Approved Admixtures
- (e) Performance of Admixtures

912.04 Latex Modifiers

912.05 Mineral Admixtures

913 -- MISCELLANEOUS

913.01 Water

913.02 Calcium Chloride

913.03 Sodium Chloride

913.04 Hydrated Lime

TABLE OF CONTENTS

Section	Title
913.05	Precast Concrete Curbing
913.06	Precast Concrete Units Not Otherwise Covered
913.07	Flexible Delineator Posts
913.08	Delineators
(a)	Acrylic Plastic Delineators
(b)	Reflective Sheeting Delineators
(c)	Barrier Delineators
913.09	Glass Beads
913.10	Traffic Signs
(a)	Sheet Signs
(b)	Panel Signs
(c)	Flexible Roll-Up Prismatic Reflective Sign
1.	Reflectivity
2.	Color
3.	Sheeting
4.	Durability
5.	Impact Resistance
6.	Sign Face Backing Fabric
7.	Cross Brace Assembly and Attaching Fasteners
8.	General Characteristics and Packaging
9.	Basis of Use
(d)	Reflective Sheeting
1.	General
a.	Reflectivity
b.	Color
c.	Adhesive
d.	Sheeting
e.	Durability
f.	Impact Resistance
g.	General Characteristics and Packaging
2.	Enclosed Lens, Engineer Grade, and Super Engineer Grade, Reflective Sheeting
a.	Reflectivity
b.	Color
c.	Adhesive
d.	Sheeting
e.	Durability
f.	Impact Resistance
g.	General Characteristics and Packaging
3.	Encapsulated Lens, High Intensity, Reflective Sheeting
a.	Reflectivity
b.	Color
c.	Adhesive
d.	Sheeting
e.	Durability
f.	Impact Resistance
g.	General Characteristics and Packaging
4.	Flexible Encapsulated Lens Reflective Sheeting, High Intensity
a.	Reflectivity
b.	Color
c.	Adhesive
d.	Sheeting
e.	Durability
f.	Impact Resistance
g.	General Characteristics and Packaging
5.	Prismatic Lens, High Intensity, Reflective Sheeting

TABLE OF CONTENTS

Section	Title
	a. Reflectivity
	b. Color
	c. Adhesive
	d. Sheeting
	e. Durability
	f. Impact Resistance
	g. General Characteristics and Packaging
6.	Prismatic Lens, Super High Intensity, Reflective Sheeting
	a. Reflectivity
	b. Color
	c. Adhesive
	d. Sheeting
	e. Durability
	f. Impact Resistance
	g. General Characteristics and Packaging
(e)	Letters, Numerals, Symbols, and Accessories
	1. Embossed Reflective Sheeting Type
	2. Acrylic Plastic Type
(f)	Fiberglass Reinforced Plastic Sign Panels
	1. Mechanical Properties
	2. Physical Properties
	a. Thickness
	b. Length and Width
	(1) Panel Length of 3660 mm (144 in.) or Less
	(2) Panel Length Exceeding 3660 mm (144 in.)
	(3) Panel Width of 3660 mm (144 in.) or Less
	c. Squareness
	d. Weather Resistance
	e. Fire Resistance
	f. Impact Resistance
	g. Coefficient of Linear Thermal Expansion
	h. Panel Smoothness
	i. Flatness
	(1) Test Purpose
	(2) Test Procedure
	j. Color
(g)	Samples and Tests
	1. Reflective Sheeting
	2. Traffic Signal Materials
913.11	Highway Illumination Materials
(a)	Lighting Standards and Mast Arms, under 80 feet (24.4 m)
	1. General Requirements
	2. Aluminum Lighting Standards
	a. Round Seamless
	b. Single Longitudinal Welded
	3. Stainless Steel Lighting Standards
	4. Galvanized Steel Lighting Standards
	5. Wood Pole Lighting Standards
	6. Frangible Breakaway Bases
	a. Cast Aluminum Transformer Base
	b. Breakaway Coupling
	7. Anchor Bolts
(b)	High Mast Standards of 24.5 m (80 ft) and Over
	1. High Mast Poles
	2. Welding

TABLE OF CONTENTS

Section	Title
	3. Handholes
	4. Luminaire Ring Assembly
	5. Head Frame Assembly
	6. Winch Assembly
	7. External Drive System
	8. Cable Terminator
	9. Lightning Rod Assembly and Grounding System
	10. Anchor Bolts
(c)	Wire and Cable
	1. Polyethylene Conduit
	2. Conductors in Cable-Duct
	3. Lighting Standard Circuit Wiring
	4. Sign and Underpass Wiring
	5. Aerial Cable
	6. High Mast Tower Luminaire Ring Conductors
	7. Power Cable-High Mast Poles
	8. Electrical Connectors
(d)	Luminaires
	1. General Requirements
	2. Roadway Lighting Luminaires
	3. Sign Luminaires
	4. Underpass Luminaires
	5. High Mast Luminaires
(e)	Circuit Breakers and Enclosure
	1. Circuit Breakers for Type II Service Point
	2. Circuit Breakers for Sign and Underpass Circuits
	3. Circuit Breakers for High Mast Poles
	4. E-Series Magnetic Circuit Breakers
(f)	Multiple Relay Switches with Photocell Receptacles
(g)	Shop Drawings
(h)	Materials Certification
913.12	Construction Warning Lights
(a)	Types of Warning Lights
	1. Type A
	2. Type B
	3. Type C
(b)	General Requirements
(c)	Flash Requirements
	1. Flash Rate
	2. On-Time
	a. Definition
	b. Type A
	c. Type B
(d)	Optical Requirements
	1. Effective Intensity
	2. Lens Illumination
	3. Reflex-Reflective Performance
	4. Testing Procedure
(e)	Lens Requirements
	1. Size of Lens
	2. Number of Lenses
	3. Lens Chromaticity
	4. Lens Luminous Transmittance
	5. Lens Material
(f)	Head and Housing

TABLE OF CONTENTS

Section	Title
	1. Swivel Head
	2. Housing
	3. Weatherproofing
	(g) Photoelectric Controls
	(h) Basis For Use
913.13	Flashing Arrow Sign
913.14	Pavement Marking Material
	(a) Traffic Paint
	(b) Durable Marking Material
	1. Thermoplastic
	a. Material Requirements
	(1) Reflectorization
	(2) Set Time
	(3) Water Absorption
	(4) Softening Point
	(5) Specific Gravity
	(6) Impact Resistance
	(7) Low Temperature Stress Resistance
	(8) Bond Strength
	(9) Hardness
	b. Packaging
	c. Basis for Use
	2. Preformed Plastic
	a. Material Requirements
	(1) Tensile Strength
	(2) Adhesive Stability Test
	(3) Adhesive Shear Strength
	(4) Bend Test
	b. Packaging
	c. Basis For Use
	3. 100 Percent Solids Epoxy
	a. Material Requirements
	(1) Glass Beads
	(2) Abrasion Resistance
	(3) Hardness
	(4) Tensile Strength
	(5) Compressive Strength
	(6) Weather Resistance
	(7) Laboratory Drying Time
	(8) Viscosity
	b. Materials Preparation
	c. Packaging and Storage
	d. Basis For Use
(c)	Temporary Pavement Marking Tape
(d)	Raised Pavement Marker
	1. Snowplowable Raised Pavement Marker
	a. Prismatic Reflector
	(1) Optical Performance
	(2) Seal Test
	(3) Heat Resistance Test
	(4) Strength Test
	(5) Impact Test
	(6) Temperature Cycling Test
	(7) Adhesive Tensile Strength Test
	(8) Basis for Use

TABLE OF CONTENTS

Section	Title
	b. Cast Metal Base
	(1) Epoxy Adhesive
	(2) Basis for Use
	c. Precast Cement Concrete Base
	(1) Adhesive for Precast Concrete Base
	(2) Packaging
	(3) Basis for Use
2.	Temporary Raised Pavement Marker
	a. Optical Requirements
	b. Strength Requirements
	c. Adhesive
	d. Acceptance Evaluation
	e. Basis for Use
913.15	Traffic Signal Materials and Equipment
(a)	Traffic Signal Controller and Cabinet
	1. Model Approval
	2. Controllers or Control Units Furnished and Installed by the Contractor
	3. Blank
	4. Bench Testing
	5. Pretimed Solid State Digital Controller
	a. General
	b. Controller Requirements
	c. Spare Modules
	d. Controller Enclosure
	e. Power Requirements
	f. Certification of Traffic Control Units
	g. Warranty
	6. Traffic Actuated Solid State Digital Controller
	a. General
	b. Controller Requirements
	c. Spare Modules
	d. Controller Enclosure
	e. Power Requirements
	f. Certification of Traffic Control Units
	(1) Certification of a Production Run Model
	(2) Certification of Environmental Testing
	g. Warranty
	7. Cabinet Requirements for Traffic Signal Controllers
	a. General
	b. G Cabinet
	(1) Cast Aluminum Pedestal Base
	(2) Pedestal Pole
	(3) Pole Cap
	c. M Cabinet
	d. P-1 Cabinet
	8. Two Circuit Alternating Flasher
	a. General
	b. Cabinet Requirements
(b)	Interconnection Equipment.
	1. Hardwire Interconnection
	a. Electro-Mechanical Dial Coordination Unit
	(1) General
	(2) Additional Requirements for Master Locations
	(3) Additional Requirements for Secondary Locations
(c)	Blank

TABLE OF CONTENTS

Section	Title
(d)	Signal Head Components
1.	Vehicle Signal Face
a.	General
b.	Housing, Door, and Visor
c.	Lens
d.	Reflector Assembly
e.	Lamp Receptacle and Wiring
f.	Section Coupling
g.	Terminal Block
h.	Material Requirements
(1)	Polycarbonate Signal Head
(2)	Die-Cast Aluminum Signal Head
i.	Certification
2.	Pedestrian Signal Head
a.	Housing, Door, and Visor
b.	Optical Unit
c.	Lens
d.	Message
e.	Reflector Assembly
f.	Light Distribution
g.	Electrical
3.	Disconnect Hanger Junction Box
4.	Signal Bulbs
5.	Free Swinging Signal Support Assemblies
6.	Mid-Mast Arm Mount Signal Bracket
7.	Pedestal Mounted Control Cabinets or Pedestrian Signal Heads
(e)	Signal Support
1.	Steel Strain Pole
a.	Maximum Load 35.6 kN (8000 lbs)
2.	Wood Strain Pole
3.	Signal Cantilever Structures
a.	General
b.	Signal Support
c.	Combination Signal-Luminaire Support
d.	Pole Requirements
(1)	General
(2)	Deflection
(3)	Materials
(4)	Hardware
(5)	Anchor Base
e.	Arm Requirements
(1)	Signal Cantilever Arm
(2)	Luminaire Mast Arm for Combination Support
(3)	Materials
f.	Anchor Bolts
g.	Finish
h.	Certification
i.	Shop Drawings
4.	Downguys, Anchors, Rods, and Guards
(f)	Messenger Cable
1.	Messenger Cable
2.	Span, Catenary, and Downguy Cable
3.	Tether and Support Cable
4.	Cable Hardware
a.	Messenger Hangers

TABLE OF CONTENTS

Section	Title
	b. Cable Ring
	c. Clamps
	d. Servi-Sleeves
	e. Straight Eye-Bolts
	f. Hub-Eyes
5.	Signal Cable
	a. Hook-up Wire
	b. Signal Control Cable
	c. Integral Messenger Interconnect Cable
	d. 6 Pair/19 Telemetry Cable
	e. Fiber Optic Interconnect Cable
	f. Service Cable
	g. Detection Wire and Sealant
	(1) Loop Detector Lead-in Cable
	(2) Roadway Loop Wire
	(3) Sealant
	h. Ground Wire
	i. Splicing Kit
(g)	Ground Rod and Connections
(h)	Castings for Handholes
(i)	Entrance Switch
(j)	Conduit and Fittings
	1. Steel Conduit
	2. Polyvinyl Chloride Conduit
(k)	Detector Housing
(l)	Certification
913.16	Fabric for Waterproofing
913.17	Packaged, Dry, Combined Materials for Mortar and Concrete
913.18	Geotextile for Use Under Riprap
913.19	Geotextile for Use with Underdrains
913.20	Geotextile for Silt Fence
914 --	ROADSIDE DEVELOPMENT MATERIALS
914.01	Special Topsoil for Roadside Development
914.02	Blank
914.03	Fertilizer
914.04	Grass and Legume Seed
914.05	Mulch
	(a) Mulch for Seeding
	1. Excelsior Mulch
	2. Wood Cellulose Fiber
	3. Excelsior Blanket
	4. Paper Mat
	5. Straw Mat
	(b) Mulch for Plants
914.06	Leguminous Inoculants
914.07	Sod
914.08	Plant Materials
	(a) Quality of Plant Materials
	(b) Plant Names
	(c) Substitutions
	(d) Grading Standards
	(e) Nursery Inspection and Plant Quarantine
	(f) Balled and Burlapped Plants

TABLE OF CONTENTS

Section Title

(g) Container Grown Plants	
(h) Bare Rooted Plants	
(i) Collected Plants	
(j) Forms, Shapes, and Condition of Plants	
(k) Inspection	
(l) Shipment	
(m) Certification	
914.09 Miscellaneous Material	
(a) Water	
(b) Stakes for Bracing and Anchoring	
(c) Tree Wound Dressing	
(d) Porous Material	
(e) Pipe	
(f) Staples	
(g) Plastic Net	
915 -- BRIDGE PILES AND BEARINGS	
915.01 Steel Shell Encased Concrete Piles and Epoxy Coated Steel Shell Encased Reinforced Concrete Piles	
(a) General Requirements	
(b) Fluted Steel Pile Shells	
(c) Rounded Steel Pipe Shells	
(d) Epoxy Coating for Piles	
1. Prequalification of Organic Coatings for Steel Piles	
a. Product Data Sheet	
b. Fingerprint	
c. Materials Safety Data Sheets	
d. Laboratory Report	
(1) Tensile Strength and Elongation	
(2) Impact Resistance	
(3) Abrasion Resistance	
(4) Salt Fog	
2. Application	
a. Surface Preparation	
b. Coating Application	
(1) Thickness	
(2) Cure	
(3) Continuity of Coating	
3. Certification	
915.02 Steel H Piles and Epoxy Coated Steel H Piles	
915.03 Wood Piles	
915.04 Elastomeric Bearings	
(a) Description	
(b) Materials	
(c) Manufacturing Requirements	
(d) Appearance and Dimensions	
(e) Quality Assurance	
(f) Certification	
916 -- MATERIALS CERTIFICATIONS	
916.01 General	
916.02 Types of Certifications	
(a) Type A	
(b) Type B	
(d) Type D	
(e) Other Types	
(f) Requirements for Small Quantities of Materials	

TABLE OF CONTENTS

Section	Title
	(g) Buy American Requirement
916.03	Sample Forms
	(a) For Plants
	(b) For Certificate of Nursery Inspection
	(c) For Welding Electrodes
	(d) For Buy American Requirement
	(e) For Fly Ash Source Certification
	(f) For Portland Cements and Blended Cements
	(g) For Geotextiles Used Under Riprap
	(h) For Geotextiles Used With Underdrains
	(i) Blank
	(j) Sample Type A Certification Form
	(k) Sample Type B Certification Form
	(l) Sample Type C Certification Form
	(m) Sample Type D Certification Form
	(n) For Ground Granulated Blast Furnace Slag
	(o) For Microsilica
	(p) Sample Asbestos Exclusion Letter
917 --	QUALITY ASSURANCE AGGREGATE CERTIFICATION
917.01	General Requirements
917.02	Quality Control Plan
917.03	Source Approval Requirements
	(a) Step 1
	(b) Step 2
	(c) Step 3
917.04	Removal from Certified Producer Status
917.05	Appeals