



**TYPE D-1 SAWED CONTRACTION
JOINT SEALANT OPTIONS**

NOTES

1. Transverse joints shall be constructed perpendicular to the centerline with a maximum spacing of 5500 unless otherwise specified.
2. The configuration of the preformed elastomeric joint seal shall be a 14 to 16 wide seal with at least a five cell internal design. The seal height shall be 14 to 21 in uncompressed stage.
3. For transverse construction joints, the initial saw cut may be eliminated.

All Dimension are in mm unless otherwise specified	
INDIANA DEPARTMENT OF TRANSPORTATION	
TRANSVERSE JOINT SEALS	
MARCH 2004	
STANDARD DRAWING NO. 503-CCPJ-06	
	/s/ Richard L. VanCleave 3-01-04 DESIGN STANDARDS ENGINEER DATE
	/s/ Richard K. Smutzer 3-01-04 CHIEF HIGHWAY ENGINEER DATE
DESIGN STANDARDS ENGINEER	