BRIDGE INVENTORY REPORT

Prepared for

FLOYD COUNTY, INDIANA

Phase II - 2020

THE BOARD OF COUNTY COMMISSIONERS FLOYD COUNTY, INDIANA

Shawn Carruthers

John Schellenberger

Tim Kamer

Prepared by:



Approved by: Floyd County Engineer

Nicholas J. Kocher, P.E.

Nicholae J. Kocher

Project Manager

IN000409-2020-ATL-F-LRE

Michael Rowe

Michael A. Rowe, P.E. Transportation Director No. PEI1100665

No. PEI1100665

STATE OF

STONAL F



Table of Contents

Title Page	i
Table of Contents	1
Bridge Evaluation Criteria	2
Listing of Personnel/Qualifications	5
Signature of Team Leaders	5
Priority Schedule for Bridges	6
Increased Frequency Inspections List	8
Recommended Maintenance Items	9
List of Posted Bridges	15
List of Closed Bridges	16
List of Bridges That Must Be Posted	17
List of Bridges That Must Be Closed	18
List of Bridges That Require Posting Corrections	19
Summary of New, Rehabilitated, and Repaired Bridges	20
Summary of Added, Archived, and Deleted Bridges	21
Summary of Structure Types	22
Listing of Bridges With Inventory Routes On The National Highway System	23
Listing of Historical Structures	24
Listing of Navigable Waterways	25
Summary of Changes in Items 92A, 92B, and 92C	26
Inspection Status of Scour Critical Bridges	27
Load Capacity Status	28
Routine Inspection Status	31
Fracture Critical Inspection Status	34
Underwater/In-Water Inspection Status	35
Special Feature Inspection Status	36
Work Plan for Inspections and Re-Inspections	37
Master List of In-Depth Inspections	38
Structure Inventory and Appraisal Reports	By Bridge Number
Appendix A - NBI Item Descriptions and Structure Types Abbr.	
Appendix B - Supplemental Photos	
Appendix C - Fracture Critical and Special Feature Reports	

BRIDGE EVALUATION CRITERIA

Introduction

This report was prepared in accordance with the "INDOT BRIDGE INSPECTION MANUAL, 2019", the AASHTO "MANUAL FOR BRIDGE EVALUATION, THIRD EDITION, 2018", and the AASHTO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, 2002", and ALL INTERIM SPECIFICATIONS.

Scope

Included in this report is an appraisal for all public Highway Bridges with a total span of more than twenty feet in Floyd County, Indiana, except those bridges maintained by the Indiana Department of Transportation. Bridges located on the north or west borders of Floyd County are not included due to a statutory definition of responsibility, which gives the responsibility for these bridges to the adjoining county.

A total of ninety (90) bridges are included in this report.

Bridge Numbering System

The bridge numbering system used in this report corresponds with the numbering system used in the Inventory of County Highway Bridges compiled by Indiana LTAP (Local Transportation Assistance Program).

Structural Inventory and Appraisal Sheet

The results of this bridge inspection are recorded on each bridge's individual "Structure Inventory and Appraisal Sheets." The inspection was completed in accordance with the Guidelines and Item Designation as set forth in the Federal Highway Administration Publication "Recording and Coding guide for the Structure Inventory and Appraisal of the Nation's Bridges," published December 1995 with 2001 Revisions and by the Indiana Department of Transportation Bridge Inspection Program "BRAGI Coding Guide, 2011".

Field Survey

All bridges over twenty feet in span length were located, inspected, and documented on their "Structure Inventory and Appraisal Sheets." A field crew, using the previous reports to compare with the current conditions, inspected all bridges included in this report. New color photos were taken of all structures as well as individual structure items that had a changed condition.

Office Evaluation

After completion of the field inspection, the structures were reviewed in the office. The field data collected was evaluated and compared with the data from the previous Structural Inventory & Appraisals, and condition and appraisal ratings were revised to reflect present conditions.

The Design, Legal, and Permit Ratings were calculated based on structure data obtained during this inspection. During the field inspection, the conditions of structural steel, concrete, and timber were compared with new materials and a percentage of section loss was estimated reflecting the current degree of material deterioration. This estimated percentage loss was used in determining the new operating and inventory ratings.

Replacement Priorities and Repair Recommendations

All structures were evaluated for replacement priorities and repair recommendations. The following are among items, which are given important consideration when determining replacement priorities and repair recommendations:

<u>The Average Daily Traffic</u> on a structure measures the importance of a structure to the County transportation system. Therefore, structures which receive high traffic counts were given higher priorities for replacement or repair than those bridges which handle only a few vehicles per day.

<u>The Structural Condition</u> of a bridge helps estimate the length of time the structure can safely carry traffic at its present capacity. Many structures have deteriorated from age, weathering, or other factors to a condition where repairs are not economically feasible, and must eventually be replaced.

<u>Bridge Alignment and Width</u> is a major indicator of the safety of the structure to the traveling public. Factors included are horizontal and vertical alignment to the approaches in relationship to the bridge, bridge width, approach signing and marking, bridge rail, guard rail, and slope protection.

<u>Legal Load Capacity</u> indicates the safe load that can repeatedly travel over the bridge in its present structural condition. Structures with low load capacities were given higher replacement priorities than those with more adequate ratings.

<u>Waterway Adequacy</u> indicates if the waterway area under the structure is large enough to handle floodwaters. Existing channel alignment in relationship to the substructure is also analyzed.

Replacement Priorities and Repair Recommendations (continued)

<u>Estimated Replacement Cost</u> is important in setting repair recommendations or replacement priorities. Large structures cost a great deal to replace and were recommended for repairs whenever possible; likewise, many small structures were recommended for replacement. Since replacement costs were not that much greater than extensive repair costs, some of these small bridges can be replaced with pipes or pipe arches at a considerable savings over replacement with a conventional bridge. However, this can only be recommended after a complete hydraulic analysis has been completed.

Whenever practical, repair recommendations were given to structures where repairs could significantly increase their life and safety. In many cases, extensive repairs are not feasible since the structures would still be deficient in other aforementioned vital areas.

Rusting is a major problem on any bridge consisting of steel members. The rusting and resulting deterioration of members can greatly decrease a structure's future usable life. Cleaning and painting the steel as soon as possible is very important in insuring the longevity of these structures.

Signs and Markings

The recommended signing tabulated in this report is the minimum required by the "Manual on Uniform Traffic Control Devices for Streets and Highways" published by the Federal Highway Administration and the Indiana Department of Highways. An assessment should be made in the field for the possibility of extending the signing to include features such as intersections, curves, or other substandard conditions near the bridge.

LISTING OF BRIDGE INSPECTION PERSONNEL, TITLE, QUALIFICATIONS, AND RESPONSIBILITIES

Reponsibilities/Duties	General Project Supervision Inspection Team Leader	Project Manager Inspection Team Leader Field Inspection Inventory Report Q/A Load Rating Q/A Fracture Critical Inspection FC Report Q/A	Inspection Team Leader Field Inspection	Team Member Field Inspection Inventory Report Q/A FC Report Q/A	Tæm Member Field Inspection SI&A Coding Report Preparation
Load Rating	1	×	•	×	ı
Special Detail	1	×	1	1	
Under- water		1			
Fracture Critical		×			
Biennial Inspection	1	×	×	•	ı
Attended NHI Class	×	×	×	•	•
Experience/ Qualifications	B.S Civil Engineering Purdue University Indiana Professional Engineer #19800071 29 Years Experience in Bridge Design, Inspection, and Load Rating	B.S Civil Engineering University of Illinois Indiana Professional Engineer #11100665 14 Years Experience in Bridge Design, Inspection, and Load Rating	B.S Industrial Technology Indiana State University Construction Project Manager 35 Years Experience in Bridge Construction and Inspection	B.S Civil Engineering University of Evansville Indiana Professional Engineer #11900814 5 Years Experience in Bridge Design, Inspection, and Load Rating	A.E.T Architectural Engineering Technology ITT AutoCAD Designer 25 Years Experience in Bridge Detailing
Name/Title	Jon Clodfelter, P.E. Bridge Department Manager IN000631-2028-ATL	Nick Kocher, P.E. Project Manager IN000409-2020-ATL-F-LRE	Mark Berry, S.I. Construction Manager IN000154-2025-ATL	Abby Browder, P.E. Project Engineer IN000553-2022-ATM	Dave Zola CAD Designer

The following Inspection Team Leaders were present and were actively involved in the Field Inspections of bridges in Floyd County.

Micholae J. Hosher

Mark Berry, S.I.

PRIORITY SCHEDULE FOR COUNTY BRIDGES

(1) REPLACEMENT (2) REHABILITATION

(3) WIDENING (4) REPAIR (5) ELIMINATE

CATEGORY: 1

						Estimat	ed Costs (x	\$1,000)
Bridge	Priority	Year of	Type of	Gross	Sufficiency			
Number	Number	Work	Work	Tons	Rating	Bridge	Roadway	Total
00051	1	2020	31	20	44.9	983	467	1830
00003	2	2021	31	20	56.4	232	184	525
00506	3	2022	31	10	70.7	202	184	488
00043	4	2023	31	20	66.3	365	184	693
00038	5	2024	31	20	76.5	274	184	578
00085	6	2025	31	20	49.3	209	184	496
00087	7	2026	31	20	71.4	281	184	587
00024	8	2027	31	20	68.8	306	184	619
00039	9	2028	31	20	85.9	194	184	477
00041	10	2029	31	23	65.5	329	184	648

Total Bridges for Category 1: 10

Estimated Costs for Replacement Projects =

\$6,941,000

CATEGORY: 2

						Estimat	ted Costs (x	\$1,000)
Bridge Number	Priority Number	Year of Work	Type of Work	Gross Tons	Sufficiency Rating	Bridge	Roadway	Total
•								
00027	1	2020	35	48	67.7	423	184	735
00031	2	2021	35	25	60.8	137	184	389
00035	3	2022	35	42	81.6	336	184	630
00007	4	2023	35	20	76.6	170	184	429
00063	5	2024	35	53	54.4	131	184	382
00101	6	2025	35	20	95.2	148	184	402

Total Bridges for Category 2: 6

Estimated Costs for Rehabilitation Projects = \$2,967,000

PRIORITY SCHEDULE FOR COUNTY BRIDGES

(1) REPLACEMENT

(2) REHABILITATION

(3) WIDENING

(4) REPAIR

(5) ELIMINATE

CATEGORY: 3

						Estimated Costs (x \$1,00		\$1,000)
Bridge	Priority	Year of	Type of	Gross	Sufficiency			
Number	Number	Work	Work	Tons	Rating	Bridge	Roadway	Total

NONE

Total Bridges for Category 3: 0

CATEGORY: 4

						Estimat	ed Costs (x	\$1,000)
Bridge	Priority	Year of	Type of	Gross	Sufficiency			
Number	Number	Work	Work	Tons	Rating	Bridge	Roadway	Total

NONE

Total Bridges for Category 4: 0

CATEGORY: 5

						Estimat	ed Costs (x	sts (x \$1,000)		
Bridg	e Priority	Year of	Type of	Gross	Sufficiency					
Numb	er Numbe	Work	Work	Tons	Rating	Bridge	Roadway	Total		

NONE

Total Bridges for Category 5: 0

SUMMARY OF BRIDGES WITH INCREASED FREQUENCY INSPECTIONS

Bridge Number	Designated Inspection Frequency	Fracture Critical Required	Fracture Critical Frequency	Fracture Critical Inspection Date	Underwater Required	Underwater Inspection Frequency	Underwater Inspection Date	Special Inspection Required	Special Inspection Frequency	Special Inspection Date
22-00003	12	N			N			N		
22-00027	12	N			N			N		
22-00031	12	N			N			N		
22-00035	12	N			N			N		
22-00051	12	N			N			N		
22-00063	12	N		05/01/2014	N		09/21/2017	N		
22-00085	12	N			N			N		

Total Increased Frequency Inspections: 7

Bridge Number	Facility Carried	Feature Intersected	Riprap Needed	Clear Vegetation Around Bridge	Clear Bridge Joints, Deck, Gutters, Drains	Regrade Approaches	Clear Debris in Channel	Damaged or Low Guardrail	Remarks
00001	SCOTTSVILLE RD	BANNAMON CREEK						✓	RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, EXTENDING WEARING SURFACE FULL WIDTH, REPAIR DAMAGED BRIDGE AND APPROACH GUARDRAIL IN NW CORNER.
00002	HANKA Rd	BANNAMON Creek							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S.
00003	CHAPEL HILL	THOMPSON CREEK							UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD APPROACH RAILING WITH END TREATMENT AND NORTHEAST AND SOUTHWEST BRIDGE END MARKERS.
00004	MILLER RD	MILLER BR OF JERSEY PK B	✓						RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S, PLACING RIPRAP BEHIND WINGS AND AT BRIDGE CORNERS.
00005	ARTHUR COFFMAN RD	JERSEY PARK CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S, AND REPAIR NW SHOULDER EROSION.
00006	BORDEN RD	JERSEY PARK CREEK							RECOMMEND INSTALLING CURRENT STD. NE & SW B.E.M.'S.
00007	SCTSVILLE- NAVILLE.	LITTLE INDIAN CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.
00009	ATKINS ROAD	BRANCH of BIG INDIAN CR.							NO NEW RECOMMENDATIONS
00010	BALMER- FENWICK Rd	BIG INDIAN Creek	✓						RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S, AND PLACING RIPRAP ALONG EAST PIER.
00011	BETHEL- FREIBERGER	BIG INDIAN Creek							RECOMMEND INSTALLING CURRENT STD. NW & SE B.E.M.'S.
00012	BANET Rd	Little INDIAN Creek							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S
00013	BANET RD	BIG INDIAN CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S.
00014	NAVILLETON Rd	Little INDIAN Creek							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S, AND REPAIR SE CORNER GUARDRAIL.
00015	G'TOWN- GREENVILLE	RICHLAND CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S, AND PATCHING SPALLS IN BOTTOM OF SUPERSTRUCTURE.
00016	STILLER Rd	BIG INDIAN Creek			✓			1 1/	RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL W/END TREATMENT AND ALL B.E.M.'S, REMOVING DEBRIS FROM, DECK, WIDENING OVERLAY TO CURBS, REPAIRING NE GUARDRAIL, AND PATCHING DECK.
00017	FEATHERINGILL Rd	Branch Little INDIAN Cr							RECOMMEND PATCHING AROUND THE UNDERSIDE DRAINS.
00018	BUCK CREEK RD	BUCK CREEK							RECOMMEND INSTALLING CURRENT STD. NE, NW & SW B.E.M.'S.
00019	NAVILLETON Rd	BIG INDIAN Creek							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, REPAIR APPROACH GUARDRAIL

Bridge Number	Facility Carried	Feature Intersected	Riprap Needed	Clear Vegetation Around Bridge	Clear Bridge Joints, Deck, Gutters, Drains	Regrade Approaches	Clear Debris in Channel	Damaged or Low Guardrail	Remarks
00020	OLD VINCENNES RD	YELLOW FORK							NO MAINTENANCE NEEDED.
00021	JOHN PECTOL Rd	Little INDIAN Creek							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, AND REPLACING APPROACHES.
00022	HAMBY Rd	BIG INDIAN Creek			✓				RECOMMEND INSTALLING CURRENT STD. ALL B.E.M.'S, AND CLEANING DECK.
00023	JOHN PECTOL RD	BIG INDIAN CREEK			√				RECOMMEND CLEANING DEBRIS FROM LOWER CHORDS.
00024	G'TOWN- GREENVILLE	RICHLAND CREEK							UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD APPROACH AND END TREATMENT GUARDRAIL.
00025	BAKER ROAD	RICHLAND CREEK	✓						RECOMMEND PLACING RIPRAP AT SOUTHWEST CORNER AND INSTALLING CURRENT STANDARD APPROACH GUARDRAIL.
00026	G'TOWN- GREENVILLE	RICHLAND CREEK	✓						RECOMMEND INSTALLING CURRENT STANDARD APPROACH RAIL AND BRIDGE END MARKERS AT NORTHEAST AND SOUTHEAST, PLACING RIPRAP AT SOUTHWEST AND SOUTHEAST CORNERS.
00027	G'TOWN- GREENVILLE	BIG INDIAN Creek	✓						UNTIL REHABILITATION, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT, AND PLACING BACKFILL AND RIPRAP AT END BENTS.
00028	G'TOWN- GREENVILLE	RICHLAND CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S.
00029	EDWARDSVIL GALENA	LITTLE INDIAN CREEK							RECOMMEND PATCHING SPALL ON PIER CAP AND REPLACING BRIDGE END JOINTS.
00031	N LUTHER RD	LITTLE INDIAN CREEK	✓						UNTIL REHABILITATION, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT AND MISSING NORTHEAST AND SOUTHWEST BRIDGE END MARKERS, AND PLACING RIPRAP IN SOUTHEAST QUADRANT.
00032	REASOR RD	LITTLE INDIAN CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND SE B.E.M.'S. AND FILL NORTHEAST SHOULDER EROSION
00033	MALINEE-OTT RD	GEORGETOWN CREEK	✓						RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, REPAIRING SE SHOULDER EROSION, AND PLACING RIPRAP AT SE CORNER AND BEHIND SE WING.
00035	G'TOWN- LANESVILLE	GEORGETOWN CREEK	✓						UNTIL REHABILITATION, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT AND MISSING NORTHEAST, SOUTHWEST, AND NORTHWEST BRIDGE END MARKERS, AND PLACING RIPRAP AT SOUTH ABUTMENT.
00036	WISSMAN RD	GEORGETOWN CREEK	✓						RECOMMEND PLACING RIPRAP ON S SPILLSLOPE.

Bridge Number	Facility Carried	Feature Intersected	Riprap Needed	Clear Vegetation Around Bridge	Clear Bridge Joints, Deck, Gutters, Drains	Regrade Approaches	Clear Debris in Channel	Damaged or Low Guardrail	Remarks
00037	WALTS RD	GEORGETOWN CREEK							NO MAINTENANCE NEEDED.
00038	BAYLOR- WISSMAN RD	GEORGETOWN CREEK							UNTIL REPLACEMENT RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.
00039	MOSER KNOB	LITTLE INDIAN CREEK					√		RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, AND CLEANING CHANNEL IN S SPAN.
00040	SCOTTSVILLE RD	BIG INDIAN CREEK							NO MAINTENANCE REQUIRED.
00041	ST MARY'S RD	LITTLE INDIAN CREEK	√						UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S AND PLACING RIPRAP AT S ABUTMENT.
00042	SPICKERT KNOB RD	LITTLE INDIAN CREEK	√				√		RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S, AND PLACING RIPRAP BEHIND SW WING. REMOVE TREE SOUTH OF BRIDGE THAT IS LEANING OVER THE DOCK.
00043	SCOTTSVILLE RD	LITTLE INDIAN CREEK	✓				√		RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.
00044	ST MARY'S RD	LITTLE INDIAN CREEK							RECOMMEND INSTALLING CURRENT STD. NW B.E.M.'S.
00045	PAYNE/KOEHLER RD	UPHILL RUN							RECOMMEND INSTALLING CURRENT STD. NE & NW B.E.M.'S.
00046	PAOLI PIKE	LITTLE INDIAN CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.
00047	DUFFY RD	LITTLE INDIAN CREEK	✓						RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, PLACING RIPRAP AT SW CORNER.
00050	KLERNER LN	SLATE Run Creek							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S, PATCHING SPALLS ON DECK, AND REPLACING EXPANSION JOINT SEALS.
00051	BLACKISTON MILL RD	SILVER CREEK	✓						UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING AND ALL BRIDGE END MARKERS, PLACING RIPRAP AT UPSTREAM END OF PIER SOUTHWEST CORNER, AND NORTHEAST WING, AND REPAIRING CONCRETE AT UPSTREAM END NOSE OF PIER.
00055	CHAPEL LN	LEWIS BR OF JACOABS CR							NO MAINTENANCE NEEDED.
00057	HIGHWATER RD	MIDDLE CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

Bridge Number	Facility Carried	Feature Intersected	Riprap Needed	Clear Vegetation Around Bridge	Clear Bridge Joints, Deck, Gutters, Drains	Regrade Approaches	Clear Debris in Channel	Damaged or Low Guardrail	Remarks
00058	BUDD RD	FRENCH CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.
00060	BORDEN ROAD	BRANCH OF JERSEY PARK CR			✓		✓		RECOMMEND CLEANING DEBRIS FROM DECK AND CLEARING SILT/ GRAVEL FROM CHANNEL.
00061	BUDD RD	KNOB CREEK							RECOMMEND INSTALLING CURRENT STD. NE & SW B.E.M.'S
00062	OLD RIVER RD	MIDDLE CREEK					√		RECOMMEND REMOVING DEBRIS FROM GUTTERS.
00063	FIVE MILE LN	KNOB CREEK	✓						UNTIL REHABILITATION, RECOMMEND PLACING RIPRAP ALONG EAST ABUTMENT.
00064	SEVEN MILE LN	KNOB CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & NW B.E.M.'S
00065	DAILY RD	KNOB CREEK	✓						RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE NW & SW B.E.M.'S, REPLACE FILL BEHIND S ABUTMENT, AND PLACING RIPRAP ON SOUTH ABUTMENT.
00066	RIDGEVIEW DR	LITTLE INDIAN CREEK							RECOMMEND INSTALLING CURRENT STD. NE NW & SW B.E.M.'S.
00070	SPRING ST	SILVER CREEK	✓		✓				RECOMMEND CLEANING DRAINS, AND PLACING RIPRAP ALONG NW WING.
00071	TWO MILE LN	FRENCH CREEK	✓						RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE & SW B.E.M.'S, AND PLACING RIPRAP AT SE CORNER.
00072	EVANS-JACOBI RD	BRANCH LITTLE INDIAN CR							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/ END TREATMENT.
00073	CROWDER RD	RICHLAND CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT.
00076	TWO MILE LN	FRENCH CREEK	✓						RECOMMEND INSTALLING CURRENT STD. NW & SE B.E.M.'S, AND PLACING RIPRAP ALONG S ABUTMENT.
00080	SEVEN MILE LN	STEWART CREEK							NO MAINTENANCE NEEDED.
00081	JOHN PECTOL RD	BR LITTLE INDIAN CR					✓		RECOMMEND CLEARING CHANNEL UPSTREAM AND DOWNSTREAM AND REMOVING EXCESSIVE WEARING SURFACE.

Bridge Number	Facility Carried	Feature Intersected	Riprap Needed	Clear Vegetation Around Bridge	Clear Bridge Joints, Deck, Gutters, Drains	Regrade Approaches	Clear Debris in Channel	Damaged or Low Guardrail	Remarks
00085	BRADFORD RD	CORN CREEK							UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT AND ALL BRIDGE END MARKERS, REPLACING NARROW SIGN AT WEST END, AND REPAIRING NORTHEAST WINGWALL.
00087	MARY NAVILE RD	BANNAMON CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S AND FILL EROSION IN NW CORNER.
00088	BORDEN RD	MILLER BR OF JERSEY PK B							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S AND REPAIR NW SHOULDER EROSION.
00089	CHAPEL HILL RD	CAMPBELL BR JERSEY PK CR	✓						RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S, PLACING RIPRAP AT NE CORNER, AND REPAIR NE SHOULDER EROSION.
00091	GAP HOLLOW RD	KNOB CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL & NE & SE B.E.M.'S
00093	BUDD RD	EISEMAN CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL AND ALL B.E.M.'S.
00094	E MCCARTHY KNOB RD	AL'S CREEK	✓						RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S, AND PLACING RIPRAP AT SE CORNER.
00096	BEECHWOOD AVE	FALL RUN							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SW B.E.M.'S. PATCH SPALLED BEAMS.
00101	OLD SR 111	BRANCH ELK RUN							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S, AND REPLACING BRIDGE JOINT AND DECK OVERLAY.
00102	CHARLESTOWN RD	JACOBS CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE GUARDRAIL, NW & SW B.E.M.'S.
00103	ASHBURY DRIVE	BALD KNOB CREEK					√		RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, AND CLEANING DEBRIS IN CHANNEL.
00104	ENDRES PARKWAY	JACOBS CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.
00105	BEAR CREEK ROAD	BEAR CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. TRANSITION RAIL.
00501	BINFORD PARK ST	FALLING RUN CREEK	✓						RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, PLACING RIPRAP AT SW CORNER.
00502	FLOYD ST	FALLING RUN CREEK							RECOMMEND REMOVING LOGJAM AT INLET, INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

Bridge Number	Facility Carried	Feature Intersected	Riprap Needed	Clear Vegetation Around Bridge	Clear Bridge Joints, Deck, Gutters, Drains	Regrade Approaches	Clear Debris in Channel	Damaged or Low Guardrail	Remarks
00503	DAISY LN	FALLING RUN CREEK						✓	DAMAGED SOUTHWEST END TREATMENT
00504	SPRING HILL RD	FALLING RUN CREEK							NO MAINTENANCE NEEDED.
00505	SCRIBNER DR	FALLING RUN CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.
00506	PAMELA DR	FALLING RUN CREEK							UNTIL BRIDGE REPLACEMENT RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S. CLEAN ON REPLACE VANDALIZED NORTH LOAD LIMIT SIGN.
00507	WILLIAM LN	MIDDLE CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL.
00508	GRAYBROOK LN	FALLING RUN CREEK							RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.
00509	PEARL ST	FALLING RUN CREEK							RECOMMEND INSTALLING CURRENT STANDARD APPROACH RAIL WITH END TREATMENT AND NE, SE AND SW B.E.M.'S.
00510	CHARLESTOWN RD	BLACKISTON RUN							NO MAINTENANCE NEEDED.
00511	DAISY LN	TRINITY RUN							RECOMMEND INSTALLING CURRENT STD. ALL B.E.M.'S.
00512	GREEN VALLEY RD	TRINITY RUN							RECOMMEND INSTALLING CURRENT STD. ALL B.E.M.'S. REMOVE RIPRAP FROM CENTER OF CHANNEL TO THE SLOPES.
00513	STATE ST	FALLING RUN CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.
00514	COUNTRY CLUB DR	FALLING RUN CREEK							RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL AND ALL B.E.M.'S.

LIST OF POSTED BRIDGES

Bridge Number	Facility Carried	Feature Intersected	Location	Tons Posted	Date Posted
22-00506	PAMELA DR	FALLING RUN CREEK	00.20 N OF DAISY LANE	10	08/01/2007

Total Bridges Posted: 1

Notes:

The bridges above are posted based on a series of new vehicles classified as 'legal', 'routine permit', and 'emergency vehicles'. Bridges are load posted according to the safe posting load associated with these vehicles. Any vehicles which do not conform to those specified in the Indiana Bridge Inspection Manual should be evaluated before crossing any county bridge.

LIST OF CLOSED BRIDGES

Bridge				Tons	
Number	Facility Carried	Feature Intersected	Location	Posted	Date Posted

Total Bridges Closed: 0

LIST OF BRIDGES THAT MUST BE POSTED

Bridge				Required	
Number	Facility Carried	Feature Intersected	Location	Posting	Date Posted

Total Bridges That Must Be Posted: 0

LIST OF BRIDGES THAT MUST BE CLOSED

Bridge				Tons	
Number	Facility Carried	Feature Intersected	Location	Posted	Date Posted

Total Bridges That Must Be Closed: 0

LISTING OF BRIDGES THAT REQUIRE POSTING CORRECTIONS

Bridge				Required Posting	Current Tons
Number	Facility Carried	Feature Intersected	Location	Tons	Posted

Total Bridges With Posting Revisions: 0

SUMMARY OF BRIDGES (1) NEW AND (2) REHABILITATED

		(1) 14E44	AND (2) KLHADILHATED		
Bridge Number	NBI Number	Facility Carried	Feature Intersected	Location	Year of Work
CATEGORY: 1					
22-00009 B	2200112	ATKINS ROAD	BRANCH of BIG INDIAN CR.	00.10 S of RENN ROAD	2019
22-00105	2200111	BEAR CREEK ROAD	BEAR CREEK	0.1 mi. E. of SR-335	2019
Total Bridges fo	r Category 1 : 2				
CATEGORY: 2					
22-00009 B	2200112	ATKINS ROAD	BRANCH of BIG INDIAN CR.	00.10 S of RENN ROAD	2019
22-00010	2200009	BALMER- FENWICK Rd	BIG INDIAN Creek	00.10 W of ATKINS Rd	2017
22-00040	2200039	SCOTTSVILLE RD	BIG INDIAN CREEK	00.00 INT OF STARLIGHT RD	2017
22-00055	2200051	CHAPEL LN	LEWIS BR OF JACOABS CR	01.10 S OF GRANTLINE RD	2017

Total Bridges for Category 2:4

SUMMARY OF BRIDGES (1) ADDED, (2) ARCHIVED/DELETED

		. ,	, , ,		
Bridge Number	Facility Carried	Feature Intersected	Location	Year Built	NBI Number
CATEGOR	RY: 1				
22-00105	BEAR CREEK ROAD	BEAR CREEK	0.1 mi. E. of SR-335	2019	2200111
	ATKINS ROAD	BRANCH of BIG INDIAN CR.	00.10 S of RENN ROAD	2019	2200112
Total Bridg	jes for Category 1	1:2			
CATEGOR	Y: 2				
(311)31W- 22-01179 A RELQ	SR 311	JACOBS CREEK	01.00 N I-265	1931	031290
111-22- 05968 B archived	SR 111	FALL RUN	00.44 N SR 311	1967	025590
22-00009 Archived	ATKINS Rd	Branch of BIG INDIAN Cr	00.10 S of RENN Rd	1967	2200008
22-00018 archived	BUCK CREEK Rd	BUCK Creek	00.30 N of US 150	1974	2200017
22-00023 archived	JOHN PECTOL Rd	BIG INDIAN Creek	00.00 INT HAMBY/JOHN PECTOL	1915	2200022
22-00036 archived	WISSMAN Rd	GEORGETOWN Creek	00.10 S of US 64	1935	2200035
22-00060 archived	BORDEN Rd	Branch of JERSEY PARK Cr	00.10 N of RUFFING Rd	1933	2200054
22-00080 archived	SEVEN MILE Ln	STEWART Creek	00.80 N of HWY 111	1955	2200064
22-00097 unrelinquish ed		FRENCH CREEK	03.69 S SR 62	1940	2200097
22-00098 unrelinquish ed		MIDDLE CREEK	01.25 S SR 62	1940	2200098
22-00099 unrelinquish ed		FALLING RUN	00.37 S SR 62	1945	2200099
22-00100 unrelinquish ed		SLATE RUN CREEK	00.20 S I-265	1972	2200100
22-00503 archived	DAISY Ln	FALLING Run Creek	00.00 INT of ZURSCHMEIDE Dr	1971	2200076
Land Dutate		1.40			

Total Bridges for Category 2: 13

SUMMARY OF STRUCTURE TYPES

NBI 43A Kind of Material and/or Design	NBI 43B Type of Design and/or Construction	Total	
1 - Concrete	01 - Slab	7	
1 - Concrete	11 - Arch - Deck	8	
1 - Concrete	19 - Culvert (includes frame culverts)	9	
1 - Concrete	22 - Channel Beam	1	
2 - Concrete continuous	01 - Slab	12	
2 - Concrete continuous	04 - Tee Beam	1	
3 - Steel	02 - Stringer/Multi-beam or Girder	4	
3 - Steel	10 - Truss - Thru	1	
4 - Steel continuous	02 - Stringer/Multi-beam or Girder	1	
5 - Prestressed concrete	02 - Stringer/Multi-beam or Girder	3	
5 - Prestressed concrete	05 - Box Beam or Girders - Multiple	35	
5 - Prestressed concrete	06 - Box Beam or Girders - Single or Spread	3	
6 - Prestressed concrete continuous	02 - Stringer/Multi-beam or Girder	1	
6 - Prestressed concrete continuous	05 - Box Beam or Girders - Multiple	1	
6 - Prestressed concrete continuous	06 - Box Beam or Girders - Single or Spread	2	
7 - Wood or Timber	01 - Slab	1	

90 Total Structures

LISTING OF BRIDGES WITH INVENTORY ROUTES ON THE NATIONAL HIGHWAY SYSTEM

Bridge				
Number	Facility Carried	Feature Intersected	Location	

Total Bridges On NHS: 0

LISTING OF HISTORICAL STRUCTURES (1) ON NATIONAL REGISTER OF HISTORIC PLACES

(2) ELIGIBLE FOR NATIONAL REGISTER OF HISTORIC PLACES

(3) POSSIBLY ELIGIBLE FOR NATIONAL REGISTER OF HISTORIC PLACES

Brideg No.	Year Built	NBI43A - Kind of Material	NBI43B - Type of Design	Location	Features Intersected
		and/or Design	and/or Construction		

CATEGORY: 1

Total Bridges for Category 1:0

CATEGORY: 2

22-00024	1929	2 - Concrete continuous	01 - Slab	00.60 S of BAKER Rd	RICHLAND CREEK
22-00046	1921	1 - Concrete	11 - Arch - Deck	00.10 W OF SCTTS'VLLE	LITTLE INDIAN CREEK
22-00070	1920	1 - Concrete	11 - Arch - Deck	00.02 N OF HWY 62	SILVER CREEK

Total Bridges for Category 2:3

CATEGORY: 3

Total Bridges for Category 3:1

LISTING OF NAVIGABLE WATERWAYS

Bridge No.	Facility Intersected	Facility Carried	Vertical Clearance (ft)
22-00070	SILVER CREEK	SPRING ST	045.0

SUMMARY OF CHANGES IN 91, 92A, 92B, AND 92C

	Routine		Fractu	Fracture Critical		Underwater		Special	
Bridge Number	91 Old Value	91 New Value	92A Old Value	92A New Value	92B Old Value	92B New Value	92C Old Value	92C New Value	
22-00015	24	48	N	N	N	N	N	N	
22-00017	24	48	N	N	N	N	N	N	
22-00020	24	48	N	N	N	N	N	N	
22-00022	24	48	N	N	N	N	N	N	
22-00029	24	48	N	N	N	N	N	N	
22-00037	24	48	N	N	N	N	N	N	
22-00063	12	12	N	N	Y24	N	N	N	
22-00091	24	48	N	N	N	N	N	N	
22-00096	24	48	N	N	N	N	N	N	
22-00103	24	48	N	N	N	N	N	N	

Total Bridges With Changes: 10

INSPECTION STATUS OF SCOUR CRITICAL BRIDGES

- 90 Bridges currently in FLOYD County's Inventory.
- 90 Bridges over a waterway (Item #42B coded = 5,6,7,8,9 or 0)
- 0 Bridges CLOSED due to scour problems
- 2 Bridges considered SCOUR CRITICAL
- 1 Bridges with designed and working scour counter measures in-place
- 0 Bridges with Unknown foundation types

LIST OF "SCOUR CRITICAL BRIDGES":

Bridge No.	NBI Item #113 Code
22-00041	3 - Foundations unstable for scour conditions
22-00063	3 - Foundations unstable for scour conditions

LIST OF BRIDGES "WITH UNKNOWN FOUNDATION TYPES":

Bridge No.	NBI Item #113 Code	

LOAD CAPACITY STATUS

90 Bridges currently in FLOYD County's Inventory.

Method Used:

36	Field Evaluation and Documented Engineering Judgement	40%
2	Load Factor (LF) Method Used	2.22%
0	Allowable Stress (AS) Method Used	0%
52	Load and Resistance Factor (LRFD) Method Used	57.78%
0	Load Testing Method Used	0%
0	No Rating Analysis Performed	0%
0	Load Factor (LF) Rating Reported by Rating Factor (RF) Method Using MS18 Loading	0%
0	Allowable Stress (AS) Rating Reported By Rating Factor (RF) Method Using MS 18 Loading	0%
0	Load and Resistance Factor Rating (LRFR) Rating Reported By Rating Factor (RF) Method Using HL-93 Loadings	0%
0	Assigned Rating Based On Load Factor Design (LFD) Reported In Metric Tons	0%
0	Assigned Ratings Based On Allowable Stress Design (ASD) Reported In Metric Tons	0%
0	Assigned Ratings Based On Load And Resistance Factor Design (LRFD) Reported In Metric Tons	0%
0	Assigned Rating Based On Load Factor Design (LFD) Reported By Rating Factor Using MS18 Loading	0%
0	Assigned Ratings Based On Allowable Stress Design (ASD) Reported By Rating Factor Using MS18 Loadings	0%
0	Assigned Ratings Based On Load And Resistance Factor Design (LRFD) Reported By Rating Factor Using MS18 Loadings	0%

	Inventory Rating	Operating Rating	H Inventory	HS Inventory	HS Operating
Bridge No.	Method	Method	Rating	Rating	Rating
22-00001	3	3	28	36	48
22-00002	3	3	24	40	55
22-00003	0	0	20	36	36
22-00004	3	3	53	73	89
22-00005	3	3	28	34	55
22-00006	3	3	13	16	35
22-00007	3	3	20	24	43
22-00009 B	0	0	20	36	45
22-00010	3	3	27	49	59
22-00011	3	3	41	48	65
22-00012	3	3	38	45	62
22-00013	3	3	25	33	58
22-00014	3	3	33	43	63
22-00015	3	3	29	45	54
22-00016	3	3	22	29	46
22-00017	3	3	34	43	57
22-00018 B	0	0	20	36	36
22-00019	3	3	30	49	69

06/23/2020

LOAD CAPACITY STATUS

			CAI ACII I STATOS		
Bridge No.	Inventory Rating Method	Operating Rating Method	H Inventory Rating	HS Inventory Rating	HS Operating Rating
22-00020	0	0	20	36	36
22-00021	3	3	51	60	60
22-00022	3	3	22	31	61
22-00023 B	3	3	27	49	53
22-00024	0	0	20	36	36
22-00025	0	0	20	36	36
22-00026	1	1	23	42	71
22-00027	3	3	48	61	66
22-00028	0	0	20	36	36
22-00029	3	3	47	63	94
22-00031	3	3	25	32	43
22-00032	0	0	20	36	36
22-00033	3	3	33	37	52
22-00035	3	3	42	58	63
22-00036 B	3	3	39	48	58
22-00037	3	3	35	53	66
22-00038	0	0	20	36	36
22-00039	0	0	20	36	36
22-00040	3	3	45	64	79
22-00041	3	3	23	31	53
22-00042	3	3	29	49	68
22-00043	0	0	20	36	36
22-00044	0	0	20	36	36
22-00045	3	3	47	54	66
22-00046	0	0	20	36	36
22-00047	3	3	29	39	52
22-00050	3	3	42	65	78
22-00051	0	0	20	36	36
22-00055	3	3	27	46	55
22-00057	0	0	20	36	36
22-00058	3	3	37	55	79
22-00060 B	0	0	20	36	36
22-00061	3	3	41	55	75
22-00062	3	3	52	70	70
22-00063	3	3	53	67	90
22-00064	1	1	19	39	65
22-00065	3	3	35	59	80
22-00066	3	3	35	46	63
22-00060	0	0	20	36	36
22-00070	0	0	20	36	36
	3	3	41	50	69
22-00072	3	3	24	39	52
22-00073					
22-00076	3	3	33	40	56
22-00080 B	0	0	20	36	36
22-00081	3	3	41	51	69

06/23/2020

LOAD CAPACITY STATUS

Bridge No.	Inventory Rating Method	Operating Rating Method	H Inventory Rating	HS Inventory Rating	HS Operating Rating
22-00085	0	0	20	36	36
22-00087	0	0	20	36	36
22-00088	0	0	20	36	36
22-00089	3	3	40	46	57
22-00091	3	3	23	37	58
22-00093	3	3	23	35	59
22-00094	0	0	20	36	36
22-00096	3	3	46	55	76
22-00101	0	0	20	36	36
22-00102	0	0	20	36	36
22-00103	0	0	20	36	36
22-00104	0	0	20	36	36
22-00105	0	0	20	36	45
22-00501	0	0	20	36	36
22-00502	0	0	20	36	36
22-00503 B	0	0	20	36	36
22-00504	0	0	20	36	36
22-00505	3	3	30	47	71
22-00506	0	0	10	22	25
22-00507	3	3	40	56	77
22-00508	3	3	39	50	71
22-00509	3	3	16	19	55
22-00510	0	0	20	36	36
22-00511	3	3	26	46	79
22-00512	3	3	26	47	84
22-00513	0	0	20	36	36
22-00514	0	0	20	36	36

90 Total Structures

Notes:

The values reported are for the H-20 inventory, HS-20 inventory, and HS-20 operating rating values. This report is included as the H and HS trucks have historically been used to set load posting standards and the SIA reports still contain this information. The current load posting requirements utilize a series of new vehicles classified as 'legal', 'routine permit', and 'emergency vehicles'. Bridges are load posted according to the safe posting load associated with these vehicles. The list of load posted bridges can be found on the 'List of Posted Bridges' report.

ROUTINE INSPECTION STATUS

90 Bridges currently in FLOYD County's Inventory.

90 Bridges inspected within Required Re-inspection Timeframe

100%

0 Bridges inspected BEYOND Required Re-inspection Timeframe

0%

Bridge No.	New Inspection Date	Old Inspection Date	Months Between	Required Months Between Inspections	Number of Months Late
22-00001	03/04/2020	03/12/2018	24	24	0
22-00001	03/04/2020	03/12/2018	24	24	0
22-00003	03/04/2020	03/19/2019	12	12	0
22-00004	03/05/2020	03/13/2018	24	24	0
22-00005	03/05/2020	03/13/2018	24	24	0
22-00005	03/05/2020	03/13/2018	24	24	0
22-00007	03/05/2020	03/13/2018	24	24	0
22-00007 22-00009 B	03/04/2020	N/A	N/A	24	N/A
22-00009 B	03/04/2020	03/08/2018	24	24	0
22-00010	03/04/2020	03/12/2018	24	24	0
22-00011	03/04/2020	03/12/2018	24	24	0
22-00012	03/04/2020	03/08/2018	24	24	0
22-00013	03/04/2020	03/08/2018	24	24	0
22-00014	03/05/2020	03/07/2018	24	24	0
22-00015	03/02/2020	03/07/2018	24	24	0
22-00016	03/03/2020	03/07/2018	24	24	0
22-00017 22-00018 B	03/04/2020	03/07/2018	24	24	0
22-00019 22-00020	03/05/2020 03/04/2020	03/07/2018 03/06/2018	24 24	24 24	0
			24	24	0
22-00021 22-00022	03/04/2020 03/04/2020	03/06/2018 03/06/2018	24	24	
					0
22-00023 B	03/04/2020	03/06/2018	24	24	0
22-00024	03/02/2020	03/05/2018	24	24	0
22-00025	03/02/2020	03/05/2018	24	24	0
22-00026	03/02/2020	03/07/2018	24	24	0
22-00027	03/02/2020	03/20/2019	12	12	0
22-00028	03/02/2020	03/05/2018	24	24	0
22-00029	03/04/2020	03/06/2018	24	24	0
22-00031	03/04/2020	03/20/2019	12	12	0
22-00032	03/04/2020	03/08/2018	24	24	0
22-00033	03/03/2020	03/05/2018	24	24	0
22-00035	03/03/2020	03/20/2019	12	12	0
22-00036 B	03/03/2020	03/05/2018	24	24	0
22-00037	03/03/2020	03/05/2018	24	24	0
22-00038	03/03/2020	03/13/2018	24	24	0
22-00039	03/02/2020	03/08/2018	24	24	0
22-00040	03/04/2020	03/08/2018	24	24	0
22-00041	03/02/2020	03/05/2018	24	24	0
22-00042	03/02/2020	03/05/2018	24	24	0
22-00043	03/02/2020	03/05/2018	24	24	0
22-00044	03/02/2020	03/05/2018	24	24	0

06/23/2020

ROUTINE INSPECTION STATUS

				D	N 1 (82 11
Bridge No.	New Inspection Date	Old Inspection Date	Months Between	Required Months Between Inspections	Number of Months Late
22-00045	03/02/2020	03/06/2018	24	24	0
22-00046	03/02/2020	03/12/2018	24	24	0
22-00047	03/04/2020	03/06/2018	24	24	0
22-00050	03/03/2020	03/09/2018	24	24	0
22-00051	03/03/2020	03/20/2019	12	12	0
22-00055	03/04/2020	03/09/2018	24	24	0
22-00057	03/05/2020	03/08/2018	24	24	0
22-00058	03/03/2020	03/07/2018	24	24	0
22-00060 B	03/05/2020	03/08/2018	24	24	0
22-00061	03/03/2020	03/07/2018	24	24	0
22-00062	03/05/2020	03/07/2018	24	24	0
22-00063	03/03/2020	03/26/2019	12	12	0
22-00064	03/03/2020	03/13/2018	24	24	0
22-00065	03/03/2020	03/13/2018	24	24	0
22-00066	03/02/2020	03/05/2018	24	24	0
22-00070	03/04/2020	03/09/2018	24	24	0
22-00071	03/03/2020	03/07/2018	24	24	0
22-00072	03/04/2020	03/06/2018	24	24	0
22-00073	03/02/2020	03/07/2018	24	24	0
22-00076	03/03/2020	03/07/2018	24	24	0
22-00080 B	03/03/2020	03/13/2018	24	24	0
22-00081	03/04/2020	03/06/2018	24	24	0
22-00085	03/02/2020	03/19/2019	12	12	0
22-00087	03/04/2020	03/09/2018	24	24	0
22-00088	03/05/2020	03/08/2018	24	24	0
22-00089	03/05/2020	03/08/2018	24	24	0
22-0009	03/03/2020	03/07/2018	24	24	0
22-00091	03/03/2020	03/07/2018	24	24	0
22-00093	03/03/2020	03/07/2018	24	24	0
					-
22-00096 22-00101	03/03/2020	03/05/2018	24 24	24 24	0
	03/04/2020	03/09/2018			-
22-00102	03/04/2020	03/06/2018	24	24	0
22-00103	03/04/2020	03/09/2018	24	24	0
22-00104	03/04/2020	03/06/2018	24	24	0
22-00105	03/02/2020	N/A	N/A	0.4	N/A
22-00501	03/03/2020	03/06/2018	24	24	0
22-00502	03/03/2020	03/14/2018	24	24	0
22-00503 B	03/03/2020	03/06/2018	24	24	0
22-00504	03/03/2020	03/07/2018	24	24	0
22-00505	03/03/2020	03/07/2018	24	24	0
22-00506	03/03/2020	03/06/2018	24	24	0
22-00507	03/03/2020	03/08/2018	24	24	0
22-00508	03/03/2020	03/06/2018	24	24	0
22-00509	03/03/2020	03/06/2018	24	24	0
22-00510	03/03/2020	03/14/2018	24	24	0
22-00511	03/03/2020	03/06/2018	24	24	0

06/23/2020

ROUTINE INSPECTION STATUS

Bridge No.	New Inspection Date	Old Inspection Date	Months Between	Required Months Between Inspections	Number of Months Late
22-00512	03/03/2020	03/06/2018	24	24	0
22-00513	03/03/2020	03/07/2018	24	24	0
22-00514	03/03/2020	03/05/2018	24	24	0

90 Total Structures

INSPECTION STATUS OF FRACTURE CRITICAL BRIDGE INSPECTION

90 Bridges currently in FLOYD County's Inventory.

1 Bridges coded "YES" in Item 92A (Non-Redundant)

1 Bridges inspected within Required Re-inspection Timeframe

100% **0%**

0 Bridges inspected BEYOND Required Re-inspection Timeframe

Bridge No.	New Inspection Date	Old Inspection Date	Item #92A Coding	Months Between Inspection	Required Months Between Inspections	Number of Months Late	
22-00023 B	03/04/2020	03/06/2018	Y24	24	24	0	

¹ Total Structures

INSPECTION STATUS OF UNDERWATER/IN-WATER INSPECTION

90 Bridges currently in FLOYD County's Inventory.

0 Bridges coded "YES" in Item 92B

0 Bridges inspected within Required Re-inspection Timeframe
 0%
 0 Bridges inspected BEYOND Required Re-inspection Timeframe
 0%

	Months		Required Months			
Bridge No.	New Inspection Date	Old Inspection Date	Item #92B Coding	Between Inspection	Between Inspections	Number of Months Late
2.1490 1101	24.5	Date	- CCug	шоросион	шоросшене	months zato

0 Total Structures

INSPECTION STATUS OF SPECIAL BRIDGE INSPECTION

90 Bridges currently in FLOYD County's Inventory.

0 Bridges coded "YES" in Item 92C

0 Bridges inspected within Required Re-inspection Timeframe 0%
0 Bridges inspected BEYOND Required Re-inspection Timeframe 0%

	New Inspection	Old Inspection	Item #92C	Months Between	Required Months Between	Number of
Bridge No.	Date	Date	Coding	Inspection	Inspections	Months Late

0 Total Structures

WORK PLAN FOR INSPECTIONS AND RE-INSPECTIONS

90	Bridges currently in FLOYD County's Inventory.	
83	Bridges with Biennial Re-Inspection Frequencies of 24 Months	92.22%
7	Bridges with Biennial Re-Inspection Frequencies of Less than 24 Months	7.78%
1	Bridges Require Item #92A Inspections: Non-Redundant Bridges	
1	Bridges with 92A Re-Inspection Frequencies of 24 Months	100%
0	Bridges with 92A Re-Inspection Frequencies of Less than 24 Months	0%
0	Bridges Require Item #92B Inspections: Underwater Inspections	
0	Bridges with 92B Re-Inspection Frequencies of 60 Months	N/A
0	Bridges with 92B Re-Inspection Frequencies of Less than 60 Months	N/A
0	Bridges Require Item #92C Inspections: Special Bridge Detail Inspections	
0	Bridges with 92C Re-Inspection Frequencies of 24 Months	N/A
0	Bridges with 92C Re-Inspection Frequencies of Less than 24 Months	N/A

The County or assigned representitive will monitor all of the bridges that have been recommended to be monitored in this Report by the Consultant.

MASTER LIST - LIST OF BRIDGES REQUIRING IN-DEPTH INSPECTIONS

Bridge No.	Fracture Critical / Non- Redundant Inspection	Underwater Inspection	Special Inspection
22-00023 B	Y24	N	N

Total Bridges Requiring In-Depth Inspection: 1

FOR

FLOYD COUNTY INDIANA

Prepared For:

Board of County Commissioners Floyd County



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



LOOKING NORTH AT ABUTMENT



NBI Number: 2200001 Bridge Number: 22-00001

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: BANNAMON CREEK

				<u>ITIFICATION</u>	<u>IDEN</u>
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200001	NBI Number:	3.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	BANNAMON CREEK	Feat Intersected:	6.
38.39199	Latitude:	16.	SCOTTSVILLE RD	Facility Carried:	7.
-85.910622	Longitude:	17.	00.00 INT OFCHAPEL HILLRD	Location:	9.
				JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	05 (ADJACENT BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	2 (CONCRETE PRECAST)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1969	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	793 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	1168 VPD	Future ADT:	114.
5 mi.	Bypass Detour Length:	19.	6 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
50.1 ft.	Structure Length:	49.	48 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
30.3 ft.	Deck Width (O-O)	52.	29.7 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	24 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	10 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	29.7 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
016					

NBI Number: 2200001 Bridge Number: 22-00001

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: BANNAMON CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - EXCESSIVE WEARING SURFACE				
58.01.	Wearing Surface:	Material:	BITUMINOUS (6")	Rating:	6
	SATIS - NOT FULL WIDTH, LONG AND TRANSVERSE CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - SEEPAGE BETWEEN BEAMS				
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - SPALLS, VERT HAIRLINE CRACKS, TOP OF FOOTING E	XPOSED			
61.	Channel:	Material:	STONE	Rating:	6
	SATIS - MINOR BANK EROSION				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	48	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	28 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200001 Bridge Number: 22-00001

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: BANNAMON CREEK

APPRAISAL

Structural: 6 68. 6 Geometry: 69. Underclearance: Ν Waterway Adequacy:

Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS) 36A.

Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36C. 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

6 - IN CURVE, HILL EACH WAY, INT. NW COR. Roadway Alignment:

Material: BITUMINOUS

LONG. AND TRANS. CRACKS Scour Critical Bridges 5 (STABLE - WITHIN LIMITS)

PROPOSED IMPROVEMENTS

(NO WORK NEEDED.) 75A. Type of Work:

Work Done By:

76. Improvement Length: 0 ft. 94. Bridge Improvement Costs: 0 x 1000 95. Roadway Improvement Costs: 0 x 1000 Total Project Cost: 96. 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, EXTENDING WEARING SURFACE FULL WIDTH, REPAIR DAMAGED BRIDGE AND APPROACH GUARDRAIL IN NW CORNER.

INSPECTION DATA

90. 3/4/2020 91. Des. Inspection Frequency: 24 Months 92. Critical Feature Inspection: Α: Ν 93. B:

Α:

Unofficial Sufficiency Rating: Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



BEAM 6 SPALL



NBI Number: 2200002 Bridge Number: 22-00002

Facility Carried: HANKA Rd Feature(s) Intersected: BANNAMON Creek

Facil	ity Carried: HANKA Rd	Fea	ature(s)	Intersected: BANNAMON C	reek
IDEN	<u>TIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 (
8.	NBI Number:	2200002			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BANNAMON Creek	11.	Mile Point (over):	(
7.	Facility Carried:	HANKA Rd	16.	Latitude:	38.3930
9.	Location:	00.20 E of SCTS'VILE Rd	17.	Longitude:	-85.908287
<u>STRL</u>	ICTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1989	106.	Reconstructed:	(
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	(
29.	ADT - Over:	244 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	359 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	5 mi
GEO!	METRIC DATA				
48.	Maximum Span Length:	27.5 ft.	49.	Structure Length:	30 ft
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft
51.	Bridge Roadway Width:	23.7 ft.	52.	Deck Width (O-O)	24.1 ft
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 fi
47.	Total Horiz. Clearance:	23.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft

55B. Lateral Right:

Lateral Left:

0 ft.

NBI Number: 2200002 Bridge Number: 22-00002

Facility Carried: HANKA Rd Feature(s) Intersected: BANNAMON Creek

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
102. 110. 21.	Direction of Traffic: Des. Nat. Network: Maint. Responsibility:	2 (2-WAY TRAFFIC) 0 02 (COUNTY HIGHWAY AGENCY)	103.	Temporary Structure Des: Toll:	3 (ON FREE ROAD-NO TOLL)

CONDITION

	58.	Deck:	Material:	CONCRETE	Rating:	7
		GOOD - NO MAJOR DEFECTS				
	58.01.	Wearing Surface:	Material:	BITUMINOUS (3")	Rating:	7
		GOOD - NOT A FULL WIDTH, CRACKS AT BRIDGE ENDS				
	59.	Superstructure:	Material:	CONCRETE	Rating:	7
		GOOD - SMALL SPALL AT BEAM 6				
(60.	Substructure:	Material:	CONCRETE	Rating:	7
		GOOD - TOP OF FOOTINGS EXPOSED, FOUNDED ON ROCK				
(61.	Channel:	Material:	NATURAL & RIPRAP	Rating:	6
		SATIS - TREES NEAR BRIDGE, WEIR JUST UPSTREAM, GRAVE	L STREAM	MBED		
(62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
		N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	55	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	40	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	24 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200002 Bridge Number: 22-00002

Facility Carried: HANKA Rd Feature(s) Intersected: BANNAMON Creek

APPRAISAL

Waterway Adequacy:

 67.
 Structural:
 7

 68.
 Geometry:
 4

 69.
 Underclearance:
 N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - TANGENT, CURVE & UPGRADE TO HILL EAST

Material: BITUMINOUS

Comments: LONG. CRACKS, CRACKS AT BRIDGE ENDS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. National Project Cost:
98. Total Project Cost:
99. National Project Cost:
90. K 1000
90. National Project Cost:
90.

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 89.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



NORTH SPAN SPALLS



NBI Number: 2200003 Bridge Number: 22-00003

Facility Carried: CHAPEL HILL Feature(s) Intersected: THOMPSON CREEK

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200003			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	THOMPSON CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	CHAPEL HILL	16.	Latitude:	38.39624
9.	Location:	00.50 N MARY-NAVILE	17.	Longitude:	-85.925125
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	·			
27.	Year Built:	1930	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	1	28B.	Lanes Under Structure:	0
29.	ADT - Over:	244 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	359 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	4 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	15 ft.	49.	Structure Length:	34.2 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	16.1 ft.	52.	Deck Width (O-O)	18.4 ft.
32.	Approach Roadway Width:	14 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	20 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	16.1 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200003 Bridge Number: 22-00003

Facility Carried: CHAPEL HILL Feature(s) Intersected: THOMPSON CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	3 (ONE LANE BRIDGE FOR 2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	4			
	POOR - WIDE VERTICAL CRACKS IN RAILING OVER PIER, SEV SOUTHEAST CORNER	ERE SCAL	LING BOTTOM 1' OF WEST COPING, TOP OF BRIDGE I	RAILING MISSING AT				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	6			
	SATIS - MANY CRACKS, DEBRIS IN GUTTERS							
59.	Superstructure:	Material:	CONT. CONC. SLAB	Rating:	4			
	POOR - LARGE SPALLS WITH EXPOSED REINFORCING, EXTENSIVE EFFLORESCENCE THRU MANY CRACKS IN SLAB							
60.	Substructure:	Material:	CONC. ABUTS/PIERS	Rating:	5			
	FAIR - TOP OF FOOTINGS EXPOSED							
61.	Channel:	Material:	NATURAL/RIPRAP	Rating:	6			
	SATIS - EROSION, SILT BUILDUP IN NORTH SPAN							
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν			
	N/A							

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200003 Bridge Number: 22-00003

Facility Carried: CHAPEL HILL Feature(s) Intersected: THOMPSON CREEK

APPRAISAL

67. Structural: 4
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - CURVE & HILL N., CURVE & LEVEL SOUTH

Material: BITUMINOUS

Comments: NUMEROUS LONGITUDINAL AND TRANSVERSE CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUPERSTRUCTURE.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 56 ft. 94. Bridge Improvement Costs: 232 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 525 x 1000 Year of Cost Estimate: 2020 97

RECOMMENDED MAINTENANCE

UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD APPROACH RAILING WITH END TREATMENT AND NORTHEAST AND SOUTHWEST BRIDGE END MARKERS.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 12 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

74. Bate.

Unofficial Sufficiency Rating: 56.4

Unofficial Structural and Functional Classification: 1 (STRUCTURALLY DEFICIENT)



LOOKING NW FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING SE FROM ROAD



EAST ABUTMENT AND UNDERSIDE EFFL.



NBI Number: 2200004 Bridge Number: 22-00004

Facility Carried: MILLER RD Feature(s) Intersected: MILLER BR OF JERSEY PK B

IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200004			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	MILLER BR OF JERSEY PK B	11.	Mile Point (over):	0
7.	Facility Carried:	MILLER RD	16.	Latitude:	38.40067
9.	Location:	00.20 N of BORDEN RD	17.	Longitude:	-85.970123
<u>STRL</u>	JCTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1972	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	146 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	215 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	42 ft.	49.	Structure Length:	44 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	28.8 ft.	52.	Deck Width (O-O)	30.5 ft.
32.	Approach Roadway Width:	16 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	20 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	28.8 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200004 Bridge Number: 22-00004

Facility Carried: MILLER RD Feature(s) Intersected: MILLER BR OF JERSEY PK B

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	7
	GOOD - SEEPAGE BETWEEN BEAMS			
58.01	Wearing Surface:	Material: BITUMINOUS (1")	Rating:	6
	SATIS - NOT FULL WIDTH, CRACKS			
59.	Superstructure:	Material: CONCRETE	Rating:	6
	SATIS - SEEPAGE BETWEEN BEAMS WITH HVY EFFL. BTW B	MS 4-8		
60.	Substructure:	Material: CONCRETE, FOUNDATION SOLID ROCK	Rating:	7
	GOOD - EAST FOOTING MOSTLY EXPOSED, E ABUTMENT 1	/ERT HL CRK UNDER BM 5		
61.	Channel:	Material: NATURAL ROCK BOTTOM	Rating:	6
	SATIS - LARGE TREES NEAR BRIDGE, FLOW ALONG E ABUT	MENT		
62.	Culvert/Ret:	Material: N/A	Rating:	N
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	89	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	73	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	53 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200004 Bridge Number: 22-00004

Facility Carried: MILLER RD Feature(s) Intersected: MILLER BR OF JERSEY PK B

APPRAISAL

67. Structural: 6
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, HUMP UP TO BRIDGE FROM EAST

Material: BITUMINOUS

Comments: CRACKING EDGE DETERIORATION. TREE LIMBS GROWING OVER GUARD RAIL

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S, PLACING RIPRAP BEHIND WINGS AND AT BRIDGE CORNERS.

INSPECTION DATA

90.Date:3/5/202091.Des. Inspection Frequency:24 Months92.Critical Feature Inspection:A:NB:NC:N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 98.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



SOUTH COPING BEAM CRACK



NBI Number: 2200005 Bridge Number: 22-00005

Facility Carried: ARTHUR COFFMAN RD Feature(s) Intersected: JERSEY PARK CREEK

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200005			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
<u>)</u> .	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
).	Feat Intersected:	JERSEY PARK CREEK	11.	Mile Point (over):	0
· .	Facility Carried:	ARTHUR COFFMAN RD	16.	Latitude:	38.37439
).	Location:	00.10 W OF GREEN'VL/BORDE	17.	Longitude:	-85.965958
<u>STRL</u>	JCTURE DATA	1			
3A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
3B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
07.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
08A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
08C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1992	106.	Reconstructed:	0
2A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
8A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
19.	ADT - Over:	663 VPD	30.	ADT Year Over:	2016
14.	Future ADT:	976 VPD	115.	Future ADT Year:	2036
09.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	2 mi.
<u> </u>	METRIC DATA				
18.	Maximum Span Length:	60.5 ft.	49.	Structure Length:	62.8 ft.
0A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
1.	Bridge Roadway Width:	24 ft.	52.	Deck Width (O-O)	24.3 ft.
2.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
4.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
0.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
		24 ft.	54A.	Min Vert Clear Code:	N
	Total Horiz. Clearance:	2110			
17. 55A.	I otal Horiz. Clearance: Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.

NBI Number: 2200005 Bridge Number: 22-00005

Facility Carried: ARTHUR COFFMAN RD Feature(s) Intersected: JERSEY PARK CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - POPOUTS, HAIRLINE CRACKS, 1/32" CRACK DOWN CL	OF DECK			
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	7
	GOOD - POPOUTS, LIGHT SCALING				
59.	Superstructure:	Material:	CONCRETE	Rating:	5
	FAIR - CRACKS IN BOTTOM OF BOTH COPING BEAMS, SPALL	W/ EXP. R	EIN. IN BOTTOM OF BEAM 4		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - VERTICAL HAIRLINE CRACKS, WABUT VERTHL CRACEFFL., TOP OF FOOTING EXPOSED	CKS UND	ER BM 2 & 4 WITH EFFL., E ABUT VERT HL CRACKS UI	NDER BM 2 & 5 WITH	
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	6
	SATIS - BANK EROSION, FLOW AGAINST NW WING				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	55	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	34	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	28 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200005 Bridge Number: 22-00005

Facility Carried: ARTHUR COFFMAN RD Feature(s) Intersected: JERSEY PARK CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - CURVE BOTH WAYS, DIP & INT. E, HILL W.

Material: BITUMINOUS

Comments: NEW OVERLAY

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. National Project Cost:
98. Total Project Cost:
99. National Project Cost:
90. K 1000
90. National Project Cost:
90.

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S, AND REPAIR NW SHOULDER EROSION.

INSPECTION DATA

 90.
 Date:
 3/5/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 76.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



BEAM 5 AND 6 CRACKS AND DELAM.



NBI Number: 2200006 Bridge Number: 22-00006

Facility Carried: BORDEN RD Feature(s) Intersected: JERSEY PARK CREEK

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200006			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	JERSEY PARK CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BORDEN RD	16.	Latitude:	38.38169
9.	Location:	00.50 N OF JERSEY PARK	17.	Longitude:	-85.966461
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	'			
27.	Year Built:	1980	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	713 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1051 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	5 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	69.5 ft.	49.	Structure Length:	72 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	32.2 ft.	52.	Deck Width (O-O)	32.4 ft.
32.	Approach Roadway Width:	26 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	32.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200006 Bridge Number: 22-00006

Facility Carried: BORDEN RD Feature(s) Intersected: JERSEY PARK CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7	
	GOOD - NO MAJOR DEFECTS					
58.01.	Wearing Surface:	Material:	BITUMINOUS (3")	Rating:	7	
	GOOD - NOT FULL WIDTH					
59.	Superstructure:	Material:	CONCRETE	Rating:	5	
	FAIR - HL CRACKS WITH 2 DELAMS IN BOTTOM OF BEAM 3, SMALL DELAM IN BOTTOM OF BEAM 5 & 6					
60.	Substructure:	Material:	CONCRETE	Rating:	6	
	SATIS - VERT HL CRACKS, S ABUTMENT HAS 3 VERT HL CRACAT ABUTMENT DRAINS WITH LT EFFL., EXPOSED FOOTING FO			3 VERT HL CRACKS		
61.	Channel:	Material:	NATURAL SOLID ROCK BOTTOM	Rating:	7	
	GOOD - FLOW TOWARDS NE CORNER					
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν	
	N/A					

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	35	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	16	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	13 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200006 Bridge Number: 22-00006

Facility Carried: BORDEN RD Feature(s) Intersected: JERSEY PARK CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - BRIDGE ON HUMP IN "S" CURVE

Material: BITUMINOUS
Comments: NEW OVERLAY

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NE & SW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/5/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 71.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



BEAMS 5 & 6 EXPOSED AND BROKEN STRANDS



NBI Number: 2200007 Bridge Number: 22-00007

Facility Carried: SCTSVILLE-NAVILLE. Feature(s) Intersected: LITTLE INDIAN CREEK

<u>IDEN</u>	<u>ITIFICATION</u>		l		
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200007			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SCTSVILLE-NAVILLE.	16.	Latitude:	38.38199
9.	Location:	00.00 INT OF MARY NAVILLE	17.	Longitude:	-85.930023
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE		1		
27.	Year Built:	1977	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	468 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	690 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	3 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	62.5 ft.	49.	Structure Length:	65.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	32.2 ft.	52.	Deck Width (O-O)	32.4 ft.
32.	Approach Roadway Width:	20 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	28 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	32.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200007 Bridge Number: 22-00007

Facility Carried: SCTSVILLE-NAVILLE. Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	08 (RURAL - MINOR COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
2 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.
		l			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	5
	FAIR - SEEPAGE BETWEEN BEAMS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (5")	Rating:	7
	GOOD - EXCESSIVE WEARING SURFACE				
59.	Superstructure:	Material:	CONCRETE	Rating:	5
	FAIR - BM 2 1/16" CRACK LONG. DOWN MIDDLE, BTM 20" LONG STRANDS 1 BROKEN	FROM W	ABUTMENT, 24" SPALL 1 EXP. STRAND RUSTED, BM	6 48" SPALL 2 EXP.	
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - HAIRLINE VERTICAL CRACKS, E ABUTMENT 3 VERT HI CRACKS WITH LT. EFFL. UNDER BMS 2-8	L CRACKS	WITH LT. EFFL. UNDER BMS 2,4, AND 6, W ABUTMEN	JT 7 VERT HL	
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	6
	SATIS - FLOW ALONG E ABUTMENT				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

3 (LOAD RESISTANCE FACTOR (LRFR))	Oper Rating Method:	NKNOWN) 63.	ad: 0 (UNKNOWN)	31. Design Load:	31.
3 (LOAD AND RESISTANCE FACTOR (LRFR))	Inv Rating Method:	43 65.	Rating: 43	64. Operating Rating:	64.
Tons	Tons Posted:	24 66C.	Rating: 24	66. Inventory Rating:	66.
	Date Posted/Closed:	20 Tons 66D.	s or H Rating: 20 Tons	66B. Gross Tons or H Rating:	66B.
5 (EQUAL TO OR ABOVE LEGAL LOADS)	Bridge Posting:	A (OPEN) 70.	ted, or Closed: A (OPEN)	41. Open, Posted, or Closed:	41.

NBI Number: 2200007 Bridge Number: 22-00007

Facility Carried: SCTSVILLE-NAVILLE. Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, UPGRADE TO EAST, INT. E. END

Material: BITUMINOUS

Comments: NUMEROUS LONG, AND TRANS. CRACKS, SOME SEALED

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: 35 (REHABILITATE BRIDGE DUE TO SUPERSTRUCTURE DETERIORATION.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 66 ft. 94. Bridge Improvement Costs: 170 x 1000 95. Roadway Improvement Costs: 184 x 1000 Total Project Cost: 96. 429 x 1000 97. Year of Cost Estimate: 2020

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

INSPECTION DATA

90. Date: 3/5/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N
93. Date: A: B: C:

Unofficial Sufficiency Rating: 76.6
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



LOOKING WEST DOWNSTREAM



NBI Number: 2200112 Bridge Number: 22-00009 B

Facility Carried: ATKINS ROAD Feature(s) Intersected: BRANCH of BIG INDIAN CR.

IDEN	ITIFICATION	1			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200112			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BRANCH of BIG INDIAN CR.	11.	Mile Point (over):	0
7.	Facility Carried:	ATKINS ROAD	16.	Latitude:	38.39563
9.	Location:	00.10 S of RENN ROAD	17.	Longitude:	-85.84545
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	0 (NONE)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2019	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	244 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	359 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	3 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	22.5 ft.	49.	Structure Length:	25 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	22.6 ft.	52.	Deck Width (O-O)	22.6 ft.
32.	Approach Roadway Width:	19 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	22.6 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200112 Bridge Number: 22-00009 B

Facility Carried: ATKINS ROAD Feature(s) Intersected: BRANCH of BIG INDIAN CR.

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.
		1			

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	RIPRAP AND NATURAL	Rating:	7
	GOOD - CHANNEL DEEPENS THROUGH STRUCTURE				
62.	Culvert/Ret:	Material:	CONCRETE ABUTMENTS	Rating:	8
	VERY GOOD - WATER SEEPAGE BETWEEN PRECAST UNITS				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	45	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200112 Bridge Number: 22-00009 B

Facility Carried: ATKINS ROAD Feature(s) Intersected: BRANCH of BIG INDIAN CR.

APPRAISAL

67. Structural: 8
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - TANGENT, CURVE AND MODERATE UPGRADE TO SOUTH

Material: BITUMINOUS

Comments: NEW BITUMINOUS, STONE SHOULDERS

113. Scour Critical Bridges: 7 (FIXED - NOT SCOUR CRITICAL)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NEW CONSPAN CULVERT)

75B. Work Done By: 1 (CONTRACT)
76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO NEW RECOMMENDATIONS

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 90.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



LOOKING EAST AT CENTER SPAN AND PIER #3



NBI Number: 2200009 Bridge Number: 22-00010

Facility Carried: BALMER-FENWICK Rd Feature(s) Intersected: BIG INDIAN Creek

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200009			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN Creek	11.	Mile Point (over):	0
7.	Facility Carried:	BALMER-FENWICK Rd	16.	Latitude:	38.39687
9.	Location:	00.10 W of ATKINS Rd	17.	Longitude:	-85.847321
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1981	106.	Reconstructed:	2017
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	380 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	559 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	3 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	24 ft.	49.	Structure Length:	62 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	30 ft.	52.	Deck Width (O-O)	32.5 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	30 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	30 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200009 Bridge Number: 22-00010

Facility Carried: BALMER-FENWICK Rd Feature(s) Intersected: BIG INDIAN Creek

|--|

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE SLAB	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
58.01	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	7
	GOOD - NO MAJOR DEFECTS, SURFACE WORN, POPOUTS				
59.	Superstructure:	Material:	CONCRETE SLAB	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - EROSION AROUND NORTHEAST WING, FLOW ALONG OF EAST BENT(ON S. SIDE) VERTICAL HAIRLINE CRACKS IN			PALL AND BEARING	
61.	Channel:	Material:	NATURAL & RIPRAP	Rating:	5
	FAIR - LOCAL SCOUR AREAS, GRANULAR STREAM BED, BRU	JSHY STRE	EAM BANKS, GRAVEL BUILD-UP IN CENTER AND WES	T SPANS	
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	59	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	49	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	27 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200009 Bridge Number: 22-00010

Facility Carried: BALMER-FENWICK Rd Feature(s) Intersected: BIG INDIAN Creek

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 6

 69.
 Underclearance:
 N

 71.
 Waterway Adequacy:
 6

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT & LEVEL NEAR BRIDGE, DIP W, INT. & HILL TO E

Material: BITUMINOUS

Comments: LONG, AND TRANS. CRACKS, SHOULDERS SETTLING AT BRIDGE CORNERS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments: LOCAL SCOUR HOLE WEST SPAN, SCOUR ALONG WEST SIDE OF EAST PIER BUT FOOTING

NOT VISIBLE, MINOR DRIFT LODGED ON EAST PIER

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S, AND PLACING RIPRAP ALONG EAST PIER.

INSPECTION DATA

90. Date: 3/4/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C

Unofficial Sufficiency Rating: 98.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING EAST FROM ROAD



LOOKING SOUTH THROUGH CHANNEL



WEST SPAN SILT BUILDUP



NBI Number: 2200010 Bridge Number: 22-00011

Facility Carried: BETHEL-FREIBERGER Feature(s) Intersected: BIG INDIAN Creek

<u>IDEN</u>	TIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200010			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN Creek	11.	Mile Point (over):	0
7.	Facility Carried:	BETHEL-FREIBERGER	16.	Latitude:	38.37768
9.	Location:	00.60 E of StARLIGHT Rd	17.	Longitude:	-85.887657
<u>STRU</u>	ICTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
	05.050,405	l			
<u>AGE</u> 27.	OF SERVICE Year Built:	1997	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	421 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	620 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	4 mi.
GFOI	METRIC DATA				
48.	Maximum Span Length:	49 ft.	49.	Structure Length:	92.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	28 ft.	52.	Deck Width (O-O)	28.1 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	28 ft.	54A.	Min Vert Clear Code:	N
	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55A.					

NBI Number: 2200010 Bridge Number: 22-00011

Facility Carried: BETHEL-FREIBERGER Feature(s) Intersected: BIG INDIAN Creek

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8
	VERY GOOD - FEW POPOUTS, SPALL AT WEST BRIDGE END J	JOINT			
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	8
	VERY GOOD - FEW POPOUTS				
59.	Superstructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - CONCRETE SPALL ABOVE EAST PIER ON UPST	REAM EN	D		
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - HAIRLINE CRACKS, 3 VERT. 1/32" CRACKS IN W	'EST ABU	TMENT, 1 VERT. 1/32" CRACK IN EAST ABUTMENT		
61.	Channel:	Material:	RIPRAP / NATURAL	Rating:	7
	GOOD - MODERATE GRAVEL DEPOSITS, IN THE WEST SPAN				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	65	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	48	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	41 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200010 Bridge Number: 22-00011

Facility Carried: BETHEL-FREIBERGER Feature(s) Intersected: BIG INDIAN Creek

APPRAISAL

67. Structural: 8
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - BRIDGE ON HUMP, CURVES BOTH WAYS

Material: BITUMINOUS

Comments: NEW OVERLAY

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NW & SE B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 98.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



EAST ABUTMENT



NBI Number: 2200011 Bridge Number: 22-00012

Facility Carried: BANET Rd Feature(s) Intersected: Little INDIAN Creek

	-/		0.000(0)		
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200011			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	Little INDIAN Creek	11.	Mile Point (over):	0
7.	Facility Carried:	BANET Rd	16.	Latitude:	38.38578
9.	Location:	00.80 E of StARLIGHT Rd	17.	Longitude:	-85.883583
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1979	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	567 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	836 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	38 ft.	49.	Structure Length:	41 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	31.8 ft.	52.	Deck Width (O-O)	32 ft.
32.	Approach Roadway Width:	27 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	35 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	31.8 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200011 Bridge Number: 22-00012

Facility Carried: BANET Rd Feature(s) Intersected: Little INDIAN Creek

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	08 (RURAL - MINOR COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.
		11			

CONDITION

58.	Deck:	Material: Concrete	Rating:	7
	GOOD - NEW CONC. OVERLAY			
58.01.	Wearing Surface:	Material: INTEGRAL CONCRETE	Rating:	7
	GOOD - NEW CONC. OVERLAY			
59.	Superstructure:	Material: CONCRETE	Rating:	7
	GOOD - NO MAJOR DEFECTS			
60.	Substructure:	Material: CONCRETE	Rating:	7
	GOOD - VERTICAL HL CRACKS AT ABUTMENT DRAINS, LIGHT	SCALING, TOPS OF FOOTINGS VISIBLE		
61.	Channel:	Material: NATURAL ROCK BOTTOM	Rating:	6
	SATIS - EAST BANK EROSION, TREES UNDERCUT AT NW CO	RNER, HVY BANK EROSION DOWNSTREAM AT SE		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	62	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	45	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	38 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200011 Bridge Number: 22-00012

Facility Carried: BANET Rd Feature(s) Intersected: Little INDIAN Creek

APPRAISAL

67. Structural: 7
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - UPGRADE TO HILL & CURVE E, CURVE W.

Material: BITUMINOUS
Comments: NEW OVERLAY

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 99.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



EAST ABUTMENT



NBI Number: 2200012 Bridge Number: 22-00013

Facility Carried: BANET RD Feature(s) Intersected: BIG INDIAN CREEK

	,				
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200012			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BANET RD	16.	Latitude:	38.38528
9.	Location:	01.50 E STARLIGHT RD	17.	Longitude:	-85.873817
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1965	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	283 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	417 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	4 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	45.5 ft.	49.	Structure Length:	48 ft.
50A.	Sidewalk/Curb Left:	0.9 ft.	50B.	Sidewalk/Curb Right:	0.9 ft.
51.	Bridge Roadway Width:	22.5 ft.	52.	Deck Width (O-O)	24.2 ft.
32.	Approach Roadway Width:	20 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200012 Bridge Number: 22-00013

Facility Carried: BANET RD Feature(s) Intersected: BIG INDIAN CREEK

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40. Navigational Horizontal Clearance: 0) ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE BOX BEAM	Rating:	6
	SATIS - COPING SPALLS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (8")	Rating:	5
	FAIR - CRACKS, EXCESSIVE OVERLAY, NOT FULL WIDTH				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - LEAKS BETWEEN BEAMS, THIRD BEAM FROM NORTH	HAS 2' LC	NG HAIRLINE CRACK 10' FROM WEST ABUTMENT		
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - HAIRLINE VERTICAL CRACKS, E ABUTMENT TOP FTG.	EXP.			
61.	Channel:	Material:	NATURAL/ROCK	Rating:	6
	SATIS - BANK EROSION, FLOW TOWARDS E. ABUTMENT				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31. D	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64. C	Operating Rating:	58	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66. Ir	Inventory Rating:	33	66C.	Tons Posted:	Tons
66B. G	Gross Tons or H Rating:	25 Tons	66D.	Date Posted/Closed:	
41. C	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200012 Bridge Number: 22-00013

Facility Carried: BANET RD Feature(s) Intersected: BIG INDIAN CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - TANGENT, BRIDGE ON HUMP, INT. NW COR.

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS, PATCHES

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)
75B. Work Done By: ()
76. Improvement Length: 0 ft.

94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. 0 x 1000
98. 0 x 1000
99. 0 x 100

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 81.6
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



DOWNSTREAM BEAM CRACKS AND EFFL.



NBI Number: 2200013 Bridge Number: 22-00014

Facility Carried: NAVILLETON Rd Feature(s) Intersected: Little INDIAN Creek

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200013			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	Little INDIAN Creek	11.	Mile Point (over):	0
7.	Facility Carried:	NAVILLETON Rd	16.	Latitude:	38.37074
9.	Location:	00.30 S of REASOR Rd	17.	Longitude:	-85.93856
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	·			
27.	Year Built:	1974	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1230 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1812 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	4 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	47.5 ft.	49.	Structure Length:	50 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	30.9 ft.	52.	Deck Width (O-O)	32.2 ft.
32.	Approach Roadway Width:	26 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	31.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200013 Bridge Number: 22-00014

Facility Carried: NAVILLETON Rd Feature(s) Intersected: Little INDIAN Creek

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE BOX BEAM	Rating:	6
	SATIS - DEBRIS IN GUTTERS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (8")	Rating:	7
	GOOD - EXCESSIVE OVERLAY				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - LONG. HAIRLINE CRACKS IN BEAM SIDES, SEEPAGE B	BTW BEAN	IS		
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - VERTICAL HAIRLINE CRACKS				
61.	Channel:	Material:	RIPRAP AND NATURAL	Rating:	6
	SATIS - TREES & DENSE VEG. NEAR BRIDGE				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	63	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	43	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	33 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
71.	open, i osteu, di Gioseu.	A (OPEN)	70.	bridge i ostilig.	5 (LQUAL TO OR ABOVE LEGAL LOF

NBI Number: 2200013 Bridge Number: 22-00014

Facility Carried: NAVILLETON Rd Feature(s) Intersected: Little INDIAN Creek

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - HILL BOTH WAYS, SHARP CURVE S. END BR.

Material: BITUMINOUS
Comments: NEW OVERLAY

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S, AND REPAIR SE CORNER GUARDRAIL.

INSPECTION DATA

90.Date:3/5/202091.Des. Inspection Frequency:24 Months92.Critical Feature Inspection:A:NB:NC:N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 93.1
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



SOUTH SPAN WEST COPING SPALLS



NBI Number: 2200014 Bridge Number: 22-00015

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

				<u>ITIFICATION</u>	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200014	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	RICHLAND CREEK	Feat Intersected:	6.
38.36191	Latitude:	16.	G'TOWN-GREENVILLE	Facility Carried:	7.
-86.001778	Longitude:	17.	01.00 S of US 150	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	2 (CONTINUOUS CONCRETE)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			8 (UNKNOWN)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1981	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	1262 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	1860 VPD	Future ADT:	114.
5 mi.	Bypass Detour Length:	19.	6 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
99 ft.	Structure Length:	49.	39 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
34.5 ft.	Deck Width (O-O)	52.	32 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	26 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	5 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	32 ft.	Total Horiz. Clearance:	47.
		54B.	N	Min Latr. Cl. Right - Code:	55A.
0 ft.	Underclearance:	54B.	14	Will Latt. Cl. Night - Code.	33A.

NBI Number: 2200014 Bridge Number: 22-00015

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - CRKS & DELAMS BOTTOM WEST EDGE				
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	7
	GOOD - MANY POPOUTS				
59.	Superstructure:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - LONG. CRACKS ALONG UPSTREAM COPING, SPALL W	// EXP. RE	IN. AT UPSTREAM COPING SOUTH SPAN		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - VERTICAL HAIRLINE CRACKS IN WINGS				
61.	Channel:	Material:	NATURAL/ ROCK	Rating:	7
	GOOD - TREES ON BANKS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	54	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	45	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	29 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200014 Bridge Number: 22-00015

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - CURVE & HILL BOTH WAYS, BRIDGE ON HUMP

Material: RCBA

Comments: SOME POPOUTS, LIGHT WEAR
Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S, AND PATCHING SPALLS IN BOTTOM OF SUPERSTRUCTURE.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 95.5
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



TYPICAL HAIRLINE CRACKS AT BEAM ENDS



NBI Number: 2200015 Bridge Number: 22-00016

Facility Carried: STILLER Rd Feature(s) Intersected: BIG INDIAN Creek

				<u>ITIFICATION</u>	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200015	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	BIG INDIAN Creek	Feat Intersected:	6.
38.35683	Latitude:	16.	STILLER Rd	Facility Carried:	7.
-85.91954	Longitude:	17.	00.80 N of US 150	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
2	Number of Spans - Main:	45.	05 (ADJACENT BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	2 (CONCRETE PRECAST)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1966	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	244 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	359 VPD	Future ADT:	114.
3 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	GEO!
96 ft.	Structure Length:	49.	47.3 ft.	Maximum Span Length:	48.
1.0 ft.	Sidewalk/Curb Right:	50B.	1.0 ft.	Sidewalk/Curb Left:	50A.
27.2 ft.	Deck Width (O-O)	52.	25.2 ft.	Bridge Roadway Width:	51.
0 (110 14501111)	Bridge Median:	33.	25 ft.	Approach Roadway Width:	32.
0 (NO MEDIAN)		35.	0 Degree(s)	Skew:	34.
0 (NO MEDIAN) 0 (NO FLARE)	Structure Flared:				
	Structure Flared: Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
0 (NO FLARE)		53. 54A.	99.99 26.7 ft.	Defense Vertical Clearance: Total Horiz. Clearance:	10. 47.
0 (NO FLARE) 99.99 ft.	Vertical Clearance/Deck:				

NBI Number: 2200015 Bridge Number: 22-00016

Facility Carried: STILLER Rd Feature(s) Intersected: BIG INDIAN Creek

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE BOX BEAMS	Rating:	6
	SATIS - DEBRIS IN GUTTERS, RAILING DAMAGE				
58.01.	Wearing Surface:	Material:	BITUMINOUS (5")	Rating:	5
	FAIR - CRACKS, PATCHES, LARGE POTHHOLES				
59.	Superstructure:	Material:	CONCRETE BOX BEAMS	Rating:	6
	SATIS - HAIRLINE CRACKS BOTTOM OF BEAM ENDS, SEEPAG	E BETWEI	EN BEAMS		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - TOP OF FOOTINGS EXPOSED, FOUNDED ON ROCK				
61.	Channel:	Material:	NATURAL ROCK & GRAVEL BOTTOM	Rating:	6
	SATIS - STEEP BANKS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/Δ				

31.	Design Load:	4 (H 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	46	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	29	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	22 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200015 Bridge Number: 22-00016

Facility Carried: STILLER Rd Feature(s) Intersected: BIG INDIAN Creek

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - NEARLY LEVEL, CURVE EACH WAY

Material: BITUMINOUS

Comments: LONG. CRACKS, CRACKS AT BRIDGE ENDS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)
75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL W/END TREATMENT AND ALL B.E.M.'S, REMOVING DEBRIS FROM, DECK, WIDENING OVERLAY TO CURBS, REPAIRING NE GUARDRAIL, AND PATCHING DECK.

INSPECTION DATA

90. Date: 3/5/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 87.5
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



EAST ABUTMENT



NBI Number: 2200016 Bridge Number: 22-00017

Facility Carried: FEATHERINGILL Rd Feature(s) Intersected: Branch Little INDIAN Cr

				NTIFICATION	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200016	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	Branch Little INDIAN Cr	Feat Intersected:	6.
38.35476	Latitude:	16.	FEATHERINGILL Rd	Facility Carried:	7.
-85.967705	Longitude:	17.	01.00 E of BUTTN'TWN Rd	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	2 (CONTINUOUS CONCRETE)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			8 (UNKNOWN)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1988	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	468 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	690 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
132 ft.	Structure Length:	49.	51 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
29 ft.	Deck Width (O-O)	52.	26 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	21 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	25 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	26 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200016 Bridge Number: 22-00017

Facility Carried: FEATHERINGILL Rd Feature(s) Intersected: Branch Little INDIAN Cr

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112. N	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104. H	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26. F	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100. E	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102. E	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110. E	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21. N	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37. H	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - CRACKS, LEACHING, DELAMINATION, SPALLS, EXPOS	ED REINF	FORCING AROUND DRAINS		
58.01.	Wearing Surface:	Material:	MONOLITHIC CONCRETE	Rating:	7
	GOOD - POPOUTS				
59.	Superstructure:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - CRACKS, LEACHING, DELAMINATION, SPALL, AND EXP	POSED RE	EINFORCING AROUND DRAINS		
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - SPALL ON EAST PIER, LOCAL PIER SCOUR				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	6
	SATIS - SILT, DENSE VEGETATION, HIGH BANKS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	57	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	43	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	34 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200016 Bridge Number: 22-00017

Facility Carried: FEATHERINGILL Rd Feature(s) Intersected: Branch Little INDIAN Cr

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - BRIDGE ON SLIGHT HUMP, CURVE EACH END

Material: RCBA

Comments: MINOR WEAR

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND PATCHING AROUND THE UNDERSIDE DRAINS.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 93.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



TYPICAL HAIRLINE CRACKS



NBI Number: 2200106 Bridge Number: 22-00018 B
Facility Carried: BUCK CREEK RD Feature(s) Intersected: BUCK CREEK

IDEN	ITIFICATION	1			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200106			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BUCK CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BUCK CREEK RD	16.	Latitude:	38.34572
9.	Location:	00.30 N of US 150	17.	Longitude:	-85.910805
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2012	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	617 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	617 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	22 ft.	49.	Structure Length:	23 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27.2 ft.	52.	Deck Width (O-O)	30 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	30 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	27.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200106 Bridge Number: 22-00018 B
Facility Carried: BUCK CREEK RD Feature(s) Intersected: BUCK CREEK

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (5")	Rating:	8
	VERY GOOD - ROUGH AT BRIDGE ENDS				
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	NATURAL ROCK BOTTOM, RIPRAP	Rating:	8
	VERY GOOD - RIPRAP WASHED INTO CHANNEL				
62.	Culvert/Ret:	Material:	CONCRETE, 3 SIDED STR.	Rating:	7
	GOOD - 3 HL CRACKS AT CENTER TYP. FULL LENGTH, SEEPA	GE BTN JO	OINTS, SMALL SPALL		

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200106 Bridge Number: 22-00018 B
Facility Carried: BUCK CREEK RD Feature(s) Intersected: BUCK CREEK

APPRAISAL

67.	Structural:	7
68.	Geometry:	5
69.	Underclearance:	Ν
71.	Waterway Adequacy:	4

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - STRAIGHT, DRIVES BOTH SIDES

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKING

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A.	Type of Work:	(NO WORK NEEDED.	
75B.	Work Done By:	()	
76.	Improvement Length:	O ft.	
94.	Bridge Improvement Costs:	0 x 1000	
95.	Roadway Improvement Costs:	0 x 1000	
96.	Total Project Cost:	0 x 1000	
97.	Year of Cost Estimate:		

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NE, NW & SW B.E.M.'S.

INSPECTION DATA

90.	Date:	3/4/2020	91.	Des. Inspection Frequency:		iency:	24 Months	
92.	Critical Feature Inspection:		A:	Ν	B:	Ν	C:	Ν
93.	Date:		A:		B:		C:	

Unofficial Sufficiency Rating: 95.3
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



NORTH PIER BEAM END CRACKS



NBI Number: 2200018 Bridge Number: 22-00019

Facility Carried: NAVILLETON Rd Feature(s) Intersected: BIG INDIAN Creek

<u>IDEN</u>	<u>ITIFICATION</u>		1		
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200018			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN Creek	11.	Mile Point (over):	0
7.	Facility Carried:	NAVILLETON Rd	16.	Latitude:	38.35993
9.	Location:	00.70 N of US 150	17.	Longitude:	-85.932968
			ı		
	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1967	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1553 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	2288 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA		1		
48.	Maximum Span Length:	53.8 ft.	49.	Structure Length:	112 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	30.8 ft.	52.	Deck Width (O-O)	32.8 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	30.8 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200018 Bridge Number: 22-00019

Facility Carried: NAVILLETON Rd Feature(s) Intersected: BIG INDIAN Creek

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE BOX BEAMS	Rating:	5
	FAIR - BEAM SPALL, BEAMS CRACKED AND EFFL.			
58.01.	Wearing Surface:	Material: BITUMINOUS (5")	Rating:	6
	SATIS - EXCESSIVE WEARING SURFACE, CRACKS AT PIERS			
59.	Superstructure:	Material: CONCRETE BOX BEAMS	Rating:	5
	FAIR - HAIRLINE CRACKS NEAR BEAM ENDS, SEEPAGE TYP.	ALONG EXT. BEAMS		
60.	Substructure:	Material: CONCRETE	Rating:	5
	FAIR - NORTH PIER FOOTING EXPOSED, SOUTH PIER UPSTR	EAM PILE FLAKING, PIER CAP CRACKS AND SPALLS, JOI	NTS ABOVE PIERS LE	AKING
61.	Channel:	Material: RIPRAP / NATURAL	Rating:	6
	SATIS - DISPLACED RIPRAP N SPILLSLOPE			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	69	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	49	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	30 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200018 Bridge Number: 22-00019

Facility Carried: NAVILLETON Rd Feature(s) Intersected: BIG INDIAN Creek

APPRAISAL

Waterway Adequacy:

67. Structural:568. Geometry:569. Underclearance:N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - UPGRADE TO HILL S., CURVE N. END BR.

Material: BITUMINOUS

Comments: NEW OVERLAY

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, REPAIR APPROACH GUARDRAIL

INSPECTION DATA

 90.
 Date:
 3/5/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 82.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



WEST ABUTMENT VERTICAL CRACKS



NBI Number: 2200019 Bridge Number: 22-00020
Facility Carried: OLD VINCENNES RD Feature(s) Intersected: YELLOW FORK

		3 (0)		, -	
			1	ITIFICATION	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200019	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	YELLOW FORK	Feat Intersected:	6.
38.33613	Latitude:	16.	OLD VINCENNES RD	Facility Carried:	7.
-85.933746	Longitude:	17.	00.00 INT EDWRDS'VL/GALENA	Location:	9.
				JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	06 (SPREAD BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	2001	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	617 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	908 VPD	Future ADT:	114.
6 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEOI</u>
60.7 ft.	Structure Length:	49.	54.7 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
32 ft.	Deck Width (O-O)	52.	29 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	28 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	20 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	29 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
		56.	0 ft.	Lateral Right:	

NBI Number: 2200019 Bridge Number: 22-00020
Facility Carried: OLD VINCENNES RD Feature(s) Intersected: YELLOW FORK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	07 (RURAL - MAJOR COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
58.01.	Wearing Surface:	Material:	Concrete	Rating:	8
	VERY GOOD - DEBRIS ALONG EDGES				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - HORIZONTAL HAIRLINE CRACK ON SIDE OF BEAM 3, 1	' GROUTE	ED HAIRLINE CRACKS ON BEAMS 2 AND 4, 1' HAIRLIN	E CRACKS BEAM 5	
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - VERTICAL HAIRLINE CRACKS				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	7
	GOOD - VERY BRUSHY AROUND BRIDGE, FLOWS TO NE & SW	1			
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200019 Bridge Number: 22-00020 Facility Carried: OLD VINCENNES RD Feature(s) Intersected: YELLOW FORK

APPRAISAL

67.	Structural:	7
68.	Geometry:	5
69.	Underclearance:	Ν
71.	Waterway Adequacy:	8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 8 - TANGENT, HILL & INTERSECTION EAST

Material: CONCRETE / BITUMINOUS

Comments: BUMP AT BRIDGE ENDS, LONG, CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A.	Type of Work:	(NO WORK	NEEDED.)
75B.	Work Done By:	()	
76.	Improvement Length:		0 ft.
94	Bridge Improvement Costs:		0 × 1000

95. Roadway Improvement Costs: 0 x 1000

96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE NEEDED.

INSPECTION DATA

90.	Date:	3/4/2020	91.	Des. Inspectio	n Frequ	ency:	48 Moi	nths
92.	Critical Feature Inspec	ction:	A:	N	B:	N	C:	Ν
93.	Date:		A:		B:		C:	

Unofficial Sufficiency Rating: 98.7
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING NORTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



EAST ABUTMENT SCOUR



NBI Number: 2200020 Bridge Number: 22-00021

Facility Carried: JOHN PECTOL Rd Feature(s) Intersected: Little INDIAN Creek

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200020			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	Little INDIAN Creek	11.	Mile Point (over):	0
7.	Facility Carried:	JOHN PECTOL Rd	16.	Latitude:	38.33887
9.	Location:	00.20 S of Old VINCENNES Rd	17.	Longitude:	-85.943932
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	3 (STEEL)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	02 (GIRDER)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	·			
27.	Year Built:	1930	106.	Reconstructed:	2008
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	567 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	836 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	6 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	71.7 ft.	49.	Structure Length:	73.3 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27.7 ft.	52.	Deck Width (O-O)	28 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24.4 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200020 Bridge Number: 22-00021

Facility Carried: JOHN PECTOL Rd Feature(s) Intersected: Little INDIAN Creek

|--|

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	8
	VERY GOOD - DIP AT BRIDGE JOINTS			
58.01.	Wearing Surface:	Material: INTEGRAL CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
59.	Superstructure:	Material: STEEL	Rating:	7
	GOOD - FLAKING AT BEARINGS			
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - HAIRLINE CRACKS, LEACHING, EAST TOP OF FOOTING	G EXPOSED		
61.	Channel:	Material: NATURAL / ROCK	Rating:	6
	SATIS - FLOW DIRECTED TOWARD NE CORNER			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	60	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	60	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	51 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200020 Bridge Number: 22-00021

Facility Carried: JOHN PECTOL Rd Feature(s) Intersected: Little INDIAN Creek

APPRAISAL

67. Structural: 668. Geometry: 5

69. Underclearance: N

71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)

36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - LEVEL, CURVE EACH WAY

Material: BITUMINOUS

Comments: SETTLED AT BRIDGE ENDS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, AND REPLACING APPROACHES.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 2/26/2008
 B:
 C:

Unofficial Sufficiency Rating: 95.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



LOOKING SOUTH AT SOUTH PIER



NBI Number: 2200021 Bridge Number: 22-00022

Facility Carried: HAMBY Rd Feature(s) Intersected: BIG INDIAN Creek

<u>IDEN</u>	NTIFICATION		1		
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200021			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN Creek	11.	Mile Point (over):	0

7. Facility Carried: HAMBY Rd 16. Latitude: 38.33012

 9.
 Location:
 00.50 S of BUTTONTWN Rd
 17.
 Longitude:
 -85.987427

STRUCTURE DATA

43A.	Structure Type - Main Span:	6 (CONT PRESTR CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Cons	t. 02 (GIRDER)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (FPOXY COATED REINFORCING)			

AGE OF SERVICE

0	Reconstructed:	106.	1996	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	444 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	654 VPD	Future ADT:	114.
5 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.

GEOMETRIC DATA

48.	Maximum Span Length:	46 ft.	49.	Structure Length:	140 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	26 ft.	52.	Deck Width (O-O)	29 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	35 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	26 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	Oft.

NBI Number: 2200021 Bridge Number: 22-00022

Facility Carried: HAMBY Rd Feature(s) Intersected: BIG INDIAN Creek

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112. N	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104. H	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26. F	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100. E	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102. E	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110. E	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21. N	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37. H	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8
	VERY GOOD - SAND & DEBRIS IN GUTTERS				
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	7
	GOOD - POPOUTS, HAIRLINE CRACKS				
59.	Superstructure:	Material:	CONCRETE I-BEAM	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
61.	Channel:	Material:	RIPRAP	Rating:	6
	SATIS - VERY BRUSHY AROUND BRIDGE				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	61	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	31	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	22 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200021 Bridge Number: 22-00022

Facility Carried: HAMBY Rd Feature(s) Intersected: BIG INDIAN Creek

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - BRIDGE ON LONG HUMP, CURVE BOTH WAYS

Material: CONCRETE / BITUMINOUS

Comments: CONC SLAB SETTLED, BIT. HIGHER

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. ALL B.E.M.'S, AND CLEANING DECK.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 90.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



LOOKING WEST AT ABUTMENT



NBI Number: 2200108 Bridge Number: 22-00023 B

Facility Carried: JOHN PECTOL RD Feature(s) Intersected: BIG INDIAN CREEK

raci	inty Carried: JOHN PECTO	L KD Fe	ature(s)	Intersected: BIG INDIAN C	KEEK
<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200108			
5.	Inventory Route On:	1-4-2- 9-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	JOHN PECTOL RD	16.	Latitude:	38.33962
9.	Location:	00.00 INT HAMBY/JOHN PECTOL	17.	Longitude:	-85.983109
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	3 (STEEL)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	10 (THRU TRUSS)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2013	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	421 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	620 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	2 %Trucks	19.	Bypass Detour Length:	7 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	88 ft.	49.	Structure Length:	92 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	26 ft.	52.	Deck Width (O-O)	26.5 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	26 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.

Lateral Left:

0 ft.

55B. Lateral Right:

NBI Number: 2200108 Bridge Number: 22-00023 B
Facility Carried: JOHN PECTOL RD Feature(s) Intersected: BIG INDIAN CREEK

NAVIGATION

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	9
	EXCELLENT - NO MAJOR DEFECTS				
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	9
	EXCELLENT - NO MAJOR DEFECTS				
59.	Superstructure:	Material:	STEEL	Rating:	8
	VERY GOOD - RUST LAMINATION TYP. AT FLOOR BEAM CONN	IECTIONS	, DEBRIS PACKED IN LOWER CHORDS		
60.	Substructure:	Material:	CONCRETE	Rating:	9
	EXCELLENT - NO MAJOR DEFECTS				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/Δ				

31.	Design Load:	A (HL 93)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	53	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	49	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	27 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200108 Bridge Number: 22-00023 B

Facility Carried: JOHN PECTOL RD Feature(s) Intersected: BIG INDIAN CREEK

APPRAISAL

Waterway Adequacy:

 67.
 Structural:
 8

 68.
 Geometry:
 5

 69.
 Underclearance:
 N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - TANGENT, CURVES EA. WAY & "T" INT. @ SW, HUMP @ E APPR.

Material: BITUMINOUS

Comments: NO MAJOR DEFECTS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments: NO EVIDENCE OF SCOUR. CHANNEL IS CLAY BANKS WITH GRAVEL BOTTOM

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND CLEANING DEBRIS FROM LOWER CHORDS.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 Y
 24
 B:
 N
 C:
 N

 93.
 Date:
 A:
 3/4/2020
 B:
 C:

Unofficial Sufficiency Rating: 87.3
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING NORTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



DOWNSTREAM PIER CRACKS AND EFFL.



NBI Number: 2200023 Bridge Number: 22-00024

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

				<u>ITIFICATION</u>	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200023	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	RICHLAND CREEK	Feat Intersected:	6.
38.32955	Latitude:	16.	G'TOWN-GREENVILLE	Facility Carried:	7.
-86.00676	Longitude:	17.	00.60 S of BAKER Rd	Location:	9.
				JCTURE DATA	STRU
000	Structure Type - Approach:	44.	2 (CONTINUOUS CONCRETE)	Structure Type - Main Span:	43A.
2	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	AGE
0	Reconstructed:	106.	1929	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	380 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	559 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	GEO
43.2 ft.	Structure Length:	49.	19.5 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
22 ft.	Deck Width (O-O)	52.	20 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	20 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	15 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	20 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
0 ft.	Lateral Left:	56.	0 ft.	Lateral Right:	55B.

NBI Number: 2200023 Bridge Number: 22-00024

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

|--|

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	2 (ELIGIBLE FOR NATIONAL REGISTER)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	5
	FAIR - SEVERE SCALING ON RAILING			
58.01.	Wearing Surface:	Material: BITUMINOUS (5")	Rating:	7
	GOOD - EXCESSIVE THICKNESS, CRACKS			
59.	Superstructure:	Material: CONCRETE	Rating:	5
	FAIR - SPALLS ON BOTTOM & COPINGS, LEACHING THROUG	HOUT, CRACKS W/ EFFL. ALONG COPINGS, RAILING AND SLAE	3 CRACKED OVER PI	ER
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - SPALLS, CRACKS, POPOUTS			
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	5
	FAIR - SOME DRIFT IN CHANNEL, FLOW TOWARDS E ABUTMI	ENT		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200023 Bridge Number: 22-00024

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

APPRAISAL

Waterway Adequacy:

 67.
 Structural:
 5

 68.
 Geometry:
 4

 69.
 Underclearance:
 N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - HUMP UP TO BRIDGE, CURVE BOTH WAYS

Material: BITUMINOUS

Comments: SEALED CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUPERSTRUCTURE.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 65 ft. 94. Bridge Improvement Costs: 306 x 1000 95. Roadway Improvement Costs: 184 x 1000 Total Project Cost: 96. 619 x 1000 Year of Cost Estimate: 2020 97

77. Todi of oost Estimato.

RECOMMENDED MAINTENANCE

UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD APPROACH AND END TREATMENT GUARDRAIL

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 67.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



WEST ABUTMENT AND DOWNSTREAM COPING



NBI Number: 2200024 Bridge Number: 22-00025

Facility Carried: BAKER ROAD Feature(s) Intersected: RICHLAND CREEK

1 401	inty carried DARLITHOAD	1 00	aturc(3)	IIICI SCCICA. MICHEAND CM	LLIX
<u>IDEN</u>	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200024			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	RICHLAND CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BAKER ROAD	16.	Latitude:	38.33829
9.	Location:	00.00 INT of G'TOWN Rd	17.	Longitude:	-86.006721
STRU	JCTURE DATA	1			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	0 (NONE)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2004	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	292 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	430 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	3 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	29.8 ft.	49.	Structure Length:	31.8 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	25.3 ft.	52.	Deck Width (O-O)	25.6 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	25.3 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200024 Bridge Number: 22-00025

Facility Carried: BAKER ROAD Feature(s) Intersected: RICHLAND CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (1")	Rating:	7
	GOOD - CRACKS				
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	8
	VERY GOOD - EROSION AT WINGS				
62.	Culvert/Ret:	Material:	PRECAST CONC. 3-SIDED	Rating:	7
	COOD EDGES CHIDDED HAIDLINE CDACKS EFFL AT JOINTS				

GOOD - EDGES CHIPPED, HAIRLINE CRACKS, EFFL. AT JOINTS

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200024 Bridge Number: 22-00025

Facility Carried: BAKER ROAD Feature(s) Intersected: RICHLAND CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - TANGENT, UPGRADE TO WEST, INT. EAST

Material: BITUMINOUS

Comments: LONG. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND PLACING RIPRAP AT SOUTHWEST CORNER AND INSTALLING CURRENT STANDARD APPROACH GUARDRAIL.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 91.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



LOOKING NORTH AT ABUTMENT



NBI Number: 2200025 Bridge Number: 22-00026

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

<u>IDEN</u>	<u>TIFICATION</u>	I			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200025			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	RICHLAND CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	G'TOWN-GREENVILLE	16.	Latitude:	38.34553
9.	Location:	00.20 S OF CROWDER	17.	Longitude:	-86.004547
<u>STRL</u>	JCTURE DATA	1			
43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	5
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1989	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	617 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	908 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	28 ft.	49.	Structure Length:	131 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	28 ft.	52.	Deck Width (O-O)	31 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	40 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	28 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200025 Bridge Number: 22-00026

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - LONG. CRACKS & POPOUTS				
58.01.	Wearing Surface:	Material:	MONOLITHIC CONCRETE	Rating:	6
	SATIS - POPOUTS, LONG. CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - COPING SPALL OVER PIER, LONG. CRACKS ON TOP				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - VERTICAL HAIRLINE CRACKS, LEACHING				
61.	Channel:	Material:	NATURAL/ ROCK	Rating:	5
	FAIR - EROSION AT WINGS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/Δ				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	1 (LOAD FACTOR (LF))
64.	Operating Rating:	71	65.	Inv Rating Method:	1 (LOAD FACTOR (LF))
66.	Inventory Rating:	42	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	23 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

1 (MEETS ACCEPTABLE STANDARDS)

NBI Number: 2200025 Bridge Number: 22-00026

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

APPRAISAL

36A.

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 4

Traffic Safety Features (Bridge Railings):

36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
72. Roadway Alignment: 6 - LEVEL, BRIDGE IN CURVE, HILL NORTH

Material:

Comments: LONG. CRACKS, SOME SEALED

Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STANDARD APPROACH RAIL AND BRIDGE END MARKERS AT NORTHEAST AND SOUTHEAST, PLACING RIPRAP AT SOUTHWEST AND SOUTHEAST CORNERS.

INSPECTION DATA

90. Date: 3/2/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 96.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING WEST FROM ROAD



LOOKING SOUTH FROM CHANNEL



LOOKING EAST AT ABUTMENT SCOUR



NBI Number: 2200026 Bridge Number: 22-00027

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: BIG INDIAN Creek

			1	<u>ITIFICATION</u>	<u>IDEN</u>
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200026	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	BIG INDIAN Creek	Feat Intersected:	6.
38.31769	Latitude:	16.	G'TOWN-GREENVILLE	Facility Carried:	7.
-86.001808	Longitude:	17.	00.10 W of COOKS MILL	Location:	9.
			1	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	4 (CONTINUOUS STEEL)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	02 (GIRDER)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			8 (UNKNOWN)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1972	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	308 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	453 VPD	Future ADT:	114.
8 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
			1	METRIC DATA	<u>GEOI</u>
163 ft.	Structure Length:	49.	69.5 ft.	Maximum Span Length:	48.
0.9 ft.	Sidewalk/Curb Right:	50B.	0.9 ft.	Sidewalk/Curb Left:	50A.
30.2 ft.	Deck Width (O-O)	52.	28.2 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	27.7 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	45 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	28.2 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
0 ft.	Lateral Left:	56.	0 ft.	Lateral Right:	55B.

NBI Number: 2200026 Bridge Number: 22-00027

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: BIG INDIAN Creek

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION

58.	Deck:	Material: (CONCRETE	Rating:	4
	POOR - LARGE SPALLS BOTTOM OF DECK WITH EXPOSED RIJOINTS AND BELOW SPALLS ON TOP OF DECK	REINFORCING	G UNDER DECK DRAINS, LEACHING THRU DECK AT	CONSTRUCTION	
58.01.	Wearing Surface:	Material: (CONCRETE	Rating:	4
	POOR - CONCRETE CRACKS, SPALLS, BITUMINOUS (3") PATC	CHES, GRAV	/EL IN GUTTERS		
59.	Superstructure:	Material: S	STEEL	Rating:	6
	SATIS - ELASTOMERIC BEARING PADS PUSHED OUT, SURFAC RUSTED THROUGH AT EAST AND WEST END BENTS	ACE RUST AN	ND FLAKING AT BEARINGS, ALL BEAM BEARING ASS	EMBLY BOLTS ARE	
60.	Substructure:	Material: (CONC. CAP ON PILES, CONC. BENTS	Rating:	4
	POOR - END BENTS UNDERMINED WITH HEAVY RUST ON EXEBENT HAS ALL 9 PILES EXPOSED, BATTERED PILES HAVE HE			EXPOSED, EAST END)
61.	Channel:	Material: 1	NATURAL/RIPRAP	Rating:	5
	FAIR - BRUSHY, ERODED SPILLSLOPES, MEANDERS UPSTRE	EAM			
62.	Culvert/Ret:	Material: N	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	66	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	61	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	48 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200026 Bridge Number: 22-00027

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: BIG INDIAN Creek

APPRAISAL

67. Structural: 4
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

2. Roadway Alignment: 6 - BRIDGE ABOVE APPROACHES, HORIZONTAL CURVE BOTH WAYS

Material: BITUMINOUS

Comments: SEALED CRACKS

113. Scour Critical Bridges: 4 (STABLE - ACTION NEEDED)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 35 (REHABILITATE BRIDGE DUE TO SUBSTRUCTURE AND DECK DETERIORATION.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 163 ft. 94. Bridge Improvement Costs: 423 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 735 x 1000 Year of Cost Estimate: 97 2020

RECOMMENDED MAINTENANCE

UNTIL REHABILITATION, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT, AND PLACING BACKFILL AND RIPRAP AT END BENTS.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 12 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

Unofficial Sufficiency Rating: 67.7

Unofficial Structural and Functional Classification: 1 (STRUCTURALLY DEFICIENT)



LOOKING WEST FROM ROAD




LOOKING SOUTH FROM CHANNEL



LOOKING EAST FROM ROAD



UPSTREAM SPALL AND WEB CRACKS



NBI Number: 2200027 Bridge Number: 22-00028

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

IDEN	ITIFICATION	ĺ			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200027			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	RICHLAND CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	G'TOWN-GREENVILLE	16.	Latitude:	38.32404
9.	Location:	00.10 S OF BYRN'VL	17.	Longitude:	-86.011879
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	22 (CHANNEL BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1964	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	308 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	453 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	8 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	35 ft.	49.	Structure Length:	37.9 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	22.3 ft.	52.	Deck Width (O-O)	22.7 ft.
32.	Approach Roadway Width:	21 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	22.3 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	Oft.

NBI Number: 2200027 Bridge Number: 22-00028

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	6
	SATIS - LOW RAILING, DIRT IN GUTTERS			
58.01.	Wearing Surface:	Material: BITUMINOUS (7")	Rating:	7
	GOOD - EXCESSIVE THICKNESS			
59.	Superstructure:	Material: CONCRETE	Rating:	5
	FAIR - LARGE SPALLS, EXPOSED REBAR, LONG. CRACKS, LEA	ACHING		
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - HAIRLINE VERTICAL CRACKS, LEACHING, NE CORNER	RSCOUR		
61.	Channel:	Material: NATURAL/ ROCK	Rating:	6
	SATIS - TREES, EROSION NE WING, FLOW TOWARDS NE & SW	V CORNERS		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200027 Bridge Number: 22-00028

Facility Carried: G'TOWN-GREENVILLE Feature(s) Intersected: RICHLAND CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - HILL SOUTH, DIP & INTERSECTION NORTH

Material: Bituminous

Comments: SEALED CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 69.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



SPALLS AT UPSTREAM OF SOUTH PIER



NBI Number: 2200028 Bridge Number: 22-00029

Facility Carried: EDWARDSVIL.-GALENA Feature(s) Intersected: LITTLE INDIAN CREEK

IDEN	ITIFICATION	I			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200028			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
Ď.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	EDWARDSVILGALENA	16.	Latitude:	38.32417
9.	Location:	00.80 S OF OLD VINCENNES	17.	Longitude:	-85.933586
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	6 (CONT PRESTR CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	06 (SPREAD BOX BEAM)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE	'			
27.	Year Built:	1997	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	663 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	976 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	8 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	56 ft.	49.	Structure Length:	163 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	30 ft.	52.	Deck Width (O-O)	33 ft.
32.	Approach Roadway Width:	29 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	40 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
17.	Total Horiz. Clearance:	30 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200028 Bridge Number: 22-00029

Facility Carried: EDWARDSVIL.-GALENA Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - HAIRLINE CRACKS, POPOUTS, EXPANSION JOINTS DA	AMAGED			
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	7
	GOOD - RANDOM HAIRLINE CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - TRANS. CRACKS AT BEAM ENDS, SW BEARING WALK	NG OUT			
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - LG SPALL & EXPOSED STEEL S PIER CAP				
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	8
	VERY GOOD - BRUSHY, MANY SMALL TREES				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	94	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	63	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	47 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200028 Bridge Number: 22-00029

Facility Carried: EDWARDSVIL.-GALENA Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - CURVED BR ON HUMP, INT. NE, DRIVE SW

Material: CONCRETE / BITUMINOUS

Comments: CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND PATCHING SPALL ON PIER CAP AND REPLACING BRIDGE END JOINTS.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 99.6
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



SOUTHEAST CORNER CRACKS



NBI Number: 2200030 Bridge Number: 22-00031

Facility Carried: N LUTHER RD Feature(s) Intersected: LITTLE INDIAN CREEK

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200030			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	N LUTHER RD	16.	Latitude:	38.31005
9.	Location:	00.10 N OF DUFFY RD	17.	Longitude:	-85.910378
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1968	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	244 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	359 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	5 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	57 ft.	49.	Structure Length:	60 ft.
50A.	Sidewalk/Curb Left:	1.0 ft.	50B.	Sidewalk/Curb Right:	1.0 ft.
51.	Bridge Roadway Width:	24.5 ft.	52.	Deck Width (O-O)	26.5 ft.
32.	Approach Roadway Width:	20 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	26.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200030 Bridge Number: 22-00031

Facility Carried: N LUTHER RD Feature(s) Intersected: LITTLE INDIAN CREEK

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	PRESTR. CONC. BOX BMS	Rating:	4
	POOR - SIX BEAMS CRACKED ON BOTTOM (SEE SKETCH)				
58.01.	Wearing Surface:	Material:	BITUMINOUS (3")	Rating:	5
	FAIR - CRACKS OVER OUTSIDE BEAM JOINTS				
59.	Superstructure:	Material:	PRESTR. CONC. BOX BEAMS	Rating:	4
	POOR - SIX BEAMS CRACKED ON BOTTOM WITH RUST COMIN	IG THRU S	SOME CRACKS, VENT HOLES DRIPPING, SEEPAGE BI	ETWEEN BEAMS	
60.	Substructure:	Material:	CONC. ABUTS	Rating:	6
	SATIS - SEVERAL VERTICAL AND DIAGONAL CRACKS WITH LE	EACHING,	SOUTH FOOTING EXPOSED BUT FOUNDED ON ROCK	<	
61.	Channel:	Material:	NATURAL	Rating:	6
	SATIS - SOUTH FOOTING EXPOSED, FLOW TOWARDS SOUTH	FOOTING			
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	43	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	32	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	25 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200030 Bridge Number: 22-00031

Facility Carried: N LUTHER RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 4
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - LEVEL, TANGENT, "T" INTERSECTION SOUTH

Material: BITUMINOUS

Comments: TRANSVERSE CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

35 (REHABII ITATE BRIDGE DUE TO SUPERSTRUCTURE AND SUBSTRUCTURE 75A. Type of Work: DETERIORATION.) 1 (CONTRACT) Work Done By: 76. Improvement Length: 60 ft. 94. Bridge Improvement Costs: 137 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 389 x 1000 97. Year of Cost Estimate: 2020

RECOMMENDED MAINTENANCE

UNTIL REHABILITATION, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT AND MISSING NORTHEAST AND SOUTHWEST BRIDGE END MARKERS, AND PLACING RIPRAP IN SOUTHEAST QUADRANT.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 12 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

Unofficial Sufficiency Rating: 60.8

Unofficial Structural and Functional Classification: 1 (STRUCTURALLY DEFICIENT)



LOOKING WEST FROM ROAD




LOOKING SOUTH FROM CHANNEL



LOOKING EAST FROM ROAD



TYPICAL SEEPAGE BETWEEN SEGMENTS



NBI Number: 2200088 Bridge Number: 22-00032

Facility Carried: REASOR RD Feature(s) Intersected: LITTLE INDIAN CREEK

IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200088			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	REASOR RD	16.	Latitude:	38.37548
9.	Location:	00.30 E OF NAVILLETON RD	17.	Longitude:	-85.932045
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	11 (DECK ARCH)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE				
27.	Year Built:	2006	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	129 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	190 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	5 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	28 ft.	49.	Structure Length:	61.4 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	24 ft.	52.	Deck Width (O-O)	24 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	O ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200088 Bridge Number: 22-00032

Facility Carried: REASOR RD Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - SEEPAGE BETWEEN SEGMENTS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - CRACKS, SMALL AREA MISSING SOUTHWEST				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - SEEPAGE BETWEEN SEGMENTS, SEGMENT HEIGHT \	/ARIES			
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - ABRASION ON UPSTREAM NOSE OF PIER AT BO	MOTTC			
61.	Channel:	Material:	ROCK BOTTOM, CONC OVER RIPRAP	Rating:	7
	GOOD - STRAIGHT				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

0 (FIELD EVAL AND ENG JUDGEMENT)	Oper Rating Method:	63.	5 (HS 20)	Design Load:	31. Design Lo	31.
0 (FIELD EVAL AND ENG JUDGEMENT)	Inv Rating Method:	65.	36	Operating Rating:	64. Operating	64.
Tons	Tons Posted:	66C.	36	Inventory Rating:	66. Inventory	66.
	Date Posted/Closed:	66D.	20 Tons	Gross Tons or H Rating:	66B. Gross Tol	66B.
5 (EQUAL TO OR ABOVE LEGAL LOADS)	Bridge Posting:	70.	A (OPEN)	Open, Posted, or Closed:	41. Open, Po	41.

NBI Number: 2200088 Bridge Number: 22-00032

Facility Carried: REASOR RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - CURVE EACH WAY, NEARLY LEVEL

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND SE B.E.M.'S. AND FILL NORTHEAST SHOULDER EROSION

INSPECTION DATA


 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 93.5
Unofficial Structural and Functional Classification: 0 (OK)






LOOKING NORTH FROM CHANNEL



LOOKING WEST FROM ROAD



SOUTHEAST CORNER EROSION



NBI Number: 2200032 Bridge Number: 22-00033

Facility Carried: MALINEE-OTT RD Feature(s) Intersected: GEORGETOWN CREEK

			. ,		
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200032			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	GEORGETOWN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	MALINEE-OTT RD	16.	Latitude:	38.30905
9.	Location:	00.10 W OF GRNVILLE/GRTWN	17.	Longitude:	-85.997803
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1984	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	193 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	274 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	5 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	58 ft.	49.	Structure Length:	63 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	24 ft.	52.	Deck Width (O-O)	24.4 ft.
32.	Approach Roadway Width:	21 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	30 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200032 Bridge Number: 22-00033

Facility Carried: MALINEE-OTT RD Feature(s) Intersected: GEORGETOWN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - GRAVEL ON EDGES, LONG/ CRACKS AT BOX BEAM JO	INTS			
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	6
	SATIS - MANY POPOUTS & HAIRLINE CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - CRACKS AROUND GUARDRAIL BOLTS ON UPSTREAM				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - HAIRLINE CRACKS, LEACHING				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	5
	FAIR - EROSION AROUND WINGS, FLOW TOWARDS EAST ABU	ITMENT			
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	52	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	37	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	33 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200032 Bridge Number: 22-00033

Facility Carried: MALINEE-OTT RD Feature(s) Intersected: GEORGETOWN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - BRIDGE ON HUMP, HILL W, CURVE WEST

Material: BITUMINOUS

Comments: SATISFACTORY - SETTLED AT BRIDGE ENDS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, REPAIRING SE SHOULDER EROSION, AND PLACING RIPRAP AT SE CORNER AND BEHIND SE WING.

INSPECTION DATA

90. Date: 3/3/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 93.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



SOUTH ABUTMENT SCOUR



NBI Number: 2200034 Bridge Number: 22-00035

Facility Carried: G'TOWN-LANESVILLE Feature(s) Intersected: GEORGETOWN CREEK

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	27324 (GEORGETOWN)
8.	NBI Number:	2200034			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	GEORGETOWN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	G'TOWN-LANESVILLE	16.	Latitude:	38.29339
9.	Location:	00.10 S OF US 64	17.	Longitude:	-85.980255
<u>STRL</u>	JCTURE DATA	1			
43A.	Structure Type - Main Span:	3 (STEEL)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	02 (GIRDER)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1976	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1301 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1916 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	43 ft.	49.	Structure Length:	129.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	32.7 ft.	52.	Deck Width (O-O)	35.2 ft.
32.	Approach Roadway Width:	26 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	32.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200034 Bridge Number: 22-00035

Facility Carried: G'TOWN-LANESVILLE Feature(s) Intersected: GEORGETOWN CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	4
	POOR - MANY HAIRLINE CRACKS BOTTOM OF DECK WITH EFEXPOSED REINFORCING, JOINTS OPEN ALLOW WATER ONT			DLY SPALLED WITH	
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	4
	POOR - NUMEROUS RANDOM HAIRLINE CRACKS AND POPO	UTS, MANY	LARGE SPALLS WITH BITUMINOUS (2") PATCHES AT	ALL SPANS	
59.	Superstructure:	Material:	STEEL BEAMS	Rating:	5
	FAIR - AREAS OF HEAVY FLAKING RUST ESPECIALLY UNDER	R OPEN DE	CK JOINTS		
60.	Substructure:	Material:	CONC. ABUTS/PIERS	Rating:	6
	SATIS - HAIRLINE CRACKS AND LIGHT EFFLORESCENCE				
61.	Channel:	Material:	NATURAL	Rating:	6
	SATIS - DRIFT, BANK EROSION, RIPRAP WASHED OFF SOUTH	H SPILLSLO)PE		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	63	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	58	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	42 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200034 Bridge Number: 22-00035

Facility Carried: G'TOWN-LANESVILLE Feature(s) Intersected: GEORGETOWN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings):

0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36B. Traffic Safety Features (Transitions):

0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail):

0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends):

0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment:

6 - CURVED BRIDGE IN LONG HORIZONTAL CURVE ON UPGRADE TO SOUTH

Material: BITUMINOUS

Comments: CRACKS, POTHOLES, AND PATCHES

113. Scour Critical Bridges: 4 (STABLE - ACTION NEEDED)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: 35 (REHABILITATE BRIDGE DUE TO SUPERSTRUCTURE DETERIORATION.)

1 (CONTRACT) 76. Improvement Length: 130 ft. 94. Bridge Improvement Costs: 336 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 630 x 1000 Year of Cost Estimate: 97 2020

RECOMMENDED MAINTENANCE

UNTIL REHABILITATION, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT AND MISSING NORTHEAST, SOUTHWEST, AND NORTHWEST BRIDGE END MARKERS, AND PLACING RIPRAP AT SOUTH ABUTMENT.

INSPECTION DATA

90. Date: 3/3/2020
91. Des. Inspection Frequency: 12 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 81.6

Unofficial Structural and Functional Classification: 1 (STRUCTURALLY DEFICIENT)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



SOUTH ABUTMENT



NBI Number: 2200090 Bridge Number: 22-00036 B

Facility Carried: WISSMAN RD Feature(s) Intersected: GEORGETOWN CREEK

	,		\ /		
<u>IDEN</u>	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	27324 (GEORGETOWN)
8.	NBI Number:	2200090			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	GEORGETOWN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	WISSMAN RD	16.	Latitude:	38.29268
9.	Location:	00.10 S US 64	17.	Longitude:	-85.976334
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	02 (GIRDER)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE	'			
27.	Year Built:	2011	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	468 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	690 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	3 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	57.2 ft.	49.	Structure Length:	61.3 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	19 ft.	52.	Deck Width (O-O)	19.5 ft.
32.	Approach Roadway Width:	20 ft.	33.	Bridge Median:	0 (NO MEDIAN)

0 Degree(s)

99.99

19 ft.

Ν

0 ft.

35.

53.

54A.

54B.

56.

Structure Flared:

Vertical Clearance/Deck:

Min Vert Clear Code:

Underclearance:

Lateral Left:

34.

47.

55A.

55B.

Skew:

Defense Vertical Clearance:

Total Horiz. Clearance:

Lateral Right:

Min Latr. Cl. Right - Code:

0 (NO FLARE)

99.99 ft.

Ν

0 ft.

0 ft.

NBI Number: 2200090 Bridge Number: 22-00036 B

Facility Carried: WISSMAN RD Feature(s) Intersected: GEORGETOWN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
59.	Superstructure:	Material: PRECAST CONCRETE I-BEAM	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
60.	Substructure:	Material: CONCRETE ABUTMENTS	Rating:	7
	GOOD - HONEYCOMBED, HAIRLINE CRACKS, 3 VERT. CRACK	S AT EACH WING, ONE AT EAST WING AND AT CENTERLINE		
61.	Channel:	Material: RIPRAP & NATURAL BEDROCK	Rating:	7
	GOOD - NO MAJOR DEFECTS, FLOWS TOWARD S ABUTMENT	-		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	58	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	48	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	39 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200090 Bridge Number: 22-00036 B

Facility Carried: WISSMAN RD Feature(s) Intersected: GEORGETOWN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - SHARP CURVE EACH END, ON UPGRADE TO HILL SOUTH

Material: BITUMINOUS

Comments: SETTLED AT BRIDGE ENDS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND PLACING RIPRAP ON S SPILLSLOPE.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 80.9

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



NORTH PIER, CENTER SPAN



NBI Number: 2200036 Bridge Number: 22-00037

Facility Carried: WALTS RD Feature(s) Intersected: GEORGETOWN CREEK

<u>IDENTIFICATION</u>	

1.	State:	185 (INDIANA)	4.	City/Town:	27324 (GEORGETOWN)
8.	NBI Number:	2200036			
5.	Inventory Route On:	1-5-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	GEORGETOWN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	WALTS RD	16.	Latitude:	38.29281
9.	Location:	00.10 S OF US 64	17.	Longitude:	-85.972244

STRUCTURE DATA

43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Cons	01 (SLAB)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (FPOXY COATED REINFORCING)			

AGE OF SERVICE

27.	Year Built:	2002	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	549 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	809 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	3 mi.

GEOMETRIC DATA

48.	Maximum Span Length:	37 ft.	49.	Structure Length:	93.7 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	25.5 ft.	52.	Deck Width (O-O)	29 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	5 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	25.5 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200036 Bridge Number: 22-00037

Facility Carried: WALTS RD Feature(s) Intersected: GEORGETOWN CREEK

NAVIGA [*]	TION
---------------------	------

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8
	VERY GOOD - FEW POPOUTS, HL CRACKS OVER PIERS, HL C	RACKS E	VERY 10' ON BARRIERS		
58.01.	Wearing Surface:	Material:	MONOLITHIC CONCRETE	Rating:	8
	${\tt VERYGOOD-DEBRISINGUTTERS,HLCRACKSOVERPIERS}$				
59.	Superstructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - HONEYCOMB AREAS, RUST STAINS AROUND D	RAINS			
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - CONSTRUCTION PATCHES, 5 VERT. CRACKS A	T N ABUT	MENT, 3 VERT. CRACKS AT S ABUTMENT		
61.	Channel:	Material:	NATURAL ROCK BOTTOM, RIPRAP	Rating:	7
	GOOD - SILT BUILT-UP AT BOTH END SPANS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	66	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	53	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	35 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200036 Bridge Number: 22-00037

Facility Carried: WALTS RD Feature(s) Intersected: GEORGETOWN CREEK

APPRAISAL

67. Structural: 8
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - CURVE & UPGRADE EACH WAY

Material: BITUMINOUS

Comments: NO MAJOR DEFECTS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE NEEDED.

INSPECTION DATA

90.	Date:	3/3/2020	91.	Des. Inspection	n Frequ	ency:	48 Mor	iths
92.	Critical Feature Inspec	ction:	A:	N	B:	Ν	C:	Ν
93.	Date:		A:		B:		C:	

Unofficial Sufficiency Rating: 91.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



SOUTH FACE OF PIER



NBI Number: 2200037 Bridge Number: 22-00038

Facility Carried: BAYLOR-WISSMAN RD Feature(s) Intersected: GEORGETOWN CREEK

IDEN	ITIFICATION	1			
1.	State:	185 (INDIANA)	4.	City/Town:	27324 (GEORGETOWN)
8.	NBI Number:	2200037			
5.	Inventory Route On:	1-5-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	GEORGETOWN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BAYLOR-WISSMAN RD	16.	Latitude:	38.29538
9.	Location:	00.10 S OF US 64	17.	Longitude:	-85.957527
STRU	JCTURE DATA	1			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1950	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	1	28B.	Lanes Under Structure:	0
29.	ADT - Over:	939 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1383 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	5 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	19.5 ft.	49.	Structure Length:	44.3 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	16.7 ft.	52.	Deck Width (O-O)	19.3 ft.
32.	Approach Roadway Width:	17 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	16.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	O ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200037 Bridge Number: 22-00038

Facility Carried: BAYLOR-WISSMAN RD Feature(s) Intersected: GEORGETOWN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	3 (ONE LANE BRIDGE FOR 2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION

58.	Deck:	Materia	: CONCRETE	Rating:	5
	FAIR - LIGHT SCALING OVERALL, LARGE SPALL WITH EXPOS	SED REBA	R SOUTH SPAN EAST COPING		
58.01.	Wearing Surface:	Materia	: BITUMINOUS (6")	Rating:	6
	SATIS - CRACKS, DEBRIS IN GUTTERS				
59.	Superstructure:	Materia	: CONCRETE	Rating:	5
	FAIR - LARGE SPALLS BOTTOM, EXPOSED REBAR				
60.	Substructure:	Materia	: CONCRETE	Rating:	5
	FAIR - CRACKS, PIER ENDS SEVERE SPALLING, LARGE TREE ABUTMENTS, TOP FOOTING VISIBLE AT PIER, HORIZONTAL C			POSED AT	
61.	Channel:	Materia	: NATURAL ROCK BOTTOM	Rating:	5
	FAIR - AGGRADATION SOUTH SPAN, FLOW SKEWED FROM C	PENING			
62.	Culvert/Ret:	Materia	: N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200037 Bridge Number: 22-00038

Facility Carried: BAYLOR-WISSMAN RD Feature(s) Intersected: GEORGETOWN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - BRIDGE IN CURVE & ON HUMP, RR & INT N.

Material: BITUMINOUS

Comments: NEW OVERLAY AT NORTH

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION.)

75B. Work Done By: 1 (CONTRACT)

76. Improvement Length: 66 ft.

94. Bridge Improvement Costs: 274 x 1000

95. Roadway Improvement Costs: 184 x 1000

96. Total Project Cost: 578 x 1000

97. Year of Cost Estimate: 2020

RECOMMENDED MAINTENANCE

UNTIL REPLACEMENT RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 76.5

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING SOUTH FROM ROAD




LOOKING WEST FROM CHANNEL



LOOKING NORTH FROM ROAD



LOOKING SOUTH CRACKED, SPALLING EAST COPING



NBI Number: 2200038 Bridge Number: 22-00039

Facility Carried: MOSER KNOB Feature(s) Intersected: LITTLE INDIAN CREEK

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200038			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	MOSER KNOB	16.	Latitude:	38.36821
9.	Location:	00.00 INT OF CHAMPION RD	17.	Longitude:	-85.846199
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1959	106.	Reconstructed:	1989
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	244 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	359 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	5 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	20 ft.	49.	Structure Length:	25.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	36.1 ft.	52.	Deck Width (O-O)	38.7 ft.
32.	Approach Roadway Width:	30 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	5 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	36.1 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200038 Bridge Number: 22-00039

Facility Carried: MOSER KNOB Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION

58.	Deck:	Material: CONCRETE SLAB	Rating:	5
	FAIR - EXTENSIVE CRACKING & LEACHING, DEEP SPALLS BO DECK	OTTOM ALONG CENTER LINE, PLYWOOD FORMS IN PLACE IN S	ST. BM. SECTION OF	
58.01.	Wearing Surface:	Material: BITUMINOUS (6")	Rating:	6
	SATIS - CRACKS, EXCESSIVE THICKNESS			
59.	Superstructure:	Material: CONCRETE SLAB AND STEEL BEAMS	Rating:	5
	FAIR - DEEP BTM. DECK SPALLS, EXPOSED STEEL, CRACKS	W/ EFFL., EXT. STEEL BEAMS HAVE SURFACE RUST		
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - LIGHT SCALING, TOP OF FTG. EXP., VERT. HL CRACK	(S, HEAVY EFFL. AT TOPS OF PIER AND NORTH BENT		
61.	Channel:	Material: NATURAL/ ROCK	Rating:	5
	FAIR - AGGRADATION, EXCESS VEGETATION, SILT BUILD-UP	IN S. SPAN		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200038 Bridge Number: 22-00039

Facility Carried: MOSER KNOB Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 8
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - INTERSECTION AT EACH END, UPGRADE TO SOUTH, HILL TO EAST

Material: BITUMINOUS

Comments: NUMEROUS CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUPERSTRUCTURE.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 47 ft. 94. Bridge Improvement Costs: 194 x 1000 95. Roadway Improvement Costs: 184 x 1000 Total Project Cost: 96. 477 x 1000 Year of Cost Estimate: 2020 97

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, AND CLEANING CHANNEL IN S SPAN.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 85.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



UPSTREAM N PIER BM SPALL



NBI Number: 2200039 Bridge Number: 22-00040

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: BIG INDIAN CREEK

IDEN	ITIFICATION	1			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200039			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BIG INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SCOTTSVILLE RD	16.	Latitude:	38.37075
9.	Location:	00.00 INT OF STARLIGHT RD	17.	Longitude:	-85.90049
STRU	JCTURE DATA	,			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	02 (GIRDER)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1971	106.	Reconstructed:	2017
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	2170 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	3196 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	5 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	34.4 ft.	49.	Structure Length:	104 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27 ft.	52.	Deck Width (O-O)	31 ft.
32.	Approach Roadway Width:	28 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	29 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200039 Bridge Number: 22-00040

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: BIG INDIAN CREEK

NAVIGA [*]	TION
---------------------	------

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	07 (RURAL - MAJOR COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - HAIRLINE CRACKS BOTTOM				
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
59.	Superstructure:	Material:	CONCRETE I-BEAM	Rating:	6
	SATIS - BEAM SPALLS & EXPOSED STEEL				
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - BTM. OF S ABUTMENT EXP.				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	6
	SATIS - LIGHT AGGRADATION				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	79	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	64	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	45 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200039 Bridge Number: 22-00040

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: BIG INDIAN CREEK

APPRAISAL

Waterway Adequacy:

 67.
 Structural:
 6

 68.
 Geometry:
 3

 69.
 Underclearance:
 N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, DIP AND INTERSECTION AT NORTH END OF BRIDGE

Material: BITUMINOUS

Comments: NEW BIT. AT BRIDGE ENDS, LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE REQUIRED.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 85.0

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



LOOKING SOUTH AT CRACK IN BEAM 9 AT EAST COPING



NBI Number: 2200040 Bridge Number: 22-00041

Facility Carried: ST MARY'S RD Feature(s) Intersected: LITTLE INDIAN CREEK

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200040			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	ST MARY'S RD	16.	Latitude:	38.35278
9.	Location:	00.40 S of CHAMPION RD	17.	Longitude:	-85.864433
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	'			
27.	Year Built:	1966	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	2590 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	3815 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	4 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	45.8 ft.	49.	Structure Length:	48 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	25.4 ft.	52.	Deck Width (O-O)	27.2 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	26.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200040 Bridge Number: 22-00041

Facility Carried: ST MARY'S RD Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - LOW BRIDGE RAILING				
58.01.	Wearing Surface:	Material:	BITUMINOUS (6")	Rating:	7
	GOOD - LONGITUDINAL CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	5
	FAIR - LEAKS BETWEEN BEAMS, HL CRACKS IN BTM. OF W CC COPING OF BM FROM S ABUTMENT TO MID SPAN WITH RUST			NG BM, AND IN	
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - SLIGHTLY UNDERMINED SE CORNER, APPROX 1'				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	6
	SATIS - FLOW AGAINST SOUTHEAST BANK, AGGREDATION, W	/INDING R	IPRAP BEHIND SE WINGWALL		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	4 (H 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	53	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	31	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	23 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200040 Bridge Number: 22-00041

Facility Carried: ST MARY'S RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - BR. ON SLIGHT HUMP, SLT. CURVE EA. END

Material: BITUMINOUS

Comments: LONG. CRACKS, TRANS. CRACKS AT BRIDGE ENDS

113. Scour Critical Bridges: 3 (SCOUR CRITICAL - UNSTABLE)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE DUE TO DETERIORATION AND SCOUR.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 70 ft. 94. Bridge Improvement Costs: 329 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 648 x 1000 Year of Cost Estimate: 97 2020

RECOMMENDED MAINTENANCE

UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S AND PLACING RIPRAP AT S ABUTMENT.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

Unofficial Sufficiency Rating: 65.5

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING EAST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING WEST FROM ROAD



LOOKING WEST AT REPAIRED BEAM 3



NBI Number: 2200041 Bridge Number: 22-00042

Facility Carried: SPICKERT KNOB RD Feature(s) Intersected: LITTLE INDIAN CREEK

<u>IDEN</u>	<u>ITIFICATION</u>		l		
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200041			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SPICKERT KNOB RD	16.	Latitude:	38.33512
9.	Location:	00.00 INT OF SAINT MARYS	17.	Longitude:	-85.870735
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE		1		
27.	Year Built:	1976	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	4291 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	6320 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	25.5 ft.	49.	Structure Length:	55.7 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	32.7 ft.	52.	Deck Width (O-O)	33.2 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	25 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	32.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200041 Bridge Number: 22-00042

Facility Carried: SPICKERT KNOB RD Feature(s) Intersected: LITTLE INDIAN CREEK

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - NO MAJOR DEFECTS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (4")	Rating:	6
	SATIS - CRACKS OVER PIER & END BENTS				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - SMALL SPALLS ON BOTTOM EDGES, WATER SEEPAG	E WITH E	FFL. BETWEEN BEAM 10 AND 11 EAST SPAN		
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - 2 VERT. HL CRACKS W/ EFFL. IN PIER; W ABUT HAS VE AND 11, HALF OF TOP OF FTG. EXP., 1 VERT. HL CRACK IN SW HL CRACKS UNDER BEAMS 2, 3, AND 8, 1/16" VERT. CRACKS L	/ WINGW	ALL, 2 VERT. HL CRACKS W/ EFFL. IN NW WINGWALL;		
61.	Channel:	Material:	NATURAL ROCK & GRAVEL BOTTOM	Rating:	6
	SATIS - AGGRADATION, DRIFT JAM, AT PIER UNDERCUT TREE	LEANING	G OVER BRIDGE.		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	68	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	49	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	29 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200041 Bridge Number: 22-00042

Facility Carried: SPICKERT KNOB RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - BR. ON HUMP, CURVE E., INT. W. END BR

Material: BITUMINOUS

Comments: SETTLED SLIGHTLY, CRACKS
Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

(NO WORK NEEDED.) 75A. Type of Work: Work Done By: 76. Improvement Length: 48 ft. 94. Bridge Improvement Costs: 118 x 1000 95. Roadway Improvement Costs: 174 × 1000 96. Total Project Cost: 354 x 1000

97. Year of Cost Estimate: 2018

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S, AND PLACING RIPRAP BEHIND SW WING. REMOVE TREE SOUTH OF BRIDGE THAT IS LEANING OVER THE DOCK.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

Unofficial Sufficiency Rating: 94.6
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST AT SILT BUILD-UP IN NORTH SPAN



LOOKING SOUTH FROM ROAD



LOOKING NORTH AT SOUTH SPAN WEST COPING T-BEAM



NBI Number: 2200042 Bridge Number: 22-00043

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: LITTLE INDIAN CREEK

				ITIFICATION	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200042	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	LITTLE INDIAN CREEK	Feat Intersected:	6.
38.3283	Latitude:	16.	SCOTTSVILLE RD	Facility Carried:	7.
-85.873543	Longitude:	17.	00.30 N OF PAOLI PIKE	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	2 (CONTINUOUS CONCRETE)	Structure Type - Main Span:	43A.
2	Number of Spans - Main:	45.	04 (TEE BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
1971	Reconstructed:	106.	1930	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	5 (HIGHWAY/PEDESTRIAN)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	8534 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	12571 VPD	Future ADT:	114.
6 mi.	Bypass Detour Length:	19.	6 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
55 ft.	Structure Length:	49.	27.8 ft.	Maximum Span Length:	48.
4.0 ft.	Sidewalk/Curb Right:	50B.	0.8 ft.	Sidewalk/Curb Left:	50A.
39.8 ft.	Deck Width (O-O)	52.	30.9 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	30 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	25 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	30.9 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
UII.					

NBI Number: 2200042 Bridge Number: 22-00043

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION

58.	Deck:	Material: CON	NCRETE	Rating:	6		
	SATIS - SPALLS, EXPOSED REIN. IN BOTTOM OF DECK IN S SPAN, EDGE SPALLING/ DETERIORATION AT W COPING WITH HEAVY EFFL.						
58.01.	Wearing Surface:	Material: BITU	TUMINOUS (10")	Rating:	7		
	GOOD - EXCESS DEPTH & DEAD LOAD						
59.	Superstructure:	Material: CON	NCRETE	Rating:	5		
	FAIR - T BEAMS CRACKED WITH EFFL., SPALLED EXPOSED R DETERIORATION AT W COPING ALSO DELAMINATIONS AND R BEAM. INT. T-BEAMS ARE SATIS WITH SMALL SPALLS.						
60.	Substructure:	Material: CON	NCRETE	Rating:	5		
	FAIR - HEAVY EFFL. ON PIER, VERT HL CRACKS IN OLDER E S	SUBSTRUCTUR	RE, ALL FOOTINGS EXP. SOME UNDERPINNED, ALI	L FOUNDED ON			
61.	Channel:	Material: NAT	TURAL ROCK BOTTOM	Rating:	6		
	SATIS - DRIFT JAM ON PIER NORTH SPAN SILTED WITH NO FL	LOW AT INSP. T	THROUGH NORTH SPAN.				
62.	Culvert/Ret:	Material: N/A	4	Rating:	Ν		
	N/A						

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200042 Bridge Number: 22-00043

Facility Carried: SCOTTSVILLE RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

Structural: 5 3 68. Geometry: 69. Underclearance: Ν Waterway Adequacy:

Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36A. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36C. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36D.

8 - BRIDGE ON HUMP, MULTIPLE HORIZ CURVES Roadway Alignment:

Material: BITUMINOUS

SEALED CRACKS, NB LANE SETTLING AT THE NORTH END OF THE BRIDGE

113. Scour Critical Bridges 5 (STABLE - WITHIN LIMITS)

PROPOSED IMPROVEMENTS

31 (REPLACE BRIDGE DUE TO DETERIORATION.) 75A. Type of Work:

Work Done By: 1 (CONTRACT) Improvement Length: 76. 78 ft. 94. Bridge Improvement Costs: 365 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 693 x 1000

Year of Cost Estimate: 2020 97

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR, RAIL W/END TREATMENT AND NE & SW B.E.M.'S.

INSPECTION DATA

90. 3/2/2020 91. Des. Inspection Frequency: 24 Months 92. Critical Feature Inspection: Α: Ν 93. Α. B:

Unofficial Sufficiency Rating: 66.3

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



LOOKING WEST AT REPAIRED BEAM 3



NBI Number: 2200043 Bridge Number: 22-00044

Facility Carried: ST MARY'S RD Feature(s) Intersected: LITTLE INDIAN CREEK

<u>IDEN</u>	ITIFICATION	[
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200043			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	ST MARY'S RD	16.	Latitude:	38.33875
9.	Location:	00.20 N OF SPICKERT KNB	17.	Longitude:	-85.86901
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE	, i			
27.	Year Built:	1964	106.	Reconstructed:	1999
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1651 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	2432 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	34 ft.	49.	Structure Length:	38.3 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27.7 ft.	52.	Deck Width (O-O)	28.5 ft.
32.	Approach Roadway Width:	21 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	25 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	27.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200043 Bridge Number: 22-00044

Facility Carried: ST MARY'S RD Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	7
	GOOD - HAIRLINE CRACKS			
58.01.	Wearing Surface:	Material: BITUMINOUS (5")	Rating:	6
	SATIS - CRACKS, ABUTMENT WIDENED AT SOUTH COPING			
59.	Superstructure:	Material: CONCRETE	Rating:	5
	FAIR - BEAM 3 PATCHED, BEAM 6 HAIRLINE CRACK 10' LONG	FROM E ABUTMENT SEALED, WATER SEEPAGE BETWEEN BEA	AMS.	
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - VERTICAL HAIRLINE CRACKS, ABUTMENT WIDENED A	AT SOUTH COPING		
61.	Channel:	Material: NATURAL ROCK BOTTOM, RIPRAP	Rating:	7
	GOOD - LARGE TREES UPSTREAM			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200043 Bridge Number: 22-00044

Facility Carried: ST MARY'S RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - DIP EAST END, SHARP CURVE & INT. W END

Material: BITUMINOUS

Comments: SETTLED, UNEVEN, FEW CRACKS, SETTLING IN EASTBOUND LANE AT EAST END OF BRIDGE

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 78.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING EAST FROM ROAD



HAIRLINE CRACK IN NORTH COPING BEAM AT



NBI Number: 2200044 Bridge Number: 22-00045
Facility Carried: PAYNE/KOEHLER RD Feature(s) Intersected: UPHILL RUN

	<u> </u>				
IDEN	ITIFICATION .				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200044			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	UPHILL RUN	11.	Mile Point (over):	0
7.	Facility Carried:	PAYNE/KOEHLER RD	16.	Latitude:	38.34715
9.	Location:	00.10 N OF FRINGE RD	17.	Longitude:	-85.784828
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	8 (UNKNOWN)			
AGE	OF SERVICE				
27.	Year Built:	1995	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1605 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	2364 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	3 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	47.5 ft.	49.	Structure Length:	50.2 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27.9 ft.	52.	Deck Width (O-O)	28.2 ft.
32.	Approach Roadway Width:	23 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	27.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200044 Bridge Number: 22-00045
Facility Carried: PAYNE/KOEHLER RD Feature(s) Intersected: UPHILL RUN

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - POURED SECTION OF NEW CONC. DECK OVER NEW POPOUTS	PCBB AT S	S COPING (5'-5" WIDE), LONG. HL CRACKS IN OLDER (CONC. DECK, MINOR	
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	7
	GOOD - POPOUTS				
59.	Superstructure:	Material:	CONCRETE	Rating:	5
	FAIR - HL CRACKS IN BTM. AND COPING OF N COPING BEAM A	AT 2 GDRL	POST CONNECTIONS		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - MINOR HAIRLINE CRACKS				
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	7
	GOOD - MINOR DRIFT				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	66	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	54	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	47 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200044 Bridge Number: 22-00045
Facility Carried: PAYNE/KOEHLER RD Feature(s) Intersected: UPHILL RUN

APPRAISAL

67. Structural: 5
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
72. Roadway Alignment: 8 - HILL & CURVE BOTH WAYS, DR NW & SW

Material: BITUMINOUS

Comments: ASPHALT APPROACHES

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NE & NW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 80.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING EAST FROM ROAD



LOOKING WEST AT CRACKING, EFFL. ON WEST ABUT.,



NBI Number: 2200045 Bridge Number: 22-00046

Facility Carried: PAOLI PIKE Feature(s) Intersected: LITTLE INDIAN CREEK

IDEN	<u>ITIFICATION</u>	ı			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200045			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	PAOLI PIKE	16.	Latitude:	38.3246
9.	Location:	00.10 W OF SCTTS'VLLE	17.	Longitude:	-85.874771
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	11 (DECK ARCH)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
AGE	OF SERVICE	·			
27.	Year Built:	1921	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	11041 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	16264 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	4 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	36.3 ft.	49.	Structure Length:	77 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	36.7 ft.	52.	Deck Width (O-O)	38.6 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	10 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	36.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200045 Bridge Number: 22-00046

Facility Carried: PAOLI PIKE Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	2 (ELIGIBLE FOR NATIONAL REGISTER)			

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - NOT FULL WIDTH, GRASS ON SHOULDERS				
59.	Superstructure:	Material:	CONCRETE ARCH	Rating:	6
	SATIS - LONGITUDINAL CRACKS WITH EFFL.				
60.	Substructure:	Material:	CONCRETE	Rating:	5
	FAIR - HEAVY SPALLING/CRACKING/DETERIORATION AT S EN HALF OF PIER FOOTING IS EXPOSED TOP 6" ON EAST SIDE	ID OF PIEI	R, VERT. CRACKS WITH MINOR SPALLS IN UNDERSID	E OF ARCH. NORTH	
61.	Channel:	Material:	NATURAL ROCK & GRAVEL	Rating:	6
	SATIS - AGGREGATION-SILT/ROCK BUILDUP IN WEST SPAN				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200045 Bridge Number: 22-00046

Facility Carried: PAOLI PIKE Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

Waterway Adequacy:

67. Structural:
5
68. Geometry:
69. Underclearance:
N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

Traffic Safety Features (Transitions):
 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 Traffic Safety Features (Approach Guardrail):
 Traffic Safety Features (Approach Guardrail Ends):
 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 Traffic Safety Features (Approach Guardrail Ends):
 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT & LEVEL, INT. EAST, DIP WEST

Material: BITUMINOUS Comments: CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 81.3
Unofficial Structural and Functional Classification: 0 (OK)






LOOKING NORTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



SOUTHWEST CORNER SCOUR



NBI Number: 2200046 Bridge Number: 22-00047

Facility Carried: DUFFY RD Feature(s) Intersected: LITTLE INDIAN CREEK

			Ī	NTIFICATION .	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200046	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	LITTLE INDIAN CREEK	Feat Intersected:	6.
38.30922	Latitude:	16.	DUFFY RD	Facility Carried:	7.
-85.904694	Longitude:	17.	00.30 E OF N LUTHER	Location:	9.
			ı	JCTURE DATA	STRU
000	Structure Type - Approach:	44.	2 (CONTINUOUS CONCRETE)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1968	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	713 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	1051 VPD	Future ADT:	114.
6 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
78.7 ft.	Structure Length:	49.	33.5 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
28 ft.	Deck Width (O-O)	52.	27.5 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	21 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	15 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
	Min Vert Clear Code:	54A.	27.5 ft.	Total Horiz. Clearance:	47.
N					
N 0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200046 Bridge Number: 22-00047

Facility Carried: DUFFY RD Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112. N	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104. H	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26. F	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100. D	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102. D	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110. D	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21. N	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37. H	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - OUTSIDE 2' REPLACED EACH SIDE, LEACHING				
58.01.	Wearing Surface:	Material:	BITUMINOUS (7")	Rating:	5
	FAIR - WIDE CRACKS, NOT FULL WIDTH				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - CRACKS, LEACHING				
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - TOPS OF PIER FOOTINGS AND WEST ABUTMENT EXPONSTRUCTION JOINT LEACHING.	OSED, W	EST PIER UPSTREAM BEARING RAVELING, EAST PIEF	RUPSTREAM	
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	5
	FAIR - AGGRADATION, LOCAL SCOUR AROUND PIERS, BANK E	EROSION	BEHIND SW WINGWALL		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	52	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	39	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	29 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200046 Bridge Number: 22-00047

Facility Carried: DUFFY RD Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 8 - TANGENT & LEVEL, CURVE EAST

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKING

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, PLACING RIPRAP AT SW CORNER.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 96.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH FROM ROAD



LOOKING EAST AT SCOUR ALONG THE NORTH



NBI Number: 2200049 Bridge Number: 22-00050

Facility Carried: KLERNER LN Feature(s) Intersected: SLATE Run Creek

<u>IDEN</u>	<u>TIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200049			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	SLATE Run Creek	11.	Mile Point (over):	0
7.	Facility Carried:	KLERNER LN	16.	Latitude:	38.33437
9.	Location:	00.10 N OF MT. TABOR RD	17.	Longitude:	-85.808929
<u>STRL</u>	ICTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	8 (UNKNOWN)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1983	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	753 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1109 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA	1			
48.	Maximum Span Length:	31.5 ft.	49.	Structure Length:	34 ft.
50A.	Sidewalk/Curb Left:	2.7 ft.	50B.	Sidewalk/Curb Right:	2.7 ft.
51.	Bridge Roadway Width:	32.2 ft.	52.	Deck Width (O-O)	40 ft.
32.	Approach Roadway Width:	32 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	15 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	32.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200049 Bridge Number: 22-00050

Facility Carried: KLERNER LN Feature(s) Intersected: SLATE Run Creek

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	17 (URBAN - COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - END JOINT SEAL DAMAGE, SPALLS W/ IN WEST GUTT WEST BRIDGE RAILING	ER WING	EXP. REIN., LONG. CRACK MIDDLE BEAM SPACING. N	MINOR DAMAGE TO	
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	7
	GOOD - MANY SMALL POPOUTS				
59.	Superstructure:	Material:	CONCRETE BOX BEAM	Rating:	7
	GOOD - SEEPAGE BETWEEN BEAMS				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - TOPS OF FOOTINGS EXPOSED, LONG. CRACKS AT B	EARINGS			
61.	Channel:	Material:	NATURAL ROCK & GRAVEL BOTTOM	Rating:	7
	GOOD - ROUGH SHALE WITH ROCK BOTTOM, FLOW TOWARD	S BOTH A	ABUTMENTS, OVERGROWN CHANNEL BANKS		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	78	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	65	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	42 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200049 Bridge Number: 22-00050

Facility Carried: KLERNER LN Feature(s) Intersected: SLATE Run Creek

APPRAISAL

67. Structural: 7
 68. Geometry: 6
 69. Underclearance: N

71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)

36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - UPGRADE & CURVE EACH WAY, DR NW & SE

Material: CONCRETE / BITUMINOUS

Comments: PORTIONS OF APPROACH GUARDRAIL MISSING, LONG. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S, PATCHING SPALLS ON DECK, AND REPLACING EXPANSION JOINT SEALS.

INSPECTION DATA

90. Date: 3/3/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 98.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST UPSTREAM



LOOKING SOUTH FROM ROAD



LOOKING NORTHEAST AT NORTH STONE ABUTMENT-



NBI Number: 2200050 Bridge Number: 22-00051
Facility Carried: BLACKISTON MILL RD Feature(s) Intersected: SILVER CREEK

IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200050			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	SILVER CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BLACKISTON MILL RD	16.	Latitude:	38.33429
9.	Location:	00.20 E PAYNE KOEHLER	17.	Longitude:	-85.794876
<u>STRU</u>	JCTURE DATA		ı		
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	02 (GIRDER)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1920	106.	Reconstructed:	1966
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	4441 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	6546 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	6 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	87.9 ft.	49.	Structure Length:	176 ft.
50A.	Sidewalk/Curb Left:	1.0 ft.	50B.	Sidewalk/Curb Right:	1.0 ft.
51.	Bridge Roadway Width:	21.9 ft.	52.	Deck Width (O-O)	24.1 ft.
32.	Approach Roadway Width:	23 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	21.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200050 Bridge Number: 22-00051
Facility Carried: BLACKISTON MILL RD Feature(s) Intersected: SILVER CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	17 (URBAN - COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION 58. Deck:

	SATIS - HAIRLINE CRACKS AND EFFLORESCENCE, WEST SPA	N NEAR SOUTH COPING BEAM		
58.01.	Wearing Surface:	Material: BITUMINOUS (2")	Rating:	4
	POOR - CRACKS OVER PIER AND AT ENDS, POTHOLES FILLE	D WITH HMA, CRACKS THROUGHOUT, ROUGH UNEVEN		
59.	Superstructure:	Material: CONCRETE	Rating:	7
	GOOD - NO MAJOR DEFECTS NOTED			
60.	Substructure:	Material: CONC.	Rating:	4
	POOR - OPEN JOINTS BETWEEN STONES, EROSION, STONES ABUTMENTS AND PIERS WERE SPRAYED WITH THIN COAT O CONCRETE CAP OVER THE UPSTREAM NOSE OF PIER.	S IN UPSTREAM END OF PIER BROKEN WITH SOME MISSING P F GUNITE IN PAST TO COVER AND PROTECT STONE, CRACKS		
61.	Channel:	Material: NATURAL	Rating:	5
	FAIR - BRUSHY BANKS, EROSION BEHIND WINGS, EROSION A CONCRETE DAM UPSTREAM	T NORTHWEST, NORTHEAST AND SOUTHWEST WINGS, APP	ROXIMATELY 8' HIGH	
62.	Culvert/Ret:	Material: N/A	Rating:	Ν

Material: CONCRETE

Rating:

LOAD RATING AND POSTING

N/A

0 (FIELD EVAL AND ENG JUDGEMENT)	Oper Rating Method:	63.	0 (UNKNOWN)	Design Load:	31.
0 (FIELD EVAL AND ENG JUDGEMENT)	Inv Rating Method:	65.	36	Operating Rating:	64.
Tons	Tons Posted:	66C.	36	Inventory Rating:	66.
	Date Posted/Closed:	66D.	20 Tons	Gross Tons or H Rating:	66B.
5 (EQUAL TO OR ABOVE LEGAL LOADS)	Bridge Posting:	70.	A (OPEN)	Open, Posted, or Closed:	41.

NBI Number: 2200050 Bridge Number: 22-00051 Facility Carried: BLACKISTON MILL RD Feature(s) Intersected: SILVER CREEK

APPRAISAL

Structural: 4 2 68. Geometry: 69 Underclearance: Ν Waterway Adequacy:

Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS) 36A.

0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) Traffic Safety Features (Transitions):

Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS) 36C. Traffic Safety Features (Approach Guardrail Ends): 36D. 1 (MEETS ACCEPTABLE STANDARDS)

3 - CURVE EACH END, DIP SO., HILL NORTH Roadway Alignment:

Material: **BITUMINOUS**

LONGITUDINAL CRACKS AND PATCHES, SETTLING AND ROUGH AT BRIDGE ENDS

Scour Critical Bridges 4 (STABLE - ACTION NEEDED)

PROPOSED IMPROVEMENTS

31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUBSTRUCTURE.) 75A. Type of Work:

1 (CONTRACT) 76. Improvement Length: 210 ft. 94. Bridge Improvement Costs: 983 x 1000 95. Roadway Improvement Costs: 467 x 1000 96. Total Project Cost: 1830 x 1000

Year of Cost Estimate: 97 2020

RECOMMENDED MAINTENANCE

UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING AND ALL BRIDGE END MARKERS. PLACING RIPRAP AT UPSTREAM END OF PIER SOUTHWEST CORNER, AND NORTHEAST WING, AND REPAIRING CONCRETE AT UPSTREAM END NOSE OF PIER.

INSPECTION DATA

3/3/2020 90. 91. Des. Inspection Frequency: 12 Months Critical Feature Inspection: B: 92. Α: Ν Ν Ν 93. Α: B:

Unofficial Sufficiency Rating: 44.9

Unofficial Structural and Functional Classification:



LOOKING SOUTH FROM ROAD




LOOKING WEST DOWNSTREAM



LOOKING NORTH FROM ROAD



LOOKING EAST AT EXPOSED TOP OF FOOTING ON



NBI Number: 2200051 Bridge Number: 22-00055

Facility Carried: CHAPEL LN Feature(s) Intersected: LEWIS BR OF JACOABS CR

		. ,			
				<u>ITIFICATION</u>	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200051	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	LEWIS BR OF JACOABS CR	Feat Intersected:	6.
38.36563	Latitude:	16.	CHAPEL LN	Facility Carried:	7.
-85.7939	Longitude:	17.	01.10 S OF GRANTLINE RD	Location:	9.
				JCTURE DATA	STRU
000	Structure Type - Approach:	44.	1 (CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			8 (UNKNOWN)	Protection	108C.
				OF SERVICE	AGE
2017	Reconstructed:	106.	1983	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	2896 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	4265 VPD	Future ADT:	114.
3 mi.	Bypass Detour Length:	19.	6 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEOI</u>
27.5 ft.	Structure Length:	49.	24.9 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
27.9 ft.	Deck Width (O-O)	52.	27.3 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	22 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	15 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	27.5 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
0 ft.	Lateral Left:	56.	0 ft.	Lateral Right:	55B.

NBI Number: 2200051 Bridge Number: 22-00055

Facility Carried: CHAPEL LN Feature(s) Intersected: LEWIS BR OF JACOABS CR

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - FILLED POTHOLES				
58.01.	Wearing Surface:	Material:	MONOLITHIC CONCRETE	Rating:	6
	SATIS - FILLED POTHOLES, SPALLS ON SURFACE, MAP CRAC	KING			
59.	Superstructure:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - HL CRACKS IN BOTTOM OF SLAB WITH LIGHT EFFL. N	EAR CEN	TERLINE.		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - SOUTH END OF EAST FOOTING EXPOSED				
61.	Channel:	Material:	NATURAL ROCKS	Rating:	5
	FAIR - VERY BRUSHY AROUND BRIDGE, BANK EROSION DOW	NSTREAN	Л		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

CE FACTOR (LRFR))
Tons
OVE LEGAL LOADS)

NBI Number: 2200051 Bridge Number: 22-00055

Facility Carried: CHAPEL LN Feature(s) Intersected: LEWIS BR OF JACOABS CR

APPRAISAL

67. Structural: 7
 68. Geometry: 3
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - CURVE AND HILL EACH WAY

Material: BITUMINOUS

Comments: NEWER BIT AT ENDS, LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE NEEDED.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 80.1

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING NORTH FROM ROAD




LOOKING EAST FROM CHANNEL



LOOKING SOUTH FROM ROAD



TYPICAL HAIRLINE CRACK



NBI Number: 2200052 Bridge Number: 22-00057
Facility Carried: HIGHWATER RD Feature(s) Intersected: MIDDLE CREEK

				<u>ITIFICATION</u>	IDEN
52326 (NEW ALBANY)	City/Town:	4.	185 (INDIANA)	State:	1.
			2200052	NBI Number:	8.
	Border Bridge:	98.	1-5-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	MIDDLE CREEK	Feat Intersected:	6.
38.2806	Latitude:	16.	HIGHWATER RD	Facility Carried:	7.
-85.863548	Longitude:	17.	00.10 S OF CORYDON PIKE	Location:	9.
				JCTURE DATA	STRU
000	Structure Type - Approach:	44.	1 (CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	11 (DECK ARCH)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	2 (CONCRETE PRECAST)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	2003	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	1655 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	2439 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
29.5 ft.	Structure Length:	49.	27.5 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
28 ft.	Deck Width (O-O)	52.	27.7 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	17 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	25 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	27.7 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
	Lateral Left:	56.	0 ft.	Lateral Right:	55B.

NBI Number: 2200052 Bridge Number: 22-00057
Facility Carried: HIGHWATER RD Feature(s) Intersected: MIDDLE CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	19 (URBAN - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - HAIRLINE TRANSVERSE CRACKS				
58.01.	Wearing Surface:	Material:	MONOLITHIC CONCRETE	Rating:	6
	SATIS - LOOSE GRAVEL & DEBRIS ON DECK				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - HL TRANS. CRACKS AT 12" SPACING AT CENTER OF	EACH SEG	SMENT		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - SMALL SPALLS ON EDGES				
61.	Channel:	Material:	NATURAL & RIPRAP	Rating:	7
	GOOD - SLIGHT AGGRADATION, TRASH				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200052 Bridge Number: 22-00057
Facility Carried: HIGHWATER RD Feature(s) Intersected: MIDDLE CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - CURVE & HILL SOUTH, HUMP OVER RR NORTH

Material: BITUMINOUS

Comments: ROUGH, SETTLEMENT AT BRIDGE ENDS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/5/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 85.7
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



BEAM SEEPAGE NEAR CENTERLINE BRIDGE



NBI Number: 2200053 Bridge Number: 22-00058
Facility Carried: BUDD RD Feature(s) Intersected: FRENCH CREEK

				1, 11 2022 112	
				<u>ITIFICATION</u>	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200053	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	FRENCH CREEK	Feat Intersected:	6.
38.25898	Latitude:	16.	BUDD RD	Facility Carried:	7.
-85.861931	Longitude:	17.	00.30 S OF HIGHWATER RD	Location:	9.
			1	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	05 (ADJACENT BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	2 (CONCRETE PRECAST)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1976	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	1376 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	2027 VPD	Future ADT:	114.
7 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
37.9 ft.	Structure Length:	49.	35.9 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
32.3 ft.	Deck Width (O-O)	52.	30.3 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	24 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	25 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N.I.	Min Vert Clear Code:	54A.	30.3 ft.	Total Horiz. Clearance:	47.
N					
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200053 Bridge Number: 22-00058
Facility Carried: BUDD RD Feature(s) Intersected: FRENCH CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	08 (RURAL - MINOR COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.
		11			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - MINOR DEBRIS IN GUTTERS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (5.5")	Rating:	7
	GOOD - NOT FULL WIDTH				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - SMALL SPALLS BOTTOM BEAMS, SEEPAGE AND EFFL	BETWEE	EN BEAMS		
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - FULL HEIGHT HL CRACKS IN N ABUT. UNDER BEAM 3 CRACK AT NW AND SW CORNERS	AND 7, FL	ILL HEIGHT HL CRACKS IN S ABUT, UNDER BEAM 3 AI	ND 5, VERT. HL	
61.	Channel:	Material:	NATURAL GRAVEL	Rating:	6
	SATIS - FLOW TOWARDS SOUTH ABUTMENT				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	79	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	55	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	37 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200053 Bridge Number: 22-00058
Facility Carried: BUDD RD Feature(s) Intersected: FRENCH CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, UPGRADE TO HILL NORTH

Material: BITUMINOUS
Comments: EDGE DROP-OFFS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)
75B. Work Done By: ()
76. Improvement Length: 0 ft.

94. Bridge Improvement Costs: 0 x 1000

95. Roadway Improvement Costs: 0 x 1000

96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 91.5
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING EAST FROM CHANNEL



LOOKING NORTH FROM ROAD



LOOKING WEST AT SILT BUILDUP



NBI Number: 2200107 Bridge Number: 22-00060 B

Facility Carried: BORDEN ROAD Feature(s) Intersected: BRANCH OF JERSEY PARK CR

IDEN	ITIFICATION	1			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200107			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BRANCH OF JERSEY PARK CR	11.	Mile Point (over):	0
7.	Facility Carried:	BORDEN ROAD	16.	Latitude:	38.38759
9.	Location:	00.10 N OF RUFFING ROAD	17.	Longitude:	-85.96672
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	6 (CONT PRESTR CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2013	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	567 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	836 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	47 ft.	49.	Structure Length:	48.4 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27 ft.	52.	Deck Width (O-O)	31 ft.
32.	Approach Roadway Width:	20 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	26.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200107 Bridge Number: 22-00060 B

Facility Carried: BORDEN ROAD Feature(s) Intersected: BRANCH OF JERSEY PARK CR

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	8
	VERY GOOD - LONG. CRACKS			
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	7
	GOOD - GRAVEL IN GUTTERS, LONG. CRACKS			
59.	Superstructure:	Material: CONCRETE	Rating:	9
	EXCELLENT - NO MAJOR DEFECTS			
60.	Substructure:	Material: CONCRETE	Rating:	8
	VERY GOOD - NW & SW CORNERS TOP OF FTG. EXP., VERTIC	AL HAIRLINE CRACKS		
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	6
	SATIS - SILT GRAVEL BUILDUP			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200107 Bridge Number: 22-00060 B

Facility Carried: BORDEN ROAD Feature(s) Intersected: BRANCH OF JERSEY PARK CR

APPRAISAL

67. Structural: 8
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, CURVE TO S, DRIVES IN SW & NE

Material: BITUMINOUS
Comments: LONG. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND CLEANING DEBRIS FROM DECK AND CLEARING SILT/ GRAVEL FROM CHANNEL.

INSPECTION DATA

 90.
 Date:
 3/5/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 95.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING SOUTH FROM ROAD



LOOKING EAST FROM CHANNEL



SOUTH AT SOUTH PIER



NBI Number: 2200055 Bridge Number: 22-00061
Facility Carried: BUDD RD Feature(s) Intersected: KNOB CREEK

IDEN	TIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200055			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	KNOB CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BUDD RD	16.	Latitude:	38.24371
9.	Location:	00.00 INT MCARTHY/KNOB RD	17.	Longitude:	-85.896011
STRU	ICTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	'			
27.	Year Built:	2004	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	793 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1168 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	9 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	37.5 ft.	49.	Structure Length:	85.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	29 ft.	52.	Deck Width (O-O)	32 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	35 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	29 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	Oft.

NBI Number: 2200055 Bridge Number: 22-00061
Facility Carried: BUDD RD Feature(s) Intersected: KNOB CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
102. 110. 21.	Direction of Traffic: Des. Nat. Network: Maint. Responsibility:	2 (2-WAY TRAFFIC) 0 02 (COUNTY HIGHWAY AGENCY)	103.	Temporary Structure Des: Toll:	3 (ON FREE ROAD-NO TOLL)

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - HAIRLINE CRACKS				
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	7
	GOOD - RANDOM HAIRLINE CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
61.	Channel:	Material:	RIPRAP & NATURAL GRAVEL BOTTOM	Rating:	7
	GOOD - AGGRADATION, SMALL TREES GROWING IN CHANNEL	_ DOWNS	TREAM		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	75	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	55	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	41 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200055 Bridge Number: 22-00061
Facility Carried: BUDD RD Feature(s) Intersected: KNOB CREEK

APPRAISAL

67. Structural: 8
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - CURVE EACH END, BRIDGE ON SLIGHT HUMP

Material: BITUMINOUS

Comments: NEW BITUMINOUS OVERLAY

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NE & SW B.E.M.'S

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 92.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



LOOKING EAST AT EAST PIER



NBI Number: 2200056 Bridge Number: 22-00062
Facility Carried: OLD RIVER RD Feature(s) Intersected: MIDDLE CREEK

	Intersected: MIDDLE CREEK	iture(s)	Fe	ity Carried: OLD RIVER RD	Facil
				<u>TIFICATION</u>	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200056	NBI Number:	3.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:).
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	MIDDLE CREEK	Feat Intersected:	5.
38.22569	Latitude:	16.	OLD RIVER RD	Facility Carried:	7.
-85.85272	Longitude:	17.	00.30 E OF HWY 111	Location:	9.
				ICTURE DATA	<u>STRU</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	06 (SPREAD BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			(EPOXY COATED REINFORCING)	Protection 1	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1999	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	421 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	620 VPD	Future ADT:	114.
5 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEOI</u>
158 ft.	Structure Length:	49.	54 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
29 ft.	Deck Width (O-O)	52.	25.8 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	24 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	25 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	25.8 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

0 ft.

56.

Lateral Left:

0 ft.

55B. Lateral Right:

NBI Number: 2200056 Bridge Number: 22-00062
Facility Carried: OLD RIVER RD Feature(s) Intersected: MIDDLE CREEK

NAVIGA [*]	TION
---------------------	------

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	8
	VERY GOOD - DEBRIS IN GUTTERS & DRAINS				
59.	Superstructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	8
	VERY GOOD - STEEP BANKS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	70	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	70	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	52 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200056 Bridge Number: 22-00062
Facility Carried: OLD RIVER RD Feature(s) Intersected: MIDDLE CREEK

APPRAISAL

67.	Structural:	8
68.	Geometry:	5
69.	Underclearance:	Ν
71.	Waterway Adequacy:	7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - CURVE EACH END, NEARLY LEVEL

Material: CONCRETE / BITUMINOUS

Comments: CRACKS IN APPROACH SLABS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A.	Type of Work:	(NO W	ORK NEEDED.)
75B.	Work Done By:	0	
76.	Improvement Length:		0 ft.
94.	Bridge Improvement Costs:		0 × 1000
95.	Roadway Improvement Costs:		0 × 1000
96.	Total Project Cost:		0 × 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND REMOVING DEBRIS FROM GUTTERS.

INSPECTION DATA

90.	Date:	3/5/2020	91.	Des. Inspection	reque	ency:	24 Mor	nths
92.	Critical Feature Inspec	tion:	A:	N	B:	N	C:	Ν
93.	Date:		A:		B:		C:	

Unofficial Sufficiency Rating: 94.3
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING NORTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



LOOKING EAST AT ABUTMENT



NBI Number: 2200057 Bridge Number: 22-00063
Facility Carried: FIVE MILE LN Feature(s) Intersected: KNOB CREEK

	, = = =				
IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200057			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	KNOB CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	FIVE MILE LN	16.	Latitude:	38.21503
9.	Location:	00.10 W OF DAILY RD	17.	Longitude:	-85.893494
STRU	JCTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE	·			
27.	Year Built:	1930	106.	Reconstructed:	2014
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	140 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	207 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	6 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	53.5 ft.	49.	Structure Length:	57.1 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	19.9 ft.	52.	Deck Width (O-O)	20.2 ft.
32.	Approach Roadway Width:	17 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	19.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200057 Bridge Number: 22-00063
Facility Carried: FIVE MILE LN Feature(s) Intersected: KNOB CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			Į.		

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - CRACK AT SOUTHEAST CORNER				
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	7
	GOOD - SOME MINOR WEAR AND SHALLOW TINING, CRACK A	AT SOUTHI	EAST CORNER		
59.	Superstructure:	Material:	PRESTR. CONC. BOX BMS	Rating:	8
	VERY GOOD - MINOR CONSTRUCTION SCRAPES IN CONCRET	TE			
60.	Substructure:	Material:	CONCRETE	Rating:	4
	POOR - SCOUR AT EAST ABUTMENT WITH EAST FOOTING EX ABUTMENT WALL, NORTH END OF EAST ABUTMENT APPEAR:			SOUTHEAST	
61.	Channel:	Material:	NATURAL	Rating:	5
	FAIR - HEAVY EROSION ON BANKS UP AND DOWNSTREAM, B	BEGINNING	TO UNDERCUT.		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	9 (HS 25 OR GREATER)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	90	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	67	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	53 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200057 Bridge Number: 22-00063
Facility Carried: FIVE MILE LN Feature(s) Intersected: KNOB CREEK

APPRAISAL

67. Structural: 4
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - IRREGULAR VERT. & HORIZ. ALIGN. BOTH WAYS, DIP AT E APPR.

Material: BITUMINOUS

Comments: NEW OVERLAY

113. Scour Critical Bridges: 3 (SCOUR CRITICAL - UNSTABLE)

Comments: SCOUR ALONG E. ABUT., NEW RIPRAP PLACED IN 2019. SLIGHT VERTICAL MISALIGNMENT OF

THE E ABUT.

PROPOSED IMPROVEMENTS

75A. Type of Work: 35 (REHABILITATE EAST SUBSTRUCTURE DUE TO SETTLEMENT.)

1 (CONTRACT) Work Done By: 76. Improvement Length: 57 ft. 94. Bridge Improvement Costs: 131 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 382 x 1000 97. Year of Cost Estimate: 2020

RECOMMENDED MAINTENANCE

UNTIL REHABILITATION, MONITOR NEW RIPRAP THAT WAS PLACED ALONG EAST ABUTMENT IN 2019

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 12 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 5/1/2014
 B:
 9/21/2017
 C:

Unofficial Sufficiency Rating: 55.4

Unofficial Structural and Functional Classification: 1 (STRUCTURALLY DEFICIENT)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



LOOKING WEST AT EAST PIER



NBI Number: 2200058 Bridge Number: 22-00064
Facility Carried: SEVEN MILE LN Feature(s) Intersected: KNOB CREEK

				, -	
				ITIFICATION	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200058	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	KNOB CREEK	Feat Intersected:	6.
38.19983	Latitude:	16.	SEVEN MILE LN	Facility Carried:	7.
-85.887642	Longitude:	17.	00.10 W OF SR 111	Location:	9.
				JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	2 (CONTINUOUS CONCRETE)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
1993	Reconstructed:	106.	1938	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	244 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	359 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEOI</u>
70.5 ft.	Structure Length:	49.	23.8 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
24 ft.	Deck Width (O-O)	52.	23.8 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	23 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	30 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	23.8 ft.	Total Horiz. Clearance:	47.
		E 4 D	N	Min Late CL Dight Codo	EE A
Oft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200058 Bridge Number: 22-00064
Facility Carried: SEVEN MILE LN Feature(s) Intersected: KNOB CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - LIGHT SCALING, POPOUTS, SPALLING AT EDGES				
58.01.	Wearing Surface:	Material:	MONOLITHIC CONCRETE	Rating:	7
	GOOD - LIGHT SURFACE WEAR, LIGHT SCALING, POPOUTS, C	RACKS 1	7"		
59.	Superstructure:	Material:	CONCRETE SLAB	Rating:	7
	GOOD - HONEYCOMB ON BOTTOM, 2' HONEYCOMB AREA ON	N SIDE O	F UNDERSIDE OF SUPERSTRUCTURE, CRACKS 17"		
60.	Substructure:	Material:	CONC ABUTS, TIMBER PILE PIERS	Rating:	6
	SATIS - SOME SPLINTERING IN PILES, SOME MINOR ROT THRECAP	OUGHOU	T, NO MAJOR DETERIORATION, OLD ABUTMENTS WIT	TH NEWER WIDENED	
61.	Channel:	Material:	NATURAL	Rating:	6
	SATIS - DRIFT, NO PROTECTION, MINOR SCOUR AT WEST PIE	R			
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	1 (LOAD FACTOR (LF))
64.	Operating Rating:	65	65.	Inv Rating Method:	1 (LOAD FACTOR (LF))
66.	Inventory Rating:	39	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	19 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200058 Bridge Number: 22-00064
Facility Carried: SEVEN MILE LN Feature(s) Intersected: KNOB CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 3

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, ON GRADE

Material: BITUMINOUS

Comments: BIT WEDGE NOW AT WEST END; CRACKING IN APPROACHES

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & NW B.E.M.'S

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 87.4

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING NORTH FROM ROAD




LOOKING WEST FROM CHANNEL



LOOKING SOUTH FROM ROAD



LOOKING SOUTH AT SOUTH PIER



NBI Number: 2200059 Bridge Number: 22-00065
Facility Carried: DAILY RD Feature(s) Intersected: KNOB CREEK

			Ī	NTIFICATION .	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200059	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	KNOB CREEK	Feat Intersected:	6.
38.21349	Latitude:	16.	DAILY RD	Facility Carried:	7.
-85.891663	Longitude:	17.	00.10 S FIVE MILE LANE	Location:	9.
			1	UCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	7 (TIMBER)	Structure Type - Main Span:	43A.
3	Number of Spans - Main:	45.	01 (SLAB)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	8 (WOOD OR TIMBER)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1981	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2014	ADT Year Over:	30.	186 VPD	ADT - Over:	29.
2034	Future ADT Year:	115.	274 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
66 ft.	Structure Length:	49.	23.3 ft.	Maximum Span Length:	48.
0.3 ft.	Sidewalk/Curb Right:	50B.	0.3 ft.	Sidewalk/Curb Left:	50A.
25.7 ft.	Deck Width (O-O)	52.	24.3 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	18 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	20 Degree(s)	Skew:	34.
0 (110 1 17 (111)		53.	99.99	Defense Vertical Clearance:	10.
99.99 ft.	Vertical Clearance/Deck:				
	Vertical Clearance/Deck: Min Vert Clear Code:	54A.	25 ft.	Total Horiz. Clearance:	47.
99.99 ft.		54A. 54B.	25 ft. N	Total Horiz. Clearance: Min Latr. Cl. Right - Code:	47. 55A.

NBI Number: 2200059 Bridge Number: 22-00065
Facility Carried: DAILY RD Feature(s) Intersected: KNOB CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: TIMBER	Rating:	6					
	SATIS - MINOR SPLITTING AND DECAY								
58.01.	Wearing Surface:	Material: BITUMINOUS (1")	Rating:	5					
	FAIR - TRANSVERSE AND LONGITUDINAL CRACKS								
59.	Superstructure:	Material: TIMBER	Rating:	6					
	SATIS - MINOR SPLITTING OF SLAB ON UNDERSIDE, METAL S	TRAPS HANGING DOWN							
60.	Substructure:	Material: TIMBER	Rating:	6					
	SATIS - EROSION AT BANK OF ABUTMENT, UNDERMINING AT SW WINGWALL, MINOR SPLITTING AT SE WINGWALL PILE AND NORTH ABUTMENT END PILES, MINOR ROT AT THE SOUTH ABUTMENT MUDWALL, SOME MINOR DECAY AT WATERLINE OF PILES								
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	5					
	FAIR - MODERATE EROSION ON BANKS UPSTREAM AND DOWNSTREAM, THE DOWNSTREAM BANKS ARE BEGINNING TO UNDERCUT.								
62.	Culvert/Ret:	Material: N/A	Rating:	Ν					
	N/A								

3 (LOAD RESISTANCE FACTOR (LRFR))	Oper Rating Method:	5 (HS 20) 63.	Design Load: 5 (HS	31. Design Load:	31.
3 (LOAD AND RESISTANCE FACTOR (LRFR))	Inv Rating Method:	80 65.	Operating Rating:	64. Operating Ra	64.
Tons	Tons Posted:	59 66C.	Inventory Rating:	66. Inventory Rat	66.
	Date Posted/Closed:	35 Tons 66D.	Gross Tons or H Rating: 35	66B. Gross Tons o	66B.
5 (EQUAL TO OR ABOVE LEGAL LOADS)	Bridge Posting:	A (OPEN) 70.	Open, Posted, or Closed: A (OF	41. Open, Posted	41.

NBI Number: 2200059 Bridge Number: 22-00065
Facility Carried: DAILY RD Feature(s) Intersected: KNOB CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - BR. ON HUMP, DIPS & CURVES BOTH WAYS

Material: BITUMINOUS

Comments: SETTLED AT BRIDGE ENDS, CRACKS, POT HOLES

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

(NO WORK NEEDED.) 75A. Type of Work: Work Done By: 76. Improvement Length: 0 ft. 94. Bridge Improvement Costs: 0 x 1000 95. Roadway Improvement Costs: 0 x 1000 Total Project Cost: 96. 0 x 1000

RECOMMENDED MAINTENANCE

Year of Cost Estimate:

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE NW & SW B.E.M.'S, REPLACE FILL BEHIND S ABUTMENT, AND PLACING RIPRAP ON SOUTH ABUTMENT.

INSPECTION DATA

97.

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 91.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH FROM CHANNEL



LOOKING WEST FROM ROAD



LOOKING EAST AT SUPERSTRUCTURE AND EAST



NBI Number: 2200087 Bridge Number: 22-00066

Facility Carried: RIDGEVIEW DR Feature(s) Intersected: LITTLE INDIAN CREEK

			. ,		
IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200087			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	LITTLE INDIAN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	RIDGEVIEW DR	16.	Latitude:	38.36349
9.	Location:	00.00 INT OF CHAMPION RD	17.	Longitude:	-85.853989
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE	'			
27.	Year Built:	1976	106.	Reconstructed:	2014
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	317 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	467 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	199 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	37 ft.	49.	Structure Length:	40 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27.2 ft.	52.	Deck Width (O-O)	28 ft.
32.	Approach Roadway Width:	23 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	27.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200087 Bridge Number: 22-00066

Facility Carried: RIDGEVIEW DR Feature(s) Intersected: LITTLE INDIAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	4" CONC. DECK	Rating:	7
	GOOD - LONGITUDINAL HAIRLINE CRACKS IN SURFACE				
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	7
	GOOD - HAIRLINE CRACKS				
59.	Superstructure:	Material:	21" PRESTRESSED CONCRETE BOX BEAMS	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS, 1 TIE ROD BOLT VISIBLE	AT N COP	ING AND 2 TIE ROD BOLTS VISIBLE AT S COPING		
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - SOUTH FOOTING EXPOSED, KEYED INTO SOLID ROCK	K, N ABUT	MENT 3 VERT. HL CRACKS, S ABUTMENT 2 VERT. HL	CRACKS	
61.	Channel:	Material:	NATURAL ROCK BOTTOM & RIPRAP	Rating:	6
	SATIS - MINOR BANK EROSION				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	63	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	46	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	35 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200087 Bridge Number: 22-00066

Facility Carried: RIDGEVIEW DR Feature(s) Intersected: LITTLE INDIAN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - CURVE AND UPGRADE TO EAST, "T" INTERSECTION TO WEST

Material: BITUMINOUS

Comments: LONG. CRACKS, SETTLING AT EAST END

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments: FOOTINGS EXPOSED BUT FOUNDED ON ROCK

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NE NW & SW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 89.5
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING EAST FROM ROAD



LOOKING SOUTH DOWNSTREAM



NBI Number: 2200086 Bridge Number: 22-00070 Facility Carried: SPRING ST Feature(s) Intersected: SILVER CREEK

	,				• •
IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200086			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	SILVER CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SPRING ST	16.	Latitude:	38.30083
9.	Location:	00.02 N OF HWY 62	17.	Longitude:	-85.79162
<u>STRU</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Cor	nst. 11 (DECK ARCH)	45.	Number of Spans - Main:	4
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE				
27.	Year Built:	1920	106.	Reconstructed:	2006
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	5445 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	8026 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	154 ft.	49.	Structure Length:	286 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	24 ft.	52.	Deck Width (O-O)	27.3 ft.
32.	Approach Roadway Width:	24 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200086 Bridge Number: 22-00070
Facility Carried: SPRING ST Feature(s) Intersected: SILVER CREEK

NAVIGATION

38.	Navigational Control:	1	40.	Navigational Horizontal Clearance:	154 ft.
39.	Navigational Vertical Clearance:	45 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:	5			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	17 (URBAN - COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	2 (ELIGIBLE FOR NATIONAL REGISTER)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8
	VERY GOOD - DEBRIS IN GUTTERS, DRAINS PLUGGED				
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	8
	VERY GOOD - HAIRLINE LONGITUDINAL CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - BEAM END CHIPS				
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - SPALLS ON MAIN SPAN ARCH, HL CRACKS ON N	NOSE OF	PIERS, HL CRACKS AT BASE OF SPANDRELS		
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	8
	VERY GOOD - BRUSHY BANKS, EROSION EAST				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200086 Bridge Number: 22-00070
Facility Carried: SPRING ST Feature(s) Intersected: SILVER CREEK

APPRAISAL

67.	Structural:	8
68.	Geometry:	2
69.	Underclearance:	Ν
71.	Waterway Adequacy:	9

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - TANGENT & LEVEL

Material: CONCRETE / BITUMINOUS

Comments: SETTLED SLIGHTLY

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A.	Type of Work:	(NO WORK	(NEEDED.)
75B.	Work Done By:	()	
76.	Improvement Length:		0 ft.
94.	Bridge Improvement Costs:		0 x 1000
95.	Roadway Improvement Costs:		0 x 1000
96.	Total Project Cost:		0 x 1000
97.	Year of Cost Estimate:		

RECOMMENDED MAINTENANCE

RECOMMEND CLEANING DRAINS, AND PLACING RIPRAP ALONG NW WING.

INSPECTION DATA

90.	Date:	3/4/2020	91.	Des. Inspection	n Frequ	iency:	24 Mo	nths
92.	Critical Feature Inspe	ction:	A:	Ν	B:	N	C:	Ν
93.	Date:		A:		B:		C:	

Unofficial Sufficiency Rating: 80.3

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING NORTH FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



LOOKING SOUTH FROM CHANNEL



NBI Number: 2200060 Bridge Number: 22-00071
Facility Carried: TWO MILE LN Feature(s) Intersected: FRENCH CREEK

IDEN	ITIFICATION	1			
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200060			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FRENCH CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	TWO MILE LN	16.	Latitude:	38.25508
9.	Location:	00.10 E OF BUDD RD	17.	Longitude:	-85.860733
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1934	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	810 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1193 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	7 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	20.2 ft.	49.	Structure Length:	24 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	23.5 ft.	52.	Deck Width (O-O)	24 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	30 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	23.5 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200060 Bridge Number: 22-00071
Facility Carried: TWO MILE LN Feature(s) Intersected: FRENCH CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - EXCESSIVE WEARING SURFACE				
58.01.	Wearing Surface:	Material:	BITUMINOUS (3.5")	Rating:	7
	GOOD - CRACKS AT ENDS & CENTERLINE				
59.	Superstructure:	Material:	CONCRETE	Rating:	7
	GOOD - NO MAJOR DEFECTS				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - HAIRLINE VERTICAL CRACKS NORTH ABUTMENT, TORWIDENING AT EAST	PS OF FOO	OTINGS PARTIALLY EXPOSED, OLDER ABUTMENTS T	O WEST AND NEWER	?
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	7
	GOOD - FLOW TOWARD SOUTH ABUTMENT				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200060 Bridge Number: 22-00071 Facility Carried: TWO MILE LN Feature(s) Intersected: FRENCH CREEK

APPRAISAL

Structural: 68. 4 Geometry: 69. Underclearance: Ν Waterway Adequacy:

Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS) 36A.

Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36C.

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

Roadway Alignment: 6 - BRIDGE ON LONG HUMP, MANY SMALL CURVES

Material: BITUMINOUS

CRACKS, SETTLED BEHIND NW WING

113. Scour Critical Bridges 5 (STABLE - WITHIN LIMITS)

PROPOSED IMPROVEMENTS

(NO WORK NEEDED.) 75A. Type of Work:

Work Done By:

76. Improvement Length: 0 ft. 94. Bridge Improvement Costs: 0 x 1000 95. Roadway Improvement Costs: 0 x 1000 Total Project Cost: 96. 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE & SW B.E.M.'S, AND PLACING RIPRAP AT SE CORNER.

INSPECTION DATA

90. 3/3/2020 91. Des. Inspection Frequency: 24 Months 92. Critical Feature Inspection: Α: B:

93. Α:

Unofficial Sufficiency Rating: Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



LOOKING NORTH AT ABUTMENT



NBI Number: 2200061 Bridge Number: 22-00072

Facility Carried: EVANS-JACOBI RD Feature(s) Intersected: BRANCH LITTLE INDIAN CR

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200061			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BRANCH LITTLE INDIAN CR	11.	Mile Point (over):	0
7.	Facility Carried:	EVANS-JACOBI RD	16.	Latitude:	38.33715
9.	Location:	00.10 S OF JOHN PECTOL	17.	Longitude:	-85.961433
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	8 (UNKNOWN)			
AGE	OF SERVICE				
27.	Year Built:	1981	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	421 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	621 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	2 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	39 ft.	49.	Structure Length:	42 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	27.9 ft.	52.	Deck Width (O-O)	28.2 ft.
32.	Approach Roadway Width:	21 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	27.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200061 Bridge Number: 22-00072

Facility Carried: EVANS-JACOBI RD Feature(s) Intersected: BRANCH LITTLE INDIAN CR

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: PRESTR. CONC. BOX BEAMS	Rating:	7
	GOOD - LIGHT SCALING, POPOUTS			
58.01.	Wearing Surface:	Material: BITUMINOUS (5")	Rating:	6
	SATIS - NOT FULL WIDTH, CRACKS			
59.	Superstructure:	Material: PRESTR. CONC. BOX BEAMS	Rating:	7
	GOOD - SMALL SPALLS ON BEAM EDGES			
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - VERTICAL CRACKS, LEACHING, TOP OF FOOTING EX	POSED AT BOTH ABUTMENTS		
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	6
	SATIS - AGGRADATION, MINOR DRIFT, FLOW TOWARDS SE C	CORNER		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	69	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	50	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	41 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200061 Bridge Number: 22-00072

Facility Carried: EVANS-JACOBI RD Feature(s) Intersected: BRANCH LITTLE INDIAN CR

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)

36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT & LEVEL, "T" INT. N., HILL S.

Material: BITUMINOUS

Comments: NO MAJOR DEFECTS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:

94. Bridge Improvement Costs:

95. Roadway Improvement Costs:

96. Total Project Cost:

97. O ft.

98. Total Project Cost:

98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/ END TREATMENT.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 94.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



LOOKING EAST AT UNDERSIDE



NBI Number: 2200062 Bridge Number: 22-00073

Facility Carried: CROWDER RD Feature(s) Intersected: RICHLAND CREEK

			. ,		
<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200062			
5.	Inventory Route On:	1-4-2- 320-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	RICHLAND CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	CROWDER RD	16.	Latitude:	38.34701
9.	Location:	00.10 E G'TOWN-GREENVLE	17.	Longitude:	-86.003487
STRU	JCTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	0 (NONE)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2003	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	98 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	144 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	199 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	27.8 ft.	49.	Structure Length:	30 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	20.9 ft.	52.	Deck Width (O-O)	21.1 ft.
32.	Approach Roadway Width:	16 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	20.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.
		·			

NBI Number: 2200062 Bridge Number: 22-00073

Facility Carried: CROWDER RD Feature(s) Intersected: RICHLAND CREEK

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE BOX BEAM	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - NOT FULL WIDTH, LONGITUDINAL CRACKS				
59.	Superstructure:	Material:	CONCRETE BOX BEAM	Rating:	8
	VERY GOOD - SEEPAGE BETWEEN BEAMS				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - 3 HL VERTICAL CRACKS AT BOTH ABUTS				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	8
	VERY GOOD - BRUSHY STREAM BANKS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	52	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	39	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	24 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200062 Bridge Number: 22-00073

Facility Carried: CROWDER RD Feature(s) Intersected: RICHLAND CREEK

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 5

 69.
 Underclearance:
 N

71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - TANGENT, UPGRADE TO EAST, INT. TO WEST

Material: BITUMINOUS

Comments: UNDERMINED, TRANSVERSE CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. National Project Cost:
98. Total Project Cost:
99. National Project Cost:
90. K 1000
90. National Project Cost:
90.

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT.

INSPECTION DATA

 90.
 Date:
 3/2/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 90.1
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH FROM CHANNEL



LOOKING EAST FROM ROAD



EAST ABUTMENT AND UNDERSIDE



NBI Number: 2200063 Bridge Number: 22-00076
Facility Carried: TWO MILE LN Feature(s) Intersected: FRENCH CREEK

L			. ,		
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200063			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FRENCH CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	TWO MILE LN	16.	Latitude:	38.24788
9.	Location:	00.10 E OF FRENCH CR RD	17.	Longitude:	-85.857132
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	·			
27.	Year Built:	1980	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	793 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	1168 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	3 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	45 ft.	49.	Structure Length:	48 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	31.9 ft.	52.	Deck Width (O-O)	32.2 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	15 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	31.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200063 Bridge Number: 22-00076
Facility Carried: TWO MILE LN Feature(s) Intersected: FRENCH CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
58.01.	Wearing Surface:	Material: BITUMINOUS (5")	Rating:	7
	GOOD - EXCESSIVE WEARING SURFACE			
59.	Superstructure:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
60.	Substructure:	Material: CONCRETE	Rating:	7
	GOOD - VERTICAL HAIRLINE CRACKS BOTH ABUTS AT ABUTN	MENT DRAIN HOLES, 3 EACH ABUTMENT, E ABUTMENT TOP OF	FOOTING EXP.	
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	6
	SATIS - TOP OF SOUTH FOOTING EXPOSED AT E ABUTMENT,	FLOW ALONG E ABUTMENT		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	56	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	40	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	33 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200063 Bridge Number: 22-00076
Facility Carried: TWO MILE LN Feature(s) Intersected: FRENCH CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)

36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - NEARLY LEVEL IN HORIZ. CURVE

Material: BITUMINOUS
Comments: CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. NW & SE B.E.M.'S, AND PLACING RIPRAP ALONG S ABUTMENT.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 98.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



HAIRLINE CRACKS ALONG CENTERLINE



NBI Number: 2200109 Bridge Number: 22-00080 B
Facility Carried: SEVEN MILE LN Feature(s) Intersected: STEWART CREEK

<u>IDEN</u>	<u>ITIFICATION</u>	ĺ			
1.	State:	185 (INDIANA)	4.	City/Town:	14734 (COLUMBUS)
8.	NBI Number:	2200109			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	STEWART CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SEVEN MILE LN	16.	Latitude:	38.1826
9.	Location:	00.80 N HWY 111	17.	Longitude:	-85.90855
<u>STRL</u>	JCTURE DATA	ı			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0
108A.	Wearing Surface:	N (N/A)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2016	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	138 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	204 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	2 %Trucks	19.	Bypass Detour Length:	5 mi.
<u>GEO</u>	METRIC DATA	1			
48.	Maximum Span Length:	36.9 ft.	49.	Structure Length:	40 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	21.5 ft.	52.	Deck Width (O-O)	21.5 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	21.6 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200109 Bridge Number: 22-00080 B
Facility Carried: SEVEN MILE LN Feature(s) Intersected: STEWART CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	09 (RURAL - LOCAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.
		1			

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν	
	N/A					
58.01	. Wearing Surface:	Material:	N/A	Rating:	Ν	
	N/A					
59.	Superstructure:	Material:	N/A	Rating:	Ν	
	N/A					
60.	Substructure:	Material:	N/A	Rating:	Ν	
	N/A					
61.	Channel:	Material:	RIPRAP	Rating:	8	
	VERY GOOD - NO MAJOR DEFECTS					
62.	Culvert/Ret:	Material:	PRECAST CONC. ARCH	Rating:	8	
	VERY GOOD - HAIRLINE CRACKS IN HEADWALL, CENTERLINE OF STRUCTURE, AND MIDHEIGHT OF LEGS.					

31.	Design Load:	9 (HS 25 OR GREATER)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200109 Bridge Number: 22-00080 B
Facility Carried: SEVEN MILE LN Feature(s) Intersected: STEWART CREEK

APPRAISAL

67. Structural: 8
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): N (NA/SAFETY FEATURE NOT REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, ON SLIGHT UPGRADE TO SOUTH

Material: BITUMINOUS

Comments: NO MAJOR DEFECTS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE NEEDED.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 87.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING NORTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



BEAM 4 SPALL NEAR WEST ABUTMENT



NBI Number: 2200065 Bridge Number: 22-00081

Facility Carried: JOHN PECTOL RD Feature(s) Intersected: BR LITTLE INDIAN CR

				ITIFICATION	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200065	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	BR LITTLE INDIAN CR	Feat Intersected:	6.
38.33861	Latitude:	16.	JOHN PECTOL RD	Facility Carried:	7.
-85.962311	Longitude:	17.	00.10 W EVANS-JACOBI	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	05 (ADJACENT BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	2 (CONCRETE PRECAST)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1981	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	468 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	690 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
42.5 ft.	Structure Length:	49.	39 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
28 ft.	Deck Width (O-O)	52.	27.5 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	22 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	10 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	28 ft.	Total Horiz. Clearance:	47.
0.6	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
0 ft.					

NBI Number: 2200065 Bridge Number: 22-00081

Facility Carried: JOHN PECTOL RD Feature(s) Intersected: BR LITTLE INDIAN CR

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	7
	GOOD - EXCESSIVE WEARING SURFACE			
58.01.	Wearing Surface:	Material: BITUMINOUS (5")	Rating:	6
	SATIS - CRACKS, NOT FULL WIDTH			
59.	Superstructure:	Material: CONCRETE	Rating:	8
	VERY GOOD - SPALL IN BOTTOM OF BEAM 4			
60.	Substructure:	Material: CONCRETE	Rating:	7
	GOOD - VERTICAL HAIRLINE CRACKS, TOP OF FOOTING EXP	OSED ALONG W ABUTMENT AND NE CORNER		
61.	Channel:	Material: NATURAL	Rating:	5
	FAIR - AGGRADATION, FLOW TOWARDS W ABUTMENT, SILT	AND VEGETATION BUILDUP IN CHANNEL		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	69	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	51	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	41 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200065 Bridge Number: 22-00081

Facility Carried: JOHN PECTOL RD Feature(s) Intersected: BR LITTLE INDIAN CR

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, BRIDGE ON MED HUMP, INT SE

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND CLEARING CHANNEL UPSTREAM AND DOWNSTREAM AND REMOVING EXCESSIVE WEARING SURFACE.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 96.4
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING EAST FROM ROAD



SOUTH COPING CRACKS WITH EFFL.



NBI Number: 2200067 Bridge Number: 22-00085
Facility Carried: BRADFORD RD Feature(s) Intersected: CORN CREEK

			. ,		
IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200067			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	CORN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	BRADFORD RD	16.	Latitude:	38.36731
9.	Location:	00.80 W OF KIESIER RD	17.	Longitude:	-86.028534
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1925	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	507 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	746 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	8 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	20.1 ft.	49.	Structure Length:	23.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	19.1 ft.	52.	Deck Width (O-O)	20.8 ft.
32.	Approach Roadway Width:	20 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	18 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	19.1 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200067 Bridge Number: 22-00085
Facility Carried: BRADFORD RD Feature(s) Intersected: CORN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	6
	SATIS - EXCESSIVE WEARING SURFACE			
58.01.	Wearing Surface:	Material: BITUMINOUS (6")	Rating:	6
	SATIS - NOT FULL WIDTH, DIRT IN GUTTERS			
59.	Superstructure:	Material: CONCRETE	Rating:	6
	SATIS - HAIRLINE CRACKS AND EFFLORESCENCE			
60.	Substructure:	Material: CONCRETE	Rating:	4
	POOR - WIDE VERTICAL CRACK AND 3.5" ROTATION AT TOP C	DF NORTHEAST WING		
61.	Channel:	Material: NATURAL	Rating:	6
	SATIS - BRUSHY AROUND BRIDGE			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200067 Bridge Number: 22-00085
Facility Carried: BRADFORD RD Feature(s) Intersected: CORN CREEK

APPRAISAL

Structural: 2 68. Geometry: 69. Underclearance: Ν Waterway Adequacy: Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36A. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED) 36C. 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - NEAR TANGENT, BR ON SLT HUMP, HILL E

Material: BITUMINOUS

Comments: LONGITUDINAL CRACKS

Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUBSTRUCTURE.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 45 ft. 94. Bridge Improvement Costs: 209 x 1000 95. Roadway Improvement Costs: 184 x 1000 96. Total Project Cost: 496 x 1000 Year of Cost Estimate: 97 2020

RECOMMENDED MAINTENANCE

UNTIL REPLACEMENT, RECOMMEND INSTALLING CURRENT STANDARD BRIDGE AND APPROACH RAILING WITH END TREATMENT AND ALL BRIDGE END MARKERS, REPLACING NARROW SIGN AT WEST END, AND REPAIRING NORTHEAST WINGWALL.

INSPECTION DATA

90.	Date:	3/2/2020	91.	Des. Inspection Frequency:		12 Months
92.	Critical Feature Inspe	ection:	A:	N	B: N	C: N
93.	Date:		A:		B:	C:

Unofficial Sufficiency Rating: 49.3

Unofficial Structural and Functional Classification: 1 (STRUCTURALLY DEFICIENT)



LOOKING SOUTH FROM ROAD




LOOKING WEST FROM CHANNEL



LOOKING NORTH FROM ROAD



LOOKING NORTH SPAN SPALL



NBI Number: 2200068 Bridge Number: 22-00087

Facility Carried: MARY NAVILE RD Feature(s) Intersected: BANNAMON CREEK

<u>IDEN</u>	<u>ITIFICATION</u>		1		
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200068			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BANNAMON CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	MARY NAVILE RD	16.	Latitude:	38.38971
9.	Location:	00.00 INT OF CHAPEL HL RD	17.	Longitude:	-85.924217
			l		
<u>STRL</u>	JCTURE DATA		l		
43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	2
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
			l		
<u>AGE</u>	OF SERVICE		1		
27.	Year Built:	1931	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	1	28B.	Lanes Under Structure:	0
29.	ADT - Over:	244 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	359 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	4 mi.
	METRIC DATA				
48.	Maximum Span Length:	21 ft.	49.	Structure Length:	46 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	16.1 ft.	52.	Deck Width (O-O)	17.9 ft.
32.	Approach Roadway Width:	15 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	16.1 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200068 Bridge Number: 22-00087

Facility Carried: MARY NAVILE RD Feature(s) Intersected: BANNAMON CREEK

NAVIGA [*]	TION
---------------------	------

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	3 (ONE LANE BRIDGE FOR 2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	Y BE ELIGIBLE FOR NATIONAL REGISTER)			

CONDITION

58.	Deck:	Material: CONCRETE SLAB	Rating:	5
	FAIR - LG SPALLS BOTTOM & COPINGS			
58.01.	Wearing Surface:	Material: BITUMINOUS (3")	Rating:	6
	SATIS - DIRT ON EDGES			
59.	Superstructure:	Material: CONCRETE SLAB	Rating:	5
	FAIR - LARGE SPALLS, EXPOSED REBAR, REBAR SECTION L	oss		
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - CRACKS, SEVERE SCALING WINGS, SPALLS W/EXP.	REIN. AT WINGS		
61.	Channel:	Material: ROCK BOTTOM NORTH, GRAVEL SOUTH	Rating:	5
	FAIR - AGGRADATION, BRUSHY BANKS, DEBRIS AT UPSTREA	AM NOSE, LOGJAM ON PIER		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200068 Bridge Number: 22-00087

Facility Carried: MARY NAVILE RD Feature(s) Intersected: BANNAMON CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - LEVEL, INT. N. END BR., CURVE EACH WAY

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUPERSTRUCTURE.)

Work Done By: 1 (CONTRACT) 76. Improvement Length: 68 ft. 94. Bridge Improvement Costs: 281 x 1000 95. Roadway Improvement Costs: 184 x 1000 Total Project Cost: 96. 587 x 1000 Year of Cost Estimate: 2020 97

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S AND FILL EROSION IN NW CORNER.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 71.4

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING SOUTH FROM ROAD




LOOKING EAST THROUGH CHANNEL



LOOKING NORTH FROM ROAD



LOOKING NW AT SHOULDER EROSION



NBI Number: 2200069 Bridge Number: 22-00088

Facility Carried: BORDEN RD Feature(s) Intersected: MILLER BR OF JERSEY PK B

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200069			
5.	Inventory Route On:	1-4-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	MILLER BR OF JERSEY PK B	11.	Mile Point (over):	0
7.	Facility Carried:	BORDEN RD	16.	Latitude:	38.39629
9.	Location:	00.10 S OF CHAPEL HILL	17.	Longitude:	-85.966698
<u>STRL</u>	JCTURE DATA	1			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE	·			
27.	Year Built:	1970	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	518 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	763 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	5 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	21.5 ft.	49.	Structure Length:	23 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	24.7 ft.	52.	Deck Width (O-O)	25.2 ft.
32.	Approach Roadway Width:	18 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	20 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200069 Bridge Number: 22-00088

Facility Carried: BORDEN RD Feature(s) Intersected: MILLER BR OF JERSEY PK B

NAVIGA [*]	TION
---------------------	------

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE SLAB	Rating:	6
	SATIS - LOW BRIDGE RAILING			
58.01.	Wearing Surface:	Material: BITUMINOUS (7")	Rating:	6
	SATIS - CRACKED			
59.	Superstructure:	Material: CONCRETE SLAB	Rating:	6
	SATIS - HONEYCOMBED CONCRETE AREAS			
60.	Substructure:	Material: CONCRETE	Rating:	5
	FAIR - CRACKS, LEACHING, TOEWALLS EXPOSED			
61.	Channel:	Material: LARGE RIPRAP	Rating:	6
	SATIS - DEEP ALONG SOUTH ABUTMENT, FLOW TOWARDS N	NW AND SE CORNERS		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200069 Bridge Number: 22-00088

Facility Carried: BORDEN RD Feature(s) Intersected: MILLER BR OF JERSEY PK B

APPRAISAL

67. Structural: 5
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, NEARLY LEVEL

Material: BITUMINOUS
Comments: CRACKS, UNEVEN

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)
75B. Work Done By: ()
76. Improvement Length: 0 ft.

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND SE B.E.M.'S AND REPAIR NW SHOULDER EROSION.

INSPECTION DATA

 90.
 Date:
 3/5/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 76.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



SOUTHWEST BEAM SPALL



NBI Number: 2200070 Bridge Number: 22-00089

Facility Carried: CHAPEL HILL RD Feature(s) Intersected: CAMPBELL BR JERSEY PK CR

				NTIFICATION .	IDEN
00000 ()	City/Town:	4.	185 (INDIANA)	State:	1.
			2200070	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	CAMPBELL BR JERSEY PK CR	Feat Intersected:	6.
38.39628	Latitude:	16.	CHAPEL HILL RD	Facility Carried:	7.
-85.955421	Longitude:	17.	00.60 E OF BORDEN	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	05 (ADJACENT BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	2 (CONCRETE PRECAST)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			8 (UNKNOWN)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1995	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	279 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	410 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	3 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
50 ft.	Structure Length:	49.	46 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
28.2 ft.	Deck Width (O-O)	52.	27.9 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	22 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	30 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	27.9 ft.	Total Horiz. Clearance:	47.
		- LD	N.I.	Min Late CL Dight Code	
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200070 Bridge Number: 22-00089

Facility Carried: CHAPEL HILL RD Feature(s) Intersected: CAMPBELL BR JERSEY PK CR

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - FEW POPOUTS, HAIRLINE CRACKS				
58.01.	Wearing Surface:	Material:	CONCRETE	Rating:	7
	GOOD - POPOUTS				
59.	Superstructure:	Material:	CONCRETE BOX BEAM	Rating:	8
	VERY GOOD - SM SPALL BOTTOM EDGE BEAM				
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - HAIRLINE CRACKS, LEACHING				
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	6
	SATIS - EROSION EAST BANK, BRUSHY BANKS, FLOW TOWAR	DS EAST	ABUTMENT		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	57	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	46	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	40 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200070 Bridge Number: 22-00089

Facility Carried: CHAPEL HILL RD Feature(s) Intersected: CAMPBELL BR JERSEY PK CR

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 6

 69.
 Underclearance:
 N

 71.
 Waterway Adequacy:
 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, SLIGHT UPGRADE TO HILL EAST

Material: BITUMINOUS

Comments: SETTLED AT BRIDGE ENDS
Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE


RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S, PLACING RIPRAP AT NE CORNER, AND REPAIR NE SHOULDER EROSION.

INSPECTION DATA

90. Date: 3/5/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 98.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



LOOKING EAST AT PIER SPALLS



NBI Number: 2200071 Bridge Number: 22-00091
Facility Carried: GAP HOLLOW RD Feature(s) Intersected: KNOB CREEK

	<u> </u>		. ,		
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200071			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	KNOB CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	GAP HOLLOW RD	16.	Latitude:	38.23686
9.	Location:	00.10 E OF BUDD RD	17.	Longitude:	-85.896645
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	6 (CONT PRESTR CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	06 (SPREAD BOX BEAM)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
AGE	OF SERVICE	·			
27.	Year Built:	1982	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	186 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	274 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	7 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	37.5 ft.	49.	Structure Length:	108.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	29 ft.	52.	Deck Width (O-O)	30 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	15 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	29 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200071 Bridge Number: 22-00091
Facility Carried: GAP HOLLOW RD Feature(s) Intersected: KNOB CREEK

NAVIGATION

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	8				
	VERY GOOD - FEW POPOUTS, IMPACT DAMAGE AT BRIDGE ENDS								
58.01.	Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	8				
	VERY GOOD - MINOR DEBRIS ON EDGES								
59.	Superstructure:	Material:	CONCRETE	Rating:	8				
	VERY GOOD - NO MAJOR DEFECTS								
60.	Substructure:	Material:	CONCRETE	Rating:	7				
	GOOD - PIER COLUMN SPALLS, EXPOSED STEEL								
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	8				
	VERY GOOD - BRUSHY STREAMBANKS								
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν				
	N/A								

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	58	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	37	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	23 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

NBI Number: 2200071 Bridge Number: 22-00091
Facility Carried: GAP HOLLOW RD Feature(s) Intersected: KNOB CREEK

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 6

 69.
 Underclearance:
 N

 71.
 Waterway Adequacy:
 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - CURVE W, ON STEEP UPGRADE TO INT. W.

Material: BITUMINOUS

Comments: SETTLED & CRACKED

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL & NE & SE B.E.M.'S

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 98.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



SOUTH ABUTMENT



00000 ()

NBI Number: 2200072 Bridge Number: 22-00093

Facility Carried: BUDD RD Feature(s) Intersected: EISEMAN CREEK

IDE	<u>NTIFICATION</u>		1		
1.	State:	185 (INDIANA)	4.	City/Town:	
8.	NBI Number:	2200072			

5. Inventory Route On: 1-4-2- 0-0 98. Border Bridge:

2. District: 05 (SEYMOUR) 99. Border Bridge Number:

3. County: 022 (FLOYD)

6. Feat Intersected: EISEMAN CREEK 11. Mile Point (over): 0

7. Facility Carried: BUDD RD 16. Latitude: 38.21819

 9.
 Location:
 00.30 N FIVE MILE LANE
 17.
 Longitude:
 -85.900375

STRUCTURE DATA

43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	06 (SPREAD BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			

AGE OF SERVICE

27.	Year Built:	1991	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	146 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	215 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	8 mi.

GEOMETRIC DATA

48.	Maximum Span Length:	34 ft.	49.	Structure Length:	38 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	23.9 ft.	52.	Deck Width (O-O)	24 ft.
32.	Approach Roadway Width:	23 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	23.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200072 Bridge Number: 22-00093
Facility Carried: BUDD RD Feature(s) Intersected: EISEMAN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	08 (RURAL - MINOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7			
	GOOD - HAIRLINE CRACKS, POPOUTS							
58.01	. Wearing Surface:	Material:	INTEGRAL CONCRETE	Rating:	7			
	GOOD - SHORT LONGITUDINAL HAIRLINE CRACKS							
59.	Superstructure:	Material:	CONCRETE BOX BEAMS	Rating:	8			
	VERY GOOD - NO MAJOR DEFECTS							
60.	Substructure:	Material:	CONCRETE	Rating:	7			
	GOOD - VERTICAL HAIRLINE CRACKS, LEACHING AT CORNERS							
61.	Channel:	Material:	NATURAL	Rating:	5			
	FAIR - AGGRADATION NORTH, LIGHT SCOUR SOUTH							
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν			
	N/A							

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	59	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	35	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	23 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			1		

NBI Number: 2200072 Bridge Number: 22-00093
Facility Carried: BUDD RD Feature(s) Intersected: EISEMAN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 4

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, NEARLY LEVEL

Material: BITUMINOUS

Comments: NO MAJOR DEFECTS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL AND ALL B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 91.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING NORTH THROUGH CHANNEL



LOOKING EAST FROM ROAD



SOUTHEAST CORNER SCOUR



NBI Number: 2200073 Bridge Number: 22-00094
Facility Carried: E MCCARTHY KNOB RD Feature(s) Intersected: AL'S CREEK

	<u> </u>				
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	00000 ()
8.	NBI Number:	2200073			
5.	Inventory Route On:	1-4-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	AL'S CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	E MCCARTHY KNOB RD	16.	Latitude:	38.24596
9.	Location:	00.30 W OF BUDD RD	17.	Longitude:	-85.901314
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	3 (STEEL)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	02 (GIRDER)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1966	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	323 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	476 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	199 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	22.2 ft.	49.	Structure Length:	26.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	22.2 ft.	52.	Deck Width (O-O)	23.9 ft.
32.	Approach Roadway Width:	16 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	35 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	22.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	Oft.

NBI Number: 2200073 Bridge Number: 22-00094
Facility Carried: E MCCARTHY KNOB RD Feature(s) Intersected: AL'S CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	6
	SATIS - BOTTOM OF DECK SPALLS WITH EXPOSED BEAMS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (5")	Rating:	6
	SATIS - EXCESSIVE WEARING SURFACE, NOT FULL WIDTH				
59.	Superstructure:	Material:	ENCASED STEEL BEAMS	Rating:	6
	SATIS - EXPOSED BOTTOMS OF BEAMS IN TWO AREAS				
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - SW WING UNDERCUT				
61.	Channel:	Material:	RIPRAP AND NATURAL	Rating:	5
	FAIR - SCOUR AT NE CORNER, FLOW TOWARDS SE CORNER				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200073 Bridge Number: 22-00094
Facility Carried: E MCCARTHY KNOB RD Feature(s) Intersected: AL'S CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - DIP NORTH, CURVE SOUTH

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 4 (STABLE - ACTION NEEDED)

Comments: SOUTHEAST CORNER FOOTING EXPOSED

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NW & SE B.E.M.'S, AND PLACING RIPRAP AT SE CORNER.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 71.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING WEST FROM ROAD



LOOKING AT SPALL WITH EXPOSED BROKEN STRANDS



NBI Number: 2200096 Bridge Number: 22-00096 Facility Carried: BEECHWOOD AVE Feature(s) Intersected: FALL RUN

<u> </u>		- (-)		,	
				ITIFICATION	IDEN
52326 (NEW ALBANY)	City/Town:	4.	185 (INDIANA)	State:	1.
			2200096	NBI Number:	8.
	Border Bridge:	98.	1-5-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	FALL RUN	Feat Intersected:	6.
38.30704	Latitude:	16.	BEECHWOOD AVE	Facility Carried:	7.
-85.82010	Longitude:	17.	00.44 N SR 311	Location:	9.
				JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	5 (PRESTRESSED CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	05 (ADJACENT BOX BEAM)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	3 (LATEX CONCRETE)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	AGE
1980	Reconstructed:	106.	1967	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	5 (HIGHWAY/PEDESTRIAN)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	14960 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	22051 VPD	Future ADT:	114.
1 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	GEO!
40 ft.	Structure Length:	49.	36.4 ft.	Maximum Span Length:	48.
3.0 ft.	Sidewalk/Curb Right:	50B.	3.0 ft.	Sidewalk/Curb Left:	50A.
51.4 ft.	Deck Width (O-O)	52.	45.4 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	45 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	0 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	45.4 ft.	Total Horiz. Clearance:	47.
Oft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200096 Bridge Number: 22-00096 Facility Carried: BEECHWOOD AVE Feature(s) Intersected: FALL RUN

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	16 (URBAN - MINOR ARTERIAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	6
	SATIS - RAILING DAMAGED, 2 POSTS LOOSE SOUTH SIDE			
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	6
	SATIS - POPOUTS AT JOINTS, LONG CRACKS AT BEAM LINES	S, MODERATE SURFACE WEAR EXPOSED AGGREGATE SURFA	CE.	
59.	Superstructure:	Material: PRESTRESSED CONCRETE BOX BEAMS	Rating:	6
	SATIS - 1 BEAM SPALLED 2ND FROM NORTH 3' LONG, EXP. A AT 2 GUARDRAIL CONNECTIONS AND ONE PREVIOUS GUAR	ND RUSTED STRANDS TWO ARE EXPOSED AND BROKEN, SOU DRAIL CONNECTION	JTH BEAM SPALLED	
60.	Substructure:	Material: CONCRETE BENT CAP ON PILES	Rating:	7
	GOOD - WATER SEEPAGE ONTO BRIDGE SEATS			
61.	Channel:	Material: CONCRETE SLOPEWALL	Rating:	6
	SATIS - ONLY MINOR DRIFT NOW IN CHANNEL			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	76	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	55	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	46 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200096 Bridge Number: 22-00096 Facility Carried: BEECHWOOD AVE Feature(s) Intersected: FALL RUN

APPRAISAL

67. Structural: 6
 68. Geometry: 9
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - STRAIGHT INTERSECTION TO THE W

Material: BITUMINOUS

Comments: NEW BITUMINOUS ON APPROACHES SIDEWALK HAVE SETTLED AT ALL CORNERS OF THE

BRIDGE

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments: TRASH & DEBRIS IN CHANNELPILES, 30' LONG, CONCRETE SLOPE WALLS, DEBRIS IN

CHANNEL

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL WIEND TREATMENT AND SW B.E.M.'S. PATCH SPALLED BEAMS.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

Unofficial Sufficiency Rating: 95.6
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH FROM ROAD



LOOKING SOUTH AT SPAN CRACKING WITH EFFL.



NBI Number: 2200101 Bridge Number: 22-00101

Facility Carried: OLD SR 111 Feature(s) Intersected: BRANCH ELK RUN

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	68670 (SELLERSBURG)
8.	NBI Number:	2200101			
5.	Inventory Route On:	1-3-1- 111-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BRANCH ELK RUN	11.	Mile Point (over):	17.6
7.	Facility Carried:	OLD SR 111	16.	Latitude:	38.39634
9.	Location:	02.10 S SR 60	17.	Longitude:	-85.808937
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	2 (CONTINUOUS CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1965	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	6419 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	9455 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	10 %Trucks	19.	Bypass Detour Length:	4 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	22 ft.	49.	Structure Length:	57 ft.
50A.	Sidewalk/Curb Left:	0.5 ft.	50B.	Sidewalk/Curb Right:	0.5 ft.
51.	Bridge Roadway Width:	41.1 ft.	52.	Deck Width (O-O)	44 ft.
32.	Approach Roadway Width:	28 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	41.1 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200101 Bridge Number: 22-00101

Facility Carried: OLD SR 111 Feature(s) Intersected: BRANCH ELK RUN

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	07 (RURAL - MAJOR COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONT REINF CONC SLAB	Rating:	6
	SATIS - SOUTH EXPAN JOINT DAMAGED, SPALLS NORTH BO	UND LANE		
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	5
	FAIR - LARGE PATCHES & NEW SPALLS, HEAVY WEARING OF	N SURFACE		
59.	Superstructure:	Material: CONT REINF CONC SLAB	Rating:	6
	SATIS - SPALLS ALONG CONSTR JOINTS, SPALLS ALONG EA SPANS.	ST COPING W/ EXP. REIN.CRACKS IN SOUTH SPAN WITH EFFL	, DELAMS IN ALL	
60.	Substructure:	Material: CONCRETE ON PILES	Rating:	7
	GOOD - HAIRLINE CRACKS, LIGHT SCALING			
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	6
	SATIS - VEGETATION BLOCKING END SPANS, GRAVEL BOTT	OM		
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200101 Bridge Number: 22-00101

Facility Carried: OLD SR 111 Feature(s) Intersected: BRANCH ELK RUN

APPRAISAL

Waterway Adequacy:

 67.
 Structural:
 6

 68.
 Geometry:
 5

 69.
 Underclearance:
 N

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, LEVEL

Material: BITUMINOUS

Comments: SPALLS AND LONG. CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: 35 (REHABILITATE BRIDGE DUE TO SUPERSTRUCTURE DETERIORATION.)

75B. Work Done By: 1 (CONTRACT)

76. Improvement Length: 57 ft.

94. Bridge Improvement Costs: 148 x 1000

95. Roadway Improvement Costs: 184 x 1000

96. Total Project Cost: 402 x 1000

97. Year of Cost Estimate: 2020

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S, AND REPLACING BRIDGE JOINT AND DECK OVERLAY.

INSPECTION DATA

90. Date: 3/4/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C:

Unofficial Sufficiency Rating: 95.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING SOUTH FROM ROAD




LOOKING WEST UPSTREAM



LOOKING NORTH FROM ROAD



LOOKING SOUTH AT EAST ARCH COPING



NBI Number: 031290 Bridge Number: 22-00102
Facility Carried: CHARLESTOWN RD Feature(s) Intersected: JACOBS CREEK

		\ /		·	
				<u>ITIFICATION</u>	IDEN
52326 (NEW ALBANY)	City/Town:	4.	185 (INDIANA)	State:	1.
			031290	NBI Number:	8.
	Border Bridge:	98.	1-4-1- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
1.06	Mile Point (over):	11.	JACOBS CREEK	Feat Intersected:	6.
38.35618	Latitude:	16.	CHARLESTOWN RD	Facility Carried:	7.
-85.789101	Longitude:	17.	01.00 N I-265	Location:	9.
				JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	1 (CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	11 (DECK ARCH)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
1964	Reconstructed:	106.	1931	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2016	ADT Year Over:	30.	21062 VPD	ADT - Over:	29.
2036	Future ADT Year:	115.	31046 VPD	Future ADT:	114.
4 mi.	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
44 ft.	Structure Length:	49.	35 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
38.9 ft.	Deck Width (O-O)	52.	36.7 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	28 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	10 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	36.7 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.
0 ft.	Lateral Left:	56.	Oft.	Lateral Right:	55B.

NBI Number: 031290 Bridge Number: 22-00102
Facility Carried: CHARLESTOWN RD Feature(s) Intersected: JACOBS CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE PCBB	Rating:	7
	GOOD - NO MAJOR DEFECTS			
58.01.	Wearing Surface:	Material: BITUMINOUS (4")	Rating:	6
	SATIS - CRACKS			
59.	Superstructure:	Material: CONCRETE ARCH W/WIDENED BOX BEAMS	Rating:	6
	SATIS - SPALL AREAS PATCHED, APPROX 16' LONG CRACK I COPING, WATER SEEPAGE WITH EFFL. BETWEEN BOX BEAM	N BEAM 2 FROM N HAS BEEN PATCHED. EFFL. IN PATCHES AT IS	NORTH ARCH.	
60.	Substructure:	Material: CONCRETE	Rating:	7
	GOOD - PATCHED SPALL AREAS			
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	6
	SATIS - LOCAL SCOUR, SILT DEPOSITS			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	4 (H 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 031290 Bridge Number: 22-00102
Facility Carried: CHARLESTOWN RD Feature(s) Intersected: JACOBS CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)

36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, NEAR LEVEL AT BRIDGE WITH UPGRADE TO HILL BOTH APPROACHES

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE GUARDRAIL, NW & SW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 89.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH FROM ROAD



LOOKING WEST AT RUSTED CENTER SPAN METAL



NBI Number: 2200103 Bridge Number: 22-00103

Facility Carried: ASHBURY DRIVE Feature(s) Intersected: BALD KNOB CREEK

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200103			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BALD KNOB CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	ASHBURY DRIVE	16.	Latitude:	38.35423
9.	Location:	00.10 NE OF ST JOSEPH RD	17.	Longitude:	-85.810806
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	0 (NONE)
108C.	Protection	8 (UNKNOWN)			
AGF	OF SERVICE		I		
27.	Year Built:	1996	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	52 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	77 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	1 %Trucks	19.	Bypass Detour Length:	999 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	13.5 ft.	49.	Structure Length:	40.2 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	28 ft.	52.	Deck Width (O-O)	30 ft.
32.	Approach Roadway Width:	28 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	45 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	28.2 ft.	54A.	Min Vert Clear Code:	99.99 II. N
55A.	Min Latr. Cl. Right - Code:	20.2 n. N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200103 Bridge Number: 22-00103

Facility Carried: ASHBURY DRIVE Feature(s) Intersected: BALD KNOB CREEK

|--|

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE SLAB	Rating:	6
	SATIS - LONG. CRACK AT CENTERLINE			
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	6
	SATIS - MANY POPOUTS, MED SCALING			
59.	Superstructure:	Material: CONCRETE SLAB	Rating:	6
	SATIS - LIGHT SCALING, METAL FORMWORK HAS HEAVY RU	ST		
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - UNDERCUT AT INLET, LT SCALING. PIER #2 - FOOTIN BENTS. PIERS HAVE 1/8" VERT. CRACKS AT CENTERLINE.	G EXPOSED AT WEST END, NO SIGNIFICANT UNDERCUT, VER	TICAL CRACKS IN EN	D
61.	Channel:	Material: CONCRETE BOTTOM	Rating:	6
	SATIS - DRIFT AT INLET, CRACKED CTR SPAN			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200103 Bridge Number: 22-00103

Facility Carried: ASHBURY DRIVE Feature(s) Intersected: BALD KNOB CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 7
 69. Underclearance: N
 71. Waterway Adequacy: 6

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - TANGENT, AT GRADE, DRIVES TO THE NW AND SE

Material: BITUMINOUS

Comments: NO MAJOR DEFECTS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT, AND CLEANING DEBRIS IN CHANNEL.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 48 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 92.5
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH AT ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH AT ROAD



LOOKING SOUTH AT PRECAST UNITS



Bridge Number: 22-00104 NBI Number: 2200110

Facility Carried: ENDRES PARKWAY Feature(s) Intersected: JACOBS CREEK

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200110			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	JACOBS CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	ENDRES PARKWAY	16.	Latitude:	38.35546
9.	Location:	0.15 MI. N CHARLESTOWN RD	17.	Longitude:	-85.79443
STRU	JCTURE DATA	1			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2016	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	0 VPD	30.	ADT Year Over:	2016
114.	Future ADT:	500 VPD	115.	Future ADT Year:	2036
109.	Average Truck Traffic:	0 %Trucks	19.	Bypass Detour Length:	199 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	58 ft.	49.	Structure Length:	62.8 ft.
50A.	Sidewalk/Curb Left:	0.5 ft.	50B.	Sidewalk/Curb Right:	8.0 ft.
51.	Bridge Roadway Width:	22.5 ft.	52.	Deck Width (O-O)	36 ft.
32.	Approach Roadway Width:	22.5 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	99.9 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200110 Bridge Number: 22-00104
Facility Carried: ENDRES PARKWAY Feature(s) Intersected: JACOBS CREEK

			_			
NI	۸١	71	\boldsymbol{c}	٩Т	IM	NI
IΝ	\vdash	٧I	U/	ч.	ıv	IV

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			I		

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (4")	Rating:	8
	VERY GOOD - SURFACE IN PLACE				
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	N/A	Rating:	7
	GOOD - AGGRADATION SAND/ GRAVEL BAR UNDER STR., FLO	OW IS ALC	ONG S ABUTMENT		
62.	Culvert/Ret:	Material:	PRECAST CONCRETE ARCH	Rating:	8
	VERY GOOD - 9" X 15" SPALL W/ EXP. REIN. IN BOT OF E PREC SECTION ON BOTTOM	CAST COP	ING SECTION, MULTIPLE HL CRACKS IN COPING EXT	END ACROSS	

31.	Design Load:	9 (HS 25 OR GREATER)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200110 Bridge Number: 22-00104
Facility Carried: ENDRES PARKWAY Feature(s) Intersected: JACOBS CREEK

APPRAISAL

 67.
 Structural:
 8

 68.
 Geometry:
 5

 69.
 Underclearance:
 N

 71.
 Waterway Adequacy:
 7

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - STR. STILL UNDER CONSTRUCTION, LEADS TO SPORTS PARK

Material: ASPHALT

Comments: ASPHALT SURFACE

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/4/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 91.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING NORTH FROM CHANNEL



LOOKING WEST FROM ROAD



EAST SPAN UNDERSIDE



NBI Number: 2200111 Bridge Number: 22-00105
Facility Carried: BEAR CREEK ROAD Feature(s) Intersected: BEAR CREEK

	Intersected: BEAR CREEK	ature(s)	TOAD FE	iity Carried: BEAR CREEK	
				ITIFICATION	IDEN
00000	City/Town:	4.	185 (INDIANA)	State:	1.
			2200111	NBI Number:	8.
	Border Bridge:	98.	1-4-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
	Mile Point (over):	11.	BEAR CREEK	Feat Intersected:	6.
38.4180	Latitude:	16.	BEAR CREEK ROAD	Facility Carried:	7.
-86.0276	Longitude:	17.	0.1 mi. E. of SR-335	Location:	9.
				JCTURE DATA	<u>STRL</u>
00	Structure Type - Approach:	44.	3 (STEEL)	Structure Type - Main Span:	43A.
	Number of Spans - Main:	45.	02 (GIRDER)	Structure Type - Main Span - Cons	43B.
	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
0 (NONE	Membrane:	108B.	1 (MONOLITHIC CONCRETE)	Wearing Surface:	108A.
			(EPOXY COATED REINFORCING)	Protection	108C.
				OF SERVICE	<u>AGE</u>
	Reconstructed:	106.	2019	Year Built:	27.
5 (WATERWA)	Type of Service Under:	42B.	1 (HIGHWAY)	Type of Service Over:	42A.
	Lanes Under Structure:	28B.	1	Lanes on Structure:	28A.
201	ADT Year Over:	30.	50 VPD	ADT - Over:	29.
203	Future ADT Year:	115.	50 VPD	Future ADT:	114.
3 m	Bypass Detour Length:	19.	5 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
36 1	Structure Length:	49.	17.5 ft.	Maximum Span Length:	48.
0.01	Sidewalk/Curb Right:	50B.	0.0 ft.	Sidewalk/Curb Left:	50A.
13.5 f	Deck Width (O-O)	52.	13 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN	Bridge Median:	33.	13.5 ft.	Approach Roadway Width:	32.
0 (NO FLARE	Structure Flared:	35.	34 Degree(s)	Skew:	34.
99.99 1	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
		54A.	13 ft.	Total Horiz. Clearance:	47.
	Min Vert Clear Code:			Total Floriz. Olcaranco.	17.
01	Min Vert Clear Code: Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200111 Bridge Number: 22-00105
Facility Carried: BEAR CREEK ROAD Feature(s) Intersected: BEAR CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	09 (RURAL - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	3 (ONE LANE BRIDGE FOR 2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS NOTED			
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS NOTED			
59.	Superstructure:	Material: STEEL BEAM	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS NOTED			
60.	Substructure:	Material: CONCRETE	Rating:	7
	GOOD - SPALL NEAR BEARING AT NORTH END OF PIER			
61.	Channel:	Material: NATURAL/ ROCK	Rating:	7
	GOOD - NO MAJOR DEFECTS NOTED			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	45	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200111 Bridge Number: 22-00105
Facility Carried: BEAR CREEK ROAD Feature(s) Intersected: BEAR CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - ALIGNMENT AT GRADE, SOUTH CURVE

Material: BITUMINOUS

Comments: NEW APPROACH

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments: EXPOSED FOOTING, FOOTING ON COMPETENT ROCK

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. TRANSITION RAIL.

INSPECTION DATA

90. Date: 3/2/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N
93. Date: A: B: C:

Unofficial Sufficiency Rating: 83.0
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING NORTH DOWNSTREAM



LOOKING EAST FROM ROAD



LOOKING SOUTH UPSTREAM



NBI Number: 2200074 Bridge Number: 22-00501

Facility Carried: BINFORD PARK ST Feature(s) Intersected: FALLING RUN CREEK

				ITIFICATION	IDEN
52326 (NEW ALBANY)	City/Town:	4.	185 (INDIANA)	State:	1.
			2200074	NBI Number:	8.
	Border Bridge:	98.	1-5-2- 0-0	Inventory Route On:	5.
	Border Bridge Number:	99.	05 (SEYMOUR)	District:	2.
			022 (FLOYD)	County:	3.
0	Mile Point (over):	11.	FALLING RUN CREEK	Feat Intersected:	6.
38.30086	Latitude:	16.	BINFORD PARK ST	Facility Carried:	7.
-85.823685	Longitude:	17.	00.10 W OF GRAYBROOK LN	Location:	9.
			ı	JCTURE DATA	<u>STRL</u>
000	Structure Type - Approach:	44.	1 (CONCRETE)	Structure Type - Main Span:	43A.
1	Number of Spans - Main:	45.	11 (DECK ARCH)	Structure Type - Main Span - Const.	43B.
0000	Number of Spans - Approach:	46.	1 (CONCRETE CAST-IN-PLACE)	Deck Structure Type:	107.
8 (UNKNOWN)	Membrane:	108B.	6 (BITUMINOUS)	Wearing Surface:	108A.
			0 (NONE)	Protection	108C.
				OF SERVICE	<u>AGE</u>
0	Reconstructed:	106.	1920	Year Built:	27.
5 (WATERWAY)	Type of Service Under:	42B.	5 (HIGHWAY/PEDESTRIAN)	Type of Service Over:	42A.
0	Lanes Under Structure:	28B.	2	Lanes on Structure:	28A.
2014	ADT Year Over:	30.	1450 VPD	ADT - Over:	29.
2034	Future ADT Year:	115.	2138 VPD	Future ADT:	114.
1 mi.	Bypass Detour Length:	19.	4 %Trucks	Average Truck Traffic:	109.
				METRIC DATA	<u>GEO</u>
39.5 ft.	Structure Length:	49.	20.1 ft.	Maximum Span Length:	48.
0.0 ft.	Sidewalk/Curb Right:	50B.	4.5 ft.	Sidewalk/Curb Left:	50A.
23.7 ft.	Deck Width (O-O)	52.	18 ft.	Bridge Roadway Width:	51.
0 (NO MEDIAN)	Bridge Median:	33.	18 ft.	Approach Roadway Width:	32.
0 (NO FLARE)	Structure Flared:	35.	0 Degree(s)	Skew:	34.
99.99 ft.	Vertical Clearance/Deck:	53.	99.99	Defense Vertical Clearance:	10.
N	Min Vert Clear Code:	54A.	18 ft.	Total Horiz. Clearance:	47.
0 ft.	Underclearance:	54B.	N	Min Latr. Cl. Right - Code:	55A.

NBI Number: 2200074 Bridge Number: 22-00501

Facility Carried: BINFORD PARK ST Feature(s) Intersected: FALLING RUN CREEK

|--|

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	19 (URBAN - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			I		

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - NORTHEAST RAILING POST DAMAGED, 20" DROP OFF	AT SW C	ORNER SHOULDER OF ROAD AND SIDE WALK, WALK	BEING UNDERMINE	D
58.01.	Wearing Surface:	Material:	BITUMINOUS (10")	Rating:	7
	GOOD - CRACKS				
59.	Superstructure:	Material:	PRECAST CONCRETE ARCH	Rating:	7
	GOOD - HL CRACKS IN ARCH				
60.	Substructure:	Material:	PRECAST CONCRETE ARCH	Rating:	7
	GOOD - HAIRLINE CRACKS WITH LT AT SE CORNER, EFFL., TO	P FOOTIN	NG EXP. AT W ABUTMENT		
61.	Channel:	Material:	NATURAL & RIPRAP	Rating:	6
	SATIS - MINOR BANK EROSION				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/Δ				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200074 Bridge Number: 22-00501

Facility Carried: BINFORD PARK ST Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 7
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 5

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - CURVE EACH WAY, LEVEL

Material: BITUMINOUS

Comments: TRANS. CRACKS, NO APPROACH SIDEWALK, NO SHOULDERS AT BRIDGE CORNERS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:

94. Bridge Improvement Costs:

95. Roadway Improvement Costs:

96. Total Project Cost:

97. O ft.

98. Total Project Cost:

98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT, PLACING RIPRAP AT SW CORNER.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 76.8

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING EAST FROM ROAD




LOOKING SOUTH THROUGH CHANNEL



LOOKING WEST FROM ROAD



LOOKING EAST AT SEWAGE TREATMENT PLANT



NBI Number: 2200075 Bridge Number: 22-00502

Facility Carried: FLOYD ST Feature(s) Intersected: FALLING RUN CREEK

<u>IDEN</u>	ITIFICATION	I			
1.	State:	185 (INDIANA)	4.	City/Town:	01342 (AMBIA)
8.	NBI Number:	2200075			
5.	Inventory Route On:	1-5-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	FLOYD ST	16.	Latitude:	38.27682
9.	Location:	00.10 S OF US 111	17.	Longitude:	-85.832886
STRU	JCTURE DATA	ı			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	3
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1952	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	10164 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	14982 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	4 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	9.1 ft.	49.	Structure Length:	28 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	22 ft.	52.	Deck Width (O-O)	115 ft.
32.	Approach Roadway Width:	22 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	20 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	Oft.

NBI Number: 2200075 Bridge Number: 22-00502

Feature(s) Intersected: FALLING RUN CREEK Facility Carried: FLOYD ST

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	19 (URBAN - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			1		

CONDITION Deck:

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - NO MAJOR DEFECTS				
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	6
	SATIS - SCOUR HOLE AT OUTLET (3.5' DEEP AVG.)				
62.	Culvert/Ret:	Material:	3-CELL CONCRETE BOX	Rating:	7
	GOOD - LEAKS, SMALL SPALLS, BOTTOM OF STR. WORN, SMA	ALL 12" X 1	12" X 5" DEEP SPALL AT NW CORNER, FLOOD GATES	IN STRUCTURE	

LOAD RATING AND POSTING

NEAR SOUTH END

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200075 Bridge Number: 22-00502

Facility Carried: FLOYD ST Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 2

 69.
 Underclearance:
 N

71. Waterway Adequacy: 9

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - SLIGHT HORIZ. CURVE, UPGRADE TO N

Material: BITUMINOUS

Comments: FEW CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND REMOVING LOGJAM AT INLET, INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 76.8

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING WEST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING EAST FROM ROAD



LOOKING WEST AT WATER SEEPAGE BETWEEN PRECAST



NBI Number: 2200105 Bridge Number: 22-00503 B

Facility Carried: DAISY LN Feature(s) Intersected: FALLING RUN CREEK

			. ,		
IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200105			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	DAISY LN	16.	Latitude:	38.31013
9.	Location:	00.00 INT ZURSCHMEIDE DR	17.	Longitude:	-85.83252
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	11 (DECK ARCH)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
AGE	OF SERVICE	·			
27.	Year Built:	2011	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	6118 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	9018 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	8 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	34 ft.	49.	Structure Length:	36.7 ft.
50A.	Sidewalk/Curb Left:	6.4 ft.	50B.	Sidewalk/Curb Right:	6.4 ft.
51.	Bridge Roadway Width:	28.5 ft.	52.	Deck Width (O-O)	45.7 ft.
32.	Approach Roadway Width:	28 ft.	33.	Bridge Median:	1 (OPEN MEDIAN)
34.	Skew:	20 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	41.3 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200105 Bridge Number: 22-00503 B

Facility Carried: DAISY LN Feature(s) Intersected: FALLING RUN CREEK

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

C	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	16 (URBAN - MINOR ARTERIAL)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	NEW BITUMINOUS (4")	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
59.	Superstructure:	Material:	PRECAST CONCRETE HYSPAN	Rating:	7
	GOOD - MANY TRANSVERSE HAIRLINE CRACKS, 12" x 22" SP CRACKS IN PRECAST SECTIONS AT MIDSPAN	ALL WITH	1 EXP. REIN. AT MIDSPAN IN PRECAST SECTION 7, FI	NE HL TRANSVERSE	
60.	Substructure:	Material:	PRECAST CONCRETE HYSPAN	Rating:	8
	VERY GOOD - SMALL SPALLS AT WINGWALL AT SW CORNER				
61.	Channel:	Material:	GROUTED RIPRAP	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200105 Bridge Number: 22-00503 B

Facility Carried: DAISY LN Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 2

69. Underclearance: N

71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, ON GRADE

Material: BITUMINOUS

Comments: NEW BITUMINOUS APPROACHES

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

DAMAGED SOUTHWEST END TREATMENT

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:

Unofficial Sufficiency Rating: 80.3

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING WEST FROM ROAD




LOOKING EAST FROM ROAD



LOOKING SOUTH EAST DOWNSTREAM



LOOKING SOUTH AT CULVERT INTERIOR



NBI Number: 2200077 Bridge Number: 22-00504

Facility Carried: SPRING HILL RD Feature(s) Intersected: FALLING RUN CREEK

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200077			
5.	Inventory Route On:	1-5-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SPRING HILL RD	16.	Latitude:	38.28234
9.	Location:	00.10 W OF SPRING ST	17.	Longitude:	-85.834625
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
AGE	OF SERVICE	·			
27.	Year Built:	1949	106.	Reconstructed:	0
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1184 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	1746 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	20.1 ft.	49.	Structure Length:	24 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	26 ft.	52.	Deck Width (O-O)	70 ft.
32.	Approach Roadway Width:	26 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	60 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200077 Bridge Number: 22-00504

Facility Carried: SPRING HILL RD Feature(s) Intersected: FALLING RUN CREEK

NAVIGATION	N/	۱V	IGA	IT.	0	N
------------	----	----	------------	-----	---	---

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	19 (URBAN - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	\ensuremath{GOOD} - NEW ASPHALT PATCH AREA HAS SETTLED APPROX.	1" OVER S	STR.		
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	NATURAL	Rating:	6
	SATIS - LARGE CONCRETE CHUNKS				
62.	Culvert/Ret:	Material:	CONC. ARCH CULVERT	Rating:	5

FAIR - WINGS BROKEN & DISPLACED, MINOR SPALLS, CRACKS, LT. HONEYCOMB AREAS, WING WALLS/ HEAD WALLS BROKEN OFF, DISPLACED

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200077 Bridge Number: 22-00504

Facility Carried: SPRING HILL RD Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - BRIDGE UNDER STEEP, WINDING ROAD

Material: BITUMINOUS

Comments: NEW ASPHALT PATCH IS SETTLING OVER STR.

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE NEEDED.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 75.6
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST THROUGH CHANNEL



LOOKING SOUTH FROM ROAD



HAIRLINE CRACK IN BOTTOM BEAM 10 AT EAST COPING



NBI Number: 2200078 Bridge Number: 22-00505

Facility Carried: SCRIBNER DR Feature(s) Intersected: FALLING RUN CREEK

IDEN	ITIFICATION .				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200078			
5.	Inventory Route On:	1-5-2- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	SCRIBNER DR	16.	Latitude:	38.28797
9.	Location:	00.10 W OF STATE ST	17.	Longitude:	-85.827515
<u>STRL</u>	JCTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1970	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1365 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	2012 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	30 ft.	49.	Structure Length:	32 ft.
50A.	Sidewalk/Curb Left:	2.8 ft.	50B.	Sidewalk/Curb Right:	2.8 ft.
51.	Bridge Roadway Width:	24.2 ft.	52.	Deck Width (O-O)	30 ft.
32.	Approach Roadway Width:	21 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	24.2 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200078 Bridge Number: 22-00505

Facility Carried: SCRIBNER DR Feature(s) Intersected: FALLING RUN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	Oft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	19 (URBAN - LOCAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - UNEVEN SIDEWALKS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - CRACKS				
59.	Superstructure:	Material:	CONCRETE	Rating:	6
	SATIS - SPALL & EXPOSED STIRRUP BEAM #10, HL LONG. CR WATER SEEPAGE BETWEEN BEAMS	RACK APPF	ROX. 14' LONG ON BOTTOM OF BM, NEAR N END OF T	HE BEAM, EFFL. ANI)
60.	Substructure:	Material:	CONCRETE	Rating:	7
	GOOD - TOPS OF FOOTINGS EXPOSED, VERT. HL CRACK AT	CL OF N A	BUTMENT		
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	6
	SATIS - LARGE ROCKS, TRASH				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	71	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	47	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	30 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200078 Bridge Number: 22-00505

Facility Carried: SCRIBNER DR Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 9

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - LEVEL, CURVE BOTH WAYS, INT. WEST

Material: BITUMINOUS

Comments: SIDEWALKS SETTLED AT BR ENDS, TRANS. CRACKS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)
75B. Work Done By: 0
76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000

97. Year of Cost Estimate:

96.

Total Project Cost:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.

0 x 1000

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 79.8
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST DOWNSTREAM



LOOKING SOUTH FROM ROAD



NW AT HEAVY EFFL. ON SLAB AND NORTH ABUT.



NBI Number: 2200079 Bridge Number: 22-00506

Facility Carried: PAMELA DR Feature(s) Intersected: FALLING RUN CREEK

<u>IDEN</u>	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200079			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	PAMELA DR	16.	Latitude:	38.313
9.	Location:	00.20 N OF DAISY LANE	17.	Longitude:	-85.832535
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	01 (SLAB)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE	'			
27.	Year Built:	1949	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	779 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	1149 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	20.2 ft.	49.	Structure Length:	22.3 ft.
50A.	Sidewalk/Curb Left:	2.6 ft.	50B.	Sidewalk/Curb Right:	2.6 ft.
51.	Bridge Roadway Width:	32.5 ft.	52.	Deck Width (O-O)	37.5 ft.
32.	Approach Roadway Width:	30 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	5 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	36.5 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

NBI Number: 2200079 Bridge Number: 22-00506

Facility Carried: PAMELA DR Feature(s) Intersected: FALLING RUN CREEK

|--|

38.	Navigational Control:	0	40. Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116. Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:			

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	17 (URBAN - COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material	: CONCRETE	Rating:	5
	FAIR - CRACKS, LIGHT TO HEAVY EFFL., CONC. CURBS SPAL	LING AND	DETERIORATING		
58.01.	Wearing Surface:	Material	: BITUMINOUS (1")	Rating:	6
	SATIS - HEAVY. DETERIORATION/ SPALLING, MINOR CRACKS	, DELAMI	NATION UNDER THE BITUMINOUS WEARING SURFACE		
59.	Superstructure:	Material	: CONCRETE CRCS	Rating:	5
	FAIR - EXTENSIVE CRACKING & EFFL. THROUGHOUT BOTTOI SLIGHT SAG IN CRACKS	M OF SLA	B, STR. SAGS THROUGH SPAN, LIKELY FROM INITIAL	CONSTRUCTION,	
60.	Substructure:	Material	: CONCRETE	Rating:	5
	FAIR - VERTICAL CRACKS WITH EFFL. AND AREAS OF HONEY	COMBIN	G IN BOTH ABUTMENTS		
61.	Channel:	Material	: NATURAL & LG CONC. CHUNKS	Rating:	6
	SATIS - FLOW ALONG S ABUTMENT				
62.	Culvert/Ret:	Material	: N/A	Rating:	Ν
	N/A				

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	25	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	22	66C.	Tons Posted:	10 Tons
66B.	Gross Tons or H Rating:	10 Tons	66D.	Date Posted/Closed:	8/1/2007
41.	Open, Posted, or Closed:	P (POSTED FOR LOAD)	70.	Bridge Posting:	2 (3-5 TONS)

NBI Number: 2200079 Bridge Number: 22-00506

Facility Carried: PAMELA DR Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 5
 68. Geometry: 6
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 6 - BRIDGE IN H. CURVE & ON SLIGHT HUMP

Material: BITUMINOUS

Comments: SETTLING AT BRIDGE CORNERS, SETTLED, CRKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: 31 (REPLACE BRIDGE DUE TO DETERIORATION OF SUPERSTRUCTURE AND TO INCREASE

LOAD CAPACITY.)

75B. Work Done By: 1 (CONTRACT)

76. Improvement Length: 43 ft.

94. Bridge Improvement Costs: 202 x 1000

95. Roadway Improvement Costs: 184 x 1000

96. Total Project Cost: 488 x 1000

97. Year of Cost Estimate: 2020

RECOMMENDED MAINTENANCE

UNTIL BRIDGE REPLACEMENT RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S. CLEAN ON REPLACE VANDALIZED NORTH LOAD LIMIT SIGN.

INSPECTION DATA

90. Date: 3/3/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N
93. Date: B: C:

Unofficial Sufficiency Rating: 70.7
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH FROM ROAD



LOOKING NORTH AT NORTH FOOTING EXPOSED



NBI Number: 2200080 Bridge Number: 22-00507
Facility Carried: WILLIAM LN Feature(s) Intersected: MIDDLE CREEK

rdCII	iity carried: WILLIAM LN	Fe	ature(s)	Intersected: MIDDLE CRE	EEK
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200080			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	MIDDLE CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	WILLIAM LN	16.	Latitude:	38.27981
9.	Location:	00.10 S CORYDON PIKE	17.	Longitude:	-85.859489
<u>STRL</u>	JCTURE DATA	1			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	1 (CONCRETE CAST-IN-PLACE)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1952	106.	Reconstructed:	2008
42A.	Type of Service Over:	1 (HIGHWAY)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	327 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	3952 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	2 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	28.7 ft.	49.	Structure Length:	30.5 ft.
50A.	Sidewalk/Curb Left:	0.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	20 ft.	52.	Deck Width (O-O)	20.6 ft.
32.	Approach Roadway Width:	18 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	10 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	20 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.

0 ft.

56.

Lateral Left:

0 ft.

55B.

Lateral Right:

NBI Number: 2200080 Bridge Number: 22-00507
Facility Carried: WILLIAM LN Feature(s) Intersected: MIDDLE CREEK

NAVIGATION

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	17 (URBAN - COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	7
	GOOD - SPALLS ON COPING			
58.01.	Wearing Surface:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
59.	Superstructure:	Material: CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS			
60.	Substructure:	Material: CONCRETE	Rating:	6
	SATIS - SPALLS AT ALL 4 CORNERS, NE, NW, AND SE HAVE R	EDUCED BEARING AREAS		
61.	Channel:	Material: CONC SLURRY COVERED RIPRAP	Rating:	7
	GOOD - NORTH TOEWALL EXPOSED			
62.	Culvert/Ret:	Material: N/A	Rating:	Ν
	N/A			

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	77	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	56	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	40 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200080 Bridge Number: 22-00507
Facility Carried: WILLIAM LN Feature(s) Intersected: MIDDLE CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)

36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - RR HUMP & CURVE SOUTH, INT. NORTH

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKING, SETTLING AT BRIDGE CORNERS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 82.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH FROM ROAD



LOOKING NORTH AT NORTH ABUTMENT



NBI Number: 2200081 Bridge Number: 22-00508

Facility Carried: GRAYBROOK LN Feature(s) Intersected: FALLING RUN CREEK

IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200081			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	GRAYBROOK LN	16.	Latitude:	38.30111
9.	Location:	00.30 S OF DAISY LANE	17.	Longitude:	-85.822906
<u>STRI</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
AGE	OF SERVICE				
27.	Year Built:	1977	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	2992 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	4411 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	47.5 ft.	49.	Structure Length:	50 ft.
50A.	Sidewalk/Curb Left:	3.1 ft.	50B.	Sidewalk/Curb Right:	3.1 ft.
51.	Bridge Roadway Width:	32.5 ft.	52.	Deck Width (O-O)	40.5 ft.
32.	Approach Roadway Width:	30 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	32.5 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200081 Bridge Number: 22-00508

Facility Carried: GRAYBROOK LN Feature(s) Intersected: FALLING RUN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	17 (URBAN - COLLECTOR)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			
			l		

CONDITION

58.	Deck:	Material:	PRESTR. CONC. BOX BEAMS	Rating:	6
	SATIS - TREES OVERHANG ROADWAY, SOME WERE REMOVE	ED			
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	6
	SATIS - CRACKS AT BRIDGE ENDS				
59.	Superstructure:	Material:	PRESTR. CONC. BOX BEAMS	Rating:	6
	SATIS - SEEPAGE BETWEEN WIDENED BEAMSWITH EFFL. SE	EPAGE BE	ETWEEN INTERIOR BEAMS AT CENTERLINE		
60.	Substructure:	Material:	CONCRETE	Rating:	6
	SATIS - TOP OF NORTH FOOTING EXPOSED, 4 VERT. HL CRACABUTMENT, 4 VERT. HL CRACKS IN S ABUTMENT	CKS RANE	O CRACKS WITH DELAMS AT BEARING AREAS ABOVE	VERT. CRACKS IN N	I
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	6
	SATIS - TREES DOWNSTREAM SIDE OF STRUCTURE UNDER I	EAST COF	PING		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	71	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	50	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	39 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200081 Bridge Number: 22-00508

Facility Carried: GRAYBROOK LN Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, UPGRADE TO NORTH

Material: BITUMINOUS

Comments: PATCHED AT BRIDGE END AT S APPROACH SIDEWALKS ARE SETTLED AT ALL CORNERS

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. APPR. RAIL W/END TREATMENT AND NE & SW B.E.M.'S.

INSPECTION DATA

90. Date: 3/3/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N
93. Date: A: B: C:

Unofficial Sufficiency Rating: 95.7
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST DOWNSTREAM



LOOKING SOUTH FROM ROAD



LOOKING SOUTH AT SOUTH ABUTMENT



NBI Number: 2200082 Bridge Number: 22-00509

Facility Carried: PEARL ST Feature(s) Intersected: FALLING RUN CREEK

	,				
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200082			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	PEARL ST	16.	Latitude:	38.29021
9.	Location:	00.30 N OF SPRING ST	17.	Longitude:	-85.825134
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	1920	106.	Reconstructed:	1969
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	6719 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	9903 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	69.8 ft.	49.	Structure Length:	75 ft.
50A.	Sidewalk/Curb Left:	3.3 ft.	50B.	Sidewalk/Curb Right:	3.3 ft.
51.	Bridge Roadway Width:	26.5 ft.	52.	Deck Width (O-O)	34.3 ft.
32.	Approach Roadway Width:	26 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	26.5 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200082 Bridge Number: 22-00509

Facility Carried: PEARL ST Feature(s) Intersected: FALLING RUN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	17 (URBAN - COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE	Rating:	7
	GOOD - POPOUTS ON RAILING				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - CRACKS AT BRIDGE ENDS				
59.	Superstructure:	Material:	CONCRETE	Rating:	5
	FAIR - SEEPAGE BETWEEN BEAMS, HORIZONTAL HL CRACK ENDS OF W COPING BEAM	10" UP FR	OM BTM. ALONG E COPING BEAM, HL HORIZONTAL C	CRACKS AT BOTH	
60.	Substructure:	Material:	STONE	Rating:	6
	SATIS - SOME STONES DETERIORATING SLIGHTLY				
61.	Channel:	Material:	NATURAL ROCK BOTTOM	Rating:	6
	SATIS - STABLE, LARGE TREES ACROSS CHANNEL, FLOW AL	ONG SOL	TH ABUTMENT		
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	55	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	19	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	16 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200082 Bridge Number: 22-00509

Facility Carried: PEARL ST Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 4
 68. Geometry: 2
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)
 36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - TANGENT, UPGRADE TO NORTH, CURVE SOUTH

Material: BITUMINOUS

Comments: SIDEWALK SETTLED AT BRIDGE ENDS, TRANS. CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STANDARD APPROACH RAIL WITH END TREATMENT AND NE, SE AND SW B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 48.2

Unofficial Structural and Functional Classification: 2 (FUNCTIONALLY OBSOLETE)



LOOKING SOUTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING NORTH FROM ROAD



LOOKING EAST AT HAIRLINE CRACKS WITH EFFL. AT THE



NBI Number: 2200089 Bridge Number: 22-00510

Facility Carried: CHARLESTOWN RD Feature(s) Intersected: BLACKISTON RUN

<u>IDEN</u>	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200089			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	BLACKISTON RUN	11.	Mile Point (over):	0
7.	Facility Carried:	CHARLESTOWN RD	16.	Latitude:	38.33443
9.	Location:	00.70 S I-265	17.	Longitude:	-85.798798
STRU	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	0 (NONE)
108C.	Protection	0 (NONE)			
<u>AGE</u>	OF SERVICE				
27.	Year Built:	2001	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	5	28B.	Lanes Under Structure:	0
29.	ADT - Over:	26213 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	38638 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	5 %Trucks	19.	Bypass Detour Length:	2 mi.
	METRIC DATA				
48.	Maximum Span Length:	24.1 ft.	49.	Structure Length:	27 ft.
50A.	Sidewalk/Curb Left:	6.0 ft.	50B.	Sidewalk/Curb Right:	6.0 ft.
51.	Bridge Roadway Width:	68 ft.	52.	Deck Width (O-O)	68 ft.
32.	Approach Roadway Width:	68 ft.	33.	Bridge Median:	1 (OPEN MEDIAN)
34.	Skew:	34 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	68 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200089 Bridge Number: 22-00510

Facility Carried: CHARLESTOWN RD Feature(s) Intersected: BLACKISTON RUN

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material:	N/A	Rating:	Ν
	N/A				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	7
	GOOD - CRACKS				
59.	Superstructure:	Material:	N/A	Rating:	Ν
	N/A				
60.	Substructure:	Material:	N/A	Rating:	Ν
	N/A				
61.	Channel:	Material:	CONCRETE BOTTOM	Rating:	7
	GOOD - CONCRETE BOTTOM THRU CULVERT				
62.	Culvert/Ret:	Material:	4-SIDED CONCRETE BOX	Rating:	7
	\ensuremath{GOOD} - $\ensuremath{VERTICAL}$ HAIRLINE CRACKS W/ LT. EFFL. IN WALLS, I RUST STAINS	LONG. HA	IRLINE CRACKS IN TOP OF STRUCTURE. ALL WITH E	FFL., SOME WITH	

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200089 Bridge Number: 22-00510

Facility Carried: CHARLESTOWN RD Feature(s) Intersected: BLACKISTON RUN

APPRAISAL

67. Structural: 7
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)
 72. Roadway Alignment: 6 - CURVE S., INT. N., IN SAG VERT. CURVE

Material: BITUMINOUS

Comments: CRACKS, SMALL POTHOLES

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

NO MAINTENANCE NEEDED.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 95.3
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING EAST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING WEST FROM ROAD



LOOKING NORTH AT LOG JAM 50 FT. UPSTREAM



NBI Number: 2200083 Bridge Number: 22-00511
Facility Carried: DAISY LN Feature(s) Intersected: TRINITY RUN

1			. ,		l l
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200083			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	TRINITY RUN	11.	Mile Point (over):	0
7.	Facility Carried:	DAISY LN	16.	Latitude:	38.31007
9.	Location:	00.00 INT OF GREENVALLEY	17.	Longitude:	-85.836189
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	8 (UNKNOWN)			
AGE	OF SERVICE				
27.	Year Built:	1971	106.	Reconstructed:	1995
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	3	28B.	Lanes Under Structure:	0
29.	ADT - Over:	6360 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	9374 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	20.1 ft.	49.	Structure Length:	23 ft.
50A.	Sidewalk/Curb Left:	5.1 ft.	50B.	Sidewalk/Curb Right:	5.1 ft.
51.	Bridge Roadway Width:	41.3 ft.	52.	Deck Width (O-O)	54.3 ft.
32.	Approach Roadway Width:	41 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	41.3 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.
		,			

NBI Number: 2200083 Bridge Number: 22-00511
Facility Carried: DAISY LN Feature(s) Intersected: TRINITY RUN

|--|

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	7					
	GOOD - LONGITUDINAL CRACKS, HL CRACKS ACROSS DECK, APPROACH GUARD RAIL DAMAGE AT NE & NW								
58.01.	Wearing Surface:	Material: INTEGRAL CONCRETE	Rating:	7					
	GOOD - CRACKED OVER BEAM JOINTS								
59.	Superstructure:	Material: CONCRETE	Rating:	8					
	VERY GOOD - NO MAJOR DEFECTS								
60.	Substructure:	Material: CONCRETE	Rating:	7					
	GOOD - E ABUTMENT 3 VERT. HL CRACKS, W ABUTMENT 3 VERT. HL CRACKS, WEST ABUTMENT CRACKING WITH RUST STAINS UNDER BEAM NO. 5								
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	7					
	GOOD - AGGRADATION, LOCAL SCOUR AT NORTHWEST CORNER, FLOW INTO NW CORNER AND ALONG E ABUTMENT, OVERGROWN CHANNEL BANKS, LOG JAM 50' UPSTREAM NORTH OF BRIDGE								
62.	Culvert/Ret:	Material: N/A	Rating:	Ν					
	N/A								

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	3 (LOAD RESISTANCE FACTOR (LRFR))
64.	Operating Rating:	79	65.	Inv Rating Method:	3 (LOAD AND RESISTANCE FACTOR (LRFR))
66.	Inventory Rating:	46	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	26 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200083 Bridge Number: 22-00511
Facility Carried: DAISY LN Feature(s) Intersected: TRINITY RUN

APPRAISAL

 67.
 Structural:
 7

 68.
 Geometry:
 4

 69.
 Underclearance:
 N

 71.
 Waterway Adequacy:
 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 6 - TANGENT, SILT UPGRADE TO E, INT W END

Material: BITUMINOUS

Comments: GUARDRAIL DAMAGE NW & SW, NE QUADRANTS, NEW BITUMINOUS ON BOTH APPROACHES.

SIDEWALKS SETTLE AT ALL CORNERS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

RECOMMENDED MAINTENANCE

Year of Cost Estimate:

RECOMMEND INSTALLING CURRENT STD. ALL B.E.M.'S.

INSPECTION DATA

97.

90. Date: 3/3/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N

93. Date: A: B: C

Unofficial Sufficiency Rating: 82.3
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING EAST DOWNSTREAM



LOOKING SOUTH FROM ROAD



NE HAIRLINE CRACKS IN THE NORTH ABUT.



NBI Number: 2200084 Bridge Number: 22-00512
Facility Carried: GREEN VALLEY RD Feature(s) Intersected: TRINITY RUN

			. ,		
IDEN	<u>ITIFICATION</u>				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200084			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	TRINITY RUN	11.	Mile Point (over):	0
7.	Facility Carried:	GREEN VALLEY RD	16.	Latitude:	38.31049
9.	Location:	00.10 N OF DAISY LANE	17.	Longitude:	-85.836525
STRU	JCTURE DATA	ı			
43A.	Structure Type - Main Span:	5 (PRESTRESSED CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	05 (ADJACENT BOX BEAM)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	1 (MONOLITHIC CONCRETE)	108B.	Membrane:	8 (UNKNOWN)
108C.	Protection	8 (UNKNOWN)			
AGE	OF SERVICE				
27.	Year Built:	1971	106.	Reconstructed:	1995
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	3	28B.	Lanes Under Structure:	0
29.	ADT - Over:	7076 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	10431 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	6 %Trucks	19.	Bypass Detour Length:	1 mi.
<u>GEO</u>	METRIC DATA				
48.	Maximum Span Length:	23.3 ft.	49.	Structure Length:	25.5 ft.
50A.	Sidewalk/Curb Left:	5.0 ft.	50B.	Sidewalk/Curb Right:	5.0 ft.
51.	Bridge Roadway Width:	41.3 ft.	52.	Deck Width (O-O)	54.3 ft.
32.	Approach Roadway Width:	41 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	30 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	41.3 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	Oft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.
		,			

NBI Number: 2200084 Bridge Number: 22-00512
Facility Carried: GREEN VALLEY RD Feature(s) Intersected: TRINITY RUN

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION

58.	Deck:	Material: CONCRETE	Rating:	7				
	GOOD - HAIRLINE LONGITUDINAL CRACKS, SIDEWALKS SETTLED 3" AT NW, SE, SW 1" AT NE							
58.01.	Wearing Surface:	Material: INTEGRAL CONCRETE	Rating:	7				
	GOOD - CRACKS OVER BEAM JOINTS							
59.	Superstructure:	Material: CONCRETE	Rating:	8				
	VERY GOOD - NO MAJOR DEFECTS							
60.	Substructure:	Material: CONCRETE	Rating:	7				
	GOOD - TOPS OF FOOTINGS EXPOSED, 4 VERT. HL CRACKS W/LT. EFFL. IN N ABUTMENT, 4 VERT. HL CRACKS W/LT. EFFL. IN S ABUTMENT, 2 DELAM/ SPALL IN S ABUTMENT, WATER SEEPAGE AT BEAM BEARINGS							
61.	Channel:	Material: RIPRAP & NATURAL	Rating:	6				
	SATIS - AGGRADATION, SCOUR, RIPRAP WASHED INTO CHAI BANKS	NNEL FROM BANK AT SW STR. CREATING RIPRAP DAM, OVER	GROWN CHANNEL					
62.	Culvert/Ret:	Material: N/A	Rating:	Ν				
	N/A							

3 (LOAD RESISTANCE FACTOR (LRFR))	Oper Rating Method:	N) 63.	0 (UNKNOWN)	Design Load:	31.
3 (LOAD AND RESISTANCE FACTOR (LRFR))	Inv Rating Method:	65.	84	Operating Rating:	64.
Tons	Tons Posted:	17 66C.	47	Inventory Rating:	66.
	Date Posted/Closed:	ns 66D.	26 Tons	Gross Tons or H Rating:	66B.
5 (EQUAL TO OR ABOVE LEGAL LOADS)	Bridge Posting:	N) 70.	A (OPEN)	Open, Posted, or Closed:	41.
		1			

NBI Number: 2200084 Bridge Number: 22-00512
Facility Carried: GREEN VALLEY RD Feature(s) Intersected: TRINITY RUN

APPRAISAL

67. Structural: 7
 68. Geometry: 4
 69. Underclearance: N
 71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)
 36B. Traffic Safety Features (Transitions): 1 (MEETS ACCEPTABLE STANDARDS)
 36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)
 36D. Traffic Safety Features (Approach Guardrail Ends): 1 (MEETS ACCEPTABLE STANDARDS)

72. Roadway Alignment: 8 - TANGENT, UPGRADE TO NORTH, INT. SOUTH

Material: BITUMINOUS

Comments: SETTLED, CRACKS AT BRIDGE END, AT NORTH, NEW BITUMINOUS TO SOUTH SIDEWALK ARE

SETTLING ALL CORNERS, GUARDRAIL DAMAGED AT SOUTHEAST APPR.

113. Scour Critical Bridges: 5 (STABLE - WITHIN LIMITS)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length: 0 ft.
94. Bridge Improvement Costs: 0 x 1000
95. Roadway Improvement Costs: 0 x 1000
96. Total Project Cost: 0 x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. ALL B.E.M.'S. REMOVE RIPRAP FROM CENTER OF CHANNEL TO THE SLOPES.

INSPECTION DATA

90.Date:3/3/202091.Des. Inspection Frequency:24 Months92.Critical Feature Inspection:A:NB:NC:N

93. Date: A: B: C

Unofficial Sufficiency Rating: 82.2
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING NORTH FROM ROAD




LOOKING WEST FROM CHANNEL



LOOKING SOUTH FROM ROAD



LOOKING EAST FROM CHANNEL



NBI Number: 2200085 Bridge Number: 22-00513

Facility Carried: STATE ST Feature(s) Intersected: FALLING RUN CREEK

IDEN	ITIFICATION				
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200085			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	STATE ST	16.	Latitude:	38.28931
9.	Location:	00.20 N OF SPRING ST	17.	Longitude:	-85.825905
STRU	JCTURE DATA	1			
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	19 (CULVERT)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	N (N/A - UNDER FILL)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	N (N/A)
108C.	Protection	N (N/A)			
AGE	OF SERVICE	·			
27.	Year Built:	1940	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	32690 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	48185 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	9 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	30 ft.	49.	Structure Length:	32 ft.
50A.	Sidewalk/Curb Left:	5.0 ft.	50B.	Sidewalk/Curb Right:	5.0 ft.
51.	Bridge Roadway Width:	52 ft.	52.	Deck Width (O-O)	52 ft.
32.	Approach Roadway Width:	52 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	52 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	0 ft.	56.	Lateral Left:	0 ft.

NBI Number: 2200085 Bridge Number: 22-00513

Facility Carried: STATE ST Feature(s) Intersected: FALLING RUN CREEK

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

112.	NBIS Bridge Length:	Υ	12.	Base Highway Network:	0
104.	Highway System - Over:	0 (NOT ON NHS)	13A.	LRS Inventory Route:	
26.	Func. Class - Over:	16 (URBAN - MINOR ARTERIAL)	13B.	LRS Inventory Subroute:	
100.	Defense Highway Des:	0	101.	Parallel Structure Des:	N
102.	Direction of Traffic:	2 (2-WAY TRAFFIC)	103.	Temporary Structure Des:	
110.	Des. Nat. Network:	0	20.	Toll:	3 (ON FREE ROAD-NO TOLL)
21.	Maint. Responsibility:	02 (COUNTY HIGHWAY AGENCY)	22.	Owner:	02 (COUNTY HIGHWAY AGENCY)
37.	Historical Significance:	5 (NOT ELIGIBLE)			

CONDITION 58. Deck:

50.	Book.	Waterial. 14	V// \	rtating.	1 4		
	N/A						
58.01.	Wearing Surface:	Material: B	BITUMINOUS (2")	Rating:	8		
	VERY GOOD - NEW OVERLAY, TRANSVERSE CRACKS						
59.	Superstructure:	Material: N	J/A	Rating:	Ν		
	N/A						
60.	Substructure:	Material: N	I/A	Rating:	Ν		
	N/A						
61.	Channel:	Material: N	NATURAL ROCKY BOTTOM	Rating:	7		
	GOOD - BROKEN CONC. AND BRICKS ON SLOPES, DEEP CHANNEL THROUGH STRUCTURE						
62.	Culvert/Ret:	Material: C	CONCRETE ARCH	Rating:	7		
	GOOD - HAIRLINE CRACKS, SPALLS						

Material: N/A

Rating:

Ν

31.	Design Load:	0 (UNKNOWN)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)

NBI Number: 2200085 Bridge Number: 22-00513

Facility Carried: STATE ST Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 7
68. Geometry: 9

69. Underclearance: N

71. Waterway Adequacy: 8

36A. Traffic Safety Features (Bridge Railings): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

72. Roadway Alignment: 8 - LEVEL & TANGENT

Material: BITUMINOUS
Comments: NEW OVERLAY

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By: ()

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE & APPR. RAIL W/END TREATMENT AND ALL B.E.M.'S.

INSPECTION DATA

90. Date: 3/3/2020
91. Des. Inspection Frequency: 24 Months
92. Critical Feature Inspection: A: N B: N C: N
93. Date: A: B: C:

Unofficial Sufficiency Rating: 93.9
Unofficial Structural and Functional Classification: 0 (OK)



LOOKING WEST FROM ROAD




LOOKING SOUTH DOWNSTREAM



LOOKING EAST FROM ROAD



LOOKING WEST AT WATER SEEPAGE, EFFL AT JOINTS



STRUCTURE INVENTORY AND APPRAISAL REPORT - 1

NBI Number: 2200104 Bridge Number: 22-00514

Facility Carried: COUNTRY CLUB DR Feature(s) Intersected: FALLING RUN CREEK

<u>IDEN</u>	<u>ITIFICATION</u>	I			
1.	State:	185 (INDIANA)	4.	City/Town:	52326 (NEW ALBANY)
8.	NBI Number:	2200104			
5.	Inventory Route On:	1-5-1- 0-0	98.	Border Bridge:	
2.	District:	05 (SEYMOUR)	99.	Border Bridge Number:	
3.	County:	022 (FLOYD)			
6.	Feat Intersected:	FALLING RUN CREEK	11.	Mile Point (over):	0
7.	Facility Carried:	COUNTRY CLUB DR	16.	Latitude:	38.3042
9.	Location:	00.40 W OF GRAYBROOK LN	17.	Longitude:	-85.829666
<u>STRL</u>	JCTURE DATA				
43A.	Structure Type - Main Span:	1 (CONCRETE)	44.	Structure Type - Approach:	000
43B.	Structure Type - Main Span - Const.	11 (DECK ARCH)	45.	Number of Spans - Main:	1
107.	Deck Structure Type:	2 (CONCRETE PRECAST)	46.	Number of Spans - Approach:	0000
108A.	Wearing Surface:	6 (BITUMINOUS)	108B.	Membrane:	0 (NONE)
108C.	Protection	1 (EPOXY COATED REINFORCING)			
AGE	OF SERVICE	'			
27.	Year Built:	2004	106.	Reconstructed:	0
42A.	Type of Service Over:	5 (HIGHWAY/PEDESTRIAN)	42B.	Type of Service Under:	5 (WATERWAY)
28A.	Lanes on Structure:	2	28B.	Lanes Under Structure:	0
29.	ADT - Over:	1559 VPD	30.	ADT Year Over:	2014
114.	Future ADT:	2298 VPD	115.	Future ADT Year:	2034
109.	Average Truck Traffic:	3 %Trucks	19.	Bypass Detour Length:	1 mi.
GEO	METRIC DATA				
48.	Maximum Span Length:	22 ft.	49.	Structure Length:	23 ft.
50A.	Sidewalk/Curb Left:	4.0 ft.	50B.	Sidewalk/Curb Right:	0.0 ft.
51.	Bridge Roadway Width:	32 ft.	52.	Deck Width (O-O)	47.7 ft.
32.	Approach Roadway Width:	32 ft.	33.	Bridge Median:	0 (NO MEDIAN)
34.	Skew:	0 Degree(s)	35.	Structure Flared:	0 (NO FLARE)
10.	Defense Vertical Clearance:	99.99	53.	Vertical Clearance/Deck:	99.99 ft.
47.	Total Horiz. Clearance:	43.7 ft.	54A.	Min Vert Clear Code:	N
55A.	Min Latr. Cl. Right - Code:	N	54B.	Underclearance:	0 ft.
55B.	Lateral Right:	Oft.	56.	Lateral Left:	0 ft.

STRUCTURE INVENTORY AND APPRAISAL REPORT - 2

NBI Number: 2200104 Bridge Number: 22-00514

Facility Carried: COUNTRY CLUB DR Feature(s) Intersected: FALLING RUN CREEK

NAVIGATION	N	٩V	IGA	١T٨	0	N
------------	---	----	------------	-----	---	---

38.	Navigational Control:	0	40.	Navigational Horizontal Clearance:	0 ft.
39.	Navigational Vertical Clearance:	0 ft.	116.	Vertical Clearance - Lift Bridge:	ft.
111.	Pier/Abutment Protection:				

CLASSIFICATION

0	Base Highway Network:	12.	Υ	NBIS Bridge Length:	112.
	LRS Inventory Route:	13A.	0 (NOT ON NHS)	Highway System - Over:	104.
	LRS Inventory Subroute:	13B.	17 (URBAN - COLLECTOR)	Func. Class - Over:	26.
N	Parallel Structure Des:	101.	0	Defense Highway Des:	100.
	Temporary Structure Des:	103.	2 (2-WAY TRAFFIC)	Direction of Traffic:	102.
3 (ON FREE ROAD-NO TOLL)	Toll:	20.	0	Des. Nat. Network:	110.
02 (COUNTY HIGHWAY AGENCY)	Owner:	22.	02 (COUNTY HIGHWAY AGENCY)	Maint. Responsibility:	21.
			5 (NOT ELIGIBLE)	Historical Significance:	37.

CONDITION

58.	Deck:	Material:	CONCRETE BOX	Rating:	6
	SATIS - NO MAJOR DEFECTS				
58.01.	Wearing Surface:	Material:	BITUMINOUS (2")	Rating:	6
	SATIS - TRANS. CRACKS				
59.	Superstructure:	Material:	CONCRETE BOX STRUCTURE	Rating:	6
	SATIS - EFFL. BETWEEN JOINTS, 3RD SEGMENT FROM S HAS	SURFACE	CRACKS AND EFFL.		
60.	Substructure:	Material:	CONCRETE	Rating:	8
	VERY GOOD - NO MAJOR DEFECTS				
61.	Channel:	Material:	RIPRAP & NATURAL	Rating:	7
	GOOD - NO MAJOR DEFECTS				
62.	Culvert/Ret:	Material:	N/A	Rating:	Ν
	N/A				

LOAD RATING AND POSTING

31.	Design Load:	5 (HS 20)	63.	Oper Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
64.	Operating Rating:	36	65.	Inv Rating Method:	0 (FIELD EVAL AND ENG JUDGEMENT)
66.	Inventory Rating:	36	66C.	Tons Posted:	Tons
66B.	Gross Tons or H Rating:	20 Tons	66D.	Date Posted/Closed:	
41.	Open, Posted, or Closed:	A (OPEN)	70.	Bridge Posting:	5 (EQUAL TO OR ABOVE LEGAL LOADS)
			l		

STRUCTURE INVENTORY AND APPRAISAL REPORT - 3

NBI Number: 2200104 Bridge Number: 22-00514

Facility Carried: COUNTRY CLUB DR Feature(s) Intersected: FALLING RUN CREEK

APPRAISAL

67. Structural: 6
 68. Geometry: 5
 69. Underclearance: N
 71. Waterway Adequacy: 7

36A. Traffic Safety Features (Bridge Railings): 1 (MEETS ACCEPTABLE STANDARDS)

36B. Traffic Safety Features (Transitions): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

36C. Traffic Safety Features (Approach Guardrail): 1 (MEETS ACCEPTABLE STANDARDS)

36D. Traffic Safety Features (Approach Guardrail Ends): 0 (DOES NOT MEET ACCEPTABLE STANDARDS/SAFETY FEATURE IS REQUIRED)

2. Roadway Alignment: 6 - STRAIGHT DRIVE IN SW QUADRANT

Material: BITUMINOUS

Comments: LONG. AND TRANS. CRACKS

113. Scour Critical Bridges: 8 (STABLE - EXCELLENT CONDITION)

Comments:

PROPOSED IMPROVEMENTS

75A. Type of Work: (NO WORK NEEDED.)

75B. Work Done By:

76. Improvement Length:
94. Bridge Improvement Costs:
95. Roadway Improvement Costs:
96. Total Project Cost:
97. O ft.
98. Total Project Cost:
98. O x 1000

97. Year of Cost Estimate:

RECOMMENDED MAINTENANCE

RECOMMEND INSTALLING CURRENT STD. BRIDGE RAIL AND ALL B.E.M.'S.

INSPECTION DATA

 90.
 Date:
 3/3/2020
 91.
 Des. Inspection Frequency:
 24 Months

 92.
 Critical Feature Inspection:
 A:
 N
 B:
 N
 C:
 N

 93.
 Date:
 A:
 B:
 C:
 C:

Unofficial Sufficiency Rating: 97.9
Unofficial Structural and Functional Classification: 0 (OK)

FLOYD COUNTY INDIANA

APPENDIX A

NBI ITEM
DESCRIPTIONS AND
STRUCTURE TYPE
ABBREVIATIONS

DESCRIPTION OF ITEMS STRUCTURE INVENTORY AND APPRAISAL SHEET

- 1. State: "Indiana" (185) for all bridges.
- 2. **Hwy. District:** INDOT* highway district number in which the bridge is located.
- 3. **County:** County code and name.
- 4. **City/Town:** City and town code and name are listed. Bridges are listed as being in an urban area rather than within actual corporation limits. This item is coded all "zeros" for bridges in rural locations.
- 5. **Inventory Route:** This is the road inventory route number used by Indiana LTAP** and INDOT.
- 6. **Features Intersected:** This is the stream, road, railroad and/or other features under the bridge.
- 7. **Facility Carried:** This is the name of the local road as named by the county.
- 8. **NBI Number:** This is the bridge number which, in general, follows Indiana LTAP bridge numbering system.
- 9. **Location:** The location of the bridge using local road designations, county lines, other locally recognized features, or map boundary location codes.
- 10. **Defense Vert. Clear:** This is the minimum vertical clearance for a 10-foot width of the pavement or traveled part of the inventory route roadway where the clearance is the greatest. A code of 9999 means unlimited.
- 11. **Milepoint:** Zeroes for all bridges.
- 16. **Latitude:** The latitude found on USGS/ESRI maps.
- 17. **Longitude:** The longitude found on USGS/ESRI maps.
- 19. **Bypass Length:** This is the total additional travel, to the nearest mile, for a vehicle which would result from closing of the bridge.
- 20. **Toll:** All of the bridges under county jurisdiction are toll free and carry a toll free highway. This item is "On Free Road" (30 for all of these bridges).
- 21. **Maintenance Responsibility:** County for most or all bridges.
- 22. **Owner:** County for most or all bridges.

^{*} the Indiana Department of Transportation

^{**} formerly Highway Extension and Research Project for Indiana Counties & Cities (HERPICC)

26. **Functional Classification:** Functional classification of the road over the bridge as determined by information from INDOT.

<u>Code</u>	<u>Description</u>
01	Principal Arterial – Interstate - Rural
02	Principal Arterial – Other
06	Minor Arterial – Rural
07	Major Collector – Rural
80	Minor Collector – rural
09	Local – Rural
11	Principal Arterial – Interstate – Urban
12	Principal Arterial – Other Freeways or Expressways
14	Other Principal Arterial – Urban
16	Minor Arterial – Urban
17	Collector – Urban
19	Local - Urban

- 27. Year Built: Year (or approximate year) the bridge was built.
- 28. **Lanes on Str.:** Lanes of highway traffic carried on the structure and lanes of highway traffic under the bridge.
- 29. **ADT:** Current average daily traffic count on bridge to the nearest ten vehicles. These were estimated where recent counts were not available.
- 30. **Year of ADT:** Year traffic count was taken or estimated.
- 31. **Design Load:** The live load which the bridge was originally designed to carry. Except for recent bridges where construction plans are available, this value is unknown.
- 32. **Approach Roadway Width/Shldr.:** Shoulder-to-shoulder width of the approach roadway.
- 33. **Bridge Median:** Describes the median on a bridge, whether none, open or closed.
- 34. **Skew:** The angle of bridge skew to the nearest degree.
- 35. **Structure Flared:** Describes whether or not the bridge varies in width. Minor flares such as flared wings are ignored. "Yes" (1) or "No" (0).
- 36A. **Traffic Safety Features:** 4 digits telling whether the bridge railing, transitions, approach guardrail, and approach guardrail terminal ends "meet" (1) or "do not meet" (0) currently acceptable standards.
- 37. **Historical Significance:** This item indicates that a bridge may be a particularly unique example of the history of engineering; the crossing itself might be significant; the bridge may be associated with a historical property or area; or the bridge may be associated with significant events or circumstances. One of the following 1-digit codes is used as applicable:

<u>Code</u>	<u>Description</u>
1	Bridge is on the National Register of Historic Places.
2	Bridge is eligible for the National Register of Historic Places.
3	Bridge is possibly eligible for the National Register of Historic Places
	or bridge is on a State or Local historic register. (Requires further
	investigation before determination can be made.)
4	Historical significance is not determinable at this time.
5	Bridge is not eligible for the National Register of Historic Places.

- 38. **Navigation Control:** Describes whether or not navigation control exists on navigable streams. "Yes" (1) or "No" (0).
- 39. **Navigation Vertical Clearance:** Minimum navigation vertical clearance in feet as shown on the navigation permit issued by the controlling agency, for Item 38 coded "Yes" (1). Otherwise, code all "zeros" (N.A.; not applicable).
- 40. **Navigation Horizontal Clearance:** Minimum navigation horizontal clearance in feet as shown on the navigation permit issued by the controlling agency, for Item 38 coded "Yes" (1). Otherwise, code all "zeros" (N.A.; not applicable).
- 41. **Open, Posted or Closed:** This item indicates the operational status of the bridge: "K" = closed to all traffic, "P" = open to traffic with load posted, "A" = open to traffic without load posted, "B" = open; posting recommended, "G" = new bridge; not yet open.
- 42. **Type Service:** Describes the function of the bridge. This is usually highway or highway-pedestrian.
- 43. **Structure Type-Main:** The structural type of bridge for the main spans of the bridge.
- 44. **Structure Type-Approach:** The structural type for the approach spans, if they are a different material or construction type than the main spans.
- 45. **Number of Spans-Main:** The number of spans in the main units of the bridge.
- 46. **Number of Spans-Approach:** The number of spans in the approach units of the bridge.
- 47. **Total Horizontal Clearance:** The distance to the nearest tenth of a foot between the most restrictive features limiting the roadway. Where no such features existed, the deck width was used. When two clearances are recorded after this item, the second clearance is the distance between the most restrictive features limiting the use of the highway or railroad under the bridge. This is recorded only when the bridge is over a highway or railroad.
- 48. **Maximum Span Length:** The length to the nearest tenth of a foot of the longest span.
- 49. **Structure Length:** The total length of bridge from backwall to backwall to the nearest foot.
- 50. Sidewalk/Curb Width: (Left) (Right): The width of sidewalks on the bridge to the nearest tenth of a foot. Narrow curbs (less than 2'-0") are not considered sidewalks, but are still reported.

- 51. **Bridge Roadway Width (Curb-Curb):** The distance between curbs on the bridge to the nearest tenth of a foot. Where curbs do not exist, the distance between parapets, railings or guardrails is used.
- 52. **Deck Width (Out-Out):** The total width of the bridge roadway to the nearest tenth of a foot.
- 53. **Vert. Clear over Deck:** The minimum vertical clearance over the bridge roadway to the nearest inch. A code of 9999 means unlimited vertical clearance.
- 54. **Vertical Underclearance:** The minimum vertical clearance beneath the structure measured from the roadway or railroad track to the underside of the superstructure, in feet and inches. Coded all "zeros" (N.A.; not applicable) for structures over any other feature.
- 55. **Lateral Underclearance Right:** The minimum lateral under-clearance to the nearest tenth of a foot on the right for roads and railroads under a bridge measured from the edge of roadway or centerline of railroad track to the nearest substructure unit. Right is with respect to the direction of travel.
- 56. **Lateral Underclearance Left:** The minimum lateral underclearance to the nearest tenth of a foot on the left for one-way roads under a bridge measured from the edge of roadway to the nearest substructure unit. Left is with respect to the direction of travel.
- 58. **Deck:** Describes the material and condition of the bridge floor, expansion joints, curbs, railings, deck drains and other associated items.
- 58.01. Wearing Surface: Describes the material and condition of the wearing surface.
- 59. **Superstructure:** Describes the material and condition of the deck supporting members, their connections and bearings.
- 60. **Substructure:** Describes the material and condition of the superstructure supporting elements such as abutments, piers, bents, piles and others.
- 61. **Channel & Channel Protection:** Describes the channel, its protections and any problems associated with the channel.
- 62. **Culvert & Retaining Wall:** Describes primarily bridge wingwalls, retaining walls and culverts associated with the bridge. Lists material, condition and erosion problems.
- 64. **Operating Rating:** Operating rating is the maximum live load that can be occasionally carried by a bridge. See Item 66, Inventory Rating.
- 66. **Inventory Rating:** Inventory rating is the maximum live load that can safely utilize an existing structure for an indefinite period of time. The range of loading above the inventory rating up to the operating rating should be allowed only by written permit from the County.
- 67. **Structural Condition:** Describes major structural deficiencies.
- 68. **Deck Geometry:** Describes deficiencies in deck width.
- 69. **Underclearance:** Describes deficiencies in the vertical and lateral underclearances of a roadway or railroad under the bridge.

- 70. **Bridge Posting:** Describes the load capacity, relative to the legal load allowed, to show when posting is required.
- 71. **Waterway Adequacy:** Describes deficiencies in the waterway, the bridge opening and slope protection at the bridge. The waterway opening under the bridge was judged to be adequate or inadequate from drift and other signs and without a hydraulic analysis.
- 72. **Approach Roadway Alignment:** Describes the deficiencies of the approach alignment, pavement width, shoulder width, signs, delineators, sight distances and other features relating to safety.
- 75. **Type of Work:** Describes the type of work recommended as repair, widening, replacement or construction of a new bridge at the same or another location or for a new type of service.

<u>Code</u>	<u>Description</u>
31	Replacement – Load/Geometry
32	Replacement – Relocation
33	Widening – No Deck Rehab.
34	Widening – With Deck Rehab.
35	Rehabilitation – Deterioration
36	Deck Rehabilitation – Some Widening
37	Deck Replacement – Some Widening
38	Other Structural Work
01	Contract
02	Local Forces

- 76. **Improvement Length:** The length of the proposed improvement.
- 90. **Inspection Date:** The date the structure was inspected.
- 91. **Designated Inspection Frequency:** The designated inspection interval, in months, for each bridge in the inventory. Bridges will require special non-scheduled inspections after unusual physical traumas.
- 92. **Critical Feature Inspection:** Critical features, which need special inspections or special emphasis during inspections, are identified, along with the designated inspection interval as follows:

<u>Code</u>	<u>Description</u>
92A	Fracture Critical Details
92B	Underwater Inspection
92C	Other Special Inspection

- 93. **Critical Feature Inspection Date:** The date of last inspection of the critical feature(s) identified in Item 92.
- 94. **Bridge Improvement Cost:** Only bridge construction costs are included. No bridge maintenance costs are included.

- 95. **Roadway Improvement Cost:** Only roadway construction costs are included. No roadway maintenance costs are included.
- 96. **Total Project Cost:** All costs normally associated with the proposed bridge improvement project, including right-of-way, detour, preliminary engineering, construction inspection and other incidental costs are included. No maintenance costs are included.
- 97. **Year of Improvement Cost Estimate:** The base year of the improvement costs provided in Items 94 through 96, with cost data provided to be no more than 8 years old.
- 98. **Border Bridge:** Indicates if a bridge is located on a borderline between two neighboring states. Many states split maintenance responsibilities and costs for any replacement or rehabilitation work.
- 99. **Border Bridge Structure Number:** Indicates the neighboring state's NBI structure number, for a structure noted in Item 98.
- 100. **Defense Highway Designation:** Identifies a bridge on the designated defense highway network, including minor off-system roads. None exist in this county, since only State bridges are presently on defense highways.
- 101. **Parallel Structure Designation:** Indicates situations where separate structures carry the inventory route in opposite directions of travel over the same feature.
- 102. **Direction of Traffic:** Provides information as follows:

<u>Code</u>	<u>Description</u>
0	Highway traffic not carried
1	1-way traffic
2	2-way traffic
3	One-lane bridge for 2-way traffic

- 103. **Temporary Structure Designation:** Identifies temporary structure(s) or conditions, which are required to facilitate traffic flow.
- 104. **Highway System:** Indicates the highway system for the inventory route, identified in Item 5, as follows:

<u>Code</u>	<u>Description</u>
0	Non NHS (National Highway System)
1	NHS

106. **Year Reconstructed:** Indicates the year of reconstruction or rehabilitation of the structure, where applicable.

For a bridge to be defined as reconstructed, the type of work performed, whether or not it meets current minimum standards, must have been eligible for funding under any of the Federal-aid funding categories. The eligibility criteria would apply to the work performed regardless of whether all state or local funds or Federal-aid funds were used.

107. **Deck Structure Type:** Describes the type of deck system on the bridge. If more than one type of deck system is on the bridge, the most predominant is indicated.

108. **Wearing Surface/Protective System:** Indicates information on the wearing surface and protective system of the bridge deck, as follows:

<u>Code</u>	<u>Description</u>
108A	Type of Wearing Surface
108B	Type of Membrane
108C	Deck Protection

- 109. **Average Daily Truck Traffic:** Indicates the percentage of Item 29 Average Daily Traffic that is truck traffic, not including vans, pickup trucks and other light delivery trucks.
 - *The percentage of truck traffic is only recorded when Item 29 Average Daily Traffic is greater than 100 vehicles.
- 110. **Designated National Network:** Indicates any roads on the designated national network for trucks identified in the code of Federal Regulations (23 CFR 658). No county roads are so designated.
- 111. **Pier or Abutment Protection (for Navigation):** Applies only to bridges over navigable channels (See Item 38 Navigation Control).
- 112. **NBIS Bridge Length:** Indicates a bridge that meets or exceeds the minimum length (more than 20 feet) specified to be designated as a bridge for National Bridge Inspection Standards purposes.
- 113. **Scour Critical Bridges:** Identifies the current status of the bridge regarding its vulnerability to scour, as follows:
 - N = The bridge is not over a waterway and the scour rating is thus not applicable.
 - 9= Bridge foundations, including piles, are on dry land well above flood elevations.
 - 8= Bridge foundations are determined to be stable because scour is above top of footing by qualitative assessment, by quantitative assessment (calculation), or by virtue of properly designed countermeasures.
 - 7= Countermeasures have been installed to mitigate an existing scour problem, or a plan of action has been implemented to reduce risk to the public that might result from a bridge failure during or immediately after a flood event.
 - 6= No scour evaluation has yet been made; this should not be the case for most bridges, but might occur with the jurisdictional transfer of an old bridge or due to other unusual circumstances.
 - 5= Bridge foundations are determined to stable because scour is within the limits of footing or piles by qualitative assessment, by quantitative assessment (calculation), or by virtue of properly designed countermeasures.
 - 4= Bridge foundations were determined to be stable by qualitative assessment or quantitative assessment (calculation), but field review indicates action is required to protect exposed foundations.

- 3= Bridge foundations are determined to be unstable because qualitative assessment or quantitative assessment (calculation) indicates scour is within limits of footing or piles, or assessment indicates scour is below spread footing base or pile tips.
- 2= Field review indicates extensive scour has occurred; bridge foundations are unstable because observed scour is below calculated acceptable limits, or because of observed scour conditions reported in item 60 (thus affecting substructure stability).
- 1= Bridge is closed to traffic; field review indicates failure of piers or abutments is imminent because observed scour is below calculated acceptable limits, or because of observed scour conditions reported in item 60 (thus affecting substructure stability).
- 0= Bridge has failed and is closed to traffic.
- U= Bridge foundations are unknown and not yet evaluated for scour; POA is required.
- 114. Future Average Daily Traffic: Indicates the forecasted average daily traffic (ADT) for the inventory route identified in Item 5. This has been projected at least 17 years but no more than 22 years from the year data was submitted to the NBI, to provide a basis for a 20-year forecast. Where planning data was not available, the best estimate based on site familiarity was used.
- 115. **Year of Future Average Daily Traffic:** Indicates the year represented by the future ADT in Item 114. The projected year of future ADT is at least 17 years but no more than 22 years from the year data was submitted to the NBI.
- 116. **Minimum Navigation Vertical Clearance**

Vertical Lift Bridge: Record to the nearest foot (rounding down) the minimum vertical clearance (in the dropped or closed position) imposed at the site as measured above a datum that is specified on a navigation permit issued by a control agency.

Items 58 through 62 and Item 65 are given a numerical "CONDITION" rating as follows:

Rating	Description
N	Not Applicable.
9	New Condition.
8	Very Good Condition: No repairs needed.
7	Good Condition: Some minor problems.
6	Satisfactory Condition: Potential exists for "major maintenance" with major items in need of repair by maintenance forces.
5	Fair Condition: Potential exists for "minor rehabilitation" with major repair by contract needed.

4	Poor Condition: Potential exists for "major rehabilitation" with minimum adequacy to tolerate present traffic; immediate rehabilitation necessary to keep open.
3	Serious Condition: Repair or rehabilitation required immediately with inadequacy to tolerate present heavy load; "warrants closing bridge to trucks."
2	Critical Condition: The need for repair or rehabilitation is urgent. The facility should be closed until the indicated repair is complete with inadequacy to tolerate any live load; "warrants closing bridge to all traffic."
1	Imminent Failure Condition: The "facility is closed." Study should determine the feasibility of the bridge being repairable, if desirable to reopen to traffic.
0	Failed Condition: The "facility is closed" and the bridge conditions are beyond repair; "danger of immediate collapse."

Items 67 through 72 are given a numerical "APPRAISAL" rating as follows:

Rating	<u>Description</u>
N	Not Applicable.
9	Superior to present desirable criteria.
8	Equal to present desirable criteria.
7	Better than present minimum criteria.
6	Equal to present minimum criteria.
5	Somewhat better than minimum adequacy to tolerate being left in place as is.
4	Meets minimum tolerable limits to be left in place as is.
3	Basically intolerable condition requiring high priority of repair.
2	Basically intolerable condition requiring high priority of replacement.
0	Closed, immediate replacement necessary to put back in service.

CURRENT ACCEPTABLE BRIDGE TYPES

1016	43A	43B		DESCRIPTION
1028	101A	RCS		REINFORCED CONCRETE SLAB
1028 RCB	101B		(2)	PRECAST CONCRETE SLAB
ROBOT REINFORCED CONCRETE GIRDER (trans. Girder) floor beam system 104				
105 RCBG REINFORCED CONCRETE BOX GIRDER - multiple 106 RCBG REINFORCED CONCRETE BOX GIRDER - single 107A RCRF REINFORCED CONCRETE BOX GIRDER - single 107B RCBF REINFORCED CONCRETE BOX 111A RCA REINFORCED CONCRETE BOX 111A RCA REINFORCED CONCRETE BOX 111B RCAOS REINFORCED CONCRETE ARCH 111D UGA UNREINFORCED CONCRETE ARCH 111D PCA PRECAST CONCRETE ARCH - UNDER FILL 111B RCAUF (1) REINFORCED CONCRETE BOX - UNDER FILL 111B RCBUF REINFORCED CONCRETE ARCH - UNDER FILL 111B PCAUF (1) PRECAST CONCRETE ARCH - UNDER FILL 111D PCA PRECAST CONCRETE BEAM (channel beam) 111D PCA PRECAST CONCRETE BOX GIRDER - single PCA PRECAST CONCRETE BOX GIRDER PCA				
105				, ,
106 RCBG REINFORCED CONCRETE BOX GIRDER - single 107A RCRF REINFORCED CONCRETE RIGID FRAME 107B RCB REINFORCED CONCRETE BOX 111A RCA REINFORCED CONCRETE ARCH 111B RCAOS REINFORCED CONCRETE ARCH 111C UCA UNREINFORCED CONCRETE ARCH 111D PCA PRECAST CONCRETE BOX - UNDER FILL 111B RCAUF (1) REINFORCED CONCRETE BASH - UNDER FILL 111B RCAUF (1) REINFORCED CONCRETE BOX - UNDER FILL 111B RCAUF (1) REINFORCED CONCRETE GREN - UNDER FILL 111B RCAUF (1) REINFORCED CONCRETE GREN - UNDER FILL 111B PCAUF (1) PRECAST CONCRETE ARCH - UNDER FILL 111B PCAUF (1) PRECAST CONCRETE ARCH - UNDER FILL 111B PCAUF (1) PRECAST CONCRETE BOX - UNDER FILL 111B PCAUF (1) PRECAST CONCRETE BOX - UNDER FILL 111B PCAUF (1) PRECAST CONCRETE BEAM (channel beam) 11D PCAUF (1) PRECAST CONCRETE BEAM (continuous REINFORCED CONCRETE BOX GIRDER - multiple 11D PCAUF (1) PRECAST CONCRETE BEAM (continuous REINFORCED CONCRETE BOX GIRDER - multiple 11D PCAUF (1) PRECAST CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 11D PCAUF (1) PRECAST CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 11D PCAUF (1) PRECAST CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 11D PCAUF (1) PRECAST CONTINUOUS REINFORCED CONCRETE BOX UNDER FILL 11D PCAUF (1) PRECAST CONTINUOUS REINFORCED CONCRETE BOX UNDER FILL 11D PCAUF (1) PRECA				
1078 RCRF REINFORCED CONCRETE RIGID FRAME RCA REINFORCED CONCRETE BOX REINFORCED CONCRETE BOX REINFORCED CONCRETE ARCH OPEN SPANDREL UCA UNIVERIFORCED CONCRETE ARCH OPEN SPANDREL UCA UNIVERIFORCED CONCRETE ARCH OPEN SPANDREL UCA UNIVERIFORCED CONCRETE ARCH OPEN SPANDREL UTA UCA UNIVERIFORCED CONCRETE ARCH OPEN SPANDREL UTA UTA UTA UNIVERIFORCED CONCRETE ARCH OPEN SPANDREL UTA				
107B RCB REINFORCED CONCRETE BOX REINFORCED CONCRETE ARCH 111B RCAOS REINFORCED CONCRETE ARCH 111C UCA UNREINFORCED CONCRETE ARCH 111D PCA PRECAST CONCRETE ARCH UNDER FILL 111D RCGUF REINFORCED CONCRETE ARCH UNDER FILL 111D RCGUF REINFORCED CONCRETE ARCH UNDER FILL 111D RCGUF REINFORCED CONCRETE GRIPE UNDER FILL 111D PCAUF (1) PRECAST SLAB - UNDER FILL 111D PCAUF (1) PRECAST CONCRETE ARCH UNDER FILL 111D PCAUF (1) PRECAST CONCRETE ARCH UNDER FILL 111D PCAUF (1) PRECAST CONCRETE BEAM (channel beam) 11D PCAUF (1) PRECAST CONCRETE BEAM (channel beam) 11D PCAUF (1) PRECAST CONCRETE BEAM (channel beam) 11D PCAUF (1) PRECAST CONCRETE BEAM UNDER FILL (PrecaST) 11D PCAUF (1) PRECAST CONCRETE BEAM UNDER FILL (PRECAST CONTINUO				
111A RCA REINFORCED CONCRETE ARCH - OPEN SPANDREL 111B RCAOS REINFORCED CONCRETE ARCH - OPEN SPANDREL 111C				
111B RCAOS REINFORCED CONCRETE ARCH - OPEN SPANDREL				
UNCA UNREINFORCED CONCRETE ARCH				
1110				
THRU REINFORCED CONCRETE ARCH				
119A RCSUF (2) REINFORCED CONCRETE SLAB - UNDER FILL 119B RCAUF (1) REINFORCED CONCRETE ARCH - UNDER FILL 119C RCSUF REINFORCED CONCRETE BOX - UNDER FILL 119D RCGUF REINFORCED CONCRETE BOX - UNDER FILL 119D RCGUF REINFORCED CONCRETE GIRDER - UNDER FILL 119F PCAUF (1) PRECAST CONCRETE ARCH - UNDER FILL 119F PCSUF (2) PRECAST SLAB - UNDER FILL 119G RCPUF REINFORCED CONCRETE BEAM (channel beam) 122 PCB PRECAST SLAB - UNDER FILL (Precast) 123 PCB PRECAST CONCRETE BEAM (channel beam) 124 PCB PRECAST CONCRETE BEAM (channel beam) 125 PCB PRECAST CONCRETE BEAM (channel beam) 126 CRCS CONTINUOUS REINFORCED CONCRETE SLAB 127 PCB CONTINUOUS REINFORCED CONCRETE BEAM 128 CRCG CONTINUOUS REINFORCED CONCRETE BEAM 129 CRCB CONTINUOUS REINFORCED CONCRETE BEAM 120 CRCB CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - SINGLE REINFORCED CONCRETE BEAM (channel beam) 120 CRCBG CONTINUOUS REINFORCED CONCRETE BEAM (channel beam) 120 CR				
119B RCAUF (1) REINFORCED CONCRETE ARCH - UNDER FILL 119C RCBUF REINFORCED CONCRETE BOX - UNDER FILL 119E PCAUF (1) PRECAST CONCRETE GIRDER - UNDER FILL 119E PCAUF (1) PRECAST SCHAB - UNDER FILL 119F PCSUF (2) PRECAST SCHAB - UNDER FILL 119G RCPUF REINFORCED CONCRETE PIPE - UNDER FILL (Precast) 122 PCB PRECAST SCHAB - UNDER FILL (Precast) 123 PCB PRECAST CONCRETE BEAM (channel beam) 124 PCB PRECAST CONCRETE BEAM (channel beam) 125 PCB PRECAST CONCRETE BEAM (channel beam) 126 RCCVS CONTINUOUS REINFORCED CONCRETE SCHAB 127 CONTINUOUS REINFORCED CONCRETE SCHAB 128 CRCG CONTINUOUS REINFORCED CONCRETE BEAM 129 CRCB CONTINUOUS REINFORCED CONCRETE BEAM 120 CONTINUOUS REINFORCED CONCRETE BEAM 120 CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX 121 CRCA CONTINUOUS REINFORCED CONCRETE BOX 122 CPCB CONTINUOUS REINFORCED CONCRETE BOX 124 CCSCG CONTINUOUS REINFORCED CONCRETE BOX 125 CONTINUOUS REINFORCED CONCRETE BOX 126 CRCBG CONTINUOUS REINFORCED CONCRETE BOX 127 CRCA CONTINUOUS REINFORCED CONCRETE BOX 128 CCBUF CONTINUOUS REINFORCED CONCRETE BOX 129 CRCBG CONTINUOUS REINFORCED CONCRETE BOX 120 CRCBG CONTIN				
1190 RCBUF REINFORCED CONCRETE BOX - UNDER FILL 1191 RCGUF REINFORCED CONCRETE GIRDER - UNDER FILL 1192 PCAUF (1) PRECAST CONCRETE FARCH - UNDER FILL 1194 PCSUF (2) PRECAST SLAB - UNDER FILL 1195 PCSUF (2) PRECAST SLAB - UNDER FILL 1196 RCPUF REINFORCED CONCRETE PIPE - UNDER FILL (Precast) 122 PCB PRECAST CONCRETE BEAM (channel beam) 2014 CRCS CONTINUOUS REINFORCED CONCRETE SLAB 2018 CRCYS CONTINUOUS REINFORCED CONCRETE GIRDER 2020 CRCG CONTINUOUS REINFORCED CONCRETE GIRDER 2021 CRCB CONTINUOUS REINFORCED CONCRETE BEAM 203 CRCGT CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS REINFORCED CONCRETE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX GIRDER - SINGle 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CRCB CONTINUOUS REINFORCED CONCRETE BOX 213 CRCB CONTINUOUS REINFORCED CONCRETE BOX 214 CCSCG CONTINUOUS REINFORCED CONCRETE BOX 215 CRCB CONTINUOUS REINFORCED CONCRETE BOX 216 CRCB CONTINUOUS REINFORCED CONCRETE BOX 217 CRCA CONTINUOUS REINFORCED CONCRETE BOX 218 CCBUF CONTINUOUS REINFORCED CONCRETE BOX 219 CCBUF CONTINUOUS REINFORCED CONCRETE BOX 210 CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CPCB CONTINUOUS REINFORCED CONCRETE BOX 213 CRCB CONTINUOUS REINFORCED CONCRETE BOX 214 CRCA CONTINUOUS REINFORCED CONCRETE BOX 215 CRCB CONTINUOUS REINFORCED CONCRETE BOX 216 CRCB CONTINUOUS REINFORCED CONCRETE BOX 217 CRCA CONTINUOUS REINFORCED CONCRETE BOX 218 CRCB CRCB CRCB CRCB 219 CRCB CRCB CRCB CRCB CRCB CR				
119D RCGUF REINFORCED CONCRETE GIRDER - UNDER FILL 119F PCAUF (1) PRECAST CONCRETE ARCH - UNDER FILL 119F PCSUF (2) PRECAST SLAB - UNDER FILL 119G RCPUF REINFORCED CONCRETE PIPE - UNDER FILL (Precast) 122 PCB PRECAST CONCRETE BEAM (channel beam) 123 PCB PRECAST CONCRETE BEAM (channel beam) 124 PCS CONTINUOUS REINFORCED CONCRETE SLAB 2018 CRCVS CONTINUOUS REINFORCED CONCRETE SUBB 2028 CRCG CONTINUOUS REINFORCED CONCRETE GIRDER 2028 CRCG CONTINUOUS REINFORCED CONCRETE BEAM 2030 CRCGT CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS REINFORCED CONCRETE BEAM 205 CRCGG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCGG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CRCB CONTINUOUS REINFORCED CONCRETE BOX 213 CRCB CONTINUOUS REINFORCED CONCRETE BOX 214 CRCG CONTINUOUS REINFORCED CONCRETE BOX 215 CRUFT CONTINUOUS REINFORCED CONCRETE BOX 216 CRUFT CONTINUOUS REINFORCED CONCRETE BOX 217 CRCA CONTINUOUS REINFORCED CONCRETE BOX 218 CRUFT CONTINUOUS REINFORCED CONCRETE BOX 219 CRUFT CONTINUOUS REINFORCED CONCRETE BOX 210 CRUFT CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CPCB CONTINUOUS REINFORCED CONCRETE BOX 213 CRUFT CONTINUOUS REINFORCED CONCRETE BOX 214 CRCG CONTINUOUS REINFORCED CONCRETE BOX 215 CRUFT CRUFT CRUFT 216 CRUFT CRUFT CRUFT 217 CRCA CONTINUOUS REINFORCED CONCRETE BOX 218 CRUFT CRUFT CRUFT 219 CRUFT CRUFT CRUFT 210 CRUFT CRUFT CRUFT 210 CRUFT CRUFT CRUFT 210 CRUFT CRUFT CRUFT 210 CRUFT			(1)	
119E PCAUF (1) PRECAST CONCRETE ARCH - UNDER FILL 119F PCSUF (2) PRECAST SUAB - UNDER FILL 119G RCPUF REINFORCED CONCRETE PIPE - UNDER FILL (Precast) 122 PCB PRECAST CONCRETE BEAM (channel beam) 123 PCB PRECAST CONCRETE BEAM (channel beam) 124 PCB PRECAST CONCRETE BEAM (channel beam) 125 PCB PRECAST CONCRETE BEAM (channel beam) 126 CRCS CONTINUOUS REINFORCED CONCRETE VOIDED SLAB 127 CRCS CONTINUOUS REINFORCED CONCRETE GIRDER 128 CRCG CONTINUOUS REINFORCED CONCRETE BEAM 129 CRCB CONTINUOUS REINFORCED CONCRETE BEAM 120 CCTB CONTINUOUS CONCRETE GIRDER (trans. Girder) floor beam system 120 CCTB CONTINUOUS CONCRETE TEE BEAM 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 120 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 120 CORCRET CONTINUOUS REINFORCED CONCRETE RIGID FRAME 120 CRCBF CONTINUOUS REINFORCED CONCRETE BOX (SIRDER - single 120 CRCBF CONTINUOUS REINFORCED CONCRETE BOX 121 CRCA CONTINUOUS REINFORCED CONCRETE BOX 121 CRCA CONTINUOUS REINFORCED CONCRETE BOX 121 CRCA CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 122 CPCB CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 123 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 124 CSCG CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 125 CORUMAN CONCRETE STAYED CABLE GIRDER 126 CORUMAN CONCRETE STAYED CABLE GIRDER 127 CONCRETE STAYED CABLE GIRDER 128 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 129 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 129 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 120 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 120 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 120 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 120 CCSUF CONTINUOUS REINFORCED CONCRETE BLAB - UNDER FILL 120 CC				
119F				
Table Richard Reinforced Concrete Pipe - Under Fill (Precast)				
PCB			(2)	
201A CRCS CONTINUOUS REINFORCED CONCRETE SLAB 201B CRCVS CONTINUOUS REINFORCED CONCRETE VOIDED SLAB 202A CRCG CONTINUOUS REINFORCED CONCRETE GIRDER 202B CRCB CONTINUOUS REINFORCED CONCRETE BEAM 203 CRCGT CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS CONCRETE TEE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CCCG CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 213B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 214B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 215B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 216C CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 217B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 218B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CRCB CONTINUOUS REINFORCED CONCRETE BOX 22C CRCB CONTINUOUS CONCRETE STEEL BEAM 23CD REINFORCED CONCRET				
201B CRCVS CONTINUOUS REINFORCED CONCRETE VOIDED SLAB 202A CRCG CONTINUOUS REINFORCED CONCRETE GIRDER 202B CRCB CONTINUOUS REINFORCED CONCRETE BEAM 203 CRCGT CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS CONCRETE TEE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CRCB CONTINUOUS REINFORCED CONCRETE BOX 213 CRCB CONTINUOUS CONCRETE STAYED CABLE GIRDER 214 CCSCG CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 215 CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 216 CCBUF CONTINUOUS PRECAST CONCRETE BOX - UNDER FILL 217 CRCB CONTINUOUS PRECAST CONCRETE BOX - UNDER FILL 22 CPCB CONTINUOUS PRECAST CONCRETE BOX - UNDE				
202A CRCG CONTINUOUS REINFORCED CONCRETE BEAM 203 CRCGT CONT. REIN. CONCRETE BEAM 204 CCTB CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS CONCRETE TEE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 212 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B CCSUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B CCSUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B CCSUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B CCSUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B COSTELL RAILROAD "FIPE CAS" 300A SRRFC STEEL RAILROAD "FIPE CAS" </td <td></td> <td></td> <td></td> <td></td>				
202B CRCB CONTINUOUS REINFORCED CONCRETE BEAM 203 CRCGT CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS CONCRETE TEE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS REINFORCED CONCRETE ARCH 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302F				
203 CRCGT CONT. REIN. CONCRETE GIRDER (trans. Girder) floor beam system 204 CCTB CONTINUOUS CONCRETE TEE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS REINFORCED CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL BEAM 302C RPG RIVETED PLATE GIRDER 302C RPG RIVETED PLATE GIRDER 302F SPG STEEL BEAM 303C KSB COMPOSITE STEEL BOX GIRDER 303A ESG COMPOSITE STEEL BOX GIRDER 303B SG SIMPLE STEEL BOX GIRDER 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C WSTG WELDED PLATE GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system				
204 CCTB CONTINUOUS CONCRETE TEE BEAM 205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL BEAM 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL BEAM 302F SPG STEEL PLATE GIRDER 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BEAM 303H ESG ENCASED STEEL GIRDER 303A ESG ENCASED STEEL GIRDER 303B SG SIMPLE STEEL BEAM 303B SG SIMPLE STEEL BEAM 303C KSB COMPOSITE STEEL BEAM SIMPLE STEEL BEAM 303B SG SIMPLE STEEL BEAM Floor beam system 303C KSB COMPOSITE STEEL BEAM Floor beam system 303C WSG WSG WELDED PLATE GIRDER - floor beam system				
205 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - multiple 206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE RIGID FRAME 207B CRCB CONTINUOUS REINFORCED CONCRETE RIGID FRAME 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "FIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302C RPG RIVETED PLATE GIRDER 302F SPG STEEL PLATE GIRDER 302F SPG STEEL PLATE GIRDER 302F SPG STEEL PLATE GIRDER 302F KSB COMPOSITE STEEL BEAM 302F SPG STEEL BEAM 302F SPG STEEL BEAM 302F SPG STEEL GIRDER 302F KSB COMPOSITE STEEL GIRDER 303C KSB COMPOSITE STEEL BOX GIRDER 303C KSB COMPOSITE STEEL GIRDER 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system				
206 CRCBG CONTINUOUS REINFORCED CONCRETE BOX GIRDER - single 207A CRCRF CONTINUOUS REINFORCED CONCRETE RIGID FRAME 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL BEAM 302E SG SIMPLE STEEL GIRDER 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER 303A ESG ENCASED STEEL GIRDER 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BOX GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB RPG RIVETED PLATE GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system				
207A CRCRF CONTINUOUS REINFORCED CONCRETE RIGID FRAME 207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 22C CPCB CONTINUOUS PRECAST CONCRETE BOX - UNDER FILL 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL GIRDER 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303C KSG COMPOSITE STEEL GIRDER - floor beam system 303D KSG COMPOSITE STEEL BEAM - floor beam system 303C WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED STEEL THRU GIRDER - floor beam system				
207B CRCB CONTINUOUS REINFORCED CONCRETE BOX 211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BOX - UNDER FILL 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL BEAM 302E SG STEEL PLATE GIRDER 302B KSB COMPOSITE STEEL BEAM 302C RSB COMPOSITE STEEL BOX GIRDER 302C RSB COMPOSITE STEEL GIRDER - floor beam system 303C RSB COMPOSITE STEEL GIRDER - floor beam system 303C RSB COMPOSITE STEEL GIRDER - floor beam system 303C RSB COMPOSITE STEEL GIRDER - floor beam system 303C RSB COMPOSITE STEEL GIRDER - floor beam system 303C RSB RPG RIVETED PLATE GIRDER - floor beam system 303C RSB RPG RIVETED PLATE GIRDER - floor beam system				·
211 CRCA CONTINUOUS REINFORCED CONCRETE ARCH 214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL GIRDER 302F SPG STEEL PLATE GIRDER 302F SPG STEEL PLATE GIRDER 302F SPG STEEL BEAM 302H KSG COMPOSITE STEEL BOX 302H KSG COMPOSITE STEEL GIRDER 302H KSBG COMPOSITE STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE ST				
214 CCSCG CONTINUOUS CONCRETE STAYED CABLE GIRDER 219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL BEAM 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER 303B SG SIMPLE STEEL GIRDER 303C KSB COMPOSITE STEEL BOX GIRDER 303C KSB COMPOSITE STEEL BOX GIRDER 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system				
219A RCSUF CONTINUOUS REINFORCED CONCRETE SLAB - UNDER FILL 219B CCBUF CONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL 222 CPCB CONTINUOUS PRECAST CONCRETE BEAM (channel beam) 300A SRRFC STEEL RAILROAD "FLAT CAR" 300B SRRP STEEL RAILROAD "PIPE CAR" (Look at 319B and 319D) 302A ESB ENCASED STEEL BEAM 302B ESG ENCASED STEEL GIRDER 302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL BEAM 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL BEAM - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL GIRDER - floor beam system				
219BCCBUFCONTINUOUS REINFORCED CONCRETE BOX - UNDER FILL222CPCBCONTINUOUS PRECAST CONCRETE BEAM (channel beam)300ASRRFCSTEEL RAILROAD "FLAT CAR"300BSRRPSTEEL RAILROAD "PIPE CAR" (Look at 319B and 319D)302AESBENCASED STEEL BEAM302BESGENCASED STEEL GIRDER302CRPGRIVETED PLATE GIRDER302DSBSIMPLE STEEL BEAM302ESGSIMPLE STEEL GIRDER302FSPGSTEEL PLATE GIRDER302GKSBCOMPOSITE STEEL BEAM302HKSGCOMPOSITE STEEL GIRDER302IKSBGCOMPOSITE STEEL BOX GIRDER303AESGENCASED STEEL GIRDER - floor beam system303BSGSIMPLE STEEL GIRDER - floor beam system303CKSBCOMPOSITE STEEL BEAM - floor beam system303DKSGCOMPOSITE STEEL GIRDER - floor beam system303EWSTGWELDED STEEL THRU GIRDER - floor beam system303FRPGRIVETED PLATE GIRDER - floor beam system303GWPGWELDED PLATE GIRDER - floor beam system				
222CPCBCONTINUOUS PRECAST CONCRETE BEAM (channel beam)300ASRRFCSTEEL RAILROAD "FLAT CAR"300BSRRPSTEEL RAILROAD "PIPE CAR" (Look at 319B and 319D)302AESBENCASED STEEL BEAM302BESGENCASED STEEL GIRDER302CRPGRIVETED PLATE GIRDER302DSBSIMPLE STEEL BEAM302ESGSIMPLE STEEL GIRDER302FSPGSTEEL PLATE GIRDER302GKSBCOMPOSITE STEEL BEAM302HKSGCOMPOSITE STEEL GIRDER302IKSBGCOMPOSITE STEEL BOX GIRDER303AESGENCASED STEEL GIRDER - floor beam system303BSGSIMPLE STEEL GIRDER - floor beam system303CKSBCOMPOSITE STEEL BEAM - floor beam system303DKSGCOMPOSITE STEEL GIRDER - floor beam system303EWSTGWELDED STEEL THRU GIRDER - floor beam system303FRPGRIVETED PLATE GIRDER - floor beam system303GWPGWELDED PLATE GIRDER - floor beam system				
300ASRRFCSTEEL RAILROAD "FLAT CAR"300BSRRPSTEEL RAILROAD "PIPE CAR" (Look at 319B and 319D)302AESBENCASED STEEL BEAM302BESGENCASED STEEL GIRDER302CRPGRIVETED PLATE GIRDER302DSBSIMPLE STEEL BEAM302ESGSIMPLE STEEL GIRDER302FSPGSTEEL PLATE GIRDER302GKSBCOMPOSITE STEEL BEAM302HKSGCOMPOSITE STEEL GIRDER302IKSBGCOMPOSITE STEEL BOX GIRDER303AESGENCASED STEEL GIRDER - floor beam system303BSGSIMPLE STEEL GIRDER - floor beam system303CKSBCOMPOSITE STEEL BEAM - floor beam system303DKSGCOMPOSITE STEEL GIRDER - floor beam system303EWSTGWELDED STEEL THRU GIRDER - floor beam system303FRPGRIVETED PLATE GIRDER - floor beam system303GWPGWELDED PLATE GIRDER - floor beam system				
300BSRRPSTEEL RAILROAD "PIPE CAR" (Look at 319B and 319D)302AESBENCASED STEEL BEAM302BESGENCASED STEEL GIRDER302CRPGRIVETED PLATE GIRDER302DSBSIMPLE STEEL BEAM302ESGSIMPLE STEEL GIRDER302FSPGSTEEL PLATE GIRDER302GKSBCOMPOSITE STEEL BEAM302HKSGCOMPOSITE STEEL GIRDER302IKSBGCOMPOSITE STEEL BOX GIRDER303AESGENCASED STEEL GIRDER - floor beam system303BSGSIMPLE STEEL GIRDER - floor beam system303CKSBCOMPOSITE STEEL BEAM - floor beam system303DKSGCOMPOSITE STEEL GIRDER - floor beam system303EWSTGWELDED STEEL THRU GIRDER - floor beam system303FRPGRIVETED PLATE GIRDER - floor beam system303GWPGWELDED PLATE GIRDER - floor beam system				
302AESBENCASED STEEL BEAM302BESGENCASED STEEL GIRDER302CRPGRIVETED PLATE GIRDER302DSBSIMPLE STEEL BEAM302ESGSIMPLE STEEL GIRDER302FSPGSTEEL PLATE GIRDER302GKSBCOMPOSITE STEEL BEAM302HKSGCOMPOSITE STEEL GIRDER302IKSBGCOMPOSITE STEEL BOX GIRDER303AESGENCASED STEEL GIRDER - floor beam system303BSGSIMPLE STEEL GIRDER - floor beam system303CKSBCOMPOSITE STEEL BEAM - floor beam system303DKSGCOMPOSITE STEEL GIRDER - floor beam system303EWSTGWELDED STEEL THRU GIRDER - floor beam system303FRPGRIVETED PLATE GIRDER - floor beam system303GWPGWELDED PLATE GIRDER - floor beam system				
302BESGENCASED STEEL GIRDER302CRPGRIVETED PLATE GIRDER302DSBSIMPLE STEEL BEAM302ESGSIMPLE STEEL GIRDER302FSPGSTEEL PLATE GIRDER302GKSBCOMPOSITE STEEL BEAM302HKSGCOMPOSITE STEEL GIRDER302IKSBGCOMPOSITE STEEL BOX GIRDER303AESGENCASED STEEL GIRDER - floor beam system303BSGSIMPLE STEEL GIRDER - floor beam system303CKSBCOMPOSITE STEEL BEAM - floor beam system303DKSGCOMPOSITE STEEL GIRDER - floor beam system303EWSTGWELDED STEEL THRU GIRDER - floor beam system303FRPGRIVETED PLATE GIRDER - floor beam system303GWPGWELDED PLATE GIRDER - floor beam system				
302C RPG RIVETED PLATE GIRDER 302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL GIRDER 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL BOX GIRDER 302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
302D SB SIMPLE STEEL BEAM 302E SG SIMPLE STEEL GIRDER 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL GIRDER 302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
302E SG SIMPLE STEEL GIRDER 302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL GIRDER 302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
302F SPG STEEL PLATE GIRDER 302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL GIRDER 302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
302G KSB COMPOSITE STEEL BEAM 302H KSG COMPOSITE STEEL GIRDER 302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
302H KSG COMPOSITE STEEL GIRDER 302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
302I KSBG COMPOSITE STEEL BOX GIRDER 303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
303A ESG ENCASED STEEL GIRDER - floor beam system 303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
303B SG SIMPLE STEEL GIRDER - floor beam system 303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				
303C KSB COMPOSITE STEEL BEAM - floor beam system 303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				SIMPLE STEEL GIRDER - floor beam system
303D KSG COMPOSITE STEEL GIRDER - floor beam system 303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system		KSB		COMPOSITE STEEL BEAM - floor beam system
303E WSTG WELDED STEEL THRU GIRDER - floor beam system 303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				COMPOSITE STEEL GIRDER - floor beam system
303F RPG RIVETED PLATE GIRDER - floor beam system 303G WPG WELDED PLATE GIRDER - floor beam system				WELDED STEEL THRU GIRDER - floor beam system
303G WPG WELDED PLATE GIRDER - floor beam system	303F	RPG		RIVETED PLATE GIRDER - floor beam system
307 WGRF WELDED GIRDER RIGID FRAME				WELDED PLATE GIRDER - floor beam system
	307	WGRF		WELDED GIRDER RIGID FRAME

309	SDT	STEEL DECK TRUSS
310A	SPT	STEEL PONY TRUSS
310B	STT	STEEL THRU TRUSS
310C	BT	BAILEY TRUSS
311	MPA	METAL PIPE ARCH (round pipe)
312A	STA	STEEL TIED ARCH
312B	TSA	THRU STEEL ARCH
313	SUSP	STEEL SUSPENSION
314	SCSG	STEEL, CABLE-STAYED, GIRDER
316	BB	BASCULE BRIDGE (lift bridge)
	MPAUF	MULTIPLATE ARCH - UNDER FILL
319B	SRPUF	STEEL RAILROAD "PIPE CAR" - UNDER FILL
319C	MPUF	METAL PIPE - ROUND PIPE - UNDER FILL
319D	MPAUF	METAL PIPE - ARCH - UNDER FILL
402A	CSB	CONTINUOUS STEEL BEAM
402B	CSG	CONTINUOUS STEEL GIRDER
402C	CESB	CONTINUOUS ENCASED STEEL BEAM
402D	KCSB	COMPOSITE CONTINUOUS STEEL BEAM
402E	KCSG	COMPOSITE CONTINUOUS STEEL GIRDER
402F	KCSBG	COMPOSITE CONTINUOUS STEEL BOX GIRDER
402G	CRSBG	CONTINUOUS RIVETED STEEL BOX GIRDER
402H	CRPG	CONTINUOUS RIVETED PLATE GIRDER
403A	CSG	CONTINUOUS STEEL GIRDER - floor beam system
403B	KCSG	COMPOSITE CONT. STEEL GIRDER - floor beam system
403C	CRPG	CONTINUOUS RIVETED PLATE GIRDER - floor beam system
	KCRPG	COMPOSITE CONTINUOUS RIVETED PLATE GIRDER - floor beam system
406	KCSBG	COMPOSITE CONTINUOUS STEEL BOX GIRDER - multiple & spread
410	CSTT	CONTINUOUS STEEL THRU TRUSS PLUS DECK TRUSS
412	CSTA	CONTINUOUS STEEL TIED ARCH
421	SBG	STEEL BOX GIRDER
501A	PPCS	PRESTRESSED PRECAST CONCRETE SLAB
501B	PTRCS	POST-TENSIONED REINFORCED CONCRETE SLAB
502	PCIB	PRESTRESSED CONCRETE I-BEAM
503	PTCTG	POST-TENSIONED CONCRETE THRU GIRDER
504	РСТВ	PRESTRESSED CONCRETE TEE-BEAM
505	PCBB	PRESTRESSED CONCRETE BOX BEAMS - multiple
506	PCBB	PRESTRESSED CONCRETE BOX BEAMS - spread
601	PTRCS	CONTINUOUS POST-TENSIONED REINFORCED CONCRETE SLAB
602	CPCIB	CONTINUOUS PRESTRESSED CONCRETE I-BEAM
604	СРСТВ	CONTINUOUS PRESTRESSED CONCRETE TEE BEAM
605	CPCBB	CONTINUOUS PRESTRESSED CONCRETE BOX BEAMS - multiple
606	CPCBB	CONTINUOUS PRESTRESSED CONCRETE BOX BEAMS - spread
614	CPTCS	CONTINUOUS POST-TENSIONED CABLE-STAYED
621	PTCBG	POST-TENSIONED CONCRETE BOX GIRDER - continuous (segmental)
701	TS	TIMBER SLAB
702A	TB	TIMBER BEAM
702B	TG	TIMER GIRDER
702C	TT	TIMBER TRESTLE
710	TCB	TIMBER COVERED BRIDGE
719	TBUF	TIMBER BOX - UNDER FILL
811	SA	STONE ARCH
819	MAUF	MASONRY CULVERT - UNDER FILL
910A	ITT	IRON THRU TRUSS
910B	IPT	IRON PONY TRUSS
911	AA	ALUMINUM ARCH
919A	MPAUF	ALUMINUM PLATE BOX - UNDER FILL
919B		ALUMINUM PLATE BOX - UNDER FILE ALUMINUM PLATE ARCH - UNDER FILL
0.00	,	p. a.c to the control of the c

- = Con-Span ~ precast concrete ~ three sided arch shape = Hy-Span ~ precast concrete ~ three sided slab shape
- (1) (2)

FLOYD COUNTY INDIANA

APPENDIX B

SUPPLEMENTAL PHOTOS



DAMAGED NW GUARDRAIL



SOUTH SPAN CRACKS WITH EFFL.



BEAM 4 EAST END SPALL



WEST ABUTMENT SCOUR



NW CORNER SHOULDER EROSION



BEAM 3 CRACK AND DELAM.



BEAM 6 CRACK WITH RUST STRAINS



BEAM 2 CRACKS WITH RUST STRAINS



WEST END JOINT SPALL



BEAM 3 HAIRLINE CRACK



SE CORNER GUARDRAIL DAMAGE



UPSTREAM GUARDRAIL DAMAGE



CENTER SPAN SPALLS



SPALL AT MIDSPAN



SOUTHEAST PIER BEAM END CRACKS



NORTH PIER SCOUR



NORTHWEST PIER BEARING EFFL.



BEAM 4 GROUTED HAIRLINE CRACKS



WEST ABUTMENT BEAM 2 BEARING DETERIORATION



UPSTREAM DEBRIS IN LOWER CHORDS



LOOKING AT WEST ABUTMENT



LOOKING NORTH FROM CHANNEL




LOOKING AT SOUTH TRUSS L12



LOOKING AT SOUTH TRUSS L12



LOOKING AT SOUTH TRUSS L6



LOOKING AT SOUTH TRUSS L6 OUTSIDE GUSSET PLATE



LOOKING AT SOUTH TRUSS L12



LOOKING AT NORTH TRUSS LO



LOOKING NORTH UPSTREAM FROM BRIDGE



LOOKING AT NORTH TRUSS L6 WITH RUST LAMINATION



FL. BM 8, RUST ON BOTH SIDES 1" FROM L8, N TRUSS



L8-L10, N TRUSS AT FLAKING ON OUTER CH. NEAR L8



LOOKING AT NORTH TRUSS L12



FL BM 2, FLAKING RUST ON E SIDE 1' FROM L2, N TRUSS



FL BM 10, FLAKING RUST ON E SIDE 2.5' FROM L10, N



FL BEAM 4 AT FLAKING RUST NEAR S TRUSS



UPSTREAM EAST SPAN AND SPALLS



SOUTHWEST WINGWALL EROSION



NE ABUTMENT PILE SELECTION LOSS



EAST ABUTMENT PILE SELECTION LOSS



EAST END DECK SPALLS/ PATCHES



WEST END DECK SPALLS/ PATCHES



WEST ABUTMENT SCOUR



WEST SPAN UNDERSIDE EFFL.



NW COPING SPALLS, LOOKING EAST



NORTH PIER WITH DEBRIS



NORTH EXPANSION JOINT



SOUTH EXPANSION JOINT



SOUTH UNDERSIDE CRACKS



EAST BEAM CRACKS



SEGMENT HEIGHT VARIES



NORTHEAST SHOULDER EROSION



EAST ABUTMENT



SOUTHEAST CORNER EROSION



SOUTHWEST CORNER DECK EFFL.



SW CORNER BEARING DETERIORATION



DOWNSTREAM COPING SPALLS



D/S COPING SPALLS AT NORTH PIER



NORTH PIER BEARING DETERIORATION



NORTH ABUTMENT BEARING



DECK SPALLS AT NORTH PIER



DECK SPALLS AT SOUTH ABUTMENT



UPSTREAM PIER NOSE



DOWNSTREAM PIER NOSE



UPSTREAM, SOUTH SPAN SPALLS



NORTHWEST GUARDRAIL DAMAGE



LOOKING NORTH AT SPALLED SLAB, EXPOSED RESTEEL,



LOOKING SOUTH AT EFFL. IN SOUTH SPAN SLAB



NORTH AT SPALLED SLAB, EXP. RESTEEL, S SPAN



S ABUTMENT BOTT. FTG. EXP.



LOOKING SOUTH AT CRACK IN SIDE OF BEAM 9 WITH



LOOKING NORTH AT HAIRLINE CRACKS IN BEAM 1



LOOKING EAST AT WEST COPING RUSTED CENTERSPAN



LOOKING NE AT EXPOSED EAST FOOTING



LOOKING WEST AT CRACKS IN THE WEST BENT



LOOKING SOUTH AT NORTH SPAN WEST COPING T-BEAM



LOOKING SOUTHEAST AT HEAVY EFFL. ALONG WEST



SOUTH BOX BM DETERIORATION OVER THE PIER



LOOKING WEST DOWNSTREAM



LOOKING WEST AT SEALED CRACK IN BEAM 6



HAIRLINE CRACK ON BOTTOM OF NORTH COPING BEAM



LOOKING NORTH AT AGGREGATION IN WEST SPAN



LOOKING SOUTH AT SCOUR ALONG THE EAST ABUT.



WEST PIER CAP RAVELING



EAST PIER EFFL.



LOOKING WEST AT DAMAGED JOINT MATERIAL



SPALLS IN W GUTTER LINE, WITH EXP. RESTEEL



S AT NORTH SPAN SUPERSTRUCTURE AND DECK



NORTHWEST AT MISSING, DET. OF STONES AT EAST END



NORTH AT SOUTH SPAN SUPERSTR. AND DECK



EAST AT UNDERMINED SW CORNER OF APPR.



NORTH AT DET. AND SETTLING SOUTH ROADWAY APPR.



SOUTH AT PATCHED, DET. SURFACE AT PIER JOINT



S HAIRLINE CRACKS WITH EFFL. ON BTM. OF SLAB



SPALLS, PATCHES, MAP CRACKING ON DECK SURFACE



TOP OF DECK



BEAM 3 EXPOSED STRAP



BEAM 1 SPALL AND SEEPAGE



SOUTHEAST CORNER CRACK



NE BRIDGE WITH OUT BEAM CONTACT



LOOKING AT EAST ABUTMENT



LOOKING AT NE CORNERS



SE BEAM WITH DECK CRACKS



SE BEAM WITH DECK CRACKS



SOUTH ABUTMENT LOSS OF FILL



LOOKING EAST AT MAIN SPAN



LOOKING E AT SPALLS, EXP. RESTEEL ON S COPING



LOOKING WEST AT APPROACH SPANS



LOOKING SOUTH AT EROSION AT NORTHWEST BRIDGE



BLOCKED DECK DRAINS



LOOKING AT DIRT FILLED BRIDGE JOINT



EAST COPING BIT. DROP-OFF



LOOKING WEST FROM ROAD



LOOKING EAST FORM ROAD



HAIRLINE CRACKS ALONG LEGS



CHANNEL SILT AND VEGETATION BUILDUP



EAST ABUTMENT SPALL



NORTHEAST WINGWALL FAILURE



LOOKING SOUTH SPAN REBAR SECTION



LOOKING SOUTHWEST WING RAVELING



LOOKING NORTHWEST CORNER EROSION



DOWNSTREAM COPING RAVELING



NORTHEAST SCOUR



NORTHEAST SHOULDER EROSION



NORTHWEST CORNER EROSION



WEST BRIDGE END DAMAGE



DOWNSTREAM COPING SPALL



LOOKING SOUTH COPING SPALL



LOOKING SOUTH AT COPING SPALL AT POST



LOOKING SOUTH COPING SPALL AT POST CONNECTION



LOOKING EAST AT EAST SLOPE WALL AND BENT



LOOKING SOUTH AT SPALLS, DELAMS. IN CENTER SPAN



LOOKING EAST AT HEAVILY DAMAGED SOUTH JOINT



N SPALLS, PATCHES, AND HEAVY WEAR ON SURFACE



LOOKING SOUTH AT WEB ARCH COPING EFFL.



LOOKING SOUTHEAST AT EXPOSED FOOTING ON PIER



LOOKING NORTH AT LONGITUDINAL CRACK IN PIER



LOOKING NORTH AT SPALL ON EAST COPING PRECAST



LOOKING WEST FROM ROAD



NORTH PIER BEARING SPALL



UPSTREAM FROM BRIDGE



LOOKING EAST AT BOTTOM OF ARCH



LOOKING EAST AT SW CORNER DROP OFF AT PAVEMENT



LOOKING AT SOUTH OPENING OF STRUCTURE



LOOKING WEST AT SPALL IN SECTION



SPALL AT SOUTHWEST WINGWALL CORNER



LOOKING SOUTH AT DAMAGED SW GUARDRAIL END



NW AT BROKEN HEADWALLS, GABIONS ABOVE



LOOKING SOUTH AT SOUTH BENT FOOTING



LOOKING NORTH AT DAMAGED NW APPROACH



SW AT HEAVY EFFL. ON SLAB AND SOUTH ABUT.



LOOKING EAST THROUGH CHANNEL



S AT HEAVY DETERIORATION OF CONCRETE AND BIT.



WEST EFFL. BTWN. THE OUTER E TWO BEAMS



HAIRLINE CRACKS AT SOUTH END OF WEST COPING



HAIRLINE CRACKS AT NORTH OF WEST COPING BEAM



HAIRLINE CRACKS 8" ABOVE BIT. OF THE E COPING BM



LOOKING WEST AT CRACKS IN BOTTOM OF CONCRETE



S HAIRLINE CRACKS, EFFL. RUST STAINS ON W ABT.



EAST AT DAMAGED SOUTHWEST APPROACH RAILING



EAST AT DAMAGED NORTHWEST APPR. RAILIING



H'LINE CRACKS IN S ABT. WITH SPALLS AND DELAMS.



WEST AT RIPRAP MOUNDED IN CHANNEL



LOOKING SOUTH AT DAMAGED SOUTH APPROACH

FLOYD COUNTY INDIANA

APPENDIX C

IN DEPTH INSPECTION REPORTS

- FRACTURE CRITICAL REPORTS - SCOUR CRITICAL REPORTS



FRACTURE CRITICAL REPORT: FLOYD COUNTY BRIDGE #23 B

Reviewing Owner Representative: Michael Rowe, P.E.

County Engineer: Horacio Urieta, P.E.

Bridge Inspection Team Leader Nicholas J. Kocher, P.E.

Prepared By: Kyle D. Kent, E.I.




Certified:

Nicholas J. Kocher, P.E.

Nicholae J. Kocher

Date: June 1, 2020





I. INTRODUCTION

A. Location and Description

Bridge No. 23 B is located at the intersection of John Pectol Road and Hamby Road. Map location is at C-6. The bridge carries traffic on John Pectol Road over Big Indian Creek. The bridge is located at latitude N38°20'22.63" and longitude W85°58'59.19".

Bridge No. 23 B is a single-span, steel pony truss. The structure has no skew, has a length of 92.0 feet, and a maximum span length of 88.0 feet. The structure has a clear roadway width of 26.0 feet with two lanes of traffic. The average daily traffic was estimated to be 421 vehicles per day in 2016. The bridge has an H rating of 20 tons, an HS Inventory Rating of 36 tons, and an HS Operating Rating of 45 tons.

B. History

Bridge No. 23 B was constructed in 2013, and replaced the previous truss bridge that was built in 1915.

II. FIELD INVESTIGATION

A. Members and Connections to be Inspected

Up-close and visual inspections of all the fracture critical members and connections of the structure were carried out in this inspection.

B. Inspection Procedures

Visual inspections of joints, members, and bearings were performed to locate possible problem areas in the fracture critical members. This was a hands-on inspection due to the relatively small size and difficulty of locating cracks. Debris was cleared that would have prohibited viewing the member or connection in question.

C. Equipment Required for Inspection

Tools and equipment used to inspect each member or connection included a hard hat, safety glasses, wire brush, hammer, awl, plumb bob, level, spade, tape measure, camera, 8' prodding rod, inspection mirror, calipers, and a flashlight. A ladder was used to inspect the upper chord connections and various members, while lower chord connections and other members were inspected by free climbing the lower chord members with safety restraints.

D. Bridge Cleaning Requirements

The bearings and lower chord members contained dirt, dust, and debris. A wire brush and spade were utilized by the inspectors to clean these locations.

E. Traffic Maintenance Requirements

Due to the low vehicular speeds and average daily traffic (ADT) of the bridge, no temporary roadway closures were required. Orange cones were used to inform motorists of the presence of inspectors on the bridge during the inspection.

F. Date and Conditions of Inspection

Date: 04/02/2020

Temperature: 50° F

Conditions: Sunny

Inspection Duration: Four hours

G. Other Items

The original bridge plans are available. The previous inspection field note deficiencies were utilized in order to monitor the developments of these deficiencies at the bridge.

III. SUMMARY OF INSPECTION RESULTS

The overall condition of the truss is considered very good.

A. Connections

All of the connections are in very good condition. Dirt and debris collect on the lower chord at the connections.

B. Members

Most of the members are in very good condition with no major defects noted. Two lower chords on the north truss have flaking steel near the connections.

C. Floor System

The floor beam connections are in good condition. Floor beams and bolted connections exhibit rust lamination typical at all connections. The concrete deck is in excellent condition with no major defects noted.

IV. NBIS CODING INFORMATION

ITEM	CODE	DESCRIPTION
92A	Y24	Fracture Critical Inspection every 24 months
93A	04/02/2020	Inspection Date April 2, 2020

V. SUMMARY OF RECOMMENDATIONS

Programmed Repairs: None currently.

Urgent Repairs: None currently.

Maintenance: Clean lower chord members following flood level storm events.

Plan of Action: The overall superstructure condition is an 8 (very good), thus, a full fracture critical inspection is required every 24 months.

VI. FIELD NOTES

The following rating system was used to rate the fracture critical members and connections:

- 9 Excellent Condition
- 8 Very Good Condition No noteworthy deficiencies
- 7 Good Condition Some minor problems
- 6 Satisfactory Condition Minor structural deterioration
- 5 Fair Condition Minor section loss
- 4 Poor Condition Advanced section loss and deterioration
- 3 Serious Condition Local failures are possible
- 2 Critical Condition Advanced deterioration of primary elements
- 1 Imminent Failure Condition Major deterioration; structure should be closed
- Failed Condition Out of service; bridge condition beyond corrective action

SOUTH TRUSS, MAIN SPAN				
MEMBER	FATIGUE CATEGORY	RATING	REMARKS	
L0-L2	В	8	Lower Chord: No major defects noted.	
L2-L4	В	8	Lower Chord: No major defects noted.	
L4-L6	В	8	Lower Chord: No major defects noted.	
L6-L8	В	8	Lower Chord: No major defects noted.	
L8-L10	В	8	Lower Chord: No major defects noted.	
L10-L12	В	8	Lower Chord: No major defects noted.	
L2-U2	В	8	Vertical: No major defects noted.	
L4-U4	В	8	Vertical: No major defects noted.	
L6-U6	В	8	Vertical: No major defects noted.	
L8-U8	В	8	Vertical: No major defects noted.	
L10-U10	В	8	Vertical: No major defects noted.	
U1-L2	В	8	Diagonal: No major defects noted.	
L2-U3	В	8	Diagonal: No major defects noted.	
U3-L4	В	8	Diagonal: No major defects noted.	
L4-U5	В	8	Diagonal: No major defects noted.	
U5-L6	В	8	Diagonal: No major defects noted.	
L6-U7	В	8	Diagonal: No major defects noted.	
U7-L8	В	8	Diagonal: No major defects noted.	
L8-U9	В	8	Diagonal: No major defects noted.	
U9-L10	В	8	Diagonal: No major defects noted.	

SOUTH TRUSS, MAIN SPAN				
MEMBER	FATIGUE CATEGORY	RATING	REMARKS	
L10-U11	В	8	Diagonal: No major defects noted.	
U11-L12	В	8	Diagonal: No major defects noted.	
L0-U1	В	8	Top Chord: No major defects noted.	
U1-U2	В	8	Top Chord: No major defects noted.	
U2-U3	В	8	Top Chord: No major defects noted.	
U3-U4	В	8	Top Chord: No major defects noted.	
U4-U5	В	8	Top Chord: No major defects noted.	
U5-U6	В	8	Top Chord: No major defects noted.	
U6-U7	В	8	Top Chord: No major defects noted.	
U7-U8	В	8	Top Chord: No major defects noted.	
U8-U9	В	8	Top Chord: No major defects noted.	
U9-U10	В	8	Top Chord: No major defects noted.	
U10-U11	В	8	Top Chord: No major defects noted.	

SOUTH TRUSS, MAIN SPAN					
CONNECTION	FATIGUE CATEGORY	RATING	REMARKS		
L0	В	8	Connection: No major defects noted.		
L2	В	8	Connection: No major defects noted.		
L4	В	8	Connection: No major defects noted.		
L6	В	8	Connection: No major defects noted.		
L8	В	8	Connection: No major defects noted.		
L10	В	8	Connection: No major defects noted.		
L12	В	8	Connection: No major defects noted.		
U1	В	8	Connection: No major defects noted.		
U2	В	8	Connection: No major defects noted.		
U3	В	8	Connection: No major defects noted.		
U4	В	8	Connection: No major defects noted.		
U5	В	8	Connection: No major defects noted.		
U6	В	8	Connection: No major defects noted.		
U7	В	8	Connection: No major defects noted.		
U8	В	8	Connection: No major defects noted.		
U9	В	8	Connection: No major defects noted.		
U10	В	8	Connection: No major defects noted.		
U11	В	8	Connection: No major defects noted.		

NORTH TRUSS, MAIN SPAN				
MEMBER	FATIGUE CATEGORY	RATING	REMARKS	
L0-L2	В	7	Lower Chord : Flaking on inner channel near L2.	
L2-L4	В	8	Lower Chord: No major defects noted.	
L4-L6	В	8	Lower Chord: No major defects noted.	
L6-L8	В	8	Lower Chord: No major defects noted.	
L8-L10	В	7	Lower Chord: Flaking on outer channel near L8.	
L10-L12	В	8	Lower Chord: No major defects noted.	
L2-U2	В	8	Vertical: No major defects noted.	
L4-U4	В	8	Vertical: No major defects noted.	
L6-U6	В	8	Vertical: No major defects noted.	
L8-U8	В	8	Vertical: No major defects noted.	
L10-U10	В	8	Vertical: No major defects noted.	
U1-L2	В	8	Diagonal: No major defects noted.	
L2-U3	В	8	Diagonal: No major defects noted.	
U3-L4	В	8	Diagonal: No major defects noted.	
L4-U5	В	8	Diagonal: No major defects noted.	
U5-L6	В	8	Diagonal: No major defects noted.	
L6-U7	В	8	Diagonal: No major defects noted.	
U7-L8	В	8	Diagonal: No major defects noted.	
L8-U9	В	8	Diagonal: No major defects noted.	
U9-L10	В	8	Diagonal: No major defects noted.	

NORTH TRUSS, MAIN SPAN					
MEMBER	FATIGUE CATEGORY	RATING	REMARKS		
L10-U11	В	8	Diagonal: No major defects noted.		
U11-L12	В	8	Diagonal: No major defects noted.		
L0-U1	В	8	Top Chord: No major defects noted.		
U1-U2	В	8	Top Chord: No major defects noted.		
U2-U3	В	8	Top Chord: No major defects noted.		
U3-U4	В	8	Top Chord: No major defects noted.		
U4-U5	В	8	Top Chord: No major defects noted.		
U5-U6	В	8	Top Chord: No major defects noted.		
U6-U7	В	8	Top Chord: No major defects noted.		
U7-U8	В	8	Top Chord: No major defects noted.		
U8-U9	В	8	Top Chord: No major defects noted.		
U9-U10	В	8	Top Chord: No major defects noted.		
U10-U11	В	8	Top Chord: No major defects noted.		

NORTH TRUSS, MAIN SPAN				
CONNECTION	FATIGUE CATEGORY	RATING	REMARKS	
L0	В	8	Connection: No major defects noted.	
L2	В	8	Connection: No major defects noted.	
L4	В	8	Connection: No major defects noted.	
L6	В	8	Connection: No major defects noted.	
L8	В	8	Connection: No major defects noted.	
L10	В	8	Connection: No major defects noted.	
L12	В	8	Connection: No major defects noted.	
U1	В	8	Connection: No major defects noted.	
U2	В	8	Connection: No major defects noted.	
U3	В	8	Connection: No major defects noted.	
U4	В	8	Connection: No major defects noted.	
U5	В	8	Connection: No major defects noted.	
U6	В	8	Connection: No major defects noted.	
U7	В	8	Connection: No major defects noted.	
U8	В	8	Connection: No major defects noted.	
U9	В	8	Connection: No major defects noted.	
U10	В	8	Connection: No major defects noted.	
U11	В	8	Connection: No major defects noted.	

		FL	OORBEAMS	
MEMBER	FATIGUE CATEGORY	RATING	REMARKS	
FB2	В	7	Floorbeam : Flaking rust on east side 1' from L2, North Truss.	
FB4	В	8	Floorbeam: No major defects noted.	
FB6	В	7	Floorbeam: Rust lamination at bolts at L6, North Truss.	
FB8	В	7	Floorbeam : Flaking rust along bottom flange and bottom of web near L8.	
FB10	В	7	Floorbeam : Flaking rust on east side 2.5' from L10, North Truss.	

VII. INSPECTION PHOTOS



LOOKING WEST FROM ROAD



LOOKING EAST FROM ROAD



LOOKING SOUTH FROM CHANNEL



LOOKING WEST AT UNDERSIDE DEBRIS



LOOKING AT WEST ABUTMENT



LOOKING NORTH FROM CHANNEL



LOOKING AT SOUTH TRUSS L12



LOOKING AT SOUTH TRUSS L12



LOOKING AT SOUTH TRUSS L6



LOOKING AT SOUTH TRUSS L6 OUTSIDE GUSSET PLATE



LOOKING AT SOUTH TRUSS L12



LOOKING AT NORTH TRUSS L0



LOOKING AT NORTH TRUSS L12



LOOKING AT NORTH TRUSS L6 WITH RUST LAMINATION



LOOKING NORTH UPSTREAM FROM BRIDGE



LOOKING AT FLOORBEAM 10 AT FLAKING RUST ON EAST SIDE 2.5' FROM L10, NORTH TRUSS.



LOOKING AT FLOORBEAM 8 AT FLAKING RUST ON BOTH SIDES 1' FROM L8, NORTH TRUSS.



LOOKING AT L8-L10, NORTH TRUSS AT FLAKING ON OUTER CHANNEL NEAR L8



LOOKING AT FLOORBEAM 2 AT FLAKING RUST ON EAST SIDE 1' FROM L2, NORTH TRUSS.



LOOKING AT FLOORBEAM 4 AT FLAKING RUST NEAR SOUTH TRUSS.



Inspected By: <u>MWB</u>

Date: <u>3/2/2020</u>

<u>FLOYD</u> COUNTY INVENTORY BRIDGE # <u>41</u> SCOUR FINDINGS

STREAMBED	MATERIAI
SINDAMIDED	WAILMAL

Rock

STREAM ALIGNMENT

• Flow along the south abutment. Meandering. Channel bends at greater than 30° upstream

SCOUR COUNTERMEASURES

• None along the abutments. Riprap protecting bank in the Southeast corner

BANK EROSION

• Repaired bank erosion in the Southeast corner

OTHER SCOUR RELATED FINDINGS

• Footing exposed along the South abutment and at the Northwest corner of the North abutment

scou	R AND FO	UNDAT	ON EVALUATION	ON F	ORM
NBI Number: 2200040			Bridge Num	ber:	22-00041
Facility Carried: ST MARY	y'S RD		Feature(s) Intersec	ted:	LITTLE INDIAN CREEK
Date of Last Review or Update: (113A) NBI Scour Evaluation:					
Foundation Data	Code	Comi	ments		
Abutment Foundation Type	Α	N/A			
		,			
Int. Pier Foundation Type	N	N/A			
Soils Information	SOILS INF	ORMATIO	N IS LINKNOWN IN	FORN	MATION NOT FOUND ON PLANS
Design Plans:	PLANS A\	/AILABLE.			
Scour Monitoring Data					
Is Bridge on a District Monitoring	Program?		NO		
Reason for Monitoring	LENGTH (OF THE FO		THE	HAS SCOUR WITH THE FULL SOUTH ABUTMENT AND ALONG BUTMENT.
Who Monitors the Bridge?	FLOYD CO	DUNTY			
Long Term Scour Solution		COUR COL JR PROBLE		HOUL	D BE DEVELOPED TO REPAIR
	<u> </u>				
Streambed Material	ROCK				
Stream Alignment			OUTH ABUTMENT. 30° UPSTREAM	MEA	NDERING. THE CHANNEL BEND
Scour Countermeasures		ONG THE A		P PRO	OTECTING THE BANK IN THE
Bank Erosion	REPAIRE	BANK ERO	OSION IN THE SOUT	ГНЕА	ST CORNER
Other Scour Related Findings			D ALONG THE SOU ER OF THE NORTH A		BUTMENT AND AT THE MENT

NIDI Niconaharin		OUNDATION EVALUATION F	
NBI Number:	2200040	Bridge Number:	22-00041
Facility Carried	ST MARY'S RD	Feature(s) Intersected:	LITTLE INDIAN CREEK
	st substructure units to		
		TENT WATER SURFACE ELEVATION IN	
DRIFT AND DEBRIS A	CCUMULATION IN THE	CHANNEL. TAKE SOUNDINGS ALON	G EACH SUBSTRUCTURE FACE.
What to Look for: Lis	st specific signs indicati	ing a problem	
STOP MONITORING \	WHEN WATER SURFAC	E ELEVATION IS 2 FEET BELOW THE F	BOTTOM OF THE BEAM CHORD
RETURN TO THE BRID	GE WHEN THE WATER	R LEVEL HAS RETURNED TO NORMAL	AND CHECK FOR SCOUR.
When to Monitor: Li	st what initiates monit	oring	
•		S OF RAIN IN THE WATERSHED WITH	
		AY SUPERINTENDENT WILL REEVALU.	ATE THE SCOUR AT THE BRIDGE
AFTER THE TRIGGERE			
	and bridge inspectors;		
		PHONE # 812-948-5490	10 5400
		R - JUSTIN TACKETT PHONE # 812-94	
		ITED CONSULTING PHONE # 317-89	5-2585
	•	owline marked on piers, etc. KIMATELY ONCE A YEAR. THERE IS N	O HISTORY OF THE TOP OF
BRIDGE DECK OVERT		MINIATELY ONCE A TEAK. THERE IS N	O HISTORY OF THE FOR OF
DIVIDGE DECK OVERT	orring.		
. Describe Channel Pr	obing/Depth Reading F	rocedures:	
		Procedures: PART 4, SUBSECTION 7.2.3 OF THE IN	IDIANA BRIDGE INSPECTION
			IDIANA BRIDGE INSPECTION
INSPECTION PROCED			IDIANA BRIDGE INSPECTION
INSPECTION PROCED MANUAL.			IDIANA BRIDGE INSPECTION
INSPECTION PROCED MANUAL. Closing Procedures:	URES SHALL FOLLOW F		
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISF	PATCH. PLACE BARRICA	PART 4, SUBSECTION 7.2.3 OF THE IN	APPROACHES AT BOTH ENDS O
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISPETITE BRIDGE. PRIOR TEAM LEADER.	PATCH. PLACE BARRICA	PART 4, SUBSECTION 7.2.3 OF THE IN	APPROACHES AT BOTH ENDS O
MANUAL. Closing Procedures: NOTIFY COUNTY DISF THE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring:	PATCH. PLACE BARRIC,	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER	APPROACHES AT BOTH ENDS C
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISPETITE BRIDGE. PRIOR TEAM LEADER.	PATCH. PLACE BARRICA	PART 4, SUBSECTION 7.2.3 OF THE IN	APPROACHES AT BOTH ENDS O
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISFITHE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring:	PATCH. PLACE BARRIC,	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER	APPROACHES AT BOTH ENDS C
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISFITHE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring:	PATCH. PLACE BARRIC,	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER	APPROACHES AT BOTH ENDS C
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISPETHE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring: Monitoring Date	PATCH. PLACE BARRIC,	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER	APPROACHES AT BOTH ENDS C
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISPITE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring: Monitoring Date Miscellaneuous:	PATCH. PLACE BARRICATO REOPENING, THE BI	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER Cause of Highwater	APPROACHES AT BOTH ENDS ORTIFIED BRIDGE INSPECTION Comments
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISPITE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring: Monitoring Date	PATCH. PLACE BARRICATO REOPENING, THE BI	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER	APPROACHES AT BOTH ENDS ORTIFIED BRIDGE INSPECTION Comments
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISPITE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring: Monitoring Date Miscellaneuous:	PATCH. PLACE BARRICATO REOPENING, THE BI	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER Cause of Highwater	APPROACHES AT BOTH ENDS ORTIFIED BRIDGE INSPECTION Comments
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISP THE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring: Monitoring Date Miscellaneuous: WEST - TAKE Mt PLEA	PATCH. PLACE BARRICATO REOPENING, THE BI	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER Cause of Highwater (VILLE ROAD. TRAVEL EAST ON SNE.)	APPROACHES AT BOTH ENDS ORTIFIED BRIDGE INSPECTION Comments
INSPECTION PROCED MANUAL. Closing Procedures: NOTIFY COUNTY DISP THE BRIDGE. PRIOR TEAM LEADER. Historic Monitoring: Monitoring Date Miscellaneuous: WEST - TAKE Mt PLEA D. Have Drawings Ava	PATCH. PLACE BARRICATO REOPENING, THE BI Water Level ASANT ROAD TO SNEAR	PART 4, SUBSECTION 7.2.3 OF THE IN ADES AND ROAD CLOSURE SIGNS AT RIDGE MUST BE INSPECTED BY A CER Cause of Highwater (VILLE ROAD. TRAVEL EAST ON SNE.)	APPROACHES AT BOTH ENDS ORTIFIED BRIDGE INSPECTION Comments



Inspected By: NJK

Date: $\frac{3}{3/20}$

FLOYD COUNTY INVENTORY BRIDGE # 63 SCOUR FINDINGS


STREAMBED MATERIAL
 Granular/soft soils
•
STREAM ALIGNMENT
• Straight
SCOUR COUNTERMEASURES
SCOOK COONTERIMENSORES
• None
T TONG
BANK EROSION
BAINK EROSION
Heavy bank erosion upstream and downstream.
Theavy bank crosson upstream and downstream.
OTHER SCOUR RELATED EINDINGS
OTHER SCOUR RELATED FINDINGS
 North abutment has settled unevenly and has some slight undercutting
- 1101th abundent has settled unevenly and has some stight undereduling

FLOYD CO. BRIDGE INVENTORY CHANNEL SOUNDINGS Bridge No. 63

BY_____NJK_____DATE____4/2/2020

DRAWN BY____DJZ_____DATE____4/6/2020

- Provide Depth Soundings referenced to water surface elevation at 4' intervals along each face of substructure unit (where applicable) and at intervals of 4' and 8' away from face of substructure unit. Greater distances may be required for larger scour holes.
- 2. Indicate direction of flow.
- 3. Dimension size of scour hole(s) in plan view.
- 4. Indicate location and limits of undermining.
- 5. Indicate location of flood debris or other channel obstructions.



BRIDGE No. 63 EAST BENT

SCOUR AND FOUNDATION EVALUATION FORM						
NBI Number: 2200057			Bridge Nu	mber:	22-00063	
Facility Carried: FIVE MIL	E LN		Feature(s) Interse		KNOB CREEK	
Date of Last Review or Update: (113A) NBI Scour Evaluation:				_		
Foundation Date	Codo	Comr				
Foundation Data	Code	Comn	ments			
Abutment Foundation Type	А	N/A				
Int. Pier Foundation Type	N	N/A				
Soils Information	SOILS INF	ORMATION	N IS UNKNOWN. N	NO ORIO	GINAL PLANS AVAILABLE.	
Design Plans:	NO ORIGI	NAL PLANS	S AVAILABLE.			
Scour Monitoring Data						
Is Bridge on a District Monitoring Program?						
Reason for Monitoring	FOUNDATIONS ARE SPREAD FOOTINGS AND HAS SCOUR WITH THE FULL LENGTH OF THE FOOTING EXPOSED AT THE NORTH ABUTMENT. SETTLEMENT HAS BEEN NOTED.					
Who Monitors the Bridge?	FLOYD COUNTY					
Long Term Scour Solution	DESIGN SCOUR COUNTERMEASURES SHOULD BE DEVELOPED TO REPAIR THE SCOUR PROBLEMS.					
Streambed Material	GRANULAR/SOFT SOILS					
Stream Alignment	STRAIGHT	-				
Scour Countermeasures	NONE					
Bank Erosion	HEAVY BANK EROSION UPSTREAM AND DOWNSTREAM. EROSION BEHIND THE NORTHEAST WINGWALL					
Other Scour Related Findings	NORTH ABUTMENT HAS SETTLED UNEVENLY AND HAS SOME SLIGHT UNDERCUTTING					

SCOUR AND FOUNDATION EVALUATION FORM					
NBI Number:	2200057	Bridge Number:	22-00063		
Facility Carried	FIVE MILE LN	Feature(s) Intersected:	KNOB CREEK		
	ist substructure units to				
		IENT WATER SURFACE ELEVATION			
DRIFT AND DEBRIS A	CCUMULATION IN THE	CHANNEL. TAKE SOUNDINGS ALO	NG EACH SUBSTRUCTURE FACE.		
2. What to Look for: L	ist specific signs indicati	ing a problem			
		E ELEVATION IS 2 FEET BELOW THE	BOTTOM OF THE BEAM		
		HE WATER LEVEL HAS RETURNED 1			
SCOUR.					
3. When to Monitor: I	ist what initiates monit	oring			
Q100 STORM EVENT PER NOAA: 2.9 INCHES OF RAIN IN THE WATERSHED WITHIN 1 HOUR OR 6.9 INCHES OF					
RAIN WITHIN 24 HO	URS. COUNTY HIGHWA	Y SUPERINTENDENT WILL REEVAL	JATE THE SCOUR AT THE BRIDGE		
AFTER THE TRIGGER					
	t and bridge inspectors;				
	R - WILLIAM GIBSON P				
2. COUNTY INFASTRUCTURE COORDINATOR - JUSTIN TACKETT PHONE # 812-948-5490					
		TED CONSULTING PHONE # 317-8	95-2585		
		owline marked on piers, etc.	NO 11107001/ OF THE TOD OF		
		(IMATELY ONCE A YEAR. THERE IS	NO HISTORY OF THE TOP OF		
BRIDGE DECK OVERT	OPPING.				
6 Describe Channel P	robing/Depth Reading F	Procedures:			
		PART 4, SUBSECTION 7.2.3 OF THE	INDIANA BRIDGE INSPECTION		
MANUAL.	70KE3 311/KEE 1 0EE0 W 1	7.1.1, 30B32011011 7:2:3 01 1112	mon mon balloge man certain		
7. Closing Procedures:					
NOTIFY COUNTY DIS	PATCH. PLACE BARRICA	ADES AND ROAD CLOSURE SIGNS A	T APPROACHES AT BOTH ENDS		
OF THE BRIDGE. PRI	OR TO REOPENING, TH	E BRIDGE MUST BE INSPECTED BY A	A CERTIFIED BRIDGE INSPECTION		
TEAM LEADER.					
8. Historic Monitoring	:				
Monitoring Date	Water Level	Cause of Highwater	Comments		
9. Miscellaneuous:					

10. Have Drawings Available: General Plan; Layout; Pier/Abutment

CROSS SECTIONS TAKEN AT UPSTREAM AND DOWNSTREAM BRIDGE COPINGS.