

◆ ◆ ◆ **REQUIRED INSPECTIONS** ◆ ◆ ◆

Generators

1. **GAS LINE INSPECTION:** After pressure gauge is on and holds minimum 15# of pressure for 20 minutes. Prior to Gas Company Hook-up. Gauge must be on and holding pressure at time of inspection.
2. **FINAL INSPECTION BEFORE POWER IS RECONNECTED:** Transfer switch installation must be complete. Meter base must be labeled identifying back-up power source and location. Generator disconnect must be readily accessible outside the dwelling unit, lockable in the open position and labeled. If current service only has one ground rod, a second ground ROD is required minimum of 6 feet apart unless Ufer rod is utilized. Ground wire must be continuous from both ground rods or Ufer rod to the first disconnect panel. Ground wire from disconnect and/or breaker panel to ground rods or Ufer rod **MUST NOT BE ROUTED** through meter base.

◆ ◆ ◆ **A TWENTY-FOUR (24) HOUR NOTICE IS REQUIRED ON ALL INSPECTIONS.** ◆ ◆ ◆