

Schedule of Pay Items Letting Date January 14, 2026 Letting ID 260114

Call: 111

Contract: R -39624-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-02245	TREE, 6 IN., REMOVE	1.00	EACH
0011	201-02250	TREE, 10 IN., REMOVE	4.00	EACH
0012	201-02255	TREE, 18 IN., REMOVE	207.00	EACH
0013	201-02260	TREE, 30 IN., REMOVE	12.00	EACH
0014	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0015	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	50.00	CYS
0016	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	50.00	CYS
0017	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	50.00	CYS
0018	202-09243	REGULATED MATERIALS, DISPOSE, TYPE Z	50.00	CYS
0019	202-09244	REGULATED MATERIALS, REMOVE, TYPE Z	50.00	CYS
0020	202-09245	REGULATED MATERIALS, TRANSPORT, TYPE Z	50.00	CYS
0021	202-93615	CONCRETE, REMOVE	75.00	SYS
0022	202-96430	FENCE AND POSTS, REMOVE	1.00	LS
0023	203-02000	EXCAVATION, COMMON	4241.00	CYS
0024	203-02020	EXCAVATION, UNCLASSIFIED	500.00	CYS
0025	205-12108	STORMWATER MANAGEMENT BUDGET	20840.00	DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0027	205-12618	SWQCP PREPARATION	1.00	LS
0028	207-08264	SUBGRADE TREATMENT, TYPE II	100.00	SYS
0029	207-09935	SUBGRADE TREATMENT, TYPE IC	7028.00	SYS
0030	211-02050	B BORROW	2430.00	CYS
0031	211-09264	STRUCTURE BACKFILL, TYPE 1	10.00	CYS

0032	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	7050.00	SYS
0033	301-12234	COMPACTED AGGREGATE, NO. 53	2050.00	CYS
0034	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	5.00	TON
0035	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	67.00	TON
0036	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	112.00	TON
0037	401-000048	QC/QA-HMA, 4, 58S, BASE, 25.0 mm	366.00	TON
0038	406-05520	ASPHALT FOR TACK COAT	1.14	TON
0039	601-01700	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 1	1.00	ACH
0040	601-02241	GUARDRAIL, REMOVE	210.00	LFT
0041	601-09238	HAND DIG GUARDRAIL POST HOLES	21.00	ACH
0042	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	1427.00	LFT
0043	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	ACH
0044	603-08648	FENCE GATE, CHAIN LINK, 72 IN. X 12 FT	2.00	ACH
0045	603-92636	FENCE, CHAIN LINK, 72 IN.	389.00	LFT
0046	604-05528	HMA FOR SIDEWALK	800.00	TON
0047	604-06070	SIDEWALK, CONCRETE	1330.00	SYS
0048	604-08086	CURB RAMP, CONCRETE	45.00	SYS
0049	604-12083	DETECTABLE WARNING SURFACES	12.00	SYS
0050	605-06140	CURB AND GUTTER, CONCRETE	42.00	LFT
0051	610-07487	HMA FOR APPROACHES, TYPE B	57.00	TON
0052	616-06405	RIPRAP, REVETMENT	6.00	TON
0053	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	22.00	SYS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0055	621-02356	SEEDING WETLAND	4.00	LBS
0056	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00	TON
0057	621-06554	SEED MIXTURE, TYPE U	330.00	LBS
0058	621-06565	MULCHING MATERIAL	5.00	TON
0059	621-06567	WATER	170.00	KGAL
0060	628-09403	FIELD OFFICE, TYPE C	18.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0062	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	10600.00	SYS
0063	629-000150	TOPSOIL AMENDMENT BUDGET	21200.00	DOL
0064	715-02397	SAFETY METAL END SECTION, 4:1, DIAMETER 36 IN.	1.00	ACH
0065	715-05177	PIPE, TYPE 3, CIRCULAR, DIAMETER 36 IN.	24.00	LFT
0066	715-09064	VIDEO INSPECTION FOR PIPE	24.00	LFT
0067	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	ACH
0068	801-06640	CONSTRUCTION SIGN, TYPE A	14.00	ACH

0069	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	ACH
0070	801-06710	FLASHING ARROW SIGN	21.00	DAY
0071	801-06775	MAINTAINING TRAFFIC	1.00	LS
0072	801-07119	BARRICADE, TYPE III-B	100.00	LFT
0073	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	60.00	LFT
0074	801-11990	TEMPORARY CURB RAMP	1.00	ACH
0075	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	50.00	LFT
0076	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	287.00	LFT
0077	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	105.00	SFT
0078	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	61.00	SFT
0079	805-01479	CONTROLLER CABINET FOUNDATION, TYPE P1, MODIFIED	1.00	ACH
0080	805-01842	HANDHOLE, SIGNAL, TYPE 1	3.00	ACH
0081	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	200.00	LFT
0082	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	1.00	ACH
0083	805-02445	CONTROLLER AND CABINET, TYPE P1	1.00	ACH
0084	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	2.00	ACH
0085	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT	1.00	ACH
0086	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT	1.00	ACH
0087	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE A	2.00	ACH
0088	805-11496	PEDESTRIAN HYBRID BEACON	6.00	ACH
0089	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00	ACH
0090	805-12016	UNINTERRUPTIBLE POWER SUPPLY	1.00	ACH
0091	805-12650	SIGNAL POLE, PEDESTAL, 5 FT	1.00	ACH
0092	805-78445	SIGNAL SERVICE	1.00	ACH
0093	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	75.00	LFT
0094	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	100.00	LFT
0095	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	575.00	LFT
0096	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	120.00	LFT
0097	805-97042	SIGNAL POLE, TIMBER, 5, 35 FT	1.00	ACH
0098	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	160.00	LFT
0099	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	15.00	LFT
0100	808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	230.00	LFT
0101	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	80.00	LFT

Call: 115

Contract: R -39911-B

Section No.: 1 PAVEMENT REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	4142.00	SYS
0014	202-02278	CURB, CONCRETE, REMOVE	5983.00	LFT
0015	202-02279	CURB AND GUTTER, REMOVE	430.00	LFT
0016	202-05544	REGULATED MATERIALS, DISPOSE, TYPE C	50.00	GAL
0017	202-05549	REGULATED MATERIALS, REMOVE, TYPE C	50.00	GAL
0018	202-05554	REGULATED MATERIALS, TRANSPORT, TYPE C	50.00	GAL
0019	202-06542	RELOCATE	1.00	EACH
0020	202-06580	CONTAMINATED SOIL, REMOVE	10.00	CYS
0021	202-07603	TESTING FOR WASTES, TYPE C	1.00	EACH
0022	202-74035	SIGN, REMOVE	2.00	EACH
0023	202-90277	DETECTOR HOUSING, REMOVE	5.00	EACH
0024	202-91385	INLET, REMOVE	18.00	EACH
0025	202-94747	POST, REMOVE	41.00	EACH
0026	202-96133	PIPE, REMOVE	284.00	LFT
0027	203-02000	EXCAVATION, COMMON	975.00	CYS
0028	203-02070	BORROW	370.00	CYS
0029	205-12108	STORMWATER MANAGEMENT BUDGET	17974.00	DOL
0030	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0031	205-12618	SWQCP PREPARATION	1.00	LS

0032	207-08264	SUBGRADE TREATMENT, TYPE II	3274.00	SYS
0033	207-08266	SUBGRADE TREATMENT, TYPE III	3838.00	SYS
0034	207-09935	SUBGRADE TREATMENT, TYPE IC	7140.00	SYS
0035	211-02050	B BORROW	43.00	CYS
0036	211-09265	STRUCTURE BACKFILL, TYPE 2	3860.00	CYS
0037	214-11796	GEOGRID, TYPE IB	5877.00	SYS
0038	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	3833.00	SYS
0039	301-12232	COMPACTED AGGREGATE, NO. 5	100.00	CYS
0040	301-12233	COMPACTED AGGREGATE, NO. 8	27.00	CYS
0041	301-12234	COMPACTED AGGREGATE, NO. 53	1504.00	CYS
0042	302-07455	DENSE GRADED SUBBASE	413.00	CYS
0043	303-01180	COMPACTED AGGREGATE, NO. 53	48.00	TON
0044	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	420.00	TON
0045	304-07494	WIDENING WITH HMA, TYPE C	1442.00	TON
0046	306-11872	MILLING, PROFILE	13421.00	SYS
0047	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	1376.00	TON
0048	401-000067	QC/QA-HMA, 4, 58E, INTERMEDIATE, OG, 19.0 mm	1201.00	TON
0049	401-11526	JOINT ADHESIVE	7701.00	LFT
0050	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	18804.00	LFT
0051	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	342.00	TON
0052	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0053	503-05240	D-1 CONTRACTION JOINT	62.00	LFT
0054	601-01522	GUARDRAIL TRANSITION, TYPE TGB	1.00	EACH
0055	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	EACH
0056	603-03829	FENCE	102.00	LFT
0057	604-05528	HMA FOR SIDEWALK	461.00	TON
0058	604-06070	SIDEWALK, CONCRETE	2090.00	SYS
0059	604-08086	CURB RAMP, CONCRETE	286.00	SYS
0060	604-12083	DETECTABLE WARNING SURFACES	51.00	SYS
0061	604-44251	STEPS, CONCRETE	1.00	CYS
0062	604-92237	HANDRAIL, STEEL	6.00	LFT
0063	605-06120	CURB, CONCRETE	1869.00	LFT
0064	605-06140	CURB AND GUTTER, CONCRETE	6540.00	LFT
0065	605-06215	CENTER CURB, CONCRETE, TYPE D	24.00	LFT
0066	610-07488	HMA FOR APPROACHES, TYPE C	177.00	TON
0067	610-08446	PCCP FOR APPROACHES, 6 IN.	434.00	SYS
0068	610-09108	PCCP FOR APPROACHES, 9 IN.	2039.00	SYS

0069	615-06505	MONUMENT, TYPE B	9.00	ACH
0070	616-06405	RIPRAP, REVETMENT	16.00	TON
0071	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	21.00	SYS
0072	621-06565	MULCHING MATERIAL	1.00	TON
0073	621-06567	WATER	23.00	kGAL
0074	621-06574	SODDING	5434.00	SYS
0075	622-05645	PLANT, DECIDUOUS TREE, MULTI-STEM, 72 IN. TO 96 IN.	6.00	ACH
0076	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	ACH
0077	628-12683	FIELD OFFICE, TYPE D	30.00	MOS
0078	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	5434.00	SYS
0079	629-000150	TOPSOIL AMENDMENT BUDGET	10868.00	DOL
0080	703-06029	REINFORCING BARS, EPOXY COATED	5432.00	LBS
0081	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	65.00	SYS
0082	706-08500	REINFORCED CONCRETE MOMENT SLAB, 14 IN.	93.00	SYS
0083	706-09959	RAILING, CONCRETE TYPE FT	116.00	LFT
0084	706-09962	RAILING, CONCRETE TYPE PF-1	45.00	LFT
0085	706-11404	RAILING, STEEL TYPE PF-1	45.00	LFT
0086	709-51821	SURFACE SEAL	1.00	LS
0087	710-11640	MASONRY COLUMN	6.00	ACH
0088	710-11640	MASONRY COLUMN	2.00	ACH
0089	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	6520.00	LFT
0090	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	3720.00	LFT
0091	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	2054.00	LFT
0092	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	814.00	LFT
0093	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	720.00	LFT
0094	718-12306	GEOTEXTILE FOR UNDERDRAINS, TYPE 1B	5216.00	SYS
0095	718-52610	AGGREGATE FOR UNDERDRAINS	587.00	CYS
0096	720-01092	MANHOLE, TYPE J15, MODIFIED	7.00	ACH
0097	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	ACH
0098	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	8.00	ACH
0099	720-45030	INLET, TYPE E7	8.00	ACH
0100	720-45075	INLET, TYPE R13	1.00	ACH
0101	720-45410	MANHOLE, TYPE C4	50.00	ACH
0102	720-45510	MANHOLE, TYPE C4, MODIFIED	3.00	ACH
0103	720-98174	INLET, TYPE B15	56.00	ACH
0104	720-98555	INLET, TYPE C15	11.00	ACH
0105	720-99417	CATCH BASIN, TYPE C15	1.00	ACH

0106	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	35942.00	LFT
0107	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	15.00	ACH
0108	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	104.00	LFT
0109	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0110	801-06640	CONSTRUCTION SIGN, TYPE A	30.00	ACH
0111	801-06645	CONSTRUCTION SIGN, TYPE B	22.00	ACH
0112	801-06775	MAINTAINING TRAFFIC	1.00	LS
0113	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	8.00	ACH
0114	801-07118	BARRICADE, TYPE III-A	302.00	LFT
0115	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	418.00	LFT
0116	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	27.00	SYS
0117	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	36.00	LFT
0118	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	504.00	LFT
0119	802-07060	SIGN, SHEET, RELOCATE	40.00	ACH
0120	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	107.00	SFT
0121	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	31.00	SFT
0122	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.00	ACH
0123	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00	ACH
0124	805-01842	HANDHOLE, SIGNAL, TYPE 1	1.00	ACH
0125	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	3.00	ACH
0126	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1793.00	LFT
0127	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0128	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	5.00	ACH
0129	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	5.00	ACH
0130	805-05405	SIGNAL POLE, PEDESTAL, 4 FT	1.00	ACH
0131	805-06595	CONDUIT, PVC, 2 IN.	5419.00	LFT
0132	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	5.00	ACH
0133	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	30.00	LFT
0134	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	200.00	LFT
0135	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	250.00	LFT
0136	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	ACH
0137	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00	ACH
0138	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	4.00	ACH
0139	805-78415	SPAN, CATENARY, AND TETHER	2.00	ACH
0140	805-78420	DISCONNECT HANGER	4.00	ACH
0141	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2500.00	LFT
0142	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	3500.00	LFT

0143	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	250.00	LFT
0144	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	700.00	LFT
0145	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	1150.00	LFT
0146	805-78785	SIGNAL DETECTOR HOUSING	5.00	≡ACH
0147	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	900.00	LFT
0148	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00	≡ACH
0149	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00	≡ACH
0150	807-02191	HANDHOLE, LIGHTING	26.00	≡ACH
0151	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	3.00	≡ACH
0152	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	3.00	≡ACH
0153	807-03950	LUMINAIRE, ORNAMENTAL	3.00	≡ACH
0154	807-03951	LIGHT POLE, ORNAMENTAL	1.00	≡ACH
0155	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	866.00	LFT
0156	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	6.00	≡ACH
0157	807-86805	SERVICE POINT, TYPE I	1.00	≡ACH
0158	807-86955	CABLE-DUCT MARKER	2.00	≡ACH
0159	807-91082	LUMINAIRE, REMOVE AND RELOCATE	1.00	≡ACH
0160	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1120.00	LFT
0161	808-06716	LINE, REMOVE	8445.00	LFT
0162	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0163	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	6742.00	LFT
0164	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	7244.00	LFT
0165	808-12032	GROOVING FOR PAVEMENT MARKINGS	15402.00	LFT
0166	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	50.00	LFT
0167	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	1366.00	LFT
0168	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	279.00	LFT
0169	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	35.00	LFT
0170	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	220.00	LFT
0171	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	38.00	≡ACH
0172	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	60.00	≡ACH

Call: 121

Contract: R -40648-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
0012	202-02271	HEADWALL, REMOVE	1.00	ACH
0013	202-02279	CURB AND GUTTER, REMOVE	4276.00	LFT
0014	202-02771	CONCRETE APRON, REMOVE	6.00	ACH
0015	202-52710	SIDEWALK CONCRETE, REMOVE	1117.00	SYS
0016	202-91385	INLET, REMOVE	8.00	ACH
0017	202-93047	MANHOLE, REMOVE	6.00	ACH
0018	202-96133	PIPE, REMOVE	757.00	LFT
0019	202-96133	PIPE, REMOVE	220.00	LFT
0020	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	1.00	ACH
0021	203-02000	EXCAVATION, COMMON	16090.00	CYS
0022	203-02020	EXCAVATION, UNCLASSIFIED	225.00	CYS
0023	205-12108	STORMWATER MANAGEMENT BUDGET	32521.00	DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0025	205-12618	SWQCP PREPARATION	1.00	LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	619.00	SYS
0027	207-08266	SUBGRADE TREATMENT, TYPE III	2267.00	SYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	647.00	SYS
0029	207-12635	SUBGRADE TREATMENT, TYPE IBC	10850.00	SYS
0030	211-02050	B BORROW	225.00	CYS
0031	211-09265	STRUCTURE BACKFILL, TYPE 2	882.00	CYS

0032	214-11796	GEOGRID, TYPE IB	11473.00	SYS
0033	301-12234	COMPACTED AGGREGATE, NO. 53	2103.00	CYS
0034	302-07455	DENSE GRADED SUBBASE	104.00	CYS
0035	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	933.00	TON
0036	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	1170.00	TON
0037	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	3133.00	TON
0038	401-11526	JOINT ADHESIVE	4060.00	LFT
0039	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	4060.00	LFT
0040	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0041	502-08201	PCCP, 9.5 IN.	516.00	SYS
0042	502-11543	PCCP, 4 IN.	1889.00	SYS
0043	503-05240	D-1 CONTRACTION JOINT	252.00	LFT
0044	603-06065	FENCE, CHAIN LINK, RESET	50.00	LFT
0045	604-06070	SIDEWALK, CONCRETE	1083.00	SYS
0046	604-08086	CURB RAMP, CONCRETE	298.00	SYS
0047	604-12083	DETECTABLE WARNING SURFACES	38.00	SYS
0048	605-06120	CURB, CONCRETE	202.00	LFT
0049	605-06140	CURB AND GUTTER, CONCRETE	4670.00	LFT
0050	605-06255	CENTER CURB, CONCRETE, TYPE D	387.00	SYS
0051	605-97937	CURB AND GUTTER, ROLLED CURB	327.00	LFT
0052	610-09108	PCCP FOR APPROACHES, 9 IN.	619.00	SYS
0053	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	ACH
0054	615-06505	MONUMENT, TYPE B	26.00	ACH
0055	615-06510	MONUMENT, TYPE C	4.00	ACH
0056	615-06515	MONUMENT, TYPE D	2.00	ACH
0057	616-06405	RIPRAP, REVETMENT	17.00	TON
0058	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	20.00	SYS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	ACH
0060	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00	TON
0061	621-06554	SEED MIXTURE, TYPE U	267.00	LBS
0062	621-06565	MULCHING MATERIAL	3.00	TON
0063	621-06567	WATER	27.00	KGAL
0064	621-06575	SODDING, NURSERY	6989.00	SYS
0065	628-09403	FIELD OFFICE, TYPE C	10.00	MOS
0066	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0067	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	13562.00	SYS
0068	629-000150	TOPSOIL AMENDMENT BUDGET	27124.00	DOL

0069	715-02388	WATER MAIN	1.00	ACH
0070	715-02388	WATER MAIN	1.00	ACH
0071	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	912.00	LFT
0072	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1957.00	LFT
0073	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	252.00	LFT
0074	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	244.00	LFT
0075	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	159.00	LFT
0076	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	59.00	LFT
0077	715-06051	PIPE EXTENSION, CIRCULAR, DIAMETER 8 IN.	5.00	LFT
0078	715-09064	VIDEO INSPECTION FOR PIPE	2617.00	LFT
0079	715-11360	INSERTION VALVE 12 IN.	1.00	ACH
0080	715-46000	PIPE END SECTION, DIAMETER 12 IN.	7.00	ACH
0081	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	ACH
0082	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	ACH
0083	715-92544	WATER MAIN, DUCTILE IRON, 12 IN.	210.00	LFT
0084	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	657.00	SYS
0085	718-52610	AGGREGATE FOR UNDERDRAINS	83.00	CYS
0086	720-01092	MANHOLE, TYPE J15, MODIFIED	23.00	ACH
0087	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	ACH
0088	720-45075	INLET, TYPE R13	2.00	ACH
0089	720-45410	MANHOLE, TYPE C4	4.00	ACH
0090	720-96999	FIRE HYDRANT ASSEMBLY	2.00	ACH
0091	720-99416	CATCH BASIN, TYPE B15	16.00	ACH
0092	720-99417	CATCH BASIN, TYPE C15	3.00	ACH
0093	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	ACH
0094	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	ACH
0095	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	ACH
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, TYPE III-A	156.00	LFT
0098	801-07119	BARRICADE, TYPE III-B	24.00	LFT
0099	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	ACH
0100	802-04089	SIGN, SHEET, REMOVE	5.00	ACH
0101	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	337.00	LFT
0102	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	21.00	LFT
0103	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	208.00	SFT
0104	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	44.00	SFT
0105	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	20.00	SFT

0106	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	ACH
0107	805-01842	HANDHOLE, SIGNAL, TYPE 1	3.00	ACH
0108	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00	ACH
0109	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	2.00	ACH
0110	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	2.00	ACH
0111	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	300.00	LFT
0112	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	950.00	LFT
0113	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00	ACH
0114	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	2.00	ACH
0115	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	1400.00	LFT
0116	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1300.00	LFT
0117	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	1200.00	LFT
0118	805-78785	SIGNAL DETECTOR HOUSING	3.00	ACH
0119	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	500.00	LFT
0120	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00	ACH
0121	805-92504	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 2 CHANNEL	1.00	ACH
0122	807-02191	HANDHOLE, LIGHTING	9.00	ACH
0123	807-03950	LUMINAIRE, ORNAMENTAL	6.00	ACH
0124	807-03950	LUMINAIRE, ORNAMENTAL	7.00	ACH
0125	807-03951	LIGHT POLE, ORNAMENTAL	13.00	ACH
0126	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1800.00	LFT
0127	807-11694	ILLUMINATED SIGN	2.00	ACH
0128	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	13.00	ACH
0129	807-86810	SERVICE POINT, TYPE II	1.00	ACH
0130	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1100.00	LFT
0131	807-86910	CONNECTOR KIT, UNFUSED	13.00	ACH
0132	807-86915	CONNECTOR KIT, FUSED	13.00	ACH
0133	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	24.00	ACH
0134	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	20.00	ACH
0135	807-86930	INSULATION LINK, NON-WATERPROOFED	26.00	ACH
0136	807-86935	INSULATION LINK, WATERPROOFED	40.00	ACH
0137	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING, LOCATION IDENTIFICATION	13.00	ACH
0138	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	416.00	LFT
0139	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	17.00	SYS
0140	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	476.00	LFT
0141	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	50.00	LFT
0142	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	218.00	LFT

0143	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	297.00	LFT
0144	808-12032	GROOVING FOR PAVEMENT MARKINGS	5140.00	LFT
0145	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4367.00	LFT
0146	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	33.00	LFT
0147	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	341.00	LFT
0148	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	64.00	LFT
0149	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	8.00	EACH

Call: 125

Contract: R -42755-A

Section No.: 1 NEW ROAD CONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-01025	SCALPING	3.00	ACRE
0013	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0014	202-02240	PAVEMENT REMOVAL	33.00	SYS
0015	202-02278	CURB, CONCRETE, REMOVE	588.00	LFT
0016	202-91385	INLET, REMOVE	3.00	EACH
0017	202-96133	PIPE, REMOVE	457.00	LFT
0018	202-99187	FENCE, FARM FIELD, REMOVE	556.00	LFT
0019	203-02000	EXCAVATION, COMMON	24845.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	18920.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	116.00	SYS
0024	207-12635	SUBGRADE TREATMENT, TYPE IBC	21982.00	SYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	401.00	CYS
0026	217-11917	DRYING SOILS FOR EMBANKMENT	199.00	TON
0027	301-12234	COMPACTED AGGREGATE, NO. 53	132.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	8.00	CYS
0029	303-01180	COMPACTED AGGREGATE, NO. 53	2104.00	TON
0030	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	2426.00	TON
0031	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	5559.00	TON

0032	401-11526	JOINT ADHESIVE	9712.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	18.00	TON
0034	410-000073	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm - SMA	1945.00	TON
0035	410-12466	VOID REDUCING ASPHALT MEMBRANE FOR SMA	9712.00	LFT
0036	502-11564	PCCP, 7 IN.	926.00	SYS
0037	503-05240	D-1 CONTRACTION JOINT	838.00	LFT
0038	601-01839	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 6	1.00	≡ACH
0039	601-05586	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 9	2.00	≡ACH
0040	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	1744.00	LFT
0041	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	3.00	≡ACH
0042	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	3.00	≡ACH
0043	605-06090	CURB, INTEGRAL CONCRETE	63.00	LFT
0044	605-06095	CURB, INTEGRAL CONCRETE, TYPE B	879.00	LFT
0045	605-06095	CURB, INTEGRAL CONCRETE, TYPE B	233.00	LFT
0046	605-06120	CURB, CONCRETE	80.00	LFT
0047	605-06140	CURB AND GUTTER, CONCRETE	1292.00	LFT
0048	605-06255	CENTER CURB, CONCRETE, TYPE D	17.00	SYS
0049	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	377.00	LFT
0050	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	5624.00	LFT
0051	610-08446	PCCP FOR APPROACHES, 6 IN.	46.00	SYS
0052	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	4.00	≡ACH
0053	615-06490	RIGHT-OF-WAY MARKER	55.00	≡ACH
0054	615-06505	MONUMENT, TYPE B	10.00	≡ACH
0055	615-06510	MONUMENT, TYPE C	2.00	≡ACH
0056	616-05688	RIPRAP, CLASS 1	34.00	TON
0057	616-06405	RIPRAP, REVETMENT	48.00	TON
0058	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	154.00	SYS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	≡ACH
0060	621-02770	EROSION CONTROL BLANKET	9303.00	SYS
0061	621-06553	SEED MIXTURE, TYPE R	1618.00	LBS
0062	621-06565	MULCHING MATERIAL	16.00	TON
0063	621-06567	WATER	4.00	kgAL
0064	621-06574	SODDING	783.00	SYS
0065	628-09401	FIELD OFFICE, TYPE A	12.00	MOS
0066	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	39454.00	SYS
0067	629-000150	TOPSOIL AMENDMENT BUDGET	78908.00	DOL
0068	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	247.00	LFT

0069	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	96.00	LFT
0070	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	97.00	LFT
0071	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	56.00	LFT
0072	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	29.00	LFT
0073	715-05171	PIPE, TYPE 3, CIRCULAR, DIAMETER 18 IN.	50.00	LFT
0074	715-05175	PIPE, TYPE 3, CIRCULAR, DIAMETER 30 IN.	50.00	LFT
0075	715-05237	PIPE, TYPE 1, DEFORMED, MIN. AREA 6.4 SFT	67.00	LFT
0076	715-05595	PIPE EXTENSION, CIRCULAR, DIAMETER 15 IN.	12.00	LFT
0077	715-05595	PIPE EXTENSION, CIRCULAR, DIAMETER 15 IN.	3.00	LFT
0078	715-09064	VIDEO INSPECTION FOR PIPE	879.00	LFT
0079	715-11665	PIPE END SECTION, DIAMETER 6 IN.	6.00	ACH
0080	715-12405	PIPE, TYPE 3, CIRCULAR, DIAMETER 6 IN.	172.00	LFT
0081	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	ACH
0082	715-46005	PIPE END SECTION, DIAMETER 15 IN.	6.00	ACH
0083	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	ACH
0084	715-46020	PIPE END SECTION, DIAMETER 24 IN.	3.00	ACH
0085	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	ACH
0086	715-46095	PIPE END SECTION, MIN. AREA 6.4 SFT	2.00	ACH
0087	720-45030	INLET, TYPE E7	1.00	ACH
0088	720-45035	INLET, TYPE F7	1.00	ACH
0089	720-45040	INLET, TYPE G7	1.00	ACH
0090	720-94432	MANHOLE, TYPE C7	2.00	ACH
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	ACH
0092	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	ACH
0093	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	ACH
0094	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	ACH
0095	801-06775	MAINTAINING TRAFFIC	1.00	LS
0096	801-07118	BARRICADE, TYPE III-A	147.00	LFT
0097	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	324.00	LFT
0098	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	71.00	LFT
0099	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	3.00	ACH
0100	802-07060	SIGN, SHEET, RELOCATE	3.00	ACH
0101	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	121.00	SFT
0102	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	98.00	SFT
0103	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	8.00	ACH
0104	807-85480	LIGHT POLE, 30 FT E.M.H., 5 FT MAST ARM, BREAKAWAY BASE	8.00	ACH
0105	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8285.00	LFT

0106	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0107	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	112.00	LFT
0108	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	53.00	LFT
0109	808-12032	GROOVING FOR PAVEMENT MARKINGS	17507.00	LFT
0110	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	9169.00	LFT
0111	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	12.00	EACH

Call: 131

Contract: R -43151-A

Section No.: 1 HMA OVERLAY MINOR STRUCTURAL

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02271	HEADWALL, REMOVE	2.00	≡ACH
0014	202-02928	CATCH BASIN, REMOVE	1.00	≡ACH
0015	202-91385	INLET, REMOVE	4.00	≡ACH
0016	202-96133	PIPE, REMOVE	85.00	LFT
0017	202-98488	PIPE END SECTION, REMOVE	1.00	≡ACH
0018	203-02000	EXCAVATION, COMMON	3257.00	CYS
0019	203-08607	LINEAR GRADING	12111.00	LFT
0020	205-11626	PUMP AROUND	5.00	≡ACH
0021	205-12108	STORMWATER MANAGEMENT BUDGET	21500.00	DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	4553.00	SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	5323.00	SYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	115.00	CYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	16.00	CYS
0027	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	23.00	CYS
0028	214-11796	GEOGRID, TYPE IB	4553.00	SYS
0029	303-01180	COMPACTED AGGREGATE, NO. 53	2087.00	TON
0030	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	3966.00	TON
0031	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	400.00	TON

0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	67617.00	SYS
0033	306-08038	MILLING, ASPHALT, 4 IN.	164655.00	SYS
0034	306-08432	MILLING, APPROACH	4451.00	SYS
0035	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	19563.00	TON
0036	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	23277.00	TON
0037	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	2257.00	TON
0038	401-11526	JOINT ADHESIVE	128165.00	LFT
0039	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0040	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	128165.00	LFT
0041	401-12664	HMA SPRAY PAVER EMULSION	189.00	TON
0042	406-05520	ASPHALT FOR TACK COAT	12.00	TON
0043	601-06035	GUARDRAIL, RESET	169.00	LFT
0044	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	ACH
0045	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	100880.00	LFT
0046	610-07488	HMA FOR APPROACHES, TYPE C	371.00	TON
0047	615-06500	MONUMENT, TYPE A	26.00	ACH
0048	615-06510	MONUMENT, TYPE C	11.00	ACH
0049	616-06405	RIPRAP, REVETMENT	35.00	TON
0050	616-11954	RIPRAP, GROUTED, 30 IN.	7.00	SYS
0051	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	101.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0053	621-06559	MULCHED SEEDING, TYPE R	8600.00	SYS
0054	621-06567	WATER	38.00	KGAL
0055	621-06574	SODDING	511.00	SYS
0056	621-06575	SODDING, NURSERY	223.00	SYS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0058	628-12683	FIELD OFFICE, TYPE D	20.00	MOS
0059	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	3257.00	LFT
0060	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	1199.00	LFT
0061	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	30.00	LFT
0062	715-09064	VIDEO INSPECTION FOR PIPE	353.00	LFT
0063	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	ACH
0064	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	ACH
0065	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	ACH
0066	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	ACH
0067	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	85.00	LFT
0068	716-07634	PIPE INSTALLATION, TRENCHLESS, 30 IN.	140.00	LFT

0069	718-06526	HMA FOR UNDERDRAINS	476.00 TON
0070	718-06528	OUTLET PROTECTOR, TYPE 1	57.00 EACH
0071	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3257.00 LFT
0072	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	2216.00 SYS
0073	718-52610	AGGREGATE FOR UNDERDRAINS	251.00 CYS
0074	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00 EACH
0075	720-45005	INLET, TYPE A2	1.00 EACH
0076	720-45030	INLET, TYPE E7	1.00 EACH
0077	720-45065	INLET, TYPE N12	2.00 EACH
0078	725-08291	PIPE LINER, CURED-IN-PLACE, 24 IN.	183.00 LFT
0079	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0080	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	8000.00 LFT
0081	801-06640	CONSTRUCTION SIGN, TYPE A	76.00 EACH
0082	801-06645	CONSTRUCTION SIGN, TYPE B	24.00 EACH
0083	801-06710	FLASHING ARROW SIGN	280.00 DAY
0084	801-06775	MAINTAINING TRAFFIC	1.00 LS
0085	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00 EACH
0086	801-07118	BARRICADE, TYPE III-A	48.00 LFT
0087	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	600.00 LFT
0088	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0089	801-12042	TRUCK MOUNTED ATTENUATOR	280.00 DAY
0090	802-03783	SIGN, PANEL, REMOVE	4.00 EACH
0091	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	120.00 LFT
0092	802-07057	SIGN, PANEL, WITH LEGEND	945.00 SFT
0093	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	206.00 SFT
0094	808-06716	LINE, REMOVE	8000.00 LFT
0095	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0096	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	450.00 LFT
0097	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	57845.00 LFT
0098	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	51897.00 LFT
0099	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	14314.00 LFT
0100	808-12032	GROOVING FOR PAVEMENT MARKINGS	124505.00 LFT
0101	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	200.00 LFT
0102	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	20.00 EACH
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	716.00 EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	772.00 EACH

Call: 135

Contract: R -43393-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0014	202-02240	PAVEMENT REMOVAL	24014.00	SYS
0015	202-02271	HEADWALL, REMOVE	10.00	EACH
0016	202-02859	GRATED BOX END SECTION, REMOVE	3.00	EACH
0017	202-02928	CATCH BASIN, REMOVE	11.00	EACH
0018	202-12026	SAFETY TERMINAL, REMOVE	16.00	EACH
0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0020	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0021	202-51368	SLOPEWALL, REMOVE	580.00	SYS
0022	202-91385	INLET, REMOVE	2.00	EACH
0023	202-93741	GUARDRAIL END TREATMENT, REMOVE	1.00	EACH
0024	202-94954	BARRIER WALL, CONCRETE, REMOVE	20.00	LFT
0025	202-95027	IMPACT ATTENUATOR, REMOVE	1.00	EACH
0026	202-98488	PIPE END SECTION, REMOVE	17.00	EACH
0027	203-02000	EXCAVATION, COMMON	31417.00	CYS
0028	205-11626	PUMP AROUND	26.00	EACH
0029	205-12108	STORMWATER MANAGEMENT BUDGET	111468.00	DOL
0030	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0031	205-12618	SWQCP PREPARATION	1.00	LS

0032	206-51235	COFFERDAM	1.00	LS
0033	207-08264	SUBGRADE TREATMENT, TYPE II	5112.00	SYS
0034	207-09935	SUBGRADE TREATMENT, TYPE IC	32218.00	SYS
0035	211-09265	STRUCTURE BACKFILL, TYPE 2	501.00	CYS
0036	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	184.00	CYS
0037	214-11796	GEOGRID, TYPE IB	37330.00	SYS
0038	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	284.00	SYS
0039	301-12233	COMPACTED AGGREGATE, NO. 8	97.00	CYS
0040	301-12234	COMPACTED AGGREGATE, NO. 53	3249.00	CYS
0041	302-06464	SUBBASE FOR PCCP	528.00	CYS
0042	303-01180	COMPACTED AGGREGATE, NO. 53	5817.00	TON
0043	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	117.00	TON
0044	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	1681.00	TON
0045	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	945.00	TON
0046	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	1091.00	TON
0047	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	3531.00	TON
0048	305-97019	RUBBLIZING PCCP	38.00	SYS
0049	306-08034	MILLING, ASPHALT, 1 1/2 IN.	445842.00	SYS
0050	306-08038	MILLING, ASPHALT, 4 IN.	167358.00	SYS
0051	306-08039	MILLING, ASPHALT REMOVAL	19063.00	SYS
0052	306-08432	MILLING, APPROACH	1126.00	SYS
0053	307-12253	CORRECTIVE AGGREGATE, FDR	7280.00	TON
0054	307-12254	FULL DEPTH RECLAMATION	42892.00	SYS
0055	307-12256	STABILIZING MATERIAL, PORTLAND CEMENT	1340.00	TON
0056	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	12527.00	TON
0057	401-000037	QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	1061.00	TON
0058	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	46135.00	TON
0059	401-000045	QC/QA-HMA, 4, 58E, INTERMEDIATE, 19.0 mm	1652.00	TON
0060	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	4942.00	TON
0061	401-000048	QC/QA-HMA, 4, 58S, BASE, 25.0 mm	5358.00	TON
0062	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	9436.00	TON
0063	401-000067	QC/QA-HMA, 4, 58E, INTERMEDIATE, OG, 19.0 mm	2619.00	TON
0064	401-11526	JOINT ADHESIVE	21918.00	LFT
0065	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0066	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	941.00	LFT
0067	401-12664	HMA SPRAY PAVER EMULSION	202.00	TON
0068	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	6069.00	TON

0069	406-05520	ASPHALT FOR TACK COAT	171.00 TON
0070	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00 TON
0071	410-000073	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm - SMA	25829.00 TON
0072	410-12466	VOID REDUCING ASPHALT MEMBRANE FOR SMA	314576.00 LFT
0073	410-12665	SMA SPRAY PAVER EMULSION	218.00 TON
0074	502-06331	PCCP, 14 IN.	1268.00 SYS
0075	503-03489	RETROFITTED TIE BARS	226.00 EACH
0076	503-05240	D-1 CONTRACTION JOINT	1243.00 LFT
0077	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	656.00 LFT
0078	503-12478	TERMINAL JOINT, TYPE PCCP	156.00 LFT
0079	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	152.00 LFT
0080	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	476.00 SFT
0081	503-12505	JOINTED REINFORCED CONCRETE PAVEMENT, 14 IN.	676.00 SYS
0082	506-06333	PCCP PATCHING, FULL DEPTH	1555.00 SYS
0083	507-07480	PROFILING PCCP	23398.00 SYS
0084	507-08272	JOINTS IN PCCP, SAW AND SEAL	49351.00 LFT
0085	509-12191	JOINT REPAIR, PARTIAL DEPTH	2362.00 SFT
0086	509-12192	JOINT REPAIR, BOTTOM-HALF	590.00 SFT
0087	601-01522	GUARDRAIL TRANSITION, TYPE TGB	2.00 EACH
0088	601-06035	GUARDRAIL, RESET	679.00 LFT
0089	601-06854	GUARDRAIL, W-BEAM, NESTED	4.00 EACH
0090	601-07009	IMPACT ATTENUATOR, LS-W1, TL-1	1.00 EACH
0091	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	3415.00 LFT
0092	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	6.00 EACH
0093	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	3.00 EACH
0094	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	5.00 EACH
0095	601-94689	GUARDRAIL END TREATMENT, TYPE OS	7.00 EACH
0096	601-94690	GUARDRAIL END TREATMENT, TYPE MS	2.00 EACH
0097	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	456.00 LFT
0098	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	214385.00 LFT
0099	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	412.00 SYS
0100	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	284.00 SYS
0101	610-07488	HMA FOR APPROACHES, TYPE C	93.00 TON
0102	616-05688	RIPRAP, CLASS 1	1291.00 TON
0103	616-05689	RIPRAP, CLASS 2	1138.00 TON
0104	616-06405	RIPRAP, REVETMENT	7.00 TON
0105	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	888.00 SYS

0106	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0107	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0108	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0109	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0110	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0111	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0112	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	ACH
0113	621-02770	EROSION CONTROL BLANKET	204.00	SYS
0114	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00	TON
0115	621-06553	SEED MIXTURE, TYPE R	36.00	LBS
0116	621-06559	MULCHED SEEDING, TYPE R	5582.00	SYS
0117	621-06565	MULCHING MATERIAL	1.00	TON
0118	621-12612	SEED MIXTURE, FLOODPLAIN	11.00	LBS
0119	627-09330	SAFETY TERMINAL, TYPE TL-3	16.00	ACH
0120	627-10178	CABLE BARRIER SYSTEM, TYPE TL-4, SPARE PARTS	1.00	LS
0121	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4, RESET	24017.00	LFT
0122	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0123	628-12683	FIELD OFFICE, TYPE D	24.00	MOS
0124	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	5582.00	SYS
0125	629-000150	TOPSOIL AMENDMENT BUDGET	11164.00	DOL
0126	702-51863	FIELD DRILLED HOLE IN CONCRETE	444.00	ACH
0127	703-06029	REINFORCING BARS, EPOXY COATED	41860.00	LBS
0128	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	184.00	ACH
0129	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	8.00	ACH
0130	709-51821	SURFACE SEAL	1.00	LS
0131	709-51821	SURFACE SEAL	1.00	LS
0132	710-09158	PATCHING CONCRETE STRUCTURES	247.00	SFT
0133	714-11192	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 3 FT	187.00	LFT
0134	714-11197	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 3 FT X 2 FT	182.00	LFT
0135	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	10.00	LFT
0136	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	6746.00	LFT
0137	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	1249.00	LFT
0138	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	46.00	LFT
0139	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	36.00	LFT
0140	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	8.00	LFT
0141	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	322.00	LFT
0142	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	94.00	LFT

0143	715-09064	VIDEO INSPECTION FOR PIPE	546.00	LFT
0144	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	2.00	ACH
0145	715-12871	GEOTEXTILE FOR PIPE, TYPE 2A	193.00	SYS
0146	715-46005	PIPE END SECTION, DIAMETER 15 IN.	6.00	ACH
0147	715-46010	PIPE END SECTION, DIAMETER 18 IN.	5.00	ACH
0148	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	ACH
0149	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	ACH
0150	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	420.00	LFT
0151	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	269.00	LFT
0152	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	119.00	LFT
0153	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	276.00	LFT
0154	718-06528	OUTLET PROTECTOR, TYPE 1	14.00	ACH
0155	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	7995.00	LFT
0156	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	5748.00	SYS
0157	718-52610	AGGREGATE FOR UNDERDRAINS	537.00	CYS
0158	720-45065	INLET, TYPE N12	19.00	ACH
0159	720-45410	MANHOLE, TYPE C4	7.00	ACH
0160	722-000183	BRIDGE DECK, REMOVE CONCRETE OVERLAY AND SURFACE	628.00	SYS
0161	722-01066	HYDRODEMOLITION	3058.00	SYS
0162	722-12380	BRIDGE DECK OVERLAY BUDGET	109974.00	DOL
0163	722-12464	BRIDGE DECK, REMOVE CONCRETE SURFACE	2430.00	SYS
0164	722-12732	LONGITUDINAL GROOVING	3754.00	SYS
0165	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	838.00	SFT
0166	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3058.00	SYS
0167	722-51874	OVERLAY DAM	164.00	SFT
0168	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	2.00	GAL
0169	727-90308	EPOXY INJECTION, CRACK PREPARATION	40.00	LFT
0170	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0171	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0172	801-04308	ROAD CLOSURE SIGN ASSEMBLY	41.00	ACH
0173	801-06206	TEMPORARY PAVEMENT MARKING, 6 IN.	175600.00	LFT
0174	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1058181.00	LFT
0175	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	7020.00	LFT
0176	801-06625	DETOUR ROUTE MARKER ASSEMBLY	216.00	ACH
0177	801-06640	CONSTRUCTION SIGN, TYPE A	253.00	ACH
0178	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	ACH
0179	801-06710	FLASHING ARROW SIGN	1095.00	DAY

0180	801-06775	MAINTAINING TRAFFIC	1.00	LS
0181	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	26.00	ACH
0182	801-07119	BARRICADE, TYPE III-B	84.00	LFT
0183	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	23684.00	LFT
0184	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	58938.00	LFT
0185	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	ACH
0186	801-12042	TRUCK MOUNTED ATTENUATOR	290.00	DAY
0187	801-12324	LAW ENFORCEMENT OFFICER	800.00	HRS
0188	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	10.00	ACH
0189	801-12652	QUEUE TRUCK	64.00	DAY
0190	801-52817	TEMPORARY CROSSOVER, TYPE B	2.00	ACH
0191	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	7.00	LFT
0192	802-07057	SIGN, PANEL, WITH LEGEND	392.00	SFT
0193	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	5.00	SFT
0194	802-09860	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE H	1.00	ACH
0195	802-13009	CANTILEVER SIGN SUPPORT FOUNDATION, TYPE FGHIJ DRILLED SHAFT 36 IN.	1.00	ACH
0196	802-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.00	ACH
0197	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	829.00	LFT
0198	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	320.00	LFT
0199	807-02191	HANDHOLE, LIGHTING	10.00	ACH
0200	807-04654	LIGHT POLE	1.00	ACH
0201	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	386.00	LFT
0202	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	5170.00	LFT
0203	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	12.00	ACH
0204	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	12.00	ACH
0205	807-85752	LIGHT POLE, 40 FT E.M.H., 10 FT MAST ARM, BREAKAWAY BASE	1.00	ACH
0206	807-85762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	11.00	ACH
0207	807-86810	SERVICE POINT, TYPE II	2.00	ACH
0208	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	690.00	LFT
0209	808-06716	LINE, REMOVE	175600.00	LFT
0210	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0211	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	248.00	LFT
0212	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	248.00	LFT
0213	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	13172.00	LFT
0214	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	13172.00	LFT
0215	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	340.00	LFT
0216	808-12032	GROOVING FOR PAVEMENT MARKINGS	263452.00	LFT

0217	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	4972.00	LFT
0218	808-12848	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 10 IN.	2686.00	LFT
0219	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	102216.00	LFT
0220	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	26022.00	LFT
0221	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	101864.00	LFT
0222	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	58.00	LFT
0223	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	463.00	LFT
0224	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	148.00	LFT
0225	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	3.00	EACH
0226	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1753.00	EACH
0227	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1348.00	EACH

Call: 141

Contract: R -43470-A

Section No.: 1 HMA OVERLAY, STRUCTURAL

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	8133.00	SYS
0013	202-02637	PIPE ABANDON AND GROUT FILL	6699.00	LFT
0014	202-02772	CASTING, REMOVE	23.00	EACH
0015	202-86946	HANDHOLE, REMOVE	8.00	EACH
0016	202-93047	MANHOLE, REMOVE	43.00	EACH
0017	202-96133	PIPE, REMOVE	6375.00	LFT
0018	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	7.00	EACH
0019	203-02000	EXCAVATION, COMMON	13295.00	CYS
0020	205-11626	PUMP AROUND	1.00	EACH
0021	205-12108	STORMWATER MANAGEMENT BUDGET	41871.00	DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0023	205-12618	SWQCP PREPARATION	1.00	LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	3489.00	SYS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	28413.00	SYS
0026	211-02050	B BORROW	916.00	CYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	8542.00	CYS
0028	214-11796	GEOGRID, TYPE IB	3488.00	SYS
0029	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	8747.00	SYS
0030	301-12233	COMPACTED AGGREGATE, NO. 8	2908.00	CYS
0031	301-12234	COMPACTED AGGREGATE, NO. 53	3872.00	CYS

0032	302-07455	DENSE GRADED SUBBASE	524.00	CYS
0033	303-01180	COMPACTED AGGREGATE, NO. 53	84.00	TON
0034	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	181.00	TON
0035	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2354.00	SYS
0036	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	1848.00	TON
0037	401-000037	QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	3079.00	TON
0038	401-000052	QC/QA-HMA, 2, 58S, BASE, 19.0 mm	4927.00	TON
0039	401-11526	JOINT ADHESIVE	10484.00	LFT
0040	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	10484.00	LFT
0041	406-05520	ASPHALT FOR TACK COAT	16.00	TON
0042	603-06045	FENCE, CHAIN LINK, 48 IN.	52.00	LFT
0043	604-06070	SIDEWALK, CONCRETE	2714.00	SYS
0044	604-08086	CURB RAMP, CONCRETE	206.00	SYS
0045	604-12083	DETECTABLE WARNING SURFACES	43.00	SYS
0046	605-06140	CURB AND GUTTER, CONCRETE	7814.00	LFT
0047	605-97937	CURB AND GUTTER, ROLLED CURB	10.00	LFT
0048	610-07487	HMA FOR APPROACHES, TYPE B	1033.00	TON
0049	610-08446	PCCP FOR APPROACHES, 6 IN.	2535.00	SYS
0050	610-09108	PCCP FOR APPROACHES, 9 IN.	354.00	SYS
0051	611-06497	MAILBOX ASSEMBLY, SINGLE	65.00	≡ACH
0052	615-06505	MONUMENT, TYPE B	9.00	≡ACH
0053	616-05688	RIPRAP, CLASS 1	11.00	TON
0054	616-06405	RIPRAP, REVETMENT	127.00	TON
0055	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	227.00	SYS
0056	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	≡ACH
0057	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00	TON
0058	621-06554	SEED MIXTURE, TYPE U	394.00	LBS
0059	621-06565	MULCHING MATERIAL	4.00	TON
0060	621-06567	WATER	41.00	kGAL
0061	621-06575	SODDING, NURSERY	735.00	SYS
0062	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	≡ACH
0063	628-12683	FIELD OFFICE, TYPE D	30.00	MOS
0064	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	10416.00	SYS
0065	629-000150	TOPSOIL AMENDMENT BUDGET	20832.00	DOL
0066	715-02574	WATER SERVICE CONNECTION, 2 IN.	3.00	≡ACH
0067	715-02743	GATE VALVE WITH VALVE BOX, 4 IN.	4.00	≡ACH
0068	715-02744	GATE VALVE WITH VALVE BOX, 6 IN.	4.00	≡ACH

0069	715-02745	GATE VALVE WITH VALVE BOX, 8 IN.	29.00	ACH
0070	715-04836	GATE VALVE	2.00	ACH
0071	715-04987	CONNECTION	6.00	ACH
0072	715-04987	CONNECTION	1.00	ACH
0073	715-04987	CONNECTION	8.00	ACH
0074	715-04987	CONNECTION	1.00	ACH
0075	715-04987	CONNECTION	4.00	ACH
0076	715-04987	CONNECTION	9.00	ACH
0077	715-04987	CONNECTION	33.00	ACH
0078	715-04987	CONNECTION	4.00	ACH
0079	715-04987	CONNECTION	8.00	ACH
0080	715-04987	CONNECTION	1.00	ACH
0081	715-04987	CONNECTION	4.00	ACH
0082	715-04987	CONNECTION	15.00	ACH
0083	715-04987	CONNECTION	16.00	ACH
0084	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	9965.00	LFT
0085	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	2916.00	LFT
0086	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	904.00	LFT
0087	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	1464.00	LFT
0088	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	761.00	LFT
0089	715-05156	PIPE, TYPE 2, CIRCULAR, DIAMETER 30 IN.	26.00	LFT
0090	715-05203	PIPE, TYPE 4, CIRCULAR, DIAMETER 4 IN.	2.00	LFT
0091	715-05408	PIPE, SANITARY SEWER, DIAMETER 8 IN.	661.00	LFT
0092	715-05408	PIPE, SANITARY SEWER, DIAMETER 8 IN.	1753.00	LFT
0093	715-05408	PIPE, SANITARY SEWER, DIAMETER 8 IN.	154.00	LFT
0094	715-05409	PIPE, SANITARY SEWER, DIAMETER 10 IN.	20.00	LFT
0095	715-06050	CAP	1.00	ACH
0096	715-06050	CAP	1.00	ACH
0097	715-07794	WATER MAIN CONNECTIONS	49.00	ACH
0098	715-09064	VIDEO INSPECTION FOR PIPE	6077.00	LFT
0099	715-09843	BYPASS PUMPING	1.00	LS
0100	715-09843	BYPASS PUMPING	1.00	LS
0101	715-10142	PIPE, TYPE 5, CIRCULAR, DIAMETER 8 IN.	2.00	LFT
0102	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	281.00	LFT
0103	715-12019	PIPE, TYPE 5, CIRCULAR, DIAMETER 6 IN.	2.00	LFT
0104	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	ACH
0105	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	ACH

0106	715-46020	PIPE END SECTION, DIAMETER 24 IN.	3.00	ACH
0107	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00	ACH
0108	715-90853	TAPPING SLEEVE WITH VALVE	1.00	ACH
0109	715-91742	WATER METER RELOCATE	21.00	ACH
0110	715-93911	WATER MAIN, 4 IN.	177.00	LFT
0111	715-93912	WATER MAIN, 6 IN.	74.00	LFT
0112	715-93913	WATER MAIN, 8 IN.	5955.00	LFT
0113	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	20.00	LFT
0114	716-01382	AIR RELEASE VALVE	2.00	ACH
0115	716-01382	AIR RELEASE VALVE	1.00	ACH
0116	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3000.00	LFT
0117	718-12306	GEOTEXTILE FOR UNDERDRAINS, TYPE 1B	6831.00	SYS
0118	718-52610	AGGREGATE FOR UNDERDRAINS	900.00	CYS
0119	720-01092	MANHOLE, TYPE J15, MODIFIED	6.00	ACH
0120	720-02442	PIPE, PLUG EXISTING	13.00	ACH
0121	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	ACH
0122	720-45030	INLET, TYPE E7	5.00	ACH
0123	720-45035	INLET, TYPE F7	3.00	ACH
0124	720-45042	INLET, TYPE HAS	3.00	ACH
0125	720-45045	INLET, TYPE J10	1.00	ACH
0126	720-45075	INLET, TYPE R13	1.00	ACH
0127	720-45410	MANHOLE, TYPE C4	46.00	ACH
0128	720-45510	MANHOLE, TYPE C4, MODIFIED	6.00	ACH
0129	720-94432	MANHOLE, TYPE C7	4.00	ACH
0130	720-95422	MANHOLE, TYPE J4	3.00	ACH
0131	720-96999	FIRE HYDRANT ASSEMBLY	11.00	ACH
0132	720-98174	INLET, TYPE B15	38.00	ACH
0133	720-98555	INLET, TYPE C15	30.00	ACH
0134	732-11770	AGGREGATE FOR DRAINAGE FILL	46.00	CYS
0135	732-11810	MODULAR BLOCK WALL	360.00	SFT
0136	732-11811	MODULAR BLOCK WALL ERECTION	360.00	SFT
0137	801-03290	CONSTRUCTION SIGN, TYPE C	5.00	ACH
0138	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	ACH
0139	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	ACH
0140	801-06640	CONSTRUCTION SIGN, TYPE A	18.00	ACH
0141	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	ACH
0142	801-06775	MAINTAINING TRAFFIC	1.00	LS

0143	801-07118	BARRICADE, TYPE III-A	276.00	LFT
0144	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0145	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	467.00	LFT
0146	802-07060	SIGN, SHEET, RELOCATE	11.00	EACH
0147	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	294.00	SFT
0148	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	52.00	SFT
0149	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00	SFT
0150	802-09841	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	5.00	SFT
0151	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.00	EACH
0152	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	3.00	EACH
0153	805-01842	HANDHOLE, SIGNAL, TYPE 1	4.00	EACH
0154	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH
0155	805-02445	CONTROLLER AND CABINET, TYPE P1	2.00	EACH
0156	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0157	805-07842	VEHICLE DETECTION SYSTEM	3.00	EACH
0158	805-09089	RADIO, YAGI ANTENNA	2.00	EACH
0159	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	700.00	LFT
0160	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0161	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	22.00	EACH
0162	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	8.00	EACH
0163	805-78415	SPAN, CATENARY, AND TETHER	5.00	EACH
0164	805-78420	DISCONNECT HANGER	11.00	EACH
0165	805-78445	SIGNAL SERVICE	1.00	EACH
0166	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	50.00	LFT
0167	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1900.00	LFT
0168	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	600.00	LFT
0169	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	2200.00	LFT
0170	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	2.00	EACH
0171	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	3.00	EACH
0172	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00	EACH
0173	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0174	808-10192	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, BIKE SYMBOL	35.00	EACH
0175	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	151.00	LFT
0176	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	9523.00	LFT
0177	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	11655.00	LFT
0178	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	102.00	LFT
0179	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	369.00	LFT

0180	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	834.00	LFT
0181	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	33.00	EACH
0182	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, 'ONLY'	8.00	EACH
0183	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	367.00	LFT
0184	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	1919.00	LFT

Call: 151

Contract: R -43608-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	1985.00	CYS
0013	203-02070	BORROW	50.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	34141.20	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	205-12618	SWQCP PREPARATION	1.00	LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	3781.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	17.00	CYS
0019	214-11796	GEOGRID, TYPE IB	2244.00	SYS
0020	301-12234	COMPACTED AGGREGATE, NO. 53	337.00	CYS
0021	302-07455	DENSE GRADED SUBBASE	376.00	CYS
0022	303-01180	COMPACTED AGGREGATE, NO. 53	16.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	133.00	SYS
0024	401-11526	JOINT ADHESIVE	1820.00	LFT
0025	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0026	603-98225	FENCE, CHAIN LINK, PVC COATED, 48 IN.	70.00	LFT
0027	604-06070	SIDEWALK, CONCRETE	1617.00	SYS
0028	604-08086	CURB RAMP, CONCRETE	52.00	SYS
0029	604-08086	CURB RAMP, CONCRETE	142.00	SYS
0030	604-12083	DETECTABLE WARNING SURFACES	4.00	SYS
0031	604-12083	DETECTABLE WARNING SURFACES	23.00	SYS

0032	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	270.00	LFT
0033	605-06120	CURB, CONCRETE	717.00	LFT
0034	605-06121	CURB, CONCRETE, TYPE B	44.00	LFT
0035	605-06140	CURB AND GUTTER, CONCRETE	1172.00	LFT
0036	610-07487	HMA FOR APPROACHES, TYPE B	371.00	TON
0037	610-08446	PCCP FOR APPROACHES, 6 IN.	146.00	SYS
0038	610-09108	PCCP FOR APPROACHES, 9 IN.	2098.00	SYS
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	ACH
0040	621-06553	SEED MIXTURE, TYPE R	237.80	LBS
0041	621-06565	MULCHING MATERIAL	2.30	TON
0042	621-06567	WATER	22.50	kGAL
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0044	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0045	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	5959.00	SYS
0046	629-000150	TOPSOIL AMENDMENT BUDGET	11916.00	DOL
0047	703-06029	REINFORCING BARS, EPOXY COATED	2597.00	LBS
0048	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	6.00	LFT
0049	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	84.00	LFT
0050	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	12.00	LFT
0051	715-09064	VIDEO INSPECTION FOR PIPE	117.00	LFT
0052	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	ACH
0053	715-92037	PIPE PVC, 4 IN.	7.00	LFT
0054	715-96960	PIPE, PVC, 15 IN.	8.00	LFT
0055	720-12797	CASTING, INLET, ADJUST TO GRADE	7.00	ACH
0056	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	8.00	ACH
0057	720-44296	INLET, CAP	2.00	ACH
0058	720-45030	INLET, TYPE E7	1.00	ACH
0059	720-45042	INLET, TYPE HA5	8.00	ACH
0060	720-45045	INLET, TYPE J10	2.00	ACH
0061	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9920.00	LFT
0062	801-06217	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 6 IN.	628.00	LFT
0063	801-06640	CONSTRUCTION SIGN, TYPE A	22.00	ACH
0064	801-06645	CONSTRUCTION SIGN, TYPE B	13.00	ACH
0065	801-06775	MAINTAINING TRAFFIC	1.00	LS
0066	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	ACH
0067	801-07119	BARRICADE, TYPE III-B	102.00	LFT
0068	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	307.00	LFT

0069	801-11990	TEMPORARY CURB RAMP	2.00	ACH
0070	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	348.00	LFT
0071	802-02475	SIGN, PANEL, RELOCATE	2.00	ACH
0072	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	156.00	LFT
0073	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	50.00	SFT
0074	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	24.00	SFT
0075	805-01842	HANDHOLE, SIGNAL, TYPE 1	1.00	ACH
0076	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	ACH
0077	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	4.00	ACH
0078	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	140.00	LFT
0079	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	ACH
0080	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	220.00	LFT
0081	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	770.00	LFT
0082	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	810.00	LFT
0083	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	90.00	LFT
0084	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00	ACH
0085	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	44.00	LFT
0086	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	95.00	LFT
0087	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1524.00	LFT
0088	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	2.00	ACH
0089	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	60.00	LFT
0090	808-12032	GROOVING FOR PAVEMENT MARKINGS	244.00	LFT
0091	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	284.00	LFT
0092	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	200.00	LFT
0093	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	138.00	LFT
0094	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	621.00	LFT
0095	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	2.00	ACH

Call: 161

Contract: R -43697-A

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-96133	PIPE, REMOVE	168.00	LFT
0012	203-02000	EXCAVATION, COMMON	195.00	CYS
0013	203-02070	BORROW	1013.00	CYS
0014	205-11626	PUMP AROUND	1.00	EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	15222.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	480.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	1899.00	CYS
0019	214-11796	GEOGRID, TYPE IB	480.00	SYS
0020	301-12233	COMPACTED AGGREGATE, NO. 8	89.00	CYS
0021	303-01180	COMPACTED AGGREGATE, NO. 53	51.00	TON
0022	304-07493	WIDENING WITH HMA, TYPE B	113.00	TON
0023	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	16.00	TON
0024	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	26.00	TON
0025	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	62.00	TON
0026	401-11526	JOINT ADHESIVE	928.00	LFT
0027	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0028	601-02241	GUARDRAIL, REMOVE	496.00	LFT
0029	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	319.00	LFT
0030	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	EACH
0031	615-06490	RIGHT-OF-WAY MARKER	18.00	EACH

0032	616-05688	RIPRAP, CLASS 1	16.00 TON
0033	616-06405	RIPRAP, REVETMENT	17.00 TON
0034	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	64.00 SYS
0035	621-06559	MULCHED SEEDING, TYPE R	1520.00 SYS
0036	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	12.00 EACH
0037	628-09403	FIELD OFFICE, TYPE C	9.00 MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0039	702-04325	TEMPORARY SHORING	1.00 LS
0040	715-05127	PIPE, TYPE 1, CIRCULAR, DIAMETER 42 IN.	149.00 LFT
0041	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00 EACH
0042	801-06625	DETOUR ROUTE MARKER ASSEMBLY	37.00 EACH
0043	801-06640	CONSTRUCTION SIGN, TYPE A	6.00 EACH
0044	801-06775	MAINTAINING TRAFFIC	1.00 LS
0045	801-07118	BARRICADE, TYPE III-A	48.00 LFT
0046	801-07119	BARRICADE, TYPE III-B	192.00 LFT
0047	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	595.00 LFT
0048	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	102.00 LFT

Call: 171

Contract: R -43741-A

Section No.: 1 HMA OVERLAY MINOR STRUCTURAL

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-11823	CONSTRUCTION ENGINEERING, GPS ROVER	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	113-01614	PARTNERING OVERHEAD	1.00	LS
0014	201-06587	CLEARING AND GRUBBING	11.00	ACRE
0015	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0016	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0017	202-02240	PAVEMENT REMOVAL	145108.00	SYS
0018	202-02272	PAVED SIDE DITCH, REMOVE	880.00	LFT
0019	202-02278	CURB, CONCRETE, REMOVE	228.00	LFT
0020	202-02279	CURB AND GUTTER, REMOVE	120.00	LFT
0021	202-02637	PIPE ABANDON AND GROUT FILL	678.00	LFT
0022	202-02928	CATCH BASIN, REMOVE	9.00	EACH
0023	202-12024	CABLE BARRIER, REMOVE	22754.00	LFT
0024	202-12026	SAFETY TERMINAL, REMOVE	11.00	EACH
0025	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0026	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0027	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0028	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0029	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0030	202-51368	SLOPEWALL, REMOVE	872.00	SYS
0031	202-92953	CURB AND GUTTER TURNOUT, REMOVE	12.00	SYS

0032	202-93741	GUARDRAIL END TREATMENT, REMOVE	23.00	EACH
0033	202-96133	PIPE, REMOVE	5500.00	LFT
0034	203-02000	EXCAVATION, COMMON	83700.00	CYS
0035	203-02070	BORROW	18896.00	CYS
0036	205-11626	PUMP AROUND	1.00	EACH
0037	205-12108	STORMWATER MANAGEMENT BUDGET	846501.00	DOL
0038	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0039	205-12618	SWQCP PREPARATION	1.00	LS
0040	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	728.00	CYS
0041	206-51235	COFFERDAM	1.00	LS
0042	207-08264	SUBGRADE TREATMENT, TYPE II	1953.00	SYS
0043	207-09935	SUBGRADE TREATMENT, TYPE IC	71187.00	SYS
0044	207-12635	SUBGRADE TREATMENT, TYPE IBC	97672.00	SYS
0045	211-09264	STRUCTURE BACKFILL, TYPE 1	1285.00	CYS
0046	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.00	CYS
0047	213-09270	FLOWABLE BACKFILL, REMOVABLE	71.00	CYS
0048	214-11796	GEOGRID, TYPE IB	65690.00	SYS
0049	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	27091.00	SYS
0050	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	7144.00	SYS
0051	301-12231	COMPACTED AGGREGATE, NO. 2	8.00	CYS
0052	301-12233	COMPACTED AGGREGATE, NO. 8	3010.00	CYS
0053	301-12234	COMPACTED AGGREGATE, NO. 53	14585.00	CYS
0054	302-06464	SUBBASE FOR PCCP	1216.00	CYS
0055	303-01180	COMPACTED AGGREGATE, NO. 53	38656.00	TON
0056	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	1382.00	TON
0057	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	322.00	TON
0058	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	1969.00	TON
0059	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	43.00	TON
0060	305-97019	RUBBLIZING PCCP	93221.00	SYS
0061	306-08036	MILLING, ASPHALT, 2 IN.	172387.00	SYS
0062	306-08039	MILLING, ASPHALT REMOVAL	92939.00	SYS
0063	306-08043	MILLING, TRANSITION	493.00	SYS
0064	306-08599	MILLING, ASPHALT, 1/2 IN.	57123.00	SYS
0065	309-12695	LEAN CONCRETE BASE, 9 IN.	1022.00	SYS
0066	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	73.00	TON
0067	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	12657.00	TON
0068	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	22.00	TON

0069	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	25628.00	TON
0070	401-000045	QC/QA-HMA, 4, 58E, INTERMEDIATE, 19.0 mm	28644.00	TON
0071	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	90.00	TON
0072	401-000048	QC/QA-HMA, 4, 58S, BASE, 25.0 mm	904.00	TON
0073	401-000052	QC/QA-HMA, 2, 58S, BASE, 19.0 mm	10369.00	TON
0074	401-000056	QC/QA-HMA, 4, 58S, BASE, 19.0 mm	83852.00	TON
0075	401-000067	QC/QA-HMA, 4, 58E, INTERMEDIATE, OG, 19.0 mm	21381.00	TON
0076	401-11526	JOINT ADHESIVE	302673.00	LFT
0077	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0078	401-12664	HMA SPRAY PAVER EMULSION	623.00	TON
0079	402-07787	HMA WEDGE AND LEVEL, TYPE D	19067.00	TON
0080	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	12467.00	TON
0081	406-05520	ASPHALT FOR TACK COAT	175.00	TON
0082	410-000073	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm - SMA	41528.00	TON
0083	410-12466	VOID REDUCING ASPHALT MEMBRANE FOR SMA	276294.00	LFT
0084	410-12665	SMA SPRAY PAVER EMULSION	293.00	TON
0085	503-03489	RETROFITTED TIE BARS	320.00	≡ACH
0086	503-05240	D-1 CONTRACTION JOINT	1245.00	LFT
0087	503-09261	PCCP STITCHING	72.00	≡ACH
0088	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT, 12 IN.	4683.00	SYS
0089	503-12477	TERMINAL JOINT, TYPE HMA	472.00	LFT
0090	503-12478	TERMINAL JOINT, TYPE PCCP	267.00	LFT
0091	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	264.00	LFT
0092	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	683.00	SFT
0093	506-06333	PCCP PATCHING, FULL DEPTH	1022.00	SYS
0094	509-12191	JOINT REPAIR, PARTIAL DEPTH	1148.00	SFT
0095	509-12192	JOINT REPAIR, BOTTOM-HALF	98.00	SFT
0096	601-02206	TEMPORARY GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1313.00	LFT
0097	601-02241	GUARDRAIL, REMOVE	28888.00	LFT
0098	601-06035	GUARDRAIL, RESET	1073.00	LFT
0099	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	30223.00	LFT
0100	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	463.00	LFT
0101	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	14.00	≡ACH
0102	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	30.00	≡ACH
0103	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	21.00	≡ACH
0104	601-52501	GUARDRAIL, POST	80.00	≡ACH
0105	601-94689	GUARDRAIL END TREATMENT, TYPE OS	27.00	≡ACH

0106	601-94690	GUARDRAIL END TREATMENT, TYPE MS	3.00	ACH
0107	601-97080	TEMPORARY GUARDRAIL END TREATMENT, TYPE OS	7.00	ACH
0108	602-06729	BARRIER DELINEATOR	80.00	ACH
0109	603-06065	FENCE, CHAIN LINK, RESET	75.00	LFT
0110	605-06100	CURB, INTEGRAL CONCRETE, TYPE C	92.00	LFT
0111	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	212.00	LFT
0112	605-06120	CURB, CONCRETE	44.00	LFT
0113	605-06150	CURB AND GUTTER, CONCRETE, TYPE C	120.00	LFT
0114	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	203570.00	LFT
0115	607-06340	PAVED SIDE DITCH, TYPE B	957.00	LFT
0116	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	2736.00	SYS
0117	610-07487	HMA FOR APPROACHES, TYPE B	471.00	TON
0118	615-06510	MONUMENT, TYPE C	25.00	ACH
0119	615-06515	MONUMENT, TYPE D	12.00	ACH
0120	616-05688	RIPRAP, CLASS 1	1580.00	TON
0121	616-05689	RIPRAP, CLASS 2	5576.00	TON
0122	616-06405	RIPRAP, REVETMENT	1657.00	TON
0123	616-06451	RIPRAP, UNIFORM	274.00	TON
0124	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	9772.00	SYS
0125	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	765.00	SYS
0126	616-93019	RIPRAP, GROUTED, 18 IN.	10.00	SYS
0127	619-11049	CLEAN STEEL BRIDGE, PARTIAL, QP-1, BRIDGE NO.	1.00	LS
0128	619-11049	CLEAN STEEL BRIDGE, PARTIAL, QP-1, BRIDGE NO.	1.00	LS
0129	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0130	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0131	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0132	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0133	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0134	619-12460	DISPOSAL OF CLEANING WASTE, NON-HAZARDOUS, BRIDGE NO.	1.00	LS
0135	619-12460	DISPOSAL OF CLEANING WASTE, NON-HAZARDOUS, BRIDGE NO.	1.00	LS
0136	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0137	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0138	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0139	619-51860	COAT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0140	619-95315	CLEAN AND COAT BEARING ASSEMBLIES, BRIDGE NO.	1.00	LS
0141	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	15.00	ACH
0142	621-02770	EROSION CONTROL BLANKET	55058.00	SYS

0143	621-06553	SEED MIXTURE, TYPE R	10135.00	LBS
0144	621-06559	MULCHED SEEDING, TYPE R	840.00	SYS
0145	621-06560	MULCHED SEEDING, TYPE U	3109.00	SYS
0146	621-06565	MULCHING MATERIAL	123.00	TON
0147	621-06574	SODDING	3819.00	SYS
0148	621-12612	SEED MIXTURE, FLOODPLAIN	6.00	LBS
0149	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	22754.00	LFT
0150	627-09330	SAFETY TERMINAL, TYPE TL-3	11.00	≡ACH
0151	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4, RESET	26593.00	LFT
0152	628-12684	FIELD OFFICE, TYPE E	36.00	MOS
0153	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	4115.00	SYS
0154	629-000150	TOPSOIL AMENDMENT BUDGET	8230.00	DOL
0155	701-06011	DYNAMIC PILE LOAD TEST	4.00	≡ACH
0156	701-09557	TEST PILE, DYNAMIC, PRODUCTION	256.00	LFT
0157	701-09559	TEST PILE, DYNAMIC, RESTRIKE	4.00	≡ACH
0158	701-09779	PREBORED HOLE, DIAMETER 15 IN.	576.00	LFT
0159	701-95780	PILE, STEEL H, HP 12 X 74	4495.00	LFT
0160	702-51005	CONCRETE, A, SUBSTRUCTURE	490.20	CYS
0161	702-51015	CONCRETE, B, FOOTINGS	79.20	CYS
0162	702-51863	FIELD DRILLED HOLE IN CONCRETE	272.00	≡ACH
0163	702-92857	CONCRETE, C, SUBSTRUCTURE	2.60	CYS
0164	703-06028	REINFORCING BARS	34240.00	LBS
0165	703-06029	REINFORCING BARS, EPOXY COATED	393002.00	LBS
0166	703-08247	EMBEDDED GALVANIC ANODE	134.00	≡ACH
0167	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	226.00	≡ACH
0168	704-51002	CONCRETE, C, SUPERSTRUCTURE	1013.70	CYS
0169	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPS-1	4.00	≡ACH
0170	706-11601	RAILING, CONCRETE TYPE FT	43.40	CYS
0171	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	32.00	≡ACH
0172	706-51020	RAILING, CONCRETE TYPE C	11.90	CYS
0173	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0174	709-51821	SURFACE SEAL	1.00	LS
0175	709-51821	SURFACE SEAL	1.00	LS
0176	709-51821	SURFACE SEAL	1.00	LS
0177	709-51821	SURFACE SEAL	1.00	LS
0178	709-51821	SURFACE SEAL	1.00	LS
0179	709-51821	SURFACE SEAL	1.00	LS

0180	709-51821	SURFACE SEAL	1.00	LS
0181	709-51821	SURFACE SEAL	1.00	LS
0182	709-51821	SURFACE SEAL	1.00	LS
0183	709-51821	SURFACE SEAL	1.00	LS
0184	709-51821	SURFACE SEAL	1.00	LS
0185	709-51821	SURFACE SEAL	1.00	LS
0186	710-09158	PATCHING CONCRETE STRUCTURES	548.00	SFT
0187	711-51035	STRUCTURAL STEEL	6400.00	LBS
0188	711-51864	DRILLED HOLE	72.00	≡ACH
0189	711-51877	JACKING AND SUPPORTING BEAMS	1.00	LS
0190	711-51877	JACKING AND SUPPORTING BEAMS	1.00	LS
0191	711-90114	JACKING AND SUPPORTING SUPERSTRUCTURE	1.00	LS
0192	711-95291	JACKING AND SUPPORTING STEEL BEAMS	1.00	LS
0193	715-04611	SAFETY METAL END SECTION, 4:1, DIAMETER 12 IN.	1.00	≡ACH
0194	715-04694	PIPE END SECTION, MIN. AREA 6.5 SFT	1.00	≡ACH
0195	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	224.00	LFT
0196	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	106665.00	LFT
0197	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	5943.00	LFT
0198	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	318.00	LFT
0199	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	84.00	LFT
0200	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	698.00	LFT
0201	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	92.00	LFT
0202	715-05153	PIPE, TYPE 2, CIRCULAR, DIAMETER 21 IN.	99.00	LFT
0203	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	91.00	LFT
0204	715-05172	PIPE, TYPE 3, CIRCULAR, DIAMETER 21 IN.	329.00	LFT
0205	715-05173	PIPE, TYPE 3, CIRCULAR, DIAMETER 24 IN.	5500.00	LFT
0206	715-05236	PIPE, TYPE 1, DEFORMED, MIN. AREA 5.0 SFT	341.00	LFT
0207	715-05238	PIPE, TYPE 1, DEFORMED, MIN. AREA 6.5 SFT	159.00	LFT
0208	715-05242	PIPE, TYPE 1, DEFORMED, MIN. AREA, 8.9 SFT	311.00	LFT
0209	715-05424	PIPE, SLOTTED DRAIN, DIAMETER 18 IN.	1750.00	LFT
0210	715-06566	PIPE EXTENSION, CIRCULAR, DIAMETER 6 IN.	18.00	LFT
0211	715-08453	SAFETY METAL END SECTION, 4:1, MIN. AREA 7.1 SFT	1.00	≡ACH
0212	715-09064	VIDEO INSPECTION FOR PIPE	1562.00	LFT
0213	715-09307	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 6.28 SFT	4.00	≡ACH
0214	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	4.00	≡ACH
0215	715-12068	GRATED BOX END SECTION, TYPE I, 3:1, MIN. AREA 8.9 SFT	1.00	≡ACH
0216	715-26767	GRATED BOX END SECTION, TYPE I, 5:1, DIAMETER 15 IN.	1.00	≡ACH

0217	715-26770	GRATED BOX END SECTION, TYPE I, 3:1, DIAMETER 24 IN.	2.00	ACH
0218	715-46000	PIPE END SECTION, DIAMETER 12 IN.	3.00	ACH
0219	715-46005	PIPE END SECTION, DIAMETER 15 IN.	5.00	ACH
0220	715-46015	PIPE END SECTION, DIAMETER 21 IN.	6.00	ACH
0221	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	ACH
0222	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	ACH
0223	715-97402	GRATED BOX END SECTION, TYPE I, 4:1, DIAMETER 15 IN.	1.00	ACH
0224	715-97404	GRATED BOX END SECTION, TYPE I, 3:1, DIAMETER 15 IN.	4.00	ACH
0225	715-97406	GRATED BOX END SECTION, TYPE I, 3:1, DIAMETER 18 IN.	1.00	ACH
0226	715-97559	GRATED BOX END SECTION, TYPE II, 10:1, DIAMETER 12 IN.	2.00	ACH
0227	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	224.00	LFT
0228	718-06526	HMA FOR UNDERDRAINS	9531.00	TON
0229	718-06528	OUTLET PROTECTOR, TYPE 1	48.00	ACH
0230	718-06529	OUTLET PROTECTOR, TYPE 2	175.00	ACH
0231	718-06531	OUTLET PROTECTOR, TYPE 3	46.00	ACH
0232	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	10000.00	LFT
0233	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	240.00	SYS
0234	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	72944.00	SYS
0235	718-52610	AGGREGATE FOR UNDERDRAINS	3748.00	CYS
0236	720-12797	CASTING, INLET, ADJUST TO GRADE	21.00	ACH
0237	720-45065	INLET, TYPE N12	11.00	ACH
0238	722-000134	BRIDGE DECK OVERLAY, RIGID	5872.00	SYS
0239	722-000183	BRIDGE DECK, REMOVE CONCRETE OVERLAY AND SURFACE	2252.00	SYS
0240	722-01066	HYDRODEMOLITION	5698.00	SYS
0241	722-12380	BRIDGE DECK OVERLAY BUDGET	99048.00	DOL
0242	722-12464	BRIDGE DECK, REMOVE CONCRETE SURFACE	3446.00	SYS
0243	722-12732	LONGITUDINAL GROOVING	9777.00	SYS
0244	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1080.00	SFT
0245	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1101.00	SFT
0246	722-51874	OVERLAY DAM	398.00	SFT
0247	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	68.00	LFT
0248	726-92406	BEARING ASSEMBLY, ELASTOMERIC	32.00	ACH
0249	726-92406	BEARING ASSEMBLY, ELASTOMERIC	8.00	ACH
0250	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	11.00	GAL
0251	727-90308	EPOXY INJECTION, CRACK PREPARATION	114.00	LFT
0252	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0253	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS

0254	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	9169.00	SYS
0255	738-12856	POLYMER OVERLAY, OTHER CONCRETE SURFACE	1155.00	SYS
0256	738-12917	BRIDGE DECK, REMOVE EXISTING POLYMER OVERLAY SYSTEM	10324.00	SYS
0257	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	ACH
0258	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	ACH
0259	801-06196	DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	29.00	ACH
0260	801-06206	TEMPORARY PAVEMENT MARKING, 6 IN.	107439.00	LFT
0261	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	38618.00	LFT
0262	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	459278.00	LFT
0263	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0264	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	ACH
0265	801-06640	CONSTRUCTION SIGN, TYPE A	251.00	ACH
0266	801-06645	CONSTRUCTION SIGN, TYPE B	19.00	ACH
0267	801-06710	FLASHING ARROW SIGN	2493.00	DAY
0268	801-06775	MAINTAINING TRAFFIC	1.00	LS
0269	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	ACH
0270	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	10.00	ACH
0271	801-07118	BARRICADE, TYPE III-A	350.00	LFT
0272	801-07119	BARRICADE, TYPE III-B	105.00	LFT
0273	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	4050.00	LFT
0274	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	28464.00	LFT
0275	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	14642.00	LFT
0276	801-09087	TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN.	274.00	LFT
0277	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	24.00	ACH
0278	801-11880	VEHICLES FOR ADVANCED SLOWDOWN	12.00	DAY
0279	801-12042	TRUCK MOUNTED ATTENUATOR	18.00	DAY
0280	801-12081	PORTABLE SIGNAL	1.00	LS
0281	801-12324	LAW ENFORCEMENT OFFICER	424.00	HRS
0282	801-12421	AUTOMATED WORK ZONE INFORMATION SYSTEM	1.00	LS
0283	801-12652	QUEUE TRUCK	40.00	DAY
0284	801-12832	TEMPORARY SPEED FEEDBACK ASSEMBLY	2.00	ACH
0285	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	30.00	ACH
0286	801-12955	TEMPORARY PAVEMENT MARKING, 10 IN.	13893.00	LFT
0287	801-12956	TEMPORARY PAVEMENT MARKING, REMOVABLE, 10 IN.	6876.00	LFT
0288	801-52817	TEMPORARY CROSSOVER, TYPE B	3.00	ACH
0289	801-97643	TEMPORARY BUZZ STRIPS	12096.00	LFT
0290	802-04893	REFERENCE POST	8.00	ACH

0291	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	48.00	LFT
0292	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	2.00	ACH
0293	802-76055	SIGN POST, TYPE A	280.00	LFT
0294	802-91122	SIGN, GROUND MOUNTED, RESET	51.00	ACH
0295	804-06725	DELINEATOR WITH POST, TYPE D1	298.00	ACH
0296	804-97955	DELINEATOR POST, FLEXIBLE, RESET	175.00	ACH
0297	805-06595	CONDUIT, PVC, 2 IN.	258.00	LFT
0298	807-01653	WIRE, NO. 4 COPPER, IN CONDUIT, BRIDGE 1/C	1700.00	LFT
0299	807-02191	HANDHOLE, LIGHTING	4.00	ACH
0300	808-06368	TRANSVERSE MARKING, REMOVE	672.00	LFT
0301	808-06716	LINE, REMOVE	90087.00	LFT
0302	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	25.00	LFT
0303	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0304	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 24 IN.	1643.00	LFT
0305	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	126043.00	LFT
0306	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	123726.00	LFT
0307	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	35014.00	LFT
0308	808-12032	GROOVING FOR PAVEMENT MARKINGS	282386.00	LFT
0309	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	2015.00	LFT
0310	808-12666	LINE, PREFORMED PLASTIC, SOLID, WHITE, 10 IN.	1245.00	LFT
0311	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	269.00	LFT
0312	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	8699.00	LFT
0313	808-12783	LINE, PREFORMED PLASTIC, BROKEN, BLACK, 6 IN.	398.00	LFT
0314	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	4018.00	LFT
0315	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	2943.00	LFT
0316	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	1139.00	LFT
0317	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	296.00	LFT
0318	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	881.00	LFT
0319	808-75994	PRISMATIC REFLECTOR	90.00	ACH
0320	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	866.00	ACH
0321	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1538.00	ACH
0322	808-99077	LINE, PREFORMED PLASTIC, SOLID, WHITE, 24 IN.	160.00	LFT

Call: 181

Contract: R -43813-A

Section No.: 1 MEDIAN CONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	15.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	15.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0015	202-02273	CENTER CURB, CONCRETE, REMOVE	21.00	SYS
0016	202-07003	REMOVE	1.00	LS
0017	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	9.00	EACH
0018	203-02000	EXCAVATION, COMMON	4795.00	CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	9675.00	DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0021	205-12618	SWQCP PREPARATION	1.00	LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	3473.00	SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	5900.00	SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	3012.00	CYS
0025	214-11796	GEOGRID, TYPE IB	4618.00	SYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	1758.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	466.00	CYS
0028	303-01180	COMPACTED AGGREGATE, NO. 53	247.00	TON
0029	304-07494	WIDENING WITH HMA, TYPE C	290.00	TON
0030	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	66.00	TON
0031	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	1095.00	TON

0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	17020.00	SYS
0033	306-08432	MILLING, APPROACH	153.00	SYS
0034	306-11872	MILLING, PROFILE	1042.00	SYS
0035	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	1667.00	TON
0036	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	436.00	TON
0037	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	1166.00	TON
0038	401-000067	QC/QA-HMA, 4, 58E, INTERMEDIATE, OG, 19.0 mm	428.00	TON
0039	401-11526	JOINT ADHESIVE	7906.00	LFT
0040	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	7906.00	LFT
0041	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0042	604-06070	SIDEWALK, CONCRETE	1834.00	SYS
0043	604-08086	CURB RAMP, CONCRETE	277.00	SYS
0044	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0045	605-06120	CURB, CONCRETE	4142.00	LFT
0046	605-06140	CURB AND GUTTER, CONCRETE	4352.00	LFT
0047	605-06205	CENTER CURB, CONCRETE, TYPE B	76.00	LFT
0048	605-06255	CENTER CURB, CONCRETE, TYPE D	52.00	SYS
0049	605-06255	CENTER CURB, CONCRETE, TYPE D	883.00	SYS
0050	610-07487	HMA FOR APPROACHES, TYPE B	245.00	TON
0051	610-09108	PCCP FOR APPROACHES, 9 IN.	2737.00	SYS
0052	611-02825	MAILBOX ASSEMBLY, TRIPLE	1.00	ACH
0053	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	ACH
0054	621-06567	WATER	28.00	KGAL
0055	621-06575	SODDING, NURSERY	6828.00	SYS
0056	628-12683	FIELD OFFICE, TYPE D	20.00	MOS
0057	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	6828.00	SYS
0058	629-000150	TOPSOIL AMENDMENT BUDGET	13656.00	DOL
0059	702-51863	FIELD DRILLED HOLE IN CONCRETE	6.00	ACH
0060	715-01902	WATER SERVICE LINE, 2 IN.	370.00	LFT
0061	715-02745	GATE VALVE WITH VALVE BOX, 8 IN.	8.00	ACH
0062	715-03053	METER PIT	1.00	ACH
0063	715-04965	WATER SERVICE LINE	215.00	LFT
0064	715-04965	WATER SERVICE LINE	10.00	LFT
0065	715-04965	WATER SERVICE LINE	5.00	LFT
0066	715-04995	LINE STOP	2.00	ACH
0067	715-04995	LINE STOP	1.00	ACH
0068	715-04995	LINE STOP	1.00	ACH

0069	715-04995	LINE STOP	2.00	ACH
0070	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	3997.00	LFT
0071	715-05061	WATER SERVICE LINE, 6 IN.	55.00	LFT
0072	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1458.00	LFT
0073	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	206.00	LFT
0074	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	464.00	LFT
0075	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	250.00	LFT
0076	715-05159	PIPE, TYPE 2, CIRCULAR, DIAMETER 42 IN.	95.00	LFT
0077	715-05408	PIPE, SANITARY SEWER, DIAMETER 8 IN.	64.00	LFT
0078	715-05409	PIPE, SANITARY SEWER, DIAMETER 10 IN.	44.00	LFT
0079	715-05411	PIPE, SANITARY SEWER, DIAMETER 12 IN.	98.00	LFT
0080	715-05712	PIPE, SANITARY SEWER, DIAMETER 16 IN.	32.00	LFT
0081	715-06050	CAP	10.00	ACH
0082	715-11896	WATER SERVICE CONNECTION	16.00	ACH
0083	715-11896	WATER SERVICE CONNECTION	1.00	ACH
0084	715-11896	WATER SERVICE CONNECTION	2.00	ACH
0085	715-11896	WATER SERVICE CONNECTION	1.00	ACH
0086	715-12674	GATE VALVE AND VALVE BOX, 12 IN.	12.00	ACH
0087	715-90714	PIPE PVC, 12 IN.	1930.00	LFT
0088	715-90853	TAPPING SLEEVE WITH VALVE	1.00	ACH
0089	715-93913	WATER MAIN, 8 IN.	105.00	LFT
0090	715-93913	WATER MAIN, 8 IN.	545.00	LFT
0091	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	3371.00	SYS
0092	718-52610	AGGREGATE FOR UNDERDRAINS	374.00	CYS
0093	720-01092	MANHOLE, TYPE J15, MODIFIED	10.00	ACH
0094	720-04467	INLET, TYPE C5	2.00	ACH
0095	720-08660	MANHOLE, TYPE J5, MODIFIED	1.00	ACH
0096	720-44015	CASTING, TYPE 2, FURNISH AND ADJUST TO GRADE	1.00	ACH
0097	720-45030	INLET, TYPE E7	3.00	ACH
0098	720-45065	INLET, TYPE N12	1.00	ACH
0099	720-45135	INLET, TYPE F7, MODIFIED	1.00	ACH
0100	720-45410	MANHOLE, TYPE C4	7.00	ACH
0101	720-90984	MANHOLE, TYPE C2	1.00	ACH
0102	720-94612	MANHOLE, TYPE K4	2.00	ACH
0103	720-95422	MANHOLE, TYPE J4	4.00	ACH
0104	720-96999	FIRE HYDRANT ASSEMBLY	5.00	ACH
0105	720-96999	FIRE HYDRANT ASSEMBLY	5.00	ACH

0106	720-96999	FIRE HYDRANT ASSEMBLY	3.00	ACH
0107	720-98174	INLET, TYPE B15	18.00	ACH
0108	720-98555	INLET, TYPE C15	20.00	ACH
0109	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	ACH
0110	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	34370.00	LFT
0111	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	72.00	ACH
0112	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00	ACH
0113	801-06640	CONSTRUCTION SIGN, TYPE A	56.00	ACH
0114	801-06645	CONSTRUCTION SIGN, TYPE B	41.00	ACH
0115	801-06775	MAINTAINING TRAFFIC	1.00	LS
0116	801-07119	BARRICADE, TYPE III-B	240.00	LFT
0117	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	ACH
0118	801-12324	LAW ENFORCEMENT OFFICER	500.00	HRS
0119	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	60.00	LFT
0120	801-12863	AUDIBLE INFORMATION DEVICE	4.00	ACH
0121	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	ACH
0122	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	5.00	ACH
0123	805-01842	HANDHOLE, SIGNAL, TYPE 1	7.00	ACH
0124	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	86.00	LFT
0125	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	12.00	ACH
0126	805-02383	CONDUIT, STEEL, GALVANIZED, 2.5 IN.	1689.00	LFT
0127	805-02445	CONTROLLER AND CABINET, TYPE P1	1.00	ACH
0128	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	3.00	ACH
0129	805-02658	CABLE COAXIAL	10.00	LFT
0130	805-03965	CONDUIT, PVC, 2.50 IN. SCHEDULE 80	3077.00	LFT
0131	805-05405	SIGNAL POLE, PEDESTAL, 4 FT	3.00	ACH
0132	805-11817	PEDESTRIAN PUSH BUTTON, APS	12.00	ACH
0133	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	17.00	ACH
0134	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	6.00	ACH
0135	805-78230	TRAFFIC SIGNAL HEAD, NO. 5 SECTION, 12 IN.	3.00	ACH
0136	805-78420	DISCONNECT HANGER	8.00	ACH
0137	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	8736.00	LFT
0138	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1480.00	LFT
0139	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1036.00	LFT
0140	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	161.00	LFT
0141	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	572.00	LFT
0142	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	8531.00	LFT

0143	805-78785	SIGNAL DETECTOR HOUSING	25.00	ACH
0144	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2496.00	LFT
0145	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00	ACH
0146	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	5.00	ACH
0147	807-02191	HANDHOLE, LIGHTING	8.00	ACH
0148	807-03758	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. X 24 IN. X 96 IN.	28.00	ACH
0149	807-86805	SERVICE POINT, TYPE I	2.00	ACH
0150	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	1434.00	LFT
0151	808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	414.00	LFT
0152	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0153	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	31.00	LFT
0154	808-12032	GROOVING FOR PAVEMENT MARKINGS	13230.00	LFT
0155	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	263.00	LFT
0156	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	4600.00	LFT
0157	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	6750.00	LFT
0158	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	14.00	LFT
0159	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	44.00	ACH
0160	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	194.00	LFT
0161	808-96016	LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN.	181.00	LFT
0162	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	1120.00	LFT
0163	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	91.00	LFT

Call: 191

Contract: R -43843-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	280.00	CYS
0013	205-11626	PUMP AROUND	5.00	EACH
0014	205-12108	STORMWATER MANAGEMENT BUDGET	19519.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	613.00	SYS
0017	211-09265	STRUCTURE BACKFILL, TYPE 2	1322.00	CYS
0018	214-11796	GEOGRID, TYPE IB	314.00	SYS
0019	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	613.00	SYS
0020	301-12233	COMPACTED AGGREGATE, NO. 8	91.00	CYS
0021	303-01180	COMPACTED AGGREGATE, NO. 53	47.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	403.00	SYS
0023	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	69.00	TON
0024	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	60.00	TON
0025	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	145.00	TON
0026	401-11526	JOINT ADHESIVE	330.00	LFT
0027	406-05521	ASPHALT FOR TACK COAT	1266.00	SYS
0028	601-06035	GUARDRAIL, RESET	150.00	LFT
0029	603-06060	FENCE, FARM FIELD, RESET	100.00	LFT
0030	615-06490	RIGHT-OF-WAY MARKER	23.00	EACH
0031	615-06505	MONUMENT, TYPE B	2.00	EACH

0032	616-05688	RIPRAP, CLASS 1	588.00 TON
0033	616-06405	RIPRAP, REVETMENT	669.00 TON
0034	616-06451	RIPRAP, UNIFORM	148.00 TON
0035	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1481.00 SYS
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00 EACH
0037	621-06559	MULCHED SEEDING, TYPE R	9087.00 SYS
0038	628-09403	FIELD OFFICE, TYPE C	12.00 MOS
0039	714-000086	WATERPROOFING MEMBRANE, TYPE 2	7088.00 SFT
0040	715-11347	CONCRETE ANCHOR, DIAMETER 132 IN.	2.00 EACH
0041	715-12341	PIPE, TYPE 1, CIRCULAR, DIAMETER 132 IN.	188.00 LFT
0042	725-10245	PERPETUATION, EXISTING PIPE	2.00 EACH
0043	725-11039	LINER PIPE, THERMOPLASTIC, CIRCULAR, 19.6-19.7 SFT	1221.00 LFT
0044	725-11795	LINER PIPE, THERMOPLASTIC, CIRCULAR, 49.2-50.3 SFT	103.00 LFT
0045	725-11985	LINER PIPE, THERMOPLASTIC, CIRCULAR, 62.3-63.7 SFT	272.33 LFT
0046	725-12321	PIPE LINER, CURED-IN-PLACE, MIN. AREA 42.4 SFT	103.00 LFT
0047	801-03291	CONSTRUCTION SIGN, TYPE D	8.00 EACH
0048	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00 EACH
0049	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00 EACH
0050	801-06640	CONSTRUCTION SIGN, TYPE A	73.00 EACH
0051	801-06645	CONSTRUCTION SIGN, TYPE B	3.00 EACH
0052	801-06775	MAINTAINING TRAFFIC	1.00 LS
0053	801-07118	BARRICADE, TYPE III-A	168.00 LFT
0054	801-07119	BARRICADE, TYPE III-B	120.00 LFT
0055	801-12042	TRUCK MOUNTED ATTENUATOR	14.00 DAY
0056	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	4.00 EACH
0057	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	330.00 LFT
0058	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	330.00 LFT

Call: 201

Contract: R -43844-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	61.00	SYS
0014	202-90277	DETECTOR HOUSING, REMOVE	18.00	EACH
0015	203-02000	EXCAVATION, COMMON	19.00	CYS
0016	203-08607	LINEAR GRADING	818.00	LFT
0017	205-11626	PUMP AROUND	2.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	3560.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	792.00	SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	48.00	CYS
0022	214-11796	GEOGRID, TYPE IB	760.00	SYS
0023	303-01180	COMPACTED AGGREGATE, NO. 53	1235.00	TON
0024	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	586.00	TON
0025	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	311.00	TON
0026	306-08036	MILLING, ASPHALT, 2 IN.	92184.00	SYS
0027	306-08432	MILLING, APPROACH	8661.00	SYS
0028	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	9781.00	TON
0029	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0030	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	49635.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	39.00	TON

0032	509-12191	JOINT REPAIR, PARTIAL DEPTH	9.00	SFT
0033	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	41817.00	LFT
0034	610-07488	HMA FOR APPROACHES, TYPE C	966.00	TON
0035	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	4.00	EACH
0036	615-06520	MONUMENT, RE-ESTABLISH	46.00	EACH
0037	616-05688	RIPRAP, CLASS 1	29.00	TON
0038	616-06405	RIPRAP, REVETMENT	9.80	TON
0039	616-06451	RIPRAP, UNIFORM	6.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	58.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0042	621-02770	EROSION CONTROL BLANKET	60.60	SYS
0043	621-06559	MULCHED SEEDING, TYPE R	284.20	SYS
0044	628-09403	FIELD OFFICE, TYPE C	9.00	MOS
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0046	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	57.00	LFT
0047	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	88.00	LFT
0048	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	21.30	TON
0049	720-44080	CASTING, TYPE 15, FURNISH AND ADJUST TO GRADE	1.00	EACH
0050	725-11300	PIPE LINER, CURED-IN-PLACE, MIN. AREA 8.9 SFT	152.00	LFT
0051	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0052	801-06206	TEMPORARY PAVEMENT MARKING, 6 IN.	10970.00	LFT
0053	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	10970.00	LFT
0054	801-06640	CONSTRUCTION SIGN, TYPE A	44.00	EACH
0055	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07118	BARRICADE, TYPE III-A	240.00	LFT
0058	801-12042	TRUCK MOUNTED ATTENUATOR	23.00	DAY
0059	801-12324	LAW ENFORCEMENT OFFICER	150.00	HRS
0060	801-92448	CONSTRUCTION SIGNS MOBILE	120.00	DAY
0061	804-11920	DELINEATOR POST, FLEXIBLE, TYPE I	4.00	EACH
0062	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	5410.00	LFT
0063	805-78785	SIGNAL DETECTOR HOUSING	18.00	EACH
0064	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1835.00	LFT
0065	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0066	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 12 IN.	258.00	LFT
0067	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	207.00	LFT
0068	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	49451.00	LFT

0069	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	274.00	LFT
0070	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	371.00	LFT
0071	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	27513.00	LFT
0072	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	22.00	EACH
0073	808-10097	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 27 IN.	70.00	LFT
0074	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	977.00	LFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	82720.00	LFT
0076	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	172.00	LFT
0077	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	1544.00	LFT
0078	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	3090.00	LFT
0079	808-12859	LINE, MULTI-COMPONENT, SOLID, YELLOW, 10 IN.	628.00	LFT
0080	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	19.00	EACH
0081	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	284.00	EACH

Call: 211

Contract: R -43848-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	160.00	SYS
0013	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0014	203-02000	EXCAVATION, COMMON	130.00	CYS
0015	205-11626	PUMP AROUND	3.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	4148.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	58.00	SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	643.00	SYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	261.00	CYS
0021	211-09268	STRUCTURE BACKFILL, TYPE 5	18.00	CYS
0022	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	287.00	SYS
0023	301-12234	COMPACTED AGGREGATE, NO. 53	10.00	CYS
0024	303-01180	COMPACTED AGGREGATE, NO. 53	180.00	TON
0025	304-07789	WIDENING WITH HMA, TYPE D	108.00	TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	596.00	SYS
0027	401-000009	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm	100.00	TON
0028	401-000045	QC/QA-HMA, 4, 58E, INTERMEDIATE, 19.0 mm	57.00	TON
0029	401-000048	QC/QA-HMA, 4, 58S, BASE, 25.0 mm	233.00	TON
0030	401-11526	JOINT ADHESIVE	869.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	1708.00	SYS

0032	601-05586	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 9	1.00	ACH
0033	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	144.00	LFT
0034	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	2.00	ACH
0035	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00	ACH
0036	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	ACH
0037	610-07487	HMA FOR APPROACHES, TYPE B	13.00	TON
0038	615-06490	RIGHT-OF-WAY MARKER	7.00	ACH
0039	615-06505	MONUMENT, TYPE B	3.00	ACH
0040	616-05688	RIPRAP, CLASS 1	262.00	TON
0041	616-05689	RIPRAP, CLASS 2	51.00	TON
0042	616-06405	RIPRAP, REVETMENT	39.00	TON
0043	616-06451	RIPRAP, UNIFORM	66.00	TON
0044	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	327.00	SYS
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	ACH
0046	621-02770	EROSION CONTROL BLANKET	583.00	SYS
0047	621-06559	MULCHED SEEDING, TYPE R	692.00	SYS
0048	621-12612	SEED MIXTURE, FLOODPLAIN	2.00	LBS
0049	621-52448	SIGN, 'DO NOT SPRAY'	4.00	ACH
0050	628-09403	FIELD OFFICE, TYPE C	15.00	MOS
0051	702-51015	CONCRETE, B, FOOTINGS	64.70	CYS
0052	703-06028	REINFORCING BARS	14136.00	LBS
0053	714-000086	WATERPROOFING MEMBRANE, TYPE 2	2016.00	SFT
0054	714-11179	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 6 FT	84.00	LFT
0055	725-11295	PIPE LINER, CURED-IN-PLACE, 54 IN.	491.00	LFT
0056	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	ACH
0057	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00	ACH
0058	801-06640	CONSTRUCTION SIGN, TYPE A	46.00	ACH
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07118	BARRICADE, TYPE III-A	96.00	LFT
0061	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0062	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0063	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	47.50	LFT
0064	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	3.50	SFT
0065	802-91122	SIGN, GROUND MOUNTED, RESET	6.00	ACH
0066	804-11920	DELINEATOR POST, FLEXIBLE, TYPE I	4.00	ACH
0067	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	539.00	LFT
0068	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	539.00	LFT

Call: 221

Contract: R -43895-A

Section No.: 1 HMA OVERLAY, PREVENTATIVE MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-12976	RAILROAD FLAGGING BUDGET	5000.00	DOL
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02271	HEADWALL, REMOVE	6.00	EACH
0014	202-93741	GUARDRAIL END TREATMENT, REMOVE	6.00	EACH
0015	202-96133	PIPE, REMOVE	128.00	LFT
0016	203-02000	EXCAVATION, COMMON	383.00	CYS
0017	203-02070	BORROW	88.00	CYS
0018	203-08607	LINEAR GRADING	2364.00	LFT
0019	205-11626	PUMP AROUND	5.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	358.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	4384.00	SYS
0023	207-08266	SUBGRADE TREATMENT, TYPE III	1423.00	SYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	53.00	CYS
0025	214-11796	GEOGRID, TYPE IB	4384.00	SYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	474.00	TON
0027	303-07449	COMPACTED AGGREGATE, NO. 73	3561.00	TON
0028	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	3356.00	TON
0029	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	2010.00	TON
0030	306-08036	MILLING, ASPHALT, 2 IN.	130008.00	SYS
0031	306-08039	MILLING, ASPHALT REMOVAL	1707.00	SYS

0032	306-08432	MILLING, APPROACH	1396.00	SYS
0033	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	14301.00	TON
0034	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	39717.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	45.00	TON
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.50	TON
0037	601-01700	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 1	1.00	ACH
0038	601-02241	GUARDRAIL, REMOVE	953.00	LFT
0039	601-06035	GUARDRAIL, RESET	951.00	LFT
0040	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	733.00	LFT
0041	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	1.00	ACH
0042	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	5.00	ACH
0043	601-94689	GUARDRAIL END TREATMENT, TYPE OS	5.00	ACH
0044	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	102381.00	LFT
0045	610-07487	HMA FOR APPROACHES, TYPE B	154.00	TON
0046	616-06405	RIPRAP, REVETMENT	49.00	TON
0047	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	118.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0049	621-06559	MULCHED SEEDING, TYPE R	493.00	SYS
0050	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	ACH
0052	714-96273	HEADWALL RECONSTRUCT	1.00	LS
0053	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	67.00	LFT
0054	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	61.00	LFT
0055	715-08283	PCCP FOR STRUCTURE INSTALLATION	78.00	SYS
0056	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	74.00	TON
0057	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	ACH
0058	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00	ACH
0059	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00	ACH
0060	801-06640	CONSTRUCTION SIGN, TYPE A	56.00	ACH
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, TYPE III-A	178.00	LFT
0063	801-07119	BARRICADE, TYPE III-B	200.00	LFT
0064	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	117.00	LFT
0065	802-07060	SIGN, SHEET, RELOCATE	1.00	ACH
0066	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	26.00	SFT
0067	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	81.00	SFT
0068	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	7.80	SFT

0069	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	1.00	ACH
0070	805-02389	SIGNAL CABLE, LOOP DETECTOR LEAD-IN, COPPER, 2C/14 GAUGE	76.00	LFT
0071	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	689.00	LFT
0072	805-78785	SIGNAL DETECTOR HOUSING	2.00	ACH
0073	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	251.00	LFT
0074	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0075	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	69256.00	LFT
0076	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	11874.00	LFT
0077	808-12032	GROOVING FOR PAVEMENT MARKINGS	88728.00	LFT
0078	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	7598.00	LFT
0079	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	76.00	LFT
0080	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	2.00	ACH
0081	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, 'ONLY'	1.00	ACH
0082	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, RXR	1.00	ACH
0083	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	421.00	ACH
0084	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	421.00	ACH

Call: 231

Contract: R -43908-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	205-12108	STORMWATER MANAGEMENT BUDGET	10797.00	DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0013	207-08264	SUBGRADE TREATMENT, TYPE II	350.00	SYS
0014	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	231.00	TON
0015	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	138.00	TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	14106.00	SYS
0017	306-08432	MILLING, APPROACH	1765.00	SYS
0018	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	1164.00	TON
0019	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	6152.00	LFT
0020	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0021	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0022	604-06070	SIDEWALK, CONCRETE	188.00	SYS
0023	604-08086	CURB RAMP, CONCRETE	283.00	SYS
0024	604-12083	DETECTABLE WARNING SURFACES	47.00	SYS
0025	605-06120	CURB, CONCRETE	72.00	LFT
0026	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	875.00	LFT
0027	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	768.00	LFT
0028	610-07487	HMA FOR APPROACHES, TYPE B	146.00	TON
0029	615-06490	RIGHT-OF-WAY MARKER	13.00	EACH
0030	615-06505	MONUMENT, TYPE B	2.00	EACH
0031	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH

0032	621-06560	MULCHED SEEDING, TYPE U	500.00	SYS
0033	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0034	720-12797	CASTING, INLET, ADJUST TO GRADE	4.00	EACH
0035	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	10.00	EACH
0036	720-44030	CASTING, TYPE 5, FURNISH AND ADJUST TO GRADE	8.00	EACH
0037	720-45615	STRUCTURE, INLET, RECONSTRUCTED	8.00	LFT
0038	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	3205.00	LFT
0039	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	65.00	LFT
0040	801-06640	CONSTRUCTION SIGN, TYPE A	114.00	EACH
0041	801-06645	CONSTRUCTION SIGN, TYPE B	49.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07119	BARRICADE, TYPE III-B	24.00	LFT
0044	801-11990	TEMPORARY CURB RAMP	34.00	EACH
0045	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	103.00	SYS
0046	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	1081.00	LFT
0047	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	50.00	LFT
0048	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	33.00	SFT
0049	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	2.00	EACH
0050	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	2.00	EACH
0051	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	881.00	LFT
0052	808-12032	GROOVING FOR PAVEMENT MARKINGS	8819.00	LFT
0053	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	2010.00	LFT
0054	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	6714.00	LFT
0055	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	212.00	LFT
0056	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	132.00	EACH
0057	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	132.00	EACH
0058	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	95.00	LFT

Call: 241

Contract: R -43920-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02637	PIPE ABANDON AND GROUT FILL	908.00	LFT
0013	202-91385	INLET, REMOVE	2.00	EACH
0014	202-96133	PIPE, REMOVE	171.00	LFT
0015	203-02000	EXCAVATION, COMMON	105.00	CYS
0016	203-08607	LINEAR GRADING	1108.00	LFT
0017	205-12108	STORMWATER MANAGEMENT BUDGET	30920.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	31.00	CYS
0020	303-01180	COMPACTED AGGREGATE, NO. 53	528.00	TON
0021	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	734.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	51627.00	SYS
0023	306-08043	MILLING, TRANSITION	889.00	SYS
0024	306-11872	MILLING, PROFILE	8766.00	SYS
0025	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	1146.00	TON
0026	401-000009	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm	4061.00	TON
0027	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	508.00	TON
0028	401-000045	QC/QA-HMA, 4, 58E, INTERMEDIATE, 19.0 mm	179.00	TON
0029	401-11526	JOINT ADHESIVE	43761.00	LFT
0030	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0031	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	43761.00	LFT

0032	401-12664	HMA SPRAY PAVER EMULSION	28.00 TON
0033	406-05520	ASPHALT FOR TACK COAT	7.00 TON
0034	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	14796.00 LFT
0035	616-06405	RIPRAP, REVETMENT	6.00 TON
0036	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	14.00 SYS
0037	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0038	621-06553	SEED MIXTURE, TYPE R	173.00 LBS
0039	628-09403	FIELD OFFICE, TYPE C	10.00 MOS
0040	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0041	715-01354	CLEAN EXISTING PIPE	881.00 LFT
0042	715-09064	VIDEO INSPECTION FOR PIPE	171.00 LFT
0043	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00 EACH
0044	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	171.00 LFT
0045	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3000.00 LFT
0046	718-09979	UNDERDRAIN OUTLET CLEANING	48.00 EACH
0047	720-45065	INLET, TYPE N12	2.00 EACH
0048	801-000138	SMART ARROW BOARD	300.00 DAY
0049	801-000209	CONNECTED WORK ZONE LOCATION MARKERS	4.00 EACH
0050	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	154516.00 LFT
0051	801-06640	CONSTRUCTION SIGN, TYPE A	57.00 EACH
0052	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	264.00 EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00 LS
0054	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00 EACH
0055	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3040.00 LFT
0056	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0057	801-12042	TRUCK MOUNTED ATTENUATOR	200.00 DAY
0058	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	4.00 EACH
0059	801-12594	DIGITAL SPEED LIMIT SIGN ASSEMBLY	6.00 EACH
0060	801-12956	TEMPORARY PAVEMENT MARKING, REMOVABLE, 10 IN.	1630.00 LFT
0061	808-06716	LINE, REMOVE	51491.00 LFT
0062	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0063	808-12032	GROOVING FOR PAVEMENT MARKINGS	52254.00 LFT
0064	808-12567	LINE, PREFORMED PLASTIC, SOLID, WHITE WITH BLACK TRIM, 6 IN.	339.00 LFT
0065	808-12568	LINE, PREFORMED PLASTIC, SOLID, YELLOW WITH BLACK TRIM, 6 IN.	339.00 LFT
0066	808-12667	LINE, THERMOPLASTIC, SOLID, WHITE, 10 IN.	1198.00 LFT
0067	808-12782	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 6 IN.	152.00 LFT
0068	808-12783	LINE, PREFORMED PLASTIC, BROKEN, BLACK, 6 IN.	85.00 LFT

0069	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	20459.00	LFT
0070	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	8663.00	LFT
0071	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	21019.00	LFT
0072	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	242.00	LFT
0073	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	313.00	LFT
0074	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	476.00	EACH
0075	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	316.00	EACH

Call: 251

Contract: R -43945-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0008	202-74035	SIGN, REMOVE	3.00	ACH
0009	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	21754.00	LFT
0010	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	16.00	ACH
0011	801-06640	CONSTRUCTION SIGN, TYPE A	20.00	ACH
0012	801-06645	CONSTRUCTION SIGN, TYPE B	4.00	ACH
0013	801-06775	MAINTAINING TRAFFIC	1.00	LS
0014	802-07058	SIGN, SHEET ASSEMBLY, RELOCATE	12.00	ACH
0015	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	68.00	SFT
0016	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00	SFT
0017	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	42.00	SFT
0018	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	5.00	ACH
0019	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0020	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	19.00	ACH
0021	805-01842	HANDHOLE, SIGNAL, TYPE 1	20.00	ACH
0022	805-02445	CONTROLLER AND CABINET, TYPE P1	3.00	ACH
0023	805-08244	CELLULAR MODEM KIT	3.00	ACH
0024	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	5.00	ACH
0025	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	5655.00	LFT
0026	805-11965	SOLAR POWERED FLASHING LED SIGN ASSEMBLY	1.00	ACH
0027	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	39.00	ACH
0028	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	9.00	ACH
0029	805-78415	SPAN, CATENARY, AND TETHER	20.00	ACH
0030	805-78420	DISCONNECT HANGER	17.00	ACH
0031	805-78445	SIGNAL SERVICE	5.00	ACH

0032	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	91.00	LFT
0033	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	8343.00	LFT
0034	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	2107.00	LFT
0035	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	506.00	LFT
0036	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	2259.00	LFT
0037	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	14699.00	LFT
0038	805-78785	SIGNAL DETECTOR HOUSING	28.00	EACH
0039	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2342.00	LFT
0040	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	2.00	EACH
0041	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	20.00	EACH
0042	805-92504	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 2 CHANNEL	5.00	EACH
0043	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	14.00	SYS
0044	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1826.00	LFT
0045	808-06716	LINE, REMOVE	4230.00	LFT
0046	808-12032	GROOVING FOR PAVEMENT MARKINGS	2643.00	LFT
0047	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	817.00	LFT
0048	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	491.00	LFT
0049	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	8.00	EACH
0050	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	56.00	EACH
0051	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	56.00	EACH

Call: 261

Contract: R -43956-A

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-12018	UTILITY PROTECTION	1.00	LS
0003	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00	EACH
0004	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	5.00	EACH
0005	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0006	109-08360	CONTRACT LIENS	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	2683.00	DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014	616-05689	RIPRAP, CLASS 2	7.00	TON
0015	616-06405	RIPRAP, REVETMENT	5.00	TON
0016	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	25.00	SYS
0017	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0018	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00	TON
0019	621-06554	SEED MIXTURE, TYPE U	25.00	LBS
0020	715-05122	PIPE, TYPE 1, CIRCULAR, DIAMETER 21 IN.	136.00	LFT
0021	715-46015	PIPE END SECTION, DIAMETER 21 IN.	2.00	EACH
0022	716-09631	PIPE INSTALLATION, TRENCHLESS, 21 IN.	136.00	LFT
0023	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	EACH
0024	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 271

Contract: R -43994-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	1378.00	SYS
0013	202-74035	SIGN, REMOVE	1.00	EACH
0014	202-93995	SIGNAL POLE FOUNDATION, REMOVE	4.00	EACH
0015	202-95579	SERVICE POINT, REMOVE	1.00	EACH
0016	203-02000	EXCAVATION, COMMON	127.00	CYS
0017	203-02070	BORROW	55.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	1900.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	192.00	SYS
0021	211-02050	B BORROW	2.00	CYS
0022	301-12234	COMPACTED AGGREGATE, NO. 53	337.00	CYS
0023	304-07493	WIDENING WITH HMA, TYPE B	60.00	TON
0024	306-11872	MILLING, PROFILE	3357.00	SYS
0025	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	284.00	TON
0026	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	278.00	TON
0027	401-11526	JOINT ADHESIVE	2836.00	LFT
0028	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0029	502-06329	PCCP, 12 IN.	200.00	SYS
0030	502-11564	PCCP, 7 IN.	438.00	SYS
0031	503-05240	D-1 CONTRACTION JOINT	400.00	LFT

0032	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	722.00	LFT
0033	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	277.00	LFT
0034	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1257.00	LFT
0035	615-06505	MONUMENT, TYPE B	4.00	EACH
0036	615-06510	MONUMENT, TYPE C	1.00	EACH
0037	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0038	621-03909	SEED MIXTURE, NATIVE	8.00	LBS
0039	621-06545	FERTILIZER FOR PERMANENT SEEDING	0.20	TON
0040	621-06553	SEED MIXTURE, TYPE R	15.00	LBS
0041	621-06565	MULCHING MATERIAL	0.30	TON
0042	621-06567	WATER	3.00	KGAL
0043	621-06570	TOPSOIL	36.00	CYS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0045	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0046	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	37.00	LFT
0047	718-06528	OUTLET PROTECTOR, TYPE 1	2.00	EACH
0048	801-03621	TEMPORARY ILLUMINATION	1.00	LS
0049	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0050	801-06201	TEMPORARY PANEL SIGNS	48.00	SFT
0051	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1214.00	LFT
0052	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	36.00	LFT
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	43.00	EACH
0054	801-06640	CONSTRUCTION SIGN, TYPE A	39.00	EACH
0055	801-06645	CONSTRUCTION SIGN, TYPE B	3.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0058	801-07118	BARRICADE, TYPE III-A	132.00	LFT
0059	801-07119	BARRICADE, TYPE III-B	24.00	LFT
0060	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	240.00	LFT
0061	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
0062	801-12081	PORTABLE SIGNAL	1.00	LS
0063	801-97643	TEMPORARY BUZZ STRIPS	432.00	LFT
0064	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	440.00	LFT
0065	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	142.00	SFT
0066	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	124.00	SFT
0067	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0068	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS

0069	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	630.00	LFT
0070	807-02191	HANDHOLE, LIGHTING	6.00	ACH
0071	807-03758	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. X 24 IN. X 96 IN.	5.00	ACH
0072	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	5.00	ACH
0073	807-85762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	5.00	ACH
0074	807-86810	SERVICE POINT, TYPE II	1.00	ACH
0075	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	16.00	SYS
0076	808-06716	LINE, REMOVE	4921.00	LFT
0077	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 24 IN.	275.00	LFT
0078	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	3798.00	LFT
0079	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	3534.00	LFT
0080	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	311.00	LFT
0081	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	72.00	LFT
0082	808-12700	LINE, MULTI-COMPONENT, DOTTED, WHITE, 12 IN.	133.00	LFT
0083	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	72.00	LFT
0084	808-75994	PRISMATIC REFLECTOR	15.00	ACH
0085	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	ACH
0086	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	137.00	ACH
0087	808-97323	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	216.00	LFT

Call: 275

Contract: R -44001-A

Section No.: 1 PAVEMENT REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	12315.00	SYS
0013	202-02278	CURB, CONCRETE, REMOVE	7200.00	LFT
0014	202-02928	CATCH BASIN, REMOVE	14.00	EACH
0015	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	25.00	CYS
0016	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	25.00	CYS
0017	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	25.00	CYS
0018	202-09243	REGULATED MATERIALS, DISPOSE, TYPE Z	25.00	CYS
0019	202-09244	REGULATED MATERIALS, REMOVE, TYPE Z	25.00	CYS
0020	202-09245	REGULATED MATERIALS, TRANSPORT, TYPE Z	25.00	CYS
0021	202-52710	SIDEWALK CONCRETE, REMOVE	5800.00	SYS
0022	202-91385	INLET, REMOVE	14.00	EACH
0023	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	24.00	EACH
0024	202-96133	PIPE, REMOVE	1110.00	LFT
0025	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	8.00	EACH
0026	203-02000	EXCAVATION, COMMON	5784.00	CYS
0027	203-02020	EXCAVATION, UNCLASSIFIED	250.00	CYS
0028	203-02070	BORROW	100.00	CYS
0029	205-12108	STORMWATER MANAGEMENT BUDGET	22320.00	DOL
0030	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0031	205-12618	SWQCP PREPARATION	1.00	LS

0032	207-08264	SUBGRADE TREATMENT, TYPE II	1107.00	SYS
0033	207-08266	SUBGRADE TREATMENT, TYPE III	3750.00	SYS
0034	207-09935	SUBGRADE TREATMENT, TYPE IC	25487.00	SYS
0035	211-09264	STRUCTURE BACKFILL, TYPE 1	16590.00	CYS
0036	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	250.00	CYS
0037	214-11796	GEOGRID, TYPE IB	869.00	SYS
0038	302-07455	DENSE GRADED SUBBASE	203.00	CYS
0039	303-01180	COMPACTED AGGREGATE, NO. 53	6302.00	TON
0040	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	675.00	TON
0041	306-08034	MILLING, ASPHALT, 1 1/2 IN.	110.00	SYS
0042	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	1909.00	TON
0043	401-000040	QC/QA-HMA, 2, 58H, INTERMEDIATE, 19.0 mm	3510.00	TON
0044	401-000055	QC/QA-HMA, 3, 58H, BASE, 19.0 mm	6640.00	TON
0045	401-11526	JOINT ADHESIVE	10790.00	LFT
0046	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	10790.00	LFT
0047	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	960.00	TON
0048	406-05520	ASPHALT FOR TACK COAT	19.70	TON
0049	604-05528	HMA FOR SIDEWALK	520.00	TON
0050	604-06070	SIDEWALK, CONCRETE	1843.00	SYS
0051	604-08086	CURB RAMP, CONCRETE	475.00	SYS
0052	604-12083	DETECTABLE WARNING SURFACES	80.00	SYS
0053	605-06120	CURB, CONCRETE	431.00	LFT
0054	605-06140	CURB AND GUTTER, CONCRETE	2812.00	LFT
0055	605-06140	CURB AND GUTTER, CONCRETE	3945.00	LFT
0056	605-06240	CENTER CURB, CONCRETE, TYPE A	20.00	SYS
0057	605-97937	CURB AND GUTTER, ROLLED CURB	175.00	LFT
0058	610-08446	PCCP FOR APPROACHES, 6 IN.	224.00	SYS
0059	610-09108	PCCP FOR APPROACHES, 9 IN.	866.00	SYS
0060	616-03096	RIVER ROCK	60.00	TON
0061	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0062	621-06545	FERTILIZER FOR PERMANENT SEEDING	0.10	TON
0063	621-06554	SEED MIXTURE, TYPE U	30.00	LBS
0064	621-06565	MULCHING MATERIAL	1.00	TON
0065	621-06567	WATER	16.00	kGAL
0066	621-06575	SODDING, NURSERY	3270.00	SYS
0067	628-09403	FIELD OFFICE, TYPE C	18.00	MOS
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	ACH

0069	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	3240.00	SYS
0070	629-000150	TOPSOIL AMENDMENT BUDGET	4120.00	DOL
0071	715-01354	CLEAN EXISTING PIPE	1110.00	LFT
0072	715-01383	INSERTION VALVE, 8 IN.	5.00	ACH
0073	715-01902	WATER SERVICE LINE, 2 IN.	668.00	LFT
0074	715-02743	GATE VALVE WITH VALVE BOX, 4 IN.	5.00	ACH
0075	715-02744	GATE VALVE WITH VALVE BOX, 6 IN.	17.00	ACH
0076	715-02745	GATE VALVE WITH VALVE BOX, 8 IN.	11.00	ACH
0077	715-02874	CURB STOP AND BOX	20.00	ACH
0078	715-02904	INSERTION VALVE, 4 IN.	3.00	ACH
0079	715-03053	METER PIT	17.00	ACH
0080	715-04750	CORPORATION STOP	20.00	ACH
0081	715-04836	GATE VALVE	10.00	ACH
0082	715-04965	WATER SERVICE LINE	100.00	LFT
0083	715-05146	PIPE, TYPE 2, CIRCULAR, DIAMETER 6 IN.	1640.00	LFT
0084	715-05148	PIPE, TYPE 2, CIRCULAR, DIAMETER 10 IN.	54.00	LFT
0085	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	2781.00	LFT
0086	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	370.00	LFT
0087	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	954.00	LFT
0088	715-05153	PIPE, TYPE 2, CIRCULAR, DIAMETER 21 IN.	70.00	LFT
0089	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	50.00	LFT
0090	715-05156	PIPE, TYPE 2, CIRCULAR, DIAMETER 30 IN.	20.00	LFT
0091	715-05408	PIPE, SANITARY SEWER, DIAMETER 8 IN.	210.00	LFT
0092	715-05409	PIPE, SANITARY SEWER, DIAMETER 10 IN.	224.00	LFT
0093	715-05411	PIPE, SANITARY SEWER, DIAMETER 12 IN.	2226.00	LFT
0094	715-05412	PIPE, SANITARY SEWER, DIAMETER 15 IN.	1366.00	LFT
0095	715-05413	PIPE, SANITARY SEWER, DIAMETER 18 IN.	338.00	LFT
0096	715-05711	PIPE, SANITARY SEWER, DIAMETER 6 IN.	280.00	LFT
0097	715-06039	INSERTION VALVE, 6 IN.	5.00	ACH
0098	715-08627	PIPE, TYPE 2, CIRCULAR, DIAMETER 4 IN.	200.00	LFT
0099	715-09064	VIDEO INSPECTION FOR PIPE	7400.00	LFT
0100	715-09228	INSERTION VALVE, 16 IN.	2.00	ACH
0101	715-09843	BYPASS PUMPING	1.00	LS
0102	715-11360	INSERTION VALVE 12 IN.	4.00	ACH
0103	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	1587.00	LFT
0104	715-12674	GATE VALVE AND VALVE BOX, 12 IN.	5.00	ACH
0105	715-40000	PIPE, SANITARY SEWER, DIAMETER 4 IN.	200.00	LFT

0106	715-90853	TAPPING SLEEVE WITH VALVE	1.00	ACH
0107	715-90853	TAPPING SLEEVE WITH VALVE	1.00	ACH
0108	715-90853	TAPPING SLEEVE WITH VALVE	6.00	ACH
0109	715-90853	TAPPING SLEEVE WITH VALVE	4.00	ACH
0110	715-90853	TAPPING SLEEVE WITH VALVE	1.00	ACH
0111	715-92544	WATER MAIN, DUCTILE IRON, 12 IN.	448.00	LFT
0112	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	679.00	LFT
0113	715-96629	WATER SERVICE LINE, 1 IN.	150.00	LFT
0114	715-96669	WATER MAIN, DUCTILE IRON, 16 IN.	2182.00	LFT
0115	715-98265	WATER MAIN, DUCTILE IRON, 4 IN.	474.00	LFT
0116	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	280.00	SYS
0117	718-52610	AGGREGATE FOR UNDERDRAINS	33.00	CYS
0118	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	8.00	ACH
0119	720-44080	CASTING, TYPE 15, FURNISH AND ADJUST TO GRADE	2.00	ACH
0120	720-45005	INLET, TYPE A2	3.00	ACH
0121	720-45030	INLET, TYPE E7	1.00	ACH
0122	720-45045	INLET, TYPE J10	47.00	ACH
0123	720-45055	INLET, TYPE M10	22.00	ACH
0124	720-45155	INLET, TYPE M10, MODIFIED	1.00	ACH
0125	720-45275	PIPE CATCH BASIN, 24 IN.	4.00	ACH
0126	720-45410	MANHOLE, TYPE C4	20.00	ACH
0127	720-45410	MANHOLE, TYPE C4	18.00	ACH
0128	720-45415	MANHOLE, TYPE D4	1.00	ACH
0129	720-96999	FIRE HYDRANT ASSEMBLY	8.00	ACH
0130	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	ACH
0131	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	42915.00	LFT
0132	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	775.00	LFT
0133	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	ACH
0134	801-06640	CONSTRUCTION SIGN, TYPE A	53.00	ACH
0135	801-06645	CONSTRUCTION SIGN, TYPE B	195.00	ACH
0136	801-06710	FLASHING ARROW SIGN	540.00	DAY
0137	801-06775	MAINTAINING TRAFFIC	1.00	LS
0138	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	6.00	ACH
0139	801-07119	BARRICADE, TYPE III-B	300.00	LFT
0140	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5850.00	LFT
0141	801-11990	TEMPORARY CURB RAMP	3.00	ACH
0142	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	360.00	LFT

0143	801-94295	SIGNAL HEAD RELOCATE	20.00	ACH
0144	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	401.00	LFT
0145	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	28.00	ACH
0146	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	217.44	SFT
0147	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	48.00	SFT
0148	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	148.53	SFT
0149	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	ACH
0150	805-01842	HANDHOLE, SIGNAL, TYPE 1	12.00	ACH
0151	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1080.00	LFT
0152	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	12.00	ACH
0153	805-02445	CONTROLLER AND CABINET, TYPE P1	2.00	ACH
0154	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	7.00	ACH
0155	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	5.00	ACH
0156	805-11374	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 20 FT	1.00	ACH
0157	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT	2.00	ACH
0158	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT	2.00	ACH
0159	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE A	5.00	ACH
0160	805-11385	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE E	1.00	ACH
0161	805-11393	SIGNAL CANTILEVER STRUCTURE, DUAL ARM 35 FT	1.00	ACH
0162	805-11817	PEDESTRIAN PUSH BUTTON, APS	12.00	ACH
0163	805-12016	UNINTERRUPTIBLE POWER SUPPLY	2.00	ACH
0164	805-12650	SIGNAL POLE, PEDESTAL, 5 FT	5.00	ACH
0165	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00	ACH
0166	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	4.00	ACH
0167	805-78230	TRAFFIC SIGNAL HEAD, NO. 5 SECTION, 12 IN.	3.00	ACH
0168	805-78445	SIGNAL SERVICE	2.00	ACH
0169	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	200.00	LFT
0170	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	5680.00	LFT
0171	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	795.00	LFT
0172	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	3835.00	LFT
0173	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	3000.00	LFT
0174	805-78785	SIGNAL DETECTOR HOUSING	10.00	ACH
0175	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1880.00	LFT
0176	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	2.00	ACH
0177	805-92504	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 2 CHANNEL	6.00	ACH
0178	807-02191	HANDHOLE, LIGHTING	6.00	ACH
0179	807-03950	LUMINAIRE, ORNAMENTAL	47.00	ACH

0180	807-03951	LIGHT POLE, ORNAMENTAL	47.00	ACH
0181	807-04866	LUMINAIRE	43.00	ACH
0182	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	935.00	LFT
0183	807-09637	WIRE, NO. 6 COPPER, IN PLASTIC DUCT, 4 1/C	10164.00	LFT
0184	807-11694	ILLUMINATED SIGN	4.00	ACH
0185	807-86805	SERVICE POINT, TYPE I	1.00	ACH
0186	807-86810	SERVICE POINT, TYPE II	2.00	ACH
0187	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	11280.00	LFT
0188	807-86915	CONNECTOR KIT, FUSED	47.00	ACH
0189	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	114.00	ACH
0190	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	5.00	ACH
0191	807-86930	INSULATION LINK, NON-WATERPROOFED	103.00	ACH
0192	807-86935	INSULATION LINK, WATERPROOFED	56.00	ACH
0193	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING, LOCATION IDENTIFICATION	47.00	ACH
0194	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1396.00	LFT
0195	808-06716	LINE, REMOVE	12600.00	LFT
0196	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0197	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	2071.00	LFT
0198	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	9104.00	LFT
0199	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	226.00	LFT
0200	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	691.00	LFT
0201	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	101.00	LFT
0202	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	30.00	ACH
0203	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, 'ONLY'	26.00	ACH
0204	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	714.00	LFT
0205	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	577.00	LFT

Call: 281

Contract: R -44328-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	205-11626	PUMP AROUND	1.00	ACH
0010	205-12108	STORMWATER MANAGEMENT BUDGET	3480.00	DOL
0011	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0012	615-06490	RIGHT-OF-WAY MARKER	6.00	ACH
0013	616-05688	RIPRAP, CLASS 1	66.00	TON
0014	616-06405	RIPRAP, REVETMENT	17.00	TON
0015	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	128.00	SYS
0016	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0017	621-06560	MULCHED SEEDING, TYPE U	757.00	SYS
0018	621-09867	MULCHED SEEDING	23.00	SYS
0019	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0020	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0021	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	3120.00	LFT
0022	801-06640	CONSTRUCTION SIGN, TYPE A	18.00	ACH
0023	801-06710	FLASHING ARROW SIGN	28.00	DAY
0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
0025	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY

Call: 291

Contract: R -45209-A

Section No.: 1 ROAD RECONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	3982.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	1224.00	LFT
0013	202-04650	PARKING METER	1000.00	≡ACH
0014	202-04650	PARKING METER	3.00	≡ACH
0015	202-04650	PARKING METER	22.00	≡ACH
0016	202-52710	SIDEWALK CONCRETE, REMOVE	1949.00	SYS
0017	202-91385	INLET, REMOVE	30.00	≡ACH
0018	202-93047	MANHOLE, REMOVE	3.00	≡ACH
0019	202-96133	PIPE, REMOVE	609.00	LFT
0020	202-96151	TRANSPORTATION OF SALVAGEABLE ITEMS	1.00	LS
0021	203-02000	EXCAVATION, COMMON	1490.00	CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	3140.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	3299.00	SYS
0026	207-09935	SUBGRADE TREATMENT, TYPE IC	16.00	SYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	149.00	CYS
0028	211-09268	STRUCTURE BACKFILL, TYPE 5	6.00	CYS
0029	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	990.00	SYS
0030	301-12231	COMPACTED AGGREGATE, NO. 2	340.00	CYS
0031	302-06464	SUBBASE FOR PCCP	825.00	CYS

0032	302-07455	DENSE GRADED SUBBASE	315.00	CYS
0033	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	150.00	TON
0034	305-95873	BRICK PAVEMENT, REMOVE AND SALVAGE	100.00	SYS
0035	306-08043	MILLING, TRANSITION	306.00	SYS
0036	402-07451	HMA WEDGE AND LEVEL, TYPE B	84.00	TON
0037	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	50.00	TON
0038	502-06457	PCCP, 9 IN.	3252.00	SYS
0039	502-06627	PCCP, 6 IN.	1890.00	SYS
0040	502-08204	PCCP, 12.5 IN.	41.00	SYS
0041	502-12313	PCCP, 5 IN.	166.00	SYS
0042	503-03489	RETROFITTED TIE BARS	267.00	EACH
0043	503-05240	D-1 CONTRACTION JOINT	1821.00	LFT
0044	604-04740	PAVERS	47868.00	SFT
0045	604-04740	PAVERS	3461.00	SFT
0046	604-06070	SIDEWALK, CONCRETE	51.00	SYS
0047	604-08086	CURB RAMP, CONCRETE	324.00	SYS
0048	604-12083	DETECTABLE WARNING SURFACES	35.00	SYS
0049	605-06120	CURB, CONCRETE	13.00	LFT
0050	605-06120	CURB, CONCRETE	648.00	LFT
0051	605-06120	CURB, CONCRETE	679.00	LFT
0052	605-06120	CURB, CONCRETE	35.00	LFT
0053	605-06120	CURB, CONCRETE	148.00	LFT
0054	605-06120	CURB, CONCRETE	94.00	LFT
0055	605-06121	CURB, CONCRETE, TYPE B	16.00	LFT
0056	605-06205	CENTER CURB, CONCRETE, TYPE B	15.00	LFT
0057	610-07487	HMA FOR APPROACHES, TYPE B	26.00	TON
0058	618-03812	BENCH	9.00	EACH
0059	618-04181	BICYCLE RACK	11.00	EACH
0060	618-97672	TRASH RECEPTACLE	5.00	EACH
0061	621-06570	TOPSOIL	150.00	CYS
0062	621-06570	TOPSOIL	23.00	CYS
0063	621-06570	TOPSOIL	524.00	CYS
0064	621-98038	MULCH, HARDWOOD SHREDDED BARK	41.00	CYS
0065	622-03948	PLANTER	10.00	EACH
0066	622-03948	PLANTER	22.00	EACH
0067	622-04648	TREE GRATE	14.00	EACH
0068	622-05605	PLANT, ANNUAL	616.00	EACH

0069	622-05652	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 3.5 IN.	17.00	EA
0070	622-05654	PLANT, PERENNIAL	258.00	EA
0071	622-05654	PLANT, PERENNIAL	135.00	EA
0072	622-05654	PLANT, PERENNIAL	12.00	EA
0073	622-05654	PLANT, PERENNIAL	448.00	EA
0074	628-09403	FIELD OFFICE, TYPE C	20.00	MOS
0075	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EA
0076	710-09158	PATCHING CONCRETE STRUCTURES	100.00	SFT
0077	714-000086	WATERPROOFING MEMBRANE, TYPE 2	1783.00	SFT
0078	714-000087	WATERPROOFING MEMBRANE, TYPE 3	5474.00	SFT
0079	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	1056.00	LFT
0080	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	528.00	LFT
0081	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	25.00	LFT
0082	715-08048	STORMWATER TREATMENT SYSTEM	2.00	EA
0083	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	15.00	TON
0084	715-09064	VIDEO INSPECTION FOR PIPE	631.00	LFT
0085	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	743.00	SYS
0086	718-52610	AGGREGATE FOR UNDERDRAINS	75.00	CYS
0087	720-03757	MANHOLE, TYPE C15	1.00	EA
0088	720-07309	TRENCH DRAIN	209.00	LFT
0089	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	EA
0090	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	EA
0091	720-45015	INLET, TYPE A8	1.00	EA
0092	720-45030	INLET, TYPE E7	1.00	EA
0093	720-45045	INLET, TYPE J10	2.00	EA
0094	720-45135	INLET, TYPE F7, MODIFIED	2.00	EA
0095	720-45250	CATCH BASIN, TYPE K10	1.00	EA
0096	720-45510	MANHOLE, TYPE C4, MODIFIED	3.00	EA
0097	720-95422	MANHOLE, TYPE J4	2.00	EA
0098	720-98174	INLET, TYPE B15	2.00	EA
0099	720-98555	INLET, TYPE C15	5.00	EA
0100	720-99417	CATCH BASIN, TYPE C15	1.00	EA
0101	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	EA
0102	801-03290	CONSTRUCTION SIGN, TYPE C	3.00	EA
0103	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EA
0104	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6235.00	LFT
0105	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00	EA

0106	801-06640	CONSTRUCTION SIGN, TYPE A	11.00	≡ACH
0107	801-06645	CONSTRUCTION SIGN, TYPE B	47.00	≡ACH
0108	801-06710	FLASHING ARROW SIGN	595.00	DAY
0109	801-06735	TUBULAR MARKER, PERMANENT	12.00	≡ACH
0110	801-06775	MAINTAINING TRAFFIC	1.00	LS
0111	801-07118	BARRICADE, TYPE III-A	177.00	LFT
0112	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	40.00	LFT
0113	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	600.00	LFT
0114	801-11990	TEMPORARY CURB RAMP	5.00	≡ACH
0115	801-12324	LAW ENFORCEMENT OFFICER	400.00	HRS
0116	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	76.00	LFT
0117	802-04089	SIGN, SHEET, REMOVE	3.00	≡ACH
0118	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	57.00	LFT
0119	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	64.00	SFT
0120	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	20.00	SFT
0121	802-11648	SIGN POST, TYPE	32.00	≡ACH
0122	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	≡ACH
0123	805-01842	HANDHOLE, SIGNAL, TYPE 1	6.00	≡ACH
0124	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0125	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	10.00	≡ACH
0126	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	7.00	≡ACH
0127	805-03083	CONDUIT, RIGID PVC, 1.50 IN.	221.00	LFT
0128	805-03972	CONDUIT, PVC, 1 IN. SCHEDULE 40	205.00	LFT
0129	805-04782	VIDEO VEHICLE DETECTOR SYSTEM	1.00	≡ACH
0130	805-04952	CONTROLLER AND CABINET	1.00	≡ACH
0131	805-05405	SIGNAL POLE, PEDESTAL, 4 FT	5.00	≡ACH
0132	805-08129	SIGNAL CABLE	181.00	LFT
0133	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	1644.00	LFT
0134	805-08244	CELLULAR MODEM KIT	1.00	≡ACH
0135	805-08487	BACKPLATE, SIGNAL	10.00	≡ACH
0136	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT	2.00	≡ACH
0137	805-11379	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 45 FT	1.00	≡ACH
0138	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE B	1.00	≡ACH
0139	805-11394	SIGNAL CANTILEVER STRUCTURE, DUAL ARM 40 FT	1.00	≡ACH
0140	805-11816	CONDUIT, RIGID FIBERGLASS, 2 IN.	1088.00	LFT
0141	805-11817	PEDESTRIAN PUSH BUTTON, APS	14.00	≡ACH
0142	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	5.00	≡ACH

0143	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	1.00	ACH
0144	805-78445	SIGNAL SERVICE	1.00	ACH
0145	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	16.00	LFT
0146	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1239.00	LFT
0147	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	2235.00	LFT
0148	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	193.00	LFT
0149	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	183.00	LFT
0150	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GAUGE	442.00	LFT
0151	805-78930	CONTROLLER CABINET FOUNDATION, TYPE M	1.00	ACH
0152	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00	ACH
0153	805-95568	CONDUIT, PVC, 4 IN.	565.00	LFT
0154	805-95568	CONDUIT, PVC, 4 IN.	111.00	LFT
0155	807-02194	SERVICE POINT, II, MODIFIED	1.00	ACH
0156	807-02819	LIGHTING RECEPTACLE, SINGLE, WATERPROOF	15.00	ACH
0157	807-08612	HANDHOLE, RECTANGULAR	15.00	ACH
0158	807-11712	WIRE, NO. 6 COPPER, 1/C	1434.00	LFT
0159	807-12184	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. DIAMETER X 72 IN.	16.00	ACH
0160	807-12354	METERED SERVICE POINT	1.00	ACH
0161	807-86843	WIRE, NO. 4 COPPER, 1/C	1146.00	LFT
0162	807-91704	LIGHT POLE, HANDHOLE COVER	15.00	ACH
0163	807-95888	WIRE, NO. 8 COPPER, 1/C	1443.00	LFT
0164	807-95889	WIRE, NO. 10 COPPER, 1/C	1465.00	LFT
0165	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	3.00	ACH
0166	808-06609	PAVEMENT MESSAGE MARKING	1.00	ACH
0167	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	199.00	LFT
0168	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1047.00	LFT
0169	808-06716	LINE, REMOVE	100.00	LFT
0170	808-09968	PAVEMENT MARKING	666.00	SFT
0171	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	20.00	LFT
0172	808-11493	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	112.00	LFT
0173	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE, 4 IN.	77.00	LFT
0174	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	84.00	LFT
0175	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	209.00	LFT
0176	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	56.00	LFT
0177	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	4.00	ACH
0178	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, 'ONLY'	1.00	ACH
0179	809-04969	SPLICE ENCLOSURE	1.00	ACH

Call: 301

Contract: R -45468-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	4.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0013	203-08607	LINEAR GRADING	100.00	LFT
0014	205-12108	STORMWATER MANAGEMENT BUDGET	990.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-08266	SUBGRADE TREATMENT, TYPE III	17.00	SYS
0017	211-09268	STRUCTURE BACKFILL, TYPE 5	11.00	CYS
0018	301-12231	COMPACTED AGGREGATE, NO. 2	41.00	CYS
0019	302-07455	DENSE GRADED SUBBASE	3.00	CYS
0020	303-01180	COMPACTED AGGREGATE, NO. 53	2100.00	TON
0021	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	219.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	20100.00	SYS
0023	306-08042	MILLING, SCARIFICATION	32.00	SYS
0024	306-08159	MILLING, ASPHALT	900.00	SYS
0025	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	1758.00	TON
0026	406-05520	ASPHALT FOR TACK COAT	5.80	TON
0027	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.50	TON
0028	506-06333	PCCP PATCHING, FULL DEPTH	17.00	SYS
0029	605-06140	CURB AND GUTTER, CONCRETE	30.00	LFT
0030	616-06405	RIPRAP, REVETMENT	33.00	TON
0031	621-06575	SODDING, NURSERY	180.00	SYS

0032	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0033	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	85.00	LFT
0034	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	15.00	TON
0035	720-44025	CASTING, TYPE 4, FURNISH AND ADJUST TO GRADE	1.00	EACH
0036	720-45005	INLET, TYPE A2	1.00	EACH
0037	801-06640	CONSTRUCTION SIGN, TYPE A	6.00	EACH
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-07119	BARRICADE, TYPE III-B	36.00	LFT
0040	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	56.00	LFT
0041	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	11.00	SFT
0042	808-06609	PAVEMENT MESSAGE MARKING	60.00	EACH
0043	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5660.00	LFT
0044	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	350.00	LFT
0045	808-75056	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 8 IN.	370.00	LFT
0046	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	6.00	EACH

Call: 321

Contract: R -45573-A

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02271	HEADWALL, REMOVE	3.00	≡ACH
0012	202-06542	RELOCATE	1.00	≡ACH
0013	203-02020	EXCAVATION, UNCLASSIFIED	663.00	CYS
0014	203-02070	BORROW	316.00	CYS
0015	205-11626	PUMP AROUND	1.00	≡ACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	8813.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	155.00	SYS
0019	211-09265	STRUCTURE BACKFILL, TYPE 2	73.00	CYS
0020	214-11796	GEOGRID, TYPE IB	155.00	SYS
0021	303-01180	COMPACTED AGGREGATE, NO. 53	39.00	TON
0022	304-07493	WIDENING WITH HMA, TYPE B	33.00	TON
0023	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	11.00	TON
0024	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	19.00	TON
0025	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	44.00	TON
0026	406-05521	ASPHALT FOR TACK COAT	398.00	SYS
0027	615-06490	RIGHT-OF-WAY MARKER	9.00	≡ACH
0028	615-06505	MONUMENT, TYPE B	2.00	≡ACH
0029	615-06510	MONUMENT, TYPE C	1.00	≡ACH
0030	616-05688	RIPRAP, CLASS 1	8.00	TON
0031	616-05689	RIPRAP, CLASS 2	53.00	TON

0032	616-06405	RIPRAP, REVETMENT	65.00 TON
0033	616-06451	RIPRAP, UNIFORM	52.00 TON
0034	616-12251	GEOTEXTILE FOR RIPRAP, TYPE 3	313.00 SYS
0035	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0036	621-06559	MULCHED SEEDING, TYPE R	379.00 SYS
0037	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0038	628-12683	FIELD OFFICE, TYPE D	8.00 MOS
0039	715-04555	PIPE END SECTION, MIN. AREA 5.1 SFT	2.00 EACH
0040	715-06398	CONCRETE ANCHOR, MIN. AREA 6.4 SFT	2.00 EACH
0041	715-08447	PIPE, TYPE 1, DEFORMED, MIN. AREA 5.1 SFT	41.00 LFT
0042	715-11774	PIPE, TYPE 1, DEFORMED, MIN. AREA 6.3 SFT	62.00 LFT
0043	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0044	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00 EACH
0045	801-06640	CONSTRUCTION SIGN, TYPE A	14.00 EACH
0046	801-06775	MAINTAINING TRAFFIC	1.00 LS
0047	801-07118	BARRICADE, TYPE III-A	48.00 LFT
0048	801-07119	BARRICADE, TYPE III-B	96.00 LFT
0049	801-12324	LAW ENFORCEMENT OFFICER	80.00 HRS
0050	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	48.00 LFT
0051	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	48.00 LFT

Call: 331

Contract: R -45752-A

Section No.: 1 SLIDE CORRECTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-96133	PIPE, REMOVE	127.00	LFT
0012	203-02020	EXCAVATION, UNCLASSIFIED	5390.00	CYS
0013	203-02588	LAGGING, PRECAST CONCRETE	1081.00	SYS
0014	203-02590	PIER, DRILL IN BEDROCK SOCKET	2494.00	LFT
0015	203-02592	PIER, NONFORMED, DRILL ABOVE BEDROCK SOCKET	1991.00	LFT
0016	205-12108	STORMWATER MANAGEMENT BUDGET	40438.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	81.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	256.00	SYS
0021	211-09266	STRUCTURE BACKFILL, TYPE 3	2200.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	46.00	CYS
0023	214-11796	GEOGRID, TYPE IB	81.00	SYS
0024	303-01180	COMPACTED AGGREGATE, NO. 53	205.00	TON
0025	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	47.00	TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2650.00	SYS
0027	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	219.00	TON
0028	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	39.00	TON
0029	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	60.00	TON
0030	401-11526	JOINT ADHESIVE	826.00	LFT
0031	405-05518	ASPHALT FOR PRIME COAT	81.00	SYS

0032	406-05521	ASPHALT FOR TACK COAT	309.00	SYS
0033	610-07487	HMA FOR APPROACHES, TYPE B	18.00	TON
0034	616-06405	RIPRAP, REVETMENT	1053.00	TON
0035	616-06451	RIPRAP, UNIFORM	761.00	TON
0036	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	3836.00	SYS
0037	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0038	628-12683	FIELD OFFICE, TYPE D	14.00	MOS
0039	711-51038	STRUCTURAL STEEL	1.00	LS
0040	715-05052	PIPE, TYPE 4, CIRCULAR, DIAMETER 12 IN.	816.00	LFT
0041	715-05118	PIPE, TYPE 1, CIRCULAR, DIAMETER 12 IN.	40.00	LFT
0042	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	127.00	LFT
0043	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0044	715-97122	PIPE, PVC, 2 IN.	315.00	LFT
0045	720-45030	INLET, TYPE E7	2.00	EACH
0046	732-11770	AGGREGATE FOR DRAINAGE FILL	310.00	CYS
0047	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0048	801-06625	DETOUR ROUTE MARKER ASSEMBLY	25.00	EACH
0049	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	EACH
0050	801-06775	MAINTAINING TRAFFIC	1.00	LS
0051	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0052	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0053	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0054	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1653.00	LFT
0055	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1130.00	LFT
0056	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	22.00	EACH
0057	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	22.00	EACH
0058	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	523.00	LFT

Call: 341

Contract: R -45966-A

Section No.: 1 PAVEMENT PATCHING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	207-08264	SUBGRADE TREATMENT, TYPE II	377.00	SYS
0010	214-000202	GEOGRID, TYPE IC	377.00	SYS
0011	302-06464	SUBBASE FOR PCCP	56.00	CYS
0012	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	154.00	TON
0013	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	2787.00	TON
0014	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	706.00	TON
0015	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	11027.00	LFT
0016	406-05520	ASPHALT FOR TACK COAT	5.26	TON
0017	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0018	503-03489	RETROFITTED TIE BARS	10.00	ACH
0019	503-05240	D-1 CONTRACTION JOINT	49.00	LFT
0020	506-06333	PCCP PATCHING, FULL DEPTH	221.00	SYS
0021	507-07480	PROFILING PCCP	590.00	SYS
0022	509-12191	JOINT REPAIR, PARTIAL DEPTH	3320.00	SFT
0023	509-12192	JOINT REPAIR, BOTTOM-HALF	830.00	SFT
0024	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0025	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	ACH
0026	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1238.00	LFT
0027	801-06640	CONSTRUCTION SIGN, TYPE A	53.00	ACH
0028	801-06710	FLASHING ARROW SIGN	70.00	DAY
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
0030	801-07118	BARRICADE, TYPE III-A	110.00	LFT
0031	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	ACH

0032	801-12042	TRUCK MOUNTED ATTENUATOR	70.00	DAY
0033	801-12324	LAW ENFORCEMENT OFFICER	456.00	HRS
0034	801-12652	QUEUE TRUCK	32.00	DAY
0035	801-12832	TEMPORARY SPEED FEEDBACK ASSEMBLY	1.00	EACH
0036	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	20.00	EACH
0037	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	2881.00	LFT
0038	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	12147.00	LFT
0039	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	228.00	LFT
0040	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	145.00	EACH

Call: 351

Contract: R -46022-A

Section No.: 1 PAVEMENT PATCHING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	3232.00	TON
0010	306-08036	MILLING, ASPHALT, 2 IN.	3650.00	SYS
0011	309-12695	LEAN CONCRETE BASE, 9 IN.	35.00	SYS
0012	401-000009	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm	402.00	TON
0013	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	3497.00	LFT
0014	406-05520	ASPHALT FOR TACK COAT	14.50	TON
0015	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0016	503-05240	D-1 CONTRACTION JOINT	12.00	LFT
0017	506-06333	PCCP PATCHING, FULL DEPTH	35.00	SYS
0018	507-07480	PROFILING PCCP	44.00	SYS
0019	509-12191	JOINT REPAIR, PARTIAL DEPTH	80.00	SFT
0020	509-12192	JOINT REPAIR, BOTTOM-HALF	27.00	SFT
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0022	628-12683	FIELD OFFICE, TYPE D	9.00	MOS
0023	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	3027.00	LFT
0024	801-06640	CONSTRUCTION SIGN, TYPE A	40.00	EACH
0025	801-06710	FLASHING ARROW SIGN	65.00	DAY
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0028	801-12042	TRUCK MOUNTED ATTENUATOR	65.00	DAY
0029	801-12324	LAW ENFORCEMENT OFFICER	780.00	HRS
0030	801-12652	QUEUE TRUCK	75.00	DAY
0031	801-12832	TEMPORARY SPEED FEEDBACK ASSEMBLY	1.00	EACH

0032	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	20.00	EACH
0033	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	4439.00	LFT
0034	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	17244.00	LFT
0035	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1906.00	LFT
0036	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	111.00	EACH

Call: 361

Contract: R -46152-A

Section No.: 1 IDIQ, PAVEMENT PATCHING

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	225000.00	DOL
0009	203-08607	LINEAR GRADING	1000.00	LFT
0010	207-08264	SUBGRADE TREATMENT, TYPE II	200.00	SYS
0011	207-09935	SUBGRADE TREATMENT, TYPE IC	200.00	SYS
0012	214-11796	GEOGRID, TYPE IB	100.00	SYS
0013	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	100.00	SYS
0014	301-12231	COMPACTED AGGREGATE, NO. 2	35.00	CYS
0015	302-06464	SUBBASE FOR PCCP	50.00	CYS
0016	303-01180	COMPACTED AGGREGATE, NO. 53	100.00	TON
0017	303-07449	COMPACTED AGGREGATE, NO. 73	100.00	TON
0018	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	400.00	TON
0019	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	200.00	TON
0020	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	1000.00	TON
0021	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	500.00	TON
0022	306-08036	MILLING, ASPHALT, 2 IN.	4000.00	SYS
0023	309-12695	LEAN CONCRETE BASE, 9 IN.	200.00	SYS
0024	401-000014	QC/QA-HMA, 3, 58H, SURFACE, 12.5 mm	200.00	TON
0025	401-000018	QC/QA-HMA, 4, 58E, SURFACE, 12.5 mm	200.00	TON
0026	401-11526	JOINT ADHESIVE	1500.00	LFT
0027	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	1500.00	LFT
0028	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0029	503-03489	RETROFITTED TIE BARS	75.00	EACH
0030	503-05240	D-1 CONTRACTION JOINT	108.00	LFT
0031	506-06333	PCCP PATCHING, FULL DEPTH	200.00	SYS

0032	506-06334	PCCP PATCHING, PARTIAL DEPTH	50.00	SYS
0033	507-07480	PROFILING PCCP	200.00	SYS
0034	507-08272	JOINTS IN PCCP, SAW AND SEAL	500.00	LFT
0035	509-12191	JOINT REPAIR, PARTIAL DEPTH	300.00	SFT
0036	509-12192	JOINT REPAIR, BOTTOM-HALF	50.00	SFT
0037	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2500.00	LFT
0038	801-06640	CONSTRUCTION SIGN, TYPE A	150.00	EACH
0039	801-06645	CONSTRUCTION SIGN, TYPE B	25.00	EACH
0040	801-06710	FLASHING ARROW SIGN	30.00	DAY
0041	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0042	801-12042	TRUCK MOUNTED ATTENUATOR	30.00	DAY
0043	801-12440	MAINTAINING TRAFFIC, IDIQ	225000.00	DOL
0044	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	16.00	EACH
0045	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	16.00	EACH
0046	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	1000.00	LFT
0047	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	1500.00	LFT
0048	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	5000.00	LFT
0049	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	5000.00	LFT
0050	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH

Call: 401

Contract: B -40892-A

Section No.: 1 BRIDGE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0013	202-74035	SIGN, REMOVE	1.00	EACH
0014	203-02000	EXCAVATION, COMMON	1180.00	CYS
0015	203-02070	BORROW	3440.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	47100.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51215	EXCAVATION, X	95.00	CYS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	385.00	CYS
0021	206-51235	COFFERDAM	1.00	LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	509.00	SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	2286.00	SYS
0024	211-02050	B BORROW	860.00	CYS
0025	211-06467	AGGREGATE FOR END BENT BACKFILL	52.00	CYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	6.00	CYS
0027	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	182.00	SYS
0028	301-12234	COMPACTED AGGREGATE, NO. 53	309.00	CYS
0029	302-06464	SUBBASE FOR PCCP	46.00	CYS
0030	303-01180	COMPACTED AGGREGATE, NO. 53	211.00	TON
0031	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	159.00	TON

0032	401-000037	QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	502.00	TON
0033	401-11526	JOINT ADHESIVE	1594.00	LFT
0034	406-05521	ASPHALT FOR TACK COAT	2462.00	SYS
0035	601-01701	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 2	1.00	EACH
0036	601-06037	GUARDRAIL END TREATMENT, TYPE I	3.00	EACH
0037	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	3.00	EACH
0038	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	1.00	EACH
0039	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	119.00	LFT
0040	603-03829	FENCE	227.00	LFT
0041	603-03829	FENCE	50.00	LFT
0042	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	182.00	SYS
0043	610-07487	HMA FOR APPROACHES, TYPE B	96.00	TON
0044	611-06497	MAILBOX ASSEMBLY, SINGLE	4.00	EACH
0045	615-06490	RIGHT-OF-WAY MARKER	14.00	EACH
0046	616-05688	RIPRAP, CLASS 1	856.00	TON
0047	616-06405	RIPRAP, REVETMENT	403.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	932.00	SYS
0049	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	502.00	SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0051	621-06559	MULCHED SEEDING, TYPE R	3226.00	SYS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0053	628-12683	FIELD OFFICE, TYPE D	18.00	MOS
0054	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	3226.00	SYS
0055	629-000150	TOPSOIL AMENDMENT BUDGET	6500.00	DOL
0056	701-02938	CORED HOLE IN ROCK, DIAMETER 24 IN.	60.00	LFT
0057	701-09739	PILE SHOE, HP 12 X 53	12.00	EACH
0058	701-51195	PILE, STEEL H, HP 12 X 53	264.00	LFT
0059	702-51005	CONCRETE, A, SUBSTRUCTURE	95.20	CYS
0060	702-51015	CONCRETE, B, FOOTINGS	90.80	CYS
0061	703-06028	REINFORCING BARS	28892.00	LBS
0062	703-06029	REINFORCING BARS, EPOXY COATED	65326.00	LBS
0063	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	30.00	EACH
0064	704-51002	CONCRETE, C, SUPERSTRUCTURE	211.50	CYS
0065	706-06344	RAILING, STEEL TYPE TS-1	350.00	LFT
0066	707-05983	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 36 IN. X 12 IN.	674.00	LFT
0067	709-51821	SURFACE SEAL	1.00	LS
0068	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	57.00	LFT

0069	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0070	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	130.00	SYS
0071	722-12732	LONGITUDINAL GROOVING	723.00	SYS
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	32.00	EACH
0074	801-06640	CONSTRUCTION SIGN, TYPE A	15.00	EACH
0075	801-06775	MAINTAINING TRAFFIC	1.00	LS
0076	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0077	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0078	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	28.00	LFT
0079	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	12.00	SFT
0080	802-91122	SIGN, GROUND MOUNTED, RESET	1.00	EACH

Call: 411

Contract: B -42792-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	213.00	SYS
0012	202-02272	PAVED SIDE DITCH, REMOVE	337.00	LFT
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0014	203-02000	EXCAVATION, COMMON	400.00	CYS
0015	203-02070	BORROW	80.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	21000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	22.00	CYS
0019	206-51235	COFFERDAM	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	184.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1098.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	22.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	57.00	CYS
0024	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	374.00	SYS
0025	301-12231	COMPACTED AGGREGATE, NO. 2	245.00	CYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	144.00	CYS
0027	302-06464	SUBBASE FOR PCCP	36.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	17.00	CYS
0029	303-01180	COMPACTED AGGREGATE, NO. 53	47.00	TON
0030	306-08034	MILLING, ASPHALT, 1 1/2 IN.	96.00	SYS
0031	306-08043	MILLING, TRANSITION	667.00	SYS

0032	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	95.00 TON
0033	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	100.00 TON
0034	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	394.00 TON
0035	401-11526	JOINT ADHESIVE	590.00 LFT
0036	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0037	503-12477	TERMINAL JOINT, TYPE HMA	59.00 LFT
0038	601-01704	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, MODIFIED	1.00 EACH
0039	601-02241	GUARDRAIL, REMOVE	404.00 LFT
0040	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	50.00 LFT
0041	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00 EACH
0042	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00 EACH
0043	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00 EACH
0044	602-06729	BARRIER DELINEATOR	22.00 EACH
0045	605-05523	CURB, HMA	219.00 LFT
0046	607-06175	GUTTER, CONCRETE, TYPE A	55.00 LFT
0047	607-06340	PAVED SIDE DITCH, TYPE B	133.00 LFT
0048	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	144.00 SYS
0049	610-07487	HMA FOR APPROACHES, TYPE B	42.00 TON
0050	610-08446	PCCP FOR APPROACHES, 6 IN.	94.00 SYS
0051	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00 EACH
0052	615-06490	RIGHT-OF-WAY MARKER	2.00 EACH
0053	615-06505	MONUMENT, TYPE B	2.00 EACH
0054	616-05688	RIPRAP, CLASS 1	248.00 TON
0055	616-06405	RIPRAP, REVETMENT	1480.00 TON
0056	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	2443.00 SYS
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0058	621-06560	MULCHED SEEDING, TYPE U	1212.00 SYS
0059	621-06567	WATER	3.00 KGAL
0060	621-06574	SODDING	58.00 SYS
0061	621-06575	SODDING, NURSERY	512.00 SYS
0062	628-09401	FIELD OFFICE, TYPE A	12.00 MOS
0063	702-51005	CONCRETE, A, SUBSTRUCTURE	12.00 CYS
0064	702-51863	FIELD DRILLED HOLE IN CONCRETE	72.00 EACH
0065	703-06029	REINFORCING BARS, EPOXY COATED	135375.00 LBS
0066	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00 EACH
0067	704-51002	CONCRETE, C, SUPERSTRUCTURE	391.00 CYS
0068	706-09960	RAILING, CONCRETE TYPE FC	728.00 LFT

0069	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	ACH
0070	709-51821	SURFACE SEAL	1.00	LS
0071	710-09158	PATCHING CONCRETE STRUCTURES	184.00	SFT
0072	711-51877	JACKING AND SUPPORTING BEAMS	1.00	LS
0073	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	170.00	LFT
0074	715-05327	PIPE, TYPE 2, DEFORMED, MIN. AREA 1.83 SFT	30.00	LFT
0075	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	120.00	LFT
0076	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	ACH
0077	715-46055	PIPE END SECTION, MIN. AREA 1.8 SFT	2.00	ACH
0078	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	54.00	SYS
0079	722-12732	LONGITUDINAL GROOVING	1132.00	SYS
0080	726-92406	BEARING ASSEMBLY, ELASTOMERIC	50.00	ACH
0081	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	ACH
0082	801-03291	CONSTRUCTION SIGN, TYPE D	4.00	ACH
0083	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	ACH
0084	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00	ACH
0085	801-06640	CONSTRUCTION SIGN, TYPE A	7.00	ACH
0086	801-06775	MAINTAINING TRAFFIC	1.00	LS
0087	801-07118	BARRICADE, TYPE III-A	60.00	LFT
0088	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0089	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	6.00	SFT
0090	802-76055	SIGN POST, TYPE A	10.00	LFT
0091	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1600.00	LFT
0092	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2170.00	LFT
0093	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	142.00	LFT

Call: 421

Contract: B -42951-A

Section No.: 1 SCOUR PROTECTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0010	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0011	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0012	203-51223	EXCAVATION, WATERWAY	73.00	CYS
0013	205-11626	PUMP AROUND	2.00	ACH
0014	205-12108	STORMWATER MANAGEMENT BUDGET	48065.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	206-51235	COFFERDAM	1.00	LS
0017	301-12234	COMPACTED AGGREGATE, NO. 53	18.00	CYS
0018	601-06035	GUARDRAIL, RESET	125.00	LFT
0019	601-09238	HAND DIG GUARDRAIL POST HOLES	20.00	ACH
0020	616-05688	RIPRAP, CLASS 1	715.00	TON
0021	616-05689	RIPRAP, CLASS 2	617.00	TON
0022	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1455.00	SYS
0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	ACH
0024	621-06559	MULCHED SEEDING, TYPE R	2068.00	SYS
0025	621-12612	SEED MIXTURE, FLOODPLAIN	3.00	LBS
0026	621-52448	SIGN, 'DO NOT SPRAY'	4.00	ACH
0027	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
0028	628-09409	MOBILE INTERNET SERVICE	8.00	MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0030	628-11977	COMPUTER SYSTEM	1.00	ACH
0031	713-04331	TEMPORARY CAUSEWAY	1.00	LS

0032	713-04509	TEMPORARY PIPE	1.00	LS
0033	801-03290	CONSTRUCTION SIGN, TYPE C	3.00	EACH
0034	801-03291	CONSTRUCTION SIGN, TYPE D	2.00	EACH
0035	801-06640	CONSTRUCTION SIGN, TYPE A	24.00	EACH
0036	801-06645	CONSTRUCTION SIGN, TYPE B	3.00	EACH
0037	801-06710	FLASHING ARROW SIGN	30.00	DAY
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH

Call: 431

Contract: B -43233-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0012	202-96133	PIPE, REMOVE	50.00	LFT
0013	203-02000	EXCAVATION, COMMON	655.00	CYS
0014	203-02070	BORROW	1060.00	CYS
0015	203-51223	EXCAVATION, WATERWAY	5.00	CYS
0016	204-02290	SETTLEMENT PLATE	1.00	EACH
0017	205-11626	PUMP AROUND	1.00	EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	19716.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1120.00	SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	64.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	368.00	CYS
0023	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	1126.00	SYS
0024	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	924.00	SYS
0025	301-12233	COMPACTED AGGREGATE, NO. 8	275.00	CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	718.00	TON
0027	304-07494	WIDENING WITH HMA, TYPE C	88.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1876.00	SYS
0029	306-08043	MILLING, TRANSITION	437.00	SYS
0030	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	268.00	TON
0031	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	150.00	TON

0032	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	388.00 TON
0033	401-11526	JOINT ADHESIVE	2689.00 LFT
0034	406-05520	ASPHALT FOR TACK COAT	3.00 TON
0035	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.20 TON
0036	601-02241	GUARDRAIL, REMOVE	554.00 LFT
0037	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	293.75 LFT
0038	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	2.00 ÷ACH
0039	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 ÷ACH
0040	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	550.00 LFT
0041	615-06490	RIGHT-OF-WAY MARKER	6.00 ÷ACH
0042	616-06405	RIPRAP, REVETMENT	323.00 TON
0043	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	520.00 SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 ÷ACH
0045	621-02770	EROSION CONTROL BLANKET	521.00 SYS
0046	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00 TON
0047	621-06553	SEED MIXTURE, TYPE R	203.00 LBS
0048	621-06565	MULCHING MATERIAL	2.00 TON
0049	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 ÷ACH
0050	628-12683	FIELD OFFICE, TYPE D	12.00 MOS
0051	701-09558	TEST PILE, INDICATOR, PRODUCTION	107.00 LFT
0052	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00 ÷ACH
0053	701-09683	PILE SHOE, HP 12 X 74	28.00 ÷ACH
0054	701-95780	PILE, STEEL H, HP 12 X 74	1125.00 LFT
0055	702-04325	TEMPORARY SHORING	1.00 LS
0056	702-51046	CONCRETE, FOUNDATION SEAL	15.00 CYS
0057	714-000086	WATERPROOFING MEMBRANE, TYPE 2	1967.00 SFT
0058	715-05173	PIPE, TYPE 3, CIRCULAR, DIAMETER 24 IN.	60.00 LFT
0059	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 ÷ACH
0060	723-000179	STRUCTURE, COATED REINFORCED CONCRETE, THREE-SIDED SECTIONS, 216 IN. X 120 IN.	52.00 LFT
0061	801-03291	CONSTRUCTION SIGN, TYPE D	1.00 ÷ACH
0062	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	4031.00 LFT
0063	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	43.00 LFT
0064	801-06640	CONSTRUCTION SIGN, TYPE A	18.00 ÷ACH
0065	801-06645	CONSTRUCTION SIGN, TYPE B	7.00 ÷ACH
0066	801-06775	MAINTAINING TRAFFIC	1.00 LS
0067	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	3.00 ÷ACH
0068	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	820.00 LFT

0069	801-12081	PORTABLE SIGNAL	1.00	LS
0070	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0071	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	4.00	EACH
0072	808-12032	GROOVING FOR PAVEMENT MARKINGS	1240.00	LFT
0073	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1100.00	LFT
0074	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH
0075	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	5.00	EACH
0076	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	140.00	LFT

Call: 441

Contract: B -43431-C

Section No.: 1 TRUSS CONSTRUCTION OR REPAIR

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0012	202-01845	CONDUIT, REMOVE	136.00	LFT
0013	202-02240	PAVEMENT REMOVAL	72.00	SYS
0014	202-12017	SIGNAL CABLE, REMOVE	1714.00	LFT
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0016	202-74035	SIGN, REMOVE	11.00	EACH
0017	202-86946	HANDHOLE, REMOVE	2.00	EACH
0018	202-90277	DETECTOR HOUSING, REMOVE	2.00	EACH
0019	202-95579	SERVICE POINT, REMOVE	1.00	EACH
0020	203-02000	EXCAVATION, COMMON	215.00	CYS
0021	203-02070	BORROW	1035.00	CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	21854.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	355.00	SYS
0025	211-06467	AGGREGATE FOR END BENT BACKFILL	2.00	CYS
0026	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	347.00	SYS
0027	302-06464	SUBBASE FOR PCCP	20.00	CYS
0028	303-01180	COMPACTED AGGREGATE, NO. 53	430.00	TON
0029	304-07493	WIDENING WITH HMA, TYPE B	26.00	TON
0030	306-08043	MILLING, TRANSITION	435.00	SYS
0031	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	66.00	TON

0032	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	34.00 TON
0033	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	78.00 TON
0034	401-11526	JOINT ADHESIVE	593.00 LFT
0035	406-05521	ASPHALT FOR TACK COAT	1220.00 SYS
0036	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00 TON
0037	601-01522	GUARDRAIL TRANSITION, TYPE TGB	1.00 EACH
0038	601-02241	GUARDRAIL, REMOVE	1137.00 LFT
0039	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	550.00 LFT
0040	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00 EACH
0041	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	3.00 EACH
0042	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 EACH
0043	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	13.00 LFT
0044	602-06729	BARRIER DELINEATOR	36.00 EACH
0045	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	74.00 SYS
0046	615-06505	MONUMENT, TYPE B	3.00 EACH
0047	616-06401	RIPRAP, DUMPED	442.00 TON
0048	616-06405	RIPRAP, REVETMENT	326.00 TON
0049	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	235.00 SYS
0050	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0051	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00 LS
0052	619-12506	CLEAN STEEL BRIDGE, TOP FLANGES, TYPE QP-2, BRIDGE NO.	1.00 LS
0053	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0055	621-02770	EROSION CONTROL BLANKET	3222.00 SYS
0056	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00 TON
0057	621-06553	SEED MIXTURE, TYPE R	49.00 LBS
0058	621-06567	WATER	1.00 kGAL
0059	621-06574	SODDING	74.00 SYS
0060	621-12612	SEED MIXTURE, FLOODPLAIN	34.00 LBS
0061	628-09403	FIELD OFFICE, TYPE C	20.00 MOS
0062	628-09409	MOBILE INTERNET SERVICE	20.00 MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0064	628-11977	COMPUTER SYSTEM	1.00 EACH
0065	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	26.00 EACH
0066	703-06029	REINFORCING BARS, EPOXY COATED	92392.00 LBS
0067	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	16.00 EACH
0068	704-01989	CONCRETE, C, SUPERSTRUCTURE, LIGHTWEIGHT	213.40 CYS

0069	704-51002	CONCRETE, C, SUPERSTRUCTURE	7.00	CYS
0070	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	4.00	ACH
0071	706-09962	RAILING, CONCRETE TYPE PF-1	1288.00	LFT
0072	706-11404	RAILING, STEEL TYPE PF-1	1304.00	LFT
0073	709-51821	SURFACE SEAL	1.00	LS
0074	710-09158	PATCHING CONCRETE STRUCTURES	810.00	SFT
0075	711-05395	REPLACE	2.00	ACH
0076	711-05395	REPLACE	5.00	ACH
0077	711-05395	REPLACE	10.00	ACH
0078	711-05395	REPLACE	48.00	ACH
0079	711-05395	REPLACE	28.00	ACH
0080	711-05395	REPLACE	38.00	ACH
0081	711-05395	REPLACE	34.00	ACH
0082	711-05395	REPLACE	1.00	ACH
0083	711-05728	REPAIR	6.00	ACH
0084	711-05728	REPAIR	2.00	ACH
0085	711-05728	REPAIR	37.00	ACH
0086	711-51035	STRUCTURAL STEEL	118845.00	LBS
0087	711-51864	DRILLED HOLE	8768.00	ACH
0088	711-51866	RIVET, REMOVE	6953.00	ACH
0089	711-96800	STUD SHEAR CONNECTORS	11856.00	ACH
0090	711-96899	BEAMS, RESET	1.00	LS
0091	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	26.00	ACH
0092	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	75.00	LFT
0093	726-11773	BEARING ASSEMBLY, RESET	1.00	ACH
0094	726-92406	BEARING ASSEMBLY, ELASTOMERIC	2.00	ACH
0095	801-03290	CONSTRUCTION SIGN, TYPE C	4.00	ACH
0096	801-03291	CONSTRUCTION SIGN, TYPE D	6.00	ACH
0097	801-06775	MAINTAINING TRAFFIC	1.00	LS
0098	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0099	802-04893	REFERENCE POST	2.00	ACH
0100	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	54.00	SFT
0101	802-76055	SIGN POST, TYPE A	136.00	LFT
0102	802-91122	SIGN, GROUND MOUNTED, RESET	1.00	ACH
0103	805-01842	HANDHOLE, SIGNAL, TYPE 1	5.00	ACH
0104	805-02596	CONDUIT RISER WITH WEATHERHEAD, STEEL	2.00	ACH
0105	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	2.00	ACH

0106	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	1572.00	LFT
0107	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00	EACH
0108	805-12650	SIGNAL POLE, PEDESTAL, 5 FT	2.00	EACH
0109	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	4.00	EACH
0110	805-78445	SIGNAL SERVICE	1.00	EACH
0111	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	346.00	LFT
0112	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1083.00	LFT
0113	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	1214.00	LFT
0114	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	1221.00	LFT
0115	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	94.00	LFT
0116	805-93755	SIGNAL POLE, TIMBER, 5, 30 FT	2.00	EACH
0117	805-96309	PEDESTRIAN PUSH BUTTON, RETROFIT	2.00	EACH
0118	807-02191	HANDHOLE, LIGHTING	2.00	EACH
0119	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	57.00	LFT
0120	807-86805	SERVICE POINT, TYPE I	1.00	EACH
0121	807-95888	WIRE, NO. 8 COPPER, 1/C	2504.00	LFT
0122	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1054.00	LFT
0123	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	959.00	LFT
0124	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	43.00	LFT

Call: 451

Contract: B -43516-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
0012	203-02000	EXCAVATION, COMMON	820.00	CYS
0013	203-02070	BORROW	1035.00	CYS
0014	205-11626	PUMP AROUND	1.00	EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	9669.50	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	599.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	734.00	CYS
0019	301-12233	COMPACTED AGGREGATE, NO. 8	37.00	CYS
0020	303-01180	COMPACTED AGGREGATE, NO. 53	164.00	TON
0021	304-07494	WIDENING WITH HMA, TYPE C	357.00	TON
0022	306-08036	MILLING, ASPHALT, 2 IN.	3036.00	SYS
0023	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	381.00	TON
0024	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	57.00	TON
0025	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	163.00	TON
0026	401-11526	JOINT ADHESIVE	200.00	LFT
0027	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	1740.00	LFT
0028	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0029	601-02241	GUARDRAIL, REMOVE	1111.00	LFT
0030	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	862.50	LFT
0031	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	EACH

0032	615-06490	RIGHT-OF-WAY MARKER	8.00	ACH
0033	615-06505	MONUMENT, TYPE B	2.00	ACH
0034	616-05689	RIPRAP, CLASS 2	298.00	TON
0035	616-06405	RIPRAP, REVETMENT	33.00	TON
0036	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	370.00	SYS
0037	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0038	621-02770	EROSION CONTROL BLANKET	882.00	SYS
0039	621-06559	MULCHED SEEDING, TYPE R	887.00	SYS
0040	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0041	714-000086	WATERPROOFING MEMBRANE, TYPE 2	300.00	SFT
0042	714-11179	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 6 FT	96.00	LFT
0043	715-12872	GEOTEXTILE FOR PIPE, TYPE 2B	360.00	SYS
0044	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	ACH
0045	801-06625	DETOUR ROUTE MARKER ASSEMBLY	53.00	ACH
0046	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	ACH
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0049	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0050	808-12032	GROOVING FOR PAVEMENT MARKINGS	2828.00	LFT
0051	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1740.00	LFT
0052	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	870.00	LFT
0053	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	22.00	ACH
0054	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	22.00	ACH
0055	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	218.00	LFT

Call: 461

Contract: B -43618-A

Section No.: 1 BRIDGE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0012	203-02000	EXCAVATION, COMMON	1146.00	CYS
0013	203-51223	EXCAVATION, WATERWAY	415.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	21000.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	218.00	CYS
0017	206-51235	COFFERDAM	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	1201.00	SYS
0019	211-02050	B BORROW	246.00	CYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	98.00	CYS
0021	214-07202	GEOGRID, TYPE IA	368.00	SYS
0022	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	736.00	SYS
0023	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	134.00	SYS
0024	301-12232	COMPACTED AGGREGATE, NO. 5	184.00	CYS
0025	301-12234	COMPACTED AGGREGATE, NO. 53	62.00	CYS
0026	302-06464	SUBBASE FOR PCCP	34.00	CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	68.00	TON
0028	304-07493	WIDENING WITH HMA, TYPE B	11.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	122.00	SYS
0030	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	97.00	TON
0031	401-000028	QC/QA-HMA, 2, 58S, INTERMEDIATE, 12.5 mm	112.00	TON

0032	401-000046	QC/QA-HMA, 2, 58S, BASE, 25.0 mm	170.00 TON
0033	401-11526	JOINT ADHESIVE	638.00 LFT
0034	406-05521	ASPHALT FOR TACK COAT	2185.00 SYS
0035	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	4.00 EACH
0036	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	125.00 LFT
0037	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00 EACH
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	140.00 SYS
0039	615-06490	RIGHT-OF-WAY MARKER	8.00 EACH
0040	615-06505	MONUMENT, TYPE B	2.00 EACH
0041	616-06405	RIPRAP, REVETMENT	290.00 TON
0042	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	472.00 SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0044	621-06559	MULCHED SEEDING, TYPE R	2589.00 SYS
0045	621-06574	SODDING	23.00 SYS
0046	628-09401	FIELD OFFICE, TYPE A	9.00 MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0048	701-09558	TEST PILE, INDICATOR, PRODUCTION	97.00 LFT
0049	701-09560	TEST PILE, INDICATOR, RESTRIKE	1.00 EACH
0050	701-09663	PILE, STEEL PIPE, 0.312 IN., DIAMETER 14 IN.	1391.00 LFT
0051	702-92857	CONCRETE, C, SUBSTRUCTURE	95.90 CYS
0052	703-06029	REINFORCING BARS, EPOXY COATED	28377.00 LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00 EACH
0054	704-51002	CONCRETE, C, SUPERSTRUCTURE	53.20 CYS
0055	706-06344	RAILING, STEEL TYPE TS-1	87.00 LFT
0056	707-11443	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 17 IN. X 36 IN.	178.00 LFT
0057	709-51821	SURFACE SEAL	1.00 LS
0058	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	94.00 LFT
0059	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	102.00 SYS
0060	726-92406	BEARING ASSEMBLY, ELASTOMERIC	8.00 EACH
0061	801-03290	CONSTRUCTION SIGN, TYPE C	2.00 EACH
0062	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00 EACH
0063	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00 EACH
0064	801-06640	CONSTRUCTION SIGN, TYPE A	10.00 EACH
0065	801-06775	MAINTAINING TRAFFIC	1.00 LS
0066	801-07118	BARRICADE, TYPE III-A	52.00 LFT
0067	801-07119	BARRICADE, TYPE III-B	22.00 LFT
0068	802-07060	SIGN, SHEET, RELOCATE	2.00 EACH

0069 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.

860.00 LFT

Call: 471

Contract: B -43650-A

Section No.: 1 BRIDGE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0012	203-02000	EXCAVATION, COMMON	285.00	CYS
0013	203-02070	BORROW	10.00	CYS
0014	203-51223	EXCAVATION, WATERWAY	172.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	217.00	CYS
0018	206-51235	COFFERDAM	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	86.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	775.00	SYS
0021	211-02050	B BORROW	104.00	CYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	24.00	CYS
0023	211-09267	STRUCTURE BACKFILL, TYPE 4	16.00	CYS
0024	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	959.00	SYS
0025	301-12234	COMPACTED AGGREGATE, NO. 53	15.00	CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	94.00	TON
0027	306-08043	MILLING, TRANSITION	223.00	SYS
0028	309-12695	LEAN CONCRETE BASE, 9 IN.	184.00	SYS
0029	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	73.00	TON
0030	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	90.00	TON
0031	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	216.00	TON

0032	401-11526	JOINT ADHESIVE	1330.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0034	601-01522	GUARDRAIL TRANSITION, TYPE TGB	1.00	EACH
0035	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	3.00	EACH
0036	601-94689	GUARDRAIL END TREATMENT, TYPE OS	3.00	EACH
0037	602-06729	BARRIER DELINEATOR	6.00	EACH
0038	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	184.00	SYS
0039	610-07487	HMA FOR APPROACHES, TYPE B	20.00	TON
0040	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0041	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0042	615-06505	MONUMENT, TYPE B	2.00	EACH
0043	616-05688	RIPRAP, CLASS 1	96.00	TON
0044	616-06405	RIPRAP, REVETMENT	323.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	720.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0047	621-06559	MULCHED SEEDING, TYPE R	1431.00	SYS
0048	621-06574	SODDING	232.00	SYS
0049	628-09403	FIELD OFFICE, TYPE C	8.00	MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0051	701-09558	TEST PILE, INDICATOR, PRODUCTION	277.00	LFT
0052	701-09560	TEST PILE, INDICATOR, RESTRIKE	4.00	EACH
0053	701-09683	PILE SHOE, HP 12 X 74	20.00	EACH
0054	701-95780	PILE, STEEL H, HP 12 X 74	935.00	LFT
0055	702-51005	CONCRETE, A, SUBSTRUCTURE	98.00	CYS
0056	703-06028	REINFORCING BARS	6614.00	LBS
0057	703-06029	REINFORCING BARS, EPOXY COATED	37986.00	LBS
0058	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	36.00	EACH
0059	704-51002	CONCRETE, C, SUPERSTRUCTURE	102.00	CYS
0060	706-09960	RAILING, CONCRETE TYPE FC	104.00	LFT
0061	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	EACH
0062	709-51821	SURFACE SEAL	1.00	LS
0063	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	78.00	LFT
0064	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0065	722-12732	LONGITUDINAL GROOVING	291.00	SYS
0066	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0067	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00	EACH
0068	801-06640	CONSTRUCTION SIGN, TYPE A	18.00	EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0071	801-07119	BARRICADE, TYPE III-B	60.00	LFT
0072	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	750.00	LFT
0073	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	750.00	LFT

Call: 481

Contract: B -43729-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	321.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0014	202-91840	FENCE, CHAIN LINK, REMOVE	150.00	LFT
0015	202-93741	GUARDRAIL END TREATMENT, REMOVE	6.00	EACH
0016	202-96133	PIPE, REMOVE	100.00	LFT
0017	203-02000	EXCAVATION, COMMON	11969.00	CYS
0018	203-02070	BORROW	215.00	CYS
0019	203-08607	LINEAR GRADING	402.00	LFT
0020	204-02290	SETTLEMENT PLATE	2.00	EACH
0021	205-11626	PUMP AROUND	5.00	EACH
0022	205-12108	STORMWATER MANAGEMENT BUDGET	64461.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	206-51235	COFFERDAM	1.00	LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	1005.00	SYS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	1114.00	SYS
0028	207-12635	SUBGRADE TREATMENT, TYPE IBC	4007.00	SYS
0029	211-02050	B BORROW	1426.00	CYS
0030	211-09264	STRUCTURE BACKFILL, TYPE 1	82.00	CYS
0031	211-09265	STRUCTURE BACKFILL, TYPE 2	136.00	CYS

0032	211-09266	STRUCTURE BACKFILL, TYPE 3	2367.00	CYS
0033	211-09268	STRUCTURE BACKFILL, TYPE 5	213.00	CYS
0034	214-11796	GEOGRID, TYPE IB	714.00	SYS
0035	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	3282.00	SYS
0036	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	1512.00	SYS
0037	215-12637	CHEMICAL MODIFICATION, SOILS, CEMENT	960.00	SYS
0038	301-12233	COMPACTED AGGREGATE, NO. 8	1947.00	CYS
0039	301-12234	COMPACTED AGGREGATE, NO. 53	41.00	CYS
0040	302-06464	SUBBASE FOR PCCP	99.00	CYS
0041	303-01180	COMPACTED AGGREGATE, NO. 53	382.00	TON
0042	304-07493	WIDENING WITH HMA, TYPE B	26.00	TON
0043	304-07494	WIDENING WITH HMA, TYPE C	386.00	TON
0044	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	28.00	TON
0045	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	33.00	TON
0046	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1443.00	SYS
0047	306-08043	MILLING, TRANSITION	440.00	SYS
0048	306-11872	MILLING, PROFILE	3147.00	SYS
0049	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	208.00	TON
0050	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	558.00	TON
0051	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	136.00	TON
0052	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	343.00	TON
0053	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	1527.00	TON
0054	401-11526	JOINT ADHESIVE	5112.00	LFT
0055	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	4013.00	LFT
0056	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0057	503-12477	TERMINAL JOINT, TYPE HMA	70.00	LFT
0058	601-01839	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 6	1.00	ACH
0059	601-01846	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 3	1.00	ACH
0060	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	50.00	LFT
0061	601-02241	GUARDRAIL, REMOVE	1947.50	LFT
0062	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	573.25	LFT
0063	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	2.00	ACH
0064	601-12291	GUARDRAIL TRANSITION, MGS WITH CURB	2.00	ACH
0065	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	6.00	ACH
0066	601-12422	GUARDRAIL, W-BEAM, STRUCTURE TOP-MOUNTED POSTS	6.00	ACH
0067	601-94689	GUARDRAIL END TREATMENT, TYPE OS	8.00	ACH
0068	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	75.00	LFT

0069	602-06729	BARRIER DELINEATOR	22.00	≡ACH
0070	603-06045	FENCE, CHAIN LINK, 48 IN.	150.00	LFT
0071	605-06095	CURB, INTEGRAL CONCRETE, TYPE B	10.00	LFT
0072	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	72.00	LFT
0073	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	387.90	SYS
0074	610-07487	HMA FOR APPROACHES, TYPE B	414.00	TON
0075	611-02825	MAILBOX ASSEMBLY, TRIPLE	1.00	≡ACH
0076	615-06490	RIGHT-OF-WAY MARKER	13.00	≡ACH
0077	615-06505	MONUMENT, TYPE B	4.00	≡ACH
0078	615-06530	BENCHMARK POST	1.00	≡ACH
0079	616-05688	RIPRAP, CLASS 1	155.00	TON
0080	616-06025	BORROW, COHESIVE	8.00	CYS
0081	616-06405	RIPRAP, REVETMENT	379.00	TON
0082	616-09395	GEOMEMBRANE	70.00	SYS
0083	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	763.00	SYS
0084	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	1518.00	SYS
0085	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	706.00	SYS
0086	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	≡ACH
0087	621-06553	SEED MIXTURE, TYPE R	79.00	LBS
0088	621-06560	MULCHED SEEDING, TYPE U	1113.00	SYS
0089	621-06565	MULCHING MATERIAL	2.00	TON
0090	621-06567	WATER	5.00	kGAL
0091	621-06574	SODDING	91.00	SYS
0092	621-06575	SODDING, NURSERY	765.00	SYS
0093	621-09815	ARTICULATED CONCRETE BLOCK	103.00	SYS
0094	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	≡ACH
0095	628-12683	FIELD OFFICE, TYPE D	30.00	MOS
0096	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	1880.00	SYS
0097	629-000150	TOPSOIL AMENDMENT BUDGET	3760.00	DOL
0098	701-06011	DYNAMIC PILE LOAD TEST	2.00	≡ACH
0099	701-09557	TEST PILE, DYNAMIC, PRODUCTION	107.00	LFT
0100	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	≡ACH
0101	701-51195	PILE, STEEL H, HP 12 X 53	348.00	LFT
0102	702-51005	CONCRETE, A, SUBSTRUCTURE	1.60	CYS
0103	702-51863	FIELD DRILLED HOLE IN CONCRETE	50.00	≡ACH
0104	703-06029	REINFORCING BARS, EPOXY COATED	95809.00	LBS
0105	703-08247	EMBEDDED GALVANIC ANODE	130.00	≡ACH

0106	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	133.00	≡ACH
0107	704-51002	CONCRETE, C, SUPERSTRUCTURE	235.80	CYS
0108	706-11600	RAILING, CONCRETE TYPE FC	34.50	CYS
0109	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	≡ACH
0110	709-51821	SURFACE SEAL	1.00	LS
0111	709-51821	SURFACE SEAL	1.00	LS
0112	710-09158	PATCHING CONCRETE STRUCTURES	351.00	SFT
0113	711-51038	STRUCTURAL STEEL	1.00	LS
0114	714-000086	WATERPROOFING MEMBRANE, TYPE 2	6606.00	SFT
0115	714-11178	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 5 FT	60.00	LFT
0116	714-11634	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 15 FT X 4 FT	76.00	LFT
0117	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	235.00	LFT
0118	715-05123	PIPE, TYPE 1, CIRCULAR, DIAMETER 24 IN.	76.00	LFT
0119	715-05171	PIPE, TYPE 3, CIRCULAR, DIAMETER 18 IN.	91.00	LFT
0120	715-05263	PIPE, TYPE 1, DEFORMED, MIN. AREA 29 SFT	60.00	LFT
0121	715-06939	CONCRETE ANCHOR, MIN. AREA 29.5 SFT	2.00	≡ACH
0122	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	≡ACH
0123	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	≡ACH
0124	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	106.00	LFT
0125	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	749.00	SYS
0126	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	184.00	SYS
0127	718-52610	AGGREGATE FOR UNDERDRAINS	19.00	CYS
0128	722-000134	BRIDGE DECK OVERLAY, RIGID	582.00	SYS
0129	722-01066	HYDRODEMOLITION	582.00	SYS
0130	722-12380	BRIDGE DECK OVERLAY BUDGET	11000.00	DOL
0131	722-12464	BRIDGE DECK, REMOVE CONCRETE SURFACE	582.00	SYS
0132	722-12732	LONGITUDINAL GROOVING	1652.00	SYS
0133	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	112.00	SFT
0134	726-92406	BEARING ASSEMBLY, ELASTOMERIC	5.00	≡ACH
0135	731-93945	FACE PANELS, CONCRETE	3208.00	SFT
0136	731-93946	WALL ERECTION	3208.00	SFT
0137	731-93947	LEVELING PAD, CONCRETE	202.00	LFT
0138	801-03291	CONSTRUCTION SIGN, TYPE D	2.00	≡ACH
0139	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00	≡ACH
0140	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	17011.00	LFT
0141	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	96.00	LFT
0142	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	≡ACH

0143	801-06640	CONSTRUCTION SIGN, TYPE A	54.00	ACH
0144	801-06645	CONSTRUCTION SIGN, TYPE B	8.00	ACH
0145	801-06775	MAINTAINING TRAFFIC	1.00	LS
0146	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	6.00	ACH
0147	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0148	801-07119	BARRICADE, TYPE III-B	372.00	LFT
0149	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2435.00	LFT
0150	801-11880	VEHICLES FOR ADVANCED SLOWDOWN	40.00	DAY
0151	801-12081	PORTABLE SIGNAL	1.00	LS
0152	801-12482	DRIVEWAY ASSISTANCE DEVICE	2.00	ACH
0153	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	8.00	ACH
0154	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	127.00	LFT
0155	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	23.00	LFT
0156	802-07058	SIGN, SHEET ASSEMBLY, RELOCATE	4.00	ACH
0157	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	14.00	SFT
0158	805-11965	SOLAR POWERED FLASHING LED SIGN ASSEMBLY	1.00	ACH
0159	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	60.00	LFT
0160	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	4982.00	LFT
0161	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	4790.00	LFT
0162	808-12032	GROOVING FOR PAVEMENT MARKINGS	8595.00	LFT
0163	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	127.00	LFT
0164	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	182.00	LFT
0165	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	72.00	LFT
0166	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	3.00	ACH
0167	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	21.00	ACH
0168	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.00	ACH

Call: 491

Contract: B -43822-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0009	203-02000	EXCAVATION, COMMON	65.00	CYS
0010	203-08607	LINEAR GRADING	1220.00	LFT
0011	507-08271	JOINTS IN PCCP, FILLED	414.00	LFT
0012	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0013	621-02770	EROSION CONTROL BLANKET	67.00	SYS
0014	621-06559	MULCHED SEEDING, TYPE R	167.00	SYS
0015	709-51821	SURFACE SEAL	1.00	LS
0016	709-51821	SURFACE SEAL	1.00	LS
0017	709-51821	SURFACE SEAL	1.00	LS
0018	709-51821	SURFACE SEAL	1.00	LS
0019	709-51821	SURFACE SEAL	1.00	LS
0020	709-51821	SURFACE SEAL	1.00	LS
0021	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	724.00	SFT
0022	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	4278.00	SYS
0023	738-12856	POLYMER OVERLAY, OTHER CONCRETE SURFACE	1221.00	SYS
0024	801-03290	CONSTRUCTION SIGN, TYPE C	4.00	ACH
0025	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	ACH
0026	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	37034.00	LFT
0027	801-06625	DETOUR ROUTE MARKER ASSEMBLY	99.00	ACH
0028	801-06640	CONSTRUCTION SIGN, TYPE A	87.00	ACH
0029	801-06645	CONSTRUCTION SIGN, TYPE B	12.00	ACH
0030	801-06710	FLASHING ARROW SIGN	56.00	DAY
0031	801-06775	MAINTAINING TRAFFIC	1.00	LS

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	ACH
0034	801-07118	BARRICADE, TYPE III-A	152.00	LFT
0035	801-07119	BARRICADE, TYPE III-B	176.00	LFT
0036	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1068.00	LFT
0037	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY
0038	801-12324	LAW ENFORCEMENT OFFICER	100.00	HRS
0039	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	310.00	LFT
0040	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	16.00	ACH
0041	808-06716	LINE, REMOVE	14941.00	LFT
0042	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	3610.00	LFT
0043	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2823.00	LFT
0044	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	540.00	LFT
0045	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	640.00	LFT
0046	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	4806.00	LFT
0047	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	4176.00	LFT
0048	808-75994	PRISMATIC REFLECTOR	38.00	ACH
0049	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	ACH

Call: 501

Contract: B -43998-A

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	182.00	SYS
0014	202-02272	PAVED SIDE DITCH, REMOVE	70.00	LFT
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0016	202-62420	BRIDGE RAILING, REMOVE	64.00	LFT
0017	202-96133	PIPE, REMOVE	100.00	LFT
0018	203-02000	EXCAVATION, COMMON	78.00	CYS
0019	203-02020	EXCAVATION, UNCLASSIFIED	1000.00	CYS
0020	203-08607	LINEAR GRADING	410.00	LFT
0021	205-11626	PUMP AROUND	2.00	EACH
0022	205-12108	STORMWATER MANAGEMENT BUDGET	60380.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	48.00	CYS
0026	206-51235	COFFERDAM	1.00	LS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	443.00	SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	48.00	CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	735.00	CYS
0030	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	607.00	SYS
0031	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	443.00	SYS

0032	301-12231	COMPACTED AGGREGATE, NO. 2	16.00	CYS
0033	301-12233	COMPACTED AGGREGATE, NO. 8	34.00	CYS
0034	302-06464	SUBBASE FOR PCCP	44.00	CYS
0035	303-01180	COMPACTED AGGREGATE, NO. 53	20.00	TON
0036	306-08034	MILLING, ASPHALT, 1 1/2 IN.	954.00	SYS
0037	306-08043	MILLING, TRANSITION	754.00	SYS
0038	306-12937	MILLING, ASPHALT, 7 IN.	2212.00	SYS
0039	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	185.00	TON
0040	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	183.00	TON
0041	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	37.00	TON
0042	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	305.00	TON
0043	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	88.00	TON
0044	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	365.00	TON
0045	401-11526	JOINT ADHESIVE	5796.00	LFT
0046	406-05521	ASPHALT FOR TACK COAT	4968.00	SYS
0047	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.00	TON
0048	601-02241	GUARDRAIL, REMOVE	310.00	LFT
0049	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	138.00	LFT
0050	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	7.00	EACH
0051	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00	EACH
0052	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	EACH
0053	603-06060	FENCE, FARM FIELD, RESET	50.00	LFT
0054	607-06335	PAVED SIDE DITCH, TYPE A	60.00	LFT
0055	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	184.00	SYS
0056	616-05688	RIPRAP, CLASS 1	311.00	TON
0057	616-05689	RIPRAP, CLASS 2	150.00	TON
0058	616-06405	RIPRAP, REVETMENT	558.00	TON
0059	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	1038.00	SYS
0060	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0061	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0062	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0063	619-98427	CLEAN DRAINS	8.00	EACH
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0065	621-02770	EROSION CONTROL BLANKET	10680.00	SYS
0066	621-06553	SEED MIXTURE, TYPE R	448.00	LBS
0067	621-06559	MULCHED SEEDING, TYPE R	1042.00	SYS
0068	621-06574	SODDING	287.00	SYS

0069	621-12612	SEED MIXTURE, FLOODPLAIN	11.00	LBS
0070	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0071	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0072	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	10680.00	SYS
0073	629-000150	TOPSOIL AMENDMENT BUDGET	21350.44	DOL
0074	702-92857	CONCRETE, C, SUBSTRUCTURE	14.60	CYS
0075	703-06029	REINFORCING BARS, EPOXY COATED	14418.00	LBS
0076	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	108.00	ACH
0077	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	ACH
0078	709-51821	SURFACE SEAL	1.00	LS
0079	709-51821	SURFACE SEAL	1.00	LS
0080	710-09158	PATCHING CONCRETE STRUCTURES	643.00	SFT
0081	711-51035	STRUCTURAL STEEL	4290.00	LBS
0082	711-95291	JACKING AND SUPPORTING STEEL BEAMS	1.00	LS
0083	711-96479	BOLT, REMOVE	56.00	ACH
0084	715-05019	PIPE, TYPE 1, CIRCULAR, DIAMETER 36 IN.	100.00	LFT
0085	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	50.00	LFT
0086	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	82.00	LFT
0087	715-91361	PIPE PVC, 6 IN.	5.00	LFT
0088	718-06528	OUTLET PROTECTOR, TYPE 1	2.00	ACH
0089	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	104.00	SYS
0090	722-000134	BRIDGE DECK OVERLAY, RIGID	1586.00	SYS
0091	722-000183	BRIDGE DECK, REMOVE CONCRETE OVERLAY AND SURFACE	1586.00	SYS
0092	722-01066	HYDRODEMOLITION	1586.00	SYS
0093	722-12380	BRIDGE DECK OVERLAY BUDGET	32000.00	DOL
0094	722-12732	LONGITUDINAL GROOVING	1756.00	SYS
0095	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	286.00	SFT
0096	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	244.00	SFT
0097	722-51874	OVERLAY DAM	42.00	SFT
0098	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	42.00	LFT
0099	724-12774	BRIDGE EXPANSION JOINT, TYPE SS, REPLACE	42.00	LFT
0100	724-12918	SILICONE JOINT SEALANT	24.00	LFT
0101	725-08293	PIPE LINER, CURED-IN-PLACE, 36 IN.	80.00	LFT
0102	726-92406	BEARING ASSEMBLY, ELASTOMERIC	14.00	ACH
0103	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	1350.00	SYS
0104	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	ACH
0105	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	15880.00	LFT

0106	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0107	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0108	801-06625	DETOUR ROUTE MARKER ASSEMBLY	45.00	EACH
0109	801-06640	CONSTRUCTION SIGN, TYPE A	53.00	EACH
0110	801-06645	CONSTRUCTION SIGN, TYPE B	8.00	EACH
0111	801-06775	MAINTAINING TRAFFIC	1.00	LS
0112	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0113	801-07118	BARRICADE, TYPE III-A	120.00	LFT
0114	801-07119	BARRICADE, TYPE III-B	96.00	LFT
0115	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	612.00	LFT
0116	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	495.00	LFT
0117	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0118	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY
0119	801-12081	PORTABLE SIGNAL	1.00	LS
0120	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0121	802-04893	REFERENCE POST	3.00	EACH
0122	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	42.00	LFT
0123	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	10.00	SFT
0124	808-06716	LINE, REMOVE	8365.00	LFT
0125	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	40.00	LFT
0126	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	5060.00	LFT
0127	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	5140.00	LFT
0128	808-75994	PRISMATIC REFLECTOR	9.00	EACH
0129	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	52.00	EACH
0130	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	52.00	EACH

Call: 511

Contract: B -44098-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	172.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0013	202-96133	PIPE, REMOVE	50.00	LFT
0014	203-02000	EXCAVATION, COMMON	95.00	CYS
0015	203-51223	EXCAVATION, WATERWAY	90.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	16000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	206-51235	COFFERDAM	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	1040.00	SYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	16.00	CYS
0021	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	1212.00	SYS
0022	302-06464	SUBBASE FOR PCCP	43.00	CYS
0023	303-01180	COMPACTED AGGREGATE, NO. 53	214.00	TON
0024	306-08043	MILLING, TRANSITION	245.00	SYS
0025	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	88.00	TON
0026	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	113.00	TON
0027	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	277.00	TON
0028	401-11526	JOINT ADHESIVE	628.00	LFT
0029	406-05521	ASPHALT FOR TACK COAT	982.00	SYS
0030	601-01740	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 4	1.00	EACH
0031	601-01846	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 3	1.00	EACH

0032	601-02241	GUARDRAIL, REMOVE	256.00	LFT
0033	601-05071	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 7	2.00	≡ACH
0034	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	4.00	≡ACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	69.00	LFT
0036	603-02969	FENCE GATE, RELOCATE	1.00	LS
0037	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	172.00	SYS
0038	615-06490	RIGHT-OF-WAY MARKER	8.00	≡ACH
0039	616-06405	RIPRAP, REVETMENT	387.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	583.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	≡ACH
0042	621-06559	MULCHED SEEDING, TYPE R	645.00	SYS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	≡ACH
0044	628-12683	FIELD OFFICE, TYPE D	9.00	MOS
0045	703-06029	REINFORCING BARS, EPOXY COATED	45575.00	LBS
0046	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	28.00	≡ACH
0047	704-51002	CONCRETE, C, SUPERSTRUCTURE	129.10	CYS
0048	706-06344	RAILING, STEEL TYPE TS-1	255.00	LFT
0049	707-11443	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 17 IN. X 36 IN.	517.00	LFT
0050	710-09158	PATCHING CONCRETE STRUCTURES	10.00	SFT
0051	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	70.00	LFT
0052	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	102.00	LFT
0053	715-05757	PIPE EXTENSION, CIRCULAR, DIAMETER 36 IN.	15.00	LFT
0054	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	≡ACH
0055	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	≡ACH
0056	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	56.00	SYS
0057	722-12732	LONGITUDINAL GROOVING	575.00	SYS
0058	726-92406	BEARING ASSEMBLY, ELASTOMERIC	48.00	≡ACH
0059	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	10.00	GAL
0060	727-90308	EPOXY INJECTION, CRACK PREPARATION	60.00	LFT
0061	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0062	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	≡ACH
0063	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00	≡ACH
0064	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	≡ACH
0065	801-06775	MAINTAINING TRAFFIC	1.00	LS
0066	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0067	801-07119	BARRICADE, TYPE III-B	72.00	LFT
0068	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1100.00	LFT

0069 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.

1100.00 LFT

Call: 521

Contract: B -44216-A

Section No.: 1 BRIDGE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-01261	TESTING FOR ASBESTOS	1.00	ACH
0012	202-01845	CONDUIT, REMOVE	9.00	LFT
0013	202-02240	PAVEMENT REMOVAL	150.00	SYS
0014	202-02279	CURB AND GUTTER, REMOVE	916.00	LFT
0015	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	50.00	SFT
0016	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0017	202-52710	SIDEWALK CONCRETE, REMOVE	644.00	SYS
0018	202-86946	HANDHOLE, REMOVE	1.00	ACH
0019	202-90747	RETAINING WALL, REMOVE	175.00	LFT
0020	202-91385	INLET, REMOVE	4.00	ACH
0021	202-91840	FENCE, CHAIN LINK, REMOVE	60.00	LFT
0022	202-96022	CONCRETE FOUNDATION, REMOVE	1.00	ACH
0023	203-02000	EXCAVATION, COMMON	1015.00	CYS
0024	203-02070	BORROW	730.00	CYS
0025	205-12108	STORMWATER MANAGEMENT BUDGET	15715.00	DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0027	206-51215	EXCAVATION, X	110.00	CYS
0028	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	120.00	CYS
0029	207-08264	SUBGRADE TREATMENT, TYPE II	170.00	SYS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	2219.00	SYS
0031	211-02050	B BORROW	10.00	CYS

0032	211-06467	AGGREGATE FOR END BENT BACKFILL	12.00	CYS
0033	211-09265	STRUCTURE BACKFILL, TYPE 2	221.00	CYS
0034	214-11796	GEOGRID, TYPE IB	111.00	SYS
0035	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	2834.00	SYS
0036	301-12233	COMPACTED AGGREGATE, NO. 8	170.00	CYS
0037	301-12234	COMPACTED AGGREGATE, NO. 53	420.00	CYS
0038	302-06464	SUBBASE FOR PCCP	55.00	CYS
0039	302-07455	DENSE GRADED SUBBASE	17.00	CYS
0040	304-07493	WIDENING WITH HMA, TYPE B	20.00	TON
0041	306-08034	MILLING, ASPHALT, 1 1/2 IN.	75.00	SYS
0042	306-11872	MILLING, PROFILE	1249.00	SYS
0043	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	264.00	TON
0044	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	385.00	TON
0045	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	598.00	TON
0046	401-11526	JOINT ADHESIVE	3259.00	LFT
0047	402-07451	HMA WEDGE AND LEVEL, TYPE B	12.00	TON
0048	406-05521	ASPHALT FOR TACK COAT	6567.00	SYS
0049	503-05240	D-1 CONTRACTION JOINT	98.00	LFT
0050	503-12477	TERMINAL JOINT, TYPE HMA	41.00	LFT
0051	601-03667	RAILING ORNAMENTAL	210.00	LFT
0052	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	2.00	≡ACH
0053	603-01932	FENCE, CHAIN LINK, 96 IN.	48.00	LFT
0054	603-97461	TEMPORARY FENCE	1990.00	LFT
0055	604-06070	SIDEWALK, CONCRETE	392.00	SYS
0056	604-08086	CURB RAMP, CONCRETE	165.00	SYS
0057	604-12083	DETECTABLE WARNING SURFACES	17.00	SYS
0058	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	36.00	LFT
0059	605-06150	CURB AND GUTTER, CONCRETE, TYPE C	789.00	LFT
0060	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	248.00	SYS
0061	610-07487	HMA FOR APPROACHES, TYPE B	14.00	TON
0062	610-09108	PCCP FOR APPROACHES, 9 IN.	124.00	SYS
0063	615-97768	PARKING BARRIER, RESET	22.00	≡ACH
0064	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	183.00	SYS
0065	616-93019	RIPRAP, GROUTED, 18 IN.	183.00	SYS
0066	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	≡ACH
0067	621-06560	MULCHED SEEDING, TYPE U	1070.00	SYS
0068	622-05652	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 3.5 IN.	2.00	≡ACH

0069	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0070	628-12683	FIELD OFFICE, TYPE D	15.00	MOS
0071	701-02936	PILE, STEEL H, HP 14 IN. X 89 IN.	412.00	LFT
0072	701-02938	CORED HOLE IN ROCK, DIAMETER 24 IN.	107.00	LFT
0073	701-09560	TEST PILE, INDICATOR, RESTRIKE	19.00	ACH
0074	701-09684	PILE SHOE, HP 14 X 89	19.00	ACH
0075	702-03607	CORED HOLE IN CONCRETE	17.00	ACH
0076	702-92857	CONCRETE, C, SUBSTRUCTURE	121.50	CYS
0077	703-06029	REINFORCING BARS, EPOXY COATED	80662.00	LBS
0078	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	226.00	ACH
0079	704-51002	CONCRETE, C, SUPERSTRUCTURE	204.60	CYS
0080	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPS-1	4.00	ACH
0081	706-08500	REINFORCED CONCRETE MOMENT SLAB, 14 IN.	193.00	SYS
0082	706-09961	RAILING, CONCRETE TYPE PS-1	130.00	LFT
0083	706-09961	RAILING, CONCRETE TYPE PS-1	210.00	LFT
0084	706-11418	RAILING, STEEL TYPE PS-1	148.00	LFT
0085	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	128.00	LFT
0086	709-51821	SURFACE SEAL	1.00	LS
0087	711-51038	STRUCTURAL STEEL	1.00	LS
0088	715-01354	CLEAN EXISTING PIPE	22.00	LFT
0089	715-05118	PIPE, TYPE 1, CIRCULAR, DIAMETER 12 IN.	75.00	LFT
0090	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	215.00	LFT
0091	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	178.00	LFT
0092	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	189.00	SYS
0093	720-01092	MANHOLE, TYPE J15, MODIFIED	3.00	ACH
0094	720-45410	MANHOLE, TYPE C4	2.00	ACH
0095	720-90349	MANHOLE, TYPE C8	2.00	ACH
0096	720-98555	INLET, TYPE C15	1.00	ACH
0097	722-12732	LONGITUDINAL GROOVING	447.00	SYS
0098	726-92406	BEARING ASSEMBLY, ELASTOMERIC	9.00	ACH
0099	734-10240	CUT-WALL, NO.	1658.00	SFT
0100	734-10240	CUT-WALL, NO.	17.00	SFT
0101	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	2.00	ACH
0102	801-03290	CONSTRUCTION SIGN, TYPE C	2.00	ACH
0103	801-03291	CONSTRUCTION SIGN, TYPE D	9.00	ACH
0104	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	ACH
0105	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	490.00	LFT

0106	801-06625	DETOUR ROUTE MARKER ASSEMBLY	17.00	ACH
0107	801-06640	CONSTRUCTION SIGN, TYPE A	55.00	ACH
0108	801-06645	CONSTRUCTION SIGN, TYPE B	42.00	ACH
0109	801-06775	MAINTAINING TRAFFIC	1.00	LS
0110	801-07118	BARRICADE, TYPE III-A	168.00	LFT
0111	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0112	801-11662	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 12 IN.	200.00	LFT
0113	801-11990	TEMPORARY CURB RAMP	4.00	ACH
0114	801-12081	PORTABLE SIGNAL	1.00	LS
0115	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	32.00	SYS
0116	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	450.00	LFT
0117	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	60.00	SFT
0118	802-91122	SIGN, GROUND MOUNTED, RESET	7.00	ACH
0119	805-000161	CONDUIT, PVC, 3 IN. SCHEDULE 80	1416.00	LFT
0120	805-000162	CONDUIT, PVC, 5 IN. SCHEDULE 80	634.00	LFT
0121	805-01842	HANDHOLE, SIGNAL, TYPE 1	5.00	ACH
0122	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	ACH
0123	805-02445	CONTROLLER AND CABINET, TYPE P1	1.00	ACH
0124	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	5.00	ACH
0125	805-05405	SIGNAL POLE, PEDESTAL, 4 FT	1.00	ACH
0126	805-10029	CONDUIT, PVC, 1.25 IN.	8.00	LFT
0127	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT	3.00	ACH
0128	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT	1.00	ACH
0129	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE A	4.00	ACH
0130	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	310.00	LFT
0131	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	334.00	LFT
0132	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	ACH
0133	805-12650	SIGNAL POLE, PEDESTAL, 5 FT	1.00	ACH
0134	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	8.00	ACH
0135	805-78412	SIGNAL POLE, PEDESTAL, 9 FT	3.00	ACH
0136	805-78445	SIGNAL SERVICE	1.00	ACH
0137	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	42.00	LFT
0138	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	2420.00	LFT
0139	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	943.00	LFT
0140	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00	ACH
0141	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	1.00	ACH
0142	807-08612	HANDHOLE, RECTANGULAR	1.00	ACH

0143	807-11712	WIRE, NO. 6 COPPER, 1/C	42.00	LFT
0144	807-12184	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. DIAMETER X 72 IN.	1.00	EACH
0145	807-86805	SERVICE POINT, TYPE I	1.00	EACH
0146	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	5.00	EACH
0147	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	313.00	LFT
0148	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	206.00	LFT
0149	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	309.00	LFT
0150	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE, 4 IN.	577.00	LFT
0151	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	151.00	LFT
0152	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1024.00	LFT
0153	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	870.00	LFT
0154	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	61.00	LFT
0155	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	5.00	EACH
0156	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1.00	EACH
0157	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ADA ACCESSIBLE SYMBOL	4.00	EACH

Call: 531

Contract: B -44218-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00	LS
0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0011	202-62420	BRIDGE RAILING, REMOVE	424.00	LFT
0012	205-12108	STORMWATER MANAGEMENT BUDGET	10915.00	DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	80.00	CYS
0015	303-01180	COMPACTED AGGREGATE, NO. 53	8.00	TON
0016	303-07449	COMPACTED AGGREGATE, NO. 73	4.00	TON
0017	601-06035	GUARDRAIL, RESET	82.00	LFT
0018	615-11538	PARKING BARRIER, TIMBER POST	10.00	EACH
0019	616-02281	GROUT FOR RIPRAP	4.00	CYS
0020	616-05688	RIPRAP, CLASS 1	111.00	TON
0021	616-06401	RIPRAP, DUMPED	19.00	TON
0022	616-06401	RIPRAP, DUMPED	36.00	TON
0023	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	198.00	SYS
0024	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0025	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0026	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0027	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0028	621-06565	MULCHING MATERIAL	1.00	TON
0029	621-12612	SEED MIXTURE, FLOODPLAIN	10.00	LBS
0030	621-52448	SIGN, 'DO NOT SPRAY'	8.00	EACH
0031	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH

0032	628-12683	FIELD OFFICE, TYPE D	9.00 MOS
0033	702-51005	CONCRETE, A, SUBSTRUCTURE	2.40 CYS
0034	702-51010	CONCRETE, B, ABOVE FOOTINGS	2.50 CYS
0035	702-51863	FIELD DRILLED HOLE IN CONCRETE	114.00 EACH
0036	703-06029	REINFORCING BARS, EPOXY COATED	419.00 LBS
0037	703-08247	EMBEDDED GALVANIC ANODE	12.00 EACH
0038	706-04683	RAILING	426.00 LFT
0039	709-51821	SURFACE SEAL	1.00 LS
0040	710-09158	PATCHING CONCRETE STRUCTURES	350.00 SFT
0041	711-05395	REPLACE	2.00 EACH
0042	711-05395	REPLACE	2.00 EACH
0043	711-05728	REPAIR	2.00 EACH
0044	711-05728	REPAIR	8.00 EACH
0045	711-51035	STRUCTURAL STEEL	3331.00 LBS
0046	711-51864	DRILLED HOLE	660.00 EACH
0047	711-51866	RIVET, REMOVE	358.00 EACH
0048	712-94080	TIMBER DECK	2532.00 SFT
0049	801-03290	CONSTRUCTION SIGN, TYPE C	4.00 EACH
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0051	801-06775	MAINTAINING TRAFFIC	1.00 LS
0052	801-07118	BARRICADE, TYPE III-A	24.00 LFT
0053	801-07119	BARRICADE, TYPE III-B	30.00 LFT
0054	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	88.00 LFT
0055	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	45.00 SFT
0056	802-91122	SIGN, GROUND MOUNTED, RESET	1.00 EACH

Call: 541

Contract: B -44942-A

Section No.: 1 SCOUR PROTECTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0010	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
0011	203-51223	EXCAVATION, WATERWAY	67.00	CYS
0012	205-11626	PUMP AROUND	2.00	ACH
0013	205-12108	STORMWATER MANAGEMENT BUDGET	18022.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	301-12234	COMPACTED AGGREGATE, NO. 53	46.00	CYS
0016	601-06035	GUARDRAIL, RESET	188.00	LFT
0017	616-02281	GROUT FOR RIPRAP	8.00	CYS
0018	616-05689	RIPRAP, CLASS 2	300.00	TON
0019	616-06405	RIPRAP, REVETMENT	150.00	TON
0020	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	542.00	SYS
0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0022	621-02356	SEEDING WETLAND	1.00	LBS
0023	621-06559	MULCHED SEEDING, TYPE R	1385.00	SYS
0024	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0025	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	ACH
0026	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	ACH
0027	801-06640	CONSTRUCTION SIGN, TYPE A	34.00	ACH
0028	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	ACH
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
0030	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0031	801-07119	BARRICADE, TYPE III-B	48.00	LFT

Call: 551

Contract: B -45541-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	203-02000	EXCAVATION, COMMON	161.00	CYS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	12100.00	DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014	206-51235	COFFERDAM	1.00	LS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	34.00	SYS
0016	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	176.00	SYS
0017	302-06464	SUBBASE FOR PCCP	44.00	CYS
0018	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	19.00	TON
0019	306-08043	MILLING, TRANSITION	593.00	SYS
0020	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	49.00	TON
0021	401-11526	JOINT ADHESIVE	540.00	LFT
0022	406-05521	ASPHALT FOR TACK COAT	660.00	SYS
0023	605-06090	CURB, INTEGRAL CONCRETE	20.00	LFT
0024	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	176.00	SYS
0025	616-02281	GROUT FOR RIPRAP	16.00	CYS
0026	616-06396	RIPRAP	141.00	TON
0027	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	234.00	SYS
0028	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0029	621-06559	MULCHED SEEDING, TYPE R	890.00	SYS
0030	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0031	628-12683	FIELD OFFICE, TYPE D	8.00	MOS

0032	702-51863	FIELD DRILLED HOLE IN CONCRETE	278.00	≡ACH
0033	703-06029	REINFORCING BARS, EPOXY COATED	10094.00	LBS
0034	709-51821	SURFACE SEAL	1.00	LS
0035	710-09158	PATCHING CONCRETE STRUCTURES	50.00	SFT
0036	711-91981	TIE ROD	2.00	≡ACH
0037	722-000134	BRIDGE DECK OVERLAY, RIGID	209.00	SYS
0038	722-01066	HYDRODEMOLITION	209.00	SYS
0039	722-12380	BRIDGE DECK OVERLAY BUDGET	5050.00	DOL
0040	722-12464	BRIDGE DECK, REMOVE CONCRETE SURFACE	209.00	SYS
0041	722-12732	LONGITUDINAL GROOVING	385.00	SYS
0042	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	86.00	SFT
0043	722-51874	OVERLAY DAM	76.00	SFT
0044	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	≡ACH
0045	801-06625	DETOUR ROUTE MARKER ASSEMBLY	45.00	≡ACH
0046	801-06640	CONSTRUCTION SIGN, TYPE A	4.00	≡ACH
0047	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	≡ACH
0048	801-06775	MAINTAINING TRAFFIC	1.00	LS
0049	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0050	801-07119	BARRICADE, TYPE III-B	96.00	LFT
0051	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	68.00	LFT
0052	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	540.00	LFT
0053	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	270.00	LFT
0054	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.00	≡ACH

Call: 561

Contract: B -45637-A

Section No.: 1 REPAIR OR REPLACE JOINTS

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	106-12979	E-TICKET INCENTIVE	6.00	ACH
0003	107-12976	RAILROAD FLAGGING BUDGET	12000.00	DOL
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	725.00	SFT
0011	724-12420	BRIDGE JOINT NOSING	164.00	SFT
0012	724-12779	BRIDGE EXPANSION JOINT SEAL, TYPE PCF, REPLACE	780.00	LFT
0013	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	125276.00	LFT
0014	801-06640	CONSTRUCTION SIGN, TYPE A	120.00	ACH
0015	801-06710	FLASHING ARROW SIGN	50.00	DAY
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
0017	801-07118	BARRICADE, TYPE III-A	300.00	LFT
0018	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	ACH
0019	801-12042	TRUCK MOUNTED ATTENUATOR	136.00	DAY
0020	801-12324	LAW ENFORCEMENT OFFICER	144.00	HRS
0021	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	20.00	ACH
0022	808-06716	LINE, REMOVE	50830.00	LFT
0023	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 24 IN.	272.00	LFT
0024	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	19796.00	LFT
0025	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	6961.00	LFT
0026	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	6065.00	LFT

Call: 601

Contract: T -43756-A

Section No.: 1 DISTRICT SIGNAL PROJECT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	203-02000	EXCAVATION, COMMON	2625.00	CYS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	36000.00	DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0014	205-12618	SWQCP PREPARATION	1.00	LS
0015	207-08264	SUBGRADE TREATMENT, TYPE II	436.00	SYS
0016	207-12635	SUBGRADE TREATMENT, TYPE IBC	4912.00	SYS
0017	211-09264	STRUCTURE BACKFILL, TYPE 1	166.00	CYS
0018	214-11796	GEOGRID, TYPE IB	96.00	SYS
0019	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	4912.00	SYS
0020	301-12234	COMPACTED AGGREGATE, NO. 53	63.00	CYS
0021	303-01180	COMPACTED AGGREGATE, NO. 53	448.00	TON
0022	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	5.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4216.00	SYS
0024	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	672.00	TON
0025	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	539.00	TON
0026	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	1788.00	TON
0027	401-11526	JOINT ADHESIVE	4269.00	LFT
0028	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0029	402-07452	HMA WEDGE AND LEVEL, TYPE C	402.00	TON
0030	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON

0032	601-05999	CURVED TERMINAL END	1.00	ACH
0033	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	257.00	LFT
0034	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	ACH
0035	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	2709.00	LFT
0036	610-07487	HMA FOR APPROACHES, TYPE B	128.00	TON
0037	611-06497	MAILBOX ASSEMBLY, SINGLE	7.00	ACH
0038	615-06505	MONUMENT, TYPE B	4.00	ACH
0039	616-06405	RIPRAP, REVETMENT	45.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	49.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0042	621-02770	EROSION CONTROL BLANKET	1103.00	SYS
0043	621-06554	SEED MIXTURE, TYPE U	202.00	LBS
0044	621-06565	MULCHING MATERIAL	3.00	TON
0045	621-06567	WATER	3.00	kGAL
0046	621-06574	SODDING	818.00	SYS
0047	628-09403	FIELD OFFICE, TYPE C	20.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0049	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	6503.00	SYS
0050	629-000150	TOPSOIL AMENDMENT BUDGET	13006.00	DOL
0051	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	444.00	LFT
0052	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	173.00	LFT
0053	715-09064	VIDEO INSPECTION FOR PIPE	628.00	LFT
0054	715-46005	PIPE END SECTION, DIAMETER 15 IN.	11.00	ACH
0055	720-45030	INLET, TYPE E7	2.00	ACH
0056	720-45410	MANHOLE, TYPE C4	2.00	ACH
0057	720-98174	INLET, TYPE B15	3.00	ACH
0058	720-98555	INLET, TYPE C15	2.00	ACH
0059	801-02595	CONTROLLER, RESET TIMING	4.00	ACH
0060	801-06206	TEMPORARY PAVEMENT MARKING, 6 IN.	7950.00	LFT
0061	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	13920.00	LFT
0062	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0063	801-06640	CONSTRUCTION SIGN, TYPE A	13.00	ACH
0064	801-06645	CONSTRUCTION SIGN, TYPE B	3.00	ACH
0065	801-06775	MAINTAINING TRAFFIC	1.00	LS
0066	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	10.00	ACH
0067	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1450.00	LFT
0068	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	ACH

0069	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0070	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	6.00	ACH
0071	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	30.00	LFT
0072	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	26.00	LFT
0073	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	44.00	SFT
0074	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	24.00	SFT
0075	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0076	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	ACH
0077	805-01842	HANDHOLE, SIGNAL, TYPE 1	5.00	ACH
0078	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	7.00	ACH
0079	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1323.00	LFT
0080	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	1.00	ACH
0081	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	6.00	ACH
0082	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	1.00	ACH
0083	805-78415	SPAN, CATENARY, AND TETHER	4.00	ACH
0084	805-78420	DISCONNECT HANGER	3.00	ACH
0085	805-78445	SIGNAL SERVICE	1.00	ACH
0086	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	46.00	LFT
0087	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	2449.00	LFT
0088	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	150.00	LFT
0089	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	337.00	LFT
0090	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	287.00	LFT
0091	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2562.00	LFT
0092	805-78785	SIGNAL DETECTOR HOUSING	6.00	ACH
0093	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	765.00	LFT
0094	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00	ACH
0095	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	4.00	ACH
0096	808-06716	LINE, REMOVE	6045.00	LFT
0097	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 12 IN.	52.00	LFT
0098	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	3313.00	LFT
0099	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	81.00	LFT
0100	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2816.00	LFT
0101	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	6.00	ACH
0102	808-12032	GROOVING FOR PAVEMENT MARKINGS	6129.00	LFT
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	34.00	ACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	34.00	ACH

Call: 611

Contract: T -44144-A

Section No.: 1 INSTALL NEW CABLE RAIL BARRIERS

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-93741	GUARDRAIL END TREATMENT, REMOVE	1.00	ACH
0009	203-02070	BORROW	200.00	CYS
0010	203-08607	LINEAR GRADING	46992.00	LFT
0011	205-12108	STORMWATER MANAGEMENT BUDGET	100112.50	DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0013	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	188.00	LFT
0014	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00	ACH
0015	601-94690	GUARDRAIL END TREATMENT, TYPE MS	1.00	ACH
0016	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.00	ACH
0017	621-06559	MULCHED SEEDING, TYPE R	105350.00	SYS
0018	621-06567	WATER	20.00	KGAL
0019	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	47220.00	LFT
0020	627-09330	SAFETY TERMINAL, TYPE TL-3	26.00	ACH
0021	627-10178	CABLE BARRIER SYSTEM, TYPE TL-4, SPARE PARTS	1.00	LS
0022	628-09403	FIELD OFFICE, TYPE C	4.00	MOS
0023	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0024	801-03290	CONSTRUCTION SIGN, TYPE C	4.00	ACH
0025	801-06640	CONSTRUCTION SIGN, TYPE A	84.00	ACH
0026	801-06645	CONSTRUCTION SIGN, TYPE B	10.00	ACH
0027	801-06710	FLASHING ARROW SIGN	240.00	DAY
0028	801-06775	MAINTAINING TRAFFIC	1.00	LS
0029	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	ACH
0030	801-12042	TRUCK MOUNTED ATTENUATOR	60.00	DAY
0031	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	8.00	ACH

0032 804-06725 DELINEATOR WITH POST, TYPE D1

24.00 EACH

Call: 621

Contract: T -45493-A

Section No.: 1 SIGNING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	20.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	801-06775	MAINTAINING TRAFFIC	1.00	LS
0009	801-92448	CONSTRUCTION SIGNS MOBILE	150.00	DAY
0010	802-04089	SIGN, SHEET, REMOVE	2.00	EACH
0011	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	2904.00	LFT
0012	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	285.00	EACH
0013	802-07060	SIGN, SHEET, RELOCATE	3.00	EACH
0014	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	1617.00	SFT
0015	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	84.00	SFT

Call: 631

Contract: T -45735-A

Section No.: 1 SIGN MODERNIZATION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	202-06541	REMOVE	11.00	EACH
0010	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0011	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	434.00	LFT
0012	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	EACH
0013	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	9.00	LFT
0014	601-99132	GUARDRAIL HEIGHT TRANSITION, VH, 6 FT 3 IN. SPACING	1.00	EACH
0015	801-03290	CONSTRUCTION SIGN, TYPE C	10.00	EACH
0016	801-06640	CONSTRUCTION SIGN, TYPE A	26.00	EACH
0017	801-06645	CONSTRUCTION SIGN, TYPE B	14.00	EACH
0018	801-06710	FLASHING ARROW SIGN	50.00	DAY
0019	801-06775	MAINTAINING TRAFFIC	1.00	LS
0020	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00	LFT
0021	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0022	801-11880	VEHICLES FOR ADVANCED SLOWDOWN	9.00	DAY
0023	801-12324	LAW ENFORCEMENT OFFICER	40.00	HRS
0024	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	2.00	EACH
0025	802-03783	SIGN, PANEL, REMOVE	3.00	EACH
0026	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0027	802-04893	REFERENCE POST	191.00	EACH
0028	802-04993	SIGN	1.00	LS
0029	802-05706	SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	30.00	LFT
0030	802-07057	SIGN, PANEL, WITH LEGEND	6479.00	SFT
0031	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00	EACH

0032	802-09221	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE A	2.00	ACH
0033	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	4.00	ACH
0034	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE A	22.00	ACH
0035	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE B	2.00	ACH
0036	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE C	14.00	ACH
0037	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	22.00	ACH
0038	802-74050	SIGN, OVERHEAD, REMOVE	15.00	ACH
0039	802-76095	STRUCTURAL STEEL, BREAKAWAY	15786.00	LBS

Call: 641

Contract: T -45736-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-03290	CONSTRUCTION SIGN, TYPE C	16.00	ACH
0008	801-06640	CONSTRUCTION SIGN, TYPE A	48.00	ACH
0009	801-06775	MAINTAINING TRAFFIC	1.00	LS
0010	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	14.00	ACH
0011	805-01842	HANDHOLE, SIGNAL, TYPE 1	70.00	ACH
0012	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	74.00	ACH
0013	805-09540	LOOP DETECTOR RACK	2.00	ACH
0014	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	14665.00	LFT
0015	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	49096.00	LFT
0016	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	43680.00	LFT
0017	805-78785	SIGNAL DETECTOR HOUSING	126.00	ACH
0018	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	24805.00	LFT
0019	805-92504	LOOP DETECTOR DELAY AMPLIFIER, NONCOUNTING 2 CHANNEL	17.00	ACH
0020	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	48.00	LFT

Call: 651

Contract: T -45737-A

Section No.: 1 RAISED PAVEMENT MARKINGS, REFURBISHED

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-06710	FLASHING ARROW SIGN	130.00	DAY
0008	801-06775	MAINTAINING TRAFFIC	1.00	LS
0009	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0010	801-12042	TRUCK MOUNTED ATTENUATOR	130.00	DAY
0011	801-92448	CONSTRUCTION SIGNS MOBILE	130.00	DAY
0012	808-75994	PRISMATIC REFLECTOR	14254.00	EACH
0013	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1233.00	EACH
0014	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6125.00	EACH

Call: 661

Contract: T -45900-A

Section No.: 1 PAVEMENT MARKINGS

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-06775	MAINTAINING TRAFFIC	1.00	LS
0008	808-06716	LINE, REMOVE	1906.00	LFT
0009	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	958793.00	LFT
0010	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	304670.00	LFT
0011	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	99090.00	LFT

Call: 671

Contract: T -45902-A

Section No.: 1 PAVEMENT MARKINGS

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-06640	CONSTRUCTION SIGN, TYPE A	8.00	EACH
0008	801-06775	MAINTAINING TRAFFIC	1.00	LS
0009	801-12042	TRUCK MOUNTED ATTENUATOR	5.00	DAY
0010	801-92448	CONSTRUCTION SIGNS MOBILE	5.00	DAY
0011	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	37885.00	LFT
0012	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	163648.00	LFT