

Schedule of Pay Items Letting Date September 2, 2026 Letting ID 260902

Call: 141

Contract: R -43371-A

Section No.: 1 SLIDE CORRECTION

Line	Item No	Item Code	Description	Quantity	Unit
0001	104-05404		DESIGN BUILD	1.00	LS
0002	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0003	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360		CONTRACT LIENS	1.00	DOL
0005	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES AND MARKINGS	1.00	DOL
0007	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0013	202-02271		HEADWALL, REMOVE	2.00	ACH
0014	203-02000		EXCAVATION, COMMON	2035.00	CYS
0015	205-11626		PUMP AROUND	1.00	ACH
0016	205-12108		STORMWATER MANAGEMENT BUDGET	13500.00	DOL
0017	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618		SWQCP PREPARATION	1.00	LS
0019	207-09935		SUBGRADE TREATMENT, TYPE IC	567.00	SYS
0020	211-09265		STRUCTURE BACKFILL, TYPE 2	70.00	CYS
0021	214-11796		GEOGRID, TYPE IB	567.00	SYS
0022	301-12234		COMPACTED AGGREGATE, NO. 53	22.00	CYS
0023	303-01180		COMPACTED AGGREGATE, NO. 53	517.00	TON
0024	304-07494		WIDENING WITH HMA, TYPE C	11.00	TON
0025	306-08034		MILLING, ASPHALT, 1 1/2 IN.	2067.00	SYS
0026	401-000005		QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	176.00	TON
0027	401-000023		QC/QA-HMA, 3, 58H, INTERMEDIATE, 9.5 mm	16.00	TON
0028	401-000047		QC/QA-HMA, 3, 58S, BASE, 25.0 mm	52.00	TON
0029	401-11526		JOINT ADHESIVE	865.00	LFT
0030	406-05520		ASPHALT FOR TACK COAT	1.00	TON
0031	601-02241		GUARDRAIL, REMOVE	775.00	LFT

0032	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	693.00	LFT
0033	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00	ACH
0034	601-94689	GUARDRAIL END TREATMENT, TYPE OS	1.00	ACH
0035	615-06490	RIGHT-OF-WAY MARKER	14.00	ACH
0036	615-06505	MONUMENT, TYPE B	5.00	ACH
0037	616-05688	RIPRAP, CLASS 1	30.00	TON
0038	616-05689	RIPRAP, CLASS 2	51.00	TON
0039	616-06405	RIPRAP, REVETMENT	21.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	184.00	SYS
0041	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	46.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0043	621-02770	EROSION CONTROL BLANKET	359.00	SYS
0044	621-03909	SEED MIXTURE, NATIVE	19.00	LBS
0045	622-03672	TREE PROTECTION AND TRIMMING	1.00	LS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0047	628-12683	FIELD OFFICE, TYPE D	15.00	MOS
0048	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	1924.00	SYS
0049	629-000150	TOPSOIL AMENDMENT BUDGET	3848.00	DOL
0050	702-51005	CONCRETE, A, SUBSTRUCTURE	6.00	CYS
0051	714-000086	WATERPROOFING MEMBRANE, TYPE 2	798.00	SFT
0052	714-12807	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 4 FT	42.00	LFT
0053	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	ACH
0054	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	ACH
0055	801-06640	CONSTRUCTION SIGN, TYPE A	13.00	ACH
0056	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	ACH
0057	801-06775	MAINTAINING TRAFFIC	1.00	LS
0058	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0059	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0060	808-12032	GROOVING FOR PAVEMENT MARKINGS	3100.00	LFT
0061	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1550.00	LFT
0062	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1550.00	LFT
0063	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	ACH
0064	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.00	ACH