

Schedule of Pay Items Letting Date November 13, 2025 Letting ID 251113

Call: 231

Contract: R -43888-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0014	203-02000	EXCAVATION, COMMON	255.00	CYS
0015	203-02070	BORROW	140.00	CYS
0016	205-11626	PUMP AROUND	2.00	EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	16713.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	638.00	SYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	12.00	CYS
0021	211-09268	STRUCTURE BACKFILL, TYPE 5	287.00	CYS
0022	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	222.00	SYS
0023	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	673.00	SYS
0024	301-12232	COMPACTED AGGREGATE, NO. 5	18.00	CYS
0025	301-12233	COMPACTED AGGREGATE, NO. 8	6.00	CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	84.00	TON
0027	304-07493	WIDENING WITH HMA, TYPE B	86.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	347.00	SYS
0029	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	75.00	TON
0030	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	48.00	TON
0031	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	119.00	TON

0032	401-11526	JOINT ADHESIVE	805.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	2351.00	SYS
0034	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.00	TON
0035	601-02241	GUARDRAIL, REMOVE	250.00	LFT
0036	615-06490	RIGHT-OF-WAY MARKER	10.00	EACH
0037	615-06505	MONUMENT, TYPE B	4.00	EACH
0038	616-05688	RIPRAP, CLASS 1	93.00	TON
0039	616-06405	RIPRAP, REVETMENT	59.00	TON
0040	616-06451	RIPRAP, UNIFORM	43.00	TON
0041	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	348.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0043	621-06559	MULCHED SEEDING, TYPE R	1043.00	SYS
0044	621-06574	SODDING	51.00	SYS
0045	621-06575	SODDING, NURSERY	180.00	SYS
0046	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0048	714-000086	WATERPROOFING MEMBRANE TYPE 2	1584.00	SFT
0049	714-000087	WATERPROOFING MEMBRANE TYPE 3	572.00	SFT
0050	714-000181	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 11 FT X 9 FT	44.00	LFT
0051	714-12499	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 3 FT	44.00	LFT
0052	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	39.00	LFT
0053	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0054	801-06625	DETOUR ROUTE MARKER ASSEMBLY	45.00	EACH
0055	801-06640	CONSTRUCTION SIGN, TYPE A	14.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0058	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0059	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	610.00	LFT
0060	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	610.00	LFT

Call: 331

Contract: B -43624-A

Section No.: 1 BRIDGE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00	LS
0012	203-02000	EXCAVATION, COMMON	655.00	CYS
0013	203-51223	EXCAVATION, WATERWAY	210.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	25500.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	206-51220	EXCAVATION, WET	165.00	CYS
0017	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	38.00	CYS
0018	206-51235	COFFERDAM	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	1540.00	SYS
0020	211-09264	STRUCTURE BACKFILL, TYPE 1	5.00	CYS
0021	211-09267	STRUCTURE BACKFILL, TYPE 4	18.00	CYS
0022	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	150.00	SYS
0023	301-12234	COMPACTED AGGREGATE, NO. 53	245.00	CYS
0024	302-06464	SUBBASE FOR PCCP	38.00	CYS
0025	303-01180	COMPACTED AGGREGATE, NO. 53	270.00	TON
0026	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	115.00	TON
0027	401-000037	QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	195.00	TON
0028	401-11526	JOINT ADHESIVE	1160.00	LFT
0029	406-05521	ASPHALT FOR TACK COAT	1350.00	SYS
0030	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	62.00	LFT
0031	601-02241	GUARDRAIL, REMOVE	100.00	LFT

0032	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	4.00	ACH
0033	601-52540	GUARDRAIL TERMINAL SECTION, W-BEAM	2.00	ACH
0034	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	ACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	19.00	LFT
0036	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	150.00	SYS
0037	615-06505	MONUMENT, TYPE B	2.00	ACH
0038	616-06405	RIPRAP, REVETMENT	365.00	TON
0039	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	550.00	SYS
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0041	621-06559	MULCHED SEEDING, TYPE R	2800.00	SYS
0042	621-06567	WATER	1.00	KGAL
0043	621-06574	SODDING	45.00	SYS
0044	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0045	701-09739	PILE SHOE, HP 12 X 53	32.00	ACH
0046	701-51195	PILE, STEEL H, HP 12 X 53	600.00	LFT
0047	702-51005	CONCRETE, A, SUBSTRUCTURE	87.00	CYS
0048	702-51015	CONCRETE, B, FOOTINGS	33.80	CYS
0049	703-06028	REINFORCING BARS	23596.00	LBS
0050	703-06029	REINFORCING BARS, EPOXY COATED	56053.00	LBS
0051	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	28.00	ACH
0052	704-51002	CONCRETE, C, SUPERSTRUCTURE	175.30	CYS
0053	706-06344	RAILING, STEEL TYPE TS-1	200.00	LFT
0054	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	24.00	LFT
0055	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	ACH
0056	722-12732	LONGITUDINAL GROOVING	419.00	SYS
0057	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	ACH
0058	801-06625	DETOUR ROUTE MARKER ASSEMBLY	4.00	ACH
0059	801-06640	CONSTRUCTION SIGN, TYPE A	8.00	ACH
0060	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	ACH
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0063	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0064	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	175.00	LFT
0065	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1400.00	LFT

Call: 441

Contract: B -45038-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	142.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0013	202-52710	SIDEWALK CONCRETE, REMOVE	84.00	SYS
0014	203-02000	EXCAVATION, COMMON	635.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	4193.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	1800.00	SYS
0018	211-06467	AGGREGATE FOR END BENT BACKFILL	11.00	CYS
0019	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	689.00	SYS
0020	301-12234	COMPACTED AGGREGATE, NO. 53	49.00	CYS
0021	302-06464	SUBBASE FOR PCCP	100.00	CYS
0022	306-08043	MILLING, TRANSITION	734.00	SYS
0023	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	177.00	TON
0024	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	194.00	TON
0025	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	667.00	TON
0026	401-11526	JOINT ADHESIVE	3260.00	LFT
0027	406-05521	ASPHALT FOR TACK COAT	4947.00	SYS
0028	503-12477	TERMINAL JOINT, TYPE HMA	90.00	LFT
0029	601-02241	GUARDRAIL, REMOVE	230.00	LFT
0030	601-06035	GUARDRAIL, RESET	465.00	LFT
0031	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	50.00	LFT

0032	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	2.00	ACH
0033	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	ACH
0034	602-06729	BARRIER DELINEATOR	11.00	ACH
0035	604-06070	SIDEWALK, CONCRETE	68.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	13.00	SYS
0037	604-12083	DETECTABLE WARNING SURFACES	3.00	SYS
0038	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	395.00	SYS
0039	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0040	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0041	619-51859	COAT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0043	628-12683	FIELD OFFICE, TYPE D	10.00	MOS
0044	702-04325	TEMPORARY SHORING	1.00	LS
0045	702-51863	FIELD DRILLED HOLE IN CONCRETE	64.00	ACH
0046	703-06029	REINFORCING BARS, EPOXY COATED	46297.00	LBS
0047	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	274.00	ACH
0048	704-51002	CONCRETE, C, SUPERSTRUCTURE	94.50	CYS
0049	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	2.00	ACH
0050	706-11404	RAILING, STEEL TYPE PF-1	305.00	LFT
0051	706-11602	RAILING, CONCRETE TYPE PF-1	20.00	CYS
0052	709-51821	SURFACE SEAL	1.00	LS
0053	711-51864	DRILLED HOLE	64.00	ACH
0054	711-93035	JACKING AND SUPPORTING STRUCTURAL STEEL	1.00	LS
0055	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	142.00	LFT
0056	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	60.00	SYS
0057	722-000134	BRIDGE DECK OVERLAY, RIGID	1456.00	SYS
0058	722-01066	HYDRODEMOLITION	1340.00	SYS
0059	722-12380	BRIDGE DECK OVERLAY BUDGET	29700.00	DOL
0060	722-12464	BRIDGE DECK, REMOVE CONCRETE SURFACE	1340.00	SYS
0061	722-12732	LONGITUDINAL GROOVING	1788.00	SYS
0062	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	363.00	SFT
0063	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	16.00	LFT
0064	726-92406	BEARING ASSEMBLY, ELASTOMERIC	16.00	ACH
0065	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	4032.00	LFT
0066	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0067	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	ACH
0068	801-06645	CONSTRUCTION SIGN, TYPE B	8.00	ACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	ACH
0071	801-07119	BARRICADE, TYPE III-B	304.00	LFT
0072	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	330.00	LFT
0073	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	580.00	LFT
0074	801-12081	PORTABLE SIGNAL	1.00	LS
0075	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	745.00	LFT
0076	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	4.00	ACH
0077	802-91122	SIGN, GROUND MOUNTED, RESET	2.00	ACH
0078	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	330.00	LFT
0079	807-01653	WIRE, NO. 4 COPPER, IN CONDUIT, BRIDGE 1/C	1100.00	LFT
0080	807-02191	HANDHOLE, LIGHTING	1.00	ACH
0081	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	2.00	ACH
0082	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	25.00	LFT
0083	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	210.00	LFT
0084	808-06716	LINE, REMOVE	1622.00	LFT
0085	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1565.00	LFT
0086	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	1295.00	LFT
0087	808-12032	GROOVING FOR PAVEMENT MARKINGS	3030.00	LFT
0088	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	170.00	LFT