

Schedule of Pay Items Letting Date February 11, 2026 Letting ID 260211

Call: 130

Contract: R -41954-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358		INSPECTION HOLE, DEEPER THAN 3 FT	6.00	EACH
0003	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360		CONTRACT LIENS	1.00	DOL
0005	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08441		QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0007	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0010	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0013	203-02000		EXCAVATION, COMMON	8213.00	CYS
0014	205-12108		STORMWATER MANAGEMENT BUDGET	34000.00	DOL
0015	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	205-12618		SWQCP PREPARATION	1.00	LS
0017	207-08264		SUBGRADE TREATMENT, TYPE II	622.00	SYS
0018	207-09935		SUBGRADE TREATMENT, TYPE IC	49.00	SYS
0019	207-12635		SUBGRADE TREATMENT, TYPE IBC	6993.00	SYS
0020	211-09264		STRUCTURE BACKFILL, TYPE 1	1048.00	CYS
0021	214-11796		GEOGRID, TYPE IB	367.00	SYS
0022	214-12238		GEOTEXTILE FOR PAVEMENT, TYPE 2A	823.00	SYS
0023	301-12232		COMPACTED AGGREGATE, NO. 5	69.00	CYS
0024	301-12234		COMPACTED AGGREGATE, NO. 53	1592.00	CYS
0025	302-07455		DENSE GRADED SUBBASE	93.00	CYS
0026	303-07449		COMPACTED AGGREGATE, NO. 73	34.00	TON
0027	304-12625		HMA PATCHING, FULL DEPTH, TYPE C	33.00	TON
0028	306-08038		MILLING, ASPHALT, 4 IN.	403.00	SYS
0029	401-000005		QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	419.00	TON
0030	401-000041		QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	695.00	TON
0031	401-000047		QC/QA-HMA, 3, 58S, BASE, 25.0 mm	1904.00	TON

0032	401-11526	JOINT ADHESIVE	1308.00	LFT
0033	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	1302.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0035	502-06457	PCCP, 9 IN.	550.00	SYS
0036	502-11543	PCCP, 4 IN.	353.00	SYS
0037	503-05240	D-1 CONTRACTION JOINT	264.00	LFT
0038	604-08086	CURB RAMP, CONCRETE	31.00	SYS
0039	605-06120	CURB, CONCRETE	842.00	LFT
0040	605-06140	CURB AND GUTTER, CONCRETE	1550.00	LFT
0041	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	418.00	LFT
0042	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	330.00	LFT
0043	605-06215	CENTER CURB, CONCRETE, TYPE D	24.00	LFT
0044	610-07487	HMA FOR APPROACHES, TYPE B	26.00	TON
0045	610-08446	PCCP FOR APPROACHES, 6 IN.	136.00	SYS
0046	610-09108	PCCP FOR APPROACHES, 9 IN.	367.00	SYS
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	1.00	ACH
0048	615-06505	MONUMENT, TYPE B	16.00	ACH
0049	615-06510	MONUMENT, TYPE C	1.00	ACH
0050	615-06515	MONUMENT, TYPE D	12.00	ACH
0051	616-06405	RIPRAP, REVETMENT	7.00	TON
0052	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	7.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0054	621-06560	MULCHED SEEDING, TYPE U	3547.00	SYS
0055	621-06570	TOPSOIL	404.00	CYS
0056	621-08538	MULCH	218.00	CYS
0057	621-09273	WEED BARRIER	480.00	SYS
0058	622-05638	PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	46.00	ACH
0059	622-05640	PLANT, DECIDUOUS SHRUB, 24 IN. TO 36 IN.	7.00	ACH
0060	622-05654	PLANT, PERENNIAL	196.00	ACH
0061	628-09403	FIELD OFFICE, TYPE C	15.00	MOS
0062	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	3547.00	SYS
0063	629-000150	TOPSOIL AMENDMENT BUDGET	7094.00	DOL
0064	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	162.00	LFT
0065	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	1021.00	LFT
0066	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	1239.00	LFT
0067	715-09064	VIDEO INSPECTION FOR PIPE	2422.00	LFT
0068	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	ACH

0069	715-98961	FORCE MAIN	40.00	LFT
0070	716-01382	AIR RELEASE VALVE	2.00	ACH
0071	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	478.00	LFT
0072	720-01092	MANHOLE, TYPE J15, MODIFIED	1.00	ACH
0073	720-08659	MANHOLE, TYPE C5	1.00	ACH
0074	720-08660	MANHOLE, TYPE J5, MODIFIED	1.00	ACH
0075	720-45035	INLET, TYPE F7	5.00	ACH
0076	720-45042	INLET, TYPE HA5	2.00	ACH
0077	720-45235	CATCH BASIN, TYPE E7	1.00	ACH
0078	720-45410	MANHOLE, TYPE C4	1.00	ACH
0079	720-90984	MANHOLE, TYPE C2	1.00	ACH
0080	720-98174	INLET, TYPE B15	7.00	ACH
0081	720-98555	INLET, TYPE C15	9.00	ACH
0082	801-03291	CONSTRUCTION SIGN, TYPE D	6.00	ACH
0083	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	ACH
0084	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	ACH
0085	801-06640	CONSTRUCTION SIGN, TYPE A	30.00	ACH
0086	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	ACH
0087	801-06775	MAINTAINING TRAFFIC	1.00	LS
0088	801-07118	BARRICADE, TYPE III-A	96.00	LFT
0089	801-07119	BARRICADE, TYPE III-B	96.00	LFT
0090	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	206.00	LFT
0091	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	110.00	SFT
0092	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	46.00	SFT
0093	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	348.00	LFT
0094	807-02191	HANDHOLE, LIGHTING	6.00	ACH
0095	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1663.00	LFT
0096	807-11941	LIGHT POLE, 30 FT E.M.H., 5 FT MAST ARM, BREAKAWAY BASE	1.00	ACH
0097	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	12.00	ACH
0098	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	12.00	ACH
0099	807-84492	LIGHT POLE, 30 FT E.M.H., 10 FT MAST ARM, BREAKAWAY BASE	7.00	ACH
0100	807-85502	LIGHT POLE, 30 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	4.00	ACH
0101	807-86805	SERVICE POINT, TYPE I	1.00	ACH
0102	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	990.00	LFT
0103	807-86910	CONNECTOR KIT, UNFUSED	12.00	ACH
0104	807-86915	CONNECTOR KIT, FUSED	12.00	ACH
0105	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	27.00	ACH

0106	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.00	EACH
0107	807-86930	INSULATION LINK, NON-WATERPROOFED	27.00	EACH
0108	807-86935	INSULATION LINK, WATERPROOFED	24.00	EACH
0109	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	251.00	LFT
0110	808-12032	GROOVING FOR PAVEMENT MARKINGS	3326.00	LFT
0111	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	72.00	LFT
0112	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	539.00	LFT
0113	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	2464.00	LFT
0114	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	8.00	EACH

Call: 140

Contract: R -42006-A

Section No.: 1 NEW ROAD CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0014	202-90277	DETECTOR HOUSING, REMOVE	2.00 EACH
0015	203-02000	EXCAVATION, COMMON	93660.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	147216.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	2366.00 SYS
0020	207-08266	SUBGRADE TREATMENT, TYPE III	4453.00 SYS
0021	207-12635	SUBGRADE TREATMENT, TYPE IBC	47190.00 SYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	920.00 CYS
0023	301-12234	COMPACTED AGGREGATE, NO. 53	1487.00 CYS
0024	302-07455	DENSE GRADED SUBBASE	21.00 CYS
0025	303-01180	COMPACTED AGGREGATE, NO. 53	9214.00 TON
0026	304-07493	WIDENING WITH HMA, TYPE B	7.00 TON
0027	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	496.00 TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	25795.00 SYS
0029	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	6132.00 TON
0030	401-000041	QC/QA-HMA, 3, 58H, INTERMEDIATE, 19.0 mm	6742.00 TON
0031	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	15078.00 TON

0032	401-000069	QC/QA-HMA, 4, 58E, BASE, OG, 19.0 mm	5773.00	TON
0033	401-11526	JOINT ADHESIVE	26182.00	LFT
0034	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0035	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	46082.00	LFT
0036	406-05520	ASPHALT FOR TACK COAT	20.00	TON
0037	415-11527	BASE SEAL	292.00	TON
0038	603-06040	FENCE, FARM FIELD, 47 IN.	11297.00	LFT
0039	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	655.00	LFT
0040	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	11538.00	LFT
0041	610-07487	HMA FOR APPROACHES, TYPE B	489.00	TON
0042	610-08446	PCCP FOR APPROACHES, 6 IN.	117.00	SYS
0043	611-06497	MAILBOX ASSEMBLY, SINGLE	10.00	ACH
0044	611-06498	MAILBOX ASSEMBLY, DOUBLE	3.00	ACH
0045	615-06490	RIGHT-OF-WAY MARKER	23.00	ACH
0046	615-06505	MONUMENT, TYPE B	25.00	ACH
0047	615-06527	MONUMENT, SECTION CORNER	4.00	ACH
0048	616-06405	RIPRAP, REVETMENT	1462.00	TON
0049	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	2458.00	SYS
0050	616-93019	RIPRAP, GROUTED, 18 IN.	151.00	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0052	621-06559	MULCHED SEEDING, TYPE R	85822.00	SYS
0053	621-06574	SODDING	14047.00	SYS
0054	621-08161	PERMANENT TURF REINFORCEMENT MAT	423.00	SYS
0055	628-09403	FIELD OFFICE, TYPE C	20.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0057	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	85822.00	SYS
0058	629-000150	TOPSOIL AMENDMENT BUDGET	171644.00	DOL
0059	714-11089	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 11 FT X 4 FT	113.00	LFT
0060	714-11198	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 3 FT	128.00	LFT
0061	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	13034.00	LFT
0062	715-05049	PIPE, TYPE 4, CIRCULAR, DIAMETER 8 IN.	100.00	LFT
0063	715-05052	PIPE, TYPE 4, CIRCULAR, DIAMETER 12 IN.	100.00	LFT
0064	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	730.00	LFT
0065	715-05147	PIPE, TYPE 2, CIRCULAR, DIAMETER 8 IN.	28.00	LFT
0066	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	689.00	LFT
0067	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	229.00	LFT
0068	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	444.00	LFT

0069	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	125.00	LFT
0070	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	866.00	LFT
0071	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	406.00	LFT
0072	715-06337	PIPE EXTENSION, CIRCULAR, DIAMETER 48 IN.	83.00	LFT
0073	715-08653	PIPE, TYPE 1, DEFORMED, MIN. AREA 216.0 SFT	114.00	LFT
0074	715-09064	VIDEO INSPECTION FOR PIPE	3087.00	LFT
0075	715-46000	PIPE END SECTION, DIAMETER 12 IN.	31.00	ACH
0076	715-46005	PIPE END SECTION, DIAMETER 15 IN.	11.00	ACH
0077	715-46010	PIPE END SECTION, DIAMETER 18 IN.	3.00	ACH
0078	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	ACH
0079	718-06531	OUTLET PROTECTOR, TYPE 3	40.00	ACH
0080	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3000.00	LFT
0081	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	8911.00	SYS
0082	718-52610	AGGREGATE FOR UNDERDRAINS	745.00	CYS
0083	720-45335	CATCH BASIN, TYPE E7, MODIFIED	11.00	ACH
0084	720-45410	MANHOLE, TYPE C4	1.00	ACH
0085	720-98174	INLET, TYPE B15	1.00	ACH
0086	720-98555	INLET, TYPE C15	3.00	ACH
0087	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	ACH
0088	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00	ACH
0089	801-06640	CONSTRUCTION SIGN, TYPE A	6.00	ACH
0090	801-06775	MAINTAINING TRAFFIC	1.00	LS
0091	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0092	801-07119	BARRICADE, TYPE III-B	120.00	LFT
0093	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	225.00	LFT
0094	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	161.00	SFT
0095	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	82.00	SFT
0096	805-01479	CONTROLLER CABINET FOUNDATION, TYPE P1, MODIFIED	1.00	ACH
0097	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	ACH
0098	805-01842	HANDHOLE, SIGNAL, TYPE 1	8.00	ACH
0099	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	50.00	LFT
0100	805-06595	CONDUIT, PVC, 2 IN.	2570.00	LFT
0101	805-06600	CONDUIT, PVC, 3 IN.	600.00	LFT
0102	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	7.00	ACH
0103	805-10029	CONDUIT, PVC, 1.25 IN.	45510.00	LFT
0104	805-10234	CONTROLLER AND CABINET, TYPE R	1.00	ACH
0105	805-11888	THERMAL DETECTION SYSTEM	1.00	LS

0106	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	12.00	ACH
0107	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	4.00	ACH
0108	805-78415	SPAN, CATENARY, AND TETHER	4.00	ACH
0109	805-78420	DISCONNECT HANGER	4.00	ACH
0110	805-78445	SIGNAL SERVICE	1.00	ACH
0111	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	60.00	LFT
0112	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	1130.00	LFT
0113	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	390.00	LFT
0114	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	220.00	LFT
0115	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GAUGE	1000.00	LFT
0116	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2520.00	LFT
0117	805-78785	SIGNAL DETECTOR HOUSING	7.00	ACH
0118	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	420.00	LFT
0119	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00	ACH
0120	807-02785	LUMINAIRE, MAST ARM, 25 FT	4.00	ACH
0121	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	4.00	ACH
0122	807-12733	HANDHOLE, ATMS	12.00	ACH
0123	807-95709	PHOTOCELLS	1.00	ACH
0124	807-95889	WIRE, NO. 10 COPPER, 1/C	3100.00	LFT
0125	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0126	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	30390.00	LFT
0127	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	243.00	LFT
0128	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	23383.00	LFT
0129	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	1285.00	LFT
0130	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	15.00	ACH
0131	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	453.00	LFT
0132	808-12032	GROOVING FOR PAVEMENT MARKINGS	55973.00	LFT
0133	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	915.00	LFT
0134	809-06128	CCTV ASSEMBLY	1.00	ACH

Call: 150

Contract: R -42008-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0012	202-02637	PIPE ABANDON AND GROUT FILL	1334.00 LFT
0013	202-06541	REMOVE	11.00 EACH
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00 LS
0015	202-96133	PIPE, REMOVE	320.00 LFT
0016	202-99187	FENCE, FARM FIELD, REMOVE	50.00 LFT
0017	203-02000	EXCAVATION, COMMON	12555.00 CYS
0018	203-08607	LINEAR GRADING	20.00 LFT
0019	203-51223	EXCAVATION, WATERWAY	25.00 CYS
0020	205-11626	PUMP AROUND	4.00 EACH
0021	205-12108	STORMWATER MANAGEMENT BUDGET	15350.00 DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0023	205-12618	SWQCP PREPARATION	1.00 LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	16923.00 SYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	377.00 CYS
0026	211-09267	STRUCTURE BACKFILL, TYPE 4	14.00 CYS
0027	211-09268	STRUCTURE BACKFILL, TYPE 5	24.00 CYS
0028	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	8.00 EACH
0029	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	6.00 CYS
0030	214-11796	GEOGRID, TYPE IB	218.00 SYS
0031	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	70.00 SYS

0032	301-12231	COMPACTED AGGREGATE, NO. 2	250.00	CYS
0033	301-12233	COMPACTED AGGREGATE, NO. 8	21.00	CYS
0034	301-12234	COMPACTED AGGREGATE, NO. 53	145.00	CYS
0035	303-01180	COMPACTED AGGREGATE, NO. 53	1502.00	TON
0036	304-07493	WIDENING WITH HMA, TYPE B	100.00	TON
0037	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	101.00	TON
0038	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1843.00	SYS
0039	309-12695	LEAN CONCRETE BASE, 9 IN.	70.00	SYS
0040	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	1303.00	TON
0041	401-000019	QC/QA-HMA, 2, 58S, INTERMEDIATE, 9.5 mm	1956.00	TON
0042	401-000046	QC/QA-HMA, 2, 58S, BASE, 25.0 mm	4817.00	TON
0043	401-11526	JOINT ADHESIVE	4365.00	LFT
0044	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	4541.00	LFT
0045	406-05520	ASPHALT FOR TACK COAT	16.00	TON
0046	601-06374	GUARDRAIL TRANSITION, TYPE TGS-1	4.00	ACH
0047	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	25.00	LFT
0048	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	ACH
0049	603-97461	TEMPORARY FENCE	487.00	LFT
0050	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	63.00	LFT
0051	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	76.00	SYS
0052	610-07487	HMA FOR APPROACHES, TYPE B	312.00	TON
0053	611-06497	MAILBOX ASSEMBLY, SINGLE	7.00	ACH
0054	615-06490	RIGHT-OF-WAY MARKER	59.00	ACH
0055	615-06505	MONUMENT, TYPE B	8.00	ACH
0056	616-05688	RIPRAP, CLASS 1	209.00	TON
0057	616-06405	RIPRAP, REVETMENT	1511.00	TON
0058	616-06451	RIPRAP, UNIFORM	158.00	TON
0059	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	132.00	SYS
0060	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	110.00	SYS
0061	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	2352.00	SYS
0062	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0063	621-06559	MULCHED SEEDING, TYPE R	1234.00	SYS
0064	621-06567	WATER	11.00	KGAL
0065	621-06570	TOPSOIL	453.00	CYS
0066	621-06575	SODDING, NURSERY	2716.00	SYS
0067	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0068	628-12683	FIELD OFFICE, TYPE D	16.00	MOS

0069	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	3950.00	SYS
0070	629-000150	TOPSOIL AMENDMENT BUDGET	7900.00	DOL
0071	702-51863	FIELD DRILLED HOLE IN CONCRETE	60.00	ACH
0072	703-06029	REINFORCING BARS, EPOXY COATED	9043.00	LBS
0073	704-51002	CONCRETE, C, SUPERSTRUCTURE	39.20	CYS
0074	706-06344	RAILING, STEEL TYPE TS-1	100.00	LFT
0075	707-11443	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 17 IN. X 36 IN.	107.00	LFT
0076	707-11497	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 17 IN. X 48 IN.	320.00	LFT
0077	710-09158	PATCHING CONCRETE STRUCTURES	60.00	SFT
0078	714-000086	WATERPROOFING MEMBRANE, TYPE 2	1014.00	SFT
0079	714-11192	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 3 FT	48.00	LFT
0080	714-11197	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 3 FT X 2 FT	46.00	LFT
0081	715-02388	WATER MAIN	30.00	ACH
0082	715-02743	GATE VALVE WITH VALVE BOX, 4 IN.	4.00	ACH
0083	715-04522	PIPE END SECTION, DIAMETER 42 IN.	2.00	ACH
0084	715-04612	PIPE	100.00	LFT
0085	715-05052	PIPE, TYPE 4, CIRCULAR, DIAMETER 12 IN.	50.00	LFT
0086	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	54.00	LFT
0087	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	426.00	LFT
0088	715-05217	PIPE, TYPE 5, CIRCULAR, DIAMETER 12 IN.	72.00	LFT
0089	715-06050	CAP	2.00	ACH
0090	715-06050	CAP	3.00	ACH
0091	715-07794	WATER MAIN CONNECTIONS	1.00	ACH
0092	715-07794	WATER MAIN CONNECTIONS	1.00	ACH
0093	715-07794	WATER MAIN CONNECTIONS	1.00	ACH
0094	715-07794	WATER MAIN CONNECTIONS	1.00	ACH
0095	715-07806	PIPE, STEEL CASING	194.00	LFT
0096	715-07806	PIPE, STEEL CASING	40.00	LFT
0097	715-11896	WATER SERVICE CONNECTION	4.00	ACH
0098	715-11896	WATER SERVICE CONNECTION	5.00	ACH
0099	715-12166	GATE VALVE WITH VALVE BOX 2 IN	2.00	ACH
0100	715-46005	PIPE END SECTION, DIAMETER 15 IN.	18.00	ACH
0101	715-92525	WATER MAIN, 10 IN.	2040.00	LFT
0102	715-92525	WATER MAIN, 10 IN.	40.00	LFT
0103	715-93911	WATER MAIN, 4 IN.	194.00	LFT
0104	715-93911	WATER MAIN, 4 IN.	100.00	LFT
0105	715-97873	WATER SERVICE LINE, 1 IN.	250.00	ACH

0106	715-98479	GATE VALVE AND BOX, 10 IN.	4.00	ACH
0107	720-45035	INLET, TYPE F7	1.00	ACH
0108	720-96999	FIRE HYDRANT ASSEMBLY	2.00	ACH
0109	720-96999	FIRE HYDRANT ASSEMBLY	1.00	ACH
0110	720-98174	INLET, TYPE B15	2.00	ACH
0111	722-12732	LONGITUDINAL GROOVING	269.00	SYS
0112	726-92406	BEARING ASSEMBLY, ELASTOMERIC	32.00	ACH
0113	732-05538	TESTING AND DISINFECTION	1.00	LS
0114	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	ACH
0115	801-06625	DETOUR ROUTE MARKER ASSEMBLY	17.00	ACH
0116	801-06640	CONSTRUCTION SIGN, TYPE A	15.00	ACH
0117	801-06645	CONSTRUCTION SIGN, TYPE B	4.00	ACH
0118	801-06775	MAINTAINING TRAFFIC	1.00	LS
0119	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0120	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0121	802-04089	SIGN, SHEET, REMOVE	4.00	ACH
0122	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	150.00	LFT
0123	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	17.00	ACH
0124	802-09837	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	6.00	SFT
0125	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	71.00	SFT
0126	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	150.00	LFT
0127	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	150.00	LFT
0128	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	8468.00	LFT
0129	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	8782.00	LFT
0130	808-75140	PAVEMENT MESSAGE MARKING, PAINT, RXR	2.00	ACH
0131	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	97.00	LFT
0132	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	116.00	ACH

Call: 170

Contract: R -42543-A

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0010	202-02272	PAVED SIDE DITCH, REMOVE	10.00 LFT
0011	202-96133	PIPE, REMOVE	29.00 LFT
0012	207-08264	SUBGRADE TREATMENT, TYPE II	38.00 SYS
0013	211-09265	STRUCTURE BACKFILL, TYPE 2	31.00 CYS
0014	214-11796	GEOGRID, TYPE IB	38.00 SYS
0015	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	7.00 SYS
0016	301-12232	COMPACTED AGGREGATE, NO. 5	1.00 CYS
0017	303-07449	COMPACTED AGGREGATE, NO. 73	2.00 TON
0018	306-08034	MILLING, ASPHALT, 1 1/2 IN.	228.00 SYS
0019	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	20.00 TON
0020	401-11526	JOINT ADHESIVE	150.00 LFT
0021	406-05520	ASPHALT FOR TACK COAT	0.30 TON
0022	607-06340	PAVED SIDE DITCH, TYPE B	10.00 LFT
0023	615-06490	RIGHT-OF-WAY MARKER	4.00 EACH
0024	616-05688	RIPRAP, CLASS 1	50.00 TON
0025	616-06941	GROUT	5.00 CYS
0026	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	72.00 SYS
0027	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0028	621-02770	EROSION CONTROL BLANKET	250.00 SYS
0029	621-06559	MULCHED SEEDING, TYPE R	200.00 SYS
0030	621-06574	SODDING	15.00 SYS
0031	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH

0032	628-12683	FIELD OFFICE, TYPE D	5.00	MOS
0033	715-05121	PIPE, TYPE 1, CIRCULAR, DIAMETER 18 IN.	59.00	LFT
0034	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	28.00	TON
0035	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0036	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0037	801-06206	TEMPORARY PAVEMENT MARKING, 6 IN.	220.00	LFT
0038	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	220.00	LFT
0039	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH
0040	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	EACH
0041	801-06775	MAINTAINING TRAFFIC	1.00	LS
0042	801-07118	BARRICADE, TYPE III-A	70.00	LFT
0043	801-07119	BARRICADE, TYPE III-B	55.00	LFT
0044	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	20.00	LFT
0045	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	100.00	LFT
0046	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	100.00	LFT
0047	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH
0048	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00	EACH

Call: 180

Contract: R -43031-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0012	202-74035	SIGN, REMOVE	10.00 EACH
0013	202-94747	POST, REMOVE	6.00 EACH
0014	203-02000	EXCAVATION, COMMON	10.00 CYS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	773.00 SYS
0016	211-02050	B BORROW	5.00 CYS
0017	214-11796	GEOGRID, TYPE IB	773.00 SYS
0018	303-07449	COMPACTED AGGREGATE, NO. 73	213.00 TON
0019	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	511.00 TON
0020	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	15.00 TON
0021	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	48.00 TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	12557.00 SYS
0023	306-08432	MILLING, APPROACH	127.00 SYS
0024	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	1037.00 TON
0025	401-12169	INERTIAL PROFILER, HMA	1.00 LS
0026	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	6889.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	6.00 TON
0028	601-06035	GUARDRAIL, RESET	30.00 LFT
0029	610-07487	HMA FOR APPROACHES, TYPE B	11.00 TON
0030	615-06520	MONUMENT, RE-ESTABLISH	3.00 EACH
0031	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH

0032	621-06560	MULCHED SEEDING, TYPE U	48.00	SYS
0033	621-06570	TOPSOIL	5.00	CYS
0034	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0035	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0036	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.00	ACH
0037	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	5764.00	LFT
0038	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	12.00	LFT
0039	801-06640	CONSTRUCTION SIGN, TYPE A	27.00	ACH
0040	801-06645	CONSTRUCTION SIGN, TYPE B	9.00	ACH
0041	801-06775	MAINTAINING TRAFFIC	1.00	LS
0042	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	ACH
0043	801-07119	BARRICADE, TYPE III-B	96.00	LFT
0044	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	30.00	LFT
0045	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	274.00	LFT
0046	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	4.00	ACH
0047	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	11.00	LFT
0048	802-07057	SIGN, PANEL, WITH LEGEND	268.00	SFT
0049	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	60.00	SFT
0050	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00	SFT
0051	802-96994	SIGN POST, TIMBER, 4 IN. X 6 IN.	153.00	LFT
0052	804-11921	DELINEATOR POST, FLEXIBLE, TYPE II	17.00	ACH
0053	805-11379	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 45 FT	1.00	ACH
0054	805-11380	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 50 FT	1.00	ACH
0055	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE B	2.00	ACH
0056	808-06716	LINE, REMOVE	545.00	LFT
0057	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0058	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 12 IN.	438.00	LFT
0059	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	7618.00	LFT
0060	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	2.00	ACH
0061	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	9312.00	LFT
0062	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	570.00	LFT
0063	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	5.00	ACH
0064	808-10192	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, BIKE SYMBOL	1.00	ACH
0065	808-11516	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, PED XING	1.00	ACH
0066	808-12032	GROOVING FOR PAVEMENT MARKINGS	16884.00	LFT
0067	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	40.00	LFT
0068	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	245.00	LFT

0069	808-12851	LINE, MULTI-COMPONENT, DOTTED, WHITE, 10 IN.	195.00	LFT
0070	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	145.00	EACH
0071	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	136.00	EACH

Call: 200

Contract: R -43476-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0012	202-91385	INLET, REMOVE	2.00 :ACH
0013	202-93047	MANHOLE, REMOVE	1.00 :ACH
0014	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	2.00 :ACH
0015	202-96133	PIPE, REMOVE	407.00 LFT
0016	203-02070	BORROW	3607.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	15738.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	395.00 SYS
0021	207-12635	SUBGRADE TREATMENT, TYPE IBC	9058.00 SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	545.00 CYS
0023	214-11796	GEOGRID, TYPE IB	395.00 SYS
0024	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	9328.00 SYS
0025	301-12234	COMPACTED AGGREGATE, NO. 53	1094.00 CYS
0026	302-07455	DENSE GRADED SUBBASE	66.00 CYS
0027	303-01180	COMPACTED AGGREGATE, NO. 53	1144.00 TON
0028	306-08036	MILLING, ASPHALT, 2 IN.	547.00 SYS
0029	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	775.00 TON
0030	401-000037	QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	949.00 TON
0031	401-000052	QC/QA-HMA, 2, 58S, BASE, 19.0 mm	1329.00 TON

0032	401-000067	QC/QA-HMA, 4, 58E, INTERMEDIATE, OG, 19.0 mm	1048.00 TON
0033	401-11526	JOINT ADHESIVE	3975.00 LFT
0034	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	4431.00 LFT
0035	406-05520	ASPHALT FOR TACK COAT	8.00 TON
0036	502-11564	PCCP, 7 IN.	664.00 SYS
0037	503-05240	D-1 CONTRACTION JOINT	458.00 LFT
0038	605-06090	CURB, INTEGRAL CONCRETE	470.00 LFT
0039	605-06140	CURB AND GUTTER, CONCRETE	1182.00 LFT
0040	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	311.00 LFT
0041	605-06205	CENTER CURB, CONCRETE, TYPE B	557.00 LFT
0042	605-97937	CURB AND GUTTER, ROLLED CURB	315.00 LFT
0043	610-09108	PCCP FOR APPROACHES, 9 IN.	358.00 SYS
0044	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0045	615-06490	RIGHT-OF-WAY MARKER	32.00 EACH
0046	615-06505	MONUMENT, TYPE B	23.00 EACH
0047	615-06515	MONUMENT, TYPE D	11.00 EACH
0048	616-06405	RIPRAP, REVETMENT	121.00 TON
0049	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	179.00 SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0051	621-03909	SEED MIXTURE, NATIVE	7.00 LBS
0052	621-06565	MULCHING MATERIAL	1.00 TON
0053	621-06567	WATER	37.00 kGAL
0054	621-06574	SODDING	8739.00 SYS
0055	628-09403	FIELD OFFICE, TYPE C	6.00 MOS
0056	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	9119.00 SYS
0057	629-000150	TOPSOIL AMENDMENT BUDGET	18238.00 DOL
0058	715-05024	PIPE, TYPE 2, CIRCULAR, DIAMETER 36 IN.	215.00 LFT
0059	715-05032	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	368.00 LFT
0060	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	3354.00 LFT
0061	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	224.00 LFT
0062	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	101.00 LFT
0063	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	288.00 LFT
0064	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	27.00 LFT
0065	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00 EACH
0066	715-46005	PIPE END SECTION, DIAMETER 15 IN.	8.00 EACH
0067	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00 EACH
0068	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00 EACH

0069	718-06528	OUTLET PROTECTOR, TYPE 1	6.00	ACH
0070	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	2299.00	SYS
0071	718-52610	AGGREGATE FOR UNDERDRAINS	302.00	CYS
0072	720-45040	INLET, TYPE G7	2.00	ACH
0073	720-45410	MANHOLE, TYPE C4	2.00	ACH
0074	720-45510	MANHOLE, TYPE C4, MODIFIED	1.00	ACH
0075	720-93501	MANHOLE, TYPE L4	1.00	ACH
0076	720-94612	MANHOLE, TYPE K4	3.00	ACH
0077	720-98174	INLET, TYPE B15	1.00	ACH
0078	720-98555	INLET, TYPE C15	1.00	ACH
0079	720-99416	CATCH BASIN, TYPE B15	6.00	ACH
0080	720-99417	CATCH BASIN, TYPE C15	1.00	ACH
0081	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	ACH
0082	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00	ACH
0083	801-06640	CONSTRUCTION SIGN, TYPE A	28.00	ACH
0084	801-06775	MAINTAINING TRAFFIC	1.00	LS
0085	801-07118	BARRICADE, TYPE III-A	96.00	LFT
0086	801-07119	BARRICADE, TYPE III-B	144.00	LFT
0087	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	ACH
0088	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	340.00	LFT
0089	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	56.00	LFT
0090	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	14.00	ACH
0091	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	141.00	SFT
0092	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	110.00	SFT
0093	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	232.00	LFT
0094	807-02191	HANDHOLE, LIGHTING	7.00	ACH
0095	807-03758	LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 24 IN. X 24 IN. X 96 IN.	15.00	ACH
0096	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	4301.00	LFT
0097	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	15.00	ACH
0098	807-83748	LIGHT POLE, 40 FT E.M.H., 8 FT MAST ARM, ANCHOR BASE	15.00	ACH
0099	807-86810	SERVICE POINT, TYPE II	1.00	ACH
0100	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1200.00	LFT
0101	807-86910	CONNECTOR KIT, UNFUSED	15.00	ACH
0102	807-86915	CONNECTOR KIT, FUSED	15.00	ACH
0103	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	44.00	ACH
0104	807-86935	INSULATION LINK, WATERPROOFED	88.00	ACH
0105	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	464.00	LFT

0106	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	72.00	LFT
0107	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	189.00	LFT
0108	808-12032	GROOVING FOR PAVEMENT MARKINGS	6514.00	LFT
0109	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1823.00	LFT
0110	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	4502.00	LFT
0111	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	72.00	LFT

Call: 230

Contract: R -43693-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	203-02000	EXCAVATION, COMMON	3204.00	CYS
0012	203-08607	LINEAR GRADING	9724.00	LFT
0013	205-12108	STORMWATER MANAGEMENT BUDGET	9009.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	207-08264	SUBGRADE TREATMENT, TYPE II	2371.00	SYS
0016	214-11796	GEOGRID, TYPE IB	2371.00	SYS
0017	303-01180	COMPACTED AGGREGATE, NO. 53	6421.00	TON
0018	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	162.00	TON
0019	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	27.00	TON
0020	304-12627	HMA PATCHING, FULL DEPTH, TYPE D	2055.00	TON
0021	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	2314.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	24794.00	SYS
0023	306-08036	MILLING, ASPHALT, 2 IN.	350454.00	SYS
0024	309-12695	LEAN CONCRETE BASE, 9 IN.	235.00	SYS
0025	401-000005	QC/QA-HMA, 3, 58H, SURFACE, 9.5 mm	8299.00	TON
0026	401-000008	QC/QA-HMA, 3, 58E, SURFACE, 9.5 mm	1411.00	TON
0027	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0028	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	6580.00	LFT
0029	401-12664	HMA SPRAY PAVER EMULSION	20.00	TON
0030	406-05520	ASPHALT FOR TACK COAT	27.00	TON
0031	410-000073	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm - SMA	30734.00	TON

0032	410-12466	VOID REDUCING ASPHALT MEMBRANE FOR SMA	171793.00	LFT
0033	410-12665	SMA SPRAY PAVER EMULSION	235.00	TON
0034	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	32.00	SFT
0035	506-06333	PCCP PATCHING, FULL DEPTH	235.00	SYS
0036	509-12191	JOINT REPAIR, PARTIAL DEPTH	350.00	SFT
0037	509-12192	JOINT REPAIR, BOTTOM-HALF	8.00	SFT
0038	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	159454.00	LFT
0039	628-12683	FIELD OFFICE, TYPE D	10.00	MOS
0040	718-09978	UNDERDRAIN OUTLET INSPECTION	254.00	ACH
0041	718-09979	UNDERDRAIN OUTLET CLEANING	254.00	ACH
0042	801-000138	SMART ARROW BOARD	675.00	DAY
0043	801-000209	CONNECTED WORK ZONE LOCATION MARKERS	10.00	ACH
0044	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	21280.00	LFT
0045	801-06640	CONSTRUCTION SIGN, TYPE A	123.00	ACH
0046	801-06775	MAINTAINING TRAFFIC	1.00	LS
0047	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0048	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	10.00	ACH
0049	801-12042	TRUCK MOUNTED ATTENUATOR	675.00	DAY
0050	801-12324	LAW ENFORCEMENT OFFICER	1200.00	HRS
0051	801-12594	DIGITAL SPEED LIMIT SIGN ASSEMBLY	16.00	ACH
0052	801-12652	QUEUE TRUCK	240.00	DAY
0053	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	125.00	LFT
0054	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	45.00	LFT
0055	808-06716	LINE, REMOVE	3371.00	LFT
0056	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0057	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	89834.00	LFT
0058	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	89834.00	LFT
0059	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	22083.00	LFT
0060	808-12032	GROOVING FOR PAVEMENT MARKINGS	205677.00	LFT
0061	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	1674.00	LFT
0062	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	3650.00	LFT
0063	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	1026.00	LFT
0064	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1194.00	ACH
0065	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	892.00	ACH
0066	809-11763	WEIGH-IN-MOTION STATION, REBUILD	1.00	LS

Call: 240

Contract: R -43831-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	205-12108	STORMWATER MANAGEMENT BUDGET	1000.00	DOL
0010	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0011	615-06490	RIGHT-OF-WAY MARKER	4.00	ACH
0012	616-05688	RIPRAP, CLASS 1	38.00	TON
0013	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	42.00	SYS
0014	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0015	621-06559	MULCHED SEEDING, TYPE R	600.00	SYS
0016	628-09401	FIELD OFFICE, TYPE A	5.00	MOS
0017	702-03607	CORED HOLE IN CONCRETE	12.00	ACH
0018	703-01540	THREADED TIE BAR ASSEMBLY	6.00	ACH
0019	710-09158	PATCHING CONCRETE STRUCTURES	9.00	SFT
0020	711-51035	STRUCTURAL STEEL	870.00	LBS
0021	711-91996	REPAIR EXISTING STRUCTURE	1.00	LS
0022	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	12.00	GAL
0023	727-90308	EPOXY INJECTION, CRACK PREPARATION	40.00	LFT
0024	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0025	801-06640	CONSTRUCTION SIGN, TYPE A	14.00	ACH
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	6.00	ACH

Call: 260

Contract: R -43907-A

Section No.: 1 INTERSECTION IMPROVEMENT, MEDIAN U-TURN

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	6.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0014	202-02240	PAVEMENT REMOVAL	65.00 SYS
0015	202-02637	PIPE ABANDON AND GROUT FILL	141.00 LFT
0016	202-02928	CATCH BASIN, REMOVE	2.00 EACH
0017	202-96133	PIPE, REMOVE	280.00 LFT
0018	203-02000	EXCAVATION, COMMON	4588.00 CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	31467.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	210.00 SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	12195.00 SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	709.00 CYS
0025	214-11796	GEOGRID, TYPE IB	65.00 SYS
0026	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	577.00 SYS
0027	301-12233	COMPACTED AGGREGATE, NO. 8	343.00 CYS
0028	301-12234	COMPACTED AGGREGATE, NO. 53	2545.00 CYS
0029	303-01180	COMPACTED AGGREGATE, NO. 53	670.00 TON
0030	304-07789	WIDENING WITH HMA, TYPE D	168.00 TON
0031	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	99.00 TON

0032	306-08038	MILLING, ASPHALT, 4 IN.	449.00	SYS
0033	306-08043	MILLING, TRANSITION	1045.00	SYS
0034	306-11872	MILLING, PROFILE	12300.00	SYS
0035	401-000008	QC/QA-HMA, 3, 58E, SURFACE, 9.5 mm	1885.00	TON
0036	401-000044	QC/QA-HMA, 3, 58E, INTERMEDIATE, 19.0 mm	1225.00	TON
0037	401-000053	QC/QA-HMA, 3, 58S, BASE, 19.0 mm	3425.00	TON
0038	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	14038.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	15.00	TON
0040	502-06999	PCCP, 8 IN.	42.00	SYS
0041	603-03398	FENCE, RELOCATE	490.00	LFT
0042	604-06070	SIDEWALK, CONCRETE	25.00	SYS
0043	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	130.00	LFT
0044	605-06245	CENTER CURB, CONCRETE, TYPE B	605.00	SYS
0045	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	4220.00	LFT
0046	610-07487	HMA FOR APPROACHES, TYPE B	988.00	TON
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	4.00	ACH
0048	615-06490	RIGHT-OF-WAY MARKER	18.00	ACH
0049	616-06451	RIPRAP, UNIFORM	282.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	503.00	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0052	621-06559	MULCHED SEEDING, TYPE R	3665.00	SYS
0053	621-06574	SODDING	6352.00	SYS
0054	628-09403	FIELD OFFICE, TYPE C	9.00	MOS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	ACH
0056	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	10017.00	SYS
0057	629-000150	TOPSOIL AMENDMENT BUDGET	20034.00	DOL
0058	715-05119	PIPE, TYPE 1, CIRCULAR, DIAMETER 15 IN.	154.00	LFT
0059	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	303.00	LFT
0060	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	460.00	LFT
0061	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	558.00	LFT
0062	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	178.00	LFT
0063	715-05169	PIPE, TYPE 3, CIRCULAR, DIAMETER 15 IN.	35.00	LFT
0064	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	47.00	TON
0065	715-46005	PIPE END SECTION, DIAMETER 15 IN.	5.00	ACH
0066	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	ACH
0067	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	ACH
0068	720-45065	INLET, TYPE N12	1.00	ACH

0069	720-45066	INLET, TYPE N12, MODIFIED	1.00	ACH
0070	720-45069	INLET, TYPE P12	1.00	ACH
0071	720-45069	INLET, TYPE P12	1.00	ACH
0072	720-45235	CATCH BASIN, TYPE E7	6.00	ACH
0073	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	ACH
0074	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	24510.00	LFT
0075	801-06640	CONSTRUCTION SIGN, TYPE A	22.00	ACH
0076	801-06645	CONSTRUCTION SIGN, TYPE B	4.00	ACH
0077	801-06710	FLASHING ARROW SIGN	120.00	DAY
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	5.00	ACH
0080	801-07119	BARRICADE, TYPE III-B	96.00	LFT
0081	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3310.00	LFT
0082	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	322.00	LFT
0083	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	213.00	LFT
0084	802-07057	SIGN, PANEL, WITH LEGEND	108.00	SFT
0085	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	9.00	ACH
0086	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	68.00	SFT
0087	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	268.00	SFT
0088	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	16.00	SFT
0089	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE A	4.00	ACH
0090	802-76095	STRUCTURAL STEEL, BREAKAWAY	693.00	LBS
0091	802-91122	SIGN, GROUND MOUNTED, RESET	2.00	ACH
0092	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	438.00	LFT
0093	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	21.00	ACH
0094	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	21.00	ACH
0095	807-85762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	21.00	ACH
0096	807-86810	SERVICE POINT, TYPE II	1.00	ACH
0097	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1260.00	LFT
0098	807-86910	CONNECTOR KIT, UNFUSED	21.00	ACH
0099	807-86915	CONNECTOR KIT, FUSED	21.00	ACH
0100	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	53.00	ACH
0101	807-86935	INSULATION LINK, WATERPROOFED	52.00	ACH
0102	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	4213.00	LFT
0103	808-06716	LINE, REMOVE	6260.00	LFT
0104	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0105	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	173.00	LFT

0106	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	8256.00	LFT
0107	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	71.00	LFT
0108	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	4959.00	LFT
0109	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	1055.00	LFT
0110	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	14.00	EACH
0111	808-10097	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 27 IN.	48.00	LFT
0112	808-10101	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 8 IN.	133.00	LFT
0113	808-12032	GROOVING FOR PAVEMENT MARKINGS	14443.00	LFT
0114	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	74.00	EACH
0115	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	127.00	EACH

Call: 280

Contract: R -44814-A

Section No.: 1 IDIQ, PAVEMENT PATCHING

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0007	110-12655		MOBILIZATION AND DEMOBILIZATION, IDIQ	50000.00	DOL
0008	202-02240		PAVEMENT REMOVAL	500.00	SYS
0009	202-52710		SIDEWALK CONCRETE, REMOVE	60.00	SYS
0010	203-02000		EXCAVATION, COMMON	35.00	CYS
0011	303-01180		COMPACTED AGGREGATE, NO. 53	100.00	TON
0012	303-07449		COMPACTED AGGREGATE, NO. 73	70.00	TON
0013	304-12625		HMA PATCHING, FULL DEPTH, TYPE C	300.00	TON
0014	304-12626		HMA PATCHING, PARTIAL DEPTH, TYPE C	300.00	TON
0015	304-12627		HMA PATCHING, FULL DEPTH, TYPE D	250.00	TON
0016	304-12628		HMA PATCHING, PARTIAL DEPTH, TYPE D	250.00	TON
0017	306-08034		MILLING, ASPHALT, 1 1/2 IN.	5000.00	SYS
0018	306-08036		MILLING, ASPHALT, 2 IN.	5000.00	SYS
0019	401-11526		JOINT ADHESIVE	7500.00	LFT
0020	402-07452		HMA WEDGE AND LEVEL, TYPE C	250.00	TON
0021	402-07787		HMA WEDGE AND LEVEL, TYPE D	250.00	TON
0022	406-05520		ASPHALT FOR TACK COAT	6.00	TON
0023	503-03489		RETROFITTED TIE BARS	60.00	EACH
0024	503-05240		D-1 CONTRACTION JOINT	115.00	LFT
0025	506-06333		PCCP PATCHING, FULL DEPTH	425.00	SYS
0026	506-06334		PCCP PATCHING, PARTIAL DEPTH	300.00	SYS
0027	507-08269		CRACKS IN PCCP, FILLED	4000.00	LFT
0028	507-08272		JOINTS IN PCCP, SAW AND SEAL	3500.00	LFT
0029	604-06070		SIDEWALK, CONCRETE	5.00	SYS
0030	604-08086		CURB RAMP, CONCRETE	50.00	SYS
0031	605-06120		CURB, CONCRETE	60.00	LFT

0032	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2500.00	LFT
0033	801-06640	CONSTRUCTION SIGN, TYPE A	150.00	EACH
0034	801-06645	CONSTRUCTION SIGN, TYPE B	10.00	EACH
0035	801-06710	FLASHING ARROW SIGN	100.00	DAY
0036	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0037	801-12042	TRUCK MOUNTED ATTENUATOR	10.00	DAY
0038	801-12440	MAINTAINING TRAFFIC, IDIQ	100000.00	DOL
0039	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	2600.00	LFT
0040	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	2600.00	LFT
0041	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	5280.00	LFT
0042	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	5280.00	LFT
0043	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	EACH
0044	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.00	EACH

Call: 300

Contract: R -44966-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0011	202-52710	SIDEWALK CONCRETE, REMOVE	155.00 SYS
0012	203-02000	EXCAVATION, COMMON	33.00 CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	4473.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	207-08264	SUBGRADE TREATMENT, TYPE II	56.00 SYS
0016	211-09264	STRUCTURE BACKFILL, TYPE 1	83.00 CYS
0017	214-11796	GEOGRID, TYPE IB	56.00 SYS
0018	301-12234	COMPACTED AGGREGATE, NO. 53	4.00 CYS
0019	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	11.00 TON
0020	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2225.00 SYS
0021	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	184.00 TON
0022	401-11526	JOINT ADHESIVE	2790.00 LFT
0023	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0024	604-06070	SIDEWALK, CONCRETE	96.00 SYS
0025	604-07092	BED COURSE MATERIAL	4.00 TON
0026	605-02278	CURB, REMOVE	69.00 LFT
0027	605-06120	CURB, CONCRETE	98.00 LFT
0028	605-06140	CURB AND GUTTER, CONCRETE	64.00 LFT
0029	616-06405	RIPRAP, REVETMENT	25.00 TON
0030	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	58.00 SYS
0031	621-06567	WATER	2.00 kGAL

0032	621-06575	SODDING, NURSERY	356.00	SYS
0033	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	183.00	LFT
0034	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	120.00	LFT
0035	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	6.00	TON
0036	715-09064	VIDEO INSPECTION FOR PIPE	303.00	LFT
0037	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	ACH
0038	715-92253	SEWER SANITARY LATERAL RECONNECT	1.00	ACH
0039	720-45030	INLET, TYPE E7	1.00	ACH
0040	720-45035	INLET, TYPE F7	2.00	ACH
0041	720-45045	INLET, TYPE J10	2.00	ACH
0042	720-45055	INLET, TYPE M10	2.00	ACH
0043	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	ACH
0044	801-06645	CONSTRUCTION SIGN, TYPE B	1.00	ACH
0045	801-06775	MAINTAINING TRAFFIC	1.00	LS
0046	801-07118	BARRICADE, TYPE III-A	36.00	LFT
0047	801-07119	BARRICADE, TYPE III-B	113.00	LFT
0048	801-11990	TEMPORARY CURB RAMP	1.00	ACH
0049	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	66.00	LFT
0050	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	5.00	ACH
0051	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	152.00	LFT
0052	808-12316	TRANSVERSE MARKING, PAINT, PARKING LINE, WHITE, 4 IN.	760.00	LFT
0053	808-75056	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 8 IN.	346.00	LFT
0054	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	36.00	LFT
0055	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	2.00	ACH

Call: 310

Contract: R -45553-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-93615	CONCRETE, REMOVE	169.00	SYS
0011	207-08264	SUBGRADE TREATMENT, TYPE II	1402.00	SYS
0012	207-08266	SUBGRADE TREATMENT, TYPE III	169.00	SYS
0013	214-11796	GEOGRID, TYPE IB	1571.00	SYS
0014	302-07455	DENSE GRADED SUBBASE	29.00	CYS
0015	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	387.00	TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	10892.00	SYS
0017	306-08599	MILLING, ASPHALT, 1/2 IN.	7180.00	SYS
0018	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	1492.00	TON
0019	401-11526	JOINT ADHESIVE	11142.00	LFT
0020	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0021	502-06999	PCCP, 8 IN.	169.00	SYS
0022	503-05240	D-1 CONTRACTION JOINT	120.00	LFT
0023	615-97768	PARKING BARRIER, RESET	32.00	ACH
0024	628-09403	FIELD OFFICE, TYPE C	6.00	MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0026	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	14.00	ACH
0027	801-06640	CONSTRUCTION SIGN, TYPE A	6.00	ACH
0028	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 320

Contract: R -45581-A

Section No.: 1 PAVEMENT PATCHING

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	304-12628	HMA PATCHING, PARTIAL DEPTH, TYPE D	1650.00	TON
0010	503-09261	PCCP STITCHING	56.00	ACH
0011	509-12191	JOINT REPAIR, PARTIAL DEPTH	28.00	SFT
0012	801-000138	SMART ARROW BOARD	240.00	DAY
0013	801-000209	CONNECTED WORK ZONE LOCATION MARKERS	4.00	ACH
0014	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	222666.00	LFT
0015	801-06640	CONSTRUCTION SIGN, TYPE A	76.00	ACH
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
0017	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	ACH
0018	801-12042	TRUCK MOUNTED ATTENUATOR	240.00	DAY
0019	801-12594	DIGITAL SPEED LIMIT SIGN ASSEMBLY	8.00	ACH
0020	808-06716	LINE, REMOVE	256423.00	LFT
0021	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0022	808-12842	LINE, PAINT, DOTTED, WHITE, 6 IN.	855.00	LFT
0023	808-12973	LINE, PAINT, SOLID, WHITE, 10 IN.	4137.00	LFT
0024	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	27576.00	LFT
0025	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	110300.00	LFT
0026	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	110300.00	LFT
0027	808-75072	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 24 IN.	693.00	LFT
0028	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	276.00	ACH

Call: 330

Contract: R -45636-A

Section No.: 1 HMA OVERLAY, PREVENTIVE MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
0001	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360		CONTRACT LIENS	1.00	DOL
0004	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-01015		CLEARING AND GRUBBING	1.00	LS
0011	202-02637		PIPE ABANDON AND GROUT FILL	23.00	LFT
0012	202-02928		CATCH BASIN, REMOVE	1.00	ACH
0013	202-96133		PIPE, REMOVE	165.00	LFT
0014	203-02000		EXCAVATION, COMMON	435.00	CYS
0015	205-12108		STORMWATER MANAGEMENT BUDGET	3035.00	DOL
0016	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	207-08264		SUBGRADE TREATMENT, TYPE II	469.00	SYS
0018	211-09265		STRUCTURE BACKFILL, TYPE 2	54.00	CYS
0019	214-11796		GEOGRID, TYPE IB	469.00	SYS
0020	301-12233		COMPACTED AGGREGATE, NO. 8	22.00	CYS
0021	301-12234		COMPACTED AGGREGATE, NO. 53	79.00	CYS
0022	304-12623		HMA PATCHING, FULL DEPTH, TYPE B	129.00	TON
0023	306-08563		MILLING, ASPHALT, 1 1/4 IN.	3462.00	SYS
0024	401-000002		QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	280.00	TON
0025	401-11526		JOINT ADHESIVE	3462.00	LFT
0026	406-05521		ASPHALT FOR TACK COAT	3996.00	SYS
0027	603-06065		FENCE, CHAIN LINK, RESET	140.00	LFT
0028	615-11537		PARKING BARRIER, CONCRETE	4.00	ACH
0029	615-97768		PARKING BARRIER, RESET	4.00	ACH
0030	616-06405		RIPRAP, REVETMENT	12.00	TON
0031	616-12246		GEOTEXTILE FOR RIPRAP, TYPE 1A	27.00	SYS

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0033	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00	TON
0034	621-06560	MULCHED SEEDING, TYPE U	727.00	SYS
0035	621-06567	WATER	2.00	kGAL
0036	621-06575	SODDING, NURSERY	339.00	SYS
0037	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	181.00	LFT
0038	715-08283	PCCP FOR STRUCTURE INSTALLATION	5.00	SYS
0039	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	ACH
0040	720-45042	INLET, TYPE HAS	1.00	ACH
0041	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0042	802-03896	BOLLARD	2.00	ACH
0043	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	6.00	SFT
0044	802-76065	SIGN POST, TYPE B	21.00	LFT
0045	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2219.00	LFT
0046	808-06716	LINE, REMOVE	99.00	LFT
0047	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	567.00	LFT
0048	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	5.00	ACH

Call: 340

Contract: R -45756-A

Section No.: 1 PAVEMENT PATCHING

Line			Quantity Unit	
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	207-08264	SUBGRADE TREATMENT, TYPE II	752.00	SYS
0010	214-11796	GEOGRID, TYPE IB	752.00	SYS
0011	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	414.00	TON
0012	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	1015.00	TON
0013	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	20762.00	LFT
0014	406-05520	ASPHALT FOR TACK COAT	4.40	TON
0015	615-06527	MONUMENT, SECTION CORNER	1.00	ACH
0016	801-06640	CONSTRUCTION SIGN, TYPE A	41.00	ACH
0017	801-06775	MAINTAINING TRAFFIC	1.00	LS
0018	801-92448	CONSTRUCTION SIGNS MOBILE	90.00	DAY
0019	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	2420.00	LFT
0020	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	9736.00	LFT
0021	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	3797.00	LFT

Call: 400

Contract: B -41845-A

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	30.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	30.00 EACH
0004	107-12976	RAILROAD FLAGGING BUDGET	480000.00 DOL
0005	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0006	109-08360	CONTRACT LIENS	1.00 DOL
0007	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0008	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0009	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0010	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0011	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0014	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	14628.00 SYS
0016	202-02278	CURB, CONCRETE, REMOVE	5270.00 LFT
0017	202-05571	TESTING FOR WASTES, TYPE	4.00 EACH
0018	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	2000.00 CYS
0019	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	2000.00 CYS
0020	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	2000.00 CYS
0021	202-52710	SIDEWALK CONCRETE, REMOVE	1894.00 SYS
0022	202-93047	MANHOLE, REMOVE	3.00 EACH
0023	203-02000	EXCAVATION, COMMON	31978.00 CYS
0024	203-02055	EMBANKMENT	8240.00 CYS
0025	203-02070	BORROW	4798.00 CYS
0026	204-02290	SETTLEMENT PLATE	7.00 EACH
0027	204-08415	STAKE, SETTLEMENT	6.00 EACH
0028	205-12108	STORMWATER MANAGEMENT BUDGET	90780.00 DOL
0029	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0030	205-12618	SWQCP PREPARATION	1.00 LS
0031	207-08264	SUBGRADE TREATMENT, TYPE II	2479.00 SYS

0032	207-09935	SUBGRADE TREATMENT, TYPE IC	1460.00	SYS
0033	207-12635	SUBGRADE TREATMENT, TYPE IBC	29949.00	SYS
0034	211-02050	B BORROW	7915.00	CYS
0035	211-09265	STRUCTURE BACKFILL, TYPE 2	7637.00	CYS
0036	211-09266	STRUCTURE BACKFILL, TYPE 3	18834.00	CYS
0037	211-09266	STRUCTURE BACKFILL, TYPE 3	3700.00	CYS
0038	211-09268	STRUCTURE BACKFILL, TYPE 5	270.00	CYS
0039	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	149.00	CYS
0040	214-11796	GEOGRID, TYPE IB	2395.00	SYS
0041	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	26339.00	SYS
0042	214-12238	GEOTEXTILE FOR PAVEMENT, TYPE 2A	3363.00	SYS
0043	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	314.00	SYS
0044	301-12231	COMPACTED AGGREGATE, NO. 2	827.00	CYS
0045	301-12233	COMPACTED AGGREGATE, NO. 8	194.00	CYS
0046	301-12234	COMPACTED AGGREGATE, NO. 53	2076.00	CYS
0047	301-12234	COMPACTED AGGREGATE, NO. 53	895.00	CYS
0048	302-06464	SUBBASE FOR PCCP	64.00	CYS
0049	302-07455	DENSE GRADED SUBBASE	524.00	CYS
0050	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	112.00	TON
0051	304-12624	HMA PATCHING, PARTIAL DEPTH, TYPE B	55.00	TON
0052	306-08038	MILLING, ASPHALT, 4 IN.	252.00	SYS
0053	306-08042	MILLING, SCARIFICATION	912.00	SYS
0054	306-08159	MILLING, ASPHALT	3782.00	SYS
0055	401-000001	QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	2425.00	TON
0056	401-000037	QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	4876.00	TON
0057	401-000052	QC/QA-HMA, 2, 58S, BASE, 19.0 mm	5091.00	TON
0058	401-000067	QC/QA-HMA, 4, 58E, INTERMEDIATE, OG, 19.0 mm	3518.00	TON
0059	401-11526	JOINT ADHESIVE	29472.00	LFT
0060	406-05520	ASPHALT FOR TACK COAT	33.00	TON
0061	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0062	503-12477	TERMINAL JOINT, TYPE HMA	92.00	LFT
0063	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	1.00	ACH
0064	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	238.00	LFT
0065	601-12291	GUARDRAIL TRANSITION, MGS WITH CURB	2.00	ACH
0066	601-12294	GUARDRAIL, MGS W-BEAM, CABLE TERMINAL ANCHOR	6.00	ACH
0067	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00	ACH
0068	602-06729	BARRIER DELINEATOR	32.00	ACH

0069	603-01932	FENCE, CHAIN LINK, 96 IN.	325.00	LFT
0070	603-97461	TEMPORARY FENCE	896.00	LFT
0071	604-06070	SIDEWALK, CONCRETE	5118.00	SYS
0072	604-08086	CURB RAMP, CONCRETE	355.00	SYS
0073	604-12083	DETECTABLE WARNING SURFACES	56.00	SYS
0074	605-06120	CURB, CONCRETE	421.00	LFT
0075	605-06140	CURB AND GUTTER, CONCRETE	8598.00	LFT
0076	605-06140	CURB AND GUTTER, CONCRETE	718.00	LFT
0077	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	24.00	LFT
0078	605-06150	CURB AND GUTTER, CONCRETE, TYPE C	198.00	LFT
0079	605-06150	CURB AND GUTTER, CONCRETE, TYPE C	518.00	LFT
0080	607-06335	PAVED SIDE DITCH, TYPE A	78.00	LFT
0081	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	290.00	SYS
0082	610-07487	HMA FOR APPROACHES, TYPE B	33.00	TON
0083	610-08446	PCCP FOR APPROACHES, 6 IN.	1113.00	SYS
0084	610-09108	PCCP FOR APPROACHES, 9 IN.	1288.00	SYS
0085	615-06505	MONUMENT, TYPE B	41.00	ACH
0086	615-06510	MONUMENT, TYPE C	3.00	ACH
0087	616-05688	RIPRAP, CLASS 1	34.00	TON
0088	616-06405	RIPRAP, REVETMENT	174.00	TON
0089	616-06451	RIPRAP, UNIFORM	68.00	TON
0090	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	208.00	SYS
0091	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	411.00	SYS
0092	621-06575	SODDING, NURSERY	44060.00	SYS
0093	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0094	628-12683	FIELD OFFICE, TYPE D	36.00	MOS
0095	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	44060.00	SYS
0096	629-000150	TOPSOIL AMENDMENT BUDGET	88120.00	DOL
0097	701-06011	DYNAMIC PILE LOAD TEST	5.00	ACH
0098	701-08253	PILE, SLEEVES	18.00	ACH
0099	701-09557	TEST PILE, DYNAMIC, PRODUCTION	629.00	LFT
0100	701-09559	TEST PILE, DYNAMIC, RESTRIKE	5.00	ACH
0101	701-09665	PILE, STEEL PIPE, 0.375 IN., DIAMETER 14 IN.	10464.00	LFT
0102	701-12304	VIBRATION MONITORING	1.00	LS
0103	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	4.00	ACH
0104	702-51005	CONCRETE, A, SUBSTRUCTURE	475.10	CYS
0105	702-51015	CONCRETE, B, FOOTINGS	187.50	CYS

0106	702-92857	CONCRETE, C, SUBSTRUCTURE	47.00	CYS
0107	703-06028	REINFORCING BARS	127439.00	LBS
0108	703-06029	REINFORCING BARS, EPOXY COATED	343467.00	LBS
0109	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	46.00	ACH
0110	704-51002	CONCRETE, C, SUPERSTRUCTURE	1014.80	CYS
0111	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	563.00	SYS
0112	706-09295	REINFORCED CONCRETE MOMENT SLAB, 24 IN.	316.00	SYS
0113	706-09959	RAILING, CONCRETE TYPE FT	398.00	LFT
0114	706-11404	RAILING, STEEL TYPE PF-1	464.00	LFT
0115	706-11418	RAILING, STEEL TYPE PS-1	588.00	LFT
0116	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	184.00	LFT
0117	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	530.00	LFT
0118	706-11601	RAILING, CONCRETE TYPE FT	76.80	CYS
0119	706-11604	RAILING, CONCRETE TYPE PS-1	60.90	CYS
0120	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	2.00	ACH
0121	707-11046	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 60 IN. X 49 IN.	2620.00	LFT
0122	709-51821	SURFACE SEAL	1.00	LS
0123	715-01384	PIPE, DUCTILE IRON, DIAMETER 10 IN.	120.00	LFT
0124	715-02185	WATER SERVICE LINE, 1.50 IN.	206.00	LFT
0125	715-02745	GATE VALVE WITH VALVE BOX, 8 IN.	7.00	ACH
0126	715-04995	LINE STOP	4.00	ACH
0127	715-04995	LINE STOP	5.00	ACH
0128	715-04995	LINE STOP	1.00	ACH
0129	715-04995	LINE STOP	8.00	ACH
0130	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	10313.00	LFT
0131	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	150.00	LFT
0132	715-05148	PIPE, TYPE 2, CIRCULAR, DIAMETER 10 IN.	13.00	LFT
0133	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	5191.00	LFT
0134	715-05151	PIPE, TYPE 2, CIRCULAR, DIAMETER 15 IN.	672.00	LFT
0135	715-05152	PIPE, TYPE 2, CIRCULAR, DIAMETER 18 IN.	983.00	LFT
0136	715-05154	PIPE, TYPE 2, CIRCULAR, DIAMETER 24 IN.	294.00	LFT
0137	715-05156	PIPE, TYPE 2, CIRCULAR, DIAMETER 30 IN.	389.00	LFT
0138	715-05159	PIPE, TYPE 2, CIRCULAR, DIAMETER 42 IN.	25.00	LFT
0139	715-05159	PIPE, TYPE 2, CIRCULAR, DIAMETER 42 IN.	403.00	LFT
0140	715-05161	PIPE, TYPE 2, CIRCULAR, DIAMETER 48 IN.	65.00	LFT
0141	715-05408	PIPE, SANITARY SEWER, DIAMETER 8 IN.	868.00	LFT
0142	715-05409	PIPE, SANITARY SEWER, DIAMETER 10 IN.	364.00	LFT

0143	715-05411	PIPE, SANITARY SEWER, DIAMETER 12 IN.	398.00	LFT
0144	715-05422	PIPE, SLOTTED DRAIN, DIAMETER 12 IN.	33.00	LFT
0145	715-05711	PIPE, SANITARY SEWER, DIAMETER 6 IN.	65.00	LFT
0146	715-06050	CAP	21.00	ACH
0147	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	625.00	TON
0148	715-09475	STORMWATER QUALITY STRUCTURE	65.00	ACH
0149	715-09843	BYPASS PUMPING	1.00	LS
0150	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0151	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	1780.00	LFT
0152	715-11896	WATER SERVICE CONNECTION	9.00	ACH
0153	715-11896	WATER SERVICE CONNECTION	5.00	ACH
0154	715-12674	GATE VALVE AND VALVE BOX, 12 IN.	6.00	ACH
0155	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	ACH
0156	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	ACH
0157	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	ACH
0158	715-90853	TAPPING SLEEVE WITH VALVE	1.00	ACH
0159	715-92253	SEWER SANITARY LATERAL RECONNECT	8.00	ACH
0160	715-92544	WATER MAIN, DUCTILE IRON, 12 IN.	1420.00	LFT
0161	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	120.00	LFT
0162	715-96629	WATER SERVICE LINE, 1 IN.	293.00	LFT
0163	715-96669	WATER MAIN, DUCTILE IRON, 16 IN.	520.00	LFT
0164	715-96691	BUTTERFLY VALVE WITH BOX, 16 IN.	2.00	ACH
0165	715-97559	GRATED BOX END SECTION, TYPE II, 10:1, DIAMETER 12 IN.	1.00	ACH
0166	718-06529	OUTLET PROTECTOR, TYPE 2	1.00	ACH
0167	718-06531	OUTLET PROTECTOR, TYPE 3	2.00	ACH
0168	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	8901.00	SYS
0169	718-52610	AGGREGATE FOR UNDERDRAINS	818.00	CYS
0170	720-01092	MANHOLE, TYPE J15, MODIFIED	16.00	ACH
0171	720-08241	MANHOLE, TYPE K15, MODIFIED	9.00	ACH
0172	720-08628	SLOTTED DRAIN PIPE CLEANOUT PORT TYPE II	1.00	ACH
0173	720-08660	MANHOLE, TYPE J5, MODIFIED	3.00	ACH
0174	720-45030	INLET, TYPE E7	5.00	ACH
0175	720-45042	INLET, TYPE HA5	8.00	ACH
0176	720-45070	INLET, TYPE P12A	2.00	ACH
0177	720-45075	INLET, TYPE R13	1.00	ACH
0178	720-45270	PIPE CATCH BASIN, 18 IN.	2.00	ACH
0179	720-45410	MANHOLE, TYPE C4	18.00	ACH

0180	720-45510	MANHOLE, TYPE C4, MODIFIED	11.00	ACH
0181	720-45510	MANHOLE, TYPE C4, MODIFIED	3.00	ACH
0182	720-45510	MANHOLE, TYPE C4, MODIFIED	4.00	ACH
0183	720-93409	INLET, TYPE B15, MODIFIED	12.00	ACH
0184	720-93411	INLET, TYPE C15, MODIFIED	16.00	ACH
0185	720-93501	MANHOLE, TYPE L4	1.00	ACH
0186	720-94432	MANHOLE, TYPE C7	3.00	ACH
0187	720-94612	MANHOLE, TYPE K4	6.00	ACH
0188	720-95422	MANHOLE, TYPE J4	2.00	ACH
0189	720-96999	FIRE HYDRANT ASSEMBLY	7.00	ACH
0190	720-98174	INLET, TYPE B15	30.00	ACH
0191	720-98555	INLET, TYPE C15	18.00	ACH
0192	722-12732	LONGITUDINAL GROOVING	2163.00	SYS
0193	724-03855	EXPANSION JOINT SLIDING PLATE	22.00	LFT
0194	726-92406	BEARING ASSEMBLY, ELASTOMERIC	30.00	ACH
0195	731-03915	ARCHITECTURAL SURFACE TREATMENT	31211.00	SFT
0196	731-93945	FACE PANELS, CONCRETE	23461.00	SFT
0197	731-93946	WALL ERECTION	23461.00	SFT
0198	731-93947	LEVELING PAD, CONCRETE	1033.00	LFT
0199	735-10241	TEMPORARY WIRE-FACING	10272.00	SFT
0200	735-10242	TEMPORARY WALL ERECTION	10272.00	SFT
0201	801-03290	CONSTRUCTION SIGN, TYPE C	1.00	ACH
0202	801-04308	ROAD CLOSURE SIGN ASSEMBLY	32.00	ACH
0203	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2539.00	LFT
0204	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8725.00	LFT
0205	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	216.00	LFT
0206	801-06625	DETOUR ROUTE MARKER ASSEMBLY	203.00	ACH
0207	801-06640	CONSTRUCTION SIGN, TYPE A	30.00	ACH
0208	801-06645	CONSTRUCTION SIGN, TYPE B	41.00	ACH
0209	801-06710	FLASHING ARROW SIGN	120.00	DAY
0210	801-06775	MAINTAINING TRAFFIC	1.00	LS
0211	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	ACH
0212	801-07118	BARRICADE, TYPE III-A	488.00	LFT
0213	801-07119	BARRICADE, TYPE III-B	600.00	LFT
0214	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	410.00	LFT
0215	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	120.00	LFT
0216	801-11990	TEMPORARY CURB RAMP	1.00	ACH

0217	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	282.00	SYS
0218	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	1195.00	LFT
0219	801-12863	AUDIBLE INFORMATION DEVICE	14.00	ACH
0220	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	703.00	LFT
0221	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	156.00	LFT
0222	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	366.00	SFT
0223	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	125.00	SFT
0224	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	233.00	SFT
0225	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	ACH
0226	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	4943.00	LFT
0227	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	14.00	ACH
0228	805-02383	CONDUIT, STEEL, GALVANIZED, 2.5 IN.	1843.00	LFT
0229	805-02445	CONTROLLER AND CABINET, TYPE P1	3.00	ACH
0230	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	7.00	ACH
0231	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	1.00	ACH
0232	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT	4.00	ACH
0233	805-11378	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT	2.00	ACH
0234	805-11379	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 45 FT	5.00	ACH
0235	805-11381	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 55 FT	1.00	ACH
0236	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, TYPE B	12.00	ACH
0237	805-11744	HANDHOLE, SIGNAL, TYPE 2	25.00	ACH
0238	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	1.00	ACH
0239	805-11817	PEDESTRIAN PUSH BUTTON, APS	14.00	ACH
0240	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	16.00	ACH
0241	805-78230	TRAFFIC SIGNAL HEAD, NO. 5 SECTION, 12 IN.	8.00	ACH
0242	805-78445	SIGNAL SERVICE	3.00	ACH
0243	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	80.00	LFT
0244	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	7924.00	LFT
0245	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1216.00	LFT
0246	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	2635.00	LFT
0247	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	491.00	LFT
0248	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	1597.00	LFT
0249	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	6698.00	LFT
0250	805-78785	SIGNAL DETECTOR HOUSING	21.00	ACH
0251	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2774.00	LFT
0252	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	3.00	ACH
0253	805-87715	GROUND ROD WITH CONNECTOR	132.00	ACH

0254	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	6.00	ACH
0255	807-02191	HANDHOLE, LIGHTING	32.00	ACH
0256	807-03950	LUMINAIRE, ORNAMENTAL	116.00	ACH
0257	807-03951	LIGHT POLE, ORNAMENTAL	116.00	ACH
0258	807-04653	LIGHTING FOUNDATION	108.00	ACH
0259	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	8682.00	LFT
0260	807-86805	SERVICE POINT, TYPE I	2.00	ACH
0261	807-86810	SERVICE POINT, TYPE II	3.00	ACH
0262	807-86843	WIRE, NO. 4 COPPER, 1/C	5892.00	LFT
0263	807-86910	CONNECTOR KIT, UNFUSED	116.00	ACH
0264	807-86915	CONNECTOR KIT, FUSED	116.00	ACH
0265	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	128.00	ACH
0266	807-95889	WIRE, NO. 10 COPPER, 1/C	6612.00	LFT
0267	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	4.00	ACH
0268	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	72.00	LFT
0269	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	386.00	LFT
0270	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5947.00	LFT
0271	808-06716	LINE, REMOVE	2831.00	LFT
0272	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1176.00	LFT
0273	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1176.00	LFT
0274	808-11953	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 18 IN.	24.00	LFT
0275	808-12032	GROOVING FOR PAVEMENT MARKINGS	19189.00	LFT
0276	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	253.00	LFT
0277	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	12602.00	LFT
0278	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	250.00	LFT
0279	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	1073.00	LFT
0280	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	466.00	LFT
0281	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1051.00	LFT
0282	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	16.00	ACH
0283	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, 'ONLY'	9.00	ACH

Call: 410

Contract: B -42399-B

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00 LS
0012	202-74035	SIGN, REMOVE	1.00 EACH
0013	202-96133	PIPE, REMOVE	24.00 LFT
0014	203-02000	EXCAVATION, COMMON	1359.00 CYS
0015	203-51223	EXCAVATION, WATERWAY	210.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	19000.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	206-51215	EXCAVATION, X	166.00 CYS
0019	206-51225	EXCAVATION, DRY	24.00 CYS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	84.00 SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1563.00 SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	48.00 CYS
0023	211-09268	STRUCTURE BACKFILL, TYPE 5	486.00 CYS
0024	214-11796	GEOGRID, TYPE IB	1563.00 SYS
0025	301-12231	COMPACTED AGGREGATE, NO. 2	89.00 CYS
0026	301-12234	COMPACTED AGGREGATE, NO. 53	89.00 CYS
0027	302-07455	DENSE GRADED SUBBASE	14.00 CYS
0028	303-01180	COMPACTED AGGREGATE, NO. 53	208.00 TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	312.00 SYS
0030	306-08043	MILLING, TRANSITION	560.00 SYS
0031	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	193.00 TON

0032	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	193.00 TON
0033	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	462.00 TON
0034	401-11526	JOINT ADHESIVE	3900.00 LFT
0035	406-05521	ASPHALT FOR TACK COAT	2330.00 SYS
0036	601-05071	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 7	1.00 EACH
0037	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	231.25 LFT
0038	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00 EACH
0039	601-12293	GUARDRAIL, MGS, STRUCTURE TOP-MOUNTED POSTS	14.00 EACH
0040	601-94689	GUARDRAIL END TREATMENT, TYPE OS	3.00 EACH
0041	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	56.25 LFT
0042	610-08446	PCCP FOR APPROACHES, 6 IN.	84.00 SYS
0043	615-06490	RIGHT-OF-WAY MARKER	11.00 EACH
0044	615-06505	MONUMENT, TYPE B	2.00 EACH
0045	616-05688	RIPRAP, CLASS 1	688.00 TON
0046	616-05689	RIPRAP, CLASS 2	100.00 TON
0047	616-06405	RIPRAP, REVETMENT	63.00 TON
0048	616-09395	GEOMEMBRANE	717.00 SYS
0049	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	958.00 SYS
0050	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	121.00 SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0052	621-03909	SEED MIXTURE, NATIVE	12.00 LBS
0053	621-06545	FERTILIZER FOR PERMANENT SEEDING	1.00 TON
0054	621-06559	MULCHED SEEDING, TYPE R	138.00 SYS
0055	621-06567	WATER	1.00 kGAL
0056	621-06574	SODDING	260.00 SYS
0057	628-09403	FIELD OFFICE, TYPE C	24.00 MOS
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0059	702-51015	CONCRETE, B, FOOTINGS	77.50 CYS
0060	703-06029	REINFORCING BARS, EPOXY COATED	97693.00 LBS
0061	704-51002	CONCRETE, C, SUPERSTRUCTURE	209.40 CYS
0062	714-000086	WATERPROOFING MEMBRANE, TYPE 2	1969.00 SFT
0063	715-05149	PIPE, TYPE 2, CIRCULAR, DIAMETER 12 IN.	10.00 LFT
0064	715-05168	PIPE, TYPE 3, CIRCULAR, DIAMETER 12 IN.	42.00 LFT
0065	718-12306	GEOTEXTILE FOR UNDERDRAINS, TYPE 1B	296.00 SYS
0066	720-44015	CASTING, TYPE 2, FURNISH AND ADJUST TO GRADE	1.00 EACH
0067	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0068	801-06625	DETOUR ROUTE MARKER ASSEMBLY	23.00 EACH

0069	801-06640	CONSTRUCTION SIGN, TYPE A	14.00	EACH
0070	801-06775	MAINTAINING TRAFFIC	1.00	LS
0071	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0072	801-07119	BARRICADE, TYPE III-B	48.00	LFT
0073	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	11.50	LFT
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	5.00	SFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	2113.00	LFT
0076	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1300.00	LFT
0077	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	650.00	LFT
0078	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	163.00	LFT

Call: 420

Contract: B -42775-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0011	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00 LS
0012	202-74035	SIGN, REMOVE	4.00 EACH
0013	203-02000	EXCAVATION, COMMON	1565.00 CYS
0014	203-02070	BORROW	1485.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	206-51215	EXCAVATION, X	10.00 CYS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	315.00 CYS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	210.00 SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1519.00 SYS
0021	211-02050	B BORROW	570.00 CYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	97.00 CYS
0023	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	142.00 SYS
0024	301-12234	COMPACTED AGGREGATE, NO. 53	145.00 CYS
0025	302-06464	SUBBASE FOR PCCP	36.00 CYS
0026	303-01180	COMPACTED AGGREGATE, NO. 53	147.00 TON
0027	304-07494	WIDENING WITH HMA, TYPE C	6.00 TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	107.00 SYS
0029	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	115.00 TON
0030	401-000020	QC/QA-HMA, 3, 58S, INTERMEDIATE, 9.5 mm	212.00 TON
0031	401-11526	JOINT ADHESIVE	973.00 LFT

0032	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0033	601-01522	GUARDRAIL TRANSITION, TYPE TGB	1.00 EACH
0034	601-01846	GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, TYPE 3	1.00 EACH
0035	601-02241	GUARDRAIL, REMOVE	455.00 LFT
0036	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	1.00 EACH
0037	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	2.00 EACH
0038	601-94689	GUARDRAIL END TREATMENT, TYPE OS	2.00 EACH
0039	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	31.25 LFT
0040	602-06729	BARRIER DELINEATOR	8.00 EACH
0041	603-03398	FENCE, RELOCATE	60.00 LFT
0042	605-06095	CURB, INTEGRAL CONCRETE, TYPE B	18.00 LFT
0043	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	142.00 SYS
0044	610-07487	HMA FOR APPROACHES, TYPE B	21.00 TON
0045	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00 EACH
0046	615-06490	RIGHT-OF-WAY MARKER	14.00 EACH
0047	615-06505	MONUMENT, TYPE B	4.00 EACH
0048	615-06510	MONUMENT, TYPE C	1.00 EACH
0049	616-06405	RIPRAP, REVETMENT	608.00 TON
0050	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	687.00 SYS
0051	616-12251	GEOTEXTILE FOR RIPRAP, TYPE 3	801.00 SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0053	621-06559	MULCHED SEEDING, TYPE R	1580.00 SYS
0054	621-06567	WATER	1.00 KGAL
0055	621-06575	SODDING, NURSERY	82.00 SYS
0056	628-09401	FIELD OFFICE, TYPE A	11.00 MOS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0058	701-09558	TEST PILE, INDICATOR, PRODUCTION	110.00 LFT
0059	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00 EACH
0060	701-09663	PILE, STEEL PIPE, 0.312 IN., DIAMETER 14 IN.	445.00 LFT
0061	702-92857	CONCRETE, C, SUBSTRUCTURE	46.70 CYS
0062	703-06029	REINFORCING BARS, EPOXY COATED	59705.00 LBS
0063	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	34.00 EACH
0064	704-51002	CONCRETE, C, SUPERSTRUCTURE	124.40 CYS
0065	706-11600	RAILING, CONCRETE TYPE FC	19.00 CYS
0066	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00 EACH
0067	707-08158	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 42 IN. X 49 IN.	388.00 LFT
0068	709-51821	SURFACE SEAL	1.00 LS

0069	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	176.00	LFT
0070	722-12732	LONGITUDINAL GROOVING	438.00	SYS
0071	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	32.00	EACH
0073	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	EACH
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0076	801-07119	BARRICADE, TYPE III-B	36.00	LFT
0077	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	20.00	LFT
0078	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	22.50	SFT
0079	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1200.00	LFT
0080	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	1200.00	LFT
0081	808-12032	GROOVING FOR PAVEMENT MARKINGS	1846.00	LFT

Call: 430

Contract: B -42786-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0011	202-02637	PIPE ABANDON AND GROUT FILL	70.00 LFT
0012	202-51330	PRESENT STRUCTURE, REMOVE, STRUCTURE NO.	1.00 LS
0013	203-02000	EXCAVATION, COMMON	1022.00 CYS
0014	203-02010	EXCAVATION, ROCK	285.00 CYS
0015	203-02070	BORROW	1850.00 CYS
0016	203-51223	EXCAVATION, WATERWAY	210.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	48696.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	206-51215	EXCAVATION, X	75.00 CYS
0021	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	220.00 CYS
0022	206-51235	COFFERDAM	1.00 LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	936.00 SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	2950.00 SYS
0025	211-06467	AGGREGATE FOR END BENT BACKFILL	28.00 CYS
0026	211-09264	STRUCTURE BACKFILL, TYPE 1	15.00 CYS
0027	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	180.00 SYS
0028	301-12231	COMPACTED AGGREGATE, NO. 2	106.00 CYS
0029	301-12234	COMPACTED AGGREGATE, NO. 53	554.00 CYS
0030	303-01180	COMPACTED AGGREGATE, NO. 53	209.00 TON
0031	306-08043	MILLING, TRANSITION	447.00 SYS

0032	309-12695	LEAN CONCRETE BASE, 9 IN.	180.00	SYS
0033	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	275.00	TON
0034	401-000004	QC/QA-HMA, 2, 58H, SURFACE, 9.5 mm	40.00	TON
0035	401-000019	QC/QA-HMA, 2, 58S, INTERMEDIATE, 9.5 mm	515.00	TON
0036	401-000046	QC/QA-HMA, 2, 58S, BASE, 25.0 mm	1083.00	TON
0037	401-11526	JOINT ADHESIVE	6864.00	LFT
0038	402-07451	HMA WEDGE AND LEVEL, TYPE B	12.00	TON
0039	406-05521	ASPHALT FOR TACK COAT	11062.00	SYS
0040	601-02241	GUARDRAIL, REMOVE	375.00	LFT
0041	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	107.00	LFT
0042	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00	ACH
0043	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	ACH
0044	605-06150	CURB AND GUTTER, CONCRETE, TYPE C	300.00	LFT
0045	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	186.00	SYS
0046	610-07487	HMA FOR APPROACHES, TYPE B	57.00	TON
0047	611-08232	MAILBOX ASSEMBLY, RESET, SINGLE	2.00	ACH
0048	615-06490	RIGHT-OF-WAY MARKER	19.00	ACH
0049	616-05688	RIPRAP, CLASS 1	1396.00	TON
0050	616-05689	RIPRAP, CLASS 2	141.00	TON
0051	616-06405	RIPRAP, REVETMENT	183.00	TON
0052	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	2344.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	ACH
0054	621-02770	EROSION CONTROL BLANKET	1199.00	SYS
0055	621-06554	SEED MIXTURE, TYPE U	46.00	LBS
0056	621-06560	MULCHED SEEDING, TYPE U	1513.00	SYS
0057	621-06567	WATER	1.00	KGAL
0058	621-06574	SODDING	45.00	SYS
0059	621-12612	SEED MIXTURE, FLOODPLAIN	2.00	LBS
0060	628-09403	FIELD OFFICE, TYPE C	9.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0062	628-11977	COMPUTER SYSTEM	1.00	ACH
0063	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	2853.00	SYS
0064	629-000150	TOPSOIL AMENDMENT BUDGET	5706.00	DOL
0065	701-02938	CORED HOLE IN ROCK, DIAMETER 24 IN.	27.00	LFT
0066	701-09560	TEST PILE, INDICATOR, RESTRIKE	9.00	ACH
0067	701-09683	PILE SHOE, HP 12 X 74	9.00	ACH
0068	701-95780	PILE, STEEL H, HP 12 X 74	102.00	LFT

0069	702-51005	CONCRETE, A, SUBSTRUCTURE	72.00	CYS
0070	702-51015	CONCRETE, B, FOOTINGS	32.50	CYS
0071	703-06028	REINFORCING BARS	17412.00	LBS
0072	703-06029	REINFORCING BARS, EPOXY COATED	63885.00	LBS
0073	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	30.00	EACH
0074	704-09031	ARTICULATING CONCRETE MATTRESS	15.00	SYS
0075	704-51002	CONCRETE, C, SUPERSTRUCTURE	192.30	CYS
0076	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TYPE TPF-1	4.00	EACH
0077	706-09962	RAILING, CONCRETE TYPE PF-1	164.00	LFT
0078	706-11404	RAILING, STEEL TYPE PF-1	182.00	LFT
0079	709-51821	SURFACE SEAL	1.00	LS
0080	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	300.00	LFT
0081	715-05053	PIPE, UNDERDRAIN OUTLET, DIAMETER 6 IN.	26.00	LFT
0082	715-05125	PIPE, TYPE 1, CIRCULAR, DIAMETER 30 IN.	56.00	LFT
0083	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	100.00	LFT
0084	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	300.00	LFT
0085	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	259.00	SYS
0086	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	93.00	SYS
0087	718-52610	AGGREGATE FOR UNDERDRAINS	26.00	CYS
0088	722-12732	LONGITUDINAL GROOVING	436.00	SYS
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00	EACH
0091	801-06640	CONSTRUCTION SIGN, TYPE A	31.00	EACH
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-07118	BARRICADE, TYPE III-A	108.00	LFT
0094	801-07119	BARRICADE, TYPE III-B	156.00	LFT
0095	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	39.00	LFT
0096	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	15.00	SFT
0097	802-91122	SIGN, GROUND MOUNTED, RESET	2.00	EACH
0098	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1797.00	LFT
0099	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1888.00	LFT
0100	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	45.00	LFT

Call: 440

Contract: B -43242-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	948.00 SYS
0013	202-02278	CURB, CONCRETE, REMOVE	20.00 LFT
0014	202-62420	BRIDGE RAILING, REMOVE	40.00 LFT
0015	203-08607	LINEAR GRADING	262.50 LFT
0016	205-12108	STORMWATER MANAGEMENT BUDGET	19200.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	494.00 SYS
0019	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	428.00 CYS
0020	213-09270	FLOWABLE BACKFILL, REMOVABLE	132.00 CYS
0021	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	494.00 SYS
0022	301-12234	COMPACTED AGGREGATE, NO. 53	80.00 CYS
0023	303-01180	COMPACTED AGGREGATE, NO. 53	92.00 TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4636.00 SYS
0025	309-12695	LEAN CONCRETE BASE, 9 IN.	468.00 SYS
0026	401-000009	QC/QA-HMA, 4, 58E, SURFACE, 9.5 mm	422.00 TON
0027	401-000045	QC/QA-HMA, 4, 58E, INTERMEDIATE, 19.0 mm	66.00 TON
0028	401-000048	QC/QA-HMA, 4, 58S, BASE, 25.0 mm	284.00 TON
0029	401-11526	JOINT ADHESIVE	1680.00 LFT
0030	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	1680.00 LFT
0031	406-05521	ASPHALT FOR TACK COAT	4214.00 SYS

0032	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	3032.00	SFT
0033	507-08272	JOINTS IN PCCP, SAW AND SEAL	4093.00	LFT
0034	601-02241	GUARDRAIL, REMOVE	237.00	LFT
0035	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	3.00	ACH
0036	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	3.00	ACH
0037	602-06729	BARRIER DELINEATOR	18.00	ACH
0038	605-06120	CURB, CONCRETE	50.00	LFT
0039	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1120.00	LFT
0040	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	484.00	SYS
0041	616-06405	RIPRAP, REVETMENT	126.00	TON
0042	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	168.00	SYS
0043	619-98427	CLEAN DRAINS	196.00	ACH
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	ACH
0045	621-06559	MULCHED SEEDING, TYPE R	276.00	SYS
0046	621-06574	SODDING	22.00	SYS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	ACH
0048	628-12683	FIELD OFFICE, TYPE D	16.00	MOS
0049	703-06029	REINFORCING BARS, EPOXY COATED	30371.00	LBS
0050	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	272.00	ACH
0051	704-51002	CONCRETE, C, SUPERSTRUCTURE	3.10	CYS
0052	704-51106	DECK DRAIN	3.00	ACH
0053	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFT	4.00	ACH
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	709-51821	SURFACE SEAL	1.00	LS
0059	709-51821	SURFACE SEAL	1.00	LS
0060	709-51821	SURFACE SEAL	1.00	LS
0061	709-51821	SURFACE SEAL	1.00	LS
0062	709-51821	SURFACE SEAL	1.00	LS
0063	709-51821	SURFACE SEAL	1.00	LS
0064	709-51821	SURFACE SEAL	1.00	LS
0065	709-51821	SURFACE SEAL	1.00	LS
0066	709-51821	SURFACE SEAL	1.00	LS
0067	709-51821	SURFACE SEAL	1.00	LS
0068	709-51821	SURFACE SEAL	1.00	LS

0069	709-51821	SURFACE SEAL	1.00	LS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	709-51821	SURFACE SEAL	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	709-51821	SURFACE SEAL	1.00	LS
0078	709-51821	SURFACE SEAL	1.00	LS
0079	709-51821	SURFACE SEAL	1.00	LS
0080	709-51821	SURFACE SEAL	1.00	LS
0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	709-51821	SURFACE SEAL	1.00	LS
0084	709-51821	SURFACE SEAL	1.00	LS
0085	709-51821	SURFACE SEAL	1.00	LS
0086	709-51821	SURFACE SEAL	1.00	LS
0087	709-51821	SURFACE SEAL	1.00	LS
0088	709-51821	SURFACE SEAL	1.00	LS
0089	709-51821	SURFACE SEAL	1.00	LS
0090	709-51821	SURFACE SEAL	1.00	LS
0091	709-51821	SURFACE SEAL	1.00	LS
0092	709-51821	SURFACE SEAL	1.00	LS
0093	709-51821	SURFACE SEAL	1.00	LS
0094	709-51821	SURFACE SEAL	1.00	LS
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	709-51821	SURFACE SEAL	1.00	LS
0098	710-09158	PATCHING CONCRETE STRUCTURES	313.00	SFT
0099	715-05048	PIPE, TYPE 4, CIRCULAR, DIAMETER 6 IN.	120.00	LFT
0100	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0101	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0102	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0103	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0104	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0105	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS

0106	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0107	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0108	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0109	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0110	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0111	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0112	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0113	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0114	715-11446	CONCRETE ANCHOR, DIAMETER 24 IN.	1.00	ACH
0115	715-98938	PIPE, RELAID, DIAMETER 24 IN.	8.00	LFT
0116	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	56.00	SYS
0117	718-52610	AGGREGATE FOR UNDERDRAINS	8.00	CYS
0118	721-09548	AUTOMATIC DRAINAGE GATE	1.00	ACH
0119	722-12732	LONGITUDINAL GROOVING	17508.00	SYS
0120	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	23.00	SFT
0121	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	3364.00	SFT
0122	724-12777	BRIDGE EXPANSION JOINT SEAL, TYPE SS, REPLACE	176.00	LFT
0123	724-12778	BRIDGE EXPANSION JOINT SEAL, TYPE M, REPLACE	444.00	LFT
0124	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	15.00	GAL
0125	727-90308	EPOXY INJECTION, CRACK PREPARATION	15.00	LFT
0126	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0127	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0128	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0129	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0130	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0131	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	70498.00	SYS
0132	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	ACH
0133	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	884457.00	LFT
0134	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	35.00	LFT
0135	801-06625	DETOUR ROUTE MARKER ASSEMBLY	118.00	ACH
0136	801-06640	CONSTRUCTION SIGN, TYPE A	425.00	ACH
0137	801-06645	CONSTRUCTION SIGN, TYPE B	50.00	ACH
0138	801-06710	FLASHING ARROW SIGN	431.00	DAY
0139	801-06775	MAINTAINING TRAFFIC	1.00	LS
0140	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00	ACH
0141	801-07118	BARRICADE, TYPE III-A	372.00	LFT
0142	801-07119	BARRICADE, TYPE III-B	216.00	LFT

0143	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	3880.00	LFT
0144	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	12.00	ACH
0145	801-12042	TRUCK MOUNTED ATTENUATOR	231.00	DAY
0146	801-12832	TEMPORARY SPEED FEEDBACK ASSEMBLY	2.00	ACH
0147	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	60.00	ACH
0148	802-04893	REFERENCE POST	44.00	ACH
0149	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	17651.00	LFT
0150	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	17552.00	LFT
0151	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	3783.00	LFT
0152	808-12032	GROOVING FOR PAVEMENT MARKINGS	2750.00	LFT
0153	808-75994	PRISMATIC REFLECTOR	110.00	ACH
0154	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	50.00	ACH
0155	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	64.00	ACH

Call: 450

Contract: B -43850-A

Section No.: 1 BRIDGE REHABILITATION, PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0010	202-06541	REMOVE	4.00	ACH
0011	202-51368	SLOPEWALL, REMOVE	75.00	SYS
0012	202-96531	FENCE RIGHT-OF-WAY, REMOVE	109.00	LFT
0013	203-02000	EXCAVATION, COMMON	40.00	CYS
0014	203-02070	BORROW	6.00	CYS
0015	205-11626	PUMP AROUND	6.00	ACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	18000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	55.00	CYS
0019	211-09265	STRUCTURE BACKFILL, TYPE 2	40.00	CYS
0020	301-12232	COMPACTED AGGREGATE, NO. 5	10.00	CYS
0021	603-06040	FENCE, FARM FIELD, 47 IN.	109.00	LFT
0022	603-06065	FENCE, CHAIN LINK, RESET	200.00	LFT
0023	615-06490	RIGHT-OF-WAY MARKER	8.00	ACH
0024	616-05688	RIPRAP, CLASS 1	85.00	TON
0025	616-05689	RIPRAP, CLASS 2	93.00	TON
0026	616-06405	RIPRAP, REVETMENT	440.00	TON
0027	616-06451	RIPRAP, UNIFORM	28.00	TON
0028	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	624.00	SYS
0029	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	363.00	SYS
0030	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	ACH
0031	621-06559	MULCHED SEEDING, TYPE R	4004.00	SYS

0032	621-09867	MULCHED SEEDING	119.00	SYS
0033	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0034	702-51005	CONCRETE, A, SUBSTRUCTURE	15.20	CYS
0035	703-06029	REINFORCING BARS, EPOXY COATED	1012.00	LBS
0036	709-51821	SURFACE SEAL	1.00	LS
0037	715-07679	CONCRETE ANCHOR, DIAMETER 36 IN.	2.00	ACH
0038	715-12322	CONCRETE ANCHOR, MIN. AREA 42.4 SFT	2.00	ACH
0039	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	342.00	LFT
0040	716-07726	PIPE INSTALLATION, TRENCHLESS, 54 IN.	359.00	LFT
0041	725-10198	LINER PIPE, THERMOPLASTIC, DEFORMED, 26.6-28.3 SFT	937.00	LFT
0042	725-10228	LINER PIPE, THERMOPLASTIC, CIRCULAR, 37.7-38.5 SFT	342.00	LFT
0043	725-11043	LINER PIPE, THERMOPLASTIC, CIRCULAR, 32.3-33.2 SFT	367.00	LFT
0044	725-11791	PIPE LINER, CURED-IN-PLACE, MIN. AREA 15.6 SFT	308.00	LFT
0045	725-12358	PIPE LINER, CURED-IN-PLACE, MIN. AREA 34.2 SFT	181.00	LFT
0046	725-12948	PIPE LINER, CURED-IN-PLACE, MIN. AREA 13.2 SFT	132.00	LFT
0047	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1380.00	LFT
0048	801-06640	CONSTRUCTION SIGN, TYPE A	152.00	ACH
0049	801-06645	CONSTRUCTION SIGN, TYPE B	13.00	ACH
0050	801-06775	MAINTAINING TRAFFIC	1.00	LS
0051	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	ACH
0052	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	5.00	ACH
0053	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2610.00	LFT
0054	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY

Call: 470

Contract: B -43957-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0011	202-74035	SIGN, REMOVE	1.00 EACH
0012	202-96531	FENCE RIGHT-OF-WAY, REMOVE	110.00 LFT
0013	203-02000	EXCAVATION, COMMON	498.00 CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	17105.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	216-06394	CELLULAR CONCRETE FILL, CLASS IV	255.00 CYS
0017	301-12231	COMPACTED AGGREGATE, NO. 2	414.00 CYS
0018	603-06045	FENCE, CHAIN LINK, 48 IN.	110.00 LFT
0019	616-05688	RIPRAP, CLASS 1	88.00 TON
0020	616-06405	RIPRAP, REVETMENT	40.00 TON
0021	616-06941	GROUT	20.00 CYS
0022	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	185.00 SYS
0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0024	621-02770	EROSION CONTROL BLANKET	768.00 SYS
0025	621-06560	MULCHED SEEDING, TYPE U	2128.00 SYS
0026	628-09403	FIELD OFFICE, TYPE C	12.00 MOS
0027	715-06358	CONCRETE ANCHOR, DIAMETER 78 IN.	2.00 EACH
0028	715-09064	VIDEO INSPECTION FOR PIPE	373.00 LFT
0029	716-11716	PIPE INSTALLATION, TRENCHLESS	373.00 LFT
0030	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00 EACH
0031	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	704.00 LFT

0032	801-06640	CONSTRUCTION SIGN, TYPE A	13.00	ACH
0033	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	ACH
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	ACH
0036	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	210.00	LFT
0037	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	70.00	LFT
0038	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	ACH
0039	801-12324	LAW ENFORCEMENT OFFICER	100.00	HRS
0040	802-91122	SIGN, GROUND MOUNTED, RESET	1.00	ACH
0041	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	22.00	SYS
0042	808-06716	LINE, REMOVE	468.00	LFT
0043	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	24.00	LFT
0044	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	179.00	LFT
0045	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	60.00	LFT
0046	808-10077	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, LANE INDICATION ARROW	2.00	ACH

Call: 490

Contract: B -44426-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS, STRUCTURE NO.	1.00	LS
0012	203-02000	EXCAVATION, COMMON	250.00	CYS
0013	203-02070	BORROW	585.00	CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	11929.00	DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	672.00	SYS
0017	214-12239	GEOTEXTILE FOR PAVEMENT, TYPE 2B	672.00	SYS
0018	301-12234	COMPACTED AGGREGATE, NO. 53	60.00	CYS
0019	303-01180	COMPACTED AGGREGATE, NO. 53	225.00	TON
0020	306-08034	MILLING, ASPHALT, 1 1/2 IN.	255.00	SYS
0021	306-08043	MILLING, TRANSITION	672.00	SYS
0022	401-000002	QC/QA-HMA, 3, 58S, SURFACE, 9.5 mm	133.00	TON
0023	401-000038	QC/QA-HMA, 3, 58S, INTERMEDIATE, 19.0 mm	150.00	TON
0024	401-000047	QC/QA-HMA, 3, 58S, BASE, 25.0 mm	228.00	TON
0025	401-11526	JOINT ADHESIVE	1200.00	LFT
0026	401-12439	VOID REDUCING ASPHALT MEMBRANE FOR HMA	1335.00	LFT
0027	406-05521	ASPHALT FOR TACK COAT	2558.00	SYS
0028	503-05240	D-1 CONTRACTION JOINT	51.00	LFT
0029	601-02241	GUARDRAIL, REMOVE	270.00	LFT
0030	601-06035	GUARDRAIL, RESET	60.00	LFT
0031	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	113.00	LFT

0032	601-12289	GUARDRAIL HEIGHT TRANSITION, MGS	1.00	ACH
0033	601-12292	GUARDRAIL TRANSITION, MGS WITHOUT CURB	4.00	ACH
0034	601-94689	GUARDRAIL END TREATMENT, TYPE OS	3.00	ACH
0035	602-06729	BARRIER DELINEATOR	4.00	ACH
0036	615-06490	RIGHT-OF-WAY MARKER	8.00	ACH
0037	615-06505	MONUMENT, TYPE B	4.00	ACH
0038	615-06510	MONUMENT, TYPE C	1.00	ACH
0039	616-06405	RIPRAP, REVETMENT	9.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	12.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0042	621-06559	MULCHED SEEDING, TYPE R	1452.00	SYS
0043	621-06574	SODDING	4.00	SYS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0045	628-12683	FIELD OFFICE, TYPE D	10.00	MOS
0046	702-92857	CONCRETE, C, SUBSTRUCTURE	6.70	CYS
0047	703-06029	REINFORCING BARS, EPOXY COATED	8423.00	LBS
0048	706-09960	RAILING, CONCRETE TYPE FC	70.00	LFT
0049	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TYPE TFC	4.00	ACH
0050	706-12272	REINFORCED CONCRETE MOMENT SLAB, 10 IN.	126.00	SYS
0051	709-51821	SURFACE SEAL	1.00	LS
0052	710-09158	PATCHING CONCRETE STRUCTURES	334.00	SFT
0053	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	ACH
0054	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	ACH
0055	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	ACH
0056	801-06645	CONSTRUCTION SIGN, TYPE B	8.00	ACH
0057	801-06775	MAINTAINING TRAFFIC	1.00	LS
0058	801-07118	BARRICADE, TYPE III-A	48.00	LFT
0059	801-07119	BARRICADE, TYPE III-B	40.00	LFT
0060	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	890.00	LFT
0061	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	890.00	LFT

Call: 510

Contract: B -44815-A

Section No.: 1 IDIQ DISTRICT WIDE BRIDGE MAINTENANCE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	42000.00	DOL
0008	202-02240	PAVEMENT REMOVAL	195.00	SYS
0009	202-51368	SLOPEWALL, REMOVE	358.00	SYS
0010	203-02000	EXCAVATION, COMMON	58.00	CYS
0011	213-09270	FLOWABLE BACKFILL, REMOVABLE	173.00	CYS
0012	303-01180	COMPACTED AGGREGATE, NO. 53	58.00	TON
0013	304-12625	HMA PATCHING, FULL DEPTH, TYPE C	50.00	TON
0014	304-12626	HMA PATCHING, PARTIAL DEPTH, TYPE C	150.00	TON
0015	402-07452	HMA WEDGE AND LEVEL, TYPE C	200.00	TON
0016	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	325.00	SYS
0017	616-06405	RIPRAP, REVETMENT	98.00	TON
0018	616-51367	SLOPEWALL, CONCRETE, 4 IN.	285.00	SYS
0019	616-93772	INSPECTION HOLE	7.00	EACH
0020	702-51015	CONCRETE, B, FOOTINGS	5.00	CYS
0021	702-90915	CONCRETE, A	15.00	CYS
0022	702-93722	CONCRETE, C	20.00	CYS
0023	703-06029	REINFORCING BARS, EPOXY COATED	2000.00	LBS
0024	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	525.00	SFT
0025	710-09158	PATCHING CONCRETE STRUCTURES	500.00	SFT
0026	711-04297	STRUCTURAL STEEL, FIELD CUT	105.00	SQIN
0027	711-11599	REPAIR WELD	36.00	IN
0028	711-51035	STRUCTURAL STEEL	1500.00	LBS
0029	711-51864	DRILLED HOLE	47.00	EACH
0030	722-12464	BRIDGE DECK, REMOVE CONCRETE SURFACE	625.00	SYS
0031	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	73.00	SFT

0032	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	542.00	SFT
0033	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	161.00	LFT
0034	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	9.00	GAL
0035	727-90308	EPOXY INJECTION, CRACK PREPARATION	55.00	LFT
0036	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	717.00	SYS
0037	801-06640	CONSTRUCTION SIGN, TYPE A	32.00	EACH
0038	801-06645	CONSTRUCTION SIGN, TYPE B	15.00	EACH
0039	801-06710	FLASHING ARROW SIGN	38.00	DAY
0040	801-07118	BARRICADE, TYPE III-A	83.00	LFT
0041	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	350.00	LFT
0042	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	9.00	EACH
0043	801-12042	TRUCK MOUNTED ATTENUATOR	18.00	DAY
0044	801-12324	LAW ENFORCEMENT OFFICER	100.00	HRS
0045	801-12440	MAINTAINING TRAFFIC, IDIQ	84000.00	DOL

Call: 520

Contract: B -44930-A

Section No.: 1 SCOUR PROTECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT-OF-WAY	1.00	LS
0009	205-12108	STORMWATER MANAGEMENT BUDGET	24790.00	DOL
0010	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0011	206-51235	COFFERDAM	1.00	LS
0012	616-05689	RIPRAP, CLASS 2	879.00	TON
0013	616-12249	GEOTEXTILE FOR RIPRAP, TYPE 2B	601.00	SYS
0014	619-12459	DISPOSAL OF CLEANING WASTE, HAZARDOUS, BRIDGE NO.	1.00	LS
0015	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0016	621-02356	SEEDING WETLAND	7.00	LBS
0017	621-02770	EROSION CONTROL BLANKET	215.00	SYS
0018	621-06559	MULCHED SEEDING, TYPE R	1206.00	SYS
0019	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0020	702-51005	CONCRETE, A, SUBSTRUCTURE	38.00	CYS
0021	703-06029	REINFORCING BARS, EPOXY COATED	2700.00	LBS
0022	710-09158	PATCHING CONCRETE STRUCTURES	12.00	SFT
0023	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	4.00	GAL
0024	727-90308	EPOXY INJECTION, CRACK PREPARATION	143.00	LFT
0025	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 530

Contract: B -44941-A

Section No.: 1 SCOUR PROTECTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT-OF-WAY	1.00 LS
0010	201-90788	DEBRIS, REMOVE, STRUCTURE NO.	1.00 LS
0011	203-51223	EXCAVATION, WATERWAY	161.00 CYS
0012	205-11626	PUMP AROUND	1.00 ACH
0013	205-12108	STORMWATER MANAGEMENT BUDGET	17402.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	206-51235	COFFERDAM	1.00 LS
0016	303-01180	COMPACTED AGGREGATE, NO. 53	8.00 TON
0017	601-06035	GUARDRAIL, RESET	180.00 LFT
0018	616-02281	GROUT FOR RIPRAP	41.00 CYS
0019	616-06405	RIPRAP, REVETMENT	1322.00 TON
0020	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	514.00 SYS
0021	616-12251	GEOTEXTILE FOR RIPRAP, TYPE 3	1183.00 SYS
0022	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 ACH
0023	621-06560	MULCHED SEEDING, TYPE U	2449.00 SYS
0024	628-09403	FIELD OFFICE, TYPE C	10.00 MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 ACH
0026	715-05407	PIPE, END BENT DRAIN, DIAMETER 6 IN.	40.00 LFT
0027	801-03290	CONSTRUCTION SIGN, TYPE C	4.00 ACH
0028	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1320.00 LFT
0029	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	3.00 ACH
0030	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	2.00 ACH
0031	801-06640	CONSTRUCTION SIGN, TYPE A	37.00 ACH

0032	801-06645	CONSTRUCTION SIGN, TYPE B	6.00	EACH
0033	801-06710	FLASHING ARROW SIGN	14.00	DAY
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-07118	BARRICADE, TYPE III-A	24.00	LFT
0036	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	120.00	LFT
0037	801-12042	TRUCK MOUNTED ATTENUATOR	14.00	DAY
0038	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	8.00	EACH
0039	801-12930	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, INTERMITTENT	2.00	EACH
0040	801-12956	TEMPORARY PAVEMENT MARKING, REMOVABLE, 10 IN.	550.00	LFT
0041	802-91122	SIGN, GROUND MOUNTED, RESET	2.00	EACH
0042	808-06716	LINE, REMOVE	165.00	LFT
0043	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	200.00	LFT
0044	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	200.00	LFT
0045	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	215.00	LFT

Call: 550

Contract: B -45595-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	202-74035	SIGN, REMOVE	2.00 EACH
0009	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	120.00 SFT
0010	507-12941	RCBA CRACK FILLING, PCC SEALER/HEALER	36.00 LFT
0011	628-09403	FIELD OFFICE, TYPE C	8.00 MOS
0012	709-51821	SURFACE SEAL	1.00 LS
0013	709-51821	SURFACE SEAL	1.00 LS
0014	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	98.00 SFT
0015	738-12855	WARRANTED POLYMER OVERLAY, BRIDGE DECK	626.00 SYS
0016	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00 EACH
0017	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	5522.00 LFT
0018	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00 LFT
0019	801-06625	DETOUR ROUTE MARKER ASSEMBLY	38.00 EACH
0020	801-06640	CONSTRUCTION SIGN, TYPE A	26.00 EACH
0021	801-06645	CONSTRUCTION SIGN, TYPE B	7.00 EACH
0022	801-06775	MAINTAINING TRAFFIC	1.00 LS
0023	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00 EACH
0024	801-07118	BARRICADE, TYPE III-A	112.00 LFT
0025	801-07119	BARRICADE, TYPE III-B	240.00 LFT
0026	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	150.00 LFT
0027	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	240.00 LFT
0028	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0029	801-12081	PORTABLE SIGNAL	1.00 LS
0030	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY, CONTINUOUS	4.00 EACH
0031	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	1.00 SFT

0032	808-06716	LINE, REMOVE	2080.00	LFT
0033	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2112.00	LFT
0034	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	185.00	LFT
0035	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	395.00	LFT
0036	809-08372	ROADWAY WEATHER INFORMATION SYSTEM	1.00	ACH

Call: 560

Contract: B -45609-A

Section No.: 1 SUBSTRUCTURE REPAIR AND REHABILITATION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	703-08247	EMBEDDED GALVANIC ANODE	150.00	ACH
0008	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	190.00	SFT
0009	710-09158	PATCHING CONCRETE STRUCTURES	175.00	SFT
0010	801-06640	CONSTRUCTION SIGN, TYPE A	10.00	ACH
0011	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 570

Contract: B -45796-A

Section No.: 1 IDIQ, SOIL NAILED WALL AND MSE REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	897646.63 DOL
0007	201-06587	CLEARING AND GRUBBING	0.09 ACRE
0008	201-06587	CLEARING AND GRUBBING	0.50 ACRE
0009	203-02000	EXCAVATION, COMMON	900.00 CYS
0010	203-02070	BORROW	65.00 CYS
0011	213-09270	FLOWABLE BACKFILL, REMOVABLE	200.00 CYS
0012	605-06121	CURB, CONCRETE, TYPE B	25.00 LFT
0013	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	550.00 LFT
0014	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	70.00 LFT
0015	612-04315	MATERIAL FOR UNDERSEAL	5.00 TON
0016	612-12681	DEFLECTION TESTING FOR UNDERSEAL	2.00 ACH
0017	612-60410	DRILLED HOLE FOR UNDERSEAL	6.00 ACH
0018	616-01763	RIPRAP, RELAID	570.00 SYS
0019	616-06405	RIPRAP, REVETMENT	1060.00 TON
0020	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	2280.00 SYS
0021	628-09403	FIELD OFFICE, TYPE C	12.00 MOS
0022	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 ACH
0023	702-12675	MAINTAINABLE DRAIN, STEEL, 4 IN.	10.00 ACH
0024	702-51863	FIELD DRILLED HOLE IN CONCRETE	20.00 ACH
0025	708-51813	PNEUMATICALLY PLACED MORTAR	35.00 SFT
0026	708-51814	WELDED STEEL WIRE REINFORCEMENT	35.00 SFT
0027	710-09158	PATCHING CONCRETE STRUCTURES	30.00 SFT
0028	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	120.00 LFT
0029	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	40.00 GAL
0030	727-90308	EPOXY INJECTION, CRACK PREPARATION	40.00 LFT
0031	731-000191	MSE WALL PANEL REPLACEMENT, AND REPAIR	30.00 SFT

0032	731-05947	CONCRETE COPING	288.00	LFT
0033	731-05947	CONCRETE COPING	170.00	LFT
0034	731-12677	SOIL NAILED WALL REINFORCEMENT	12.00	EACH
0035	731-12679	MSE PANEL JOINT SEALING	1040.00	LFT
0036	801-06640	CONSTRUCTION SIGN, TYPE A	280.00	EACH
0037	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0038	801-06710	FLASHING ARROW SIGN	30.00	DAY
0039	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0040	801-12440	MAINTAINING TRAFFIC, IDIQ	415621.90	DOL

Call: 580

Contract: B -45797-A

Section No.: 1 IDIQ, SOIL NAILED WALL AND MSE REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	897646.30	DOL
0007	201-06587	CLEARING AND GRUBBING	0.09	ACRE
0008	201-06587	CLEARING AND GRUBBING	0.50	ACRE
0009	203-02000	EXCAVATION, COMMON	900.00	CYS
0010	203-02070	BORROW	65.00	CYS
0011	213-09270	FLOWABLE BACKFILL, REMOVABLE	200.00	CYS
0012	605-06121	CURB, CONCRETE, TYPE B	25.00	LFT
0013	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	550.00	LFT
0014	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	70.00	LFT
0015	612-04315	MATERIAL FOR UNDERSEAL	5.00	TON
0016	612-12681	DEFLECTION TESTING FOR UNDERSEAL	2.00	ACH
0017	612-60410	DRILLED HOLE FOR UNDERSEAL	6.00	ACH
0018	616-01763	RIPRAP, RELAID	570.00	SYS
0019	616-06405	RIPRAP, REVETMENT	1060.00	TON
0020	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	2280.00	SYS
0021	628-09403	FIELD OFFICE, TYPE C	12.00	MOS
0022	702-12675	MAINTAINABLE DRAIN, STEEL, 4 IN.	10.00	ACH
0023	702-51863	FIELD DRILLED HOLE IN CONCRETE	20.00	ACH
0024	708-51813	PNEUMATICALLY PLACED MORTAR	35.00	SFT
0025	708-51814	WELDED STEEL WIRE REINFORCEMENT	35.00	SFT
0026	710-09158	PATCHING CONCRETE STRUCTURES	30.00	SFT
0027	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	120.00	LFT
0028	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	40.00	GAL
0029	727-90308	EPOXY INJECTION, CRACK PREPARATION	40.00	LFT
0030	731-000191	MSE WALL PANEL REPLACEMENT, AND REPAIR	30.00	SFT
0031	731-05947	CONCRETE COPING	302.00	LFT

0032	731-05947	CONCRETE COPING	170.00	LFT
0033	731-12677	SOIL NAILED WALL REINFORCEMENT	12.00	EACH
0034	731-12679	MSE PANEL JOINT SEALING	1040.00	LFT
0035	801-06640	CONSTRUCTION SIGN, TYPE A	280.00	EACH
0036	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	EACH
0037	801-06710	FLASHING ARROW SIGN	30.00	DAY
0038	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0039	801-12440	MAINTAINING TRAFFIC, IDIQ	415621.90	DOL

Call: 590

Contract: B -45798-A

Section No.: 1 IDIQ, SOIL NAILED WALL AND MSE REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	897646.30	DOL
0007	201-06587	CLEARING AND GRUBBING	0.09	ACRE
0008	201-06587	CLEARING AND GRUBBING	0.50	ACRE
0009	203-02000	EXCAVATION, COMMON	900.00	CYS
0010	203-02070	BORROW	69.00	CYS
0011	213-09270	FLOWABLE BACKFILL, REMOVABLE	200.00	CYS
0012	605-06121	CURB, CONCRETE, TYPE B	20.00	LFT
0013	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	550.00	LFT
0014	605-06145	CURB AND GUTTER, CONCRETE, TYPE B	70.00	LFT
0015	612-04315	MATERIAL FOR UNDERSEAL	10.00	TON
0016	612-12681	DEFLECTION TESTING FOR UNDERSEAL	3.00	ACH
0017	612-60410	DRILLED HOLE FOR UNDERSEAL	12.00	ACH
0018	616-01763	RIPRAP, RELAID	570.00	SYS
0019	616-06405	RIPRAP, REVETMENT	1060.00	TON
0020	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	2280.00	SYS
0021	702-12675	MAINTAINABLE DRAIN, STEEL, 4 IN.	10.00	ACH
0022	702-51863	FIELD DRILLED HOLE IN CONCRETE	23.00	ACH
0023	708-51813	PNEUMATICALLY PLACED MORTAR	40.00	SFT
0024	708-51814	WELDED STEEL WIRE REINFORCEMENT	40.00	SFT
0025	710-09158	PATCHING CONCRETE STRUCTURES	30.00	SFT
0026	724-12773	BRIDGE EXPANSION JOINT, TYPE PCF	120.00	LFT
0027	727-000188	EPOXY INJECTION, EPOXY INJECTION ADHESIVE	40.00	GAL
0028	727-90308	EPOXY INJECTION, CRACK PREPARATION	40.00	LFT
0029	731-000191	MSE WALL PANEL REPLACEMENT, AND REPAIR	30.00	SFT
0030	731-05947	CONCRETE COPING	346.00	LFT
0031	731-05947	CONCRETE COPING	170.00	LFT

0032	731-12677	SOIL NAILED WALL REINFORCEMENT	10.00	ACH
0033	731-12679	MSE PANEL JOINT SEALING	1040.00	LFT
0034	801-06640	CONSTRUCTION SIGN, TYPE A	280.00	ACH
0035	801-06645	CONSTRUCTION SIGN, TYPE B	2.00	ACH
0036	801-06710	FLASHING ARROW SIGN	30.00	DAY
0037	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	ACH
0038	801-12440	MAINTAINING TRAFFIC, IDIQ	415621.90	DOL

Call: 650

Contract: M -46407-A

Section No.: 1 LITTER AND DEBRIS REMOVAL

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0004	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0005	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0006	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0007	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0008	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0009	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0010	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0011	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0012	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0013	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS
0014	202-000213	LITTER AND DEBRIS, REMOVE	1.00	LS

Call: 710

Contract: T -44085-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	19.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	32.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	2.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	202-02278	CURB, CONCRETE, REMOVE	107.00 LFT
0013	202-02279	CURB AND GUTTER, REMOVE	419.00 LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	436.00 SYS
0015	202-86946	HANDHOLE, REMOVE	22.00 EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	14656.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	265.00 SYS
0019	214-11796	GEOGRID, TYPE IB	156.00 SYS
0020	302-07455	DENSE GRADED SUBBASE	26.00 CYS
0021	304-12623	HMA PATCHING, FULL DEPTH, TYPE B	287.00 TON
0022	406-05521	ASPHALT FOR TACK COAT	109.00 SYS
0023	604-06070	SIDEWALK, CONCRETE	163.00 SYS
0024	604-08086	CURB RAMP, CONCRETE	293.00 SYS
0025	604-12083	DETECTABLE WARNING SURFACES	35.00 SYS
0026	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00 SYS
0027	605-06120	CURB, CONCRETE	155.00 LFT
0028	605-06140	CURB AND GUTTER, CONCRETE	433.00 LFT
0029	610-07487	HMA FOR APPROACHES, TYPE B	61.00 TON
0030	610-09108	PCCP FOR APPROACHES, 9 IN.	156.00 SYS
0031	628-09403	FIELD OFFICE, TYPE C	12.00 MOS

0032	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	ACH
0033	720-12797	CASTING, INLET, ADJUST TO GRADE	3.00	ACH
0034	720-44070	CASTING, TYPE 13, FURNISH AND ADJUST TO GRADE	2.00	ACH
0035	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1068.00	LFT
0036	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	42.00	LFT
0037	801-06640	CONSTRUCTION SIGN, TYPE A	36.00	ACH
0038	801-06645	CONSTRUCTION SIGN, TYPE B	40.00	ACH
0039	801-06710	FLASHING ARROW SIGN	20.00	DAY
0040	801-06775	MAINTAINING TRAFFIC	1.00	LS
0041	801-11990	TEMPORARY CURB RAMP	22.00	ACH
0042	801-12390	TEMPORARY PAVEMENT MARKING, REMOVABLE, 7 IN.	722.00	LFT
0043	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	1434.00	LFT
0044	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	137.00	LFT
0045	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	10.00	ACH
0046	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	278.00	SFT
0047	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	302.00	SFT
0048	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	492.00	SFT
0049	802-74050	SIGN, OVERHEAD, REMOVE	58.00	ACH
0050	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	9.00	ACH
0051	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0052	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	19.00	ACH
0053	805-01842	HANDHOLE, SIGNAL, TYPE 1	45.00	ACH
0054	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0055	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	42.00	ACH
0056	805-02445	CONTROLLER AND CABINET, TYPE P1	9.00	ACH
0057	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	32.00	ACH
0058	805-04133	SIGNAL POLE, PEDESTAL, 12 FT	28.00	ACH
0059	805-07767	SIGNAL CABLE, CONTROL, COPPER, 12C/14 GAUGE	4637.00	LFT
0060	805-08244	CELLULAR MODEM KIT	9.00	ACH
0061	805-09451	SIGNAL POLE, PEDESTAL, 15 FT	4.00	ACH
0062	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	47.00	ACH
0063	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	2108.00	LFT
0064	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	4843.00	LFT
0065	805-11817	PEDESTRIAN PUSH BUTTON, APS	42.00	ACH
0066	805-78205	TRAFFIC SIGNAL HEAD, NO. 3 SECTION, 12 IN.	80.00	ACH
0067	805-78225	TRAFFIC SIGNAL HEAD, NO. 4 SECTION, 12 IN.	11.00	ACH
0068	805-78415	SPAN, CATENARY, AND TETHER	34.00	ACH

0069	805-78420	DISCONNECT HANGER	34.00	ACH
0070	805-78445	SIGNAL SERVICE	5.00	ACH
0071	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	213.00	LFT
0072	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	16420.00	LFT
0073	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	4681.00	LFT
0074	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	11002.00	LFT
0075	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	1937.00	LFT
0076	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	22946.00	LFT
0077	805-78785	SIGNAL DETECTOR HOUSING	52.00	ACH
0078	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	6409.00	LFT
0079	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	9.00	ACH
0080	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	12.00	ACH
0081	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	7.00	ACH
0082	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	22.00	SYS
0083	808-06368	TRANSVERSE MARKING, REMOVE	1728.00	LFT
0084	808-06716	LINE, REMOVE	15838.00	LFT
0085	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	560.00	LFT
0086	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	4998.00	LFT
0087	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	3588.00	LFT
0088	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN.	1686.00	LFT
0089	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	176.00	LFT
0090	808-12032	GROOVING FOR PAVEMENT MARKINGS	15838.00	LFT
0091	808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	163.00	LFT
0092	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	2134.00	LFT
0093	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1394.00	LFT
0094	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	225.00	LFT
0095	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	7.00	ACH
0096	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1248.00	LFT
0097	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	126.00	LFT
0098	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	641.00	LFT
0099	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION ARROW	6.00	ACH
0100	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, 'ONLY'	2.00	ACH
0101	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	189.00	ACH
0102	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	189.00	ACH
0103	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	314.00	LFT
0104	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	313.00	LFT

Call: 720

Contract: T -44798-A

Section No.: 1 ITS TRAFFIC MANAGEMENT SYSTEMS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-06775	MAINTAINING TRAFFIC	1.00	LS
0008	801-92448	CONSTRUCTION SIGNS MOBILE	28.00	DAY
0009	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	77.00	ACH
0010	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0011	805-02445	CONTROLLER AND CABINET, TYPE P1	7.00	ACH
0012	805-06483	CONTROLLER	68.00	ACH
0013	805-93555	CONTROLLER AND CABINET, TYPE M	2.00	ACH
0014	809-000119	REMOTE POWER SWITCH	7.00	ACH
0015	809-06128	CCTV ASSEMBLY	7.00	ACH
0016	809-09343	ITS	77.00	ACH
0017	809-09343	ITS	70.00	ACH
0018	809-09343	ITS	7.00	ACH

Call: 840

Contract: TM-46406-A

Section No.: 1 LIGHTING MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
0001	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360		CONTRACT LIENS	1.00	DOL
0003	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08463		PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0005	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	202-01604		ROADWAY COLUMN, REMOVE	1.00	EACH
0007	202-52710		SIDEWALK CONCRETE, REMOVE	20.00	SYS
0008	202-96391		MAST ARM, REMOVE	5.00	EACH
0009	604-06070		SIDEWALK, CONCRETE	20.00	SYS
0010	702-90915		CONCRETE, A	1.00	CYS
0011	801-06640		CONSTRUCTION SIGN, TYPE A	20.00	EACH
0012	801-06710		FLASHING ARROW SIGN	40.00	DAY
0013	801-06775		MAINTAINING TRAFFIC	1.00	LS
0014	802-09840		SIGN, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00	SFT
0015	802-10172		SIGN, LED BLANK OUT	2.00	EACH
0016	802-12222		WIDE FLANGE SIGN POST SUPPORT FOUNDATION, TYPE A	4.00	EACH
0017	805-01419		CIRCUIT BREAKER, INSTALL	10.00	EACH
0018	805-01421		SERVICE POINT RISER AND WEATHERHEAD	20.00	EACH
0019	805-01842		HANDHOLE, SIGNAL, TYPE 1	8.00	EACH
0020	805-01844		CONDUIT, STEEL, GALVANIZED, 2 IN.	390.00	LFT
0021	805-02116		CIRCUIT BREAKER, FURNISH	5.00	EACH
0022	805-02445		CONTROLLER AND CABINET, TYPE P1	1.00	EACH
0023	805-02645		SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	5.00	EACH
0024	805-07190		TRAFFIC SIGNAL HEAD, NO. 1 SECTION, 12 IN.	8.00	EACH
0025	805-08244		CELLULAR MODEM KIT	1.00	EACH
0026	805-09451		SIGNAL POLE, PEDESTAL, 15 FT	5.00	EACH
0027	805-09539		LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 2 CHANNEL	1.00	EACH
0028	805-11815		CONDUIT, HDPE, 2 IN. SCHEDULE 80	2190.00	LFT
0029	805-12830		LOOP DETECTOR DELAY AMPLIFIER, COUNTING, NO. 4 CHANNEL	1.00	EACH
0030	805-78445		SIGNAL SERVICE	1.00	EACH
0031	805-78467		SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	100.00	LFT

0032	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	1400.00	LFT
0033	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	2830.00	LFT
0034	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	4710.00	LFT
0035	805-78785	SIGNAL DETECTOR HOUSING	4.00	ACH
0036	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	500.00	LFT
0037	805-78925	CONTROLLER CABINET FOUNDATION, TYPE P1	1.00	ACH
0038	805-91706	ANCHOR BOLT REPAIR	3.00	ACH
0039	807-01562	POWER DISCONNECT PLUG FOR HIGH MAST TOWER	1.00	ACH
0040	807-01617	HANDHOLE, COVER AND RING	1.00	ACH
0041	807-02113	MAST ARM, 1.5 FT TO 6 FT, FURNISH	5.00	ACH
0042	807-02114	MAST ARM, 8 FT TO 30 FT, FURNISH	5.00	ACH
0043	807-02191	HANDHOLE, LIGHTING	3.00	ACH
0044	807-02201	SHAFT FOR ANY E.M.H., ANY MAST ARM, FURNISH	2.00	ACH
0045	807-04940	MAST ARM	5.00	ACH
0046	807-11772	LUMINAIRE, DIAGNOSIS AND REPAIR	10.00	ACH
0047	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	2.00	ACH
0048	807-12201	LUMINAIRE, HIGH MAST	2.00	ACH
0049	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	10.00	ACH
0050	807-12206	LUMINAIRE, UNDERPASS	10.00	ACH
0051	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE, WITH GROUNDING	5.00	ACH
0052	807-12962	LED DRIVER REPLACEMENT	10.00	ACH
0053	807-86810	SERVICE POINT, TYPE II	1.00	ACH
0054	807-86843	WIRE, NO. 4 COPPER, 1/C	24410.00	LFT
0055	807-86910	CONNECTOR KIT, UNFUSED	19.00	ACH
0056	807-86915	CONNECTOR KIT, FUSED	19.00	ACH
0057	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	135.00	ACH
0058	807-86930	INSULATION LINK, NON-WATERPROOFED	64.00	ACH
0059	807-86955	CABLE-DUCT MARKER	1.00	ACH
0060	807-87085	ELECTRICIAN	30.00	HRS
0061	807-87098	CALLOUT REPAIR	5.00	ACH
0062	807-87556	WIRE, TW/THW, NO. 10 COPPER, STRANDED	837.00	LFT
0063	807-87800	CABLE DUCT, INSTALL	3036.00	LFT
0064	807-91705	CONDUIT, POLYETHYLENE REPAIR	1.00	ACH
0065	807-93650	FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL, FOR ROADWAY LIGHT	1.00	SET
0066	807-93746	TOWER RING, LIFT CABLE, 0.375	80.00	LFT
0067	807-93747	TOWER RING, SUSPENSION CABLE, 0.1875	80.00	LFT
0068	807-94480	LIGHT STANDARD, INSTALL	10.00	ACH

0069	807-95078	TRANSFORMER BASE	9.00	EACH
0070	807-95488	NEMA 4/5 UNDERPASS OR SIGN CIRCUIT BREAKER, ENCLOSURE	1.00	EACH
0071	807-95513	SERVICE POINT, MAIN BREAKER	1.00	EACH
0072	807-95516	RELAY SWITCH	3.00	EACH
0073	807-95523	WATERPROOFING OF ELECTRICAL CONNECTOR	44.00	EACH
0074	807-95525	LIGHTING SUPPORT	1.00	EACH
0075	807-95709	PHOTOCELLS	10.00	EACH
0076	807-95889	WIRE, NO. 10 COPPER, 1/C	500.00	LFT
0077	807-96868	LUMINAIRE, INSTALL	10.00	EACH