

Schedule of Pay Items Letting Date November 13, 2025 Letting ID 251113

Call: 201

Contract: R -43760-A

Section No.: 1 SLIDE CORRECTION

Line	Item No	Item Code	Description	Quantity	Unit
0001	104-05404		DESIGN BUILD	1.00	LS
0002	105-06845		CONSTRUCTION ENGINEERING	1.00	LS
0003	109-08359		LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360		CONTRACT LIENS	1.00	DOL
0005	109-08440		QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443		QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444		QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489		PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.00	DOL
0009	109-11362		QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001		MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370		CLEARING RIGHT-OF-WAY	1.00	LS
0012	202-02271		HEADWALL, REMOVE	2.00	ACH
0013	202-02637		PIPE ABANDON AND GROUT FILL	211.00	LFT
0014	203-02000		EXCAVATION, COMMON	1598.00	CYS
0015	203-02010		EXCAVATION, ROCK	12.00	CYS
0016	205-11626		PUMP AROUND	1.00	ACH
0017	205-12108		STORMWATER MANAGEMENT BUDGET	12999.00	DOL
0018	205-12616		STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618		SWQCP PREPARATION	1.00	LS
0020	206-51235		COFFERDAM	1.00	LS
0021	207-09935		SUBGRADE TREATMENT, TYPE IC	745.00	SYS
0022	211-09265		STRUCTURE BACKFILL, TYPE 2	551.00	CYS
0023	301-12233		COMPACTED AGGREGATE, NO. 8	4.00	CYS
0024	303-01180		COMPACTED AGGREGATE, NO. 53	587.00	TON
0025	306-08034		MILLING, ASPHALT, 1 1/2 IN.	1755.00	SYS
0026	401-000001		QC/QA-HMA, 2, 58S, SURFACE, 9.5 mm	197.00	TON
0027	401-000037		QC/QA-HMA, 2, 58S, INTERMEDIATE, 19.0 mm	83.00	TON
0028	401-000052		QC/QA-HMA, 2, 58S, BASE, 19.0 mm	276.00	TON
0029	401-11526		JOINT ADHESIVE	1665.00	LFT
0030	406-05520		ASPHALT FOR TACK COAT	2.00	TON
0031	601-02241		GUARDRAIL, REMOVE	999.00	LFT

0032	601-12281	GUARDRAIL, MGS W-BEAM, 6 FT 3 IN. SPACING	1375.00	LFT
0033	601-94689	GUARDRAIL END TREATMENT, TYPE OS	4.00	ACH
0034	616-02281	GROUT FOR RIPRAP	21.00	CYS
0035	616-05688	RIPRAP, CLASS 1	30.00	TON
0036	616-06405	RIPRAP, REVETMENT	221.00	TON
0037	616-12246	GEOTEXTILE FOR RIPRAP, TYPE 1A	359.00	SYS
0038	616-12248	GEOTEXTILE FOR RIPRAP, TYPE 2A	64.00	SYS
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	ACH
0040	621-02770	EROSION CONTROL BLANKET	668.00	SYS
0041	621-03909	SEED MIXTURE, NATIVE	44.00	LBS
0042	621-06565	MULCHING MATERIAL	2.00	TON
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	ACH
0044	628-12683	FIELD OFFICE, TYPE D	12.00	MOS
0045	629-000149	TOPSOIL PROCESSING AND DISTRIBUTION	5265.00	SYS
0046	629-000150	TOPSOIL AMENDMENT BUDGET	10530.00	DOL
0047	702-51005	CONCRETE, A, SUBSTRUCTURE	26.00	CYS
0048	715-01662	PIPE CLEANING, DIAMETER 12 IN. TO 48 IN.	365.00	LFT
0049	715-05125	PIPE, TYPE 1, CIRCULAR, DIAMETER 30 IN.	140.00	LFT
0050	725-10221	LINER PIPE, THERMOPLASTIC, CIRCULAR, 4.3-4.4 SFT	154.00	LFT
0051	725-10245	PERPETUATION, EXISTING PIPE	1.00	ACH
0052	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	ACH
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	ACH
0054	801-06640	CONSTRUCTION SIGN, TYPE A	12.00	ACH
0055	801-06645	CONSTRUCTION SIGN, TYPE B	5.00	ACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07118	BARRICADE, TYPE III-A	72.00	LFT
0058	801-07119	BARRICADE, TYPE III-B	72.00	LFT
0059	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	24.00	LFT
0060	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	3.00	ACH
0061	802-91122	SIGN, GROUND MOUNTED, RESET	1.00	ACH
0062	808-12032	GROOVING FOR PAVEMENT MARKINGS	1979.00	LFT
0063	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1130.00	LFT
0064	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	565.00	LFT
0065	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	19.00	ACH
0066	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	19.00	ACH
0067	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	142.00	LFT
0068	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	142.00	LFT