



**State of Indiana
Department of Natural Resources**



DNR 30-DAY PUBLIC NOTICE

The Department of Natural Resources serves the DNR 30-Day Public Notice in order to satisfy the requirements of the "Procedures Concerning Certain Licenses Act", IC 14-11-4, and its associated administrative rule, 312 IAC 2-3.

The DNR 30-Day Public Notice is published weekly to serve notice of the latest permit applications received at the DNR, Division of Water. This Notice can be viewed on the web at <http://www.in.gov/dnr/water/> and can be provided by email upon written request. To receive the DNR 30-Day Public Notice as a weekly email attachment, email your full name and a valid email address to DNRPublicNoticeRecipient@dnr.IN.gov.

The permit applications and supporting documentation is available for public viewing on-line at <https://dowunity.dnr.in.gov/#>. For questions concerning a permit application, contact the Division of Water, Technical Services Section, at (317) 232-4160 or toll free at 1-877-928-3755 and select 1 during the recorded menu narrative.

Petition for Public Hearing

A pre-action public hearing on an application may be requested by filing a written petition. For a petition to be considered valid it must:

1. contain the typed or legibly printed name and complete mailing address of each petitioner;
2. be signed by a minimum of 25 individuals who are at least 18 years old and either reside in the county where the project will take place or own real property within 1 mile of the project site;
3. affirm that each signatory to the petition satisfies the requirements of item 2; and
4. identify the application for which the public hearing is being requested either by the application # or the applicant's name and the project description.

A petition which does not meet these requirements will be considered invalid and the hearing request will not be granted. To request a pre-action public hearing, send the petition by email to water_inquiry@dnr.in.gov or by mail to:

IDNR, Division of Water
Technical Services Section
402 West Washington Street, Room W264
Indianapolis, Indiana 46204-2641

Notification of Department Action

A person may request that the Department notify them when a Department Action is issued. To be notified of a Department Action, send a request that includes the permit application number or the applicant name, project description and county to email address water_inquiry@dnr.in.gov or by mail to the address above.

Permit Application Numbers with a prefix of:

FW are being reviewed under the Flood Control Act, IC 14-28-1 and the Flood Plain Management Rule, 312 IAC 10

PL are being reviewed under the Lake Preservation Act, IC 14-26-2 and the Public Freshwater Lake Rule, 312 IAC 11

DR are being reviewed under the Lowering of the Ten Acre Lake Act, IC 14-26-5

NW are being reviewed under the Navigable Waterways Act, IC 14-29-1

LM are being reviewed under the Navigable Waterways Act, IC 14-29-1 related to Lake Michigan

SG are being reviewed under the Sand and Gravel Permits Act, IC 14-29-3

AC are being reviewed under the Construction of Channels Act, IC14-29-4



**State of Indiana
Department of Natural Resources**



DNR 30-DAY PUBLIC NOTICE

Date: 7/8/2026

Application #: FW-33393-0

Received Date: 8/7/2025

Waterbody: West Fork White River

County: Morgan

Applicant: David Allson, 7195 North Waverly Park Road, Martinsville, IN, 46151

Project Description: A gravel mining facility will be developed and operated in the floodway of the West Fork White River. The gravel mining facility will have support facilities like an office building and outdoor storage of equipment. Additional site activities include excavation and material extraction operations, areas of cut associated with mining activities, and areas of fill intended to elevate portions of the site out of the floodplain for operational use. The fill will be from onsite stripping of the overburden material to begin the gravel extraction process.

There will be an 80' wide x 100 long' maintenance building, a 20' wide x 40' long office building, a truck scale, internal access drives, and supporting gravel separation plant. A 20' tall berm will be placed in the southern portion of the site as a buffer between the operations and the adjacent roadways. The berm area will be elevated to 20' above the existing grade at a slope of 3:1 with a 10' wide top. The berm will be constructed using overburden material generated from the onsite mining operations. The total disturbed area will be approximately 182 acres. Site grading activities will be completed to accommodate the operations throughout the site. Fill will be placed in an area that is 320' wide by 2,500' long and the buildings will be elevated to an approximate elevation of 630' NAVD88, which will be more than 2' above flood protection grade. The fill will be constructed using overburden material generated from the onsite mining operations. The mining area will maintain a minimum 120' of undisturbed land south of the banks of the West Fork White River to the southern property boundary. Mining operations will excavate material to depths of up to approximately 70' below existing grade.

Project Location: Approximately 2,400 feet west from the intersection of Cemetery Road and Perry Road expanding approximately 4,800 feet across near Martinsville

Application #: FW-33620-0

Waterbody: Crooked Creek

Applicant: David Allison, 7195 North Waverly Park Road, Martinsville, IN, 46151

Received Date: 8/7/2025

County: Morgan

Project Description: A gravel mining facility will be developed and operated in the floodway of Crooked Creek. The gravel mining facility will have support facilities like an office building and outdoor storage of equipment. Additional site activities include excavation and material extraction operations, areas of cut associated with mining activities, and areas of fill intended to elevate portions of the site out of the floodplain for operational use. The fill will be from onsite stripping of the overburden material to begin the gravel extraction process.

There will be an 80' wide x 100' long maintenance building, a 20' wide x 40' long office building, a truck scale, internal access drives, and supporting gravel separation plant. A 20' tall berm will be placed in the southern portion of the site as a buffer between the operations and the adjacent roadways. The berm area will be elevated to 20' above the existing grade at a slope of 3:1 with a 10' wide top. The berm will be constructed using overburden material generated from the onsite mining operations. The total disturbed area will be approximately 182 acres. Site grading activities will be completed to accommodate the operations throughout the site. Fill will be placed in an area that is 320' wide by 2,500' long and the buildings will be elevated to an approximate elevation of 630' NAVD88, which will be more than 2' above flood protection grade. The fill will be constructed using overburden material generated from the onsite mining operations. The mining area will maintain a minimum 120' of undisturbed land south of the banks of the West Fork White River to the southern property boundary. Mining operations will excavate material to depths of up to approximately 70' below existing grade.

Project Location: Approximately 2,400 feet west from the intersection of Cemetery Road and Perry Road expanding approximately 4,800 feet across at Martinsville

Application #: FW-33759-0

Waterbody: Bullerman Branch

Applicant: Olivia Reed, 8805 Maravilla Drive, , Fort Wayne, IN, 46815

Received Date: 5/21/2026

County: Allen

Project Description: A new residential fence was constructed. The fence is a 6' tall wood privacy fence and approximately 318' of fencing was placed around the property. There was a previous fence in place that was torn down and replaced about a foot in front of the previous line of fencing.

Project Location: 8805 Maravilla Drive at Fort Wayne

Application #: FW-33761-0

Waterbody: Hoffman Ditch

Applicant: Keith Young, P.O. Box 21, Bremen, IN, 46506

Received Date: 5/22/2026

County: Marshall

Project Description: A 30' by 32' steel storage building will be constructed in the Hoffman Ditch floodway. The building will be 14'-4.5" at its tallest point. All siding will be steel. The storage building will have a 10' high by 10'-6" wide entrance.

Project Location: 8047 1st Road near Bremen

Application #: FW-33768-0

Received Date: 5/28/2026

Waterbody: Grand Calumet River

County: Lake

Applicant: East Chicago Waterway Management District, John Fekete, 4444 Railroad Avenue, , East Chicago, IN, 46312

Project Description: Approximately 7,653 feet of sediment will be dredged to depths ranging from 0 feet to 6 feet. The dredging will be performed by hydraulic dredge. The excavated material will be pumped to an upland detention area where it will be dewatered before being transported to an offsite permitted landfill. Adequate detention time will be provided to allow suspended sediments to settle out of the dredged material. Decanted water will be discharge to the river or to the sanitary district, under applicable permits.

An 8.59-acre area will be capped in the Grand Calumet River East, a 5.53-acre area will be capped in the Grand Calumet River West. The fill material will be an organoclay-sand mixture chemical isolation layer and a sand armor layer. The 15-acre Junction Marsh will be excavated and backfilled with sand for habitat restoration. A temporary turbidity curtain will be installed for the duration of the dredging.

Project Location: Beginning at the crossing of Kennedy Avenue and The Grand Calumet River to the crossing of Indianapolis Boulevard along the channel of the Grand Calumet River at East Chicago

Application #: FW-33778-0

Received Date: 6/1/2026

Waterbody: Judy Creek

County: St. Joseph

Applicant: Bill Schalliol, 227 West Jefferson Boulevard, South Bend, IN, 46601

Project Description: Approximately 238' of 16" diameter water line, 2" fiber optic, and a 1.25" fiber optic conduit will be placed. The fiber optic conduits will be installed inside a 6" conduit and have 5' of cover beneath the streambed and 5' in the banks. The utility line will be placed by the horizontal directional drill method. Temporary open cut trenches and bore pits will be used to connect the piping. This will be conducted outside of the floodway. All disturbed/excavated area will be restored to existing grade upon completion of construction.

Project Location: Southwest corner of the intersection of Cleveland Road and Bittersweet Road near Mishawaka

Application #: FW-33780-0

Received Date: 6/3/2026

Waterbody: East Fork Whitewater River

County: Franklin

Applicant: Michael Wilz, 1001 Cliff Street, Brookville, IN, 47012

Project Description: An approximately 3,600' long by 15' wide gravel path will be constructed. The path will be constructed by excavating 8" of soil and that area will be replaced with gravel to match existing grade.

Project Location: 9084 Landfill Road near Brookville

Application #: FW-33787-0

Received Date: 5/28/2026

Waterbody: Indiana Harbor Canal

County: Lake

Applicant: East Chicago Waterway Management District, John Fekete, 4444 Railroad Avenue, , East Chicago, IN, 46312

Project Description: The Junction Reaches project includes portions of the Grand Calumet River and the Indiana Harbor Canal. Approximately 7,653 feet of sediment will be dredged to depths ranging from 0 feet to 6 feet. The dredging will be performed by hydraulic dredge. The excavated material will be pumped to an upland detention area where it will be dewatered before being transported to an offsite permitted landfill. Adequate detention time will be provided to allow suspended sediments to settle out of the dredged material. Decanted water will be discharge to the river or to the sanitary district, under applicable permits.

A 20.47-acre area will be capped in the Indiana Harbor Canal. The fill material will be an organoclay-sand mixture chemical isolation layer and a sand armor layer. A temporary turbidity curtain will be installed for the duration of the dredging.

Project Location: Beginning at the confluence of the Grand Calumet River and the Indiana Harbor Canal to the crossing of W Columbus Drive and the Indiana Harbor Canal at East Chicago

Application #: PL-25422-0

Received Date: 4/16/2026

Waterbody: Hamilton Lake

County: Steuben

Applicant: Roger Miller, 13801 Landeck Road, Delphos, OH, 45833

Project Description: An existing 70' rock seawall will be removed and replaced with a new 70' glacial stone seawall. The lakeward face of the seawall will be at the lake's legal shoreline. A 3' x 70' concrete sidewalk will be constructed landward of the new glacial stone seawall.

Project Location: 440 Lane 220 Hamilton Lake near Hamilton

Application #: PL-25453-0

Received Date: 5/23/2026

Waterbody: Simonton Lake

County: Elkhart

Applicant: Perri Ann McQuillan, 25552 North Shore Drive, , , Elkhart, IN, 46514

Project Description: A new glacial stone seawall will be constructed along the frontage of the applicant on Simonton Lake channel to deter shoreline erosion. The wall will be composed of 6inch to 34inch diameter and will be approximately 298ft long. Glacial stone will be placed on top of geotextile fabric and washed river rock.

Project Location: 25552 North Shore Drive near Elkhart

Application #: PL-25462-0

Received Date: 6/2/2026

Waterbody: Big Chapman Lake

County: Kosciusko

Applicant: Matthew Senica, 110 EMS C19 Lane, , , Warsaw, IN, 46582

Project Description: An existing concrete seawall will be refaced across a portion of the 56' frontage. The refacing will consist of concrete and will extend 12" from the lakeward face of the existing wall. A 36" wide concrete walkway will be constructed on the top and landward of the lakeward face of the refaced wall.

Project Location: 110 EMS C19 Lane at Warsaw

Application #: PL-25463-0

Received Date: 6/5/2026

Waterbody: South Twin Lake

County: Lagrange

Applicant: Neil & Nancy Stanton, 12363 Brighton Ln, Plainfield, IL, 60585

Project Description: An existing 50' limestone block seawall will be broken down into smaller pieces to create a new seawall. Geo-textile fabric will be added behind the seawall. The lakeward face of the seawall will be located at the lake's legal shoreline.

Project Location: 5867 North 210 West at Howe

Application #: PL-25468-0

Received Date: 6/11/2026

Waterbody: Cedar Lake

County: Lake

Applicant: Jovan Lozevski, 9516 Hook Street, , , Highland, IN, 46322

Project Description: A new 41' glacial stone seawall will be constructed. The lakeward face of the seawall will be at the lake's legal shoreline.

Project Location: 8335 Lake Shore Drive at Cedar Lake

Application #: PL-25475-0

Received Date: 6/29/2026

Waterbody: Hamilton Lake

County: Steuben

Applicant: Phil Carper, 680 Lane 150H, Hamilton, IN, 46742

Project Description: An existing 83' glacial stone seawall will be removed and replaced with a new 83' concrete seawall. The lakeward face of the seawall will be at the lake's legal shoreline.

Project Location: 680 Lane 150 H Hamilton Lake at Hamilton