



**State of Indiana  
Department of Natural Resources**



**DNR 30-DAY PUBLIC NOTICE**

The Department of Natural Resources serves the DNR 30-Day Public Notice in order to satisfy the requirements of the "Procedures Concerning Certain Licenses Act", IC 14-11-4, and its associated administrative rule, 312 IAC 2-3.

The DNR 30-Day Public Notice is published weekly to serve notice of the latest permit applications received at the DNR, Division of Water. This Notice can be viewed on the web at <http://www.in.gov/dnr/water/> and can be provided by email upon written request. To receive the DNR 30-Day Public Notice as a weekly email attachment, email your full name and a valid email address to [DNRPublicNoticeRecipient@dnr.IN.gov](mailto:DNRPublicNoticeRecipient@dnr.IN.gov).

The permit applications and supporting documentation is available for public viewing on-line at <https://dowunity.dnr.in.gov/#>. For questions concerning a permit application, contact the Division of Water, Technical Services Section, at (317) 232-4160 or toll free at 1-877-928-3755 and select 1 during the recorded menu narrative.

---

**Petition for Public Hearing**

A pre-action public hearing on an application may be requested by filing a written petition. For a petition to be considered valid it must:

1. contain the typed or legibly printed name and complete mailing address of each petitioner;
2. be signed by a minimum of 25 individuals who are at least 18 years old and either reside in the county where the project will take place or own real property within 1 mile of the project site;
3. affirm that each signatory to the petition satisfies the requirements of item 2; and
4. identify the application for which the public hearing is being requested either by the application # or the applicant's name and the project description.

A petition which does not meet these requirements will be considered invalid and the hearing request will not be granted. To request a pre-action public hearing, send the petition by email to [water\\_inquiry@dnr.in.gov](mailto:water_inquiry@dnr.in.gov) or by mail to:

IDNR, Division of Water  
Technical Services Section  
402 West Washington Street, Room W264  
Indianapolis, Indiana 46204-2641

**Notification of Department Action**

A person may request that the Department notify them when a Department Action is issued. To be notified of a Department Action, send a request that includes the permit application number or the applicant name, project description and county to email address [water\\_inquiry@dnr.in.gov](mailto:water_inquiry@dnr.in.gov) or by mail to the address above.

Permit Application Numbers with a prefix of:

FW are being reviewed under the Flood Control Act, IC 14-28-1 and the Flood Plain Management Rule, 312 IAC 10

PL are being reviewed under the Lake Preservation Act, IC 14-26-2 and the Public Freshwater Lake Rule, 312 IAC 11

DR are being reviewed under the Lowering of the Ten Acre Lake Act, IC 14-26-5

NW are being reviewed under the Navigable Waterways Act, IC 14-29-1

LM are being reviewed under the Navigable Waterways Act, IC 14-29-1 related to Lake Michigan

SG are being reviewed under the Sand and Gravel Permits Act, IC 14-29-3

AC are being reviewed under the Construction of Channels Act, IC14-29-4



**State of Indiana  
Department of Natural Resources**



**DNR 30-DAY PUBLIC NOTICE**

Date: 10/23/2024

**Application #: FW-32902-0**

Received Date: 8/22/2024

Waterbody: West Fork White River

County: Delaware

Applicant: CSX Transportation Inc, Dan Dyer, PO Box 72, Ossineke, MI, 49766

Project Description: Repairs have been made to one of the piers of the rail bridge over White River near Muncie. Riprap was placed in the river to construct a causeway for pier access. The work will consist of repairing the spalled area and bearing. It is anticipated that the work will be completed and the area will be restored by November.

Project Location: Approximately 580' southwest of the intersection of East Jackson Street and Bunch Boulevard near Muncie

**Application #: FW-32906-0**

Received Date: 8/23/2024

Waterbody: Baker Ditch

County: Hamilton

Applicant: Hamilton County Building Corporation, Lee Buckingham, 1 Hamilton County Square, Suite 157, , , Noblesville, IN, 46060

Project Description: An existing culvert will be removed and replaced with a new culvert approximately 100' downstream (east) of the existing culvert location. The existing culvert is a 25' long, 60" diameter steel culvert, and the new culvert will be a 36' long, 84" diameter corrugated metal pipe with concrete wingwalls. In addition, the stream banks will be regarded and stabilized with live stakes and vegetated coir logs.

Project Location: Approximately 300' west of the intersection of US 31 North and East 241st Street near Arcadia

**Application #: FW-32920-0**

Received Date: 8/29/2024

Waterbody: Eagle Creek

County: Boone

Applicant: Zionsville Parks and Recreation Department, Jarod Logsdon, 1075 Parkway Drive, , , Zionsville, IN, 46077

Project Description: The Town of Zionsville proposes to rehabilitate the pedestrian bridge structure that carries Turkey Foot Trail over Eagle Creek. The project includes replacing the existing timber approaches with precast concrete panel boardwalk approaches. The two truss main spans will remain in-place. The work will consist of replacing the existing timber boardwalk approach sections with precast concrete boardwalk sections. The approach boardwalk will consist of approximately 5.5" thick precast concrete panels, approximately 11' by 1'-2" concrete beams, with a 10' clear trail width and 11'-3" out-to-out width. The grades of the approach sections will be set to not exceed a 5% longitudinal slope, maintaining or lowering the existing ground tie-in points. Since the proposed guardrail and railing at the approaches are not hydraulically obstructive, the approach section structure depth will decrease, and the natural flowline will be maintained, there will be no change to the flow regime due to this work. The proposed approach section structure depth will decrease from 1'-11" to 1'-7 1/2". The profile grade of the proposed approach boardwalk sections will be altered to a 5% longitudinal grade, and the tie-in points with the existing ground elevation will remain the same or be lowered. Project Location: Located approximately 0.1 mile north of Oak Ridge Drive and Turkey Foot Road at Zionsville

**Application #: FW-32929-0**

Waterbody: Williams Creek

Applicant: Delaware County Highway Department, Angela Moyer, 7700 East Jackson Street, , Muncie, IN, 47302

Received Date: 9/5/2024

County: Delaware

Project Description: Des. No. 2003023 project is to replace the existing structure and add riprap for scour protection. The new structure will be an 85', 1 -span continuous prestressed concrete hybrid bulb-tee beam bridge. Class I riprap will be placed around spill slopes and wildlife crossings and revetment riprap will be placed on drainage turnouts and wing side slopes for scour protection. Tree clearing will be necessary as a part of this project to reach the underside of the bridge. Tree clearing is expected at 0.24 acre below the Base Flood Elevation. Permanent impacts to Williams Creek will occur from fill below the BFE. Total permanent impacts below the BFE equal 0.084 acre and 250 cubic yards. Impacts within the floodway are the result of installing Class I and revetment riprap for scour protection on spill slopes and drainage turnouts.

Project Location: Located 0.75 miles east from the intersection of South Honey Creek Road and W 600 South Road continuing east approximately 970'. at Muncie

**Application #: FW-32932-0**

Waterbody: Little Vermillion River

Applicant: Indiana Department of Transportation, Joshua Long, 100 North Senate Avenue IGCN 758 ES, Indianapolis, IN, 46204

Received Date: 9/6/2024

County: Vermillion

Project Description: INDOT Des.#2100966 and 2100967 are associated with the rehabilitation of the existing bridges on State Road 63 over Little Vermillion River. The rehabilitation for both structures will include replacing the existing bridge deck, approach slabs, and bridge railings. Existing steel beams will be cleaned, coated, and made composite with the concrete deck. End bents will be converted to semi-integral, and minor patching will be performed on the substructure units. New concrete bridge rail transitions will be placed on the new concrete approach slabs, with approach guardrail and guardrail end treatments at the incoming and outgoing ends. Terminal joints with full depth HMA pavement will be installed at each end of the approach slabs. The existing approach roadway will be milled and resurfaced to transition back into the existing grade. The proposed profile of the roadway will match the existing. Revetment riprap drainage turnouts will be placed on the northeast corner of the NB Bridge and northwest corner of the SB Bridge. Debris in the channel at the upstream end of Pier 3 on the SB Bridge will be cleared. Overall permanent impacts below the BFE are 83', 0.03 acres and 90 CYS due to debris removal and drainage turnout installation. The temporary impacts below the BFE elevation will primarily involve construction access. Total temporary impacts below the BFE are 125', 0.067 acres, and 108 CYS. No temporary or permanent impacts to wetlands and no tree clearing will occur for this project. Disturbed areas below the BFE will be restored with seed mixture floodplain and above BFE will be restored with INDOT standard mulch seeding.

Project Location: Located approximately 440' from the intersection of State Road 63 and East County Road 50 North continuing along State Road 63 for 0.38 miles at Newport

**Application #: PL-25089-0**

Waterbody: Wawasee Lake

Applicant: John Fisher, 11712 North Sunrise Drive, , Syracuse, IN, 46567

Received Date: 9/24/2024

County: Kosciusko

Project Description: An existing concrete seawall will be refaced across 100' of shoreline on Lake Wawasee. The reface will have 50' located on the main waterbody and 50' located on the channel side. The reface will consist of reinforced concrete which will be tied to the existing wall with 1/2" rebar. The refacing will have a maximum thickness of 12" and will be sloped on the lakeward side. A 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall.

Project Location: 11712 North Sunrise Drive near Syracuse

**Application #: PL-25090-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Fred Bowman, 11562 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will be refaced across a portion of the 100' of shoreline on Lake Wawasee. The reface will consist of reinforced concrete. A 36' wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall.

Project Location: 11562 North Sunrise Drive near Syracuse

**Application #: PL-25091-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Malinda Gentry, 11720 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11720 North Sunrise Drive near Syracuse

**Application #: PL-25092-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Brain Rhoades, 11738 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11728 North Sunrise Drive near Syracuse

**Application #: PL-25093-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: David Dickey, 11552 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11552 North Sunrise Drive at Syracuse

**Application #: PL-25094-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Brian Ploss, 11690 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11690 North Sunrise Drive near Syracuse

**Application #: PL-25095-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Dan Michael, 11654 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11654 North Sunrise Drive at Syracuse

**Application #: PL-25096-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Bian Vander Luitgaren, 11666 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11666 North Sunrise Drive near Syracuse

**Application #: PL-25097-0**

Received Date: 9/24/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Dan Rice, 11702 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11702 North Sunrise Drive near Syracuse

**Application #: PL-25098-0**

Received Date: 9/25/2024

Waterbody: Wawasee Lake

County: Kosciusko

Applicant: Michael Reed, 11732 North Sunrise Drive, , , Syracuse, IN, 46567

Project Description: An existing concrete seawall will refaced across 100' of shoreline on Lake Wawasee. The seawall will be refaced with concrete and a 36" wide concrete walkway will be constructed on top and landward of the lakeward face of the refaced wall. The seawall will be refaced for 50' on the main waterbody and 50' on the channel side of the property.

Project Location: 11732 North Sunrise Drive near Syracuse