

DATE: November 8th, 2018

CLARIFICATION NO. 1
TO
CONSTRUCTION DOCUMENTS
FOR PROJECT NO. E008185

DESCRIPTION: **AML SITE 345, LINTON NO. 1**

LOCATION: **GREENE COUNTY, INDIANA**

FOR AGENCY: **DEPARTMENT OF NATURAL RESOURCES**

The information contained in this Clarification is intended to correct any composition errors and serve to eliminate any misunderstanding of the basic plans and specifications the same as if being originally incorporated therein.

ITEM NO. 2:

Water for mixing substrate and dust control will be available from one of the three pits adjacent to the project limits.

ITEM NO. 2:

The honey bee hives cannot be moved. The Contractor shall be aware of their location and exercise care regarding lime dust. Keeping agricultural lime wet shall be the primary preventative measure with other measures as needed.

ITEM NO. 3:

All trees from the clearing operation shall be chipped. If there are enough wood chips generated from chipping cleared trees to make the required amount of organic substrate, the remaining wood chips shall be spread and incorporated with other soil amendments in the areas designated for tree planting seed mix. The cost of chipping trees and incorporating left over chips shall be included in the lump sum portion of the base bid. The supplemental unit price item "Wood Chips" shall only be used for commercial woods chips brought from an off-site location.

END OF CLARIFICATION