Date: December 4, 2015

ADDENDUM NO. 1

TO

PLANS AND SPECIFICATIONS

FOR

PROJECT NO. E030118

DESCRIPTION OF PROJECT: Watermain Replacement Improvements

LOCATION: Lincoln State Park Lincoln City, IN

ISSUE DATE: December 4, 2015

INDIANA STATE AGENCY: DEPARTMENT OF NATURAL RESOURCES

The information contained in this Addendum shall become a part of the basic Specifications, the same as if originally incorporated therein. The original Specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the Specifications.

The following items reflect clarifications to the Plans-Specifications for the bid of this project.

ITEM NO. 1: Plans/Specifications: Plan Sheet S-1

Add: All Disturb areas shall be mulched seeded after settling of trench has been completed. Following are the requirements:

1) Top Soil- Shall be free of foreign matter such as refuse, stumps, roots rocks or weeds.

2) Grass Seed- Shall be purchased from sources of supply that have been tested, sampled and reported by the State Seed Commission, Purdue University, West Lafayette, IN and found to be satisfactory. Seed

Mixture shall be Kentucky Bluegrass-40% by weight, Redtop-10% by weight and Perennial Rye-50% by Weight.

3) Mulch for Seeding- May consist of straw, chaff, clover timothy, alfalfa, peppermint or soybean hay, shredded fodder, excelsior mulch, wood cellulose fiber mulch, or clover chaff.

The sign in sheet from the December 2, 2015 Pre-Bid Meeting is attached.

END OF ADDENDUM

DEPARTMENT OF NATURAL RESOURCES
LINCOLN STATE PARK
WATERMAIN REPLACEMENT IMPROVEMENTS

PRE-BID MEETING
PARK OFFICE
15476 N. CR 300E LINCOLN CITY, IN
December 2, 2015, 11:00 AM EST

SIGN-IN SHEET

NAME	SIGNATURE	COMPANY	PHONE NUMBER	EMAIL ADDRESS
Michael Mathias		IDNR Engr.	3172524155	mmathias@dnr.in.gov
Ron Deig	Ron Deig	DEIG BROS. CONST.	812-423-4201	ron@deigbros.com
Jordan Dant		United Excavating; G.C.	812-486-8306	jordan.dant@unitedexcavating.com
Trent Grass		" " "	812-486-9430	trent.grass@unitedexcavating.com
Joel Clark		Clark Exc.	812-825-5981	clarkexcuu@gmail.com
Tanner Clark		"	"	"
STEVE TITZER		BUSINKEBERGER BROS	812-845-2717	STEVE.T@BBIDIGS.COM
Darren McClellan		Jerry Agner Const	812-305-3886	darrenmc@agnerconstruction.com
BEN SMITH		IDNR ENGINEERING	317-605-1983	bsmith1@dnr.in.gov
BRAD YOUNG	Brad L. Young	IDNR LINCOLN S.P.	812-937-4710	byoung@dnr.in.gov
MIKE SCHNUCK		IDNR LINCOLN SP	812-937-4710	MICHAELSCHNUCK@YAHOO.com