

Date: September 15, 2014

**ADDENDUM NO. 1**  
**TO**  
**PLANS AND SPECIFICATIONS**  
**FOR**  
**PROJECT NO. E030225**  
**Requisition No. 68123**

**DESCRIPTION OF PROJECT:** REHABILITATION AND PAINTING OF ELEVATED STEEL WATER STORAGE TANK

**LOCATION:** BROOKVILLE LAKE, MOUNDS SRA – FRANKLIN COUNTY, IN

**ISSUE DATE:** SEPTEMBER 15, 2014

**INDIANA STATE AGENCY:** DEPARTMENT OF NATURAL RESOURCES

**The information contained in this Addendum shall become a part of the basic Specifications, the same as if originally incorporated therein. The original Specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the Specifications.**

The following items reflect clarifications to the Specifications for the bid of this project.

**ITEM NO. 1:** Specification Section 01010 – Summary of Work

**DELETE** Paragraph 1.01.A.5 in its entirety and **REPLACE** with the following:

*“5. Installation of an adequately sized air break in the overflow pipe. The air break shall be equipped with a new properly aligned protective screening and a new counter weighted flap gate to prevent the ingress of unwanted species into the overflow pipe. The overflow pipe shall be directed away from the tank foundation using a reinforced concrete splash block.”*

Immediately after Paragraph 1.11 **INSERT** the following:

*"C. Campsites adjacent to the elevated water storage tank will be blocked from use by park staff during the duration of the work.*

*D. Vegetation including bushes and trees adjacent to the elevated water storage tank that may impact the work will be removed by park staff prior to the start of the work."*

**ITEM NO. 2:** Specification Section 09900 – Painting of Elevated Potable Water Storage Tank

**DELETE** Paragraph 4.11.A in its entirety and **REPLACE** with the following:

*"A. The Contractor shall remove and dispose of existing insulation on the riser pipe prior to painting. The Contractor shall paint and cure the paint on the riser pipe as required. No insulation will be reinstalled on the riser pipe."*

The sign in sheet from the September 11, 2014 Pre-Bid Meeting is attached.

**END OF ADDENDUM**

Brookville Lake Tank Painting/Repair

Pre-Bid Conference 9/16/14 10:30 am

Attendance Sheet

<u>Name</u>	<u>Representing</u>	<u>Phone No</u>	<u>Email</u>
Michael Mathias	IDNR Engr	317-232-4155	mmathias@dnr.in.gov
JOHN R BICKER	INDURON CONTRACTS	502-445-5243	JBicker@INDURON.COM
Todd Ransdell	Caldwell Tanks Inc	859-734-7749	transdell@caldwelltanks.com
Gene Rothgamb	Phoenix	703-317-271-7002	
Bill Porter	IDNR Engineering	317-232-4155	bporter@dnr.in.gov
Jeremy Weber	IDNR - Brookville/Whitewater	765-647-2657	jweber@dnr.in.gov
Tom Carr	IDNR - Brookville	765-647-2657	TCARR@dnr.in.gov

