

Date: 01/09/2023

**Addendum No. 2
For Project No. 300DM-72012-06**

Description: Hardy Lake Dam Valves Replacement

Location: Hardy Lake Reservoir, Scott County

FOR AGENCY: Department of Natural Resources

The information contained in this Addendum shall become a part of the basic plans and specifications the same as if original incorporated therein. The original plans and specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the specifications and on the plans.

ITEM No. 1: Contractor Question: Is there alternate gate mounting designs allowed? A: Yes, alternate gate mounting designs are allowed provided the performance meets the specifications.

ITEM No. 2: Contractor Question: Can the existing thimble be used for the 36" gate? A: Yes. The existing thimbles can be used for the replacement of any of the gates provided the performance meets the specifications.

ITEM No. 3: Clarification from Addendum #1: The 3rd to last question referenced an incorrect elevation. The 1968 design drawings referenced the centerline of the 36" gate openings at 567.0' and 570.0'. The centerline of the interior gate is 567.0' instead of the 570.0'. There should be 2-1/8" between the floor and the bottom of the thimble based on these elevations.

ITEM No. 4: Contractor shall not be allowed extra compensation by any matter or thing concerning which the Contractor could have fully informed their self prior to bidding. In this case, the best available information are the 1968 plans, videos, and reports from the underwater inspections. Alternate gate mounting designs and the use of the existing thimble should be based on the available information.

END OF ADDENDUM

State Form 21208R4

DAPW-118