

72 Henry Street, PO Box 47 North Vernon, IN 47265 P:(812) 346-2045 F:(812) 346-8045 Toll Free:1-866-ENG-FPBH

April 1, 2021

ADDENDUM NUMBER ONE TO SPRING MILL STATE PARK WALKWAY to DONALDSON CAVE

TO: ALL BIDDERS

PROJECT NO: ENG1903740475

Notice is hereby given that the following modifications shall be considered by the Contractor in his bid for the above referenced project:

ITEM NO. 1: Attached

The minutes from the March 31, 2021 pre bid are attached, and all information from the minutes is included as part of this addenda.


Sheet 14 of the drawing set is revised and attached.

Key points to the scope of work are:

- A. Continuous handrails are required
- B. Decking shall be perpendicular to the pathway
- C. All welded connections shall be field painted.

Contractor shall acknowledge receipt of this addendum by marking receipt thereof in the Bid Form.

File: 19-11352 Page 1 of 1 April 1, 2021





72 Henry Street, PO Box 47 North Vernon, IN 47265 P:(812) 346-2045 F:(812) 346-8045 Toll Free:1-866-ENG-FPBH

Offices in North Vernon, Seymour, and New Castle

DNR Spring Mill State Park Walkway to Donaldson Cave ENG1903740475

March 31, 2021 at 10:30am

Pre Bid Meeting On-Site

Attendance

List Attached

Office Discussion

- This is a unique project, and will be a signature item for the Park when complete
- Matthew Pore with DNR central office is the contact for administration. Questions can be sent to the engineer and they will be forwarded to Matthew.
- It is unknown how quickly it would be awarded or a Notice to Proceed issued, but if it was two months past the opening of April 15 to a start in June, then work would be finished in about December of this year
- The biggest challenge to the project is the access to bring in materials
- As shown on the plans, small equipment or UTV is the most practical
- Vehicles and equipment will need to turn around at the beginning of the project site
- A trailer can be pulled behind a UTV
- A mini excavator can probably access most locations
- The project has been designed so that most components can be fabricated off site in 10 foot sections and then brought in and assembled
- Setting of the base plates or coring for the legs will be a custom operation for each install. Base plates may need to be angled to the rock surface
- In addition to the staging area shown on the plans, the contractor can use parking North of the bridge, and at the nature center
- No clearing is anticipated to build the walkway unless a tree has fallen across the path before construction starts
- There is no provision for fencing off the area. DNR will add signage when work starts, but there will always be people on the trails, on the stairs and in the vicinity of the work
- The appearance will not be a bare metal or galvanized look. Owner selected colors for the aluminum paint and the composite decking will most likely be brown or green earth colors. All surfaces will be coated other than stainless steel hardware.
- There are sensitive areas such as the Eigenmann fish traps, old mill stones, the Wilson Monument, et al that contractor shall not disturb
- Engineer will provide CAD files so that horizontal and vertical leg locations can be staked

•



72 Henry Street, PO Box 47 North Vernon, IN 47265 P:(812) 346-2045 F:(812) 346-8045 Toll Free:1-866-ENG-FPBH

Offices in North Vernon, Seymour, and New Castle

On Site Tour & Discussion

- The bridge about halfway back to the site is rated at 2-1/2 ton limit. The department will allow equipment to cross the creek downstream of the bridge
- The wood erosion fencing will be removed by owner before construction begins
- After all leg locations are staked, engineer can meet to verify whether base plate or coring will be required. No other special testing will be needed other than contractor probing or clearing of debris for footing verification
- There is water almost always exiting out of the cave mouth at the location of the terminus landing of the walkway
- When the water is high during spring rains it can take 2 to 3 days to go back to normal pool
- Contractor will need to keep all areas clear of trash and tools or lighter items every evening in case of a rain event
- There is no cell phone service at the site. 2 way radios are the best communication medium
- Generators for tools are allowed on site





TITLE	
JOB _	19-11352
BY	
DATE	March 31, 2021

h	Spring Mill St Olkway to Done March 31, 202	Hote Park aldson Cove
Nome	Representing	Emoil
Brad Besder EDIC OSBORNE Andrew Graves	FP3H Inc. SPAMI Mill Graves Construction	Los borne 2 a DNR, IN. Gov Andrew 2 gravesinc. net
HARRISON RANDALL	HARMON CONSTRUCTION	Harrison. Randall@hermon Construction
MARK YOUNG	Spaing Mill	Myound adop, in gov

SHEET____OF___