

Schedule A				Contractor Name		Emergency Visits Included:	
Peoplesoft Dept ID		Address		City / State / zip			
Property Name		City / State / zip		Phone / Fax / Email			
Address		City / State / zip		Phone / Fax / Email			
Property Phone Number		Fax 219-369-9496		Contact names			
Property Manager		rackerson@dnr.in.gov					
Contractor Note: Please improve the accuracy of this equipment list as you progress through the year.							
Annual inspections of pumps, motors and controls. Siemens MAG 6000 flowmeter must be calibrated annually and written verification provided to comply with IDEM requirements.							
Five stage Pump performance drawdown check must be performed, verified and reported annually for pumps. All pumps have pump test flanges. A written report to include performance curves, amps/volts, specific capacity, drawdown, and recommendations is to be provided. Information is used to determine fees charged to contract users of our system.							
Qty	Location Area	Location Inside	Description	Manufacturer	Identification	Serial #	Installed
	Well A	Remote Well	10" 1000 gpm vertical hollow				
1			Inverter Duty Motor	40Hp US Motor	460volts, 3 phase		2024
1			Pump	American Turbine			
1			Packing Seal				
1			Check valves	NIBCO	6" check Model 1406BN		
1			Air Release	CLA-VAL	1 inch Model 101WS		
	Well C	Remote Well	12" 1000 gpm vertical hollow				2017
1			Inverter Duty Motor	40Hp GE (Top	460volts, 3 phase ID 5KE324DTT6005	50027177	
1			Pump	American Turbine			
1			Packing Seal				
1			Check valves	ValMatic	6" check Model 1406BN		
1			Air Release	CLA-VAL	1 inch Model 10M/S		
	Well D	Remote Well	12" 1000 gpm vertical hollow				2023
1			Inverter Duty Motor	40Hp US Motor	460volts, 3 phase	ID K01 20038591-100R-01	
1			Pump	American Turbine			
1			Seal ?				
1			Check valves	ValMatic	6" check		
1			Air Release	CLA-VAL	1 inch		
	AWP 1	Detention Building	8 " 700 GPM Vertical Hollow				2017
1			Inverter Duty Motor	25 Hp US Electric	H02BV2BLF-C 460volts, 3 phase	J12-20039006-6T-01	
1			Pump	American Turbine	Model 12-M-80 single stage		
1			Mechanical Seal	Chesterton S10 Single			
1			Check valves	NIBCO	8" check W9910B		
1			Air Release	CLA-VAL	1 371-WS.3/1AC		
	AWP 2	Detention Building	8 " 700 GPM Vertical Hollow				2017
1			Inverter Duty Motor	25 Hp US Electric	H02BV2BLF-C 460volts, 3 phase	J12-20039006-6T-02	
1			Pump	American Turbine	Model 12-M-80 single stage		
1			Mechanical Seal	Chesterton S10 Single			
1			Check valves	US Valve	8" check Model 31-2-4	1011027023	
1			Air Release	CLA-VAL	1 371-WS.3/1AC		
	Filler Flowmeter	Iron Filler	Signal converter	Siemens	Model SITRANS FM MAGFLO MAG 6000	7ME6920-2CA10-1AA0	
1			Sensor (flowtube), 8 inch	Siemens	Model SITRANS FM MAG 5100 W	7ME658 3B2101U461	