

CALL ORDER : 420
 LETTING DATE :

CONTRACT ID : B -28082-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE, PRECAST 3 SIDED CULVERT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	145.000	m2
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	3,983.000	m3
11	205-03371 SEDIMENT REMOVE	102.000	m3
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	44.000	Mg
13	205-06936 TEMPORARY SEDIMENT TRAP	27.000	Mg
14	205-06937 TEMPORARY SILT FENCE	45.000	m
15	207-08263 SUBGRADE TREATMENT, TYPE IA	600.000	m2
16	211-07454 STRUCTURE BACKFILL	216.000	m3
17	213-08058 FLOWABLE BACKFILL	215.000	m3
18	303-01180 COMPACTED AGGREGATE, NO. 53	1,191.000	Mg
19	303-07449 COMPACTED AGGREGATE, NO. 73	33.000	Mg
20	306-08042 MILLING, SCARIFICATION/PROFILE	2,328.000	m2
21	306-08043 MILLING, TRANSITION	247.000	m2
22	402-07433 HMA SURFACE, TYPE B	381.000	Mg
23	402-07438 HMA INTERMEDIATE, TYPE B	248.000	Mg
24	402-07441 HMA BASE, TYPE B	147.000	Mg
25	406-05520 ASPHALT FOR TACK COAT	1.500	Mg
26	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
27	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
28	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
29	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	78.105	m
30	610-07486 HMA FOR APPROACHES, TYPE A	59.000	Mg
31	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
32	615-06490 RIGHT OF WAY MARKER	21.000	EACH
33	615-06505 MONUMENT, B	2.000	EACH
34	615-92498 BENCH MARK	1.000	EACH
35	616-02320 GEOTEXTILES	962.000	m2
36	616-05688 RIPRAP, CLASS 1	150.000	Mg
37	616-06405 RIPRAP, REVETMENT	375.000	Mg
38	616-06451 RIPRAP, UNIFORM	320.000	Mg
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
40	621-06545 FERTILIZER	0.680	Mg
41	621-06553 SEED MIXTURE, R	144.000	kg
42	621-06565 MULCHING MATERIAL	3.400	Mg
43	621-06567 WATER	3.200	kL
44	621-06574 SODDING	174.000	m2
45	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
46	622-91786 SEEDLING	80.000	EACH
47	714-03437 WINGWALL, PRECAST, REINFORCED CONCRETE	33.000	m2
48	714-99348 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1500 mm x 900 mm	21.500	m

CALL ORDER : 420
 LETTING DATE :

CONTRACT ID : B -28082-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE, PRECAST 3 SIDED CULVERT		
49	715-02630 SAFETY METAL END SECTION, 6:1, 600 mm	3.000	EACH
50	715-05173 PIPE, TYPE 3, CIRCULAR, 600 mm	10.000	m
51	715-08486 GRATED BOX END SECTION, II, 6:1, 1240 mm X 840 mm	4.000	EACH
52	715-46020 PIPE END SECTION, 600 mm	1.000	EACH
53	723-07068 STRUCTURE, PRECAST THREE-SIDED, 6100 mm X 2130 mm	17.400	m
54	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
55	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
57	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
58	801-07118 BARRICADE, III-A	28.800	m
59	801-07119 BARRICADE, III-B	28.800	m
60	808-06712 LINE, PAINT, BROKEN, YELLOW, 100 mm	340.000	m
61	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	680.000	m
62	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	13.000	EACH
63	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	15.000	EACH

CALL ORDER : 430
 LETTING DATE :

CONTRACT ID : B -28405-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
8	203-02000 EXCAVATION, COMMON	2,383.000	m3
9	203-02070 BORROW	8,110.000	m3
10	203-51223 EXCAVATION, WATERWAY	1,604.000	m3
11	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	84.000	Mg
12	205-06936 TEMPORARY SEDIMENT TRAP	31.200	Mg
13	205-06937 TEMPORARY SILT FENCE	572.000	m
14	205-06938 TEMPORARY SLOPE DRAIN	20.000	m
15	206-51220 EXCAVATION, WET	114.200	m3
16	207-08266 SUBGRADE TREATMENT, TYPE III	2,389.500	m2
17	211-06467 AGGREGATE FOR END BENT BACKFILL	15.100	m3
18	211-07454 STRUCTURE BACKFILL	31.700	m3
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,225.900	Mg
20	302-07455 DENSE GRADED SUBBASE	32.100	m3
21	303-60012 AGGREGATE, 2	2,815.000	Mg
22	303-97820 AGGREGATE, 8	364.000	Mg
23	402-07432 HMA SURFACE, TYPE A	326.700	Mg
24	402-07435 HMA INTERMEDIATE, TYPE A	552.300	Mg
25	404-05514 SEAL COAT, 5	485.000	m2
26	406-05520 ASPHALT FOR TACK COAT	1.100	Mg
27	601-01704 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, MODIFIED	1.000	EACH
28	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 1.905 m SPACING	64.770	m
29	601-06037 GUARDRAIL END TREATMENT, I	3.000	EACH
30	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
31	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	120.015	m
32	603-06040 FENCE, FARM FIELD, 1190 mm	101.000	m
33	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 250 mm	106.900	m2
34	610-07486 HMA FOR APPROACHES, TYPE A	123.900	Mg
35	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
36	616-02320 GEOTEXTILES	5,473.700	m2
37	616-06405 RIPRAP, REVETMENT	2,645.300	Mg
38	616-06425 RIPRAP, GROUTED, 300 mm	79.400	m2
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
40	621-01371 SEED MIXTURE, LEGUME, 2	29.600	kg
41	621-02770 EROSION CONTROL BLANKET	6,240.000	m2
42	621-06545 FERTILIZER	0.900	Mg
43	621-06553 SEED MIXTURE, R	142.000	kg
44	621-06557 SEED MIXTURE, T	11.100	kg
45	621-06565 MULCHING MATERIAL	4.900	Mg
46	621-06567 WATER	22.900	kL
47	621-06575 SODDING, NURSERY	1,271.700	m2
48	622-52436 SIGN, DO NOT MOW OR SPRAY	8.000	EACH

CALL ORDER : 430
 LETTING DATE :

CONTRACT ID : B -28405-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	622-91786 SEEDLING	90.000	EACH
50	701-51195 PILE, STEEL H, HP 310 X 79	140.800	m
51	701-91792 PILE TIP, STEEL H	24.000	EACH
52	702-51005 CONCRETE, A, SUBSTRUCTURE	55.700	m3
53	702-51015 CONCRETE, B, FOOTINGS	18.200	m3
54	703-51030 REINFORCING STEEL	4,341.000	kg
55	703-51032 REINFORCING STEEL, EPOXY COATED	16,328.000	kg
56	704-51002 CONCRETE, C, SUPERSTRUCTURE	114.300	m3
57	706-06344 RAILING, TS-1	68.580	m
58	707-05983 STRUCTURAL MEMBERS, CONCRETE I-BEAM, II, 914 mm X 305 mm	145.600	m
59	709-51821 SURFACE SEAL	LUMP	LUMP
60	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	15.000	m
61	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	15.500	m
62	715-05122 PIPE, TYPE 1, CIRCULAR, 525 mm	17.500	m
63	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	8.500	m
64	715-05407 PIPE, END BENT DRAIN, 150 mm	31.000	m
65	715-46005 PIPE END SECTION, 375 mm	4.000	EACH
66	715-46010 PIPE END SECTION, 450 mm	2.000	EACH
67	715-46015 PIPE END SECTION, 525 mm	2.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118 BARRICADE, III-A	32.400	m
73	801-07119 BARRICADE, III-B	21.600	m
74	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	5.406	m2
75	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	2.880	m2
76	802-76055 SIGN POST, A	54.505	m
77	802-76065 SIGN POST, B	18.443	m

CALL ORDER : 440
 LETTING DATE :

CONTRACT ID : B -28447-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE WIDENING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02240 PAVEMENT REMOVAL	325.000	SYS
8	202-02241 GUARDRAIL, REMOVE	790.000	LFT
9	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
10	202-51822 BRIDGE DECK OVERLAY, REMOVE	489.000	SYS
11	203-02000 EXCAVATION, COMMON	294.000	CYS
12	203-02070 BORROW	914.000	CYS
13	206-51220 EXCAVATION, WET	160.000	CYS
14	206-51225 EXCAVATION, DRY	96.000	CYS
15	211-06467 AGGREGATE FOR END BENT BACKFILL	7.400	CYS
16	211-07454 STRUCTURE BACKFILL	180.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,904.000	TON
18	302-07455 DENSE GRADED SUBBASE	76.000	CYS
19	306-08043 MILLING, TRANSITION	664.000	SYS
20	402-07433 HMA SURFACE, TYPE B	59.000	TON
21	402-07438 HMA INTERMEDIATE, TYPE B	50.000	TON
22	402-07441 HMA BASE, TYPE B	219.000	TON
23	406-05521 ASPHALT FOR TACK COAT	2,374.000	SYS
24	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
25	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
26	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
27	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	463.000	LFT
28	604-07902 CURB RAMP, CONCRETE, H	11.000	SYS
29	604-91531 SIDEWALK, CONCRETE, 4 IN.	134.000	SYS
30	605-06120 CURB, CONCRETE	256.000	LFT
31	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	462.000	SYS
32	610-07487 HMA FOR APPROACHES, TYPE B	302.000	TON
33	616-02320 GEOTEXTILES	24.000	SYS
34	616-06405 RIPRAP, REVETMENT	90.000	TON
35	621-06559 MULCHED SEEDING, R	1,350.000	SYS
36	701-03753 PILE, CONCRETE, STEEL SHELL ENCASED, 0.209 IN., 14 IN.	590.000	LFT
37	702-51005 CONCRETE, A, SUBSTRUCTURE	71.100	CYS
38	702-51015 CONCRETE, B, FOOTINGS	69.800	CYS
39	702-51863 FIELD DRILLED HOLE IN CONCRETE	150.000	EACH
40	703-08247 EMBEDDED GALVANIC ANODE	376.000	EACH
41	703-51030 REINFORCING STEEL	9,522.000	LBS
42	703-51032 REINFORCING STEEL, EPOXY COATED	58,878.000	LBS
43	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	109.000	EACH
44	704-51002 CONCRETE, C, SUPERSTRUCTURE	165.600	CYS
45	706-06339 RAILING, PF-1	120.000	LFT
46	706-06342 RAILING, PS-1	120.000	LFT
47	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	2.000	EACH
48	706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1	2.000	EACH

CALL ORDER : 440
 LETTING DATE :

CONTRACT ID : B -28447-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE WIDENING		
49	706-51020 CONCRETE, C, RAILING	14.300	CYS
50	708-51813 PNEUMATICALLY PLACED MORTAR	50.000	SFT
51	709-51821 SURFACE SEAL	LUMP	LUMP
52	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	28.000	LFT
53	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	235.000	LFT
54	715-05407 PIPE, END BENT DRAIN, 6 IN.	50.000	LFT
55	715-05595 PIPE EXTENSION, CIRCULAR, 15 IN.	5.000	LFT
56	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
57	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
58	720-45015 INLET, A8	2.000	EACH
59	720-45410 MANHOLE, C4	1.000	EACH
60	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	100.000	SFT
61	722-51842 BRIDGE DECK OVERLAY	629.000	SYS
62	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	4.300	CYS
63	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	400.000	SFT
64	722-60824 SURFACE MILLING	489.000	SYS
65	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
66	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	490.000	LFT
67	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,234.000	LFT
68	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
69	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
70	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
71	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
72	801-07118 BARRICADE, III-A	24.000	LFT
73	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	660.000	LFT
74	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	250.000	LFT
75	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,339.000	LFT
76	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,090.000	LFT
77	808-06716 LINE, REMOVE	2,536.000	LFT
78	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	26.000	EACH
79	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	26.000	EACH

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : B -28682-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	3.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	203-02000 EXCAVATION, COMMON	93.000	CYS
7	203-02070 BORROW	495.000	CYS
8	210-05811 REPAIR	1.000	EACH
9	210-05811 REPAIR	1.000	EACH
10	211-06467 AGGREGATE FOR END BENT BACKFILL	14.000	CYS
11	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	118.000	TON
12	303-04853 COMPACTED AGGREGATE	13.000	TON
13	402-07432 HMA SURFACE, TYPE A	17.800	TON
14	402-07435 HMA INTERMEDIATE, TYPE A	36.000	TON
15	406-05521 ASPHALT FOR TACK COAT	331.000	SYS
16	601-03667 RAILING, ORNAMENTAL	202.170	LFT
17	604-91531 SIDEWALK, CONCRETE, 4 IN.	126.000	SYS
18	616-02320 GEOTEXTILES	351.000	SYS
19	616-06425 RIPRAP, GROUTED, 12 IN.	236.000	SYS
20	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
21	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
22	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
23	621-06559 MULCHED SEEDING, R	2,000.000	SYS
24	701-51195 PILE, STEEL H, HP 12 X 53	120.000	LFT
25	701-91792 PILE TIP, STEEL H	4.000	EACH
26	702-51005 CONCRETE, A, SUBSTRUCTURE	23.000	CYS
27	702-51863 FIELD DRILLED HOLE IN CONCRETE	8.000	EACH
28	703-51030 REINFORCING STEEL	1,430.000	LBS
29	711-51038 STRUCTURAL STEEL	LUMP	LUMP
30	711-51038 STRUCTURAL STEEL	LUMP	LUMP
31	711-91047 EXPANSION ANCHOR, 1 IN.	8.000	EACH
32	712-03812 BENCH	4.000	EACH
33	712-94080 TIMBER DECK	1,617.700	SFT
34	715-05407 PIPE, END BENT DRAIN, 6 IN.	72.000	LFT
35	724-03855 EXPANSION JOINT, SLIDING PLATE	16.000	LFT
36	726-97941 BEARING ASSEMBLY, TFE ELASTOMERIC	2.000	EACH
37	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	2.000	EACH
38	805-05695 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 3 1/C	150.000	LFT
39	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	155.000	LFT
40	807-02191 HANDHOLE, LIGHTING	1.000	EACH
41	807-02428 CONCRETE FOUNDATION WITH GROUNDING, 30 IN. X 30 IN. X 96 IN.	2.000	EACH
42	807-03051 LIGHT CABLE, 1C 10GA.	56.000	LFT
43	807-03738 LIGHT POLE ASSEMBLY, STREET	2.000	EACH
44	807-03950 LUMINAIRE, ORNAMENTAL	2.000	EACH
45	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	70.000	LFT
46	807-86805 SERVICE POINT, I	1.000	EACH
47	807-86910 CONNECTOR KIT, UNFUSED	2.000	EACH
48	807-86915 CONNECTOR KIT, FUSED	2.000	EACH

CALL ORDER : 450
 LETTING DATE :

CONTRACT ID : B -28682-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
49 807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	3.000	EACH
50 807-86930	INSULATION LINK, NONWATERPROOFED	3.000	EACH
51 807-86935	INSULATION LINK, WATERPROOFED	4.000	EACH

CALL ORDER : 460
 LETTING DATE :

CONTRACT ID : B -28702-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	7.000	MOS
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-02241 GUARDRAIL, REMOVE	440.000	LFT
8	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	2,818.000	CYS
10	203-51223 EXCAVATION, WATERWAY	2,400.000	CYS
11	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	175.000	TON
12	205-06936 TEMPORARY SEDIMENT TRAP	153.000	TON
13	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,363.000	SYS
14	211-06467 AGGREGATE FOR END BENT BACKFILL	65.000	CYS
15	211-07454 STRUCTURE BACKFILL	47.000	CYS
16	303-01180 COMPACTED AGGREGATE, NO. 53	1,658.200	TON
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	402-07432 HMA SURFACE, TYPE A	155.000	TON
19	402-07433 HMA SURFACE, TYPE B	190.000	TON
20	402-07438 HMA INTERMEDIATE, TYPE B	510.000	TON
21	404-05511 SEAL COAT, 2	950.000	SYS
22	406-05521 ASPHALT FOR TACK COAT	5,100.000	SYS
23	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
25	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	412.500	LFT
26	602-06729 BARRIER DELINEATOR	8.000	EACH
27	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	266.400	SYS
28	610-07486 HMA FOR APPROACHES, TYPE A	4.900	TON
29	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
30	615-06490 RIGHT OF WAY MARKER	11.000	EACH
31	615-06505 MONUMENT, B	2.000	EACH
32	616-02320 GEOTEXTILES	2,586.000	SYS
33	616-03472 RIPRAP, REVEMENT 18 IN.	1,685.000	TON
34	621-01956 SEED MIXTURE, LEGUME, 1	358.000	LBS
35	621-06545 FERTILIZER	0.760	TON
36	621-06553 SEED MIXTURE, R	320.000	LBS
37	621-06565 MULCHING MATERIAL	0.760	TON
38	621-06567 WATER	10.000	KGAL
39	621-06574 SODDING	1,394.000	SYS
40	622-52436 SIGN, DO NOT MOW OR SPRAY	2.000	EACH
41	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.	1,136.000	LFT
42	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	384.000	LBS
43	703-51032 REINFORCING STEEL, EPOXY COATED	53,491.000	LBS
44	704-51002 CONCRETE, C, SUPERSTRUCTURE	212.800	CYS
45	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
46	706-51020 CONCRETE, C, RAILING	17.230	CYS
47	707-05985 STRUCTURAL MEMBERS, CONCRETE I-BEAM, IV, 54 IN. X 20 IN.	342.000	LFT
48	709-51821 SURFACE SEAL	LUMP	LUMP

CALL ORDER : 460
LETTING DATE :

CONTRACT ID : B -28702-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
49	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	135.000	LFT
50	715-05407 PIPE, END BENT DRAIN, 6 IN.	120.000	LFT
51	715-46005 PIPE END SECTION, 15 IN.	6.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	10.000	EACH
53	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
54	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
55	801-07118 BARRICADE, III-A	144.000	LFT
56	801-07119 BARRICADE, III-B	144.000	LFT
57	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	842.000	LFT
58	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	8,296.000	LFT
59	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	4,148.000	LFT

CALL ORDER : 470
 LETTING DATE :

CONTRACT ID : B -28730-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
10	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
11	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
12	709-51821 SURFACE SEAL	LUMP	LUMP
13	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 480
 LETTING DATE :

CONTRACT ID : B -28731-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	8.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
10	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
11	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
12	709-51821 SURFACE SEAL	LUMP	LUMP
13	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

