

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-27611-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07039 FIELD OFFICE, B	10.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
6	105-08523 RADIO SERVICE	20.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	9,941.900	m2
14	202-02273 CENTER CURB, CONCRETE, REMOVE	20.600	m2
15	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	86.900	m
16	202-02278 CURB, CONCRETE, REMOVE	7.100	m
17	202-04089 SIGN, SHEET, REMOVE	12.000	EACH
18	202-91385 INLET, REMOVE	7.000	EACH
19	202-93047 MANHOLE, REMOVE	1.000	EACH
20	202-96133 PIPE, REMOVE	443.300	m
21	203-02000 EXCAVATION, COMMON	6,374.000	m3
22	205-06933 TEMPORARY DITCH INLET PROTECTION	11.000	EACH
23	206-51215 EXCAVATION, X	101.900	m3
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,422.000	m2
25	207-08268 SUBGRADE TREATMENT, TYPE IV	11,032.000	m2
26	211-07454 STRUCTURE BACKFILL	2,334.300	m3
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,201.600	Mg
28	302-06464 SUBBASE FOR PCCP	2,530.000	m3
29	304-07489 HMA PATCHING, TYPE A	9.600	Mg
30	306-08034 MILLING, ASPHALT, 38 mm	682.900	m2
31	306-08043 MILLING, TRANSITION	80.700	m2
32	402-07433 HMA SURFACE, TYPE B	128.500	Mg
33	402-07438 HMA INTERMEDIATE, TYPE B	198.800	Mg
34	402-07453 HMA FOR TEMPORARY PAVEMENT	97.100	Mg
35	406-05520 ASPHALT FOR TACK COAT	0.690	Mg
36	501-06322 QC/QA-PCCP, 275 mm	9,678.000	m2
37	503-03489 RETROFITTED TIE BARS	131.000	EACH
38	503-05240 D-1 CONTRACTION JOINT	1,606.800	m
39	605-06090 CURB, INTEGRAL, CONCRETE	815.800	m
40	605-06120 CURB, CONCRETE	138.400	m
41	605-94811 CURB TURNOUT	2.000	EACH
42	610-07486 HMA FOR APPROACHES, TYPE A	62.700	Mg
43	610-08446 PCCP FOR APPROACHES, 150 mm	1,551.900	m2
44	615-06490 RIGHT OF WAY MARKER	10.000	EACH
45	615-06515 MONUMENT, D	14.000	EACH
46	621-06545 FERTILIZER	0.200	Mg
47	621-06557 SEED MIXTURE, T	87.700	kg
48	621-06565 MULCHING MATERIAL	4.400	Mg

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-27611-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
49	621-06567 WATER	175.400	kL
50	621-06575 SODDING, NURSERY	9,743.800	m2
51	702-04325 TEMPORARY SHORING	LUMP	LUMP
52	702-51015 CONCRETE, B, FOOTINGS	48.200	m3
53	702-90915 CONCRETE, A	64.600	m3
54	703-06029 REINFORCING BARS, EPOXY COATED	3,677.000	kg
55	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	1,223.900	m
56	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	10.800	m
57	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	63.800	m
58	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	373.100	m
59	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	232.500	m
60	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	9.000	m
61	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	330.100	m
62	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	57.700	m
63	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	54.000	Mg
64	715-46015 PIPE END SECTION, 525 mm	1.000	EACH
65	715-46030 PIPE END SECTION, 750 mm	1.000	EACH
66	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
67	718-52610 AGGREGATE FOR UNDERDRAINS	266.000	m3
68	718-99153 GEOTEXTILES FOR UNDERDRAIN	4,885.700	m2
69	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
70	720-45145 INLET, J10, MODIFIED	1.000	EACH
71	720-45235 CATCH BASIN, E7	1.000	EACH
72	720-45250 CATCH BASIN, K10	18.000	EACH
73	720-45270 PIPE CATCH BASIN, 450 mm	3.000	EACH
74	720-45410 MANHOLE, C4	15.000	EACH
75	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	0.800	m
76	720-90984 MANHOLE, C2	8.000	EACH
77	720-95422 MANHOLE, J4	2.000	EACH
78	720-98687 CATCH BASIN, M10	1.000	EACH
79	720-99416 CATCH BASIN, B15	2.000	EACH
80	720-99417 CATCH BASIN, C15	2.000	EACH
81	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
82	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	3,474.800	m
83	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	2,517.700	m
84	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 600 mm	24.900	m
85	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	10.500	m
86	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
87	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
88	801-06710 FLASHING ARROW SIGN	270.000	DAY
89	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
90	801-07119 BARRICADE, III-B	66.000	m
91	801-94295 SIGNAL HEAD, RELOCATE	18.000	EACH
92	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	59.200	m
93	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	105.300	m
94	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	13.890	m2
95	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	3.780	m2
96	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	4.000	EACH

CALL ORDER : 120
 LETTING DATE :

CONTRACT ID : IR-27611-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
97	805-01842 HANDHOLE, SIGNAL	11.000	EACH
98	805-01879 SIGNAL SERVICE	1.000	EACH
99	805-02328 SIGNAL CABLE, 1C 14GA.	100.400	m
100	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	494.000	m
101	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
102	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	8.000	EACH
103	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	2.000	EACH
104	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
105	805-78420 DISCONNECT HANGER	4.000	EACH
106	805-78467 SIGNAL CABLE, 3C 8GA.	13.100	m
107	805-78485 SIGNAL CABLE, 5C 14GA.	100.800	m
108	805-78490 SIGNAL CABLE, 7C 14GA.	184.900	m
109	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	904.700	m
110	805-78746 PREFORMED LOOP DETECTORS	217.500	m
111	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
112	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	34.700	m
113	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
114	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
115	805-96014 SAW CUT, FULL DEPTH	39.400	m
116	808-03002 LINE, EPOXY, BROKEN, WHITE, 100 mm	199.400	m
117	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	529.700	m
118	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	1,537.000	m
119	808-04896 LINE, EPOXY, BROKEN, YELLOW, 100 mm	76.800	m
120	808-06716 LINE, REMOVE	195.000	m
121	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	12.100	m
122	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	31.900	m
123	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	5.000	EACH
124	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	5.000	EACH
125	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	114.000	EACH

CALL ORDER : 130
 LETTING DATE :

CONTRACT ID : IR-27989-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	18.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02272 PAVED SIDE DITCH, REMOVE	51.000	m
9	202-02273 CENTER CURB, CONCRETE, REMOVE	30.800	m2
10	202-02276 GUTTER TURNOUT, REINFORCED CONCRETE, REMOVE	2.000	EACH
11	202-02278 CURB, CONCRETE, REMOVE	247.000	m
12	202-02928 CATCH BASIN, REMOVE	9.000	EACH
13	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
14	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-05545 REGULATED MATERIALS, DISPOSE, C	454.000	m3
17	202-05550 REGULATED MATERIALS, REMOVE, C	454.000	m3
18	202-05555 REGULATED MATERIALS, TRANSPORT, C	454.000	m3
19	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
20	202-92222 TESTING FOR CONTAMINATED MATERIALS, TPH	5.000	EACH
21	202-94749 CURB, ASPHALT, REMOVE	75.000	m
22	202-96133 PIPE, REMOVE	498.000	m
23	203-02000 EXCAVATION, COMMON	11,258.000	m3
24	205-06932 TEMPORARY CHECK DAM, STRAW BALES	81.000	m
25	205-06933 TEMPORARY DITCH INLET PROTECTION	11.000	EACH
26	205-06937 TEMPORARY SILT FENCE	2,382.000	m
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,859.000	m2
28	207-08268 SUBGRADE TREATMENT, TYPE IV	20,794.000	m2
29	211-07454 STRUCTURE BACKFILL	1,974.000	m3
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,440.000	Mg
31	304-07493 WIDENING WITH HMA, TYPE B	1,115.000	Mg
32	306-08036 MILLING, ASPHALT, 50 mm	3,336.000	m2
33	306-08043 MILLING, TRANSITION	932.000	m2
34	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	2,010.000	Mg
35	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	6,427.000	Mg
36	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	9,352.000	Mg
37	402-07432 HMA SURFACE, TYPE A	87.000	Mg
38	402-07433 HMA SURFACE, TYPE B	88.000	Mg
39	402-07438 HMA INTERMEDIATE, TYPE B	266.000	Mg
40	402-07440 HMA BASE, TYPE A	262.000	Mg
41	406-05520 ASPHALT FOR TACK COAT	30.000	Mg
42	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
43	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	46.800	m
44	605-06120 CURB, CONCRETE	43.900	m
45	605-06140 CURB AND GUTTER, CONCRETE	1,863.000	m
46	605-94811 CURB TURNOUT	9.000	EACH
47	610-07487 HMA FOR APPROACHES, TYPE B	85.000	Mg
48	611-02375 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 175 mm	1,363.000	m2

CALL ORDER : 130
 LETTING DATE :

CONTRACT ID : IR-27989-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
49	611-06497 MAILBOX ASSEMBLY, SINGLE	6.000	EACH
50	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
51	615-06490 RIGHT OF WAY MARKER	52.000	EACH
52	615-06505 MONUMENT, B	22.000	EACH
53	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
54	621-06545 FERTILIZER	0.500	Mg
55	621-06553 SEED MIXTURE, R	100.000	kg
56	621-06565 MULCHING MATERIAL	2.400	Mg
57	621-06567 WATER	169.000	kL
58	621-06574 SODDING	498.000	m2
59	621-06575 SODDING, NURSERY	8,881.000	m2
60	714-04802 CONCRETE MODULAR BLOCK WALL	210.000	m2
61	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	1,839.000	m
62	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	30.800	m
63	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	8.800	m
64	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	726.000	m
65	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	182.000	m
66	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	23.500	m
67	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	219.000	m
68	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	12.500	m
69	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	92.400	m
70	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	11.400	Mg
71	715-46000 PIPE END SECTION, 300 mm	3.000	EACH
72	715-46005 PIPE END SECTION, 375 mm	13.000	EACH
73	718-06531 OUTLET PROTECTOR, 3	6.000	EACH
74	718-52610 AGGREGATE FOR UNDERDRAINS	390.000	m3
75	718-99153 GEOTEXTILES FOR UNDERDRAIN	5,263.000	m2
76	720-45035 INLET, F7	1.000	EACH
77	720-45270 PIPE CATCH BASIN, 450 mm	5.000	EACH
78	720-45400 MANHOLE, A4	9.000	EACH
79	720-45405 MANHOLE, B4	17.000	EACH
80	720-90455 MANHOLE, B2	1.000	EACH
81	720-90547 CATCH BASIN, A7	4.000	EACH
82	720-90768 CATCH BASIN, S14	1.000	EACH
83	720-96275 MANHOLE, A2	1.000	EACH
84	720-98174 INLET, B15	27.000	EACH
85	720-98555 INLET, C15	8.000	EACH
86	732-08421 MODULAR BLOCK WALL ERECTION	210.000	m2
87	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
88	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	14,700.000	m
89	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
90	801-06710 FLASHING ARROW SIGN	1,620.000	DAY
91	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
92	801-07118 BARRICADE, III-A	61.200	m
93	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	74.600	m
94	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	45.700	m
95	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	11.100	m2
96	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	8.200	m2

CALL ORDER : 130
 LETTING DATE :

CONTRACT ID : IR-27989-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
97	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	4.200	m2
98	805-01479 CONTROLLER CABINET FOUNDATION, P1, MODIFIED	1.000	EACH
99	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	4.000	EACH
100	805-01825 DISCONNECT HANGER, INSTALL	4.000	EACH
101	805-01842 HANDHOLE, SIGNAL	5.000	EACH
102	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	271.000	m
103	805-01879 SIGNAL SERVICE	1.000	EACH
104	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
105	805-02202 SIGNAL DETECTOR HOUSING, DOUBLE	3.000	EACH
106	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
107	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	5.000	EACH
108	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	3.000	EACH
109	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	3.000	EACH
110	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
111	805-78485 SIGNAL CABLE, 5C 14GA.	126.000	m
112	805-78490 SIGNAL CABLE, 7C 14GA.	400.000	m
113	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	6,406.200	m
114	805-78785 SIGNAL DETECTOR HOUSING	11.000	EACH
115	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	707.000	m
116	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
117	805-81060 SIGNAL STRAIN POLE, STEEL, 11.0 m	4.000	EACH
118	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	6.000	EACH
119	805-94069 CONDUIT, STEEL, GALVANIZED, 25 mm	1,450.000	m
120	808-01045 LINE, THERMOPLASTIC, DOTTED, YELLOW, 100 mm, 600 mm LINE,	23.000	m
121	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	117.000	m
122	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,317.000	m
123	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	525.000	m
124	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	216.000	m
125	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	1,284.000	m
126	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE,	83.000	m
127	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	201.000	m
128	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	107.000	m
129	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	32.000	EACH
130	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	19.000	EACH
131	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	730.000	m
132	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 100 mm, 600 mm LINE,	11.000	m

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : IR-29133-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES, HMA		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	36.000	MOS
3	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
5	202-02240 PAVEMENT REMOVAL	61,604.000	m2
6	202-04089 SIGN, SHEET, REMOVE	53.000	EACH
7	202-05546 REGULATED MATERIALS, DISPOSE, C	4,450.000	Mg
8	202-05551 REGULATED MATERIALS, REMOVE, C	4,450.000	Mg
9	202-05556 REGULATED MATERIALS, TRANSPORT, C	8,900.000	Mg
10	202-08429 REGULATED MATERIALS, DISPOSE, B	177,800.000	L
11	202-08430 REGULATED MATERIALS, REMOVE, B	176,800.000	L
12	202-08431 REGULATED MATERIALS, TRANSPORT, B	176,800.000	L
13	202-09106 TESTING FOR CONTAMINATED MATERIALS, MTBE AND	10.000	EACH
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
16	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
17	202-92222 TESTING FOR CONTAMINATED MATERIALS, TPH	10.000	EACH
18	203-02000 EXCAVATION, COMMON	50,337.000	m3
19	205-06932 TEMPORARY CHECK DAM, STRAW BALES	8.100	m
20	205-06933 TEMPORARY DITCH INLET PROTECTION	33.000	EACH
21	206-51220 EXCAVATION, WET	790.000	m3
22	207-08263 SUBGRADE TREATMENT, TYPE IA	62,996.000	m2
23	211-07454 STRUCTURE BACKFILL	17,997.000	m3
24	213-08058 FLOWABLE BACKFILL	18.400	m3
25	302-07455 DENSE GRADED SUBBASE	74.000	m3
26	303-01180 COMPACTED AGGREGATE, NO. 53	2,780.000	Mg
27	303-07449 COMPACTED AGGREGATE, NO. 73	2.000	Mg
28	304-07489 HMA PATCHING, TYPE A	298.000	Mg
29	306-08034 MILLING, ASPHALT, 38 mm	2,199.000	m2
30	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	11,779.000	Mg
31	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	19,182.000	Mg
32	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 MM	27,636.000	Mg
33	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	66,421.000	Mg
34	402-07432 HMA SURFACE, TYPE A	170.000	Mg
35	402-07435 HMA INTERMEDIATE, TYPE A	284.000	Mg
36	402-07453 HMA FOR TEMPORARY PAVEMENT	7,654.000	Mg
37	406-05520 ASPHALT FOR TACK COAT	143.000	Mg
38	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
39	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
40	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	15.240	m
41	604-06070 SIDEWALK, CONCRETE	9,561.000	m2
42	604-07900 CURB RAMP, CONCRETE, F	410.000	m2
43	604-07901 CURB RAMP, CONCRETE, G	20.000	m2
44	604-07902 CURB RAMP, CONCRETE, H	1,776.000	m2
45	604-07903 CURB RAMP, CONCRETE, K	16.000	m2
46	604-91531 SIDEWALK, CONCRETE, 100 mm	235.000	m2
47	605-06120 CURB, CONCRETE	2,377.500	m
48	605-06150 CURB AND GUTTER, C, CONCRETE	7,687.000	m

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : IR-29133-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES, HMA		
49	605-06210 CENTER CURB, C, CONCRETE	2,277.000	m
50	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	490.800	m2
51	610-05527 HMA FOR APPROACHES	248.000	Mg
52	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 150 mm	5,323.000	m2
53	616-02320 GEOTEXTILES	3,315.000	m2
54	616-05688 RIPRAP, CLASS 1	831.000	Mg
55	616-05689 RIPRAP, CLASS 2	2,256.000	Mg
56	621-06567 WATER	598.000	kL
57	621-06575 SODDING, NURSERY	32,995.000	m2
58	701-01840 PILE, REINFORCED CONCRETE, STEEL SHELL ENCASED, EPOXY COATED	86.400	m
59	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 7.92 mm, 356 mm	816.000	m
60	702-51015 CONCRETE, B, FOOTINGS	219.000	m3
61	702-51863 FIELD DRILLED HOLE IN CONCRETE	14.000	EACH
62	702-90915 CONCRETE, A	902.800	m3
63	703-51030 REINFORCING STEEL	57,894.000	kg
64	703-51032 REINFORCING STEEL, EPOXY COATED	63,255.000	kg
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	485.200	m3
66	706-01268 HANDRAIL, ALUMINUM	39.600	m
67	706-06349 RAILING, TX	54.000	m
68	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
69	709-51821 SURFACE SEAL	LUMP	LUMP
70	714-02544 WINGWALL, PRECAST CONCRETE	2.000	EACH
71	714-26726 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3600 mm x 2400 mm	50.000	m
72	715-01471 PIPE END SECTION, PRECAST CONCRETE, 375 mm	3.000	EACH
73	715-01765 PIPE END SECTION, PRECAST CONCRETE, 300 mm	6.000	EACH
74	715-04612 PIPE	2.100	m
75	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	337.800	m
76	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	8,330.000	m
77	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	28.000	m
78	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	20.600	m
79	715-05148 PIPE, TYPE 2, CIRCULAR, 250 mm	9.200	m
80	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	1,657.100	m
81	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,945.700	m
82	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	1,043.600	m
83	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	683.900	m
84	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	1,110.600	m
85	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	835.600	m
86	715-05159 PIPE, TYPE 2, CIRCULAR, 1050 mm	166.400	m
87	715-05161 PIPE, TYPE 2, CIRCULAR, 1200 mm	74.600	m
88	715-05162 PIPE, TYPE 2, CIRCULAR, 1350 mm	156.800	m
89	715-05245 PIPE, TYPE 1, DEFORMED, MIN. AREA 1.20 m2	25.600	m
90	715-05409 PIPE, SANITARY SEWER, 250 mm	75.000	m
91	715-05842 CONCRETE ANCHOR, 1050 mm	1.000	EACH
92	715-05920 PIPE END SECTION, PRECAST CONCRETE, 750 mm	3.000	EACH
93	715-06492 CONCRETE ANCHOR, 1350 mm	1.000	EACH
94	715-07536 CONCRETE ANCHOR, MIN. AREA 1.20 m2	2.000	EACH
95	715-08394 TRASH RACK	1.000	EACH
96	715-44240 CONCRETE, A, STRUCTURES	50.300	m3

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : IR-29133-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES, HMA		
97	715-46040 PIPE END SECTION, 900 mm	1.000	EACH
98	718-06528 OUTLET PROTECTOR, 1	2.000	EACH
99	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
100	718-52610 AGGREGATE FOR UNDERDRAINS	1,882.000	m3
101	718-99153 GEOTEXTILES FOR UNDERDRAIN	16,659.000	m2
102	720-04790 CASTING	2.000	EACH
103	720-44000 CASTING, ADJUST TO GRADE	70.000	EACH
104	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	4.000	EACH
105	720-45005 INLET, A2	3.000	EACH
106	720-45035 INLET, F7	3.000	EACH
107	720-45045 INLET, J10	2.000	EACH
108	720-45055 INLET, M10	2.000	EACH
109	720-45080 INLET, S14	3.000	EACH
110	720-45085 INLET, T14	2.000	EACH
111	720-45235 CATCH BASIN, E7	4.000	EACH
112	720-45265 PIPE CATCH BASIN, 375 mm	18.000	EACH
113	720-45410 MANHOLE, C4	69.000	EACH
114	720-91352 CATCH BASIN, F7	1.000	EACH
115	720-93501 MANHOLE, L4	2.000	EACH
116	720-94157 MANHOLE, C	2.000	EACH
117	720-94612 MANHOLE, K4	4.000	EACH
118	720-95422 MANHOLE, J4	18.000	EACH
119	720-98174 INLET, B15	11.000	EACH
120	720-98555 INLET, C15	6.000	EACH
121	720-98687 CATCH BASIN, M10	1.000	EACH
122	720-99416 CATCH BASIN, B15	100.000	EACH
123	720-99417 CATCH BASIN, C15	30.000	EACH
124	723-07033 STRUCTURE, PRECAST THREE-SIDED, 7920 mm X 3050	89.000	m
125	728-98377 MASONRY COATING	LUMP	LUMP
126	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	25,620.300	m
127	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	12,546.500	m
128	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	320.400	m
129	801-06640 CONSTRUCTION SIGN, A	124.000	EACH
130	801-06645 CONSTRUCTION SIGN, B	34.000	EACH
131	801-06710 FLASHING ARROW SIGN	990.000	DAY
132	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
133	801-07119 BARRICADE, III-B	165.000	m
134	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	551.000	m
135	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	437.680	m
136	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	68.000	EACH
137	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	10.860	m2
138	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	77.880	m2
139	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	33.030	m2
140	802-91122 SIGN, GROUND MOUNTED, RESET	37.000	EACH
141	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	24.000	EACH
142	805-01842 HANDHOLE, SIGNAL	57.000	EACH
143	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	2,029.000	m
144	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP

CALL ORDER : 160
 LETTING DATE :

CONTRACT ID : IR-29133-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES, HMA		
145	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 450mm	48.000	EACH
146	805-02658 CABLE, COAXIAL	110.200	m
147	805-06803 PEDESTRIAN SIGNAL, AUDIBLE	1.000	EACH
148	805-07767 SIGNAL CABLE, 12C 14 GA	401.000	m
149	805-08464 RADIO, INTERCONNECT	1.000	EACH
150	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
151	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	5.000	EACH
152	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	46.000	EACH
153	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER ARROW, GREEN	10.000	EACH
154	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	21.000	EACH
155	805-78415 SPAN, CATENARY, AND TETHER	24.000	EACH
156	805-78420 DISCONNECT HANGER	24.000	EACH
157	805-78445 SIGNAL SERVICE	6.000	EACH
158	805-78467 SIGNAL CABLE, 3C 8GA.	110.000	m
159	805-78485 SIGNAL CABLE, 5C 14GA.	2,085.000	m
160	805-78490 SIGNAL CABLE, 7C 14GA.	2,154.000	m
161	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	7,428.000	m
162	805-78746 PREFORMED LOOP DETECTORS	2,993.000	m
163	805-78925 CONTROLLER CABINET FOUNDATION, P1	6.000	EACH
164	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	24.000	EACH
165	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	88.000	EACH
166	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	48.000	EACH
167	808-01045 LINE, THERMOPLASTIC, DOTTED, YELLOW, 100 mm, 600 mm LINE,	53.600	m
168	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	3,865.800	m
169	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	4,901.600	m
170	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 200 mm	320.000	m
171	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 100 mm	58.000	m
172	808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 100 mm	56.900	m
173	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	784.800	m
174	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	5,615.300	m
175	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE,	104.300	m
176	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	570.500	m
177	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	2,501.200	m
178	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	99.000	EACH
179	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	99.000	EACH
180	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,494.000	EACH
181	808-98796 LINE, THERMOPLASTIC, DOTTED, WHITE, 100 mm, 600 mm LINE,	72.600	m

CALL ORDER : 230
 LETTING DATE :

CONTRACT ID : R -27569-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Category Number 0001		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	45.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	100.000	SYS
12	202-02241 GUARDRAIL, REMOVE	793.000	LFT
13	202-02279 CURB AND GUTTER, REMOVE	400.000	LFT
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	202-52710 SIDEWALK, CONCRETE, REMOVE	89.000	SYS
16	202-91385 INLET, REMOVE	11.000	EACH
17	202-93047 MANHOLE, REMOVE	4.000	EACH
18	202-96133 PIPE, REMOVE	965.000	LFT
19	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
20	202-96632 TRAFFIC SIGNALS AND EQUIPMENT, REMOVE	2.000	EACH
21	203-02000 EXCAVATION, COMMON	10,051.000	CYS
22	203-02070 BORROW	5,397.000	CYS
23	205-03371 SEDIMENT, REMOVE	10.000	CYS
24	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	85.000	TON
25	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
26	205-06937 TEMPORARY SILT FENCE	2,561.000	LFT
27	207-08262 SUBGRADE TREATMENT, TYPE I	17,625.000	SYS
28	207-08266 SUBGRADE TREATMENT, TYPE III	1,532.000	SYS
29	211-07454 STRUCTURE BACKFILL	6,098.000	CYS
30	303-01180 COMPACTED AGGREGATE, NO. 53	1,332.000	TON
31	304-07489 HMA PATCHING, TYPE A	64.000	TON
32	304-07492 WIDENING WITH HMA, TYPE A	441.000	TON
33	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,124.000	TON
34	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,873.000	TON
35	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,996.000	TON
36	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	1,623.000	TON
37	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	2,630.000	TON
38	402-07432 HMA SURFACE, TYPE A	255.000	TON
39	402-07435 HMA INTERMEDIATE, TYPE A	425.000	TON
40	406-05520 ASPHALT FOR TACK COAT	15.000	TON
41	502-06457 PCCP, 9 IN.	294.000	SYS
42	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
43	601-06855 GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.000	EACH
44	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
45	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	363.000	LFT
46	604-07897 CURB RAMP, CONCRETE, C	114.000	SYS
47	604-07901 CURB RAMP, CONCRETE, G	6.000	SYS
48	604-07902 CURB RAMP, CONCRETE, H	29.000	SYS

CALL ORDER : 230
 LETTING DATE :

CONTRACT ID : R -27569-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Category Number 0001		
49	604-07904 CURB RAMP, CONCRETE, L	55.000	SYS
50	605-06120 CURB, CONCRETE	233.000	LFT
51	605-06150 CURB AND GUTTER, C, CONCRETE	4,758.000	LFT
52	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	2,034.000	LFT
53	605-97937 CURB AND GUTTER, CONCRETE, ROLL	308.000	LFT
54	610-07486 HMA FOR APPROACHES, TYPE A	34.000	TON
55	610-07712 PCCP FOR APPROACHES, 6 IN.	1,815.000	SYS
56	616-02320 GEOTEXTILES	202.000	SYS
57	616-06405 RIPRAP, REVETMENT	120.000	TON
58	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
59	621-06560 MULCHED SEEDING, U	12,465.000	SYS
60	621-06575 SODDING, NURSERY	100.000	SYS
61	702-94656 CONCRETE, B	11.000	CYS
62	703-51030 REINFORCING STEEL	260.000	LBS
63	714-06660 WINGWALL	43.000	SYS
64	715-01344 PIPE END SECTION, 60 IN.	1.000	EACH
65	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	5,264.000	LFT
66	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	2,956.000	LFT
67	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	382.000	LFT
68	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	406.000	LFT
69	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	442.000	LFT
70	715-05163 PIPE, TYPE 2, CIRCULAR, 60 IN.	109.000	LFT
71	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	42.000	LFT
72	715-05711 PIPE, SANITARY SEWER, 6 IN.	30.000	LFT
73	715-06923 PIPE, TYPE 2, CIRCULAR, 84 IN.	527.000	LFT
74	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
75	715-46005 PIPE END SECTION, 15 IN.	3.000	EACH
76	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
77	718-52610 AGGREGATE FOR UNDERDRAINS	482.000	CYS
78	718-99153 GEOTEXTILES FOR UNDERDRAIN	6,144.000	SYS
79	720-44000 CASTING, ADJUST TO GRADE	12.000	EACH
80	720-45030 INLET, E7	2.000	EACH
81	720-45410 MANHOLE, C4	32.000	EACH
82	720-90984 MANHOLE, C2	4.000	EACH
83	720-91110 MANHOLE, N4	3.000	EACH
84	720-95335 MANHOLE, M4	1.000	EACH
85	720-98174 INLET, B15	9.000	EACH
86	720-98555 INLET, C15	3.000	EACH
87	720-99416 CATCH BASIN, B15	34.000	EACH
88	720-99417 CATCH BASIN, C15	9.000	EACH
89	801-04308 ROAD CLOSURE SIGN ASSEMBLY	21.000	EACH
90	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13,350.000	LFT
91	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	52.000	LFT
92	801-06625 DETOUR ROUTE MARKER ASSEMBLY	98.000	EACH
93	801-06640 CONSTRUCTION SIGN, A	52.000	EACH
94	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
95	801-07118 BARRICADE, III-A	1,020.000	LFT
96	801-07119 BARRICADE, III-B	18.000	LFT

CALL ORDER : 230
 LETTING DATE :

CONTRACT ID : R -27569-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Category Number 0001		
97	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	361.000	LFT
98	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	131.000	LFT
99	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	176.000	SFT
100	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	188.000	SFT
101	802-97812 STREET NAME IDENTIFICATION SIGN	2.000	EACH
102	805-04940 MAST ARM	2.000	EACH
103	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	520.000	LFT
104	805-78412 SIGNAL PEDESTAL, 9 FT.	1.000	EACH
105	805-78900 PEDESTAL FOUNDATION, A	1.000	EACH
106	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	2,079.000	LFT
107	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	520.000	LFT
108	807-02191 HANDHOLE, LIGHTING	5.000	EACH
109	807-02193 LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT.	42.000	EACH
110	807-04654 LIGHT POLE	37.000	EACH
111	807-04654 LIGHT POLE	5.000	EACH
112	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3,254.000	LFT
113	807-86605 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 150 WATT	76.000	EACH
114	807-86615 LUMINAIRE, ROADWAY, 250 WATT, HIGH PRESSURE SODIUM	8.000	EACH
115	807-86805 SERVICE POINT, I	2.000	EACH
116	807-86810 SERVICE POINT, II	1.000	EACH
117	807-86905 TRANSITION FITTINGS, GALVANIZED STEEL CONDUIT TO PLASTIC	32.000	EACH
118	807-86910 CONNECTOR KIT, UNFUSED	43.000	EACH
119	807-86915 CONNECTOR KIT, FUSED	43.000	EACH
120	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	93.000	EACH
121	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	20.000	EACH
122	807-86930 INSULATION LINK, NONWATERPROOFED	95.000	EACH
123	807-86935 INSULATION LINK, WATERPROOFED	20.000	EACH
124	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	416.000	LFT
125	808-04767 LINE	100.000	LFT
126	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	200.000	LFT
127	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,056.000	LFT
128	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	711.000	LFT
129	808-06716 LINE, REMOVE	325.000	LFT
130	808-08258 TRANSVERSE MARKINGS	107.000	LFT
131	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	223.000	LFT
132	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,196.000	LFT
133	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	288.000	LFT
134	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	199.000	LFT
135	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	24.000	LFT
136	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	13.000	EACH
137	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	7.000	EACH
138	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	126.000	EACH
139	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	799.000	LFT

CALL ORDER : 250
 LETTING DATE :

CONTRACT ID : R -27895-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	28.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	28.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	1,466.700	m2
12	202-02245 TREE, 150 mm, REMOVE	14.000	EACH
13	202-02250 TREE, 250 mm, REMOVE	12.000	EACH
14	202-02255 TREE, 460 mm, REMOVE	31.000	EACH
15	202-02260 TREE, 760 mm, REMOVE	26.000	EACH
16	202-02279 CURB AND GUTTER, REMOVE	2,492.200	m
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-52710 SIDEWALK, CONCRETE, REMOVE	3,585.900	m2
19	202-91922 STUMP, REMOVE	6.000	EACH
20	203-02000 EXCAVATION, COMMON	18,665.300	m3
21	203-04523 DEWATERING	LUMP	LUMP
22	205-03371 SEDIMENT REMOVE	35.000	m3
23	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
24	205-06936 TEMPORARY SEDIMENT TRAP	828.000	Mg
25	205-06937 TEMPORARY SILT FENCE	3,036.000	m
26	207-08268 SUBGRADE TREATMENT, TYPE IV	49,616.100	m2
27	210-09110 MAINTAIN	LUMP	LUMP
28	211-02050 B BORROW	16,107.000	m3
29	213-08058 FLOWABLE BACKFILL	17,608.000	m3
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	10,664.400	Mg
31	303-01180 COMPACTED AGGREGATE, NO. 53	465.000	Mg
32	304-07493 WIDENING WITH HMA, TYPE B	6,105.000	Mg
33	306-08034 MILLING, ASPHALT, 38 mm	325.000	m2
34	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,252.800	Mg
35	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	7,075.900	Mg
36	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,869.200	Mg
37	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	22,248.000	Mg
38	406-05520 ASPHALT FOR TACK COAT	46.500	Mg
39	604-07899 CURB RAMP, CONCRETE, E	85.300	m2
40	604-07899 CURB RAMP, CONCRETE, E	50.600	m2
41	604-07901 CURB RAMP, CONCRETE, G	64.100	m2
42	604-07901 CURB RAMP, CONCRETE, G	162.000	m2
43	604-07902 CURB RAMP, CONCRETE, H	58.400	m2
44	604-07902 CURB RAMP, CONCRETE, H	30.300	m2
45	604-07903 CURB RAMP, CONCRETE, K	4.800	m2
46	604-44251 STEPS, CONCRETE	0.721	m3
47	604-90256 SIDEWALK, CONCRETE, 150 mm	7,784.800	m2
48	605-06120 CURB, CONCRETE	1,849.400	m

CALL ORDER : 250
 LETTING DATE :

CONTRACT ID : R -27895-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
49	605-06140 CURB AND GUTTER, CONCRETE	4,675.800	m
50	610-08446 PCCP FOR APPROACHES, 150 mm	5,555.200	m2
51	611-06497 MAILBOX ASSEMBLY, SINGLE	61.000	EACH
52	615-06500 MONUMENT, A	1.000	EACH
53	615-06505 MONUMENT, B	10.000	EACH
54	616-06451 RIPRAP, UNIFORM	163.200	Mg
55	621-06575 SODDING, NURSERY	11,765.000	m2
56	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM OVER 32 TO 50 mm	84.000	EACH
57	702-94656 CONCRETE, B	108.100	m3
58	706-92237 HANDRAIL, STEEL	46.000	m
59	712-04784 STRUCTURE	1.000	EACH
60	712-04784 STRUCTURE	1.000	EACH
61	715-03169 WATER MAIN, DUCTILE IRON, 350 mm	3,244.000	m
62	715-04612 PIPE	440.000	m
63	715-04612 PIPE	21.000	m
64	715-04612 PIPE	450.000	m
65	715-04612 PIPE	1,180.000	m
66	715-04612 PIPE	181.000	m
67	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	163.900	m
68	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	962.800	m
69	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	83.000	m
70	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	601.100	m
71	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	185.700	m
72	715-05155 PIPE, TYPE 2, CIRCULAR, 675 mm	265.300	m
73	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	439.500	m
74	715-05161 PIPE, TYPE 2, CIRCULAR, 1200 mm	1,438.100	m
75	715-05408 PIPE, SANITARY SEWER, 200 mm	23.000	m
76	715-05409 PIPE, SANITARY SEWER, 250 mm	671.500	m
77	715-05411 PIPE, SANITARY SEWER, 300 mm	813.700	m
78	715-05412 PIPE, SANITARY SEWER, 375 mm	17.000	m
79	715-05413 PIPE, SANITARY SEWER, 450 mm	346.000	m
80	715-05415 PIPE, SANITARY SEWER, 600 mm	17.000	m
81	715-05419 PIPE, SANITARY SEWER, 900 mm	135.000	m
82	715-06379 SEWER	129.000	EACH
83	715-06379 SEWER	49.000	EACH
84	715-98265 WATER MAIN, DUCTILE IRON, 100 mm	6.000	m
85	720-03194 MANHOLE	2.000	EACH
86	720-03194 MANHOLE	2.000	EACH
87	720-04721 MANHOLE, K	13.000	EACH
88	720-44000 CASTING, ADJUST TO GRADE	38.000	EACH
89	720-45030 INLET, E7	5.000	EACH
90	720-45035 INLET, F7	1.000	EACH
91	720-45410 MANHOLE, C4	15.000	EACH
92	720-45415 MANHOLE, D4	15.000	EACH
93	720-45416 MANHOLE, E4	25.000	EACH
94	720-94157 MANHOLE, C	35.000	EACH
95	720-96999 FIRE HYDRANT ASSEMBLY	26.000	EACH
96	720-98174 INLET, B15	65.000	EACH

CALL ORDER : 250
 LETTING DATE :

CONTRACT ID : R -27895-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
97	720-98555 INLET, C15	29.000	EACH
98	732-01898 WATER MAIN, DUCTILE IRON, 250 mm	121.000	m
99	732-02745 GATE VALVE AND BOX, 200 mm	22.000	EACH
100	732-04836 GATE VALVE	3.000	EACH
101	732-04836 GATE VALVE	48.000	EACH
102	732-04995 LINE STOP	8.000	EACH
103	732-04995 LINE STOP	4.000	EACH
104	732-04995 LINE STOP	38.000	EACH
105	732-04995 LINE STOP	6.000	EACH
106	732-05560 SERVICE LINE	2,585.000	m
107	732-09111 SERVICE	212.000	EACH
108	732-91738 WATER MAIN, DUCTILE IRON, 150 mm	222.000	m
109	732-91739 WATER MAIN, DUCTILE IRON, 200 mm	396.000	m
110	732-93923 DUCTILE IRON WATER PIPE FITTINGS	6,045.000	kg
111	732-98479 GATE VALVE AND BOX, 250 mm	5.000	EACH
112	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	16,072.000	m
113	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	28.800	m
114	801-06640 CONSTRUCTION SIGN, A	80.000	EACH
115	801-06710 FLASHING ARROW SIGN	360.000	DAY
116	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
117	801-07118 BARRICADE, III-A	173.000	m
118	801-07215 TEMPORARY CHANGEABLE MESSAGE SIGN	540.000	DAY
119	805-01842 HANDHOLE, SIGNAL	9.000	EACH
120	805-02151 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 305 mm	16.000	EACH
121	805-78060 CONTROLLER AND CABINET, MENU DRIVEN, 4 PHASE	2.000	EACH
122	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
123	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	20.000	EACH
124	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	3.000	EACH
125	805-78420 DISCONNECT HANGER	4.000	EACH
126	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,032.900	m
127	805-78485 SIGNAL CABLE, 5C 14GA.	85.900	m
128	805-78490 SIGNAL CABLE, 7C 14GA.	294.900	m
129	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,562.600	m
130	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
131	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	355.800	m
132	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
133	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	300.900	m
134	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	3,741.900	m
135	808-06716 LINE, REMOVE	570.000	m
136	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	5,678.500	m
137	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	43.600	m
138	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	184.000	m
139	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	734.700	m
140	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	8.000	EACH
141	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
142	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	80.000	EACH
143	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	80.000	EACH
144	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	281.000	m

CALL ORDER : 250
LETTING DATE :

CONTRACT ID : R -27895-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	N/A		
145 202-01667	SIGN AND SUPPORTS, WOOD POSTS, REMOVE	90.000	EACH
146 202-04089	SIGN, SHEET, REMOVE	21.000	EACH
147 802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	501.200	m
148 802-07060	SIGN, SHEET, RELOCATE	34.000	EACH
149 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	4.500	m2
150 802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	2.600	m2

CALL ORDER : 260
 LETTING DATE :

CONTRACT ID : R -28094-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGHT DISTANCE IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07040 FIELD OFFICE, C	17.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	54.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	12,920.000	CYS
12	203-02070 BORROW	500.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	74.000	TON
14	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
15	205-06934 TEMPORARY MULCHING	13.000	TON
16	205-06937 TEMPORARY SILT FENCE	1,484.000	LFT
17	207-08263 SUBGRADE TREATMENT, TYPE IA	9,418.000	SYS
18	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,864.000	SYS
19	211-07454 STRUCTURE BACKFILL	196.000	CYS
20	303-01180 COMPACTED AGGREGATE, NO. 53	3,465.000	TON
21	303-02172 TEMPORARY AGGREGATE	500.000	TON
22	304-07490 HMA PATCHING, TYPE B	18.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	496.000	SYS
24	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	838.000	TON
25	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,083.000	TON
26	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,498.000	TON
27	406-05520 ASPHALT FOR TACK COAT	5.420	TON
28	610-07486 HMA FOR APPROACHES, TYPE A	190.000	TON
29	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
30	615-06490 RIGHT OF WAY MARKER	45.000	EACH
31	615-06505 MONUMENT, B	4.000	EACH
32	616-02320 GEOTEXTILES	2,227.000	SYS
33	616-05688 RIPRAP, CLASS 1	223.000	TON
34	616-05689 RIPRAP, CLASS 2	210.000	TON
35	616-06451 RIPRAP, UNIFORM	933.000	TON
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
37	621-01956 SEED MIXTURE, LEGUME, 1	261.000	LBS
38	621-06545 FERTILIZER	0.500	TON
39	621-06557 SEED MIXTURE, T	572.000	LBS
40	621-06565 MULCHING MATERIAL	10.400	TON
41	621-06567 WATER	47.000	KGAL
42	621-06575 SODDING, NURSERY	11,811.000	SYS
43	622-52436 SIGN, DO NOT MOW OR SPRAY	2.000	EACH
44	715-02397 SAFETY METAL END SECTION, 4:1, 36 IN.	2.000	EACH
45	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	59.000	LFT
46	715-05127 PIPE, TYPE 1, CURCULAR, 42 IN.	190.000	LFT
47	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	57.000	LFT
48	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	10.000	LFT

CALL ORDER : 260
 LETTING DATE :

CONTRACT ID : R -28094-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
49	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	56.000	LFT
50	715-05842 CONCRETE ANCHOR, 42 IN.	4.000	EACH
51	715-46005 PIPE END SECTION, 15 IN.	5.000	EACH
52	718-06531 OUTLET PROTECTOR, 3	1.000	EACH
53	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
54	720-45410 MANHOLE, C4	1.000	EACH
55	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	4.500	LFT
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
57	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
58	801-06640 CONSTRUCTION SIGN, A	27.000	EACH
59	801-06645 CONSTRUCTION SIGN, B	14.000	EACH
60	801-07118 BARRICADE, III-A	12.000	LFT
61	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	57.400	LFT
62	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	20.500	SFT
63	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	27.000	SFT
64	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,984.000	LFT
65	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,040.000	LFT
66	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	56.000	LFT
67	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	48.000	EACH
68	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	48.000	EACH

CALL ORDER : 270
 LETTING DATE :

CONTRACT ID : R -28329-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	FLASHER MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
3	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
6	202-05545 REGULATED MATERIALS, DISPOSE, C	550.000	CYS
7	202-05550 REGULATED MATERIALS, REMOVE, C	550.000	CYS
8	202-05555 REGULATED MATERIALS, TRANSPORT, C	550.000	CYS
9	202-09106 TESTING FOR CONTAMINATED MATERIALS, MTBE AND	8.000	EACH
10	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	10,893.000	CYS
12	203-02070 BORROW	500.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	36.000	TON
14	205-06933 TEMPORARY DITCH INLET PROTECTION	3.000	EACH
15	205-06934 TEMPORARY MULCHING	10.000	TON
16	205-06937 TEMPORARY SILT FENCE	1,175.000	LFT
17	207-08263 SUBGRADE TREATMENT, TYPE IA	6,306.000	SYS
18	211-02050 B BORROW	1,000.000	CYS
19	211-07454 STRUCTURE BACKFILL	196.000	CYS
20	213-04324 FLOWABLE FILL	3.200	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,782.000	TON
22	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	200.000	TON
23	304-07491 HMA PATCHING, TYPE C	40.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,100.000	SYS
25	402-07433 HMA SURFACE, TYPE B	227.000	TON
26	402-07434 HMA SURFACE, TYPE C	568.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	214.000	TON
28	402-07439 HMA INTERMEDIATE, TYPE C	847.000	TON
29	402-07441 HMA BASE, TYPE B	490.000	TON
30	402-07442 HMA BASE, TYPE C	1,866.000	TON
31	406-05520 ASPHALT FOR TACK COAT	7.080	TON
32	605-06145 CURB AND GUTTER, B, CONCRETE	295.000	LFT
33	607-90826 GUTTER TURNOUT, CONCRETE	1.000	EACH
34	610-07487 HMA FOR APPROACHES, TYPE B	124.000	TON
35	610-07712 PCCP FOR APPROACHES, 6 IN.	170.000	SYS
36	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
37	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
38	615-06490 RIGHT OF WAY MARKER	27.000	EACH
39	615-06505 MONUMENT, B	3.000	EACH
40	616-02320 GEOTEXTILES	2,645.000	SYS
41	616-05689 RIPRAP, CLASS 2	1,808.000	TON
42	616-06405 RIPRAP, REVETMENT	43.000	TON
43	616-06451 RIPRAP, UNIFORM	291.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	14.000	EACH
45	621-06545 FERTILIZER	1.400	TON
46	621-06553 SEED MIXTURE, R	578.000	LBS
47	621-06557 SEED MIXTURE, T	850.000	LBS
48	621-06565 MULCHING MATERIAL	7.000	TON

CALL ORDER : 270
 LETTING DATE :

CONTRACT ID : R -28329-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 FLASHER MODERNIZATION				
49	621-06567	WATER	14.000	KGAL
50	621-06574	SODDING	3,506.000	SYS
51	622-91786	SEEDLING	90.000	EACH
52	714-26708	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 8 FT. X 4 FT.	114.000	LFT
53	714-26718	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 10 FT. X 6 FT.	109.000	LFT
54	714-94664	CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3 FT. X 3 FT.	60.000	LFT
55	715-03487	SAFETY METAL END SECTION, 4:1, 30 IN.	1.000	EACH
56	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	218.000	LFT
57	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	520.000	LFT
58	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	30.000	LFT
59	715-05175	PIPE, TYPE 3, CIRCULAR, 30 IN.	150.000	LFT
60	715-06004	CONCRETE ANCHOR, 48 IN.	4.000	EACH
61	715-46005	PIPE END SECTION, 15 IN.	3.000	EACH
62	715-46030	PIPE END SECTION, 30 IN.	4.000	EACH
63	720-45070	INLET, P12A	1.000	EACH
64	720-98555	INLET, C15	2.000	EACH
65	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
66	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
67	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3,426.000	LFT
68	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,426.000	LFT
69	801-06640	CONSTRUCTION SIGN, A	26.000	EACH
70	801-06645	CONSTRUCTION SIGN, B	18.000	EACH
71	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118	BARRICADE, III-A	168.000	LFT
73	802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	69.400	LFT
74	802-05702	SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	35.200	LFT
75	802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.250	SFT
76	802-76035	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	76.500	SFT
77	802-76045	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	21.000	SFT
78	805-01815	SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
79	805-01879	SIGNAL SERVICE, INSTALL	1.000	EACH
80	805-02439	CONDUIT RISER, GALVANIZED, 2 IN.	1.000	EACH
81	805-78010	CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
82	805-78190	TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	4.000	EACH
83	805-78195	TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. RED	4.000	EACH
84	805-78415	SPAN, CATENARY, AND TETHER	1.000	EACH
85	805-78420	DISCONNECT HANGER	1.000	EACH
86	805-78480	SIGNAL CABLE, 3C 14GA.	381.000	LFT
87	805-78485	SIGNAL CABLE, 5C 14GA.	51.000	LFT
88	805-81032	SIGNAL STRAIN POLE, STEEL, 30 FT.	2.000	EACH
89	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,200.000	LFT
90	808-06716	LINE, REMOVE	1,142.000	LFT
91	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	310.000	LFT
92	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,060.000	LFT
93	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	60.000	LFT
94	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	58.000	EACH
95	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	62.000	EACH

CALL ORDER : 280
 LETTING DATE :

CONTRACT ID : R -28346-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-04089 SIGN, SHEET, REMOVE	3.000	EACH
9	203-02000 EXCAVATION, COMMON	6,602.000	CYS
10	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	140.000	TON
11	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
12	205-06937 TEMPORARY SILT FENCE	540.000	LFT
13	207-08265 SUBGRADE TREATMENT, TYPE IIA	17,783.000	SYS
14	211-07454 STRUCTURE BACKFILL	30.000	CYS
15	213-04324 FLOWABLE FILL	200.000	CYS
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,211.000	TON
17	306-08043 MILLING, TRANSITION	811.000	SYS
18	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,021.000	TON
19	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,579.000	TON
20	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,645.000	TON
21	404-05514 SEAL COAT, 5	3,638.000	SYS
22	406-05521 ASPHALT FOR TACK COAT	24,300.000	SYS
23	610-07486 HMA FOR APPROACHES, TYPE A	122.000	TON
24	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	3.000	EACH
25	616-02320 GEOTEXTILES	267.000	SYS
26	616-05688 RIPRAP, CLASS 1	63.000	TON
27	616-06451 RIPRAP, UNIFORM	70.000	TON
28	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
29	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	13,300.000	SYS
30	621-06559 MULCHED SEEDING, R	30,863.000	SYS
31	621-06575 SODDING, NURSERY	392.000	SYS
32	702-90915 CONCRETE, A	1.700	CYS
33	714-02544 WINGWALL, PRECAST CONCRETE	6.000	EACH
34	714-03571 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 12 FT. X 3 FT.	68.000	LFT
35	714-07892 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 9 FT. X 3 FT.	39.000	LFT
36	714-93641 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4 FT. X 3 FT.	39.000	LFT
37	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	2.000	EACH
38	715-02630 SAFETY METAL END SECTION, 6:1, 24 IN.	1.000	EACH
39	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	73.000	LFT
40	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	55.000	LFT
41	715-05228 PIPE, TYPE 1, DEFORMED, MIN. AREA 1.6 SQ. FT.	451.000	LFT
42	715-05232 PIPE, TYPE 1, DEFORMED, MIN. AREA 2.9 SQ.FT.	325.000	LFT
43	715-05248 PIPE, TYPE 1, DEFORMED, 16.6 SQ. FT.	116.000	LFT
44	715-05946 SAFETY METAL END SECTION, 6:1, 21 IN.	1.000	EACH
45	715-07579 SAFETY METAL END SECTION, 6:1, MIN. AREA 2.9 SQ. FT.	1.000	EACH
46	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
47	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
48	720-45135 INLET, F7, MODIFIED	5.000	EACH

CALL ORDER : 280
 LETTING DATE :

CONTRACT ID : R -28346-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
49	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
50	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
51	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
52	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
53	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
54	801-07119 BARRICADE, III-B	80.000	LFT
55	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	55.200	LFT
56	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
57	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	36.900	SFT
58	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,400.000	LFT
59	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,950.000	LFT
60	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	68.000	LFT
61	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH

CALL ORDER : 304
 LETTING DATE :

CONTRACT ID : R -28774-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-96133 PIPE, REMOVE	14.000	m
9	203-02000 EXCAVATION, COMMON	4,200.000	m3
10	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	7.000	Mg
11	205-06932 TEMPORARY CHECK DAM, STRAW BALES	45.000	m
12	205-06937 TEMPORARY SILT FENCE	100.000	m
13	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,998.000	m2
14	211-07454 STRUCTURE BACKFILL	38.100	m3
15	213-08058 FLOWABLE BACKFILL	54.500	m3
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,748.000	Mg
17	306-08034 MILLING, ASPHALT, 38 mm	6,300.000	m2
18	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,106.000	Mg
19	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,145.000	Mg
20	406-05520 ASPHALT FOR TACK COAT	3.800	Mg
21	610-07486 HMA FOR APPROACHES, TYPE A	252.500	Mg
22	616-02320 GEOTEXTILES	50.000	m2
23	616-06405 RIPRAP, REVETMENT	31.000	Mg
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
25	621-02770 EROSION CONTROL BLANKET	487.000	m2
26	621-06545 FERTILIZER	0.950	Mg
27	621-06553 SEED MIXTURE, R	195.000	kg
28	621-06565 MULCHING MATERIAL	4.600	Mg
29	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	39.000	m
30	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	16.000	m
31	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	53.000	m
32	715-06004 CONCRETE ANCHOR, 1200 mm	2.000	EACH
33	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	6.700	Mg
34	715-46010 PIPE END SECTION, 450 mm	10.000	EACH
35	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
36	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
37	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
38	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
39	801-07118 BARRICADE, III-A	14.400	m
40	801-07119 BARRICADE, III-B	7.200	m
41	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	32.400	m
42	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	4.840	m2
43	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	3,254.000	m
44	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	3,241.000	m
45	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	37.000	m

CALL ORDER : 306
 LETTING DATE :

CONTRACT ID : R -28814-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Category Number 0001		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
6	203-02000 EXCAVATION, COMMON	500.000	CYS
7	203-08607 LINEAR GRADING	2,204.640	LFT
8	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	100.000	TON
9	205-06932 TEMPORARY CHECK DAM, STRAW BALES	240.000	LFT
10	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
11	205-06937 TEMPORARY SILT FENCE	7,000.000	LFT
12	207-08264 SUBGRADE TREATMENT, TYPE II	1,833.000	SYS
13	211-02050 B BORROW	4,000.000	CYS
14	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	522.000	TON
15	303-05692 STONE, NO. 8	55.000	TON
16	303-07662 STONE	10.000	TON
17	306-08039 MILLING, ASPHALT REMOVAL	100.000	SYS
18	402-07432 HMA SURFACE, TYPE A	232.000	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	386.000	TON
20	604-04740 PAVERS	638.000	SFT
21	604-06070 SIDEWALK, CONCRETE	12.000	SYS
22	607-05729 PAVED SIDE DITCH, MODIFIED	14.000	LFT
23	607-05729 PAVED SIDE DITCH, MODIFIED	14.000	LFT
24	616-02305 GABIONS	214.000	CYS
25	616-02320 GEOTEXTILES	600.000	SYS
26	616-06405 RIPRAP, REVETMENT	12.000	TON
27	621-02770 EROSION CONTROL BLANKET	1,272.000	SYS
28	621-06574 SODDING	17,500.000	SYS
29	621-07642 SOIL PREPARATION	100.000	CYS
30	621-98038 MULCH, HARDWOOD SHREDDED BARK	15.000	CYS
31	622-99025 PLANT, BETULA NIGRA	13.000	EACH
32	622-99034 PLANT, RHUS AROMATICA	246.000	EACH
33	711-02554 PEDESTRIAN BRIDGE	LUMP	LUMP
34	711-02554 PEDESTRIAN BRIDGE	LUMP	LUMP
35	711-02554 PEDESTRIAN BRIDGE	LUMP	LUMP
36	711-05101 EDGING	1,200.000	LFT
37	711-05101 EDGING	42.000	LFT
38	711-05101 EDGING	180.000	LFT
39	714-02930 HEADWALL	9.000	EACH
40	714-02930 HEADWALL	1.000	EACH
41	715-05422 PIPE, SLOTTED DRAIN, 12 IN.	28.000	LFT
42	715-06517 PIPE, CORRUGATED PE, S, 12 IN.	120.000	LFT
43	715-06518 PIPE, CORRUGATED PE, S, 15 IN.	130.000	LFT
44	715-27015 PIPE, CORRUGATED STEEL, 0.064 IN., 12 IN.	120.000	LFT
45	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	400.000	LFT
46	718-99153 GEOTEXTILES FOR UNDERDRAIN	90.000	SYS
47	720-45030 INLET, E7	4.000	EACH
48	720-45235 CATCH BASIN, E7	2.000	EACH

CALL ORDER : 306
LETTING DATE :

CONTRACT ID : R -28814-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Category Number 0001		
49 802-04314	SIGN	4.000	EACH
50 808-04767	LINE	2,200.000	LFT
51 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	28.000	LFT
52 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3,375.000	LFT

CALL ORDER : 324
 LETTING DATE :

CONTRACT ID : R -28961-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	3.000	EACH
3	105-07038 FIELD OFFICE, A	10.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
6	105-08523 RADIO SERVICE	30.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-74035 SIGN, REMOVE	2.000	EACH
13	303-01180 COMPACTED AGGREGATE, NO. 53	1,202.000	TON
14	303-07449 COMPACTED AGGREGATE, NO. 73	4,700.000	TON
15	304-07783 HMA PATCHING, TYPE D	917.000	TON
16	306-08033 MILLING, ASPHALT, 1 IN.	374,661.000	SYS
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	8,192.000	SYS
18	306-08041 MILLING, PCCP	3,164.000	SYS
19	306-08042 MILLING, SCARIFICATION/PROFILE	4,363.000	SYS
20	306-08043 MILLING, TRANSITION	6,514.000	SYS
21	306-08432 MILLING, APPROACH	1,752.000	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-09049 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm-PWL	31,710.000	TON
24	404-05511 SEAL COAT, 2	201,630.000	SYS
25	406-05520 ASPHALT FOR TACK COAT	93.500	TON
26	503-05240 D-1 CONTRACTION JOINT	300.000	LFT
27	506-06333 PCCP PATCHING, FULL DEPTH	3,250.000	SYS
28	608-04395 AGGREGATE FOR SHOULDER DRAINS	140.000	TON
29	610-07788 HMA FOR APPROACHES, TYPE D	145.000	TON
30	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	16.400	TON
31	612-60410 DRILLED HOLE FOR UNDERSEAL	272.000	EACH
32	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	2,500.000	LFT
33	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN.	37,402.000	LFT
34	718-06526 HMA FOR UNDERDRAINS	3,900.000	TON
35	718-06528 OUTLET PROTECTOR, 1	100.000	EACH
36	718-52610 AGGREGATE FOR UNDERDRAINS	3,600.000	CYS
37	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
38	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
39	801-06204 TEMPORARY PAVEMENT MARKING, 5 IN.	13,000.000	LFT
40	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	13,000.000	LFT
41	801-06640 CONSTRUCTION SIGN, A	88.000	EACH
42	801-06710 FLASHING ARROW SIGN	150.000	DAY
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
45	805-05905 ATR STATION- 4 LANE	1.000	EACH
46	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	1,188.000	LFT
47	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	1,188.000	LFT
48	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	34,103.000	LFT

CALL ORDER : 324
LETTING DATE :

CONTRACT ID : R -28961-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	128,348.000	LFT
50 808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	8,723.000	LFT
51 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	984.000	LFT
52 808-06716	LINE, REMOVE	2,673.000	LFT
53 808-74811	LINE, EPOXY, BROKEN, WHITE, 5 IN.	297.000	LFT
54 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	128,348.000	LFT
55 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,032.000	EACH

CALL ORDER : 430
 LETTING DATE :

CONTRACT ID : RS-28413-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06899 RADIO	2.000	EACH
2	105-07040 FIELD OFFICE, C	7.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	7.000	MOS
5	105-08523 RADIO SERVICE	14.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02271 HEADWALL, REMOVE	8.000	EACH
12	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	1,000.000	TON
13	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
14	202-90277 DETECTOR HOUSING, REMOVE	21.000	EACH
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	13.000	EACH
16	203-02000 EXCAVATION, COMMON	1,250.000	CYS
17	203-91878 LINEAR DITCH GRADING	68.000	LFT
18	207-08268 SUBGRADE TREATMENT, TYPE IV	6,315.000	SYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,668.000	TON
20	303-01180 COMPACTED AGGREGATE, NO. 53	10,500.000	TON
21	304-07491 HMA PATCHING, TYPE C	1,500.000	TON
22	304-07494 WIDENING WITH HMA, TYPE C	3,891.000	TON
23	306-08033 MILLING, ASPHALT, 1 IN.	233,100.000	SYS
24	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,000.000	SYS
25	306-08043 MILLING, TRANSITION	2,240.000	SYS
26	306-08432 MILLING, APPROACH	19,700.000	SYS
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-09046 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm-PWL	6,126.000	TON
29	401-09047 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm-PWL	8,169.000	TON
30	401-09120 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm-PWL	14,325.000	TON
31	401-09126 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm-PWL	19,100.000	TON
32	402-07452 HMA, TYPE C, WEDGE AND LEVEL	85.000	TON
33	406-05520 ASPHALT FOR TACK COAT	15.000	TON
34	507-07479 HMA PARTIAL DEPTH PATCH	2,760.000	TON
35	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	4.000	EACH
36	601-92948 GUARDRAIL, ADJUST HEIGHT	2,650.000	LFT
37	601-94689 GUARDRAIL END TREATMENT, OS	9.000	EACH
38	610-07488 HMA FOR APPROACHES, TYPE C	11,249.000	TON
39	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	1.000	TON
40	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
41	612-60410 DRILLED HOLE FOR UNDERSEAL	22.000	EACH
42	615-06520 MONUMENT, RE-ESTABLISH	16.000	EACH
43	621-06575 SODDING, NURSERY	70.000	SYS
44	715-46000 PIPE END SECTION, 12 IN.	8.000	EACH
45	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
46	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	115,300.000	LFT
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	115,300.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	46.000	EACH

CALL ORDER : 430
 LETTING DATE :

CONTRACT ID : RS-28413-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
50	801-92448 CONSTRUCTION SIGNS, MOBILE	480.000	DAY
51	801-94295 SIGNAL HEAD, RELOCATE	4.000	EACH
52	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	15.000	SFT
53	805-01842 HANDHOLE, SIGNAL	9.000	EACH
54	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
55	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,540.000	LFT
56	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	9,505.000	LFT
57	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,030.000	LFT
58	805-78785 SIGNAL DETECTOR HOUSING	27.000	EACH
59	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	3,344.000	LFT
60	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
61	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.000	EACH
62	808-04723 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 4 IN.	144.000	LFT
63	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3,400.000	LFT
64	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	87,350.000	LFT
65	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6,800.000	LFT
66	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	33,000.000	LFT
67	808-75274 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	10,100.000	LFT
68	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	1,400.000	LFT
69	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	510.000	LFT
70	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	53.000	EACH
71	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	49.000	EACH
72	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,125.000	EACH
73	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,125.000	EACH

CALL ORDER : 470
 LETTING DATE :

CONTRACT ID : RS-29254-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02241 GUARDRAIL, REMOVE	410.000	LFT
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
13	203-02000 EXCAVATION, COMMON	745.000	CYS
14	205-03371 SEDIMENT, REMOVE	50.000	CYS
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	120.000	LFT
16	205-06937 TEMPORARY SILT FENCE	900.000	LFT
17	207-08263 SUBGRADE TREATMENT, TYPE IA	1,100.000	SYS
18	211-07454 STRUCTURE BACKFILL	5.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,130.000	TON
20	303-01180 COMPACTED AGGREGATE, NO. 53	600.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	2,720.000	TON
22	304-07489 HMA PATCHING, TYPE A	220.000	TON
23	304-07490 HMA PATCHING, TYPE B	4,200.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN.	157,850.000	SYS
25	306-08042 MILLING, SCARIFICATION/PROFILE	18,950.000	SYS
26	306-08043 MILLING, TRANSITION	1,540.000	SYS
27	306-08432 MILLING, APPROACH	8,800.000	SYS
28	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
29	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	13,100.000	TON
30	401-07338 QC/QA-HMA, 1, 64, SURFACE, 12.5 mm	3,200.000	TON
31	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	25,850.000	TON
32	402-07432 HMA SURFACE, TYPE A	100.000	TON
33	402-07440 HMA BASE, TYPE A	295.000	TON
34	402-07441 HMA BASE, TYPE B	640.000	TON
35	406-05520 ASPHALT FOR TACK COAT	90.000	TON
36	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
37	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
38	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	925.000	LFT
39	610-07486 HMA FOR APPROACHES, TYPE A	2,800.000	TON
40	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
41	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
42	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	155.000	TON
43	612-60410 DRILLED HOLE FOR UNDERSEAL	2,550.000	EACH
44	616-02320 GEOTEXTILES	20.000	SYS
45	616-06451 RIPRAP, UNIFORM	20.000	TON
46	715-05596 PIPE EXTENSION, CIRCULAR, 18 IN.	3.000	LFT
47	715-46010 PIPE END SECTION, 18 IN.	1.000	EACH
48	801-01506 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (RXR)	2.000	EACH

CALL ORDER : 470
 LETTING DATE :

CONTRACT ID : RS-29254-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	ASPHALT RESURFACE			
49	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	13,400.000	LFT
50	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,700.000	LFT
51	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (RXR)	1.000	EACH
52	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	135.000	LFT
53	801-06218	TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	80.000	LFT
54	801-06640	CONSTRUCTION SIGN, A	50.000	EACH
55	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
56	801-92448	CONSTRUCTION SIGNS, MOBILE	1,000.000	DAY
57	802-05704	SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	40.000	LFT
58	802-05705	SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	20.000	LFT
59	802-07060	SIGN, SHEET, RELOCATE	5.000	EACH
60	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
61	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	103,105.000	LFT
62	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	10,258.000	LFT
63	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	32,792.000	LFT
64	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	135.000	LFT
65	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
66	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	920.000	EACH
67	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	920.000	EACH

CALL ORDER : 520
LETTING DATE :

CONTRACT ID : B -28171-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1 105-07038	FIELD OFFICE, A	6.000	MOS
2 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3 619-05926	ENVIRONMENTAL CONTROL	LUMP	LUMP
4 619-05926	ENVIRONMENTAL CONTROL	LUMP	LUMP
5 619-51859	PAINT STEEL BRIDGE	LUMP	LUMP
6 619-51859	PAINT STEEL BRIDGE	LUMP	LUMP
7 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
8 619-61000	CLEAN STEEL BRIDGE	LUMP	LUMP
9 619-61000	CLEAN STEEL BRIDGE	LUMP	LUMP
10 709-51821	SURFACE SEAL	LUMP	LUMP
11 709-51821	SURFACE SEAL	LUMP	LUMP
12 801-06640	CONSTRUCTION SIGN, A	12.000	EACH
13 801-06710	FLASHING ARROW SIGN	60.000	DAY
14 801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 534
 LETTING DATE :

CONTRACT ID : B -28732-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
9	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
10	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
11	709-51821 SURFACE SEAL	LUMP	LUMP
12	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
13	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	45,000.000	LFT
14	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
15	801-06710 FLASHING ARROW SIGN	240.000	DAY
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 590
 LETTING DATE :

CONTRACT ID : M -29231-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK		
1	105-06904 PHONE(SUPERVISOR)	1.000	EACH
2	105-06906 CELLULAR SERVICE(SUPERVISOR)	12.000	MOS
3	105-07039 FIELD OFFICE, B	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02241 GUARDRAIL, REMOVE	12,000.000	LFT
9	202-93741 GUARD RAIL END TREATMENT, REMOVE	33.000	EACH
10	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
11	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
12	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	500.000	LFT
13	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
14	601-62540 GUARDRAIL POST, PLUMB	100.000	EACH
15	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	1.000	EACH
16	601-94645 GUARDRAIL END TREATMENT, SENTRE	1.000	EACH
17	601-94689 GUARDRAIL END TREATMENT, OS	20.000	EACH
18	601-94690 GUARDRAIL END TREATMENT, MS	10.000	EACH
19	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	12,000.000	LFT
20	601-99109 GUARDRAIL, W BEAM, DOUBLE FACED, 3 FT. 1.5 IN. SPACING	50.000	LFT
21	601-99123 GUARDRAIL TRANSITION, GP	1.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 600
 LETTING DATE :

CONTRACT ID : M -29232-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	105-06904 PHONE(SUPERVISOR)	1.000	EACH
2	105-06906 CELLULAR SERVICE(SUPERVISOR)	12.000	MOS
3	105-07038 FIELD OFFICE, A	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02241 GUARDRAIL, REMOVE	12,000.000	LFT
9	202-93741 GUARD RAIL END TREATMENT, REMOVE	20.000	EACH
10	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
11	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
12	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	500.000	LFT
13	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	3.000	EACH
14	601-62540 GUARDRAIL POST, PLUMB	100.000	EACH
15	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	1.000	EACH
16	601-94645 GUARDRAIL END TREATMENT, SENTRE	1.000	EACH
17	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
18	601-94690 GUARDRAIL END TREATMENT, MS	5.000	EACH
19	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	12,000.000	LFT
20	601-99109 GUARDRAIL, W BEAM, DOUBLE FACED, 3 FT. 1.5 IN. SPACING	50.000	LFT
21	601-99123 GUARDRAIL TRANSITION, GP	1.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 610
 LETTING DATE :

CONTRACT ID : M -29302-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT SMALL STRUCTURE PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
3	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
6	621-06559 MULCHED SEEDING, R	300.000	SYS
7	725-06859 PIPE LINER, THERMOPLASTIC, 48 IN.	65.000	LFT
8	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
9	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 650
 LETTING DATE :

CONTRACT ID : M -29328-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-07039 FIELD OFFICE, B	6.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-90277 DETECTOR HOUSING, REMOVE	1.000	EACH
7	305-03375 CRACKS, TRANSVERSE, ROUT, CLEAN, AND SEAL	2,652.000	LFT
8	305-93341 SAW, CLEAN AND SEAL LONGITUDINAL JOINTS	35,847.000	LFT
9	305-93342 SAW, CLEAN AND SEAL TRANSVERSE JOINTS	31,241.000	LFT
10	503-05240 D-1 CONTRACTION JOINT	385.500	LFT
11	506-06333 PCCP PATCHING, FULL DEPTH	1,436.000	SYS
12	720-44000 CASTING, ADJUST TO GRADE	14.000	EACH
13	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	5.000	LFT
14	720-45610 STRUCTURE, CATCH BASIN, RECONSTRUCT	5.000	LFT
15	720-45615 STRUCTURE, INLET, RECONSTRUCT	5.000	LFT
16	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
17	801-06710 FLASHING ARROW SIGN	60.000	DAY
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
20	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	230.000	LFT
21	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
22	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	72.000	LFT

SCHEDULE OF PAY ITEMS

CALL ORDER : 690
 LETTING DATE :

CONTRACT ID : M -29403-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 623-02344	MOWING, CYCLE NO. 1	LUMP	LUMP
2 623-02345	MOWING, CYCLE NO. 2	LUMP	LUMP
3 623-02346	MOWING, CYCLE NO. 3	LUMP	LUMP

CALL ORDER : 710
 LETTING DATE :

CONTRACT ID : M -29404-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 623-02344	MOWING, CYCLE NO. 1	LUMP	LUMP
2 623-02345	MOWING, CYCLE NO. 2	LUMP	LUMP
3 623-02346	MOWING, CYCLE NO. 3	LUMP	LUMP

CALL ORDER : 730
 LETTING DATE :

CONTRACT ID : M -29406-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 623-02344	MOWING, CYCLE NO. 1	LUMP	LUMP
2 623-02345	MOWING, CYCLE NO. 2	LUMP	LUMP
3 623-02346	MOWING, CYCLE NO. 3	LUMP	LUMP

CALL ORDER : 734
 LETTING DATE :

CONTRACT ID : T -28870-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	1.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
8	801-06640 CONSTRUCTION SIGN, A	84.000	EACH
9	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
10	805-01842 HANDHOLE, SIGNAL	51.000	EACH
11	805-01879 SIGNAL SERVICE, INSTALL	3.000	EACH
12	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
13	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	10,007.000	LFT
14	805-06595 CONDUIT, PVC, 2 IN.	45.000	LFT
15	805-06595 CONDUIT, PVC, 2 IN.	175.000	LFT
16	805-78467 SIGNAL CABLE, 3C 8GA.	210.000	LFT
17	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	23,732.000	LFT
18	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	25,453.000	LFT
19	805-78785 SIGNAL DETECTOR HOUSING	58.000	EACH
20	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	7,623.000	LFT
21	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
22	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	53.000	EACH
23	805-92512 MICROLOOP DETECTOR	2.000	EACH
24	807-04967 CABLE	900.000	LFT
25	807-05073 JUNCTION BOX	1.000	EACH
26	808-06716 LINE, REMOVE	380.000	LFT
27	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	398.000	LFT

CALL ORDER : 840
 LETTING DATE :

CONTRACT ID : T -29215-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	RAISED PAVEMENT MARKINGS, REFURBISHED		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	801-06710 FLASHING ARROW SIGN	160.000	DAY
8	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
9	801-92448 CONSTRUCTION SIGNS, MOBILE	160.000	DAY
10	808-75994 PRISMATIC REFLECTOR	5,300.000	EACH
11	808-75994 PRISMATIC REFLECTOR	28,421.000	EACH
12	808-75994 PRISMATIC REFLECTOR	3,500.000	EACH
13	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2,842.000	EACH

