

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-28200-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BR, COMP.CONT.PRES.CONC. BULB T- BEAM		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
12	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 11400	1.000	EACH
13	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 11400	1.000	EACH
14	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 11400	1.000	EACH
15	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 11400	1.000	EACH
16	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	8.000	EACH
17	203-02055 EMBANKMENT	1,481,565.000	m3
18	204-02290 SETTLEMENT PLATE	26.000	EACH
19	205-03371 SEDIMENT REMOVE	2,275.000	m3
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	4,550.000	Mg
21	205-06933 TEMPORARY DITCH INLET PROTECTION	51.000	EACH
22	205-06936 TEMPORARY SEDIMENT TRAP	3,678.000	Mg
23	205-06937 TEMPORARY SILT FENCE	2,832.000	m
24	207-08262 SUBGRADE TREATMENT, TYPE I	205,787.000	m2
25	207-08266 SUBGRADE TREATMENT, TYPE III	17,395.000	m2
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,105.000	m2
27	211-02050 B BORROW	32,647.000	m3
28	211-06467 AGGREGATE FOR END BENT BACKFILL	221.000	m3
29	211-07454 STRUCTURE BACKFILL	46,942.000	m3
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	46,970.000	Mg
31	302-06464 SUBBASE FOR PCCP	46,303.000	m3
32	302-07455 DENSE GRADED SUBBASE	122.600	m3
33	306-08043 MILLING, TRANSITION	749.000	m2
34	402-07432 HMA SURFACE, TYPE A	1,581.000	Mg
35	402-07435 HMA INTERMEDIATE, TYPE A	2,538.000	Mg
36	406-05520 ASPHALT FOR TACK COAT	5.000	Mg
37	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
38	501-06321 QC/QA-PCCP, 250 mm	30,807.000	m2
39	501-06322 QC/QA-PCCP, 275 mm	156,080.000	m2
40	503-05240 D-1 CONTRACTION JOINT	31,422.000	m
41	601-01128 GUARDRAIL TRANSITION TYPE WGB	16.000	EACH
42	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	2.000	EACH
43	601-94689 GUARDRAIL END TREATMENT, OS	10.000	EACH
44	601-94690 GUARDRAIL END TREATMENT, MS	8.000	EACH
45	601-95344 HANDRAIL, PEDESTRIAN	66.500	m
46	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	2.000	EACH
47	601-97803 GUARDRAIL END TREATMENT, MS, SPARE PARTS PACKAGE	2.000	EACH
48	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	633.000	m

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-28200-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BR, COMP.CONT.PRES.CONC. BULB T- BEAM		
49	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 1.905 m SPACING	473.000	m
50	602-06729 BARRIER DELINEATOR	40.000	EACH
51	603-06040 FENCE, FARM FIELD, 1190 mm	13,734.000	m
52	605-06095 CURB, INTEGRAL, B, CONCRETE	213.000	m
53	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	31,347.000	m
54	609-06258 REINFORCED CONCRETE BRIDGE APPROAH, 275 mm	500.800	m2
55	610-06258 REINFORCED CONCRETE BRIDGE APPROACH, 275 mm	318.000	m2
56	610-07486 HMA FOR APPROACHES, TYPE A	455.000	Mg
57	610-08446 PCCP FOR APPROACHES, 150 mm	58.000	m2
58	610-09108 PCCP FOR APPROACHES, 225 mm	250.000	m2
59	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
60	615-06490 RIGHT OF WAY MARKER	44.000	EACH
61	615-06505 MONUMENT, B	11.000	EACH
62	615-06510 MONUMENT, C	16.000	EACH
63	615-06515 MONUMENT, D	39.000	EACH
64	616-02320 GEOTEXTILES	24,545.500	m2
65	616-05688 RIPRAP, CLASS 1	1,994.000	Mg
66	616-05689 RIPRAP, CLASS 2	2,816.000	Mg
67	616-06405 RIPRAP, REVETMENT	9,680.000	Mg
68	616-06451 RIPRAP, UNIFORM	3,351.000	Mg
69	616-51367 SLOPEWALL, CONCRETE, 100 mm	982.000	m2
70	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
71	621-06545 FERTILIZER	94.000	Mg
72	621-06553 SEED MIXTURE, R	10,309.000	kg
73	621-06557 SEED MIXTURE, T	178.000	kg
74	621-06565 MULCHING MATERIAL	331.000	Mg
75	621-06567 WATER	785.000	kL
76	621-06574 SODDING	43,374.000	m2
77	622-52436 SIGN, DO NOT MOW OR SPRAY	30.000	EACH
78	622-91786 SEEDLING	10,900.000	EACH
79	701-51195 PILE, STEEL H, HP 310 X 79	1,215.600	m
80	701-91792 PILE TIP, STEEL H	104.000	EACH
81	702-04325 TEMPORARY SHORING	LUMP	LUMP
82	702-51005 CONCRETE, A, SUBSTRUCTURE	323.600	m3
83	702-51015 CONCRETE, B, FOOTINGS	79.400	m3
84	703-06029 REINFORCING BARS, EPOXY COATED	156,628.000	kg
85	704-51002 CONCRETE, C, SUPERSTRUCTURE	734.900	m3
86	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	16.000	EACH
87	706-51020 CONCRETE, C, RAILING	83.200	m3
88	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 1143 mm X 406 mm	261.600	m
89	707-06831 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM, 1372 mm x 1067 mm	640.000	m
90	709-51821 SURFACE SEAL	LUMP	LUMP
91	709-51821 SURFACE SEAL	LUMP	LUMP
92	709-51821 SURFACE SEAL	LUMP	LUMP
93	711-51070 ANCHOR PLATE, AP 1	40.000	EACH
94	714-04733 CULVERT, PRECAST, 3 SIDED, REINFORCED CONCRETE,	137.000	m
95	714-44240 CONCRETE, A, STRUCTURES	48.900	m3
96	715-05019 PIPE, TYPE 1, CIRCULAR, 900 mm	443.000	m

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-28200-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BR, COMP.CONT.PRES.CONC. BULB T- BEAM		
97	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	31,656.000	m
98	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	3,308.000	m
99	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	77.000	m
100	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	92.000	m
101	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	201.000	m
102	715-05128 PIPE, TYPE 1, CIRCULAR, 1200 mm	429.000	m
103	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	1,702.000	m
104	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	227.000	m
105	715-05153 PIPE, TYPE 2, CIRCULAR, 525 mm	163.000	m
106	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	144.000	m
107	715-05263 PIPE, TYPE 1, DEFORMED, MIN. AREA 2.73 m2	120.000	m
108	715-06004 CONCRETE ANCHOR, 1200 mm	6.000	EACH
109	715-06939 CONCRETE ANCHOR, MIN. AREA 2.73 m2	6.000	EACH
110	715-09219 PIPE EXTENSION, DEFORMED, MIN. AREA 8.0 m2	26.000	m
111	715-46005 PIPE END SECTION, 375 mm	52.000	EACH
112	715-46010 PIPE END SECTION, 450 mm	7.000	EACH
113	715-46015 PIPE END SECTION, 525 mm	1.000	EACH
114	715-46020 PIPE END SECTION, 600 mm	3.000	EACH
115	715-46040 PIPE END SECTION, 900 mm	8.000	EACH
116	718-06528 OUTLET PROTECTOR, 1	380.000	EACH
117	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	m
118	718-52610 AGGREGATE FOR UNDERDRAINS	5,967.000	m3
119	718-99153 GEOTEXTILES FOR UNDERDRAIN	67,665.000	m2
120	720-45030 INLET, E7	4.000	EACH
121	720-45045 INLET, J10	1.000	EACH
122	720-45065 INLET, N12	47.000	EACH
123	720-45250 CATCH BASIN, K10	3.000	EACH
124	720-94612 MANHOLE, K4	1.000	EACH
125	728-98377 MASONRY COATING	LUMP	LUMP
126	731-93945 FACE PANELS, CONCRETE	1,862.000	m2
127	731-93946 WALL ERECTION	1,862.000	m2
128	731-93947 LEVELING PAD, CONCRETE	273.000	m
129	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	3,556.000	m
130	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	7,647.000	m
131	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
132	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
133	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
134	801-07118 BARRICADE, III-A	36.000	m
135	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	240.000	m
136	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	87.000	m
137	802-05703 SIGN POST, SQUARE, 3, REINFORCED ANCHOR BASE	39.000	m
138	802-07057 SIGN, PANEL, WITH LEGEND	203.000	m2
139	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	8.000	EACH
140	802-07154 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	12.000	EACH
141	802-07158 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, I	2.000	EACH
142	802-08456 WIDE FLANGE SIGN POST SUPPORT	4.000	EACH
143	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	8.000	m2
144	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	44.000	m2

CALL ORDER : 131
 LETTING DATE :

CONTRACT ID : IR-28200-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BR, COMP.CONT.PRES.CONC. BULB T- BEAM		
145	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	13.000	m2
146	802-76095 STRUCTURAL STEEL, BREAKAWAY	3,712.000	kg
147	802-76140 OVERHEAD SIGN STRUCTURE, CANTILEVER DOUBLE ARM	2.000	EACH
148	802-76175 WALKWAY, HANDRAIL, AND LIGHTING SUPPORT ASSEMBLY	14.000	m
149	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	16,936.000	m
150	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	16,898.000	m
151	808-05534 LINE, EPOXY, SOLID, WHITE, 200 mm	830.000	m
152	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	2,199.000	m
153	808-06716 LINE, REMOVE	5,994.000	m
154	808-07591 LINE, EPOXY, SOLID, WHITE, 600 mm	97.000	m
155	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 600 mm	47.000	m
156	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	4.000	EACH
157	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	2.000	EACH
158	808-74811 LINE, EPOXY, BROKEN, WHITE, 125 mm	3,499.000	m
159	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	2,125.000	m
160	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	865.000	EACH
161	808-98000 LINE, EPOXY, SOLID, YELLOW, 200 mm	137.000	m

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	4.000	EACH
3	105-07040 FIELD OFFICE, C	19.000	MOS
4	105-08523 RADIO SERVICE	76.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	64.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	64.000	MOS
8	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
9	109-08359 LIQUIDATED DAMAGES	0.200	DOL
10	109-08360 CONTRACT LIENS	0.200	DOL
11	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
12	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
13	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
14	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
17	202-02240 PAVEMENT REMOVAL	74,545.000	SYS
18	202-02241 GUARDRAIL, REMOVE	10,174.000	LFT
19	202-02271 HEADWALL, REMOVE	1.000	EACH
20	202-02272 PAVED SIDE DITCH, REMOVE	4,225.000	LFT
21	202-02278 CURB, CONCRETE, REMOVE	1,420.000	LFT
22	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
23	202-51368 SLOPEWALL, REMOVE	550.000	SYS
24	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	7.000	EACH
25	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	56.000	EACH
26	202-74050 SIGN, OVERHEAD, REMOVE	3.000	EACH
27	202-74055 OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	3.000	EACH
28	202-74080 OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	6.000	EACH
29	202-91840 FENCE, CHAIN LINK, REMOVE	300.000	LFT
30	202-93741 GUARD RAIL END TREATMENT, REMOVE	13.000	EACH
31	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	62.000	EACH
32	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	61.000	LFT
33	202-95027 IMPACT ATTENUATOR, REMOVE	1.000	EACH
34	202-95579 SERVICE POINT, REMOVE	3.000	EACH
35	202-99187 FENCE, FARM FIELD, REMOVE	10,150.000	LFT
36	203-02000 EXCAVATION, COMMON	222,280.000	CYS
37	203-02070 BORROW	5,210.000	CYS
38	203-02100 EXCAVATION, PEAT	187.000	CYS
39	204-02290 SETTLEMENT PLATE	8.000	EACH
40	205-03371 SEDIMENT, REMOVE	1,421.000	CYS
41	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	663.000	TON
42	205-06933 TEMPORARY DITCH INLET PROTECTION	19.000	EACH
43	205-06936 TEMPORARY SEDIMENT TRAP	1,116.000	TON
44	205-06937 TEMPORARY SILT FENCE	9,907.000	LFT
45	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	195.000	CYS
46	206-93520 TEMPORARY SHEET PILING	6,000.000	SFT
47	207-08262 SUBGRADE TREATMENT, TYPE I	48,973.000	SYS
48	207-08263 SUBGRADE TREATMENT, TYPE IA	55,930.000	SYS

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	SIGN MODERNIZATION			
49	207-08267	SUBGRADE TREATMENT, TYPE IIIA	13,799.000	SYS
50	208-09232	REINFORCED STEEPENED SLOPE	1,820.000	SFT
51	210-08372	ROADWAY WEATHER INFORMATION SYSTEM	1.000	EACH
52	211-02050	B BORROW	38,420.000	CYS
53	211-06467	AGGREGATE FOR END BENT BACKFILL	402.600	CYS
54	211-07454	STRUCTURE BACKFILL	76,247.000	CYS
55	301-07448	COMPACTED AGGREGATE, NO. 53, BASE	85,187.000	TON
56	302-06464	SUBBASE FOR PCCP	26,224.000	CYS
57	302-07455	DENSE GRADED SUBBASE	278.000	CYS
58	303-01180	COMPACTED AGGREGATE, NO. 53	44.000	TON
59	306-08033	MILLING, ASPHALT, 1 IN.	5,407.000	SYS
60	306-08043	MILLING, TRANSITION	67.000	SYS
61	402-07432	HMA SURFACE, TYPE A	312.000	TON
62	402-07434	HMA SURFACE, TYPE C	1,253.000	TON
63	402-07435	HMA INTERMEDIATE, TYPE A	423.000	TON
64	402-07439	HMA INTERMEDIATE, TYPE C	1,353.000	TON
65	402-07440	HMA BASE, TYPE A	220.000	TON
66	402-07442	HMA BASE, TYPE C	6,162.000	TON
67	402-07453	HMA FOR TEMPORARY PAVEMENT	18.000	TON
68	406-05520	ASPHALT FOR TACK COAT	13.280	TON
69	501-06266	PROFILOGRAPH, PCCP	LUMP	LUMP
70	501-06323	QC/QA-PCCP, 12 IN.	43,569.000	SYS
71	501-06727	CORING, PCCP	LUMP	LUMP
72	501-08544	QC/QA-PCCP, 16 IN.	52,997.000	SYS
73	503-05240	D-1 CONTRACTION JOINT	53,610.000	LFT
74	503-05310	TERMINAL JOINT	909.000	LFT
75	601-01522	GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
76	601-06037	GUARDRAIL END TREATMENT, I	2.000	EACH
77	601-06238	IMPACT ATTENUATOR, R1, W1, TL-3	7.000	EACH
78	601-06246	IMPACT ATTENUATOR, R2, W1, TL-3	2.000	EACH
79	601-06247	IMPACT ATTENUATOR, R2, W2, TL-3	1.000	EACH
80	601-06421	IMPACT ATTENUATOR SPARE PARTS PACKAGE, R1, W1, TL-3	2.000	EACH
81	601-06454	IMPACT ATTENUATOR SPARE PARTS PACKAGE, R2, W1, TL-3	2.000	EACH
82	601-06455	IMPACT ATTENUATOR SPARE PARTS PACKAGE, R2, W2, TL-3	2.000	EACH
83	601-99105	GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,638.000	LFT
84	602-06729	BARRIER DELINEATOR	565.000	EACH
85	602-06944	BARRIER, CONCRETE, 33 IN.	2,426.000	LFT
86	602-06945	BARRIER, CONCRETE, 45 IN.	6,320.000	LFT
87	603-06045	FENCE, CHAIN LINK, 48 IN.	10,450.000	LFT
88	604-07903	CURB RAMP, CONCRETE, K	11.000	SYS
89	604-91531	SIDEWALK, CONCRETE, 4 IN.	1,230.000	SYS
90	605-06150	CURB AND GUTTER, C, CONCRETE	1,843.000	LFT
91	607-06370	PAVED SIDE DITCH, H	440.000	LFT
92	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	284.200	SYS
93	609-08229	REINFORCED CONCRETE BRIDGE APPROACH	1,383.800	SYS
94	615-06505	MONUMENT, B	2.000	EACH
95	615-06510	MONUMENT, C	11.000	EACH
96	615-06515	MONUMENT, D	50.000	EACH

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN MODERNIZATION			
97	616-02320 GEOTEXTILES	8,817.500	SYS
98	616-05688 RIPRAP, CLASS 1	1,546.000	TON
99	616-05689 RIPRAP, CLASS 2	275.000	TON
100	616-06405 RIPRAP, REVETMENT	3,973.000	TON
101	616-06451 RIPRAP, UNIFORM	775.000	TON
102	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
103	621-02770 EROSION CONTROL BLANKET	12,264.000	SYS
104	621-06545 FERTILIZER	13.900	TON
105	621-06554 SEED MIXTURE, U	5,134.000	LBS
106	621-06565 MULCHING MATERIAL	68.300	TON
107	621-06567 WATER	280.600	KGAL
108	621-06574 SODDING	7,639.000	SYS
109	621-06575 SODDING, NURSERY	1,552.000	SYS
110	701-01814 MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	2.000	EACH
111	701-02139 PILE, STEEL SHELL, 0.375 IN., 14 IN.	3,453.000	LFT
112	701-06011 DYNAMIC PILE LOAD TEST	5.000	EACH
113	701-06012 TEST PILE, RESTRIKE	5.000	EACH
114	701-06027 TEST PILE	5.000	EACH
115	701-95780 PILE, STEEL H, HP 12 X 74	4,894.000	LFT
116	702-51005 CONCRETE, A, SUBSTRUCTURE	216.200	CYS
117	702-51015 CONCRETE, B, FOOTINGS	302.700	CYS
118	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,160.000	EACH
119	702-90915 CONCRETE, A	535.000	CYS
120	703-01540 THREADED TIE BAR ASSEMBLY	75.000	EACH
121	703-06028 REINFORCING BARS	29,970.000	LBS
122	703-06029 REINFORCING BARS, EPOXY COATED	465,508.000	LBS
123	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	2,299.000	EACH
124	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,419.700	CYS
125	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN.	5,987.000	SYS
126	706-08504 REINFORCED CONCRETE MOMENT SLAB, 16 IN.	3,318.000	SYS
127	706-51020 CONCRETE, C, RAILING	168.100	CYS
128	706-51025 CONCRETE, C, RAILING	398.000	LFT
129	706-51025 CONCRETE, C, RAILING	6,089.000	LFT
130	707-08643 STRUCTURAL MEMBERS, CONCRETE BULB-T	1,854.900	LFT
131	709-51821 SURFACE SEAL	LUMP	LUMP
132	709-51821 SURFACE SEAL	LUMP	LUMP
133	709-51821 SURFACE SEAL	LUMP	LUMP
134	711-51038 STRUCTURAL STEEL	LUMP	LUMP
135	714-44240 CONCRETE, A, STRUCTURES	49.000	CYS
136	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	94.000	LFT
137	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	20,949.000	LFT
138	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	1,941.000	LFT
139	715-05122 PIPE, TYPE 1, CIRCULAR, 21 IN.	77.000	LFT
140	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	139.000	LFT
141	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	153.000	LFT
142	715-05127 PIPE, TYPE 1, CURCULAR, 42 IN.	145.000	LFT
143	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	194.000	LFT
144	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	3,856.000	LFT

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN MODERNIZATION			
145	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	752.000	LFT
146	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	356.000	LFT
147	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	313.000	LFT
148	715-05233 PIPE, TYPE 1, DEFORMED, 3.3 SQ. FT.	99.000	LFT
149	715-05422 PIPE, SLOTTED DRAIN, 12 IN.	1,504.000	LFT
150	715-05842 CONCRETE ANCHOR, 42 IN.	2.000	EACH
151	715-06004 CONCRETE ANCHOR, 48 IN.	4.000	EACH
152	715-06471 PIPE END SECTION, MIN. AREA 3.3 SQ. FT.	4.000	EACH
153	715-08069 CONCRETE ANCHOR, MIN. AREA 5.1 SQ. FT.	2.000	EACH
154	715-08447 PIPE, TYPE 1, DEFORMED, MIN. AREA 5.1 SQ. FT.	68.000	LFT
155	715-46000 PIPE END SECTION, 12 IN.	37.000	EACH
156	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
157	715-46010 PIPE END SECTION, 18 IN.	5.000	EACH
158	715-46015 PIPE END SECTION, 21 IN.	2.000	EACH
159	715-46020 PIPE END SECTION, 24 IN.	3.000	EACH
160	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
161	715-46035 PIPE END SECTION, 33 IN.	2.000	EACH
162	718-06529 OUTLET PROTECTOR, 2	63.000	EACH
163	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,281.000	LFT
164	718-52610 AGGREGATE FOR UNDERDRAINS	2,023.000	CYS
165	718-99153 GEOTEXTILES FOR UNDERDRAIN	18,560.000	SYS
166	720-07299 INLET TYPE H	15.000	EACH
167	720-07300 INLET TYPE H, WITH SLOTTED DRAIN	17.000	EACH
168	720-07301 INLET TYPE HA	22.000	EACH
169	720-07301 INLET TYPE HA	3.000	EACH
170	720-07302 INLET TYPE HA, WITH SLOTTED DRAIN	27.000	EACH
171	720-45030 INLET, E7	6.000	EACH
172	720-45410 MANHOLE, C4	4.000	EACH
173	720-90984 MANHOLE, C2	13.000	EACH
174	720-96422 INLET, A, MODIFIED	37.000	EACH
175	720-98174 INLET, B15	4.000	EACH
176	720-98555 INLET, C15	4.000	EACH
177	724-51925 STRUCTURAL EXPANSION JOINT, SS	102.500	LFT
178	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	10.000	EACH
179	728-98377 MASONRY COATING	LUMP	LUMP
180	728-98377 MASONRY COATING	LUMP	LUMP
181	728-98377 MASONRY COATING	LUMP	LUMP
182	731-93945 FACE PANELS, CONCRETE	118,804.000	SFT
183	731-93946 WALL ERECTION	118,804.000	SFT
184	731-93947 LEVELING PAD, CONCRETE	6,361.000	LFT
185	732-07653 COARSE AGGREGATE, NO. 8	3,987.000	TON
186	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.000	EACH
187	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
188	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
189	801-03291 CONSTRUCTION SIGN, D	2.000	EACH
190	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
191	801-06201 TEMPORARY PANEL SIGNS	2,366.000	SYS
192	801-06202 TEMPORARY PANEL SIGN SUPPORTS	840.000	LFT

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN MODERNIZATION			
193	801-06203	5,538.000	LFT
194	801-06207	46,900.000	LFT
195	801-06208	2,203.000	LFT
196	801-06212	2.000	EACH
197	801-06216	74.000	LFT
198	801-06218	24.000	LFT
199	801-06625	111.000	EACH
200	801-06640	63.000	EACH
201	801-06645	6.000	EACH
202	801-06710	300.000	DAY
203	801-06775	LUMP	LUMP
204	801-07023	4.000	EACH
205	801-07024	5.000	EACH
206	801-07118	336.000	LFT
207	801-07119	72.000	LFT
208	801-08401	16,696.000	LFT
209	801-08402	7,201.000	LFT
210	801-08508	2,098.000	LFT
211	801-08509	379.000	LFT
212	801-09133	3.000	EACH
213	802-04314	33.000	EACH
214	802-04893	20.000	EACH
215	802-05701	473.000	LFT
216	802-05702	570.000	LFT
217	802-07057	5,057.000	SFT
218	802-07101	12.000	EACH
219	802-07102	2.000	EACH
220	802-07151	10.000	EACH
221	802-07158	1.000	EACH
222	802-07268	1.000	EACH
223	802-09206	2.000	EACH
224	802-09207	2.000	EACH
225	802-09208	5.000	EACH
226	802-09209	2.000	EACH
227	802-09210	2.000	EACH
228	802-09211	8.000	EACH
229	802-09221	2.000	EACH
230	802-09222	1.000	EACH
231	802-09223	1.000	EACH
232	802-09224	4.000	EACH
233	802-09225	2.000	EACH
234	802-09226	1.000	EACH
235	802-76025	60.500	SFT
236	802-76035	959.000	SFT
237	802-76055	78.000	LFT
238	802-76095	1,547.000	LBS
239	802-76140	1.000	EACH
240	802-76160	2.000	EACH

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
241	802-76205 SIGN MODIFICATION (OVERHEAD)	1.000	EACH
242	802-76235 INSTALL OVERHEAD SIGN	2.000	EACH
243	802-93389 BARRIER WALL SIGN BRACKET, SHOULDER	2.000	EACH
244	802-94494 SIGN STRUCTURE, OVERHEAD, RELOCATE	2.000	EACH
245	804-06770 DELINEATOR POST	159.000	EACH
246	805-02971 ELECTRICAL SERVICE	LUMP	LUMP
247	805-04973 CONDUIT	9,267.000	LFT
248	805-04977 MICROLOOP	3.000	EACH
249	805-04977 MICROLOOP	4.000	EACH
250	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,226.000	LFT
251	805-06600 CONDUIT, PVC, 3 IN.	857.000	LFT
252	805-07074 ITS CONTROLLER CABINET	3.000	EACH
253	805-07075 ITS CABINET FOUNDATION	2.000	EACH
254	805-86820 CONCRETE FOUNDATION WITH GROUNDING, 30 IN. X 30 IN. X 96 IN.	8.000	EACH
255	805-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED COPPER	896.000	LFT
256	805-86920 MULTIPLE COMPRESSION FITTING, NOT WATERPROOFED	64.000	EACH
257	805-86955 CABLE DUCT MARKER	17.000	EACH
258	805-95209 TRUCK, TOW	60.000	DAY
259	805-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	17,950.000	LFT
260	805-98336 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN CONDUIT, 4 1/C	900.000	LFT
261	807-01122 LIGHT POLE, HIGH MAST, RELOCATE	6.000	EACH
262	807-02191 HANDHOLE, LIGHTING	10.000	EACH
263	807-02603 LIGHT STANDARD, RELOCATE	8.000	EACH
264	807-04309 PORTABLE TOWER LIGHTING DRIVE SYSTEM	1.000	EACH
265	807-82058 UNDERPASS CIRCUIT INSTALLATION, 8 LUMINAIRES	3.000	EACH
266	807-82400 LIGHT POLE, HIGH MAST, 125 FT. E.M.H.	3.000	EACH
267	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	54.000	EACH
268	807-86735 UNDERPASS LUMINAIRE PENDANT MOUNTED 150 WATT HIGH PRESSURE	24.000	EACH
269	807-86810 SERVICE POINT, II	3.000	EACH
270	807-86832 CONCRETE FOUNDATION WITH GROUNDING, HIGH MAST TOWER	9.000	EACH
271	807-86910 CONNECTOR KIT, UNFUSED	26.000	EACH
272	807-86915 CONNECTOR KIT, FUSED	41.000	EACH
273	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	20.000	EACH
274	807-86930 INSULATION LINK, NONWATERPROOFED	49.000	EACH
275	807-86935 INSULATION LINK, WATERPROOFED	40.000	EACH
276	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	40.000	EACH
277	808-03441 PAVEMENT MESSAGE MARKINGS, PAINT, WORD (BIKE)	4.000	EACH
278	808-03442 PAVEMENT MESSAGE MARKINGS, PAINT, BIKE SYMBOL	4.000	EACH
279	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	23,132.000	LFT
280	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	24,860.000	LFT
281	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	5,993.000	LFT
282	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	332.000	LFT
283	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	7,109.000	LFT
284	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,349.000	LFT
285	808-06716 LINE, REMOVE	49,020.000	LFT
286	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	20.000	LFT
287	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	2.000	EACH
288	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	1.000	EACH

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGN MODERNIZATION			
289	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	15,887.000	LFT
290	808-75001 LINE, PAINT, BROKEN, WHITE, 5 IN.	998.000	LFT
291	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	4,056.000	LFT
292	808-75056 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	196.000	LFT
293	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	494.000	EACH
SECTION NO. 0002 BRIDGE REPLACEMENT, CONCRETE ALTERNATE			
294	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
295	109-08359 LIQUIDATED DAMAGES	0.200	DOL
296	109-08360 CONTRACT LIENS	0.200	DOL
297	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
298	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
299	202-02240 PAVEMENT REMOVAL	51.000	SYS
300	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	50.000	LFT
301	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	221.000	CYS
302	207-08263 SUBGRADE TREATMENT, TYPE IA	72.000	SYS
303	211-06467 AGGREGATE FOR END BENT BACKFILL	96.000	CYS
304	211-07454 STRUCTURE BACKFILL	62.000	CYS
305	302-07455 DENSE GRADED SUBBASE	50.000	CYS
306	402-07434 HMA SURFACE, TYPE C	6.000	TON
307	402-07439 HMA INTERMEDIATE, TYPE C	11.000	TON
308	402-07442 HMA BASE, TYPE C	44.000	TON
309	602-06729 BARRIER DELINEATOR	25.000	EACH
310	609-06260 REINFORCED CONCRETE BRIDGE APPROACH, 13 IN.	299.200	SYS
311	616-02320 GEOTEXTILES	163.000	SYS
312	616-51367 SLOPEWALL, CONCRETE, 4 IN.	352.000	SYS
313	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
314	701-06012 TEST PILE, RESTRIKE	4.000	EACH
315	701-06027 TEST PILE	4.000	EACH
316	701-95780 PILE, STEEL H, HP 12 X 74	4,435.000	LFT
317	702-51005 CONCRETE, A, SUBSTRUCTURE	307.300	CYS
318	702-51015 CONCRETE, B, FOOTINGS	69.400	CYS
319	703-06028 REINFORCING BARS	30,893.000	LBS
320	703-06029 REINFORCING BARS, EPOXY COATED	162,554.000	LBS
321	704-51002 CONCRETE, C, SUPERSTRUCTURE	446.800	CYS
322	704-51002 CONCRETE, C, SUPERSTRUCTURE	5.200	CYS
323	706-51020 CONCRETE, C, RAILING	88.700	CYS
324	707-01065 POST-TENSIONING	LUMP	LUMP
325	707-09179 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,656.200	LFT
326	709-51821 SURFACE SEAL	LUMP	LUMP
327	715-05407 PIPE, END BENT DRAIN, 6 IN.	63.000	LFT
328	724-51925 STRUCTURAL EXPANSION JOINT, SS	106.000	LFT
329	728-98377 MASONRY COATING	LUMP	LUMP
SECTION NO. 0003 BRIDGE REPLACEMENT, STEEL ALTERNATE			
330	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 BRIDGE REPLACEMENT, STEEL ALTERNATE			
331	109-08359 LIQUIDATED DAMAGES	0.200	DOL
332	109-08360 CONTRACT LIENS	0.200	DOL
333	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
334	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
335	202-02240 PAVEMENT REMOVAL	51.000	SYS
336	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	50.000	LFT
337	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	221.000	CYS
338	207-08263 SUBGRADE TREATMENT, TYPE IA	74.000	SYS
339	211-06467 AGGREGATE FOR END BENT BACKFILL	100.000	CYS
340	211-07454 STRUCTURE BACKFILL	113.000	CYS
341	302-07455 DENSE GRADED SUBBASE	51.000	CYS
342	402-07434 HMA SURFACE, TYPE C	6.000	TON
343	402-07439 HMA INTERMEDIATE, TYPE C	11.000	TON
344	402-07442 HMA BASE, TYPE C	46.000	TON
345	602-06729 BARRIER DELINEATOR	26.000	EACH
346	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	300.000	SYS
347	616-02320 GEOTEXTILES	89.000	SYS
348	616-51367 SLOPEWALL, CONCRETE, 4 IN.	352.000	SYS
349	701-01814 MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	1.000	EACH
350	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
351	701-06012 TEST PILE, RESTRIKE	4.000	EACH
352	701-06027 TEST PILE	4.000	EACH
353	701-95780 PILE, STEEL H, HP 12 X 74	4,266.000	LFT
354	702-51005 CONCRETE, A, SUBSTRUCTURE	313.200	CYS
355	702-51015 CONCRETE, B, FOOTINGS	69.400	CYS
356	703-06028 REINFORCING BARS	29,317.000	LBS
357	703-06029 REINFORCING BARS, EPOXY COATED	181,857.000	LBS
358	704-51002 CONCRETE, C, SUPERSTRUCTURE	385.400	CYS
359	706-51020 CONCRETE, C, RAILING	89.300	CYS
360	709-51821 SURFACE SEAL	LUMP	LUMP
361	711-51038 STRUCTURAL STEEL	LUMP	LUMP
362	715-05407 PIPE, END BENT DRAIN, 6 IN.	63.000	LFT
363	724-51925 STRUCTURAL EXPANSION JOINT, SS	106.000	LFT
364	726-58789 BEARING ASSEMBLY, ELASTOMERIC, II	12.000	EACH
365	728-98377 MASONRY COATING	LUMP	LUMP
SECTION NO. 0004 BRIDGE REPLACEMENT, CONCRETE ALTERNATE			
366	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
367	109-08359 LIQUIDATED DAMAGES	0.200	DOL
368	109-08360 CONTRACT LIENS	0.200	DOL
369	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
370	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
371	202-02240 PAVEMENT REMOVAL	48.000	SYS
372	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	45.000	LFT
373	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	403.000	CYS
374	207-08263 SUBGRADE TREATMENT, TYPE IA	45.000	SYS
375	211-06467 AGGREGATE FOR END BENT BACKFILL	118.000	CYS

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 BRIDGE REPLACEMENT, CONCRETE ALTERNATE			
376	211-07454	233.600	CYS
377	302-07455	48.000	CYS
378	402-07434	4.000	TON
379	402-07439	7.000	TON
380	402-07442	28.000	TON
381	602-06729	42.000	EACH
382	609-06259	279.000	SYS
383	616-02320	175.000	SYS
384	701-01814	5.000	EACH
385	701-06011	5.000	EACH
386	701-06012	5.000	EACH
387	701-06027	5.000	EACH
388	701-95780	8,968.000	LFT
389	702-51005	336.700	CYS
390	702-51015	132.600	CYS
391	703-06028	61,469.000	LBS
392	703-06029	302,432.000	LBS
393	703-96512	120.000	EACH
394	704-51002	974.500	CYS
395	704-51002	23.100	CYS
396	706-51020	189.300	CYS
397	707-01065	LUMP	LUMP
398	707-09180	3,500.200	LFT
399	709-51821	LUMP	LUMP
400	713-51820	LUMP	LUMP
401	724-51925	99.000	LFT
402	728-98377	LUMP	LUMP
SECTION NO. 0005 BRIDGE REPLACEMENT, STEEL ALTERNATIVE			
403	105-06845	LUMP	LUMP
404	109-08359	0.200	DOL
405	109-08360	0.200	DOL
406	109-08463	0.200	DOL
407	110-01001	LUMP	LUMP
408	202-02240	38.000	SYS
409	202-94793	40.000	LFT
410	206-51230	349.000	CYS
411	207-08263	45.000	SYS
412	211-06467	127.000	CYS
413	211-07454	227.000	CYS
414	302-07455	48.000	CYS
415	402-07434	4.000	TON
416	402-07439	7.000	TON
417	402-07442	28.000	TON
418	602-06729	42.000	EACH
419	609-06259	279.000	SYS
420	616-02320	182.000	SYS

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 BRIDGE REPLACEMENT, STEEL ALTERNATIVE			
421	701-06011 DYNAMIC PILE LOAD TEST	5.000	EACH
422	701-06012 TEST PILE, RESTRIKE	5.000	EACH
423	701-06027 TEST PILE	5.000	EACH
424	701-93633 OVERSIZED PREDRILLED PILE HOLES	405.000	LFT
425	701-95780 PILE, STEEL H, HP 12 X 74	6,156.000	LFT
426	702-51005 CONCRETE, A, SUBSTRUCTURE	324.100	CYS
427	702-51015 CONCRETE, B, FOOTINGS	90.400	CYS
428	703-06028 REINFORCING BARS	40,392.000	LBS
429	703-06029 REINFORCING BARS, EPOXY COATED	425,534.000	LBS
430	704-51002 CONCRETE, C, SUPERSTRUCTURE	833.000	CYS
431	706-51020 CONCRETE, C, RAILING	189.300	CYS
432	709-51821 SURFACE SEAL	LUMP	LUMP
433	711-51038 STRUCTURAL STEEL	LUMP	LUMP
434	724-51925 STRUCTURAL EXPANSION JOINT, SS	99.000	LFT
435	726-58789 BEARING ASSEMBLY, ELASTOMERIC, II	16.000	EACH
436	728-98377 MASONRY COATING	LUMP	LUMP
SECTION NO. 0006 BRIDGE REPLACEMENT, CONCRETE ALTERNATE			
437	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
438	109-08359 LIQUIDATED DAMAGES	0.200	DOL
439	109-08360 CONTRACT LIENS	0.200	DOL
440	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
441	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
442	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	264.000	CYS
443	207-08263 SUBGRADE TREATMENT, TYPE IA	72.000	SYS
444	211-06467 AGGREGATE FOR END BENT BACKFILL	83.500	CYS
445	211-07454 STRUCTURE BACKFILL	62.100	CYS
446	302-07455 DENSE GRADED SUBBASE	47.000	CYS
447	402-07434 HMA SURFACE, TYPE C	6.000	TON
448	402-07439 HMA INTERMEDIATE, TYPE C	11.000	TON
449	402-07442 HMA BASE, TYPE C	44.000	TON
450	602-06729 BARRIER DELINEATOR	28.000	EACH
451	609-06260 REINFORCED CONCRETE BRIDGE APPROACH, 13 IN.	277.000	SYS
452	616-02320 GEOTEXTILES	215.000	SYS
453	616-06405 RIPRAP, REVETMENT	56.000	TON
454	616-51367 SLOPEWALL, CONCRETE, 4 IN.	711.000	SYS
455	621-06574 SODDING	32.000	SYS
456	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
457	701-06012 TEST PILE, RESTRIKE	4.000	EACH
458	701-06027 TEST PILE	4.000	EACH
459	701-95780 PILE, STEEL H, HP 12 X 74	4,585.000	LFT
460	702-51005 CONCRETE, A, SUBSTRUCTURE	263.200	CYS
461	702-51015 CONCRETE, B, FOOTINGS	69.400	CYS
462	703-06028 REINFORCING BARS	31,347.000	LBS
463	703-06029 REINFORCING BARS, EPOXY COATED	162,804.000	LBS
464	704-51002 CONCRETE, C, SUPERSTRUCTURE	434.900	CYS
465	704-51002 CONCRETE, C, SUPERSTRUCTURE	5.210	CYS

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006 BRIDGE REPLACEMENT, CONCRETE ALTERNATE			
466	706-51020 CONCRETE, C, RAILING	92.700	CYS
467	707-01065 POST-TENSIONING	LUMP	LUMP
468	707-09179 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,665.000	LFT
469	709-51821 SURFACE SEAL	LUMP	LUMP
470	715-05407 PIPE, END BENT DRAIN, 6 IN.	60.000	LFT
471	724-51925 STRUCTURAL EXPANSION JOINT, SS	98.000	LFT
472	728-98377 MASONRY COATING	LUMP	LUMP
SECTION NO. 0007 BRIDGE REPLACEMENT, STEEL ALTERNATE			
473	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
474	109-08359 LIQUIDATED DAMAGES	0.200	DOL
475	109-08360 CONTRACT LIENS	0.200	DOL
476	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
477	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
478	202-02240 PAVEMENT REMOVAL	21.000	SYS
479	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	35.000	LFT
480	203-02000 EXCAVATION, COMMON	463.000	CYS
481	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	224.000	CYS
482	207-08263 SUBGRADE TREATMENT, TYPE IA	72.000	SYS
483	211-06467 AGGREGATE FOR END BENT BACKFILL	87.000	CYS
484	211-07454 STRUCTURE BACKFILL	137.000	CYS
485	302-07455 DENSE GRADED SUBBASE	47.000	CYS
486	402-07434 HMA SURFACE, TYPE C	6.000	TON
487	402-07439 HMA INTERMEDIATE, TYPE C	106.000	TON
488	402-07442 HMA BASE, TYPE C	44.000	TON
489	602-06729 BARRIER DELINEATOR	28.000	EACH
490	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	277.000	SYS
491	616-02320 GEOTEXTILES	147.000	SYS
492	616-06405 RIPRAP, REVETMENT	56.000	TON
493	616-51367 SLOPEWALL, CONCRETE, 4 IN.	302.000	SYS
494	621-06574 SODDING	32.000	SYS
495	701-01814 MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	1.000	EACH
496	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
497	701-06012 TEST PILE, RESTRIKE	4.000	EACH
498	701-06027 TEST PILE	4.000	EACH
499	701-95780 PILE, STEEL H, HP 12 X 74	4,306.000	LFT
500	702-51005 CONCRETE, A, SUBSTRUCTURE	314.800	CYS
501	702-51015 CONCRETE, B, FOOTINGS	69.400	CYS
502	703-06028 REINFORCING BARS	31,404.000	LBS
503	703-06029 REINFORCING BARS, EPOXY COATED	204,690.000	LBS
504	704-51002 CONCRETE, C, SUPERSTRUCTURE	372.200	CYS
505	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	1.000	EACH
506	706-51020 CONCRETE, C, RAILING	94.000	CYS
507	709-51821 SURFACE SEAL	LUMP	LUMP
508	711-51038 STRUCTURAL STEEL	LUMP	LUMP
509	715-05407 PIPE, END BENT DRAIN, 6 IN.	60.000	LFT
510	724-51925 STRUCTURAL EXPANSION JOINT, SS	98.000	LFT

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0007 BRIDGE REPLACEMENT, STEEL ALTERNATE			
511	726-58789 BEARING ASSEMBLY, ELASTOMERIC, II	4.000	EACH
512	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	8.000	EACH
513	728-98377 MASONRY COATING	LUMP	LUMP
SECTION NO. 0008 BRIDGE REPLACEMENT, CONCRETE ALTERNATE			
514	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
515	109-08359 LIQUIDATED DAMAGES	0.200	DOL
516	109-08360 CONTRACT LIENS	0.200	DOL
517	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
518	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
519	202-02240 PAVEMENT REMOVAL	189.000	SYS
520	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
521	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	86.000	LFT
522	203-02000 EXCAVATION, COMMON	1,048.000	CYS
523	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,206.000	CYS
524	207-08263 SUBGRADE TREATMENT, TYPE IA	240.000	SYS
525	211-06467 AGGREGATE FOR END BENT BACKFILL	288.000	CYS
526	211-07454 STRUCTURE BACKFILL	462.800	CYS
527	302-07455 DENSE GRADED SUBBASE	198.000	CYS
528	402-07434 HMA SURFACE, TYPE C	20.000	TON
529	402-07439 HMA INTERMEDIATE, TYPE C	33.000	TON
530	402-07442 HMA BASE, TYPE C	146.000	TON
531	602-06729 BARRIER DELINEATOR	51.000	EACH
532	609-08579 REINFORCED CONCRETE BRIDGE APPROACH, 16 IN.	1,178.000	SYS
533	616-02320 GEOTEXTILES	231.800	SYS
534	616-51367 SLOPEWALL, CONCRETE, 4 IN.	929.000	SYS
535	701-01814 MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	1.000	EACH
536	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
537	701-06012 TEST PILE, RESTRIKE	4.000	EACH
538	701-06027 TEST PILE	4.000	EACH
539	701-95780 PILE, STEEL H, HP 12 X 74	15,030.000	LFT
540	702-51005 CONCRETE, A, SUBSTRUCTURE	1,118.500	CYS
541	702-51015 CONCRETE, B, FOOTINGS	208.000	CYS
542	703-06028 REINFORCING BARS	126,414.000	LBS
543	703-06029 REINFORCING BARS, EPOXY COATED	430,008.000	LBS
544	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,452.000	CYS
545	704-51002 CONCRETE, C, SUPERSTRUCTURE	16.900	CYS
546	706-51020 CONCRETE, C, RAILING	184.800	CYS
547	707-01065 POST-TENSIONING	LUMP	LUMP
548	707-09179 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	5,425.900	LFT
549	709-51821 SURFACE SEAL	LUMP	LUMP
550	715-05407 PIPE, END BENT DRAIN, 6 IN.	170.000	LFT
551	724-51925 STRUCTURAL EXPANSION JOINT, SS	338.000	LFT
552	728-98377 MASONRY COATING	LUMP	LUMP
SECTION NO. 0009 BRIDGE REPLACEMENT, STEEL ALTERNATE			

CALL ORDER : 141
 LETTING DATE :

CONTRACT ID : IR-28982-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0009 BRIDGE REPLACEMENT, STEEL ALTERNATE			
553	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
554	109-08359 LIQUIDATED DAMAGES	0.200	DOL
555	109-08360 CONTRACT LIENS	0.200	DOL
556	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.200	DOL
557	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
558	202-02240 PAVEMENT REMOVAL	189.000	SYS
559	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
560	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	86.000	LFT
561	203-02000 EXCAVATION, COMMON	1,048.000	CYS
562	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,088.000	CYS
563	207-08263 SUBGRADE TREATMENT, TYPE IA	240.000	SYS
564	211-06467 AGGREGATE FOR END BENT BACKFILL	313.000	CYS
565	211-07454 STRUCTURE BACKFILL	406.000	CYS
566	302-07455 DENSE GRADED SUBBASE	198.000	CYS
567	402-07434 HMA SURFACE, TYPE C	20.000	TON
568	402-07439 HMA INTERMEDIATE, TYPE C	33.000	TON
569	402-07442 HMA BASE, TYPE C	146.000	TON
570	602-06729 BARRIER DELINEATOR	51.000	EACH
571	609-08579 REINFORCED CONCRETE BRIDGE APPROACH, 16 IN.	1,178.000	SYS
572	616-02320 GEOTEXTILES	266.000	SYS
573	616-51367 SLOPEWALL, CONCRETE, 4 IN.	940.000	SYS
574	701-01814 MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	1.000	EACH
575	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
576	701-06012 TEST PILE, RESTRIKE	4.000	EACH
577	701-06027 TEST PILE	4.000	EACH
578	701-95780 PILE, STEEL H, HP 12 X 74	10,266.000	LFT
579	702-51005 CONCRETE, A, SUBSTRUCTURE	1,142.500	CYS
580	702-51015 CONCRETE, B, FOOTINGS	160.000	CYS
581	703-06028 REINFORCING BARS	107,841.000	LBS
582	703-06029 REINFORCING BARS, EPOXY COATED	657,008.000	LBS
583	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,240.200	CYS
584	706-51020 CONCRETE, C, RAILING	185.300	CYS
585	709-51821 SURFACE SEAL	LUMP	LUMP
586	711-51038 STRUCTURAL STEEL	LUMP	LUMP
587	715-05407 PIPE, END BENT DRAIN, 6 IN.	167.000	LFT
588	724-51925 STRUCTURAL EXPANSION JOINT, SS	334.000	LFT
589	726-58789 BEARING ASSEMBLY, ELASTOMERIC, II	30.000	EACH
590	728-98377 MASONRY COATING	LUMP	LUMP

CALL ORDER : 171
 LETTING DATE :

CONTRACT ID : R -27713-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BEAUTIFICATION/WILDFLOWERS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	621-06545 FERTILIZER	11.900	TON
8	622-03761 SEED MIXTURE NO. 1	286.000	LBS
9	622-03762 SEED MIXTURE NO. 2	92.000	LBS
10	622-52436 SIGN, DO NOT MOW OR SPRAY	32.000	EACH
11	624-92647 HERBICIDE TREATMENT	47.400	ACRE
12	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 181
 LETTING DATE :

CONTRACT ID : R -27714-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BEAUTIFICATION/WILDFLOWERS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	621-06545 FERTILIZER	8.600	TON
8	622-03761 SEED MIXTURE NO. 1	18.000	LBS
9	622-03762 SEED MIXTURE NO. 2	22.500	LBS
10	622-52436 SIGN, DO NOT MOW OR SPRAY	15.000	EACH
11	624-92647 HERBICIDE TREATMENT	24.300	ACRE
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 191
 LETTING DATE :

CONTRACT ID : R -27967-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-07039 FIELD OFFICE, B	18.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
6	105-08523 RADIO SERVICE	36.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	18.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	18.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
13	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
14	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
17	202-02241 GUARDRAIL, REMOVE	7,141.000	LFT
18	202-02272 PAVED SIDE DITCH, REMOVE	10,937.000	LFT
19	202-74035 SIGN, REMOVE	6.000	EACH
20	203-02000 EXCAVATION, COMMON	25,500.000	CYS
21	205-06932 TEMPORARY CHECK DAM, STRAW BALES	1,880.000	LFT
22	205-06936 TEMPORARY SEDIMENT TRAP	372.000	TON
23	205-06937 TEMPORARY SILT FENCE	37,284.000	LFT
24	207-08263 SUBGRADE TREATMENT, TYPE IA	40,722.000	SYS
25	211-07454 STRUCTURE BACKFILL	169.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	16,187.000	TON
27	304-07491 HMA PATCHING, TYPE C	2,888.000	TON
28	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,627.000	SYS
29	306-08042 MILLING, SCARIFICATION/PROFILE	118,468.000	SYS
30	306-08043 MILLING, TRANSITION	2,368.000	SYS
31	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	915.000	TON
32	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9,424.000	TON
33	401-07379 QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	12,674.000	TON
34	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	2,760.000	TON
35	406-05521 ASPHALT FOR TACK COAT	248,650.000	SYS
36	601-01128 GUARDRAIL TRANSITION TYPE WGB	8.000	EACH
37	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
38	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	2.000	EACH
39	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	2.000	EACH
40	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	2.000	EACH
41	601-06854 GUARDRAIL, W-BEAM, NESTED	4.000	EACH
42	601-94689 GUARDRAIL END TREATMENT, OS	24.000	EACH
43	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	7,562.000	LFT
44	610-07486 HMA FOR APPROACHES, TYPE A	1,064.000	TON
45	611-02825 MAILBOX ASSEMBLY, TRIPLE	1.000	EACH
46	611-06497 MAILBOX ASSEMBLY, SINGLE	17.000	EACH
47	616-02320 GEOTEXTILES	11,013.000	SYS
48	616-06405 RIPRAP, REVETMENT	3,739.000	TON

CALL ORDER : 191
 LETTING DATE :

CONTRACT ID : R -27967-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	616-06451 RIPRAP, UNIFORM	2,059.000	TON
50	621-06553 SEED MIXTURE, R	9,063.000	LBS
51	621-06567 WATER	74.000	KGAL
52	621-06570 TOP SOIL	333.000	CYS
53	621-06574 SODDING	6,709.000	SYS
54	621-06575 SODDING, NURSERY	11,630.000	SYS
55	702-90915 CONCRETE, A	11.000	CYS
56	706-91957 BRIDGE RAILING, THRIE BEAM	50.000	LFT
57	708-95370 JOINT REPAIR	1,620.000	LFT
58	714-99346 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3 FT. X 2 FT.	54.000	LFT
59	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	12.000	EACH
60	715-03476 SAFETY METAL END SECTION, 4:1, 24 IN.	1.000	EACH
61	715-04611 SAFETY METAL END SECTION, 4:1, 12 IN.	1.000	EACH
62	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	100.000	LFT
63	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	100.000	LFT
64	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	6.000	LFT
65	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	4.000	LFT
66	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	6.000	LFT
67	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	94.000	LFT
68	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	478.000	LFT
69	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	217.000	LFT
70	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN.	100.000	LFT
71	715-46000 PIPE END SECTION, 12 IN.	2.000	EACH
72	715-46005 PIPE END SECTION, 15 IN.	25.000	EACH
73	715-46010 PIPE END SECTION, 18 IN.	2.000	EACH
74	715-46015 PIPE END SECTION, 21 IN.	1.000	EACH
75	715-46020 PIPE END SECTION, 24 IN.	21.000	EACH
76	720-44296 CAP INLET	22.000	EACH
77	730-04830 GRATED BOX END SECTION	1.000	EACH
78	730-04830 GRATED BOX END SECTION	2.000	EACH
79	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
80	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	31,200.000	LFT
81	801-06206 TEMPORARY PAVEMENT MARKING, 6 IN.	3,928.000	LFT
82	801-06640 CONSTRUCTION SIGN, A	39.000	EACH
83	801-06645 CONSTRUCTION SIGN, B	47.000	EACH
84	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
85	802-04893 REFERENCE POST	10.000	EACH
86	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	796.000	LFT
87	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	118.000	LFT
88	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	65.000	EACH
89	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.000	SFT
90	804-76350 DELINEATOR WITH POST, D3, 3 IN. DIA.	10.000	EACH
91	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	74,269.000	LFT
92	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	33,206.000	LFT
93	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	6,329.000	LFT
94	808-06716 LINE, REMOVE	3,036.000	LFT
95	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	462.000	LFT
96	808-74809 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (R X R)	1.000	EACH

CALL ORDER : 191
 LETTING DATE :

CONTRACT ID : R -27967-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
97 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	827.000	EACH

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -28934-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	12.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	36.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	102.000	m2
15	202-02241 GUARDRAIL, REMOVE	158.000	m
16	202-02272 PAVED SIDE DITCH, REMOVE	40.000	m
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	203-02000 EXCAVATION, COMMON	52,002.000	m3
19	203-02070 BORROW	5,061.000	m3
20	203-51223 EXCAVATION, WATERWAY	58.000	m3
21	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,460.000	Mg
22	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
23	205-06937 TEMPORARY SILT FENCE	8,617.000	m
24	207-08262 SUBGRADE TREATMENT, TYPE I	166,479.000	m2
25	211-07454 STRUCTURE BACKFILL	3,782.500	m3
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	67,131.000	Mg
27	302-07455 DENSE GRADED SUBBASE	26.000	m3
28	303-07449 COMPACTED AGGREGATE, NO. 73	277.000	Mg
29	303-60012 AGGREGATE, 2	534.000	Mg
30	306-08033 MILLING, ASPHALT, 25 mm	142,186.000	m2
31	306-08043 MILLING, TRANSITION	3,238.500	m2
32	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
33	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	8,016.000	Mg
34	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	17,346.000	Mg
35	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	29,138.000	Mg
36	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	24,449.000	Mg
37	401-93793 WEDGE AND LEVELING	27,126.000	Mg
38	402-07442 HMA BASE, TYPE C	27,125.500	Mg
39	406-05520 ASPHALT FOR TACK COAT	136.000	Mg
40	601-01522 GUARDRAIL TRANSITION TYPE TGB	8.000	EACH
41	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	6.000	EACH
42	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	2.000	EACH
43	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	2.000	EACH
44	601-06854 GUARDRAIL, W-BEAM, NESTED	7.000	EACH
45	601-94689 GUARDRAIL END TREATMENT, OS	22.000	EACH
46	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
47	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	818.500	m
48	602-06729 BARRIER DELINEATOR	6.000	EACH

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -28934-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
49	603-06040 FENCE, FARM FIELD, 1190 mm	455.000	m
50	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	174.000	m2
51	610-07486 HMA FOR APPROACHES, TYPE A	3,730.000	Mg
52	611-06497 MAILBOX ASSEMBLY, SINGLE	42.000	EACH
53	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
54	615-06500 MONUMENT, A	39.000	EACH
55	615-06505 MONUMENT, B	25.000	EACH
56	615-06510 MONUMENT, C	1.000	EACH
57	616-02320 GEOTEXTILES	216.000	m2
58	616-05688 RIPRAP, CLASS 1	281.000	Mg
59	616-05689 RIPRAP, CLASS 2	128.000	Mg
60	616-06405 RIPRAP, REVETMENT	978.000	Mg
61	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
62	621-06545 FERTILIZER	34.200	Mg
63	621-06553 SEED MIXTURE, R	7,220.000	kg
64	621-06565 MULCHING MATERIAL	171.000	Mg
65	621-06574 SODDING	4,670.000	m2
66	702-51863 FIELD DRILLED HOLE IN CONCRETE	72.000	EACH
67	702-90915 CONCRETE, A	69.000	m3
68	703-51030 REINFORCING STEEL	2,156.000	kg
69	703-51032 REINFORCING STEEL, EPOXY COATED	6,970.000	kg
70	704-51002 CONCRETE, C, SUPERSTRUCTURE	11.600	m3
71	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
72	706-51020 CONCRETE, C, RAILING	5.200	m3
73	709-51821 SURFACE SEAL	LUMP	LUMP
74	710-51870 REPOINTING MASONRY IN STRUCTURES	4.000	m2
75	714-01366 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 3000 mm x 1200 mm	65.000	m
76	714-07032 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4800 mm X 2100 mm	25.500	m
77	714-07892 CULVERT, PRECAST BOX, REINFORCED CONCRETE,	38.000	m
78	714-26702 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 1800 mm x 900 mm	23.000	m
79	714-26708 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 2400 mm x 1200 mm	46.500	m
80	715-03475 SAFETY METAL END SECTION, 4:1, 375 mm	44.000	EACH
81	715-03476 SAFETY METAL END SECTION, 4:1, 600 mm	30.000	EACH
82	715-03584 SAFETY METAL END SECTION, 4:1, 450 mm	8.000	EACH
83	715-04618 SAFETY METAL END SECTION, 6:1, 750 mm	2.000	EACH
84	715-05119 PIPE, TYPE 1, CIRCULAR, 375 mm	67.000	m
85	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	233.000	m
86	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	289.000	m
87	715-05125 PIPE, TYPE 1, CIRCULAR, 750 mm	33.000	m
88	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	138.000	m
89	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	715.000	m
90	715-05171 PIPE, TYPE 3, CIRCULAR, 450 mm	120.600	m
91	715-05173 PIPE, TYPE 3, CIRCULAR, 600 mm	245.000	m
92	715-05233 PIPE, TYPE 1, DEFORMED, MIN. AREA 0.31 m2	73.700	m
93	715-05234 PIPE, TYPE 1, DEFORMED, MIN. AREA 0.38 m2	189.500	m
94	715-05237 PIPE, TYPE 1, DEFORMED, MIN. AREA 0.59 m2	22.500	m
95	715-06471 PIPE END SECTION, MIN. AREA .31 m2	30.000	EACH
96	715-07029 SAFETY METAL END SECTION, 4:1, MIN. AREA 0.31 m2	10.000	EACH

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -28934-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
97	715-07072 SAFETY METAL END SECTION, 4:1, MIN. AREA 0.38 m2	20.000	EACH
98	715-46005 PIPE END SECTION, 375 mm	54.000	EACH
99	715-46010 PIPE END SECTION, 450 mm	14.000	EACH
100	715-46020 PIPE END SECTION, 600 mm	8.000	EACH
101	715-46055 PIPE END SECTION, MIN. AREA .17 m2	10.000	EACH
102	715-46060 PIPE END SECTION, MIN. AREA .21 m2	2.000	EACH
103	715-46095 PIPE END SECTION, MIN. AREA .60 m2	2.000	EACH
104	720-45030 INLET, E7	1.000	EACH
105	720-45035 INLET, F7	1.000	EACH
106	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	3.000	m2
107	722-51842 BRIDGE DECK OVERLAY	125.000	m2
108	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	1.000	m3
109	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	10.000	m2
110	722-60824 SURFACE MILLING	94.000	m2
111	724-03276 EXPANSION JOINT SEALING SYSTEM	28.400	m
112	732-07653 COARSE AGGREGATE, NO. 8	534.000	Mg
113	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
114	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
115	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
116	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
117	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
118	801-07119 BARRICADE, III-B	30.000	m
119	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	430.300	m
120	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	175.700	m
121	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	23.970	m2
122	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	89.100	m2
123	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	12.600	m2
124	805-01842 HANDHOLE, SIGNAL	10.000	EACH
125	805-06592 CONDUIT, STEEL, GALVANIZED, 50mm	425.000	m
126	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
127	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	1.000	EACH
128	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	10.000	EACH
129	805-78420 DISCONNECT HANGER	8.000	EACH
130	805-78467 SIGNAL CABLE, 3C 8GA.	20.000	m
131	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	100.000	m
132	805-78480 SIGNAL CABLE, 3C 14GA.	25.000	m
133	805-78485 SIGNAL CABLE, 5C 14GA.	70.000	m
134	805-78490 SIGNAL CABLE, 7C 14GA.	120.000	m
135	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	355.000	m
136	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	48.000	m
137	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
138	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	127.000	EACH
139	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	129.000	EACH
140	808-06694 LINE, PAINT, SOLID, YELLOW, 200 mm	1,612.000	m
141	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	7,441.000	m
142	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	42,205.000	m
143	808-75060 TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	408.000	m
144	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	4,125.000	m

CALL ORDER : 201
 LETTING DATE :

CONTRACT ID : R -28934-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
145 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	14,263.000	m
146 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	483.000	m
147 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	861.000	EACH

CALL ORDER : 211
 LETTING DATE :

CONTRACT ID : R -28949-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVERLAY, PREVENTIVE MAINTENENCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	10.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	4.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	40.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	30.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	30.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	303-52308 COMPACTED AGGREGATE, O, 53	400.000	TON
15	304-07783 HMA PATCHING, TYPE D	1,320.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	440,629.000	SYS
17	306-08043 MILLING, TRANSITION	8,000.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	7,875.000	TON
20	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	28,477.000	TON
21	402-07787 HMA WEDGE AND LEVEL, TYPE D	300.000	TON
22	406-05520 ASPHALT FOR TACK COAT	121.000	TON
23	506-06333 PCCP PATCHING, FULL DEPTH	1,500.000	SYS
24	507-07480 PCCP PROFILING	9,943.000	SYS
25	605-05523 CURB, HMA	200.000	LFT
26	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
27	720-96995 CLEAN INLET	90.000	EACH
28	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
29	801-03290 CONSTRUCTION SIGN, C	16.000	EACH
30	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	22,000.000	LFT
31	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	22,000.000	LFT
32	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
33	801-06710 FLASHING ARROW SIGN	400.000	DAY
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	8.000	EACH
36	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	7,581.000	LFT
37	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	7,581.000	LFT
38	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	265.000	LFT
39	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	60.000	LFT
40	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	28,837.000	LFT
41	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	62,344.000	LFT
42	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	7,678.000	LFT
43	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	3,935.000	LFT
44	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	62,519.000	LFT
45	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	890.000	LFT
46	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,108.000	EACH
47	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2,108.000	EACH

CALL ORDER : 221
 LETTING DATE :

CONTRACT ID : R -28957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	CONCRETE PAVEMENT RESTORATION		
1	105-07039 FIELD OFFICE, B	12.000	MOS
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
6	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	1,270.000	SYS
13	203-02000 EXCAVATION, COMMON	915.000	CYS
14	205-02224 TEMPORARY EROSION AND SEDIMENT CONTROL, PERIMETER PROTECTION	1,600.000	LFT
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	235.000	LFT
16	210-07243 PATCH	800.000	EACH
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,335.000	TON
18	302-07455 DENSE GRADED SUBBASE	175.000	CYS
19	303-01180 COMPACTED AGGREGATE, NO. 53	1,311.000	TON
20	306-08039 MILLING, ASPHALT REMOVAL	275.000	SYS
21	306-08043 MILLING, TRANSITION	2,660.000	SYS
22	402-07453 HMA FOR TEMPORARY PAVEMENT	1,115.000	TON
23	402-07787 HMA WEDGE AND LEVEL, TYPE D	245.000	TON
24	406-05520 ASPHALT FOR TACK COAT	3.100	TON
25	503-05240 D-1 CONTRACTION JOINT	8,880.000	LFT
26	503-05310 TERMINAL JOINT	1,225.000	LFT
27	506-06333 PCCP PATCHING, FULL DEPTH	26,580.000	SYS
28	507-07480 PCCP PROFILING	26,850.000	SYS
29	507-07481 CRACKS AND JOINTS IN PCCP, SEAL	1,325.000	LFT
30	507-07482 CRACKS AND JOINTS IN PCCP, ROUT AND SEAL	105,200.000	LFT
31	609-06258 REINFORCED CONCRETE BRIDGE APPROACH, 11 IN.	1,270.000	SYS
32	621-06559 MULCHED SEEDING, R	1,636.000	SYS
33	621-06626 MULCHED SEEDING, D	2,683.000	SYS
34	703-06029 REINFORCING BARS, EPOXY COATED	51,000.000	LBS
35	710-09158 PATCHING CONCRETE STRUCTURES	42.000	SFT
36	720-04499 INLET, RECONSTRUCT	100.000	EACH
37	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	45.000	SFT
38	724-51925 STRUCTURAL EXPANSION JOINT, SS	12.000	LFT
39	724-51925 STRUCTURAL EXPANSION JOINT, SS	47.000	LFT
40	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
41	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
42	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	28,200.000	LFT
43	801-06640 CONSTRUCTION SIGN, A	74.000	EACH
44	801-06710 FLASHING ARROW SIGN	1,000.000	DAY
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
47	801-92448 CONSTRUCTION SIGNS, MOBILE	2,000.000	DAY
48	808-06368 TRANSVERSE MARKING, REMOVE	300.000	LFT

CALL ORDER : 221
LETTING DATE :

CONTRACT ID : R -28957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	CONCRETE PAVEMENT RESTORATION		
49 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	15,900.000	LFT
50 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5,900.000	LFT
51 808-06716	LINE, REMOVE	4,100.000	LFT
52 808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	3,400.000	LFT
53 808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	2,700.000	LFT
54 808-75072	TRANSVERSE MARKINGS, PAINT, SOLID, WHITE, CROSSHATCH LINE,	600.000	LFT

CALL ORDER : 231
 LETTING DATE :

CONTRACT ID : R -29213-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BEAUTIFICATION AND WILDFLOWER		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	621-06545 FERTILIZER	3.100	TON
8	622-03761 SEED MIXTURE NO. 1	167.200	LBS
9	622-52436 SIGN, DO NOT MOW OR SPRAY	32.000	EACH
10	624-92647 HERBICIDE TREATMENT	15.400	ACRE
11	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 241
 LETTING DATE :

CONTRACT ID : R -29240-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BEAUTIFICATION/WILDFLOWERS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	621-03424 WILDFLOWERS	0.130	ACRE
8	621-06545 FERTILIZER	1.480	TON
9	622-03761 SEED MIXTURE NO. 1	160.600	LBS
10	622-03762 SEED MIXTURE NO. 2	86.000	LBS
11	622-52436 SIGN, DO NOT MOW OR SPRAY	32.000	EACH
12	624-92647 HERBICIDE TREATMENT	15.400	ACRE
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 245
 LETTING DATE :

CONTRACT ID : R -29339-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	REASSEMBLE EXISTING TRUSS BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-04681 RESET BRICK SIDEWALK AND PAVEMENT	27.000	SYS
9	203-02000 EXCAVATION, COMMON	136.000	CYS
10	203-02070 BORROW	734.000	CYS
11	205-06937 TEMPORARY SILT FENCE	290.000	LFT
12	206-51220 EXCAVATION, WET	100.000	CYS
13	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	36.000	CYS
14	210-06389 LIMESTONE	27.200	TON
15	211-06467 AGGREGATE FOR END BENT BACKFILL	45.600	CYS
16	211-07454 STRUCTURE BACKFILL	23.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	149.000	TON
18	402-07432 HMA SURFACE, TYPE A	14.500	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	30.400	TON
20	601-03667 RAILING, ORNAMENTAL	444.800	LFT
21	601-03871 RAILING, WOOD, END TREATMENT	4.000	EACH
22	610-07712 PCCP FOR APPROACHES, 6 IN.	70.000	SYS
23	611-03671 TRASH RECEPTACLE	2.000	EACH
24	616-02320 GEOTEXTILES	415.000	SYS
25	616-05688 RIPRAP, CLASS 1	195.000	TON
26	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
27	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
28	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
29	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
30	621-01852 MULCHED SEEDING, GRASS, 2	660.000	SYS
31	621-02770 EROSION CONTROL BLANKET	311.000	SYS
32	621-06545 FERTILIZER	0.055	TON
33	621-06567 WATER	2.400	KGAL
34	621-98038 MULCH, HARDWOOD SHREDDED BARK	1.000	CYS
35	622-03948 PLANTER	18.000	EACH
36	622-05623 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT, 36 IN. OR	4.000	EACH
37	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	8.000	EACH
38	622-05653 PLANT, GROUND COVER	6.000	EACH
39	622-05654 PLANT, PERENNIAL	6.000	EACH
40	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.	836.000	LFT
41	701-99086 PILE TIP, STEEL SHELL	28.000	EACH
42	702-51005 CONCRETE, A, SUBSTRUCTURE	107.800	CYS
43	702-51015 CONCRETE, B, FOOTINGS	41.800	CYS
44	702-51863 FIELD DRILLED HOLE IN CONCRETE	24.000	EACH
45	703-51030 REINFORCING STEEL	14,457.000	LBS
46	706-04683 RAILING	174.000	LFT
47	711-51038 STRUCTURAL STEEL	LUMP	LUMP
48	711-51038 STRUCTURAL STEEL	LUMP	LUMP

CALL ORDER : 245
 LETTING DATE :

CONTRACT ID : R -29339-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	REASSEMBLE EXISTING TRUSS BRIDGE		
49	711-51823 EXPANSION ANCHOR, 0.75 IN.	30.000	EACH
50	711-96525 EXPANSION ANCHOR, THREADED ROD, 0.75 IN.	8.000	EACH
51	712-03812 BENCH	6.000	EACH
52	712-94080 TIMBER DECK	2,924.000	SFT
53	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	40.000	LFT
54	715-05407 PIPE, END BENT DRAIN, 6 IN.	110.000	LFT
55	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
56	720-45030 INLET, E7	1.000	EACH
57	724-03855 EXPANSION JOINT, SLIDING PLATE	53.000	LFT
58	726-92406 BEARING ASSEMBLY, ELASTOMERIC	2.000	EACH
59	726-97941 BEARING ASSEMBLY, TFE ELASTOMERIC	2.000	EACH
60	728-98377 MASONRY COATING	LUMP	LUMP
61	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	7.700	SYS
62	732-08421 MODULAR BLOCK WALL ERECTION	7.700	SYS
63	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
64	802-03896 BOLLARD	2.000	EACH
65	802-04314 SIGN	2.000	EACH
66	805-02618 WIRE, NO. 2 COPPER, 3 1/C	80.000	LFT
67	805-02728 CONDUIT, PVC, 1 IN.	260.000	LFT
68	805-03083 CONDUIT, RIGID, P.V.C., 1.50 IN.	140.000	LFT
69	805-06003 POLE, WOOD	1.000	EACH
70	805-86900 JUNCTION BOX	18.000	EACH
71	805-91703 CONDUIT, STEEL, GALVANIZED, 1.5 IN.	80.000	LFT
72	805-93562 WIRE, THW, NO. 10 COPPER IN PLASTIC DUCT, IN CONDUIT, 3 1/C	210.000	LFT
73	805-94821 WIRE, THW, NO. 6 COPPER IN PLASTIC DUCT, IN TRENCH, 6 1/C	140.000	LFT
74	805-95519 FLEXIBLE CONDUIT, 0.75 IN.	110.000	LFT
75	807-02191 HANDHOLE, LIGHTING	1.000	EACH
76	807-04443 CONDUIT	210.000	LFT
77	807-04651 WIRE	260.000	LFT
78	807-04866 LUMINAIRE	18.000	EACH
79	807-06935 INSULATING LINK, WATERPROOFED	8.000	EACH
80	807-86810 SERVICE POINT, II	1.000	EACH
81	807-86910 CONNECTOR KIT, UNFUSED	60.000	EACH
82	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.000	EACH

CALL ORDER : 247
 LETTING DATE :

CONTRACT ID : R -29572-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITY, ENHANCEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02241 GUARDRAIL, REMOVE	10.000	LFT
12	202-52710 SIDEWALK, CONCRETE, REMOVE	24.000	SYS
13	203-02000 EXCAVATION, COMMON	468.500	CYS
14	205-03371 SEDIMENT, REMOVE	30.000	CYS
15	205-06937 TEMPORARY SILT FENCE	2,300.000	LFT
16	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	29.300	CYS
17	210-07827 TEXTURED	143.000	SYS
18	303-01180 COMPACTED AGGREGATE, NO. 53	1,358.000	TON
19	303-04489 COMPACTED CRUSHED AGGREGATE, 8	11.000	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	497.000	TON
21	402-07434 HMA SURFACE, TYPE C	102.000	TON
22	402-07439 HMA INTERMEDIATE, TYPE C	153.000	TON
23	406-05521 ASPHALT FOR TACK COAT	3,110.000	SYS
24	601-97770 POST, GUARDRAIL, WOOD	45.000	EACH
25	604-07902 CURB RAMP, CONCRETE, H	16.000	SYS
26	604-07903 CURB RAMP, CONCRETE, K	21.300	SYS
27	605-06120 CURB, CONCRETE	1,233.000	LFT
28	614-06475 HEADER, CEMENT CONCRETE, B	4.000	LFT
29	616-02320 GEOTEXTILES	36.000	SYS
30	616-06405 RIPRAP, REVETMENT	30.000	TON
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
32	621-06560 MULCHED SEEDING, U	47,440.000	SYS
33	621-06570 TOP SOIL	650.000	CYS
34	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 0.312 IN., 14 IN.	216.000	LFT
35	701-99086 PILE TIP, STEEL SHELL	14.000	EACH
36	702-51005 CONCRETE, A, SUBSTRUCTURE	27.560	CYS
37	702-51015 CONCRETE, B, FOOTINGS	14.220	CYS
38	702-94656 CONCRETE, B	11.000	CYS
39	703-51030 REINFORCING STEEL	5,131.000	LBS
40	706-04683 RAILING	130.000	LFT
41	712-03862 PREFABRICATED BRIDGE	LUMP	LUMP
42	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN.	35.000	LFT
43	724-03855 EXPANSION JOINT, SLIDING PLATE	20.000	LFT
44	732-07653 COARSE AGGREGATE, NO. 8	50.000	TON
45	732-08419 MODULAR BLOCK WALL	71.000	SYS
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	802-03821 SIGN, SHEET WITH LEGEND	14.000	EACH
48	805-95466 FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND	2.000	EACH

CALL ORDER : 247
 LETTING DATE :

CONTRACT ID : R -29572-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITY, ENHANCEMENT		
49 805-96014	SAW CUT, FULL DEPTH	775.000	LFT
50 807-04652	SERVICE POINT	2.000	EACH
51 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	490.000	LFT

CALL ORDER : 251
 LETTING DATE :

CONTRACT ID : R -29678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	11.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	11.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	11.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	55.000	LFT
13	202-74025 FENCE, REMOVE	3,284.000	LFT
14	202-96133 PIPE, REMOVE	43.000	LFT
15	203-02000 EXCAVATION, COMMON	65,645.000	CYS
16	203-02070 BORROW	500.000	CYS
17	205-03371 SEDIMENT, REMOVE	491.000	CYS
18	205-06930 SPLASHPAD, RIPRAP	9.000	TON
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	241.000	TON
20	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
21	205-06936 TEMPORARY SEDIMENT TRAP	310.000	TON
22	205-06937 TEMPORARY SILT FENCE	1,430.000	LFT
23	205-06938 TEMPORARY SLOPE DRAIN	71.000	LFT
24	207-08262 SUBGRADE TREATMENT, TYPE I	23,110.000	SYS
25	211-07454 STRUCTURE BACKFILL	835.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	8,044.000	TON
27	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	50.000	TON
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,505.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,537.000	TON
30	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	6,286.000	TON
31	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	2,857.000	TON
32	402-07453 HMA FOR TEMPORARY PAVEMENT	52.000	TON
33	406-05520 ASPHALT FOR TACK COAT	21.000	TON
34	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	37.500	LFT
35	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
36	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	1.000	EACH
37	603-06040 FENCE, FARM FIELD, 47 IN.	1,858.000	LFT
38	603-91748 FENCE GATE, FARM FIELD, 47 IN. X 16 FT.	1.000	EACH
39	610-07486 HMA FOR APPROACHES, TYPE A	1,859.000	TON
40	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
41	615-06490 RIGHT OF WAY MARKER	37.000	EACH
42	615-06505 MONUMENT, B	13.000	EACH
43	615-06510 MONUMENT, C	4.000	EACH
44	616-02320 GEOTEXTILES	2,554.000	SYS
45	616-05688 RIPRAP, CLASS 1	126.000	TON
46	616-05689 RIPRAP, CLASS 2	144.000	TON
47	616-06405 RIPRAP, REVETMENT	91.000	TON
48	616-06451 RIPRAP, UNIFORM	1,212.000	TON

CALL ORDER : 251
 LETTING DATE :

CONTRACT ID : R -29678-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
50	621-02770 EROSION CONTROL BLANKET	14,640.000	SYS
51	621-06545 FERTILIZER	4.400	TON
52	621-06553 SEED MIXTURE, R	1,395.000	LBS
53	621-06557 SEED MIXTURE, T	839.000	LBS
54	621-06565 MULCHING MATERIAL	37.400	TON
55	621-06567 WATER	10.000	KGAL
56	621-06574 SODDING	2,500.000	SYS
57	622-52436 SIGN, DO NOT MOW OR SPRAY	11.000	EACH
58	622-91786 SEEDLING	470.000	EACH
59	714-06056 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 11 FT. X 4 FT.	102.000	LFT
60	714-08514 WINGWALL	196.000	SFT
61	715-04231 SAFETY METAL END SECTION, 4:1, 57 IN. X 38 IN.	2.000	EACH
62	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	11,761.000	LFT
63	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	998.000	LFT
64	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	93.000	LFT
65	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	169.000	LFT
66	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN.	68.000	LFT
67	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	207.000	LFT
68	715-46005 PIPE END SECTION, 15 IN.	10.000	EACH
69	715-46010 PIPE END SECTION, 18 IN.	4.000	EACH
70	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
71	715-98178 PIPE ARCH, 0.064 IN., 57 IN. X 38 IN.	114.000	LFT
72	718-06529 OUTLET PROTECTOR, 2	29.000	EACH
73	718-52610 AGGREGATE FOR UNDERDRAINS	1,045.000	CYS
74	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,127.000	SYS
75	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
76	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
77	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
78	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,578.000	LFT
79	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	801-07119 BARRICADE, III-B	96.000	LFT
82	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	198.000	LFT
83	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	67.600	SFT
84	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	51.000	SFT
85	804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA.	8.000	EACH
86	805-04197 CONDUIT, PVC, 6 IN.	385.000	LFT
87	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	12,521.000	LFT
88	808-06716 LINE, REMOVE	268.000	LFT
89	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	863.000	LFT
90	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,645.000	LFT
91	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	145.000	LFT
92	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	147.000	LFT
93	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
94	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
95	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	142.000	EACH
96	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	688.000	LFT

CALL ORDER : 261
 LETTING DATE :

CONTRACT ID : R -29914-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
4 205-06937	TEMPORARY SILT FENCE	200.000	LFT
5 621-06559	MULCHED SEEDING, R	500.000	SYS

CALL ORDER : 291
 LETTING DATE :

CONTRACT ID : RS-26390-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	16.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	16.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	250.000	TON
15	303-07449 COMPACTED AGGREGATE, NO. 73	2,012.000	TON
16	304-07491 HMA PATCHING, TYPE C	250.000	TON
17	306-08033 MILLING, ASPHALT, 1 IN.	241,782.000	SYS
18	306-08043 MILLING, TRANSITION	657.000	SYS
19	306-08432 MILLING, APPROACH	12,614.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	19,948.000	TON
22	404-05511 SEAL COAT, 2	104,215.000	SYS
23	406-05520 ASPHALT FOR TACK COAT	64.000	TON
24	610-07488 HMA FOR APPROACHES, TYPE C	1,041.000	TON
25	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	4.000	EACH
26	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
27	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,819.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	55.000	EACH
30	801-06710 FLASHING ARROW SIGN	125.000	DAY
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	805-02328 SIGNAL CABLE, 1C 14GA.	4,080.000	LFT
33	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,063.000	LFT
34	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
35	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,020.000	LFT
36	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	19,547.000	LFT
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	97,395.000	LFT
38	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	108.000	EACH
39	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	78,186.000	LFT
40	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	1,344.000	LFT
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	48.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	978.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	978.000	EACH
44	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	250.000	LFT

CALL ORDER : 301
 LETTING DATE :

CONTRACT ID : RS-26398-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	1.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	1.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	1.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-07449 COMPACTED AGGREGATE, NO. 73	112.000	TON
12	304-07491 HMA PATCHING, TYPE C	20.000	TON
13	306-08034 MILLING, ASPHALT, 1 1/2 IN.	57,875.000	SYS
14	306-08432 MILLING, APPROACH	7,439.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	4,775.000	TON
17	406-05520 ASPHALT FOR TACK COAT	16.000	TON
18	610-07488 HMA FOR APPROACHES, TYPE C	648.000	TON
19	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
20	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
21	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	21,086.000	LFT
22	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	805-02328 SIGNAL CABLE, 1C 14GA.	3,440.000	LFT
25	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	455.000	LFT
26	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	860.000	LFT
27	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	218.000	LFT
28	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	50,650.000	LFT
29	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	243.000	LFT
30	808-75078 TRANSVERSE MARKINGS, PAINT, SOLID, YELLOW CROSSHATCH LINE,	1,316.000	LFT
31	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,951.000	LFT
32	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	19,135.000	LFT
33	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	96.000	LFT
34	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	27.000	EACH
35	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	23.000	EACH
36	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	135.000	EACH
37	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	135.000	EACH
38	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	195.000	LFT

CALL ORDER : 311
 LETTING DATE :

CONTRACT ID : RS-27548-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	4.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	8.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	4.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-07449 COMPACTED AGGREGATE, NO. 73	977.000	TON
12	304-07491 HMA PATCHING, TYPE C	435.000	TON
13	306-08033 MILLING, ASPHALT, 1 IN.	122,868.000	SYS
14	306-08043 MILLING, TRANSITION	400.000	SYS
15	306-08432 MILLING, APPROACH	6,675.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	10,170.000	TON
18	406-05520 ASPHALT FOR TACK COAT	32.900	TON
19	610-07488 HMA FOR APPROACHES, TYPE C	724.000	TON
20	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	143.000	TON
21	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	2.000	EACH
22	612-60410 DRILLED HOLE FOR UNDERSEAL	2,374.000	EACH
23	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,060.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	32.000	EACH
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	26,457.000	LFT
29	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	9,090.000	LFT
30	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,251.000	LFT
31	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	205.000	LFT
32	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	501.000	EACH
33	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	501.000	EACH

CALL ORDER : 321
 LETTING DATE :

CONTRACT ID : RS-28002-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	24.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	8.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	303-07449 COMPACTED AGGREGATE, NO. 73	5,856.000	TON
15	304-07783 HMA PATCHING, TYPE D	200.000	TON
16	306-08033 MILLING, ASPHALT, 1 IN.	263,059.000	SYS
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	7,338.000	SYS
18	306-08043 MILLING, TRANSITION	1,693.000	SYS
19	306-08432 MILLING, APPROACH	20,013.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	22,308.000	TON
22	406-05520 ASPHALT FOR TACK COAT	67.600	TON
23	604-07902 CURB RAMP, CONCRETE, H	32.000	SYS
24	610-07788 HMA FOR APPROACHES, TYPE D	2,139.000	TON
25	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	312.000	TON
26	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	2.000	EACH
27	612-60410 DRILLED HOLE FOR UNDERSEAL	5,184.000	EACH
28	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	15.000	EACH
29	615-06527 MONUMENT, SECTION CORNER	13.000	EACH
30	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
31	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
32	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8,938.000	LFT
33	801-06640 CONSTRUCTION SIGN, A	65.000	EACH
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	8.000	EACH
36	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	8.000	EACH
37	808-08258 TRANSVERSE MARKINGS	578.000	LFT
38	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	18,204.000	LFT
39	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,562.000	LFT
40	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	123.000	LFT
41	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,117.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,117.000	EACH

CALL ORDER : 331
 LETTING DATE :

CONTRACT ID : RS-28596-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-07039 FIELD OFFICE, B	6.000	MOS
4	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
6	105-08523 RADIO SERVICE	6.000	MOS
7	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
8	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
9	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
10	109-08359 LIQUIDATED DAMAGES	1.000	DOL
11	109-08360 CONTRACT LIENS	1.000	DOL
12	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
13	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
14	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	202-02271 HEADWALL, REMOVE	20.000	EACH
17	202-02278 CURB, CONCRETE, REMOVE	20.000	LFT
18	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
19	213-04324 FLOWABLE FILL	3.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,317.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	1,500.000	TON
22	304-07490 HMA PATCHING, TYPE B	800.000	TON
23	306-08033 MILLING, ASPHALT, 1 IN.	86,207.000	SYS
24	306-08034 MILLING, ASPHALT, 1 1/2 IN.	8,099.000	SYS
25	306-08043 MILLING, TRANSITION	3,840.000	SYS
26	306-08432 MILLING, APPROACH	4,357.000	SYS
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	7,974.000	TON
29	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	9,762.000	TON
30	402-07432 HMA SURFACE, TYPE A	194.000	TON
31	402-07435 HMA INTERMEDIATE, TYPE A	195.000	TON
32	402-07451 HMA WEDGE AND LEVEL, TYPE B	500.000	TON
33	406-05520 ASPHALT FOR TACK COAT	67.000	TON
34	507-07479 HMA PARTIAL DEPTH PATCH	1,462.000	TON
35	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
36	604-07896 CURB RAMP, CONCRETE, B	32.800	SYS
37	604-07897 CURB RAMP, CONCRETE, C	10.800	SYS
38	605-06120 CURB, CONCRETE	20.000	LFT
39	610-07486 HMA FOR APPROACHES, TYPE A	1,252.000	TON
40	615-06527 MONUMENT, SECTION CORNER	7.000	EACH
41	621-06574 SODDING	50.000	SYS
42	715-46000 PIPE END SECTION, 12 IN.	20.000	EACH
43	720-44000 CASTING, ADJUST TO GRADE	18.000	EACH
44	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	8.000	LFT
45	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
46	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,440.000	LFT
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,290.000	LFT
48	801-06640 CONSTRUCTION SIGN, A	28.000	EACH

CALL ORDER : 331
LETTING DATE :

CONTRACT ID : RS-28596-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
49	801-06775	MAINTAINING TRAFFIC	LUMP
50	801-92448	CONSTRUCTION SIGNS, MOBILE	540.000
51	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	65,680.000
52	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	4,488.000
53	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	39,589.000
54	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	60.000
55	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	160.000
56	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	719.000
57	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	719.000

CALL ORDER : 341
 LETTING DATE :

CONTRACT ID : RS-28819-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001	ASPHALT RESURFACE			
1	105-07039	FIELD OFFICE, B	9.000	MOS
2	105-09198	LAPTOP COMPUTER SYSTEM	18.000	MOS
3	105-09199	FIELD OFFICE INTERNET SERVICE	18.000	MOS
4	109-08359	LIQUIDATED DAMAGES	1.000	DOL
5	109-08360	CONTRACT LIENS	1.000	DOL
6	109-08440	QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	303-01180	COMPACTED AGGREGATE, NO. 53	400.000	TON
11	304-07490	HMA PATCHING, TYPE B	600.000	TON
12	304-07493	WIDENING WITH HMA, TYPE B	369.000	TON
13	306-08034	MILLING, ASPHALT, 1 1/2 IN.	138,433.000	SYS
14	306-08043	MILLING, TRANSITION	17,515.000	SYS
15	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	11,486.000	TON
16	402-07451	HMA WEDGE AND LEVEL, TYPE B	500.000	TON
17	406-05520	ASPHALT FOR TACK COAT	43.000	TON
18	610-07487	HMA FOR APPROACHES, TYPE B	1,183.000	TON
19	615-06527	MONUMENT, SECTION CORNER	2.000	EACH
20	720-44000	CASTING, ADJUST TO GRADE	2.000	EACH
21	801-03290	CONSTRUCTION SIGN, C	6.000	EACH
22	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	7,926.000	LFT
23	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,926.000	LFT
24	801-06640	CONSTRUCTION SIGN, A	49.000	EACH
25	801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
26	804-06770	DELINEATOR POST	10.000	EACH
27	805-02503	CABLE, ROADWAY LOOP, 1C 14GA.	1,000.000	LFT
28	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	100.000	LFT
29	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	320.000	LFT
30	805-92951	SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000	EACH
31	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
32	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	250.000	LFT
33	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,374.000	LFT
34	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	105,410.000	LFT
35	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	91,999.000	LFT
36	808-75260	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	200.000	LFT
37	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	138.000	LFT
38	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
39	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
40	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,301.000	EACH
41	808-97323	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	144.000	LFT

CALL ORDER : 351
 LETTING DATE :

CONTRACT ID : RS-29204-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVER LAY FUNCTIONAL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	14.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	28.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	14.000	MOS
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	203-02070 BORROW	85,240.000	CYS
12	204-02290 SETTLEMENT PLATE	37.000	EACH
13	205-06936 TEMPORARY SEDIMENT TRAP	222.000	TON
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	60.000	CYS
15	213-08058 FLOWABLE BACKFILL	68.700	CYS
16	303-01180 COMPACTED AGGREGATE, NO. 53	1,000.000	TON
17	303-02051 STONE, NO 2	100.000	TON
18	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,924.000	SYS
19	306-08043 MILLING, TRANSITION	2,973.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	900.000	TON
22	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	675.000	TON
23	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	3,100.000	TON
24	402-07451 HMA WEDGE AND LEVEL, TYPE B	600.000	TON
25	406-05520 ASPHALT FOR TACK COAT	9.000	TON
26	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
27	621-06545 FERTILIZER	11.000	TON
28	621-06553 SEED MIXTURE, R	4,250.000	LBS
29	621-06557 SEED MIXTURE, T	800.000	LBS
30	621-06565 MULCHING MATERIAL	70.000	TON
31	702-51015 CONCRETE, B, FOOTINGS	11.300	CYS
32	703-51030 REINFORCING STEEL	221.000	LBS
33	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	56.000	LFT
34	715-07625 PIPE, TYPE 1, CIRCULAR, 66 IN.	118.000	LFT
35	715-07626 CONCRETE ANCHOR, 66 IN.	1.000	EACH
36	715-07667 CONCRETE ANCHOR, 36 IN.	1.000	EACH
37	715-08394 TRASH RACK	1.000	EACH
38	720-02123 INLET PIPE RISER	LUMP	LUMP
39	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
40	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	960.000	LFT
41	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	480.000	LFT
42	801-06640 CONSTRUCTION SIGN, A	29.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	802-91122 SIGN, GROUND MOUNTED, RESET	3.000	EACH
45	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	500.000	LFT
46	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	19,300.000	LFT
47	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	200.000	LFT
48	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	58.000	EACH

CALL ORDER : 351
 LETTING DATE :

CONTRACT ID : RS-29204-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVER LAY FUNCTIONAL		
49 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	58.000	EACH

CALL ORDER : 361
 LETTING DATE :

CONTRACT ID : RS-29473-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	7.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	14.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	14.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	7.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	304-07783 HMA PATCHING, TYPE D	1,650.000	TON
15	306-08033 MILLING, ASPHALT, 1 IN.	153,874.000	SYS
16	306-08043 MILLING, TRANSITION	1,889.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	12,695.000	TON
19	402-07787 HMA WEDGE AND LEVEL, TYPE D	100.000	TON
20	404-05512 SEAL COAT, 3	40,459.000	SYS
21	406-05520 ASPHALT FOR TACK COAT	42.000	TON
22	610-07788 HMA FOR APPROACHES, TYPE D	32.000	TON
23	720-44000 CASTING, ADJUST TO GRADE	66.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
25	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,228.000	LFT
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,228.000	LFT
27	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
28	801-06710 FLASHING ARROW SIGN	90.000	DAY
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
31	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	955.000	LFT
32	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	955.000	LFT
33	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	929.000	LFT
34	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	7,886.000	LFT
35	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	43,220.000	LFT
36	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	4,845.000	LFT
37	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	98.000	LFT
38	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	43,040.000	LFT
39	808-75272 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	1,210.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	826.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	826.000	EACH

CALL ORDER : 371
 LETTING DATE :

CONTRACT ID : RS-29839-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVERLAY, PREVENTIVE MAINTENENCE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	6.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	6.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	6.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02241 GUARDRAIL, REMOVE	853.000	LFT
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	7.000	EACH
16	211-07454 STRUCTURE BACKFILL	6.300	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,470.000	TON
18	303-01180 COMPACTED AGGREGATE, NO. 53	5,420.000	TON
19	304-07490 HMA PATCHING, TYPE B	2,977.000	TON
20	306-08033 MILLING, ASPHALT, 1 IN.	192,462.000	SYS
21	306-08034 MILLING, ASPHALT, 1 1/2 IN.	9,523.000	SYS
22	306-08043 MILLING, TRANSITION	1,737.000	SYS
23	306-08432 MILLING, APPROACH	15,800.000	SYS
24	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
25	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	17,106.000	TON
26	402-07432 HMA SURFACE, TYPE A	480.000	TON
27	406-05520 ASPHALT FOR TACK COAT	55.000	TON
28	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	2.000	EACH
29	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
31	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	764.000	LFT
32	610-07486 HMA FOR APPROACHES, TYPE A	3,665.000	TON
33	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
34	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
35	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	20.000	TON
36	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
37	612-60410 DRILLED HOLE FOR UNDERSEAL	400.000	EACH
38	616-02320 GEOTEXTILES	12.000	SYS
39	616-06451 RIPRAP, UNIFORM	9.500	TON
40	715-05756 PIPE EXTENSION, CIRCULAR, 12 IN.	9.000	LFT
41	715-06876 PIPE LINER, THERMOPLASTIC, 72 IN.	83.000	LFT
42	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,392.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,392.000	LFT
45	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-92448 CONSTRUCTION SIGNS, MOBILE	270.000	DAY
48	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	14.000	LFT

CALL ORDER : 371
LETTING DATE :

CONTRACT ID : RS-29839-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	HMA OVERLAY, PREVENTIVE MAINTENENCE		
49 802-91122	SIGN, GROUND MOUNTED, RESET	1.000	EACH
50 808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	14,100.000	LFT
51 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	147,888.000	LFT
52 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	60,255.000	LFT
53 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	12.000	LFT
54 808-75340	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
55 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,460.000	EACH
56 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,460.000	EACH

CALL ORDER : 391
 LETTING DATE :

CONTRACT ID : B -28826-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	12.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	12.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	12.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
11	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
12	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	294.000	SYS
16	202-02241 GUARDRAIL, REMOVE	1,050.000	LFT
17	202-51133 RAILING, REMOVE	482.000	LFT
18	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
19	203-02000 EXCAVATION, COMMON	296.000	CYS
20	208-51500 RESHAPE SPILL SLOPES	LUMP	LUMP
21	211-06467 AGGREGATE FOR END BENT BACKFILL	36.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	201.000	TON
23	302-07455 DENSE GRADED SUBBASE	49.000	CYS
24	304-07493 WIDENING WITH HMA, TYPE B	170.000	TON
25	306-08034 MILLING, ASPHALT, 1 1/2 IN.	67.000	SYS
26	306-08043 MILLING, TRANSITION	480.000	SYS
27	402-07432 HMA SURFACE, TYPE A	63.000	TON
28	402-07440 HMA BASE, TYPE A	288.000	TON
29	406-05521 ASPHALT FOR TACK COAT	1,718.000	SYS
30	502-06329 PCCP, 12 IN.	107.000	SYS
31	503-03489 RETROFITTED TIE BARS	48.000	EACH
32	503-05310 TERMINAL JOINT	48.000	LFT
33	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
34	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
35	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,162.500	LFT
36	607-95754 PAVED SIDE DITCH, BREAK	635.000	LFT
37	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	224.000	SYS
38	610-07487 HMA FOR APPROACHES, TYPE B	127.000	TON
39	616-02320 GEOTEXTILES	2,682.000	SYS
40	616-06405 RIPRAP, REVETMENT	2,182.000	TON
41	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
42	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
43	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
44	702-51005 CONCRETE, A, SUBSTRUCTURE	58.000	CYS
45	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	440.000	LBS
46	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,220.000	LBS
47	702-92857 CONCRETE, C, SUBSTRUCTURE	27.300	CYS
48	703-51030 REINFORCING STEEL	6,068.000	LBS

CALL ORDER : 391
 LETTING DATE :

CONTRACT ID : B -28826-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
49	703-51032 REINFORCING STEEL, EPOXY COATED	78,350.000	LBS
50	703-90512 THREADED BAR SPLICE	38.000	EACH
51	703-97703 THREADED BAR SPLICE, EPOXY COATED	924.000	EACH
52	704-51002 CONCRETE, C, SUPERSTRUCTURE	264.000	CYS
53	706-08312 RAILING, TF-2	496.000	LFT
54	706-08624 CONCRETE BRIDGE RAILING TRANSITION, TPBT	4.000	EACH
55	706-51020 CONCRETE, C, RAILING	52.000	CYS
56	709-51821 SURFACE SEAL	LUMP	LUMP
57	710-51864 FIELD DRILLED HOLE	464.000	EACH
58	710-51870 REPOINTING MASONRY IN STRUCTURES	50.000	SFT
59	711-51038 STRUCTURAL STEEL	LUMP	LUMP
60	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
61	711-96800 STUD SHEAR CONNECTORS	3,444.000	EACH
62	713-01260 SUPPORTING SUBSTRUCTURE	LUMP	LUMP
63	713-51820 TEMPORARY SUPPORT	LUMP	LUMP
64	715-05407 PIPE, END BENT DRAIN, 6 IN.	132.000	LFT
65	726-93525 BEARING ASSEMBLY, II	14.000	EACH
66	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
67	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
68	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,220.000	LFT
69	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,980.000	LFT
70	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.000	LFT
71	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
72	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07119 BARRICADE, III-B	32.000	LFT
75	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,085.000	LFT
76	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	373.000	LFT
77	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	2,980.000	LFT
78	808-06716 LINE, REMOVE	1,180.000	LFT
79	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.000	EACH
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	8.000	EACH

CALL ORDER : 421
 LETTING DATE :

CONTRACT ID : M -29803-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTION AND PARK ROAD MAINTENANCE		
1	105-07038 FIELD OFFICE, A	2.000	MOS
2	105-09198 LAPTOP COMPUTER SYSTEM	2.000	MOS
3	105-09199 FIELD OFFICE INTERNET SERVICE	2.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	304-07489 HMA PATCHING, TYPE A	50.000	TON
10	306-08043 MILLING, TRANSITION	283.000	SYS
11	402-07432 HMA SURFACE, TYPE A	1,409.000	TON
12	406-05520 ASPHALT FOR TACK COAT	6.000	TON
13	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 431
LETTING DATE :

CONTRACT ID : M -30040-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, HERBICIDE TREATMENT		
1 105-08520	CELLULAR TELEPHONE/RADIO	3.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 109-08359	LIQUIDATED DAMAGES	1.000	DOL
5 109-08360	CONTRACT LIENS	1.000	DOL
6 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8 624-92647	HERBICIDE TREATMENT	3,520.000	ACRE
9 801-03290	CONSTRUCTION SIGN, C	4.000	EACH
10 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 451
 LETTING DATE :

CONTRACT ID : T -29197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07038 FIELD OFFICE, A	11.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	22.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	22.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	22.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.000	EACH
14	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
15	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
16	801-06640 CONSTRUCTION SIGN, A	45.000	EACH
17	801-06710 FLASHING ARROW SIGN	200.000	DAY
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	87.000	SFT
20	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	240.000	SFT
21	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	69.000	SFT
22	805-01842 HANDHOLE, SIGNAL	16.000	EACH
23	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	5,200.000	LFT
24	805-04952 CONTROLLER AND CABINET	4.000	EACH
25	805-04977 MICROLOOP	48.000	EACH
26	805-05007 MICROLOOP DETECTOR, INSTALL	12.000	EACH
27	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	25.000	LFT
28	805-06595 CONDUIT, PVC, 2 IN.	2,800.000	LFT
29	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	52.000	EACH
30	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	7.000	EACH
31	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	13.000	EACH
32	805-78420 DISCONNECT HANGER	24.000	EACH
33	805-78445 SIGNAL SERVICE	1.000	EACH
34	805-78467 SIGNAL CABLE, 3C 8GA.	134.000	LFT
35	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	26,350.000	LFT
36	805-78485 SIGNAL CABLE, 5C 14GA.	1,500.000	LFT
37	805-78490 SIGNAL CABLE, 7C 14GA.	10,725.000	LFT
38	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	57,325.000	LFT
39	805-78785 SIGNAL DETECTOR HOUSING	65.000	EACH
40	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	8,600.000	LFT
41	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
42	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	58.000	EACH
43	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	460.000	LFT
44	808-06194 LINE, EPOXY, SOLID, WHITE, 12 IN.	230.000	LFT
45	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	120.000	LFT
46	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	1,000.000	LFT
47	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	91.000	EACH
48	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	25.000	EACH

CALL ORDER : 451
LETTING DATE :

CONTRACT ID : T -29197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
49 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
50 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
51 808-94455	TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	2,150.000	LFT
52 808-98000	LINE, EPOXY, SOLID, YELLOW, 8 IN.	320.000	LFT

CALL ORDER : 461
 LETTING DATE :

CONTRACT ID : T -29198-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	8.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	16.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	8.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.000	EACH
14	202-09239 TRANSPORTATION OF SALVAGEABLE ITEMS	4.000	EACH
15	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
16	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
17	801-06710 FLASHING ARROW SIGN	140.000	DAY
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	801-53072 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
20	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	161.000	SFT
21	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	30.000	SFT
22	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	55.000	SFT
23	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	8.000	EACH
24	805-01842 HANDHOLE, SIGNAL	11.000	EACH
25	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	2,300.000	LFT
26	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
27	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	2.000	EACH
28	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	30.000	EACH
29	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
30	805-78355 PEDESTRIAN SIGNAL HEAD, 12 IN.	16.000	EACH
31	805-78370 PEDESTRIAN PUSH BUTTON	16.000	EACH
32	805-78415 SPAN, CATENARY, AND TETHER	8.000	EACH
33	805-78420 DISCONNECT HANGER	16.000	EACH
34	805-78445 SIGNAL SERVICE	3.000	EACH
35	805-78467 SIGNAL CABLE, 3C 8GA.	455.000	LFT
36	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	10,300.000	LFT
37	805-78480 SIGNAL CABLE, 3C 14GA.	2,430.000	LFT
38	805-78485 SIGNAL CABLE, 5C 14GA.	3,450.000	LFT
39	805-78490 SIGNAL CABLE, 7C 14GA.	3,120.000	LFT
40	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	13,300.000	LFT
41	805-78785 SIGNAL DETECTOR HOUSING	21.000	EACH
42	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	3,425.000	LFT
43	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	8.000	EACH
44	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	27.000	EACH
45	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	350.000	LFT
46	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	730.000	LFT
47	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	495.000	LFT
48	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,750.000	LFT

CALL ORDER : 461
 LETTING DATE :

CONTRACT ID : T -29198-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
49 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	20.000	EACH
50 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH

CALL ORDER : 471
 LETTING DATE :

CONTRACT ID : T -29200-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW SIGNAL INSTALLATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	7.000	MOS
3	105-09198 LAPTOP COMPUTER SYSTEM	14.000	MOS
4	105-09199 FIELD OFFICE INTERNET SERVICE	14.000	MOS
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
7	202-01874 SHEET SIGN AND POST, REMOVE	2.000	EACH
8	202-95579 SERVICE POINT, REMOVE	1.000	EACH
9	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
10	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
11	801-06710 FLASHING ARROW SIGN	200.000	DAY
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	24.000	LFT
14	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	42.000	SFT
15	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	3.000	EACH
16	805-01842 HANDHOLE, SIGNAL	6.000	EACH
17	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
18	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	5,000.000	LFT
19	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,600.000	LFT
20	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
21	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
22	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
23	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
24	805-78420 DISCONNECT HANGER	4.000	EACH
25	805-78445 SIGNAL SERVICE	1.000	EACH
26	805-78467 SIGNAL CABLE, 3C 8GA.	600.000	LFT
27	805-78485 SIGNAL CABLE, 5C 14GA.	600.000	LFT
28	805-78490 SIGNAL CABLE, 7C 14GA.	3,000.000	LFT
29	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	4,000.000	LFT
30	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
31	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,600.000	LFT
32	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
33	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	3.000	EACH
34	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	6.000	EACH
35	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	8.000	SYS
36	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	4.000	SYS
37	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	24.000	LFT
38	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	140.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	8.000	EACH
40	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH

CALL ORDER : 481
 LETTING DATE :

CONTRACT ID : T -29202-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-07039 FIELD OFFICE, B	9.000	MOS
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	105-09198 LAPTOP COMPUTER SYSTEM	18.000	MOS
7	105-09199 FIELD OFFICE INTERNET SERVICE	18.000	MOS
8	109-08359 LIQUIDATED DAMAGES	1.000	DOL
9	109-08360 CONTRACT LIENS	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.000	EACH
15	621-06574 SODDING	200.000	SYS
16	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
17	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
18	801-06710 FLASHING ARROW SIGN	100.000	DAY
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	32.000	SFT
21	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	37.000	SFT
22	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	39.000	SFT
23	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
24	805-01842 HANDHOLE, SIGNAL	17.000	EACH
25	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	4,200.000	LFT
26	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
27	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	4.000	EACH
28	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	24.000	EACH
29	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
30	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
31	805-78415 SPAN, CATENARY, AND TETHER	7.000	EACH
32	805-78420 DISCONNECT HANGER	13.000	EACH
33	805-78445 SIGNAL SERVICE	3.000	EACH
34	805-78467 SIGNAL CABLE, 3C 8GA.	120.000	LFT
35	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	10,110.000	LFT
36	805-78485 SIGNAL CABLE, 5C 14GA.	520.000	LFT
37	805-78490 SIGNAL CABLE, 7C 14GA.	3,265.000	LFT
38	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	16,000.000	LFT
39	805-78785 SIGNAL DETECTOR HOUSING	33.000	EACH
40	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	3,410.000	LFT
41	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
42	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	2.000	EACH
43	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	21.000	EACH
44	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	155.000	LFT
45	808-06716 LINE, REMOVE	20.000	LFT
46	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	47.000	LFT
47	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	100.000	LFT
48	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	270.000	LFT

CALL ORDER : 481
 LETTING DATE :

CONTRACT ID : T -29202-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
49 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	22.000	EACH
50 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	10.000	EACH

CALL ORDER : 491
 LETTING DATE :

CONTRACT ID : T -29772-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ITS TRAFFIC MANAGEMENT SYSTEM		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	210-07237 SPARE	3.000	EACH
8	210-08575 HAR	24.000	EACH
9	210-08575 HAR	9.000	EACH
10	210-09237 PAGER	8.000	EACH
11	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
12	801-06640 CONSTRUCTION SIGN, A	3.000	EACH

CALL ORDER : 521
 LETTING DATE :

CONTRACT ID : TM-29963-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 OVERHEAD LIGHTING MAINTENANCE			
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-01604 ROADWAY COLUMN, REMOVE	5.000	EACH
9	202-96391 MAST ARM, REMOVE	5.000	EACH
10	702-90915 CONCRETE, A	1.000	CYS
11	715-97122 PIPE, PVC, 2 IN.	20.000	LFT
12	805-01419 CIRCUIT BREAKER, INSTALL	10.000	EACH
13	805-01523 MAST ARM, INSTALL	5.000	EACH
14	805-02116 CIRCUIT BREAKER, FURNISH	5.000	EACH
15	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	100.000	LFT
16	805-86843 WIRE, NO. 4 COPPER, 1C	1,000.000	LFT
17	805-86898 CONDUIT, STEEL, GALVANIZED, .75 IN.	50.000	LFT
18	805-87408 SIGNAL, POLE, WOOD, 5, 40 FT.	1.000	EACH
19	805-87640 BREAKAWAY COUPLING	15.000	SET
20	805-87715 GROUND ROD WITH CONNECTOR	1.000	EACH
21	805-87744 AERIAL CABLE, DUPLEX	100.000	LFT
22	805-87746 AERIAL CABLE, TRIPLEX	100.000	LFT
23	805-91706 ANCHOR BOLT, REPAIR	5.000	EACH
24	805-95518 FLEXIBLE CONDUIT, 2 IN.	50.000	LFT
25	805-95520 EXPANSION FITTING, 2 IN.	1.000	EACH
26	805-95521 EXPANSION FITTING, 0.75 IN.	1.000	EACH
27	807-01412 CONE BARRICADE TO PROTECT LUMINAIRE SUPPORT, INSTALL	15.000	EACH
28	807-01414 SERVICE POINT RISER AND WEATHERHEAD, INSTALL	2.000	EACH
29	807-01417 WOOD POLE, CLASS V, 35 FT., FURNISH	1.000	EACH
30	807-01421 SERVICE POINT RISER AND WEATHERHEAD, FURNISH	20.000	EACH
31	807-01422 SERVICE POINT TYPE II ENCLOSURE, FURNISH	1.000	EACH
32	807-01425 SHAFT FOR ANY E.M.H., ANY M.A., INSTALL	5.000	EACH
33	807-01426 SERVICE POINT MAIN BREAKER, FURNISH	2.000	EACH
34	807-01555 ROUTINE MAINTENANCE, SIGN LUMINAIRE, MERCURY VAPOR, 175 WATT	24.000	MOS
35	807-01556 LUMINAIRE SIGN, MERCURY VAPOR WITH GLARE SHIELD AND	1.000	EACH
36	807-01558 LUMINAIRE SUPPORT CONE BARRICADE, REMOVE	15.000	EACH
37	807-01559 LUMINAIRE, ROADWAY, INSTALL	35.000	EACH
38	807-01560 REPAIR CALLOUT	30.000	EACH
39	807-01562 POWER DISCONNECT PLUG FOR HIGH MAST TOWER	1.000	EACH
40	807-01563 HIGH MAST TOWER LOCATING PIN, STAINLESS STEEL	1.000	EACH
41	807-01617 HANDHOLE COVER AND RING	5.000	EACH
42	807-02111 VIBRATION DAMPER, FURNISH	1.000	EACH
43	807-02113 MAST ARM, 1.5 FT. TO 6 FT., FURNISH	5.000	EACH
44	807-02114 MAST ARM, 8 FT. TO 30 FT., FURNISH	5.000	EACH
45	807-02191 HANDHOLE, LIGHTING	5.000	EACH
46	807-02199 HANDHOLE COVER, RECTANGULAR	1.000	EACH
47	807-02201 SHAFT FOR ANY E.M.H., ANY M.A., FURNISH	5.000	EACH
48	807-04652 SERVICE POINT	2.000	EACH

CALL ORDER : 521
 LETTING DATE :

CONTRACT ID : TM-29963-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 OVERHEAD LIGHTING MAINTENANCE			
49	807-04652 SERVICE POINT	1.000	EACH
50	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	5.000	EACH
51	807-86750 LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE SODIUM, 150	2.000	EACH
52	807-86790 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, 250 WATT	5.000	EACH
53	807-86800 LUMINAIRE, SIGN, MERCURY VAPOR WITH GLARE SHIELD AND VANDAL	5.000	EACH
54	807-86886 WIRE, AWG, XHHW, XLP, SUNLIGHT RESISTANT,	150.000	LFT
55	807-86910 CONNECTOR KIT, UNFUSED	25.000	EACH
56	807-86915 CONNECTOR KIT, FUSED	20.000	EACH
57	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	50.000	EACH
58	807-86930 INSULATION LINK, NONWATERPROOFED	50.000	EACH
59	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	1.000	EACH
60	807-86955 CABLE DUCT MARKER	1.000	EACH
61	807-87022 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	6,408.000	MOS
62	807-87028 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	2,424.000	MOS
63	807-87042 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	336.000	MOS
64	807-87043 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	1,104.000	MOS
65	807-87050 ROUTINE MAINTENANCE, LUMINAIRE, SIGN, 250 WATT	2,484.000	MOS
66	807-87085 ELECTRICIAN	50.000	HRS
67	807-87200 LUMINAIRE ROADWAY, HIGH PRESSURE SODIUM, 250 WATT, FURNISH	10.000	EACH
68	807-87205 LUMINAIRE ROADWAY, HIGH PRESSURE SODIUM, 400 WATT, FURNISH	10.000	EACH
69	807-87450 TRANSFORMER BASE, FURNISH	1.000	EACH
70	807-87556 WIRE, THW OR TW, NO. 10 COPPER STRANDED	500.000	LFT
71	807-87595 REPLACEMENT OF CABLE CLAMPS ON HIGHMAST TOWER LUMINAIRE RING	5.000	EACH
72	807-87620 VANDAL SHIELD, LEXAN, INSTALL	1.000	EACH
73	807-87650 TRANSFORMER BASE, INSTALL	1.000	EACH
74	807-87785 SERVICE POINT MAIN BREAKER, INSTALL	2.000	EACH
75	807-87800 CABLE DUCT, INSTALL	1,650.000	LFT
76	807-91704 LIGHT POLE HANDHOLE COVER	1.000	EACH
77	807-91705 CONDUIT, POLYETHYLENE, REPAIR	3.000	EACH
78	807-92523 SKIRTING, EXPANDED ALUMINUM	1.000	EACH
79	807-92870 TRANSFORMER BASE HANDHOLE	1.000	EACH
80	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	1.000	SET
81	807-93746 TOWER RING LIFT CABLE, 0.375	160.000	LFT
82	807-93747 TOWER RING, SUSPENSION CABLE, 0.1875	160.000	LFT
83	807-95488 NEMA 4/5 UNDERPASS OR SIGN CIRCUIT BREAKER, ENCLOSURE	1.000	EACH
84	807-95509 GLARE SHIELD	1.000	EACH
85	807-95516 RELAY SWITCH	3.000	EACH
86	807-95519 FLEXIBLE CONDUIT, .75 IN.	100.000	LFT
87	807-95522 PIPE STRAP	6.000	EACH
88	807-95523 WATERPROOFING OF ELECTRICAL CONNECTOR	50.000	EACH
89	807-95525 LIGHTING, HIGHWAY SUPPORT, REPAIR	1.000	EACH
90	807-95528 GROUP RELAMP HIGH PRESSURE SODIUM LUMINAIRES	LUMP	LUMP
91	807-95529 GROUP RELAMP MERCURY VAPOR LUMINAIRES	LUMP	LUMP
92	807-95631 LUMINAIRES, HIGH MAST, INSTALL	10.000	EACH
93	807-95632 SERVICE POINT, OVERRIDE CIRCUIT	5.000	EACH
94	807-95709 PHOTOCELLS	10.000	EACH
95	807-96194 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	2,856.000	MOS
96	807-96197 WIRE, AWG, MTW, THHW, THWN, AWM, GASOLINE AND OIL	750.000	LFT

CALL ORDER : 521
LETTING DATE :

CONTRACT ID : TM-29963-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	OVERHEAD LIGHTING MAINTENANCE		
97 807-96204	LOWERING AND RAISING OF TOWER	1.000	EACH
98 807-96236	LIGHT POLE, HIGH MAST, TOWER POWER CABLE	1.000	EACH
99 807-98714	BALLAST, MERCURY VAPOR, 250 WATT	1.000	EACH
100 807-98716	KELLUM GRIP, STAINLESS STEEL	2.000	EACH

