

CALL ORDER : 140

CONTRACT ID : IB-30086-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	202-04345 UNDERGROUND STORAGE TANK, LIQUID WASTE DISPOSAL, A	1,200.000	GAL
11	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 3000 GAL	1.000	EACH
12	202-07601 TESTING FOR WASTE, A	2.000	EACH
13	202-09443 REGULATED MATERIALS, DISPOSE, A	100.000	CYS
14	202-09444 REGULATED MATERIALS, TRANSPORT, A	100.000	CYS
15	202-09445 REGULATED MATERIALS, REMOVE, A	100.000	CYS
16	203-02000 EXCAVATION, COMMON	37,705.000	CYS
17	203-02070 BORROW	40,100.000	CYS
18	204-02290 SETTLEMENT PLATE	10.000	EACH
19	204-08415 STAKES, SETTLEMENT	10.000	EACH
20	205-04931 SEDIMENT TRAP	1.000	EACH
21	205-06930 SPLASHPAD, RIPRAP	16.000	TON
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	125.000	TON
23	205-06937 TEMPORARY SILT FENCE	2,020.000	LFT
24	205-06938 TEMPORARY SLOPE DRAIN	311.000	LFT
25	206-51225 EXCAVATION, DRY	40.000	CYS
26	207-08264 SUBGRADE TREATMENT, TYPE II	7,691.000	SYS
27	211-06467 AGGREGATE FOR END BENT BACKFILL	78.000	CYS
28	211-09264 STRUCTURE BACKFILL, TYPE 1	606.000	CYS
29	211-09266 STRUCTURE BACKFILL, TYPE 3	1,462.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,230.000	TON
31	302-07455 DENSE GRADED SUBBASE	34.000	CYS
32	303-01180 COMPACTED AGGREGATE, NO. 53	1,850.000	TON
33	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
34	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,962.000	TON
35	402-07433 HMA SURFACE, TYPE B	580.000	TON
36	406-05520 ASPHALT FOR TACK COAT	1.800	TON
37	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
38	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	750.000	LFT
39	602-06729 BARRIER DELINEATOR	12.000	EACH
40	603-06040 FENCE, FARM FIELD, 47 IN.	10,412.000	LFT
41	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	200.000	SYS
42	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
43	615-06490 RIGHT OF WAY MARKER	11.000	EACH
44	616-02320 GEOTEXTILES	443.000	SYS
45	616-06405 RIPRAP, REVETMENT	183.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
47	621-06545 FERTILIZER	13.000	TON
48	621-06553 SEED MIXTURE, R	2,204.000	LBS
49	621-06555 SEED MIXTURE, P	3,009.000	LBS

CALL ORDER : 140

CONTRACT ID : IB-30086-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE		
50	621-06557 SEED MIXTURE, T	446.000	LBS
51	621-06565 MULCHING MATERIAL	112.000	TON
52	628-09402 FIELD OFFICE, B	12.000	MOS
53	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
54	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
55	701-06012 TEST PILE, RESTRIKE	2.000	EACH
56	701-06027 TEST PILE	2.000	EACH
57	701-93575 PILE, STEEL H, HP 14 X 73	1,445.000	LFT
58	702-51005 CONCRETE, A, SUBSTRUCTURE	78.200	CYS
59	702-51015 CONCRETE, B, FOOTINGS	4.500	CYS
60	703-51030 REINFORCING STEEL	5,338.000	LBS
61	703-51032 REINFORCING STEEL, EPOXY COATED	97,850.000	LBS
62	704-51002 CONCRETE, C, SUPERSTRUCTURE	261.900	CYS
63	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
64	706-51020 CONCRETE, C, RAILING	38.200	CYS
65	707-05985 STRUCTURAL MEMBERS, CONCRETE I-BEAM, IV, 54 IN. X 20 IN.	790.000	LFT
66	709-51821 SURFACE SEAL	LUMP	LUMP
67	711-51070 ANCHOR PLATE, AP 1	16.000	EACH
68	715-02246 PIPE END SECTION, 48 IN.	4.000	EACH
69	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	400.000	LFT
70	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	400.000	LFT
71	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN.	400.000	LFT
72	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	400.000	LFT
73	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN.	450.000	LFT
74	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	334.000	LFT
75	715-05212 PIPE, TYPE 4, CIRCULAR, 24 IN.	400.000	LFT
76	715-05407 PIPE, END BENT DRAIN, 6 IN.	152.000	LFT
77	715-05443 PIPE, DRAINTILE TERMINAL SECTION, 12 IN.	10.000	LFT
78	715-09446 PIPE, TYPE 4, CIRCULAR, 36 IN.	400.000	LFT
79	715-09447 PIPE, DRAIN TILE TERMINAL SECTION, 24 IN.	10.000	LFT
80	715-09448 PIPE, DRAIN TILE, TERMINAL SECTION, 36 IN.	10.000	LFT
81	715-46005 PIPE END SECTION, 15 IN.	12.000	EACH
82	731-93945 FACE PANELS, CONCRETE	3,595.000	SFT
83	731-93946 WALL ERECTION	3,595.000	SFT
84	731-93947 LEVELING PAD, CONCRETE	248.000	LFT
85	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
86	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
87	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
88	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
89	801-07118 BARRICADE, III-A	96.000	LFT
90	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	48.000	LFT
91	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	12.000	SFT
92	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	493.000	LFT
93	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	246.000	LFT
94	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	62.000	LFT
95	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,787.000	LFT
96	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	935.000	LFT
97	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,739.000	LFT

CALL ORDER : 170

CONTRACT ID : R -25921-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02279 CURB AND GUTTER, REMOVE	577.000	m
11	202-02637 PIPE, ABANDON AND GROUT	29.000	m
12	202-02928 CATCH BASIN, REMOVE	2.000	EACH
13	202-06580 CONTAMINATED SOIL, REMOVE	10.000	m3
14	202-52710 SIDEWALK, CONCRETE, REMOVE	1,113.000	m2
15	202-74075 OVERHEAD SIGN STRUCTURE, MONOTUBE, REMOVE	2.000	EACH
16	202-78515 TRAFFIC SIGNAL EQUIPMENT, REMOVE	LUMP	LUMP
17	202-91385 INLET, REMOVE	9.000	EACH
18	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
19	203-02000 EXCAVATION, COMMON	863.000	m3
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	448.420	m2
21	207-08268 SUBGRADE TREATMENT, TYPE IV	1,725.000	m2
22	210-05106 CONCRETE	13.000	EACH
23	210-07562 TEMPORARY	150.000	m
24	211-09265 STRUCTURE BACKFILL, TYPE 2	489.400	m3
25	306-08033 MILLING, ASPHALT, 25 mm	224.000	m2
26	306-08034 MILLING, ASPHALT, 38 mm	2,216.200	m2
27	306-08036 MILLING, ASPHALT, 50 mm	1,839.300	m2
28	306-08043 MILLING, TRANSITION	833.500	m2
29	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	561.600	Mg
30	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	642.600	Mg
31	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	466.600	Mg
32	406-05520 ASPHALT FOR TACK COAT	2.900	Mg
33	604-07896 CURB RAMP, CONCRETE, B	14.120	m2
34	604-07897 CURB RAMP, CONCRETE, C	9.940	m2
35	604-07900 CURB RAMP, CONCRETE, F	22.360	m2
36	604-07903 CURB RAMP, CONCRETE, K	23.360	m2
37	604-08373 SIDEWALK	933.630	m2
38	605-06120 CURB, CONCRETE	55.400	m
39	605-06140 CURB AND GUTTER, CONCRETE	538.800	m
40	610-08446 PCCP FOR APPROACHES, 150 mm	38.770	m2
41	610-09108 PCCP FOR APPROACHES, 225 mm	409.650	m2
42	615-06490 RIGHT OF WAY MARKER	7.000	EACH
43	615-06505 MONUMENT, B	6.000	EACH
44	621-03181 CLEANOUT, 100 mm	1.000	EACH
45	621-06567 WATER	16.800	kL
46	621-06575 SODDING, NURSERY	925.700	m2
47	628-09402 FIELD OFFICE, B	9.000	MOS
48	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
49	715-01841 PIPE, DUCTILE IRON, 375 mm	35.100	m

CALL ORDER : 170

CONTRACT ID : R -25921-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	715-02187 WATER VALVE BOX, ADJUST	3.000	EACH
51	715-03877 PIPE, DUCTILE IRON, 450 mm	28.500	m
52	715-05146 PIPE, TYPE 2, CIRCULAR, 150 mm	52.200	m
53	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	12.500	m
54	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	99.000	m
55	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	132.000	m
56	715-05156 PIPE, TYPE 2, CIRCULAR, 750 mm	3.000	m
57	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	35.100	Mg
58	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
59	720-45410 MANHOLE, C4	4.000	EACH
60	720-98174 INLET, B15	2.000	EACH
61	720-98555 INLET, C15	8.000	EACH
62	801-02595 CONTROLLER, RESET TIMING	1.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
64	801-06199 ROAD CLOSURE SIGN ASSEMBLY, PERMANENT	2.000	EACH
65	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	3,569.000	m
66	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	9.000	EACH
67	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	3.000	EACH
68	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 600 mm	84.300	m
69	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 200 mm	640.000	m
70	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
71	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
72	801-06710 FLASHING ARROW SIGN	400.000	DAY
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07118 BARRICADE, III-A	20.300	m
75	802-04314 SIGN	1.000	EACH
76	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	9.300	m
77	802-07159 CANTILEVER TRAFFIC SIGN SUPPORT FOUNDATION, II	5.000	EACH
78	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	18.940	m2
79	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	2.180	m2
80	802-76100 SPAN OVERHEAD SIGN STRUCTURE, MONOTUBE	2.000	EACH
81	802-76135 OVERHEAD SIGN STRUCTURE, CANTILEVER SINGLE ARM	1.000	EACH
82	805-01816 SIGNAL SUPPORT FOUNDATION, 900 mm X 900 mm X 2500 mm	3.000	EACH
83	805-01842 HANDHOLE, SIGNAL	6.000	EACH
84	805-01844 CONDUIT, STEEL, GALVANIZED, 50 mm, UNDERGROUND	89.000	m
85	805-02077 SIGNAL CANTILEVER STRUCTURE, 12.2 m ARM	1.000	EACH
86	805-03370 PEDESTRIAN SIGNAL HEAD, WITH INTERNATIONAL SYMBOLS, 460 mm	8.000	EACH
87	805-03582 SIGNAL AND LIGHTING COMBINATION POLE, 10.7 m SIGNAL ARM,	1.000	EACH
88	805-04973 CONDUIT	6.500	m
89	805-06641 SIGNAL TWIN ARM CANTILEVER STRUCTURE, 12 m AND 11 m	1.000	EACH
90	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
91	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	6.000	EACH
92	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	1.000	EACH
93	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
94	805-78467 SIGNAL CABLE, 3C 8GA.	72.500	m
95	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	754.000	m
96	805-78480 SIGNAL CABLE, 3C 14GA.	135.000	m
97	805-78485 SIGNAL CABLE, 5C 14GA.	90.000	m
98	805-78490 SIGNAL CABLE, 7C 14GA.	333.000	m

CALL ORDER : 170

CONTRACT ID : R -25921-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
99 805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	200.000	m
100 805-78785	SIGNAL DETECTOR HOUSING	5.000	EACH
101 805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	237.000	m
102 805-78900	PEDESTAL FOUNDATION, A	1.000	EACH
103 805-78925	CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
104 805-90005	SIGNAL PEDESTAL, 3.0 m	1.000	EACH
105 805-90187	CONDUIT, STEEL, GALVANIZED, 100 mm	28.500	m
106 805-90267	CONDUIT, STEEL, GALVANIZED, 75 mm	27.500	m
107 805-94971	FIBER OPTICS CABLE	281.000	m
108 805-94971	FIBER OPTICS CABLE	62.500	m
109 807-04652	SERVICE POINT	1.000	EACH
110 808-02066	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID WHITE CROSSHATCH	293.100	m
111 808-05866	PAVEMENT MESSAGE MARKING, REMOVE	12.200	m2
112 808-06368	TRANSVERSE MARKING, REMOVE	51.000	m
113 808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	389.800	m
114 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	243.200	m
115 808-06716	LINE, REMOVE	1,818.000	m
116 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	1,130.100	m
117 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	71.200	m
118 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
119 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	5.000	EACH
120 808-96016	LINE, THERMOPLASTIC, SOLID, YELLOW, 300 mm	4.500	m

CALL ORDER : 174

CONTRACT ID : R -28149-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNS, SIGNALS AND MEDIAN CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	240.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	5.000	EACH
15	202-02240 PAVEMENT REMOVAL	365.000	m2
16	202-02273 CENTER CURB, CONCRETE, REMOVE	2,341.000	m2
17	202-02274 CURB, CONCRETE, INTEGRAL, REMOVE	4,663.000	m
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
22	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
23	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
24	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
25	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
26	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
27	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
28	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
29	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
30	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
31	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
32	202-52710 SIDEWALK, CONCRETE, REMOVE	1,183.000	m2
33	202-74035 SIGN, REMOVE	118.000	EACH
34	202-91385 INLET, REMOVE	58.000	EACH
35	202-93047 MANHOLE, REMOVE	2.000	EACH
36	203-02000 EXCAVATION, COMMON	28,210.000	m3
37	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
38	205-06937 TEMPORARY SILT FENCE	710.000	m
39	207-08267 SUBGRADE TREATMENT, TYPE IIIA	6,816.000	m2
40	207-08268 SUBGRADE TREATMENT, TYPE IV	28,705.000	m2
41	210-06899 RADIO	3.000	EACH
42	211-09264 STRUCTURE BACKFILL, TYPE 1	7,455.000	m3
43	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	313.000	Mg
44	303-07449 COMPACTED AGGREGATE, NO. 73	26.000	Mg
45	306-08034 MILLING, ASPHALT, 38 mm	48,386.000	m2
46	306-08043 MILLING, TRANSITION	3,600.000	m2
47	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	5,852.000	Mg
48	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	1,970.000	Mg
49	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	8,821.000	Mg

CALL ORDER : 174

CONTRACT ID : R -28149-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNS, SIGNALS AND MEDIAN CONSTRUCTION		
50	401-07430 QC/QA-HMA, 5, 76, INTERMEDIATE, OG25.0 mm	3,885.000	Mg
51	406-05520 ASPHALT FOR TACK COAT	37.000	Mg
52	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
53	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
54	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
55	601-95434 HANDRAIL, STEEL PIPE, 37.5 mm	10.500	m
56	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	103.000	m
57	603-03829 FENCE	655.500	m
58	604-06070 SIDEWALK, CONCRETE	5,372.000	m2
59	604-07483 HMA FOR SIDEWALK	221.000	Mg
60	604-07900 CURB RAMP, CONCRETE, F	12.000	m2
61	604-07901 CURB RAMP, CONCRETE, G	180.000	m2
62	604-07902 CURB RAMP, CONCRETE, H	22.000	m2
63	604-44251 STEPS, CONCRETE	1.100	m3
64	605-06090 CURB, INTEGRAL, CONCRETE	26.000	m
65	605-06105 CURB, INTEGRAL, CONCRETE, MODIFIED	7.000	m
66	605-06120 CURB, CONCRETE	483.000	m
67	605-06140 CURB AND GUTTER, CONCRETE	4,836.000	m
68	605-06255 CENTER CURB, D, CONCRETE	423.000	m2
69	610-07487 HMA FOR APPROACHES, TYPE B	3,423.000	Mg
70	610-08446 PCCP FOR APPROACHES, 150 mm	2,625.000	m2
71	610-09108 PCCP FOR APPROACHES, 225 mm	3,064.000	m2
72	611-06497 MAILBOX ASSEMBLY, SINGLE	68.000	EACH
73	615-06490 RIGHT OF WAY MARKER	135.000	EACH
74	615-06500 MONUMENT, A	7.000	EACH
75	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
76	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
77	621-02770 EROSION CONTROL BLANKET	515.000	m2
78	621-04258 SEED MIXTURE	5.500	kg
79	621-04316 SPADE EDGE	12.000	m
80	621-06545 FERTILIZER	0.570	Mg
81	621-06567 WATER	353.000	kL
82	621-06570 TOP SOIL	210.300	m3
83	621-06575 SODDING, NURSERY	19,580.000	m2
84	621-98038 MULCH, HARDWOOD SHREDDED BARK	220.100	m3
85	622-01937 PLANT	747.000	EACH
86	622-05641 PLANT, DECIDUOUS SHRUB, OVER 900 TO 1200 mm	48.000	EACH
87	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM OVER 32 TO 50 mm	107.000	EACH
88	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 50 TO 63 mm	44.000	EACH
89	622-05654 PLANT, PERENNIAL	367.000	EACH
90	628-09403 FIELD OFFICE, C	48.000	MOS
91	703-51030 REINFORCING STEEL	24.000	kg
92	714-07665 RETAINING WALL	LUMP	LUMP
93	715-05024 PIPE, TYPE 2, CIRCULAR, 900 mm	35.000	m
94	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	5,468.000	m
95	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	4,271.000	m
96	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	674.000	m
97	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	465.000	m
98	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	19.500	m

CALL ORDER : 174

CONTRACT ID : R -28149-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNS, SIGNALS AND MEDIAN CONSTRUCTION			
99	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	754.000	Mg
100	715-09064 VIDEO INSPECTION FOR PIPE	5,462.000	m
101	715-46040 PIPE END SECTION, 900 mm	1.000	EACH
102	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
103	718-52610 AGGREGATE FOR UNDERDRAINS	1,128.000	m3
104	718-99153 GEOTEXTILES FOR UNDERDRAIN	16,622.000	m2
105	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
106	720-44000 CASTING, ADJUST TO GRADE	78.000	EACH
107	720-44296 CAP INLET	3.000	EACH
108	720-45035 INLET, F7	1.000	EACH
109	720-45075 INLET, R13	1.000	EACH
110	720-45265 PIPE CATCH BASIN, 375 mm	1.000	EACH
111	720-45410 MANHOLE, C4	10.000	EACH
112	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	30.000	m
113	720-93409 INLET, B15, MODIFIED	35.000	EACH
114	720-95157 CATCH BASIN, R13, MODIFIED	2.000	EACH
115	720-95422 MANHOLE, J4	7.000	EACH
116	720-98174 INLET, B15	4.000	EACH
117	720-98555 INLET, C15	142.000	EACH
118	720-99416 CATCH BASIN, B15	13.000	EACH
119	720-99417 CATCH BASIN, C15	22.000	EACH
120	732-08419 MODULAR BLOCK WALL	558.000	m2
121	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	748.000	m2
122	732-08421 MODULAR BLOCK WALL ERECTION	1,306.000	m2
123	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	97.000	EACH
124	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
125	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	30,053.000	m
126	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	10,793.000	m
127	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	68.000	EACH
128	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 600 mm	308.000	m
129	801-06640 CONSTRUCTION SIGN, A	49.000	EACH
130	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
131	801-06710 FLASHING ARROW SIGN	600.000	DAY
132	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
133	801-07119 BARRICADE, III-B	87.000	m
134	801-07612 TEMPORARY PAVEMENT MARKING, 600 mm	692.000	m
135	801-94295 SIGNAL HEAD, RELOCATE	1.000	EACH
136	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	72.000	m
137	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	72.000	m
138	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	59.000	m2
139	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	11.000	m2
140	802-76045 SIGN, SHEET ENCAPSULATED LENS WITH LEGEND, 3.18 mm THICKNESS	32.000	m2
141	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	17.000	EACH
142	805-01842 HANDHOLE, SIGNAL	46.000	EACH
143	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
144	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 450mm	6.000	EACH
145	805-02328 SIGNAL CABLE, 1C 14GA.	4,894.000	m
146	805-02373 INTERCONNECT CABLE, FIBER OPTIC	812.000	m
147	805-06592 CONDUIT, STEEL, GALVANIZED, 50 mm	2,142.000	m

CALL ORDER : 174

CONTRACT ID : R -28149-C

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNS, SIGNALS AND MEDIAN CONSTRUCTION			
148	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	1.000	EACH
149	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	3.000	EACH
150	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 305 mm RED, AMBER, GREEN	35.000	EACH
151	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 305 mm RED, AMBER, GREEN,	7.000	EACH
152	805-78370 PEDESTRIAN PUSH BUTTON	6.000	EACH
153	805-78415 SPAN, CATENARY, AND TETHER	17.000	EACH
154	805-78420 DISCONNECT HANGER	17.000	EACH
155	805-78445 SIGNAL SERVICE	5.000	EACH
156	805-78467 SIGNAL CABLE, 3C 8GA.	75.000	m
157	805-78480 SIGNAL CABLE, 3C 14GA.	435.000	m
158	805-78485 SIGNAL CABLE, 5C 14GA.	782.000	m
159	805-78490 SIGNAL CABLE, 7C 14GA.	1,592.000	m
160	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,402.000	m
161	805-78746 PREFORMED LOOP DETECTORS	923.000	m
162	805-78785 SIGNAL DETECTOR HOUSING	35.000	EACH
163	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,914.000	m
164	805-78925 CONTROLLER CABINET FOUNDATION, P1	4.000	EACH
165	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	17.000	EACH
166	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	53.000	EACH
167	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	1,468.000	m
168	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,512.000	m
169	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	1,014.000	m
170	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	6,798.000	m
171	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	308.000	m
172	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	972.000	m
173	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	68.000	EACH
174	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	55.000	EACH
175	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	710.000	EACH

CALL ORDER : 180

CONTRACT ID : R -29089-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	9.000	MOS
5	105-08523 RADIO SERVICE	18.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02241 GUARDRAIL, REMOVE	88.000	LFT
16	202-02271 HEADWALL, REMOVE	3.000	EACH
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-91385 INLET, REMOVE	1.000	EACH
19	202-96133 PIPE, REMOVE	204.000	LFT
20	203-02000 EXCAVATION, COMMON	18,802.000	CYS
21	205-03371 SEDIMENT, REMOVE	70.000	CYS
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	70.000	TON
23	205-06932 TEMPORARY CHECK DAM, STRAW BALES	300.000	LFT
24	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
25	205-06937 TEMPORARY SILT FENCE	1,093.000	LFT
26	207-08263 SUBGRADE TREATMENT, TYPE IA	6,192.000	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	311.000	SYS
28	211-02050 B BORROW	3,900.000	CYS
29	211-09264 STRUCTURE BACKFILL, TYPE 1	237.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,171.000	TON
31	303-02051 STONE, NO 2	50.000	TON
32	306-08043 MILLING, TRANSITION	585.000	SYS
33	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
34	401-07333 QC/QA-HMA, 2, 76, SURFACE, 9.5 mm	499.000	TON
35	401-07402 QC/QA-HMA, 2, 76, INTERMEDIATE, 19.0 mm	751.000	TON
36	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,401.000	TON
37	406-05520 ASPHALT FOR TACK COAT	6.000	TON
38	610-07487 HMA FOR APPROACHES, TYPE B	86.000	TON
39	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
40	615-06490 RIGHT OF WAY MARKER	27.000	EACH
41	615-06505 MONUMENT, B	7.000	EACH
42	616-02320 GEOTEXTILES	2,236.000	SYS
43	616-05688 RIPRAP, CLASS 1	251.000	TON
44	616-06405 RIPRAP, REVETMENT	941.500	TON
45	616-06451 RIPRAP, UNIFORM	429.000	TON
46	621-02770 EROSION CONTROL BLANKET	850.000	SYS
47	621-06545 FERTILIZER	0.800	TON
48	621-06553 SEED MIXTURE, R	294.000	LBS
49	621-06557 SEED MIXTURE, T	69.100	LBS

CALL ORDER : 180

CONTRACT ID : R -29089-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGHT DISTANCE IMPROVEMENT			
50	621-06565 MULCHING MATERIAL	5.300	TON
51	621-06567 WATER	3.500	KGAL
52	621-06574 SODDING	880.000	SYS
53	628-09402 FIELD OFFICE, B	9.000	MOS
54	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
55	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	150.000	LFT
56	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	75.000	LFT
57	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	115.000	LFT
58	715-09064 VIDEO INSPECTION FOR PIPE	110.000	LFT
59	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
60	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
61	715-46040 PIPE END SECTION, 36 IN.	4.000	EACH
62	720-45030 INLET, E7	1.000	EACH
63	720-45069 INLET, P12	1.000	EACH
64	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
65	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
66	801-06625 DETOUR ROUTE MARKER ASSEMBLY	66.000	EACH
67	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
68	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
69	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
70	801-07118 BARRICADE, III-A	6.000	LFT
71	801-07119 BARRICADE, III-B	10.000	LFT
72	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	112.250	LFT
73	802-05703 SIGN POST, SQUARE, 3, REINFORCED ANCHOR BASE	46.500	LFT
74	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	13.000	EACH
75	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	64.750	SFT
76	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	8.000	SFT
77	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	41.000	SFT
78	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,488.000	LFT
79	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,730.000	LFT
80	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	37.000	LFT
81	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	46.000	EACH
82	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	46.000	EACH

CALL ORDER : 190

CONTRACT ID : R -29090-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02264 TREE, 42 IN., REMOVE	4.000	EACH
10	202-02278 CURB, CONCRETE, REMOVE	427.400	LFT
11	202-02928 CATCH BASIN, REMOVE	2.000	EACH
12	203-02000 EXCAVATION, COMMON	508.000	CYS
13	203-02070 BORROW	55.000	CYS
14	205-06937 TEMPORARY SILT FENCE	416.000	LFT
15	207-08268 SUBGRADE TREATMENT, TYPE IV	847.300	SYS
16	211-02050 B BORROW	1.900	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	97.600	TON
18	306-08036 MILLING, ASPHALT, 2 IN.	2,093.800	SYS
19	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	229.000	TON
20	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	189.000	TON
21	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	286.900	TON
22	406-05520 ASPHALT FOR TACK COAT	0.700	TON
23	604-07897 CURB RAMP, CONCRETE, C	19.200	SYS
24	604-91531 SIDEWALK, CONCRETE, 4 IN.	42.600	SYS
25	605-06120 CURB, CONCRETE	403.600	LFT
26	610-07486 HMA FOR APPROACHES, TYPE A	24.300	TON
27	610-07712 PCCP FOR APPROACHES, 6 IN.	212.300	SYS
28	615-06490 RIGHT OF WAY MARKER	9.000	EACH
29	615-06505 MONUMENT, B	6.000	EACH
30	621-06574 SODDING	633.700	SYS
31	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
32	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
33	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	7.000	LFT
34	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
35	720-45250 CATCH BASIN, K10	1.000	EACH
36	720-94157 MANHOLE, C	1.000	EACH
37	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	311.000	LFT
38	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
39	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	100.500	LFT
42	802-07060 SIGN, SHEET, RELOCATE	16.000	EACH
43	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	48.000	SFT
44	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	267.600	LFT
45	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	192.000	LFT
46	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	62.800	LFT
47	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	208.500	LFT
48	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	821.200	LFT

CALL ORDER : 200

CONTRACT ID : R -29455-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	108-01614 PARTNERING OVERHEAD	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-01261 TESTING FOR ASBESTOS	2.000	EACH
11	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
12	202-02278 CURB, CONCRETE, REMOVE	911.000	LFT
13	202-02928 CATCH BASIN, REMOVE	5.000	EACH
14	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
15	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
16	202-74025 FENCE, REMOVE	22.000	LFT
17	202-74035 SIGN, REMOVE	40.000	EACH
18	202-90277 DETECTOR HOUSING, REMOVE	3.000	EACH
19	202-91385 INLET, REMOVE	2.000	EACH
20	202-93047 MANHOLE, REMOVE	1.000	EACH
21	203-02000 EXCAVATION, COMMON	21,890.000	CYS
22	205-06933 TEMPORARY DITCH INLET PROTECTION	4.000	EACH
23	205-06937 TEMPORARY SILT FENCE	5,280.000	LFT
24	207-08263 SUBGRADE TREATMENT, TYPE IA	49,470.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	6,845.000	SYS
26	210-07739 TEMPORARY	194.000	EACH
27	210-07739 TEMPORARY	1.000	EACH
28	210-07764 IRRIGATION SYSTEM	LUMP	LUMP
29	210-09164 PAVING SYSTEM	637.000	SYS
30	211-09264 STRUCTURE BACKFILL, TYPE 1	36,524.000	CYS
31	211-09265 STRUCTURE BACKFILL, TYPE 2	180.000	CYS
32	211-09267 STRUCTURE BACKFILL, TYPE 4	9.000	CYS
33	302-07455 DENSE GRADED SUBBASE	259.000	CYS
34	303-07449 COMPACTED AGGREGATE, NO. 73	263.000	TON
35	304-07491 HMA PATCHING, TYPE C	55.000	TON
36	304-07493 WIDENING WITH HMA, TYPE B	47.000	TON
37	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,809.000	SYS
38	307-05402 CEMENT	1,012.000	SYS
39	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	3,784.000	TON
40	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	5,906.000	TON
41	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	20,600.000	TON
42	406-05520 ASPHALT FOR TACK COAT	45.000	TON
43	502-06457 PCCP, 9 IN.	775.000	SYS
44	603-03398 FENCE, RELOCATE	351.000	LFT
45	604-07894 CURB RAMP, CONCRETE, A	14.000	SYS
46	604-07897 CURB RAMP, CONCRETE, C	143.000	SYS
47	604-07901 CURB RAMP, CONCRETE, G	92.000	SYS
48	604-07904 CURB RAMP, CONCRETE, L	164.000	SYS
49	604-91531 SIDEWALK, CONCRETE, 4 IN.	6,542.000	SYS

CALL ORDER : 200

CONTRACT ID : R -29455-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	605-06120 CURB, CONCRETE	1,573.000	LFT
51	605-06121 CURB, CONCRETE, B	874.000	LFT
52	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	15,407.000	LFT
53	605-06235 CENTER CURB, D, CONCRETE, MODIFIED	55.000	LFT
54	610-07487 HMA FOR APPROACHES, TYPE B	334.000	TON
55	610-08446 PCCP FOR APPROACHES, 6 IN.	2,518.000	SYS
56	610-09108 PCCP FOR APPROACHES, 9 IN.	2,834.000	SYS
57	611-06497 MAILBOX ASSEMBLY, SINGLE	62.000	EACH
58	615-06505 MONUMENT, B	21.000	EACH
59	615-06510 MONUMENT, C	2.000	EACH
60	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
61	616-02320 GEOTEXTILES	32.000	SYS
62	616-06405 RIPRAP, REVETMENT	17.000	TON
63	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
64	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	1,000.000	SYS
65	621-04317 MULCHED SEEDING	723.000	SYS
66	621-06559 MULCHED SEEDING, R	1,940.000	SYS
67	621-06567 WATER	78.000	KGAL
68	621-06575 SODDING, NURSERY	21,436.000	SYS
69	621-98038 MULCH, HARDWOOD SHREDDED BARK	138.000	CYS
70	622-05635 PLANT, CONIFEROUS EVERGREEN, PROSTRATE, BROAD SPREADING,	32.000	EACH
71	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	68.000	EACH
72	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	56.000	EACH
73	622-05645 PLANT, DECIDUOUS TREE, MULTI-STEM, OVER 72 TO 96 IN.	48.000	EACH
74	622-05654 PLANT, PERENNIAL	508.000	EACH
75	622-98200 SIGN, DO NOT DISTURB	12.000	EACH
76	628-09402 FIELD OFFICE, B	24.000	MOS
77	710-51864 FIELD DRILLED HOLE	6.000	EACH
78	711-90932 EDGING, STEEL	611.000	LFT
79	715-01902 WATER SERVICE LINE, 2 IN.	225.000	LFT
80	715-02181 SANITARY SEWER SERVICE ADJUSTMENT	20.000	LFT
81	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	1,146.000	LFT
82	715-05061 WATER SERVICE LINE, 6 IN.	738.000	LFT
83	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	5,970.000	LFT
84	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,341.000	LFT
85	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	2,693.000	LFT
86	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	1,017.000	LFT
87	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	1,466.000	LFT
88	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	322.000	LFT
89	715-05162 PIPE, TYPE 2, CIRCULAR, 54 IN.	1,290.000	LFT
90	715-05408 PIPE, SANITARY SEWER, 8 IN.	1,809.000	LFT
91	715-05413 PIPE, SANITARY SEWER, 18 IN.	333.000	LFT
92	715-05711 PIPE, SANITARY SEWER, 6 IN.	86.000	LFT
93	715-08250 PIPE, DUCTILE IRON, 12 IN.	40.000	LFT
94	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	18.000	TON
95	715-09064 VIDEO INSPECTION FOR PIPE	19,713.000	LFT
96	715-09191 PIPE, TYPE 2, DEFORMED, MIN. AREA 7.4 SFT.	127.000	LFT
97	715-91739 WATER MAIN, DUCTILE IRON, 8 IN.	797.000	LFT
98	715-92544 WATER MAIN, DUCTILE IRON, 12 IN.	9,131.000	LFT

CALL ORDER : 200

CONTRACT ID : R -29455-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99	715-96629 WATER SERVICE LINE, 1 IN.	1,550.000	LFT
100	716-09360 PIPE INSTALLATION, TRENCHLESS, 3 IN.	128.000	LFT
101	716-09396 PIPE INSTALLATION, TRENCHLESS, 2 IN.	153.000	LFT
102	720-03194 MANHOLE	2.000	EACH
103	720-03194 MANHOLE	1.000	EACH
104	720-03194 MANHOLE	1.000	EACH
105	720-03194 MANHOLE	1.000	EACH
106	720-04666 CATCH BASIN	1.000	EACH
107	720-44000 CASTING, ADJUST TO GRADE	31.000	EACH
108	720-45030 INLET, E7	1.000	EACH
109	720-45105 INLET, A2, MODIFIED	3.000	EACH
110	720-45115 INLET, A8, MODIFIED	88.000	EACH
111	720-45315 CATCH BASIN, A8, MODIFIED	91.000	EACH
112	720-45510 MANHOLE, C4, MODIFIED	39.000	EACH
113	720-45510 MANHOLE, C4, MODIFIED	8.000	EACH
114	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	11.000	LFT
115	720-90349 MANHOLE, C8	11.000	EACH
116	720-91110 MANHOLE, N4	1.000	EACH
117	720-91973 MANHOLE, H4	2.000	EACH
118	720-94612 MANHOLE, K4	22.000	EACH
119	720-94840 CASTING, ADJUST TO GRADE, WATER VALVE	16.000	EACH
120	720-95409 MANHOLE, J4, MODIFIED	16.000	EACH
121	720-96999 FIRE HYDRANT ASSEMBLY	23.000	EACH
122	720-98869 MANHOLE, L4, MODIFIED	2.000	EACH
123	732-02433 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 12 IN.	17.000	EACH
124	732-02532 VALVE WITH BOX, RESTRAINED, GATE, DUCTILE IRON, 8 IN.	10.000	EACH
125	732-06050 CAP	2.000	EACH
126	732-94780 WATER SERVICE CONNECTION	7.000	EACH
127	732-94780 WATER SERVICE CONNECTION	22.000	EACH
128	732-94780 WATER SERVICE CONNECTION	48.000	EACH
129	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	21.000	EACH
130	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
131	801-04308 ROAD CLOSURE SIGN ASSEMBLY	24.000	EACH
132	801-06625 DETOUR ROUTE MARKER ASSEMBLY	24.000	EACH
133	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
134	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
135	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
136	801-07119 BARRICADE, III-B	552.000	LFT
137	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	946.000	LFT
138	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	405.000	SFT
139	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	176.000	SFT
140	805-01479 CONTROLLER CABINET FOUNDATION, P1, MODIFIED	1.000	EACH
141	805-01842 HANDHOLE, SIGNAL	4.000	EACH
142	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	3.000	EACH
143	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	1.000	EACH
144	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
145	805-02658 CABLE, COAXIAL	618.000	LFT
146	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	4.000	EACH
147	805-04973 CONDUIT	171.000	LFT

CALL ORDER : 200

CONTRACT ID : R -29455-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
148	805-05870 SIGNAL SUPPORT FOUNDATION	4.000	EACH
149	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	114.000	LFT
150	805-06595 CONDUIT, PVC, 2 IN.	463.000	LFT
151	805-06600 CONDUIT, PVC, 3 IN.	172.000	LFT
152	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
153	805-06886 VIDEO VEHICLE DETECTOR SYSTEM WITH 4 CAMERAS	1.000	EACH
154	805-08093 POLE	4.000	EACH
155	805-08129 SIGNAL CABLE	351.000	LFT
156	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
157	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	4.000	EACH
158	805-78355 PEDESTRIAN SIGNAL HEAD, 12 IN.	8.000	EACH
159	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
160	805-78467 SIGNAL CABLE, 3C 8GA.	14.000	LFT
161	805-78485 SIGNAL CABLE, 5C 14GA.	642.000	LFT
162	805-78490 SIGNAL CABLE, 7C 14GA.	1,207.000	LFT
163	805-95888 WIRE, NO. 8 COPPER, 1C	5,476.000	LFT
164	805-95889 WIRE, NO. 10 COPPER, 1C	1,826.000	LFT
165	805-95890 WIRE, NO. 12 COPPER, 1/C	1,104.000	LFT
166	805-99338 WIRE, AWG, NO. 6 COPPER, GROUND, 1/C	128.000	LFT
167	807-02782 LUMINAIRE MAST ARM, 12 FT.	4.000	EACH
168	807-03951 LIGHT POLE, ORNAMENTAL	16.000	EACH
169	807-03968 CONDUIT, PVC, 1 IN., SCHEDULE 80, FOR ELECTRIC	1,825.000	LFT
170	807-04866 LUMINAIRE	2.000	EACH
171	807-04922 LIGHT STANDARD FOUNDATION	16.000	EACH
172	807-86805 SERVICE POINT, I	2.000	EACH
173	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	1,941.000	LFT
174	808-04767 LINE	451.000	LFT
175	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	45.000	LFT
176	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	480.000	LFT
177	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	14,114.000	LFT
178	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15,376.000	LFT
179	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	483.000	LFT
180	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	472.000	LFT
181	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	473.000	LFT
182	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	48.000	EACH
183	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	44.000	EACH
184	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	3,233.000	LFT

CALL ORDER : 210

CONTRACT ID : R -29644-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
5	202-02236 SURFACE, REMOVE	231.000	SYS
6	205-04931 SEDIMENT TRAP	1.000	EACH
7	205-06937 TEMPORARY SILT FENCE	210.000	LFT
8	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	2,394.000	CYS
9	210-05758 BUILDING	LUMP	LUMP
10	210-05758 BUILDING	LUMP	LUMP
11	210-07643 TREE PROTECTION	12.000	EACH
12	211-02050 B BORROW	1,819.000	CYS
13	211-09265 STRUCTURE BACKFILL, TYPE 2	163.000	CYS
14	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	14.000	TON
15	502-06627 PCCP, 6 IN.	127.800	SYS
16	601-03970 RAILING, WOOD, 4 FT. 6 IN.	43.000	LFT
17	604-91531 SIDEWALK, CONCRETE, 4 IN.	57.000	SYS
18	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
19	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	840.000	SYS
20	621-06554 SEED MIXTURE, U	19.000	LBS
21	621-06565 MULCHING MATERIAL	0.220	TON
22	621-06570 TOP SOIL	135.000	CYS
23	621-08149 GRASS	45.560	SYS
24	628-09402 FIELD OFFICE, B	12.000	MOS
25	702-51005 CONCRETE, A, SUBSTRUCTURE	118.600	CYS
26	702-51015 CONCRETE, B, FOOTINGS	83.000	CYS
27	703-51030 REINFORCING STEEL	20,831.000	LBS
28	731-03915 ARCHITECTURAL SURFACE TREATMENT	416.200	SFT
29	732-90573 WATER SERVICE LINE, 0.75 IN	210.000	LFT

CALL ORDER : 220

CONTRACT ID : R -29645-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE / PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02278 CURB, CONCRETE, REMOVE	43.000	LFT
9	202-52710 SIDEWALK, CONCRETE, REMOVE	12.000	SYS
10	203-02000 EXCAVATION, COMMON	463.000	CYS
11	203-02020 EXCAVATION, UNCLASSIFIED	691.000	CYS
12	203-02070 BORROW	1,080.000	CYS
13	205-06937 TEMPORARY SILT FENCE	3,318.000	LFT
14	210-08156 RESTROOM	1.000	EACH
15	211-02050 B BORROW	343.000	CYS
16	211-07454 STRUCTURE BACKFILL	9.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,063.000	TON
18	303-07662 STONE	23.000	TON
19	402-07432 HMA SURFACE, TYPE A	236.000	TON
20	402-07435 HMA INTERMEDIATE, TYPE A	414.000	TON
21	406-05521 ASPHALT FOR TACK COAT	2,851.000	SYS
22	502-06327 PCCP, 10 IN.	79.000	SYS
23	604-07896 CURB RAMP, CONCRETE, B	43.000	SYS
24	604-07901 CURB RAMP, CONCRETE, G	15.000	SYS
25	604-91531 SIDEWALK, CONCRETE, 4 IN.	385.000	SYS
26	605-06120 CURB, CONCRETE	294.000	LFT
27	616-06451 RIPRAP, UNIFORM	2.000	TON
28	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
29	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	1,737.000	SYS
30	621-06560 MULCHED SEEDING, U	1,581.000	SYS
31	621-06567 WATER	1.000	KGAL
32	621-06570 TOP SOIL	320.000	CYS
33	621-06574 SODDING	1,892.000	SYS
34	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	9.000	EACH
35	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	16.000	EACH
36	622-05654 PLANT, PERENNIAL	1,367.000	EACH
37	622-98200 SIGN, DO NOT DISTURB	13.000	EACH
38	628-09401 FIELD OFFICE, A	6.000	MOS
39	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
40	715-01765 PIPE END SECTION, PRECAST CONCRETE, 12 IN.	2.000	EACH
41	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	51.000	LFT
42	715-05756 PIPE EXTENSION, CIRCULAR, 12 IN.	9.000	LFT
43	720-45035 INLET, F7	1.000	EACH
44	720-45145 INLET, J10, MODIFIED	2.000	EACH
45	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
46	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
47	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
48	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
49	801-06645 CONSTRUCTION SIGN, B	4.000	EACH

CALL ORDER : 220

CONTRACT ID : R -29645-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE / PEDESTRIAN FACILITIES			
50	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
51	801-07118 BARRICADE, III-A	60.000	LFT
52	801-07119 BARRICADE, III-B	60.000	LFT
53	802-04993 SIGN	LUMP	LUMP
54	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	351.000	LFT
55	802-07060 SIGN, SHEET, RELOCATE	17.000	EACH
56	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	78.000	SFT
57	808-02976 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, (HWY), 4 FT.	2.000	EACH
58	808-02977 TRANSVERSE MARKING, THERMOPLASTIC, BIKE SYMBOL	2.000	EACH
59	808-03114 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, (XING) 8 FT.	2.000	EACH
60	808-03115 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (XING), 4 FT.	2.000	EACH
61	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	21.000	LFT
62	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	533.000	LFT
63	808-97664 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 230

CONTRACT ID : R -30034-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	12.000	LFT
12	304-07783 HMA PATCHING, TYPE D	1,155.000	TON
13	306-08043 MILLING, TRANSITION	1,978.000	SYS
14	306-08563 MILLING ASPHALT, 1 1/4 IN.	201,930.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	17,492.000	TON
17	404-05511 SEAL COAT, 2	8,000.000	SYS
18	406-05520 ASPHALT FOR TACK COAT	53.000	TON
19	506-06333 PCCP PATCHING, FULL DEPTH	760.000	SYS
20	602-01064 BARRIER, CONCRETE	12.000	LFT
21	628-09402 FIELD OFFICE, B	12.000	MOS
22	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
23	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	40,260.000	LFT
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	72,468.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	16,454.000	LFT
28	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	50,521.000	LFT
29	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	3,575.000	LFT
30	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	340.000	LFT
31	808-06716 LINE, REMOVE	1,604.000	LFT
32	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	50,521.000	LFT
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,382.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,382.000	EACH

CALL ORDER : 240

CONTRACT ID : R -30190-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	15.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.000	EACH
13	202-02240 PAVEMENT REMOVAL	958.000	SYS
14	203-02000 EXCAVATION, COMMON	2,822.000	CYS
15	205-06937 TEMPORARY SILT FENCE	660.000	LFT
16	207-08266 SUBGRADE TREATMENT, TYPE III	197.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	292.000	SYS
18	207-08268 SUBGRADE TREATMENT, TYPE IV	6,560.000	SYS
19	211-09264 STRUCTURE BACKFILL, TYPE 1	198.000	CYS
20	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	24.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	122.000	TON
22	304-07490 HMA PATCHING, TYPE B	140.000	TON
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	2,685.000	TON
25	402-07433 HMA SURFACE, TYPE B	503.000	TON
26	402-07438 HMA INTERMEDIATE, TYPE B	863.000	TON
27	406-05520 ASPHALT FOR TACK COAT	4.710	TON
28	604-07894 CURB RAMP, CONCRETE, A	7.000	SYS
29	604-07900 CURB RAMP, CONCRETE, F	50.000	SYS
30	604-44251 STEPS, CONCRETE	3.000	CYS
31	604-91404 SIDEWALK, CONCRETE, 5 IN.	856.000	SYS
32	605-06140 CURB AND GUTTER, CONCRETE	1,531.000	LFT
33	610-08446 PCCP FOR APPROACHES, 6 IN.	292.000	SYS
34	615-06505 MONUMENT, B	9.000	EACH
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
36	621-06545 FERTILIZER	2.000	TON
37	621-06554 SEED MIXTURE, U	225.000	LBS
38	621-06557 SEED MIXTURE, T	225.000	LBS
39	621-06565 MULCHING MATERIAL	3.000	TON
40	621-06575 SODDING, NURSERY	564.000	SYS
41	622-02564 LANDSCAPING	LUMP	LUMP
42	628-09402 FIELD OFFICE, B	15.000	MOS
43	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
44	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	338.000	LFT
45	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	81.000	LFT
46	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
47	720-45045 INLET, J10	5.000	EACH
48	720-45055 INLET, M10	4.000	EACH
49	720-45250 CATCH BASIN, K10	1.000	EACH

CALL ORDER : 240

CONTRACT ID : R -30190-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
50	720-45410 MANHOLE, C4	2.000	EACH
51	720-92240 CATCH BASIN, W4	1.000	EACH
52	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	12,930.000	LFT
53	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	84.000	LFT
54	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
55	801-06645 CONSTRUCTION SIGN, B	15.000	EACH
56	801-06710 FLASHING ARROW SIGN	1,100.000	DAY
57	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
58	801-07119 BARRICADE, III-B	96.000	LFT
59	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
60	801-94295 SIGNAL HEAD, RELOCATE	24.000	EACH
61	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	42.000	LFT
62	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	28.500	SFT
63	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	12.000	SFT
64	805-01579 MISCELLANEOUS EQUIPMENT FOR SYSTEM LOOP AND INTERCONNECT	LUMP	LUMP
65	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	4.000	EACH
66	805-01842 HANDHOLE, SIGNAL	8.000	EACH
67	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	2.000	EACH
68	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	2.000	EACH
69	805-02151 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 12 IN.	8.000	EACH
70	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	470.000	LFT
71	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
72	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	6.000	EACH
73	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
74	805-78370 PEDESTRIAN PUSH BUTTON	8.000	EACH
75	805-78412 SIGNAL PEDESTAL, 9 FT.	1.000	EACH
76	805-78445 SIGNAL SERVICE	1.000	EACH
77	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	LFT
78	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,100.000	LFT
79	805-78480 SIGNAL CABLE, 3C 14GA.	810.000	LFT
80	805-78485 SIGNAL CABLE, 5C 14GA.	1,150.000	LFT
81	805-78490 SIGNAL CABLE, 7C 14GA.	440.000	LFT
82	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,895.000	LFT
83	805-78746 PREFORMED LOOP DETECTORS	1,290.000	LFT
84	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
85	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	340.000	LFT
86	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
87	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	6.000	EACH
88	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	370.000	LFT
89	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	380.000	LFT
90	808-06716 LINE, REMOVE	9,000.000	LFT
91	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,510.000	LFT
92	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	133.000	LFT
93	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	500.000	LFT
94	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	7.000	EACH
95	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH

CALL ORDER : 250

CONTRACT ID : R -30263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07783 HMA PATCHING, TYPE D	13,702.000	TON
12	306-08036 MILLING, ASPHALT, 2 IN.	79,687.000	SYS
13	306-08432 MILLING, APPROACH	6,606.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07353 QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	9,961.000	TON
16	406-05520 ASPHALT FOR TACK COAT	37.000	TON
17	610-07788 HMA FOR APPROACHES, TYPE D	826.000	TON
18	628-09401 FIELD OFFICE, A	8.000	MOS
19	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
20	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
21	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,500.000	LFT
22	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,500.000	LFT
23	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
24	801-06710 FLASHING ARROW SIGN	90.000	DAY
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
27	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	33.000	EACH
28	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	13,750.000	LFT
29	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,375.000	LFT
30	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	4,400.000	LFT
31	808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROWS	37.000	EACH
32	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	16.000	EACH
33	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	32,355.000	LFT
34	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	28,000.000	LFT
35	808-75061 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	6,980.000	LFT
36	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	506.000	LFT
37	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	460.000	EACH
38	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	460.000	EACH

CALL ORDER : 260

CONTRACT ID : R -30936-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.000	EACH
10	202-02240 PAVEMENT REMOVAL	13,068.000	SYS
11	202-02273 CENTER CURB, CONCRETE, REMOVE	100.000	SYS
12	202-02637 PIPE, ABANDON AND GROUT FILL	1.000	LFT
13	202-06541 REMOVE	28.000	EACH
14	203-02000 EXCAVATION, COMMON	14,698.000	CYS
15	205-03371 SEDIMENT, REMOVE	100.000	CYS
16	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
17	205-06937 TEMPORARY SILT FENCE	590.000	LFT
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,622.000	SYS
19	207-08268 SUBGRADE TREATMENT, TYPE IV	38,517.000	SYS
20	211-09264 STRUCTURE BACKFILL, TYPE 1	9,249.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,750.000	TON
22	304-07490 HMA PATCHING, TYPE B	70.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,815.000	SYS
24	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
25	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	3,165.000	TON
26	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	4,902.000	TON
27	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	13,878.000	TON
28	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,959.000	TON
29	406-05520 ASPHALT FOR TACK COAT	36.500	TON
30	604-05250 PREFORMED JOINT MATERIAL, 1/2 IN.	2,721.000	LFT
31	604-07894 CURB RAMP, CONCRETE, A	36.000	SYS
32	604-07897 CURB RAMP, CONCRETE, C	9.000	SYS
33	604-07898 CURB RAMP, CONCRETE, D	28.000	SYS
34	604-07900 CURB RAMP, CONCRETE, F	276.000	SYS
35	604-07901 CURB RAMP, CONCRETE, G	84.000	SYS
36	604-07902 CURB RAMP, CONCRETE, H	18.000	SYS
37	604-91531 SIDEWALK, CONCRETE, 4 IN.	4,100.000	SYS
38	605-06120 CURB, CONCRETE	50.000	LFT
39	605-06140 CURB AND GUTTER, CONCRETE	7,633.000	LFT
40	605-06255 CENTER CURB, D, CONCRETE	100.000	SYS
41	610-08446 PCCP FOR APPROACHES, 6 IN.	483.000	SYS
42	610-09108 PCCP FOR APPROACHES, 9 IN.	2,139.000	SYS
43	615-06505 MONUMENT, B	7.000	EACH
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	1.000	TON
46	621-06554 SEED MIXTURE, U	195.000	LBS
47	621-06557 SEED MIXTURE, T	195.000	LBS
48	621-06565 MULCHING MATERIAL	3.000	TON
49	621-06567 WATER	300.000	KGAL

CALL ORDER : 260

CONTRACT ID : R -30936-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	621-06575 SODDING, NURSERY	6,100.000	SYS
51	628-09402 FIELD OFFICE, B	21.000	MOS
52	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	21.000	MOS
53	715-04836 GATE VALVE	5.000	EACH
54	715-04836 GATE VALVE	1.000	EACH
55	715-05024 PIPE, TYPE 2, CIRCULAR, 36 IN.	502.000	LFT
56	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	9,687.000	LFT
57	715-05146 PIPE, TYPE 2, CIRCULAR, 6 IN.	72.000	LFT
58	715-05147 PIPE, TYPE 2, CIRCULAR, 8 IN.	18.000	LFT
59	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	2,635.000	LFT
60	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	1,964.000	LFT
61	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	2,005.000	LFT
62	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	30.000	LFT
63	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	2,847.000	LFT
64	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	57.000	LFT
65	715-05159 PIPE, TYPE 2, CIRCULAR, 42 IN.	225.000	LFT
66	715-05161 PIPE, TYPE 2, CIRCULAR, 48 IN.	400.000	LFT
67	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN.	69.000	LFT
68	715-09064 VIDEO INSPECTION FOR PIPE	10,923.000	LFT
69	715-94151 WATER MAIN, 18 IN.	25.000	LFT
70	715-96669 WATER MAIN, DUCTILE IRON, 16 IN.	4,100.000	LFT
71	715-98265 WATER MAIN, DUCTILE IRON, 4 IN.	20.000	LFT
72	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
73	718-52610 AGGREGATE FOR UNDERDRAINS	765.000	CYS
74	718-99153 GEOTEXTILES FOR UNDERDRAIN	10,447.000	SYS
75	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
76	720-45030 INLET, E7	3.000	EACH
77	720-45035 INLET, F7	1.000	EACH
78	720-45045 INLET, J10	59.000	EACH
79	720-45055 INLET, M10	33.000	EACH
80	720-45410 MANHOLE, C4	47.000	EACH
81	720-45415 MANHOLE, D4	8.000	EACH
82	720-45416 MANHOLE, E4	4.000	EACH
83	720-96999 FIRE HYDRANT ASSEMBLY	18.000	EACH
84	732-01898 WATER MAIN, DUCTILE IRON, 10 IN.	90.000	LFT
85	732-04926 VALVE	1.000	EACH
86	732-04926 VALVE	1.000	EACH
87	732-04926 VALVE	3.000	EACH
88	732-04926 VALVE	4.000	EACH
89	732-04926 VALVE	6.000	EACH
90	732-05923 WATER SERVICE LINE, 1 IN.	1,350.000	LFT
91	732-06623 SLEEVE	1.000	EACH
92	732-06623 SLEEVE	4.000	EACH
93	732-06623 SLEEVE	3.000	EACH
94	732-06623 SLEEVE	5.000	EACH
95	732-06623 SLEEVE	7.000	EACH
96	732-06651 WATER LINE, 2 IN.	15.000	LFT
97	732-07826 BUFFALO BOX AND METER	20.000	EACH
98	732-91738 WATER MAIN, DUCTILE IRON, 6 IN.	400.000	LFT

CALL ORDER : 260

CONTRACT ID : R -30936-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
99	732-91739 WATER MAIN, DUCTILE IRON, 8 IN.	1,600.000	LFT
100	732-96670 WATER MAIN, DUCTILE IRON, 12 IN.	120.000	LFT
101	732-96948 GATE VALVE, 8 IN.	2.000	EACH
102	732-97009 FIRE HYDRANT ASSEMBLY, REMOVE	9.000	EACH
103	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	16.000	EACH
104	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	32,640.000	LFT
105	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11,200.000	LFT
106	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	340.000	LFT
107	801-06640 CONSTRUCTION SIGN, A	73.000	EACH
108	801-06645 CONSTRUCTION SIGN, B	31.000	EACH
109	801-06710 FLASHING ARROW SIGN	825.000	DAY
110	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
111	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
112	801-07119 BARRICADE, III-B	570.000	LFT
113	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN.	142.000	LFT
114	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	320.000	LFT
115	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
116	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	552.000	LFT
117	802-07135 CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	8.000	EACH
118	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	209.000	SFT
119	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	297.000	SFT
120	802-76125 SPAN OVERHEAD SIGN STRUCTURE, CABLESPAN	4.000	EACH
121	802-93494 POST, ROUND, GALVANIZED	165.000	LFT
122	802-97812 STREET NAME IDENTIFICATION SIGN	30.000	EACH
123	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	5.000	EACH
124	805-01842 HANDHOLE, SIGNAL	15.000	EACH
125	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	3.000	EACH
126	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	1.000	EACH
127	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	2.000	EACH
128	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	1.000	EACH
129	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	2.000	EACH
130	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
131	805-02151 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 12 IN.	24.000	EACH
132	805-03159 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM AND 30 FT. ARM	1.000	EACH
133	805-05698 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2FT. 6 IN. X 7 FT.	5.000	EACH
134	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	3,280.000	LFT
135	805-08464 RADIO, INTERCONNECT	3.000	EACH
136	805-08494 RADIO SPREAD SPECTRUM	3.000	EACH
137	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	3.000	EACH
138	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	16.000	EACH
139	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	8.000	EACH
140	805-78412 SIGNAL PEDESTAL, 9 FT.	2.000	EACH
141	805-78445 SIGNAL SERVICE	3.000	EACH
142	805-78467 SIGNAL CABLE, 3C 8GA.	150.000	LFT
143	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	5,040.000	LFT
144	805-78480 SIGNAL CABLE, 3C 14GA.	1,880.000	LFT
145	805-78485 SIGNAL CABLE, 5C 14GA.	3,030.000	LFT
146	805-78490 SIGNAL CABLE, 7C 14GA.	1,110.000	LFT
147	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,050.000	LFT

CALL ORDER : 260

CONTRACT ID : R -30936-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
148	805-78746	PREFORMED LOOP DETECTORS	1,780.000 LFT
149	805-78785	SIGNAL DETECTOR HOUSING	12.000 EACH
150	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALER	900.000 LFT
151	805-78900	PEDESTAL FOUNDATION, A	2.000 EACH
152	805-78925	CONTROLLER CABINET FOUNDATION, P1	3.000 EACH
153	805-86838	WIRE, NO. 4 COPPER IN CONDUIT, 1C	2,205.000 LFT
154	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	7.000 EACH
155	805-94295	SIGNAL HEAD, RELOCATE	64.000 EACH
156	805-95889	WIRE, NO. 10 COPPER, 1C	7,200.000 LFT
157	805-96121	PEDESTRIAN PUSH BUTTON AND SIGN	24.000 EACH
158	807-02191	HANDHOLE, LIGHTING	2.000 EACH
159	807-02193	LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT.	48.000 EACH
160	807-04654	LIGHT POLE	48.000 EACH
161	807-07580	WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	9,300.000 LFT
162	807-86615	LUMINAIRE, ROADWAY, 250 WATT, HIGH PRESSURE SODIUM	48.000 EACH
163	807-86810	SERVICE POINT, II	1.000 EACH
164	807-86910	CONNECTOR KIT, UNFUSED	48.000 EACH
165	807-86915	CONNECTOR KIT, FUSED	48.000 EACH
166	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	132.000 EACH
167	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000 EACH
168	807-86930	INSULATION LINK, NONWATERPROOFED	100.000 EACH
169	807-86935	INSULATION LINK, WATERPROOFED	24.000 EACH
170	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	48.000 EACH
171	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2,892.000 LFT
172	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,365.000 LFT
173	808-06716	LINE, REMOVE	15,000.000 LFT
174	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,482.000 LFT
175	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,533.000 LFT
176	808-75260	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	44.000 LFT
177	808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	28.000 LFT
178	808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	642.000 LFT
179	808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	2,564.000 LFT
180	808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	37.000 EACH
181	808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	24.000 EACH
182	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	222.000 LFT
183	808-97222	PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	3.000 EACH
184	808-98796	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN., 2 FT. LINE, 4 FT.	54.000 LFT

CALL ORDER : 270

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
4	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
5	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
6	202-02240 PAVEMENT REMOVAL	4,474.000	SYS
7	202-02241 GUARDRAIL, REMOVE	1,253.000	LFT
8	202-02278 CURB, CONCRETE, REMOVE	6,140.000	LFT
9	202-04089 SIGN, SHEET, REMOVE	23.000	EACH
10	202-52710 SIDEWALK, CONCRETE, REMOVE	4,050.000	SYS
11	202-91385 INLET, REMOVE	21.000	EACH
12	202-93047 MANHOLE, REMOVE	3.000	EACH
13	202-96133 PIPE, REMOVE	406.000	LFT
14	203-02000 EXCAVATION, COMMON	2,745.000	CYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	494.000	SYS
16	207-08268 SUBGRADE TREATMENT, TYPE IV	2,448.000	SYS
17	210-04181 BICYCLE RACK	19.000	EACH
18	210-07644 CONDUIT	30.000	EACH
19	210-08138 RECEPTACLE	37.000	EACH
20	210-09449 CURB RAMP, CONCRETE	20.310	SYS
21	210-09449 CURB RAMP, CONCRETE	80.750	SYS
22	210-09449 CURB RAMP, CONCRETE	42.700	SYS
23	210-09449 CURB RAMP, CONCRETE	15.390	SYS
24	210-09449 CURB RAMP, CONCRETE	167.000	SYS
25	210-09449 CURB RAMP, CONCRETE	13.000	SYS
26	210-09449 CURB RAMP, CONCRETE	63.420	SYS
27	210-09450 CROSSWALK	3,153.490	SFT
28	211-09264 STRUCTURE BACKFILL, TYPE 1	782.000	CYS
29	303-01180 COMPACTED AGGREGATE, NO. 53	3,061.480	TON
30	304-07490 HMA PATCHING, TYPE B	277.000	TON
31	304-07493 WIDENING WITH HMA, TYPE B	4.500	TON
32	306-08034 MILLING, ASPHALT, 1 1/2 IN.	7,869.000	SYS
33	402-07433 HMA SURFACE, TYPE B	650.000	TON
34	406-05520 ASPHALT FOR TACK COAT	2.000	TON
35	502-06327 PCCP, 10 IN.	2,282.000	SYS
36	603-03398 FENCE, RELOCATE	86.000	LFT
37	603-03692 FENCE, WOOD	14.670	LFT
38	604-04740 PAVERS	4,766.250	SFT
39	604-04740 PAVERS	31,600.270	SFT
40	604-04740 PAVERS	4,079.380	SFT
41	604-04740 PAVERS	8,248.640	SFT
42	604-04740 PAVERS	1,176.660	SFT
43	604-04740 PAVERS	11,633.810	SFT
44	604-04740 PAVERS	884.860	SFT
45	604-04740 PAVERS	7,310.160	SFT
46	604-04740 PAVERS	1,217.600	SFT
47	604-04740 PAVERS	3,548.640	SFT
48	604-04740 PAVERS	845.620	SFT
49	604-04740 PAVERS	1,645.660	SFT

CALL ORDER : 270

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
50	604-04740 PAVERS	14.670	SFT
51	604-04805 PAVER	8,714.900	LFT
52	604-06070 SIDEWALK, CONCRETE	60.540	SYS
53	604-07483 HMA FOR SIDEWALK	116.000	TON
54	604-07894 CURB RAMP, CONCRETE, A	137.000	SYS
55	604-07898 CURB RAMP, CONCRETE, D	6.000	SYS
56	604-07901 CURB RAMP, CONCRETE, G	23.060	SYS
57	604-07903 CURB RAMP, CONCRETE, K	64.000	SYS
58	604-91531 SIDEWALK, CONCRETE, 4 IN.	1,653.000	SYS
59	604-91531 SIDEWALK, CONCRETE, 4 IN.	6,843.940	SYS
60	605-06090 CURB, INTEGRAL, CONCRETE	1,680.000	LFT
61	605-06120 CURB, CONCRETE	3,857.000	LFT
62	605-06120 CURB, CONCRETE	258.770	LFT
63	605-06121 CURB, CONCRETE, B	68.000	LFT
64	605-06125 CURB, CONCRETE, MODIFIED	983.000	LFT
65	610-07487 HMA FOR APPROACHES, TYPE B	106.000	TON
66	610-08446 PCCP FOR APPROACHES, 6 IN.	128.000	SYS
67	610-08446 PCCP FOR APPROACHES, 6 IN.	1,304.870	SYS
68	610-08510 PCCP FOR APPROACHES	20.030	SYS
69	610-09108 PCCP FOR APPROACHES, 9 IN.	366.000	SYS
70	611-03671 TRASH RECEPTACLE	5.000	EACH
71	615-06505 MONUMENT, B	12.000	EACH
72	615-06515 MONUMENT, D	6.000	EACH
73	621-06570 TOP SOIL	980.190	CYS
74	621-06570 TOP SOIL	78.160	CYS
75	621-06570 TOP SOIL	330.490	CYS
76	621-06575 SODDING, NURSERY	584.000	SYS
77	621-98038 MULCH, HARDWOOD SHREDDED BARK	265.380	CYS
78	622-04992 DRAIN	11.000	EACH
79	622-04992 DRAIN	2.000	EACH
80	622-05616 PLANT, BROADLEAF EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN.	614.000	EACH
81	622-05634 PLANT, CONIFEROUS EVERGREEN, PROSTRATE, BROAD SPREADING,	180.000	EACH
82	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	329.000	EACH
83	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	282.000	EACH
84	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	34.000	EACH
85	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	46.000	EACH
86	622-05653 PLANT, GROUND COVER	5,787.000	EACH
87	622-05654 PLANT, PERENNIAL	12,238.000	EACH
88	622-05654 PLANT, PERENNIAL	790.000	EACH
89	622-05654 PLANT, PERENNIAL	589.000	EACH
90	622-06573 IRRIGATION	1.000	EACH
91	702-51005 CONCRETE, A, SUBSTRUCTURE	6.560	CYS
92	702-51007 CONCRETE, A, ENCASEMENT	9.000	CYS
93	703-06028 REINFORCING BARS	1,959.000	LBS
94	706-04683 RAILING	18.000	LFT
95	711-51035 STRUCTURAL STEEL	96.000	LBS
96	712-03812 BENCH	7.000	EACH
97	715-05032 PIPE, TYPE 2, CIRCULAR, 15 IN.	2.000	LFT
98	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	987.000	LFT

CALL ORDER : 270

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN FACILITY		
99 715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	4.000	LFT
100 715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	3,276.000	LFT
101 715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	2.000	LFT
102 715-09064	VIDEO INSPECTION FOR PIPE	6,083.000	LFT
103 715-90714	PIPE, PVC, 12 IN.	27.000	LFT
104 715-91361	PIPE, PVC, 6 IN.	1,777.000	LFT
105 715-96960	PIPE, PVC, 15 IN.	2.000	LFT
106 718-52610	AGGREGATE FOR UNDERDRAINS	30.000	CYS
107 718-99153	GEOTEXTILES FOR UNDERDRAIN	612.000	SYS
108 720-01894	CASTING, FURNISH AND ADJUST TO GRADE	7.000	EACH
109 720-02442	PIPE, PLUG EXISTING	3.000	EACH
110 720-04682	INLET,	49.000	EACH
111 720-44000	CASTING, ADJUST TO GRADE	28.000	EACH
112 720-45045	INLET, J10	9.000	EACH
113 720-45055	INLET, M10	9.000	EACH
114 720-45145	INLET, J10, MODIFIED	3.000	EACH
115 720-45235	CATCH BASIN, E7	1.000	EACH
116 720-45250	CATCH BASIN, K10	23.000	EACH
117 720-45410	MANHOLE, C4	11.000	EACH
118 720-45415	MANHOLE, D4	1.000	EACH
119 720-45510	MANHOLE, C4, MODIFIED	8.000	EACH
120 720-45515	MANHOLE, D4, MODIFIED	3.000	EACH
121 720-98687	CATCH BASIN, M10	15.000	EACH
122 732-04994	METER	10.000	EACH
123 801-03290	CONSTRUCTION SIGN, C	10.000	EACH
124 801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15,383.000	LFT
125 801-06218	TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	57.000	LFT
126 801-06640	CONSTRUCTION SIGN, A	41.000	EACH
127 801-06645	CONSTRUCTION SIGN, B	31.000	EACH
128 801-06710	FLASHING ARROW SIGN	900.000	DAY
129 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
130 801-07119	BARRICADE, III-B	350.000	LFT
131 802-03896	BOLLARD	13.000	EACH
132 802-03896	BOLLARD	34.000	EACH
133 802-03896	BOLLARD	16.000	EACH
134 802-04314	SIGN	6.000	EACH
135 802-04314	SIGN	20.000	EACH
136 802-04314	SIGN	26.000	EACH
137 802-04314	SIGN	5.000	EACH
138 802-04314	SIGN	15.000	EACH
139 802-05701	SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	186.000	LFT
140 802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	30.000	EACH
141 802-07060	SIGN, SHEET, RELOCATE	2.000	EACH
142 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	324.000	SFT
143 802-93494	POST, ROUND, GALVANIZED	395.000	LFT
144 802-96248	POST, WOOD, 4 IN. X 4 IN.	40.000	LFT
145 805-01842	HANDHOLE, SIGNAL	26.000	EACH
146 805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	4.000	EACH
147 805-02036	SIGNAL CANTILEVER STRUCTURE, 15 FT. ARM	1.000	EACH

CALL ORDER : 270

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
148	805-02037 SIGNAL CANTILEVER STRUCTURE, 20 FT. ARM	2.000	EACH
149	805-02069 SIGNAL CANTILEVER STRUCTURE, 25 FT. ARM	1.000	EACH
150	805-02072 SIGNAL CANTILEVER STRUCTURE, 30 FT. ARM	1.000	EACH
151	805-02073 SIGNAL CANTILEVER STRUCTURE, 35 FT. ARM	1.000	EACH
152	805-02077 SIGNAL CANTILEVER STRUCTURE, 40 FT. ARM	1.000	EACH
153	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
154	805-02150 PEDESTRIAN SIGNAL HEAD, 18 IN.	26.000	EACH
155	805-02328 SIGNAL CABLE, 1C 14GA.	440.000	LFT
156	805-02373 INTERCONNECT CABLE, FIBER OPTIC	1,838.000	LFT
157	805-02855 SIGNAL SUPPORT FOUNDATION, 2 FT. 6 IN. X 2 FT. 6 IN. X 6 FT.	6.000	EACH
158	805-04133 SIGNAL PEDESTAL, 12 FT.	2.000	EACH
159	805-04808 PEDESTRIAN SIGNAL	1.000	EACH
160	805-04974 SIGNAL CONTROLLER	1.000	EACH
161	805-05405 SIGNAL PEDESTAL, 4 FT.	1.000	EACH
162	805-05870 SIGNAL SUPPORT FOUNDATION	4.000	EACH
163	805-06101 FOUNDATION	57.000	EACH
164	805-06101 FOUNDATION	32.000	EACH
165	805-06101 FOUNDATION	4.000	EACH
166	805-06362 SIGNAL AND LIGHTING COMBINATION POLE	1.000	EACH
167	805-06362 SIGNAL AND LIGHTING COMBINATION POLE	1.000	EACH
168	805-06362 SIGNAL AND LIGHTING COMBINATION POLE	1.000	EACH
169	805-06483 CONTROLLER	1.000	EACH
170	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	5,071.000	LFT
171	805-08102 DECORATIVE	3,153.490	EACH
172	805-08129 SIGNAL CABLE	196.000	LFT
173	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
174	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	2.000	EACH
175	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN. AMBER	6.000	EACH
176	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	29.000	EACH
177	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
178	805-78370 PEDESTRIAN PUSH BUTTON	16.000	EACH
179	805-78445 SIGNAL SERVICE	4.000	EACH
180	805-78465 SIGNAL CABLE, 2C 8GA.	545.000	LFT
181	805-78480 SIGNAL CABLE, 3C 14GA.	48.000	LFT
182	805-78485 SIGNAL CABLE, 5C 14GA.	10,629.000	LFT
183	805-78490 SIGNAL CABLE, 7C 14GA.	465.000	LFT
184	805-78495 SIGNAL CABLE, 9C 14GA.	1,505.000	LFT
185	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	208.000	LFT
186	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
187	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	180.000	LFT
188	805-78900 PEDESTAL FOUNDATION, A	5.000	EACH
189	805-78900 PEDESTAL FOUNDATION, A	15.000	EACH
190	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
191	805-90005 SIGNAL PEDESTAL, 10 FT.	2.000	EACH
192	805-90005 SIGNAL PEDESTAL, 10 FT.	15.000	EACH
193	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.000	EACH
194	805-95568 CONDUIT, PVC, 4 IN.	520.000	LFT
195	807-02191 HANDHOLE, LIGHTING	9.000	EACH
196	807-02191 HANDHOLE, LIGHTING	1.000	EACH

CALL ORDER : 270

CONTRACT ID : R -31066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BIKE/PEDESTRIAN FACILITY			
197	807-04651 WIRE	900.000	LFT
198	807-04651 WIRE	2,400.000	LFT
199	807-04651 WIRE	1,800.000	LFT
200	807-04651 WIRE	1,400.000	LFT
201	807-04652 SERVICE POINT	8.000	EACH
202	807-04866 LUMINAIRE	32.000	EACH
203	807-04866 LUMINAIRE	4.000	EACH
204	807-04866 LUMINAIRE	4.000	EACH
205	807-04866 LUMINAIRE	8.000	EACH
206	807-04866 LUMINAIRE	4.000	EACH
207	807-04866 LUMINAIRE	57.000	EACH
208	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE	3.000	EACH
209	808-03439 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK, WHITE, 24 IN.	749.000	LFT
210	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	13.000	SYS
211	808-06368 TRANSVERSE MARKING, REMOVE	50.000	LFT
212	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	86.000	LFT
213	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	358.000	LFT
214	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	70.000	LFT
215	808-06716 LINE, REMOVE	5,699.000	LFT
216	808-08258 TRANSVERSE MARKINGS	68.000	LFT
217	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	610.000	LFT
218	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	835.000	LFT
219	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 24 IN.	280.000	LFT
220	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,098.000	LFT
221	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	330.000	LFT
222	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.000	EACH
223	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
224	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	13.000	EACH
225	808-97664 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 280

CONTRACT ID : R -31110-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DEMOLITION, REMOVE BUILDINGS			
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	202-02255 TREE, 18 IN., REMOVE	2.000	EACH
7	202-02260 TREE, 30 IN., REMOVE	2.000	EACH
8	202-02265 TREE, 48 IN., REMOVE	2.000	EACH
9	202-02844 SIGN STRUCTURE, OVERHEAD, MONOTUBE, REMOVE	1.000	EACH
10	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
12	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
13	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
14	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	3,156.000	SFT
15	202-07554 REGULATED MATERIALS, TRANSPORT, TYPE Y	20.000	CYS
16	202-07555 REGULATED MATERIALS, DISPOSE, TYPE Y	20.000	CYS
17	202-99626 FOUNDATION FOR SIGNING, REMOVE	1.000	EACH
18	205-06937 TEMPORARY SILT FENCE	1,137.000	LFT
19	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
20	621-06559 MULCHED SEEDING, R	2,733.000	SYS
21	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
22	628-09409 MOBILE INTERNET SERVICE	4.000	MOS

CALL ORDER : 320

CONTRACT ID : RS-29630-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07490 HMA PATCHING, TYPE B	170.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	20,190.600	SYS
13	306-08432 MILLING, APPROACH	4,148.000	SYS
14	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,670.000	TON
15	406-05520 ASPHALT FOR TACK COAT	10.000	TON
16	604-07894 CURB RAMP, CONCRETE, A	182.000	SYS
17	604-07897 CURB RAMP, CONCRETE, C	91.000	SYS
18	604-07901 CURB RAMP, CONCRETE, G	39.200	SYS
19	610-07487 HMA FOR APPROACHES, TYPE B	342.000	TON
20	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
21	621-06553 SEED MIXTURE, R	10.000	LBS
22	628-09402 FIELD OFFICE, B	6.000	MOS
23	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
24	720-44000 CASTING, ADJUST TO GRADE	25.000	EACH
25	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
26	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
27	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,701.000	LFT
28	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	851.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
30	801-06710 FLASHING ARROW SIGN	90.000	DAY
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
33	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,060.000	LFT
34	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	340.000	LFT
35	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6,500.000	LFT
36	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,595.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,763.000	LFT
38	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	210.000	LFT
39	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	760.000	LFT

CALL ORDER : 360

CONTRACT ID : B -28680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	373.000	LFT
13	202-02279 CURB AND GUTTER, REMOVE	134.000	LFT
14	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
15	202-52710 SIDEWALK, CONCRETE, REMOVE	57.000	SYS
16	202-90277 DETECTOR HOUSING, REMOVE	1.000	EACH
17	203-02000 EXCAVATION, COMMON	35.000	CYS
18	205-06937 TEMPORARY SILT FENCE	400.000	LFT
19	303-01180 COMPACTED AGGREGATE, NO. 53	4.000	TON
20	304-07490 HMA PATCHING, TYPE B	67.000	TON
21	304-07490 HMA PATCHING, TYPE B	6.000	TON
22	306-08033 MILLING, ASPHALT, 1 IN.	364.000	SYS
23	402-07451 HMA WEDGE AND LEVEL, TYPE B	40.000	TON
24	406-05521 ASPHALT FOR TACK COAT	644.000	SYS
25	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	193.750	LFT
26	601-02800 GUARDRAIL TRANSITION, TGT	4.000	EACH
27	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
28	601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	1.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	175.000	LFT
31	604-07897 CURB RAMP, CONCRETE, C	16.000	SYS
32	604-07903 CURB RAMP, CONCRETE, K	16.000	SYS
33	604-91531 SIDEWALK, CONCRETE, 4 IN.	40.000	SYS
34	605-06140 CURB AND GUTTER, CONCRETE	116.000	LFT
35	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
36	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
37	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-06559 MULCHED SEEDING, R	120.000	SYS
40	628-09402 FIELD OFFICE, B	6.000	MOS
41	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
42	702-51005 CONCRETE, A, SUBSTRUCTURE	8.500	CYS
43	702-51863 FIELD DRILLED HOLE IN CONCRETE	414.000	EACH
44	703-51032 REINFORCING STEEL, EPOXY COATED	19,962.000	LBS
45	704-51002 CONCRETE, C, SUPERSTRUCTURE	67.200	CYS
46	706-01268 HANDRAIL, ALUMINUM	82.000	LFT
47	706-06347 RAILING, CF-1	245.000	LFT
48	708-51813 PNEUMATICALLY PLACED MORTAR	770.000	SFT
49	708-51814 WELDED STEEL WIRE FABRIC	770.000	SFT

CALL ORDER : 360

CONTRACT ID : B -28680-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
50	709-51821 SURFACE SEAL	LUMP	LUMP
51	711-51038 STRUCTURAL STEEL	LUMP	LUMP
52	711-51864 DRILLED HOLE	48.000	EACH
53	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
54	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	145.000	SFT
55	722-51842 BRIDGE DECK OVERLAY	365.000	SYS
56	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	6.000	CYS
57	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	290.000	SFT
58	722-60824 SURFACE MILLING	320.000	SYS
59	724-51925 STRUCTURAL EXPANSION JOINT, SS	206.000	LFT
60	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	4.000	EACH
61	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	15.000	EACH
62	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	1.000	EACH
63	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	2.000	EACH
64	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	3.000	EACH
65	727-90308 EPOXY INJECTION, CRACK PREPARATION	340.000	LFT
66	727-90309 EPOXY INJECTION, EPOXY MATERIAL	51.000	GAL
67	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
68	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
69	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
70	801-06625 DETOUR ROUTE MARKER ASSEMBLY	38.000	EACH
71	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
72	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
73	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
74	801-07118 BARRICADE, III-A	48.000	LFT
75	801-07119 BARRICADE, III-B	24.000	LFT
76	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	431.000	LFT
77	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
78	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	143.000	LFT
79	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	100.000	LFT
80	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	520.000	LFT
81	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	20.000	LFT
82	808-75007 LINE, PAINT, SOLID, WHITE, 6 IN.	12.000	LFT

CALL ORDER : 370

CONTRACT ID : B -29265-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ENHANCEMENT, BRIDGE REHABILITATION			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
7	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
8	205-06937 TEMPORARY SILT FENCE	40.000	LFT
9	206-51817 SHEET PILING, STEEL	2,829.000	SFT
10	211-09265 STRUCTURE BACKFILL, TYPE 2	152.000	CYS
11	306-08034 MILLING, ASPHALT, 1 1/2 IN.	62.000	SYS
12	402-07432 HMA SURFACE, TYPE A	60.000	TON
13	402-07435 HMA INTERMEDIATE, TYPE A	93.000	TON
14	406-05521 ASPHALT FOR TACK COAT	782.000	SYS
15	610-07486 HMA FOR APPROACHES, TYPE A	5.000	TON
16	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
17	621-06559 MULCHED SEEDING, R	373.000	SYS
18	628-09401 FIELD OFFICE, A	12.000	MOS
19	702-51015 CONCRETE, B, FOOTINGS	5.700	CYS
20	702-51864 FIELD DRILLED HOLE	296.000	EACH
21	702-93722 CONCRETE, C	11.800	CYS
22	702-94656 CONCRETE, B	35.500	CYS
23	706-51020 CONCRETE, C, RAILING	3.200	CYS
24	708-51813 PNEUMATICALLY PLACED MORTAR	2,320.000	SFT
25	708-51814 WELDED STEEL WIRE FABRIC	696.000	SFT
26	709-51821 SURFACE SEAL	LUMP	LUMP
27	714-44240 CONCRETE, A, STRUCTURES	7.700	CYS
28	727-90308 EPOXY INJECTION, CRACK PREPARATION	1,344.000	LFT
29	727-90309 EPOXY INJECTION, EPOXY MATERIAL	524.000	GAL
30	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
31	728-98377 MASONRY COATING	LUMP	LUMP
32	801-07118 BARRICADE, III-A	48.000	LFT
33	805-04973 CONDUIT	261.000	LFT

CALL ORDER : 380

CONTRACT ID : B -29570-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	78.000	m2
13	202-02241 GUARDRAIL, REMOVE	207.000	m
14	202-03875 CONCRETE STEPS, REMOVE	1.000	EACH
15	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
16	202-51368 SLOPEWALL, REMOVE	1,982.000	m2
17	202-74035 SIGN, REMOVE	11.000	EACH
18	202-90747 RETAINING WALL, REMOVE	63.000	m3
19	202-91385 INLET, REMOVE	1.000	EACH
20	202-96133 PIPE, REMOVE	27.000	m
21	202-99187 FENCE, FARM FIELD, REMOVE	471.000	m
22	203-02000 EXCAVATION, COMMON	22,608.000	m3
23	203-02070 BORROW	2,996.000	m3
24	203-51223 EXCAVATION, WATERWAY	5,700.000	m3
25	205-03371 SEDIMENT REMOVE	25.000	m3
26	205-04931 SEDIMENT TRAP	1.000	EACH
27	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
28	205-06936 TEMPORARY SEDIMENT TRAP	21.000	Mg
29	205-06937 TEMPORARY SILT FENCE	2,456.000	m
30	206-51220 EXCAVATION, WET	234.000	m3
31	207-08262 SUBGRADE TREATMENT, TYPE I	15,785.000	m2
32	207-08263 SUBGRADE TREATMENT, TYPE IA	1,552.000	m2
33	207-08265 SUBGRADE TREATMENT, TYPE IIA	2,207.000	m2
34	211-06467 AGGREGATE FOR END BENT BACKFILL	48.000	m3
35	211-09264 STRUCTURE BACKFILL, TYPE 1	69.700	m3
36	211-09268 STRUCTURE BACKFILL, TYPE 5	53.000	m3
37	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	102.000	m3
38	214-07202 GEOGRID, I	1,552.000	m2
39	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	4,301.000	Mg
40	302-07455 DENSE GRADED SUBBASE	30.600	m3
41	303-93714 BOULDER	8.000	EACH
42	306-08034 MILLING, ASPHALT, 38 mm	95.000	m2
43	306-08043 MILLING, TRANSITION	293.000	m2
44	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,488.000	Mg
45	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	153.000	Mg
46	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	2,034.000	Mg
47	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	151.000	Mg
48	401-07401 QC/QA-HMA, 1, 76, INTERMEDIATE, 19.0 mm	1,503.000	Mg
49	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 MM	1,135.000	Mg

CALL ORDER : 380

CONTRACT ID : B -29570-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	129.000	Mg
51	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	3,547.000	Mg
52	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	313.000	Mg
53	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	172.000	Mg
54	406-05520 ASPHALT FOR TACK COAT	13.200	Mg
55	406-05521 ASPHALT FOR TACK COAT	4,917.000	m2
56	601-01128 GUARDRAIL TRANSITION TYPE WGB	2.000	EACH
57	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
58	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
59	601-01701 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 2	1.000	EACH
60	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
61	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
62	601-08182 GUARDRAIL, THRIE BEAM	15.200	m
63	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
64	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	303.200	m
65	602-06729 BARRIER DELINEATOR	20.000	EACH
66	605-06120 CURB, CONCRETE	41.000	m
67	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	207.800	m2
68	610-07486 HMA FOR APPROACHES, TYPE A	67.400	Mg
69	610-07487 HMA FOR APPROACHES, TYPE B	63.000	Mg
70	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
71	615-06490 RIGHT OF WAY MARKER	6.000	EACH
72	615-06505 MONUMENT, B	4.000	EACH
73	616-02320 GEOTEXTILES	4,119.000	m2
74	616-06405 RIPRAP, REVETMENT	2,727.000	Mg
75	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
76	621-02770 EROSION CONTROL BLANKET	543.000	m2
77	621-06545 FERTILIZER	5.100	Mg
78	621-06553 SEED MIXTURE, R	928.000	kg
79	621-06557 SEED MIXTURE, T	20.000	kg
80	621-06559 MULCHED SEEDING, R	1,200.000	m2
81	621-06565 MULCHING MATERIAL	23.000	Mg
82	621-06567 WATER	75.000	kL
83	621-06574 SODDING	2,982.000	m2
84	621-06575 SODDING, NURSERY	1,100.000	m2
85	622-52436 SIGN, DO NOT MOW OR SPRAY	7.000	EACH
86	622-91786 SEEDLING	320.000	EACH
87	622-98200 SIGN, DO NOT DISTURB	5.000	EACH
88	628-09402 FIELD OFFICE, B	15.000	MOS
89	701-01849 PILE, CONCRETE, STEEL SHELL ENCASED, 7.92 mm, 356 mm	1,075.500	m
90	701-99086 PILE TIP, STEEL SHELL	54.000	EACH
91	702-51005 CONCRETE, A, SUBSTRUCTURE	100.400	m3
92	702-51015 CONCRETE, B, FOOTINGS	70.200	m3
93	702-92857 CONCRETE, C, SUBSTRUCTURE	20.000	m3
94	703-51030 REINFORCING STEEL	12,534.000	kg
95	703-51032 REINFORCING STEEL, EPOXY COATED	72,261.000	kg
96	704-51002 CONCRETE, C, SUPERSTRUCTURE	370.200	m3
97	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
98	706-51020 CONCRETE, C, RAILING	45.500	m3

CALL ORDER : 380

CONTRACT ID : B -29570-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
99	707-06404 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM	469.500	m
100	709-51821 SURFACE SEAL	LUMP	LUMP
101	714-06319 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 4200 mm X 1500 mm	14.700	m
102	715-02630 SAFETY METAL END SECTION, 6:1, 600 mm	2.000	EACH
103	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	2,381.000	m
104	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	208.000	m
105	715-05121 PIPE, TYPE 1, CIRCULAR, 450 mm	49.000	m
106	715-05123 PIPE, TYPE 1, CIRCULAR, 600 mm	76.000	m
107	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	2.000	m
108	715-05169 PIPE, TYPE 3, CIRCULAR, 375 mm	11.500	m
109	715-05407 PIPE, END BENT DRAIN, 150 mm	36.000	m
110	715-46005 PIPE END SECTION, 375 mm	2.000	EACH
111	715-46010 PIPE END SECTION, 450 mm	4.000	EACH
112	715-46020 PIPE END SECTION, 600 mm	4.000	EACH
113	718-06528 OUTLET PROTECTOR, 1	13.000	EACH
114	718-06529 OUTLET PROTECTOR, 2	5.000	EACH
115	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,000.000	m
116	718-52610 AGGREGATE FOR UNDERDRAINS	514.000	m3
117	718-99153 GEOTEXTILES FOR UNDERDRAIN	4,649.000	m2
118	720-45265 PIPE CATCH BASIN, 375 mm	1.000	EACH
119	723-08608 WINGWALL	39.000	m2
120	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
121	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
122	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
123	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
124	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
125	801-07118 BARRICADE, III-A	13.200	m
126	801-07119 BARRICADE, III-B	19.800	m
127	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	8.000	m
128	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	2.700	m2
129	802-76055 SIGN POST, A	17.200	m
130	802-91122 SIGN, GROUND MOUNTED, RESET	1.000	EACH
131	808-03631 LINE, EPOXY, SOLID, WHITE, 100 mm	222.000	m
132	808-03632 LINE, EPOXY, SOLID, YELLOW, 100 mm	222.000	m
133	808-06694 LINE, PAINT, SOLID, YELLOW, 200 mm	155.000	m
134	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	223.000	m
135	808-06713 LINE, PAINT, SOLID, WHITE, 100 mm	2,810.000	m
136	808-06714 LINE, PAINT, SOLID, YELLOW, 100 mm	2,604.000	m
137	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	2.000	EACH
138	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	1.000	EACH
139	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 600 mm	8.300	m
140	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	282.000	m

CALL ORDER : 390

CONTRACT ID : B -29775-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
10	202-99187 FENCE, FARM FIELD, REMOVE	480.000	LFT
11	203-02000 EXCAVATION, COMMON	262.000	CYS
12	203-02070 BORROW	2,586.000	CYS
13	203-51223 EXCAVATION, WATERWAY	46.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	9.400	TON
15	205-06937 TEMPORARY SILT FENCE	1,570.000	LFT
16	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	179.000	CYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,567.000	SYS
18	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	9.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	228.000	TON
20	302-07455 DENSE GRADED SUBBASE	22.800	CYS
21	306-08043 MILLING, TRANSITION	467.000	SYS
22	402-07432 HMA SURFACE, TYPE A	219.000	TON
23	402-07435 HMA INTERMEDIATE, TYPE A	303.000	TON
24	402-07440 HMA BASE, TYPE A	987.000	TON
25	406-05521 ASPHALT FOR TACK COAT	4,850.000	SYS
26	601-01128 GUARDRAIL TRANSITION TYPE WGB	4.000	EACH
27	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	2.000	EACH
28	601-06037 GUARDRAIL END TREATMENT, I	2.000	EACH
29	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	113.000	LFT
30	602-06729 BARRIER DELINEATOR	8.000	EACH
31	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	137.000	SYS
32	610-07486 HMA FOR APPROACHES, TYPE A	86.000	TON
33	610-08446 PCCP FOR APPROACHES, 6 IN.	158.000	SYS
34	615-06490 RIGHT OF WAY MARKER	14.000	EACH
35	616-02320 GEOTEXTILES	755.000	SYS
36	616-06405 RIPRAP, REVETMENT	587.000	TON
37	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
38	621-06559 MULCHED SEEDING, R	3,769.000	SYS
39	621-06567 WATER	0.110	KGAL
40	621-06574 SODDING	27.000	SYS
41	628-09401 FIELD OFFICE, A	10.000	MOS
42	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
43	701-51195 PILE, STEEL H, HP 12 X 53	530.000	LFT
44	701-91792 PILE TIP, STEEL H	24.000	EACH
45	702-51005 CONCRETE, A, SUBSTRUCTURE	79.400	CYS
46	702-51015 CONCRETE, B, FOOTINGS	11.000	CYS
47	703-51030 REINFORCING STEEL	5,096.000	LBS
48	703-51032 REINFORCING STEEL, EPOXY COATED	34,254.000	LBS
49	704-51002 CONCRETE, C, SUPERSTRUCTURE	138.000	CYS

CALL ORDER : 390

CONTRACT ID : B -29775-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
51	706-51020 CONCRETE, C, RAILING	5.800	CYS
52	709-51821 SURFACE SEAL	LUMP	LUMP
53	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	64.000	LFT
54	715-05175 PIPE, TYPE 3, CIRCULAR, 30 IN.	56.000	LFT
55	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
56	715-46030 PIPE END SECTION, 30 IN.	2.000	EACH
57	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
58	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
59	801-06625 DETOUR ROUTE MARKER ASSEMBLY	14.000	EACH
60	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
61	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
62	801-07118 BARRICADE, III-A	96.000	LFT
63	801-07119 BARRICADE, III-B	48.000	LFT
64	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	9.000	EACH
65	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
66	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	18.300	SFT
67	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	7.070	SFT
68	802-76055 SIGN POST, A	50.000	LFT
69	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
70	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,700.000	LFT
71	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,700.000	LFT

CALL ORDER : 430

CONTRACT ID : M -30601-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-90277 DETECTOR HOUSING, REMOVE	1.000	EACH
10	211-09265 STRUCTURE BACKFILL, TYPE 2	29.000	CYS
11	302-06464 SUBBASE FOR PCCP	170.000	CYS
12	503-05240 D-1 CONTRACTION JOINT	512.000	LFT
13	506-06333 PCCP PATCHING, FULL DEPTH	1,980.000	SYS
14	507-08270 CRACKS IN PCCP, ROUT AND SEAL	5,700.000	LFT
15	605-06090 CURB, INTEGRAL, CONCRETE	970.000	LFT
16	621-06575 SODDING, NURSERY	215.000	SYS
17	628-09402 FIELD OFFICE, B	4.000	MOS
18	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	12.000	LFT
19	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	22.000	LFT
20	715-08283 PCCP FOR STRUCTURE INSTALLATION	10.000	SYS
21	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
22	720-96995 CLEAN INLET	1.000	EACH
23	720-99315 CLEAN EXISTING CATCH BASINS	1.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
26	801-06710 FLASHING ARROW SIGN	500.000	DAY
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
29	801-92448 CONSTRUCTION SIGNS, MOBILE	1,000.000	DAY
30	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	316.000	LFT
31	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
32	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	96.000	LFT
33	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	300.000	LFT
34	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	300.000	LFT

CALL ORDER : 440

CONTRACT ID : M -31113-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, TREE REMOVAL/TRIMMING		
1 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	14.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 109-08359	LIQUIDATED DAMAGES	1.000	DOL
5 109-08360	CONTRACT LIENS	1.000	DOL
6 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9 202-02245	TREE, 6 IN., REMOVE	40.000	EACH
10 202-02245	TREE, 6 IN., REMOVE	1.000	EACH
11 202-02250	TREE, 10 IN., REMOVE	40.000	EACH
12 202-02250	TREE, 10 IN., REMOVE	1.000	EACH
13 202-02255	TREE, 18 IN., REMOVE	40.000	EACH
14 202-02255	TREE, 18 IN., REMOVE	1.000	EACH
15 202-02260	TREE, 30 IN., REMOVE	35.000	EACH
16 202-02260	TREE, 30 IN., REMOVE	1.000	EACH
17 202-02265	TREE, 48 IN., REMOVE	35.000	EACH
18 202-02265	TREE, 48 IN., REMOVE	1.000	EACH
19 202-02270	TREE, 60 IN., REMOVE	35.000	EACH
20 202-02270	TREE, 60 IN., REMOVE	1.000	EACH
21 202-91922	STUMP, REMOVE	150.000	EACH
22 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	14.000	MOS
23 628-09409	MOBILE INTERNET SERVICE	14.000	MOS
24 801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
25 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
26 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
27 801-06710	FLASHING ARROW SIGN	70.000	DAY
28 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 450

CONTRACT ID : M -31143-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PCCP PATCHING AND REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	202-02241 GUARDRAIL, REMOVE	160.000	LFT
14	203-08607 LINEAR GRADING	400.000	LFT
15	303-01180 COMPACTED AGGREGATE, NO. 53	880.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	1,080.000	TON
17	304-07491 HMA PATCHING, TYPE C	827.000	TON
18	306-08037 MILLING, ASPHALT, 3 IN.	104.000	SYS
19	306-08042 MILLING, SCARIFICATION/PROFILE	4,809.000	SYS
20	306-08043 MILLING, TRANSITION	6,249.000	SYS
21	306-08432 MILLING, APPROACH	200.000	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	533.000	TON
24	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,092.000	TON
25	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	990.000	TON
26	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,029.000	TON
27	406-05520 ASPHALT FOR TACK COAT	9.400	TON
28	507-07479 HMA PARTIAL DEPTH PATCH	379.000	TON
29	601-93346 GUARDRAIL CONNECTOR, AS	4.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
31	610-07488 HMA FOR APPROACHES, TYPE C	50.000	TON
32	628-09401 FIELD OFFICE, A	6.000	MOS
33	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
34	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	757.000	LFT
35	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	757.000	LFT
36	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	70.000	LFT
37	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	70.000	LFT
38	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
40	802-02158 SIGN, PANEL, REMOVE AND REINSTALL	2.000	EACH
41	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	440.000	LFT
42	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	440.000	LFT
43	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,672.000	LFT
44	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	350.000	LFT
45	808-06716 LINE, REMOVE	880.000	LFT
46	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	505.000	LFT
47	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,643.000	LFT
48	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	70.000	LFT
49	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	73.000	EACH

CALL ORDER : 460

CONTRACT ID : M -31144-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
5	105-08523 RADIO SERVICE	10.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	164.000	TON
13	304-07783 HMA PATCHING, TYPE D	270.000	TON
14	306-08041 MILLING, PCCP	2,699.000	SYS
15	402-07784 HMA SURFACE, TYPE D	223.000	TON
16	406-05520 ASPHALT FOR TACK COAT	1.000	TON
17	507-07479 HMA PARTIAL DEPTH PATCH	1,686.000	TON
18	628-09401 FIELD OFFICE, A	5.000	MOS
19	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
20	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
23	801-06710 FLASHING ARROW SIGN	180.000	DAY
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	4,760.000	LFT
26	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,040.000	LFT
27	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	8,200.000	LFT
28	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	15,749.000	LFT
29	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	28,122.000	LFT
30	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	1,300.000	LFT
31	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	508.000	EACH

CALL ORDER : 490

CONTRACT ID : T -26001-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 GUARD RAIL WORK			
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02241 GUARDRAIL, REMOVE	325.000	LFT
10	202-93741 GUARD RAIL END TREATMENT, REMOVE	63.000	EACH
11	601-03467 ALUMINUM TO STEEL SPLICE CONNECTOR, TYPE A S	4.000	EACH
12	601-09146 IMPACT ATTENUATOR, CR1, W1, TL-2	2.000	EACH
13	601-09238 HAND DIG GUARDRAIL POST HOLES	36.000	EACH
14	601-94689 GUARDRAIL END TREATMENT, OS	63.000	EACH
15	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	100.000	LFT
16	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	4.000	EACH
17	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
18	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
19	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	801-92448 CONSTRUCTION SIGNS, MOBILE	300.000	DAY
22	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	5.000	LFT
23	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	5.000	LFT
24	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH

CALL ORDER : 510

CONTRACT ID : T -30093-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW SIGNAL INSTALLATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-04089 SIGN, SHEET, REMOVE	1.000	EACH
8	202-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	1.000	EACH
9	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	6.000	EACH
10	621-06559 MULCHED SEEDING, R	50.000	SYS
11	628-09402 FIELD OFFICE, B	4.000	MOS
12	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	4.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	50.000	LFT
17	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	75.000	SFT
18	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
19	805-01820 SIGNAL STRAIN POLE, STEEL, INSTALL	4.000	EACH
20	805-01842 HANDHOLE, SIGNAL	11.000	EACH
21	805-04736 SIGNAL CABLE, 4C 18GA.	2,720.000	LFT
22	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	2,035.000	LFT
23	805-06742 SOLAR POWERED FLASHING BEACON ASSEMBLY	1.000	EACH
24	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
25	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
26	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
27	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
28	805-78420 DISCONNECT HANGER	4.000	EACH
29	805-78445 SIGNAL SERVICE	1.000	EACH
30	805-78467 SIGNAL CABLE, 3C 8GA.	150.000	LFT
31	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,410.000	LFT
32	805-78485 SIGNAL CABLE, 5C 14GA.	557.000	LFT
33	805-78490 SIGNAL CABLE, 7C 14GA.	1,079.000	LFT
34	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,340.000	LFT
35	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
36	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	745.000	LFT
37	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
38	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
39	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
40	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
41	805-92512 MICROLOOP DETECTOR	10.000	EACH
42	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	29.400	SYS
43	808-06368 TRANSVERSE MARKING, REMOVE	35.000	LFT
44	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	15.000	LFT
45	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	150.000	LFT
46	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	162.000	LFT
47	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	7.000	EACH
48	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	7.000	EACH

CALL ORDER : 520

CONTRACT ID : TM-30887-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 LIGHTING INSTALLATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-86946 HANDHOLE, REMOVE	3.000	EACH
11	202-95579 SERVICE POINT, REMOVE	4.000	EACH
12	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
13	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
15	801-06710 FLASHING ARROW SIGN	30.000	DAY
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,715.000	LFT
18	805-86890 POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER	5,092.000	LFT
19	805-87485 INSULATING LINK, FURNISH	92.000	EACH
20	805-87490 INSULATING LINK, WATER PROOFED, FURNISH	24.000	EACH
21	805-95524 HANDHOLE COVER	6.000	EACH
22	807-02191 HANDHOLE, LIGHTING	6.000	EACH
23	807-02783 LUMINAIRE MAST ARM, 15 FT.	38.000	EACH
24	807-04309 PORTABLE TOWER LIGHTING DRIVE SYSTEM	1.000	EACH
25	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	19,244.000	LFT
26	807-09371 HIGH MAST TOWER LOWERING DEVICE	8.000	EACH
27	807-82003 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 4 LUMINARIES	2.000	EACH
28	807-82004 SIGN CIRCUIT INSTALLATION, BOX TRUSS, 5 LUMINAIRES	2.000	EACH
29	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE	38.000	EACH
30	807-86665 LUMINAIRE, HIGH MAST, 1000 WATT, HIGH PRESSURE SODIUM	48.000	EACH
31	807-86790 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, 250 WATT	18.000	EACH
32	807-86810 SERVICE POINT, II	4.000	EACH
33	807-86910 CONNECTOR KIT, UNFUSED	38.000	EACH
34	807-86915 CONNECTOR KIT, FUSED	38.000	EACH
35	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	95.000	EACH
36	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	24.000	EACH
37	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	2.000	EACH
38	807-86955 CABLE DUCT MARKER	25.000	EACH
39	807-92523 SKIRTING, EXPANDED ALUMINUM	14.000	EACH

