

CALL ORDER : 131

CONTRACT ID : IR-29960-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DEMOLITION, REMOVE BUILDINGS			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-02240 PAVEMENT REMOVAL	672.000	SYS
7	202-02255 TREE, 18 IN., REMOVE	12.000	EACH
8	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
9	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10	205-06937 TEMPORARY SILT FENCE	526.000	LFT
11	621-06560 MULCHED SEEDING, U	860.000	SYS
12	801-06640 CONSTRUCTION SIGN, A	6.000	EACH

CALL ORDER : 141

CONTRACT ID : IR-30991-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION REMOVE BUILDINGS		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
4 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
6 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
7 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
8 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
9 202-03000	HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
10 202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	312.000	SFT
11 202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	70.000	LFT
12 205-06937	TEMPORARY SILT FENCE	1,200.000	LFT
13 621-06560	MULCHED SEEDING, U	3,000.000	SYS

CALL ORDER : 181

CONTRACT ID : R -27109-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
3	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
4	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
5	203-02000 EXCAVATION, COMMON	300.000	CYS
6	205-02459 EROSION CONTROL	LUMP	LUMP
7	211-07454 STRUCTURE BACKFILL	35.000	CYS
8	303-01180 COMPACTED AGGREGATE, NO. 53	300.000	TON
9	303-60012 AGGREGATE, 2	29.000	TON
10	303-93714 BOULDER	12.000	EACH
11	304-07490 HMA PATCHING, TYPE B	7.000	TON
12	402-07433 HMA SURFACE, TYPE B	85.000	TON
13	402-07438 HMA INTERMEDIATE, TYPE B	170.000	TON
14	402-07441 HMA BASE, TYPE B	29.000	TON
15	406-05521 ASPHALT FOR TACK COAT	1,150.000	SYS
16	604-04740 PAVERS	2,400.000	SFT
17	604-04740 PAVERS	2,500.000	SFT
18	604-07894 CURB RAMP, CONCRETE, A	11.000	SYS
19	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
20	604-07903 CURB RAMP, CONCRETE, K	14.000	SYS
21	604-91531 SIDEWALK, CONCRETE, 4 IN.	8.000	SYS
22	605-01870 CURB, CONCRETE, A	56.000	LFT
23	605-06120 CURB, CONCRETE	434.000	LFT
24	605-09176 CURB TURNOUT, CONCRETE	12.000	LFT
25	621-02166 MULCHED SEEDING, SPECIAL CLASS	400.000	SYS
26	621-06565 MULCHING MATERIAL	30.000	TON
27	621-06570 TOP SOIL	50.000	CYS
28	621-06570 TOP SOIL	55.000	CYS
29	621-09273 WEED BARRIER	171.000	SYS
30	621-09274 PLANT MATERIAL	LUMP	LUMP
31	621-98038 MULCH, HARDWOOD SHREDDED BARK	25.000	CYS
32	622-06576 IRRIGATION	1.000	LFT
33	628-09402 FIELD OFFICE, B	9.000	MOS
34	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	9.000	MOS
35	707-99085 FLAG POLE	1.000	EACH
36	711-98282 BUILDING ELECTRICAL	LUMP	LUMP
37	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN.	35.000	LFT
38	715-92037 PIPE, PVC, 4 IN.	160.000	LFT
39	720-91333 INLET, I-C	1.000	EACH
40	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
41	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	802-03896 BOLLARD	10.000	EACH
44	802-03896 BOLLARD	2.000	EACH
45	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.500	SFT
46	805-97827 TRENCH	800.000	LFT
47	807-02560 ELECTRICAL WORK	LUMP	LUMP
48	807-03970 LIGHT POLE BASE	9.000	EACH
49	807-03972 CONDUIT, PVC, 1 IN., SCHEDULE 40, FOR ELECTRIC	625.000	LFT

CALL ORDER : 181

CONTRACT ID : R -27109-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT		
50 807-04651	WIRE	1,425.000	LFT
51 807-04651	WIRE	1,050.000	LFT
52 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	443.000	LFT
53 808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	74.000	LFT
54 808-97222	PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 191

CONTRACT ID : R -28096-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, ECKERT MILL		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 109-08359	LIQUIDATED DAMAGES	1.000	DOL
3 109-08360	CONTRACT LIENS	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 203-07084	EXCAVATION	LUMP	LUMP
7 206-51235	COFFERDAM	LUMP	LUMP
8 628-09401	FIELD OFFICE, A	12.000	MOS
9 711-03973	BUILDING ARCHITECTURAL	LUMP	LUMP
10 719-03975	BUILDING PLUMBING	LUMP	LUMP
11 807-03694	BUILDING ELECTRICAL	LUMP	LUMP
12 807-03974	BUILDING HEATING, VENTILATION, AIR CONDITIONING	LUMP	LUMP

CALL ORDER : 201

CONTRACT ID : R -28197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	60.000	m2
10	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11	202-05545 REGULATED MATERIALS, DISPOSE, C	925.000	m3
12	202-05550 REGULATED MATERIALS, REMOVE, C	925.000	m3
13	202-05556 REGULATED MATERIALS, TRANSPORT, C	925.000	Mg
14	202-08429 REGULATED MATERIALS, DISPOSE, B	3,000.000	L
15	202-08430 REGULATED MATERIALS, REMOVE, B	3,000.000	L
16	202-08431 REGULATED MATERIALS, TRANSPORT, B	3,000.000	L
17	202-09106 TESTING FOR CONTAMINATED MATERIALS, MTBE AND	10.000	EACH
18	202-52710 SIDEWALK, CONCRETE, REMOVE	530.000	m2
19	202-92222 TESTING FOR CONTAMINATED MATERIALS, TPH	16.000	EACH
20	203-02000 EXCAVATION, COMMON	1,690.000	m3
21	205-03371 SEDIMENT REMOVE	10.000	m3
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	19.000	Mg
23	205-06937 TEMPORARY SILT FENCE	360.000	m
24	207-08263 SUBGRADE TREATMENT, TYPE IA	2,586.000	m2
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,939.100	m2
26	211-09264 STRUCTURE BACKFILL, TYPE 1	7.800	m3
27	213-09270 FLOWABLE BACKFILL, REMOVEABLE	23.200	m3
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	518.000	Mg
29	306-08034 MILLING, ASPHALT, 38 mm	7,204.400	m2
30	306-08043 MILLING, TRANSITION	712.600	m2
31	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	824.000	Mg
32	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	262.000	Mg
33	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	943.000	Mg
34	402-07433 HMA SURFACE, TYPE B	76.000	Mg
35	402-07441 HMA BASE, TYPE B	170.000	Mg
36	402-07453 HMA FOR TEMPORARY PAVEMENT	64.100	Mg
37	406-05520 ASPHALT FOR TACK COAT	4.700	Mg
38	604-07899 CURB RAMP, CONCRETE, E	35.600	m2
39	604-07901 CURB RAMP, CONCRETE, G	20.500	m2
40	604-07903 CURB RAMP, CONCRETE, K	7.500	m2
41	604-91531 SIDEWALK, CONCRETE, 100 mm	631.800	m2
42	605-06120 CURB, CONCRETE	236.000	m
43	605-94811 CURB TURNOUT	2.000	EACH
44	610-07487 HMA FOR APPROACHES, TYPE B	668.000	Mg
45	610-08446 PCCP FOR APPROACHES, 150 mm	222.700	m2
46	610-09108 PCCP FOR APPROACHES, 225 mm	607.800	m2
47	615-06490 RIGHT OF WAY MARKER	10.000	EACH
48	615-06505 MONUMENT, B	7.000	EACH
49	616-02320 GEOTEXTILES	12.000	m2

CALL ORDER : 201

CONTRACT ID : R -28197-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
50	616-06405 RIPRAP, REVETMENT	4.800	Mg
51	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
52	621-06545 FERTILIZER	0.100	Mg
53	621-06557 SEED MIXTURE, T	51.000	kg
54	621-06560 MULCHED SEEDING, U	857.000	m2
55	621-06565 MULCHING MATERIAL	1.400	Mg
56	621-06567 WATER	38.200	kL
57	621-06575 SODDING, NURSERY	2,123.000	m2
58	628-09402 FIELD OFFICE, B	6.000	MOS
59	715-05118 PIPE, TYPE 1, CIRCULAR, 300 mm	108.200	m
60	715-05168 PIPE, TYPE 3, CIRCULAR, 300 mm	14.000	m
61	715-09064 VIDEO INSPECTION FOR PIPE	42.200	m
62	715-46000 PIPE END SECTION, 300 mm	4.000	EACH
63	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
64	720-44296 CAP INLET	4.000	EACH
65	720-45275 PIPE CATCH BASIN, 600 mm	5.000	EACH
66	720-99416 CATCH BASIN, B15	4.000	EACH
67	732-09163 TEST	8.000	EACH
68	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
69	801-06203 TEMPORARY PAVEMENT MARKING, 100 mm	2,637.000	m
70	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07612 TEMPORARY PAVEMENT MARKING, 600 mm	18.000	m
73	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	179.000	m
74	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	7.500	m
75	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	24.500	m2
76	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND 2.54 mm THICKNESS	8.000	m2
77	805-01815 SIGNAL SUPPORT FOUNDATION, 915mm X 3.7 m	4.000	EACH
78	805-01819 CONDUIT, STEEL, GALVANIZED, 50 mm, ABOVE GROUND	4.000	m
79	805-01879 SIGNAL SERVICE, INSTALL	1.000	EACH
80	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
81	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm AMBER	4.000	EACH
82	805-78195 TRAFFIC SIGNAL HEAD, 1 FACE, 305 mm RED	4.000	EACH
83	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
84	805-78420 DISCONNECT HANGER	4.000	EACH
85	805-78467 SIGNAL CABLE, 3C 8GA.	34.000	m
86	805-78485 SIGNAL CABLE, 5C 14GA.	182.000	m
87	805-81032 SIGNAL STRAIN POLE, STEEL, 9.2m	4.000	EACH
88	808-04298 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (R X R)	1.000	EACH
89	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,980.000	m
90	808-75067 TRANSVERSE MARKINGS, PREFORMED PLASTIC, STOP LINE, 600 mm	108.600	m
91	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	2,528.000	m
92	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 150 mm	252.000	m
93	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	12.000	EACH
94	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	12.000	EACH
95	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 200mm	828.000	m
96	808-96016 LINE, THERMOPLASTIC, SOLID, YELLOW, 300 mm	116.000	m

CALL ORDER : 211

CONTRACT ID : R -29016-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	30.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-01405 CONTAMINATED SOIL, REMOVE AND DISPOSE	58.000	CYS
13	202-02637 PIPE, ABANDON AND GROUT FILL	195.000	LFT
14	202-91385 INLET, REMOVE	9.000	EACH
15	203-02000 EXCAVATION, COMMON	574.000	CYS
16	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	41.000	EACH
17	205-06937 TEMPORARY SILT FENCE	1,083.000	LFT
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,008.000	SYS
19	207-08268 SUBGRADE TREATMENT, TYPE IV	1,375.000	SYS
20	211-02050 B BORROW	335.000	CYS
21	211-09264 STRUCTURE BACKFILL, TYPE 1	703.000	CYS
22	304-07493 WIDENING WITH HMA, TYPE B	424.000	TON
23	306-08033 MILLING, ASPHALT, 1 IN.	445.000	SYS
24	306-08036 MILLING, ASPHALT, 2 IN.	2,557.000	SYS
25	306-08042 MILLING, SCARIFICATION/PROFILE	396.000	SYS
26	306-08043 MILLING, TRANSITION	1,150.000	SYS
27	402-07433 HMA SURFACE, TYPE B	446.000	TON
28	402-07438 HMA INTERMEDIATE, TYPE B	743.000	TON
29	406-05520 ASPHALT FOR TACK COAT	2.720	TON
30	604-07900 CURB RAMP, CONCRETE, F	81.000	SYS
31	604-07902 CURB RAMP, CONCRETE, H	133.000	SYS
32	604-91531 SIDEWALK, CONCRETE, 4 IN.	823.000	SYS
33	605-06120 CURB, CONCRETE	1,361.000	LFT
34	605-06140 CURB AND GUTTER, CONCRETE	1,187.000	LFT
35	610-07487 HMA FOR APPROACHES, TYPE B	82.000	TON
36	610-08446 PCCP FOR APPROACHES, 6 IN.	101.000	SYS
37	610-09108 PCCP FOR APPROACHES, 9 IN.	608.000	SYS
38	615-06490 RIGHT OF WAY MARKER	6.000	EACH
39	615-06505 MONUMENT, B	6.000	EACH
40	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
41	621-06545 FERTILIZER	0.020	TON
42	621-06557 SEED MIXTURE, T	12.150	LBS
43	621-06565 MULCHING MATERIAL	0.300	TON
44	621-06570 TOP SOIL	82.000	CYS
45	621-06575 SODDING, NURSERY	735.000	SYS
46	622-91786 SEEDLING	24.000	EACH
47	628-09402 FIELD OFFICE, B	15.000	MOS
48	702-51863 FIELD DRILLED HOLE IN CONCRETE	1.000	EACH
49	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	42.000	LFT



CALL ORDER : 211

CONTRACT ID : R -29016-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	973.000	LFT
51	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	107.000	LFT
52	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	93.000	TON
53	715-93910 WATER SERVICE LINE, ADJUST	1.000	EACH
54	715-93910 WATER SERVICE LINE, ADJUST	1.000	EACH
55	715-93910 WATER SERVICE LINE, ADJUST	2.000	EACH
56	715-93910 WATER SERVICE LINE, ADJUST	1.000	EACH
57	720-01092 MANHOLE, J15, MODIFIED	6.000	EACH
58	720-44000 CASTING, ADJUST TO GRADE	6.000	EACH
59	720-44070 CASTING, 13, FURNISH AND ADJUST TO GRADE	1.000	EACH
60	720-45410 MANHOLE, C4	14.000	EACH
61	720-90984 MANHOLE, C2	1.000	EACH
62	720-98174 INLET, B15	19.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
64	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,494.000	LFT
65	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	88.000	LFT
66	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
67	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
68	801-07118 BARRICADE, III-A	48.000	LFT
69	801-94295 SIGNAL HEAD, RELOCATE	24.000	EACH
70	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	136.000	LFT
71	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	91.170	SFT
72	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	40.500	SFT
73	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	4.000	EACH
74	805-01820 SIGNAL STRAIN POLE, STEEL, INSTALL	4.000	EACH
75	805-01842 HANDHOLE, SIGNAL	4.000	EACH
76	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	700.000	LFT
77	805-02658 CABLE, COAXIAL	100.000	LFT
78	805-08466 RADIO ANTENNA, 9db, YAGI	1.000	EACH
79	805-08487 TRAFFIC SIGNAL BACKPLATE	4.000	EACH
80	805-08493 RADIO SYSTEM TESTING INTERCONNECT	LUMP	LUMP
81	805-08494 RADIO SPREAD SPECTRUM	1.000	EACH
82	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
83	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
84	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
85	805-78420 DISCONNECT HANGER	4.000	EACH
86	805-78445 SIGNAL SERVICE	1.000	EACH
87	805-78467 SIGNAL CABLE, 3C 8GA.	60.000	LFT
88	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,400.000	LFT
89	805-78480 SIGNAL CABLE, 3C 14GA.	520.000	LFT
90	805-78485 SIGNAL CABLE, 5C 14GA.	840.000	LFT
91	805-78490 SIGNAL CABLE, 7C 14GA.	470.000	LFT
92	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,800.000	LFT
93	805-78785 SIGNAL DETECTOR HOUSING	8.000	EACH
94	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,480.000	LFT
95	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
96	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
97	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	16.000	EACH
98	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	304.000	LFT

CALL ORDER : 211

CONTRACT ID : R -29016-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
99 808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	500.000	LFT
100 808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	140.000	LFT
101 808-06716	LINE, REMOVE	1,882.000	LFT
102 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,281.000	LFT
103 808-75260	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	84.000	LFT
104 808-75300	TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	566.000	LFT
105 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
106 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH

CALL ORDER : 221

CONTRACT ID : R -29029-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHAB			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	36.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02278 CURB, CONCRETE, REMOVE	4,211.000	LFT
13	202-52710 SIDEWALK, CONCRETE, REMOVE	2,809.000	SYS
14	202-74035 SIGN, REMOVE	41.000	EACH
15	203-02000 EXCAVATION, COMMON	13,605.000	CYS
16	205-03371 SEDIMENT, REMOVE	3.000	CYS
17	205-06937 TEMPORARY SILT FENCE	790.000	LFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	25,546.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,512.000	SYS
20	211-07454 STRUCTURE BACKFILL	3,375.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	133.000	TON
22	303-07449 COMPACTED AGGREGATE, NO. 73	2.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	273.000	SYS
24	306-08043 MILLING, TRANSITION	49.000	SYS
25	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,546.000	TON
26	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,576.000	TON
27	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	7,887.000	TON
28	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	1,658.000	TON
29	402-07450 HMA WEDGE AND LEVEL, TYPE A	137.000	TON
30	402-07453 HMA FOR TEMPORARY PAVEMENT	13.000	TON
31	406-05520 ASPHALT FOR TACK COAT	3.500	TON
32	604-07896 CURB RAMP, CONCRETE, B	28.000	SYS
33	604-07900 CURB RAMP, CONCRETE, F	67.000	SYS
34	604-07901 CURB RAMP, CONCRETE, G	186.000	SYS
35	604-07902 CURB RAMP, CONCRETE, H	20.000	SYS
36	604-44251 STEPS, CONCRETE	4.000	CYS
37	604-91531 SIDEWALK, CONCRETE, 4 IN.	5,276.000	SYS
38	605-06120 CURB, CONCRETE	130.000	LFT
39	605-06140 CURB AND GUTTER, CONCRETE	9,410.000	LFT
40	610-07487 HMA FOR APPROACHES, TYPE B	961.000	TON
41	610-08446 PCCP FOR APPROACHES, 6 IN.	1,134.000	SYS
42	610-09108 PCCP FOR APPROACHES, 9 IN.	379.000	SYS
43	611-02825 MAILBOX ASSEMBLY, TRIPLE	2.000	EACH
44	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
45	611-06498 MAILBOX ASSEMBLY, DOUBLE	8.000	EACH
46	614-06482 HEADER, CEMENT CONCRETE, D	195.000	SYS
47	615-06490 RIGHT OF WAY MARKER	8.000	EACH
48	615-06505 MONUMENT, B	3.000	EACH
49	615-06527 MONUMENT, SECTION CORNER	2.000	EACH

CALL ORDER : 221

CONTRACT ID : R -29029-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHAB		
50	616-02320 GEOTEXTILES	53.000	SYS
51	616-06405 RIPRAP, REVETMENT	41.000	TON
52	621-06575 SODDING, NURSERY	7,949.000	SYS
53	628-09401 FIELD OFFICE, A	12.000	MOS
54	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	9,205.000	LFT
55	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	2,428.000	LFT
56	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	885.000	LFT
57	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	511.000	LFT
58	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	835.000	LFT
59	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	315.000	LFT
60	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	744.000	LFT
61	715-46015 PIPE END SECTION, 21 IN.	1.000	EACH
62	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
63	716-07635 PIPE INSTALLATION, TRENCHLESS, 36 IN.	70.000	LFT
64	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	8,734.000	LFT
65	718-52610 AGGREGATE FOR UNDERDRAINS	777.000	CYS
66	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,036.000	SYS
67	720-45075 INLET, R13	2.000	EACH
68	720-45410 MANHOLE, C4	24.000	EACH
69	720-95422 MANHOLE, J4	4.000	EACH
70	720-98174 INLET, B15	40.000	EACH
71	720-98555 INLET, C15	33.000	EACH
72	732-08419 MODULAR BLOCK WALL	184.000	SYS
73	732-08421 MODULAR BLOCK WALL ERECTION	184.000	SYS
74	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
75	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
76	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
77	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	8,634.000	LFT
78	801-06625 DETOUR ROUTE MARKER ASSEMBLY	32.000	EACH
79	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
80	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
81	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
82	801-07118 BARRICADE, III-A	52.000	LFT
83	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	200.000	LFT
84	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	374.000	LFT
85	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	171.000	SFT
86	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	57.040	SFT
87	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,507.000	LFT
88	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,986.000	LFT
89	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	281.000	LFT
90	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,581.000	LFT
91	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
92	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	75.000	EACH

CALL ORDER : 241

CONTRACT ID : R -29148-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02245 TREE, 6 IN., REMOVE	3.000	EACH
9	202-02250 TREE, 10 IN., REMOVE	5.000	EACH
10	202-02255 TREE, 18 IN., REMOVE	5.000	EACH
11	202-02260 TREE, 30 IN., REMOVE	1.000	EACH
12	202-02265 TREE, 48 IN., REMOVE	1.000	EACH
13	202-02279 CURB AND GUTTER, REMOVE	101.000	LFT
14	202-74035 SIGN, REMOVE	3.000	EACH
15	202-93047 MANHOLE, REMOVE	1.000	EACH
16	202-96133 PIPE, REMOVE	308.000	LFT
17	203-02000 EXCAVATION, COMMON	929.000	CYS
18	205-06933 TEMPORARY DITCH INLET PROTECTION	10.000	EACH
19	205-06937 TEMPORARY SILT FENCE	1,100.000	LFT
20	211-02050 B BORROW	58.000	CYS
21	211-09264 STRUCTURE BACKFILL, TYPE 1	307.000	CYS
22	211-09266 STRUCTURE BACKFILL, TYPE 3	82.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	601.000	TON
24	402-07432 HMA SURFACE, TYPE A	140.000	TON
25	402-07435 HMA INTERMEDIATE, TYPE A	233.000	TON
26	406-05520 ASPHALT FOR TACK COAT	0.500	TON
27	603-03692 FENCE, WOOD	100.000	LFT
28	604-07894 CURB RAMP, CONCRETE, A	81.000	SYS
29	604-91531 SIDEWALK, CONCRETE, 4 IN.	65.000	SYS
30	605-06120 CURB, CONCRETE	1,905.000	LFT
31	605-06140 CURB AND GUTTER, CONCRETE	101.000	LFT
32	610-08510 PCCP FOR APPROACHES	114.000	SYS
33	616-02320 GEOTEXTILES	65.000	SYS
34	616-06405 RIPRAP, REVETMENT	34.000	TON
35	621-06567 WATER	9.500	KGAL
36	621-06575 SODDING, NURSERY	2,635.000	SYS
37	628-09401 FIELD OFFICE, A	10.000	MOS
38	703-06028 REINFORCING BARS	1,273.000	LBS
39	714-44240 CONCRETE, A, STRUCTURES	18.000	CYS
40	715-04612 PIPE	12.000	LFT
41	715-05147 PIPE, TYPE 2, CIRCULAR, 8 IN.	5.000	LFT
42	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	41.000	LFT
43	715-05331 PIPE, TYPE 2, DEFORMED, MIN. AREA 3.3 SFT.	308.000	LFT
44	715-06051 PIPE EXTENSION, CIRCULAR, 8 IN.	12.000	LFT
45	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
46	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
47	720-45030 INLET, E7	2.000	EACH
48	720-45070 INLET, P12A	2.000	EACH
49	720-45415 MANHOLE, D4	2.000	EACH

CALL ORDER : 241

CONTRACT ID : R -29148-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITY		
50	732-08419 MODULAR BLOCK WALL	47.000	SYS
51	732-08421 MODULAR BLOCK WALL ERECTION	47.000	SYS
52	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	720.000	LFT
54	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
55	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
56	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
57	801-07119 BARRICADE, III-B	120.000	LFT
58	802-03896 BOLLARD	8.000	EACH
59	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	149.000	LFT
60	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	50.000	SFT
61	808-06716 LINE, REMOVE	384.000	LFT
62	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	646.000	LFT
63	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	748.000	LFT
64	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	112.000	LFT
65	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	342.000	LFT
66	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH

CALL ORDER : 251

CONTRACT ID : R -29217-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
16	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
17	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	50.000	SFT
18	202-03729 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	175.000	LFT
19	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	15.000	EACH
20	203-02000 EXCAVATION, COMMON	1,590.000	CYS
21	203-93412 LIGHTWEIGHT ENGINEERED FILL, III	2,305.000	CYS
22	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	105.000	TON
23	205-06937 TEMPORARY SILT FENCE	1,370.000	LFT
24	207-08263 SUBGRADE TREATMENT, TYPE IA	11,639.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,896.000	SYS
26	211-09264 STRUCTURE BACKFILL, TYPE 1	18.000	CYS
27	213-08058 FLOWABLE BACKFILL	50.000	CYS
28	214-07202 GEOGRID, I	4,320.000	SYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,716.000	TON
30	306-08034 MILLING, ASPHALT, 1 1/2 IN.	240.000	SYS
31	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
32	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,173.000	TON
33	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,174.000	TON
34	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	3,554.000	TON
35	402-07433 HMA SURFACE, TYPE B	155.000	TON
36	402-07438 HMA INTERMEDIATE, TYPE B	260.000	TON
37	402-07441 HMA BASE, TYPE B	825.000	TON
38	406-05521 ASPHALT FOR TACK COAT	46,314.000	SYS
39	610-07486 HMA FOR APPROACHES, TYPE A	281.000	TON
40	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
41	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
42	615-06336 MONUMENT	2.000	EACH
43	615-06490 RIGHT OF WAY MARKER	41.000	EACH
44	615-06500 MONUMENT, A	8.000	EACH
45	615-06530 POST, BENCHMARK	1.000	EACH
46	616-02320 GEOTEXTILES	9,717.000	SYS
47	616-06025 BORROW, COHESIVE	1,350.000	CYS
48	616-06451 RIPRAP, UNIFORM	251.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

CALL ORDER : 251

CONTRACT ID : R -29217-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
50	621-02770 EROSION CONTROL BLANKET	3,020.000	SYS
51	621-06545 FERTILIZER	1.630	TON
52	621-06553 SEED MIXTURE, R	629.000	LBS
53	621-06565 MULCHING MATERIAL	8.140	TON
54	621-06567 WATER	14.000	KGAL
55	621-06574 SODDING	3,195.000	SYS
56	621-06575 SODDING, NURSERY	813.000	SYS
57	622-52436 SIGN, DO NOT MOW OR SPRAY	19.000	EACH
58	628-09402 FIELD OFFICE, B	6.000	MOS
59	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN.	198.000	LFT
60	715-05361 PIPE, TYPE 3, DEFORMED, MIN. AREA 1.1 SQ. FT.	78.000	LFT
61	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	30.000	TON
62	715-97692 GRATED BOX END SECTION, I, 4:1, 36 IN.	2.000	EACH
63	715-98964 GRATED BOX END SECTION, II, 6:1, 17 IN. X 13 IN.	4.000	EACH
64	715-98974 GRATED BOX END SECTION, II, 6:1, 36 IN.	2.000	EACH
65	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
66	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
67	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	28,000.000	LFT
68	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	50.000	LFT
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
71	801-06645 CONSTRUCTION SIGN, B	15.000	EACH
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-07119 BARRICADE, III-B	96.000	LFT
74	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	29.000	LFT
75	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	124.000	LFT
76	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	16.500	LFT
77	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	165.000	LFT
78	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
79	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	33.000	SFT
80	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	182.600	SFT
81	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
82	805-01842 HANDHOLE, SIGNAL	15.000	EACH
83	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
84	805-04736 SIGNAL CABLE, 4C 18GA.	1,755.000	LFT
85	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	2,205.000	LFT
86	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
87	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
88	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
89	805-78420 DISCONNECT HANGER	4.000	EACH
90	805-78445 SIGNAL SERVICE	1.000	EACH
91	805-78467 SIGNAL CABLE, 3C 8GA.	50.000	LFT
92	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,240.000	LFT
93	805-78485 SIGNAL CABLE, 5C 14GA.	131.000	LFT
94	805-78490 SIGNAL CABLE, 7C 14GA.	652.000	LFT
95	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,217.000	LFT
96	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
97	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	763.000	LFT
98	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH



CALL ORDER : 251

CONTRACT ID : R -29217-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
99	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
100	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
101	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	3.000	EACH
102	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.000	EACH
103	805-92512 MICROLOOP DETECTOR	8.000	EACH
104	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	7,871.000	LFT
105	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	9,122.000	LFT
106	808-06716 LINE, REMOVE	9,920.000	LFT
107	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	6.000	EACH
108	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	4.000	EACH
109	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	125.000	LFT
110	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,871.000	LFT
111	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,442.000	LFT
112	808-75290 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	193.000	LFT
113	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	125.000	LFT
114	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH
115	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
116	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	62.000	EACH
117	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	111.000	EACH
118	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,840.000	LFT

CALL ORDER : 261

CONTRACT ID : R -29418-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	9,929.000	CYS
13	203-02070 BORROW	3,369.000	CYS
14	203-51223 EXCAVATION, WATERWAY	984.000	CYS
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	560.000	LFT
16	205-06934 TEMPORARY MULCHING	3.100	TON
17	205-06937 TEMPORARY SILT FENCE	5,655.000	LFT
18	207-08265 SUBGRADE TREATMENT, TYPE IIA	16,283.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	538.000	SYS
20	211-09264 STRUCTURE BACKFILL, TYPE 1	25.000	CYS
21	211-09265 STRUCTURE BACKFILL, TYPE 2	75.000	CYS
22	211-09267 STRUCTURE BACKFILL, TYPE 4	9.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,551.000	TON
24	302-07455 DENSE GRADED SUBBASE	40.200	CYS
25	303-01180 COMPACTED AGGREGATE, NO. 53	4,512.000	TON
26	306-08042 MILLING, SCARIFICATION/PROFILE	2,100.000	SYS
27	306-08043 MILLING, TRANSITION	350.000	SYS
28	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
29	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,384.000	TON
30	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	4,487.000	TON
31	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	519.000	TON
32	404-05514 SEAL COAT, 5	3,347.000	SYS
33	406-05520 ASPHALT FOR TACK COAT	5.500	TON
34	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
35	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	750.000	LFT
38	605-06121 CURB, CONCRETE, B	250.000	LFT
39	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	241.200	SYS
40	610-07487 HMA FOR APPROACHES, TYPE B	321.000	TON
41	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
42	615-06505 MONUMENT, B	2.000	EACH
43	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
44	616-02320 GEOTEXTILES	711.000	SYS
45	616-06405 RIPRAP, REVETMENT	496.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
47	621-06545 FERTILIZER	2.500	TON
48	621-06553 SEED MIXTURE, R	711.000	LBS
49	621-06557 SEED MIXTURE, T	183.000	LBS

CALL ORDER : 261

CONTRACT ID : R -29418-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06565 MULCHING MATERIAL	8.400	TON
51	621-06567 WATER	7.000	KGAL
52	621-06574 SODDING	1,880.000	SYS
53	628-09402 FIELD OFFICE, B	12.000	MOS
54	701-02938 CORED HOLE IN ROCK, 24 IN.	42.000	LFT
55	701-09144 PILE, STEEL H, REINFORCED CONCRETE, HP 12 X 53	154.000	LFT
56	701-51195 PILE, STEEL H, HP 12 X 53	323.000	LFT
57	701-91792 PILE TIP, STEEL H	24.000	EACH
58	703-51030 REINFORCING STEEL	21,400.000	LBS
59	703-51032 REINFORCING STEEL, EPOXY COATED	33,739.000	LBS
60	704-51002 CONCRETE, C, SUPERSTRUCTURE	225.700	CYS
61	706-06344 RAILING, TS-1	187.500	LFT
62	709-51821 SURFACE SEAL	LUMP	LUMP
63	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	161.000	LFT
64	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	114.000	LFT
65	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN.	225.000	LFT
66	715-46005 PIPE END SECTION, 15 IN.	4.000	EACH
67	715-46010 PIPE END SECTION, 18 IN.	2.000	EACH
68	715-46020 PIPE END SECTION, 24 IN.	4.000	EACH
69	801-04308 ROAD CLOSURE SIGN ASSEMBLY	13.000	EACH
70	801-06625 DETOUR ROUTE MARKER ASSEMBLY	44.000	EACH
71	801-06640 CONSTRUCTION SIGN, A	34.000	EACH
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-07118 BARRICADE, III-A	144.000	LFT
74	801-07119 BARRICADE, III-B	384.000	LFT
75	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	40.000	LFT
76	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.250	SFT
77	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	18.000	SFT
78	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	1,109.000	LFT
79	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	9,655.000	LFT
80	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	3,280.000	LFT
81	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	30.000	LFT

CALL ORDER : 281

CONTRACT ID : R -29558-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02271 HEADWALL, REMOVE	2.000	EACH
13	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	16.000	EACH
14	202-96133 PIPE, REMOVE	95.000	LFT
15	203-02000 EXCAVATION, COMMON	586.000	CYS
16	203-02020 EXCAVATION, UNCLASSIFIED	100.000	CYS
17	203-02070 BORROW	335.000	CYS
18	205-02236 TEMPORARY EROSION AND SEDIMENT CONTROL, DROP INLET	1.000	EACH
19	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	3.000	EACH
20	205-03371 SEDIMENT, REMOVE	5.000	CYS
21	205-06932 TEMPORARY CHECK DAM, STRAW BALES	24.000	LFT
22	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
23	205-06937 TEMPORARY SILT FENCE	671.000	LFT
24	207-08263 SUBGRADE TREATMENT, TYPE IA	1,382.000	SYS
25	211-09265 STRUCTURE BACKFILL, TYPE 2	93.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	106.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN.	3,500.000	SYS
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	410.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	131.000	TON
30	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	527.000	TON
31	406-05521 ASPHALT FOR TACK COAT	6,477.000	SYS
32	604-07897 CURB RAMP, CONCRETE, C	19.000	SYS
33	604-07900 CURB RAMP, CONCRETE, F	32.000	SYS
34	604-07901 CURB RAMP, CONCRETE, G	9.000	SYS
35	604-44251 STEPS, CONCRETE	1.000	CYS
36	604-91531 SIDEWALK, CONCRETE, 4 IN.	161.000	SYS
37	605-06120 CURB, CONCRETE	41.000	LFT
38	605-06140 CURB AND GUTTER, CONCRETE	475.000	LFT
39	607-06335 PAVED SIDE DITCH, A	25.000	LFT
40	610-07486 HMA FOR APPROACHES, TYPE A	53.000	TON
41	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
42	615-06490 RIGHT OF WAY MARKER	4.000	EACH
43	615-06505 MONUMENT, B	5.000	EACH
44	616-02320 GEOTEXTILES	52.000	SYS
45	616-06451 RIPRAP, UNIFORM	43.000	TON
46	621-06575 SODDING, NURSERY	2,196.000	SYS
47	628-09401 FIELD OFFICE, A	12.000	MOS
48	706-92237 HANDRAIL, STEEL	6.000	LFT
49	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	176.000	LFT

CALL ORDER : 281

CONTRACT ID : R -29558-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	120.000	LFT
51	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	150.000	LFT
52	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
53	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
54	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
55	720-45040 INLET, G7	1.000	EACH
56	720-45415 MANHOLE, D4	2.000	EACH
57	720-90984 MANHOLE, C2	1.000	EACH
58	720-98174 INLET, B15	3.000	EACH
59	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
60	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,734.000	LFT
61	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,031.000	LFT
62	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	59.000	LFT
63	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	44.000	LFT
64	801-06586 TEMPORARY PAVEMENT MARKING, 8 IN.	70.000	LFT
65	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
66	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
67	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
68	801-92448 CONSTRUCTION SIGNS, MOBILE	260.000	DAY
69	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	370.000	LFT
70	802-76020 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.080 IN. THICKNESS	157.110	SFT
71	802-76030 SIGN, SHEET, ENCLOSED LENS WITH LEGEND, 0.100 IN. THICKNESS	27.000	SFT
72	805-01828 TRAFFIC SIGNAL HEAD, REALIGN	1.000	EACH
73	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,110.000	LFT
74	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	59.000	LFT
75	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	32.000	LFT
76	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,934.000	LFT
77	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	73.000	LFT
78	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	292.000	LFT
79	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.000	EACH
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	21.000	EACH

CALL ORDER : 291

CONTRACT ID : R -29592-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02245 TREE, 6 IN., REMOVE	9.000	EACH
12	202-02255 TREE, 18 IN., REMOVE	2.000	EACH
13	202-02278 CURB, CONCRETE, REMOVE	2,496.000	LFT
14	202-03875 CONCRETE STEPS, REMOVE	20.000	EACH
15	202-52710 SIDEWALK, CONCRETE, REMOVE	2,180.000	SYS
16	202-91385 INLET, REMOVE	10.000	EACH
17	202-93047 MANHOLE, REMOVE	1.000	EACH
18	202-96133 PIPE, REMOVE	36.000	LFT
19	203-02000 EXCAVATION, COMMON	1,292.000	CYS
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	597.000	SYS
21	207-08268 SUBGRADE TREATMENT, TYPE IV	3,502.000	SYS
22	210-06313 SEAL	4.000	LFT
23	210-06313 SEAL	3.000	LFT
24	211-09264 STRUCTURE BACKFILL, TYPE 1	623.000	CYS
25	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	9.000	CYS
26	306-08038 MILLING, ASPHALT, 4 IN.	3,605.000	SYS
27	306-08043 MILLING, TRANSITION	58.000	SYS
28	402-07433 HMA SURFACE, TYPE B	541.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	901.000	TON
30	402-07441 HMA BASE, TYPE B	1,556.000	TON
31	406-05520 ASPHALT FOR TACK COAT	4.000	TON
32	604-07896 CURB RAMP, CONCRETE, B	90.000	SYS
33	604-07900 CURB RAMP, CONCRETE, F	33.000	SYS
34	604-44251 STEPS, CONCRETE	2.000	CYS
35	604-91531 SIDEWALK, CONCRETE, 4 IN.	2,700.000	SYS
36	605-06140 CURB AND GUTTER, CONCRETE	2,363.000	LFT
37	610-07487 HMA FOR APPROACHES, TYPE B	125.000	TON
38	610-09108 PCCP FOR APPROACHES, 9 IN.	597.000	SYS
39	615-06505 MONUMENT, B	5.000	EACH
40	621-06567 WATER	1.200	KGAL
41	621-06575 SODDING, NURSERY	330.000	SYS
42	622-04648 TREE GRATE	17.000	EACH
43	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN.	17.000	EACH
44	628-09402 FIELD OFFICE, B	12.000	MOS
45	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
46	715-02181 SANITARY SEWER SERVICE ADJUSTMENT	12.000	LFT
47	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	790.000	LFT
48	715-05408 PIPE, SANITARY SEWER, 8 IN.	371.000	LFT
49	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	87.000	TON

CALL ORDER : 291

CONTRACT ID : R -29592-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	715-09064 VIDEO INSPECTION FOR PIPE	1,161.000	LFT
51	715-91361 PIPE, PVC, 6 IN.	169.000	LFT
52	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
53	720-45400 MANHOLE, A4	1.000	EACH
54	720-45410 MANHOLE, C4	1.000	EACH
55	720-93409 INLET, B15, MODIFIED	1.000	EACH
56	720-93411 INLET, C15, MODIFIED	1.000	EACH
57	720-98174 INLET, B15	6.000	EACH
58	720-98555 INLET, C15	4.000	EACH
59	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
60	801-06625 DETOUR ROUTE MARKER ASSEMBLY	36.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07118 BARRICADE, III-A	210.000	LFT
64	801-07119 BARRICADE, III-B	80.000	LFT
65	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	67.000	LFT
66	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	39.000	SFT
67	805-06101 FOUNDATION	2.000	EACH
68	805-92155 WIRE, XHHW, NO. 6 COPPER, 1/C	984.000	LFT
69	805-96014 SAW CUT, FULL DEPTH	325.000	LFT
70	805-98279 WIRE, THW, NO. 2/0 COPPER, 1/C	6,654.000	LFT
71	807-01603 SERVICE POINT, TYPE II	2.000	EACH
72	807-02191 HANDHOLE, LIGHTING	24.000	EACH
73	807-03484 WIRE XHHW, NO. 4 COPPER, 1C	4,727.000	LFT
74	807-03951 LIGHT POLE, ORNAMENTAL	24.000	EACH
75	807-04443 CONDUIT	4,275.000	LFT
76	807-04653 LIGHTING FOUNDATION	24.000	EACH
77	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	905.000	LFT
78	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,366.000	LFT
79	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	350.000	LFT
80	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	1,300.000	LFT
81	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
82	808-95933 CURB PAINTING, YELLOW	1,215.000	LFT
83	808-97664 PAVEMENT MESSAGE MARKINGS THERMOPLASTIC, HANDICAP SYMBOL	4.000	EACH

CALL ORDER : 301

CONTRACT ID : R -29755-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
5	105-08523 RADIO SERVICE	6.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
15	202-02240 PAVEMENT REMOVAL	784.000	SYS
16	202-74045 SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	2.000	EACH
17	202-86946 HANDHOLE, REMOVE	4.000	EACH
18	202-90277 DETECTOR HOUSING, REMOVE	4.000	EACH
19	202-91385 INLET, REMOVE	6.000	EACH
20	202-96133 PIPE, REMOVE	102.000	LFT
21	203-02000 EXCAVATION, COMMON	485.000	CYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	845.000	SYS
23	207-08268 SUBGRADE TREATMENT, TYPE IV	1,074.000	SYS
24	211-09264 STRUCTURE BACKFILL, TYPE 1	10.000	CYS
25	211-09265 STRUCTURE BACKFILL, TYPE 2	65.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	200.000	TON
27	302-07455 DENSE GRADED SUBBASE	90.000	CYS
28	306-08034 MILLING, ASPHALT, 1 1/2 IN.	2,960.000	SYS
29	306-08041 MILLING, PCCP	263.000	SYS
30	402-07433 HMA SURFACE, TYPE B	295.000	TON
31	402-07438 HMA INTERMEDIATE, TYPE B	49.000	TON
32	402-07441 HMA BASE, TYPE B	198.000	TON
33	406-05521 ASPHALT FOR TACK COAT	4,350.000	SYS
34	502-06329 PCCP, 12 IN.	420.000	SYS
35	503-03489 RETROFITTED TIE BARS	472.000	EACH
36	503-05240 D-1 CONTRACTION JOINT	210.000	LFT
37	506-06333 PCCP PATCHING, FULL DEPTH	100.000	SYS
38	604-07900 CURB RAMP, CONCRETE, F	30.000	SYS
39	604-91531 SIDEWALK, CONCRETE, 4 IN.	424.000	SYS
40	605-06090 CURB, INTEGRAL, CONCRETE	477.000	LFT
41	605-06120 CURB, CONCRETE	181.000	LFT
42	605-06255 CENTER CURB, D, CONCRETE	263.000	SYS
43	605-52807 CURB AND GUTTER, COMBINED	584.000	LFT
44	610-07712 PCCP FOR APPROACHES, 6 IN.	142.000	SYS
45	610-08510 PCCP FOR APPROACHES	703.000	SYS
46	615-06490 RIGHT OF WAY MARKER	13.000	EACH
47	615-06505 MONUMENT, B	1.000	EACH
48	615-06515 MONUMENT, D	5.000	EACH
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH



CALL ORDER : 301

CONTRACT ID : R -29755-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
50	621-06545 FERTILIZER	0.110	TON
51	621-06567 WATER	11.000	KGAL
52	621-06575 SODDING, NURSERY	2,634.000	SYS
53	628-09401 FIELD OFFICE, A	6.000	MOS
54	702-03607 CORED HOLE IN CONCRETE	1.000	EACH
55	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	46.000	LFT
56	715-08071 PIPE, RCP, III, DO.3=75, 12 IN.	159.000	LFT
57	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	20.000	TON
58	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
59	720-45045 INLET, J10	3.000	EACH
60	720-45055 INLET, M10	3.000	EACH
61	720-45410 MANHOLE, C4	1.000	EACH
62	720-98174 INLET, B15	4.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
64	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
65	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,300.000	LFT
66	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	9.000	EACH
67	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	3.000	EACH
68	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	30.000	LFT
69	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
70	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
71	801-06710 FLASHING ARROW SIGN	180.000	DAY
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-07119 BARRICADE, III-B	240.000	LFT
74	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	77.000	LFT
75	802-07127 SIGN, DOUBLE FACED, SHEET, ENCAPSULATED LENS, WITH LEGEND,	4.600	SFT
76	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	105.800	SFT
77	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	35.000	SFT
78	802-94715 SIGNS, SHEET, REMOVE AND RESET	LUMP	LUMP
79	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	2.000	EACH
80	805-01842 HANDHOLE, SIGNAL	3.000	EACH
81	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
82	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	4.000	EACH
83	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	145.000	LFT
84	805-08126 TRAFFIC SIGNAL HEAD	12.000	EACH
85	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
86	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	5.000	EACH
87	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	3.000	EACH
88	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	3.000	EACH
89	805-78370 PEDESTRIAN PUSH BUTTON	4.000	EACH
90	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
91	805-78420 DISCONNECT HANGER	4.000	EACH
92	805-78445 SIGNAL SERVICE	1.000	EACH
93	805-78467 SIGNAL CABLE, 3C 8GA.	100.000	LFT
94	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,380.000	LFT
95	805-78480 SIGNAL CABLE, 3C 14GA.	640.000	LFT
96	805-78485 SIGNAL CABLE, 5C 14GA.	995.000	LFT
97	805-78490 SIGNAL CABLE, 7C 14GA.	520.000	LFT
98	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,445.000	LFT

CALL ORDER : 301

CONTRACT ID : R -29755-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
99	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
100	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	450.000	LFT
101	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
102	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	2.000	EACH
103	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	12.000	EACH
104	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	389.000	LFT
105	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	408.000	LFT
106	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	1,010.000	LFT
107	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	22.000	SYS
108	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	240.000	LFT
109	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	269.000	LFT
110	808-06716 LINE, REMOVE	3,062.000	LFT
111	808-06848 LINE, EPOXY, DOTTED, WHITE, 4 IN, 24 IN LINE, 48 IN GAP	40.000	LFT
112	808-06849 LINE, EPOXY, DOTTED, YELLOW, 4 IN, 24 IN LINE, 48 IN GAP	40.000	LFT
113	808-07310 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW,	181.000	LFT
114	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	124.000	LFT
115	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	9.000	EACH
116	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	4.000	EACH
117	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	400.000	LFT
118	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	52.000	LFT
119	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	223.000	LFT
120	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	50.000	LFT
121	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	176.000	LFT
122	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH
123	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
124	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	524.000	LFT
125	808-94455 TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	116.000	LFT
126	808-98000 LINE, EPOXY, SOLID, YELLOW, 8 IN.	590.000	LFT

CALL ORDER : 311

CONTRACT ID : R -29789-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	2.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08523 RADIO SERVICE	48.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	111-04715 STOCKPILED MATERIAL,	23,000.000	CYS
15	111-04715 STOCKPILED MATERIAL,	2,000.000	CYS
16	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
17	202-05545 REGULATED MATERIALS, DISPOSE, C	700.000	CYS
18	202-05550 REGULATED MATERIALS, REMOVE, C	700.000	CYS
19	202-05555 REGULATED MATERIALS, TRANSPORT, C	700.000	CYS
20	203-02000 EXCAVATION, COMMON	37,735.000	CYS
21	203-02070 BORROW	5,015.000	CYS
22	204-02290 SETTLEMENT PLATE	4.000	EACH
23	204-08415 STAKES, SETTLEMENT	4.000	EACH
24	205-06930 SPLASHPAD, RIPRAP	29.000	TON
25	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	171.000	TON
26	205-06933 TEMPORARY DITCH INLET PROTECTION	10.000	EACH
27	205-06937 TEMPORARY SILT FENCE	6,098.000	LFT
28	205-06938 TEMPORARY SLOPE DRAIN	411.000	LFT
29	207-08262 SUBGRADE TREATMENT, TYPE I	31,994.000	SYS
30	207-08263 SUBGRADE TREATMENT, TYPE IA	10,715.000	SYS
31	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,302.000	SYS
32	211-02050 B BORROW	404.000	CYS
33	211-09264 STRUCTURE BACKFILL, TYPE 1	4,251.000	CYS
34	211-09265 STRUCTURE BACKFILL, TYPE 2	1,665.000	CYS
35	214-07202 GEOGRID, I	404.000	SYS
36	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,968.000	TON
37	303-02051 STONE, NO 2	100.000	TON
38	303-07449 COMPACTED AGGREGATE, NO. 73	45.000	TON
39	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	692.000	TON
40	304-07493 WIDENING WITH HMA, TYPE B	28.000	TON
41	306-08043 MILLING, TRANSITION	347.000	SYS
42	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,556.000	TON
43	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4,212.000	TON
44	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	12,370.000	TON
45	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	5,559.000	TON
46	402-07453 HMA FOR TEMPORARY PAVEMENT	1,552.000	TON
47	406-05520 ASPHALT FOR TACK COAT	40.000	TON
48	601-01626 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2	3.000	EACH
49	601-01701 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 2	2.000	EACH

CALL ORDER : 311

CONTRACT ID : R -29789-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
51	601-06037 GUARDRAIL END TREATMENT, I	3.000	EACH
52	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	575.000	LFT
53	604-07901 CURB RAMP, CONCRETE, G	101.000	SYS
54	605-06120 CURB, CONCRETE	247.000	LFT
55	605-06145 CURB AND GUTTER, B, CONCRETE	325.000	LFT
56	605-06150 CURB AND GUTTER, C, CONCRETE	13,968.000	LFT
57	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	9,058.000	LFT
58	605-06250 CENTER CURB, C, CONCRETE	40.000	SYS
59	610-07486 HMA FOR APPROACHES, TYPE A	1,612.000	TON
60	610-07487 HMA FOR APPROACHES, TYPE B	1,755.000	TON
61	610-09108 PCCP FOR APPROACHES, 9 IN.	1,843.000	SYS
62	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
63	611-06498 MAILBOX ASSEMBLY, DOUBLE	14.000	EACH
64	615-06490 RIGHT OF WAY MARKER	68.000	EACH
65	615-06505 MONUMENT, B	11.000	EACH
66	615-06510 MONUMENT, C	6.000	EACH
67	615-06515 MONUMENT, D	1.000	EACH
68	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
69	616-02320 GEOTEXTILES	732.000	SYS
70	616-05688 RIPRAP, CLASS 1	25.000	TON
71	616-05689 RIPRAP, CLASS 2	88.000	TON
72	616-06405 RIPRAP, REVETMENT	362.000	TON
73	616-06451 RIPRAP, UNIFORM	28.000	TON
74	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
75	621-02770 EROSION CONTROL BLANKET	3,957.000	SYS
76	621-06545 FERTILIZER	4.000	TON
77	621-06554 SEED MIXTURE, U	1,201.000	LBS
78	621-06557 SEED MIXTURE, T	328.000	LBS
79	621-06565 MULCHING MATERIAL	25.000	TON
80	621-06567 WATER	43.000	KGAL
81	621-06574 SODDING	1,319.000	SYS
82	621-06575 SODDING, NURSERY	10,438.000	SYS
83	622-03761 SEED MIXTURE NO. 1	32.000	LBS
84	622-91786 SEEDLING	468.000	EACH
85	628-09402 FIELD OFFICE, B	24.000	MOS
86	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
87	714-06278 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 9 FT. X 4 FT.	160.000	LFT
88	714-06319 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 14 FT. X 5 FT.	102.000	LFT
89	714-06688 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 5 FT. X 2 FT.	116.000	LFT
90	714-08514 WINGWALL	706.000	SFT
91	714-26702 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 6 FT. X 3 FT.	172.000	LFT
92	714-26725 CULVERT, PRECAST BOX, REINFORCED CONCRET, 6 FT. X 3 FT.	158.000	LFT
93	715-01907 WATER SERVICE CONNECTION, RELOCATE	4.000	EACH
94	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN.	3.000	EACH
95	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN.	1.000	EACH
96	715-04798 SAFETY METAL END SECTION, 4:1, 21 IN.	1.000	EACH
97	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	22,984.000	LFT
98	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	419.000	LFT

CALL ORDER : 311

CONTRACT ID : R -29789-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
99	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	1,701.000	LFT
100	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	3,019.000	LFT
101	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	1,024.000	LFT
102	715-05153 PIPE, TYPE 2, CIRCULAR, 21 IN.	872.000	LFT
103	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	806.000	LFT
104	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN.	65.000	LFT
105	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	35.000	LFT
106	715-08283 PCCP FOR STRUCTURE INSTALLATION	133.000	SYS
107	715-08316 PIPE EXTENSION, CIRCULAR, 27 IN.	96.000	LFT
108	715-46000 PIPE END SECTION, 12 IN.	8.000	EACH
109	715-46005 PIPE END SECTION, 15 IN.	9.000	EACH
110	715-46010 PIPE END SECTION, 18 IN.	1.000	EACH
111	715-46015 PIPE END SECTION, 21 IN.	1.000	EACH
112	715-46020 PIPE END SECTION, 24 IN.	4.000	EACH
113	715-46025 PIPE END SECTION, 27 IN.	1.000	EACH
114	715-46030 PIPE END SECTION, 30 IN.	1.000	EACH
115	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,000.000	LFT
116	718-52610 AGGREGATE FOR UNDERDRAINS	2,070.000	CYS
117	718-99153 GEOTEXTILES FOR UNDERDRAIN	22,984.000	SYS
118	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
119	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
120	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
121	720-44296 CAP INLET	3.000	EACH
122	720-45045 INLET, J10	1.000	EACH
123	720-45235 CATCH BASIN, E7	1.000	EACH
124	720-45270 PIPE CATCH BASIN, 18 IN.	8.000	EACH
125	720-45275 PIPE CATCH BASIN, 24 IN.	1.000	EACH
126	720-45410 MANHOLE, C4	31.000	EACH
127	720-45415 MANHOLE, D4	4.000	EACH
128	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	25.000	LFT
129	720-91352 CATCH BASIN, F7	1.000	EACH
130	720-98174 INLET, B15	20.000	EACH
131	720-98555 INLET, C15	4.000	EACH
132	720-99416 CATCH BASIN, B15	12.000	EACH
133	720-99417 CATCH BASIN, C15	24.000	EACH
134	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
135	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
136	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	16,755.000	LFT
137	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,180.000	LFT
138	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
139	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
140	801-06710 FLASHING ARROW SIGN	240.000	DAY
141	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
142	801-07118 BARRICADE, III-A	348.000	LFT
143	801-07119 BARRICADE, III-B	36.000	LFT
144	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	279.000	LFT
145	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	132.000	SFT
146	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	47.000	SFT
147	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,883.000	LFT

CALL ORDER : 311

CONTRACT ID : R -29789-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
148 808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	386.000	LFT
149 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	802.000	LFT
150 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,910.000	LFT
151 808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	93.000	LFT
152 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	288.000	LFT
153 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	20.000	EACH
154 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	17.000	EACH
155 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	91.000	EACH

CALL ORDER : 331

CONTRACT ID : R -30056-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	203-02000 EXCAVATION, COMMON	100.000	CYS
8	205-06937 TEMPORARY SILT FENCE	350.000	LFT
9	303-01180 COMPACTED AGGREGATE, NO. 53	200.000	TON
10	402-07432 HMA SURFACE, TYPE A	149.000	TON
11	402-07435 HMA INTERMEDIATE, TYPE A	248.000	TON
12	406-05520 ASPHALT FOR TACK COAT	1.000	TON
13	628-09401 FIELD OFFICE, A	3.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	800.000	LFT
18	808-97222 PAVEMENT MESSAGE MARKINGS, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 341

CONTRACT ID : R -30152-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	50.000	LFT
13	202-04089 SIGN, SHEET, REMOVE	3.000	EACH
14	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
15	203-02000 EXCAVATION, COMMON	1,300.000	CYS
16	205-03371 SEDIMENT, REMOVE	25.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	27.000	TON
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	40.000	LFT
19	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
20	205-06937 TEMPORARY SILT FENCE	550.000	LFT
21	207-08268 SUBGRADE TREATMENT, TYPE IV	2,500.000	SYS
22	211-09265 STRUCTURE BACKFILL, TYPE 2	3.200	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	460.000	TON
24	303-07449 COMPACTED AGGREGATE, NO. 73	360.000	TON
25	402-07433 HMA SURFACE, TYPE B	185.000	TON
26	402-07438 HMA INTERMEDIATE, TYPE B	260.000	TON
27	402-07441 HMA BASE, TYPE B	1,265.000	TON
28	406-05520 ASPHALT FOR TACK COAT	1.700	TON
29	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	350.000	LFT
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
32	621-06557 SEED MIXTURE, T	70.000	LBS
33	621-06559 MULCHED SEEDING, R	900.000	SYS
34	621-06559 MULCHED SEEDING, R	1,200.000	SYS
35	621-06565 MULCHING MATERIAL	0.500	TON
36	621-06574 SODDING	4.000	SYS
37	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
38	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
39	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	40.000	LFT
40	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	8.000	LFT
41	718-06526 HMA FOR UNDERDRAINS	140.000	TON
42	718-06529 OUTLET PROTECTOR, 2	1.000	EACH
43	720-45030 INLET, E7	1.000	EACH
44	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
45	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
46	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,000.000	LFT
47	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
48	801-06710 FLASHING ARROW SIGN	250.000	DAY
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP



CALL ORDER : 341

CONTRACT ID : R -30152-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	802-04893 REFERENCE POST	1.000	EACH
51	802-05704 SIGN POST, SQUARE, 1, UNREINFORCED ANCHOR BASE	15.000	LFT
52	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	30.000	LFT
53	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	1.000	EACH
54	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	4.000	EACH
55	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	55.000	SFT
56	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	85.000	SFT
57	804-06771 DELINEATOR POST, FLEXIBLE	16.000	EACH
58	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
59	805-01842 HANDHOLE, SIGNAL	12.000	EACH
60	805-04736 SIGNAL CABLE, 4C 18GA.	2,900.000	LFT
61	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	2,000.000	LFT
62	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
63	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
64	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
65	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
66	805-78420 DISCONNECT HANGER	4.000	EACH
67	805-78445 SIGNAL SERVICE	1.000	EACH
68	805-78467 SIGNAL CABLE, 3C 8GA.	65.000	LFT
69	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,600.000	LFT
70	805-78485 SIGNAL CABLE, 5C 14GA.	650.000	LFT
71	805-78490 SIGNAL CABLE, 7C 14GA.	680.000	LFT
72	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,050.000	LFT
73	805-78785 SIGNAL DETECTOR HOUSING	7.000	EACH
74	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	900.000	LFT
75	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
76	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
77	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
78	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
79	805-92512 MICROLOOP DETECTOR	10.000	EACH
80	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	270.000	LFT
81	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,500.000	LFT
82	808-06716 LINE, REMOVE	560.000	LFT
83	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	650.000	LFT
84	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	200.000	LFT
85	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	10.000	EACH
86	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	10.000	EACH
87	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	21.000	EACH
88	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	50.000	EACH

CALL ORDER : 351

CONTRACT ID : R -30159-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
9	202-02279 CURB AND GUTTER, REMOVE	1,470.000	LFT
10	203-02000 EXCAVATION, COMMON	460.000	CYS
11	205-06932 TEMPORARY CHECK DAM, STRAW BALES	20.000	LFT
12	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
13	205-06937 TEMPORARY SILT FENCE	3,230.000	LFT
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,518.000	SYS
15	211-09264 STRUCTURE BACKFILL, TYPE 1	51.000	CYS
16	303-01180 COMPACTED AGGREGATE, NO. 53	290.530	TON
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	8,135.000	SYS
18	402-07433 HMA SURFACE, TYPE B	460.000	TON
19	402-07438 HMA INTERMEDIATE, TYPE B	155.000	TON
20	402-07441 HMA BASE, TYPE B	520.000	TON
21	604-07901 CURB RAMP, CONCRETE, G	15.000	SYS
22	605-06140 CURB AND GUTTER, CONCRETE	1,040.000	LFT
23	605-06255 CENTER CURB, D, CONCRETE	83.000	SYS
24	605-94811 CURB TURNOUT	2.000	EACH
25	610-09108 PCCP FOR APPROACHES, 9 IN.	859.000	SYS
26	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
27	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
28	621-06560 MULCHED SEEDING, U	880.000	SYS
29	628-09401 FIELD OFFICE, A	3.000	MOS
30	702-90915 CONCRETE, A	5.000	CYS
31	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	15.000	LFT
32	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	205.000	LFT
33	715-46005 PIPE END SECTION, 15 IN.	1.000	EACH
34	720-44000 CASTING, ADJUST TO GRADE	7.000	EACH
35	720-44296 CAP INLET	1.000	EACH
36	720-45035 INLET, F7	1.000	EACH
37	720-45250 CATCH BASIN, K10	3.000	EACH
38	720-45410 MANHOLE, C4	1.000	EACH
39	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	1.000	LFT
40	720-96995 CLEAN INLET	1.000	EACH
41	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
42	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,575.000	LFT
43	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
44	801-06710 FLASHING ARROW SIGN	120.000	DAY
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
47	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
48	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	65.000	SFT
49	805-01816 SIGNAL SUPPORT FOUNDATION, 3 FT. X 3 FT. X 8FT.	1.000	EACH

CALL ORDER : 351

CONTRACT ID : R -30159-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
50	805-01842 HANDHOLE, SIGNAL	3.000	EACH
51	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	75.000	LFT
52	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
53	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	2.000	EACH
54	805-08487 TRAFFIC SIGNAL BACKPLATE	10.000	EACH
55	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	4.000	EACH
56	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
57	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	4.000	EACH
58	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
59	805-78420 DISCONNECT HANGER	4.000	EACH
60	805-78485 SIGNAL CABLE, 5C 14GA.	425.000	LFT
61	805-78490 SIGNAL CABLE, 7C 14GA.	270.000	LFT
62	805-78500 SIGNAL CABLE, 11C 14GA.	510.000	LFT
63	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,810.000	LFT
64	805-78746 PREFORMED LOOP DETECTORS	3,220.000	LFT
65	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,180.000	LFT
66	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	1.000	EACH
67	805-96121 PEDESTRIAN PUSH BUTTON AND SIGN	2.000	EACH
68	807-02783 LUMINAIRE MAST ARM, 15 FT.	1.000	EACH
69	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	470.000	LFT
70	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,755.000	LFT
71	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	100.000	LFT
72	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,250.000	LFT
73	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	210.000	LFT
74	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	150.000	LFT
75	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	11.000	EACH
76	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	9.000	EACH
77	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	70.000	EACH

CALL ORDER : 356

CONTRACT ID : R -30191-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	2,150.000	CYS
13	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
14	205-06936 TEMPORARY SEDIMENT TRAP	1.000	TON
15	205-06937 TEMPORARY SILT FENCE	750.000	LFT
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	713.000	SYS
17	207-08268 SUBGRADE TREATMENT, TYPE IV	5,148.000	SYS
18	211-09264 STRUCTURE BACKFILL, TYPE 1	393.000	CYS
19	303-02051 STONE, NO 2	178.000	TON
20	303-07449 COMPACTED AGGREGATE, NO. 73	14.000	TON
21	304-07492 WIDENING WITH HMA, TYPE A	18.000	TON
22	304-07493 WIDENING WITH HMA, TYPE B	15.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN.	243.000	SYS
24	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
25	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	1,253.000	TON
26	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG19.0 mm	622.000	TON
27	402-07432 HMA SURFACE, TYPE A	100.000	TON
28	402-07433 HMA SURFACE, TYPE B	272.000	TON
29	402-07435 HMA INTERMEDIATE, TYPE A	145.000	TON
30	402-07438 HMA INTERMEDIATE, TYPE B	433.000	TON
31	402-07440 HMA BASE, TYPE A	507.000	TON
32	406-05520 ASPHALT FOR TACK COAT	25.000	TON
33	604-91531 SIDEWALK, CONCRETE, 4 IN.	12.000	SYS
34	605-06140 CURB AND GUTTER, CONCRETE	1,556.000	LFT
35	610-07487 HMA FOR APPROACHES, TYPE B	6.000	TON
36	610-08446 PCCP FOR APPROACHES, 6 IN.	519.000	SYS
37	610-09108 PCCP FOR APPROACHES, 9 IN.	112.000	SYS
38	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH
39	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
40	615-06505 MONUMENT, B	4.000	EACH
41	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
42	616-02320 GEOTEXTILES	336.000	SYS
43	616-06405 RIPRAP, REVETMENT	34.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	700.000	SYS
46	621-06567 WATER	2.520	KGAL
47	621-06574 SODDING	2,073.000	SYS
48	628-09402 FIELD OFFICE, B	5.000	MOS
49	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS

CALL ORDER : 356

CONTRACT ID : R -30191-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNALS MODERNIZATION		
50	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	1,416.000	LFT
51	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN.	20.000	LFT
52	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	554.000	LFT
53	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	590.000	LFT
54	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	138.000	LFT
55	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	47.000	LFT
56	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	40.000	LFT
57	715-06690 PIPE, RCP, III, D0.01=1500, 12 IN.	159.000	LFT
58	715-41045 PIPE, REINFORCED CONCRETE, 12 IN.	56.000	LFT
59	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
60	715-46020 PIPE END SECTION, 24 IN.	1.000	EACH
61	718-52610 AGGREGATE FOR UNDERDRAINS	126.000	CYS
62	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,657.000	SYS
63	720-45030 INLET, E7	1.000	EACH
64	720-45035 INLET, F7	2.000	EACH
65	720-45410 MANHOLE, C4	3.000	EACH
66	720-90349 MANHOLE, C8	1.000	EACH
67	720-98174 INLET, B15	3.000	EACH
68	720-98555 INLET, C15	12.000	EACH
69	801-04308 ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
70	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,015.000	LFT
71	801-06625 DETOUR ROUTE MARKER ASSEMBLY	7.000	EACH
72	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
73	801-06645 CONSTRUCTION SIGN, B	17.000	EACH
74	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
75	801-07119 BARRICADE, III-B	252.000	LFT
76	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	19.000	LFT
77	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	35.000	SFT
78	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	18.000	SFT
79	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
80	805-01842 HANDHOLE, SIGNAL	5.000	EACH
81	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	322.000	LFT
82	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
83	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	6.000	EACH
84	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	2.000	EACH
85	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
86	805-78420 DISCONNECT HANGER	4.000	EACH
87	805-78445 SIGNAL SERVICE	1.000	EACH
88	805-78467 SIGNAL CABLE, 3C 8GA.	34.000	LFT
89	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,356.000	LFT
90	805-78485 SIGNAL CABLE, 5C 14GA.	157.000	LFT
91	805-78490 SIGNAL CABLE, 7C 14GA.	703.000	LFT
92	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	468.000	LFT
93	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
94	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	476.000	LFT
95	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
96	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
97	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	300.000	LFT
98	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3,576.000	LFT

CALL ORDER : 356

CONTRACT ID : R -30191-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
99 808-75278	TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	403.000	LFT
100 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	102.000	LFT
101 808-75320	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	2.000	EACH
102 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 371

CONTRACT ID : R -30578-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	5,681.000	CYS
10	203-02070 BORROW	2,154.000	CYS
11	205-02770 EROSION CONTROL BLANKET	495.000	SYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	85.000	TON
13	205-06933 TEMPORARY DITCH INLET PROTECTION	10.000	EACH
14	205-06937 TEMPORARY SILT FENCE	3,112.000	LFT
15	207-08265 SUBGRADE TREATMENT, TYPE IIA	10,772.000	SYS
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,217.000	SYS
17	211-02050 B BORROW	50.000	CYS
18	211-09264 STRUCTURE BACKFILL, TYPE 1	260.500	CYS
19	211-09265 STRUCTURE BACKFILL, TYPE 2	199.300	CYS
20	303-07449 COMPACTED AGGREGATE, NO. 73	108.000	TON
21	306-08043 MILLING, TRANSITION	140.000	SYS
22	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,382.000	TON
23	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	2,259.000	TON
24	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	3,297.000	TON
25	402-07451 HMA WEDGE AND LEVEL, TYPE B	1,906.000	TON
26	406-05520 ASPHALT FOR TACK COAT	11.500	TON
27	601-01621 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED	1.000	EACH
28	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
30	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	256.250	LFT
31	603-03692 FENCE, WOOD	250.000	LFT
32	603-06040 FENCE, FARM FIELD, 47 IN.	616.000	LFT
33	605-06120 CURB, CONCRETE	436.000	LFT
34	610-07487 HMA FOR APPROACHES, TYPE B	1,059.000	TON
35	610-08446 PCCP FOR APPROACHES, 6 IN.	12.000	SYS
36	611-06497 MAILBOX ASSEMBLY, SINGLE	13.000	EACH
37	611-06498 MAILBOX ASSEMBLY, DOUBLE	8.000	EACH
38	615-06505 MONUMENT, B	5.000	EACH
39	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
40	616-02320 GEOTEXTILES	554.000	SYS
41	616-05688 RIPRAP, CLASS 1	25.000	TON
42	616-05689 RIPRAP, CLASS 2	20.000	TON
43	616-06405 RIPRAP, REVETMENT	240.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
45	621-06545 FERTILIZER	0.100	TON
46	621-06557 SEED MIXTURE, T	50.000	LBS
47	621-06559 MULCHED SEEDING, R	3,938.000	SYS
48	621-06565 MULCHING MATERIAL	1.250	TON
49	621-06567 WATER	37.000	KGAL

CALL ORDER : 371

CONTRACT ID : R -30578-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
50	621-06574 SODDING	10,236.000	SYS
51	628-09401 FIELD OFFICE, A	15.000	MOS
52	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	50.000	LFT
53	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	50.000	LFT
54	715-05052 PIPE, TYPE 4, CIRCULAR, 12 IN.	50.000	LFT
55	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN.	130.000	LFT
56	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN.	77.000	LFT
57	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN.	234.000	LFT
58	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	60.000	LFT
59	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	514.500	LFT
60	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	564.000	LFT
61	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
62	715-46005 PIPE END SECTION, 15 IN.	29.000	EACH
63	715-46010 PIPE END SECTION, 18 IN.	2.000	EACH
64	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
65	715-92537 PIPE, PVC, 8 IN.	75.000	LFT
66	720-45030 INLET, E7	2.000	EACH
67	720-45035 INLET, F7	4.000	EACH
68	720-45270 PIPE CATCH BASIN, 18 IN.	1.000	EACH
69	720-97316 MANHOLE, TYPE C WITH BEEHIVE CASTING	2.000	EACH
70	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
71	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
72	801-06625 DETOUR ROUTE MARKER ASSEMBLY	13.000	EACH
73	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
74	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07119 BARRICADE, III-B	48.000	LFT
77	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	92.000	LFT
78	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	23.000	LFT
79	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	27.500	SFT
80	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	28.880	SFT
81	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	9,989.000	LFT
82	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,127.000	LFT
83	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	823.000	LFT
84	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	97.000	LFT



CALL ORDER : 381

CONTRACT ID : R -30584-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02279 CURB AND GUTTER, REMOVE	972.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	700.000	SYS
11	202-93047 MANHOLE, REMOVE	8.000	EACH
12	202-96133 PIPE, REMOVE	814.000	LFT
13	203-02000 EXCAVATION, COMMON	2,797.000	CYS
14	205-03371 SEDIMENT, REMOVE	5.000	CYS
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	60.000	LFT
16	207-08266 SUBGRADE TREATMENT, TYPE III	165.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	412.000	SYS
18	207-08268 SUBGRADE TREATMENT, TYPE IV	5,230.000	SYS
19	211-09264 STRUCTURE BACKFILL, TYPE 1	139.000	CYS
20	306-08043 MILLING, TRANSITION	276.000	SYS
21	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,885.000	TON
22	402-07433 HMA SURFACE, TYPE B	347.000	TON
23	402-07438 HMA INTERMEDIATE, TYPE B	556.000	TON
24	402-07453 HMA FOR TEMPORARY PAVEMENT	82.000	TON
25	406-05520 ASPHALT FOR TACK COAT	1.900	TON
26	604-07896 CURB RAMP, CONCRETE, B	6.000	SYS
27	604-07901 CURB RAMP, CONCRETE, G	43.000	SYS
28	604-07902 CURB RAMP, CONCRETE, H	16.400	SYS
29	604-91531 SIDEWALK, CONCRETE, 4 IN.	618.000	SYS
30	605-06140 CURB AND GUTTER, CONCRETE	972.000	LFT
31	605-06145 CURB AND GUTTER, B, CONCRETE	1,156.000	LFT
32	610-07486 HMA FOR APPROACHES, TYPE A	7.000	TON
33	610-08446 PCCP FOR APPROACHES, 6 IN.	318.000	SYS
34	610-09108 PCCP FOR APPROACHES, 9 IN.	94.000	SYS
35	615-06505 MONUMENT, B	2.000	EACH
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
37	621-06567 WATER	10.000	KGAL
38	621-06575 SODDING, NURSERY	3,150.000	SYS
39	628-09401 FIELD OFFICE, A	10.000	MOS
40	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	501.000	LFT
41	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN.	193.000	LFT
42	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN.	1,108.000	LFT
43	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	25.000	TON
44	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
45	720-45025 INLET, D6	13.000	EACH
46	720-45410 MANHOLE, C4	6.000	EACH
47	720-98174 INLET, B15	1.000	EACH
48	720-98555 INLET, C15	8.000	EACH
49	720-98625 MANHOLE, C4, DROP	4.000	EACH

CALL ORDER : 381

CONTRACT ID : R -30584-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
51	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
52	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,480.000	LFT
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	740.000	LFT
54	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.000	LFT
55	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
56	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
57	801-06645 CONSTRUCTION SIGN, B	11.000	EACH
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	80.000	LFT
60	801-07119 BARRICADE, III-B	80.000	LFT
61	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	50.500	LFT
62	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	28.750	SFT
63	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	60.000	LFT
64	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,034.000	LFT
65	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	72.000	LFT
66	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	270.000	LFT
67	808-95933 CURB PAINTING, YELLOW	85.000	LFT

CALL ORDER : 391

CONTRACT ID : R -30596-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, ENHANCEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	114.000	SYS
9	203-02000 EXCAVATION, COMMON	715.000	CYS
10	203-02020 EXCAVATION, UNCLASSIFIED	490.000	CYS
11	203-02070 BORROW	5,016.000	CYS
12	205-02237 TEMPORARY EROSION AND SEDIMENT CONTROL, CURB INLET	16.000	EACH
13	205-06937 TEMPORARY SILT FENCE	2,520.000	LFT
14	206-51220 EXCAVATION, WET	432.000	CYS
15	206-51817 SHEET PILING, STEEL	7,380.000	SFT
16	207-08268 SUBGRADE TREATMENT, TYPE IV	1,649.000	SYS
17	210-05066 FOUNTAIN	1.000	EACH
18	210-07766 COLUMN	33.000	EACH
19	211-09264 STRUCTURE BACKFILL, TYPE 1	949.000	CYS
20	303-01180 COMPACTED AGGREGATE, NO. 53	492.000	TON
21	304-07490 HMA PATCHING, TYPE B	25.000	TON
22	306-08042 MILLING, SCARIFICATION/PROFILE	1,654.000	SYS
23	306-08043 MILLING, TRANSITION	432.000	SYS
24	402-07432 HMA SURFACE, TYPE A	50.000	TON
25	402-07433 HMA SURFACE, TYPE B	331.000	TON
26	402-07435 HMA INTERMEDIATE, TYPE A	81.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	234.000	TON
28	402-07441 HMA BASE, TYPE B	280.000	TON
29	406-05521 ASPHALT FOR TACK COAT	3,883.000	SYS
30	603-04244 GATE	1.000	EACH
31	604-06070 SIDEWALK, CONCRETE	68.000	SYS
32	604-06844 BRICK	14,850.000	SFT
33	604-07897 CURB RAMP, CONCRETE, C	38.000	SYS
34	604-07901 CURB RAMP, CONCRETE, G	77.000	SYS
35	605-06120 CURB, CONCRETE	131.000	LFT
36	605-06125 CURB, CONCRETE, MODIFIED	3,966.000	LFT
37	611-03671 TRASH RECEPTACLE	11.000	EACH
38	615-06496 PARKING BARRIER	22.000	EACH
39	616-02320 GEOTEXTILES	909.000	SYS
40	616-05688 RIPRAP, CLASS 1	648.000	TON
41	616-06405 RIPRAP, REVETMENT	187.000	TON
42	616-94426 GEOGRID	1,400.000	SYS
43	621-02363 MULCHED SEEDING, T, CONVENTIONAL MIX	9,410.000	SYS
44	621-02770 EROSION CONTROL BLANKET	695.000	SYS
45	621-06560 MULCHED SEEDING, U	9,410.000	SYS
46	621-98038 MULCH, HARDWOOD SHREDDED BARK	40.000	CYS
47	622-05639 PLANT, DECIDUOUS SHRUB, OVER 18 TO 24 IN.	12.000	EACH
48	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 1.25 TO 2 IN.	14.000	EACH
49	622-05653 PLANT, GROUND COVER	2.000	EACH

CALL ORDER : 391

CONTRACT ID : R -30596-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, ENHANCEMENT		
50	622-05654 PLANT, PERENNIAL	32.000	EACH
51	622-05656 PLANT, ROSE GRADE	12.000	EACH
52	622-99101 PLANT, DAY LILIES	32.000	EACH
53	628-09402 FIELD OFFICE, B	12.000	MOS
54	702-90915 CONCRETE, A	172.000	CYS
55	703-51030 REINFORCING STEEL	20,073.000	LBS
56	706-04683 RAILING	594.000	LFT
57	706-91664 PIPE RAILING	180.000	LFT
58	712-03812 BENCH	27.000	EACH
59	714-04802 CONCRETE MODULAR BLOCK WALL	147.000	SYS
60	715-01902 WATER SERVICE LINE, 2 IN.	960.000	LFT
61	715-01902 WATER SERVICE LINE, 2 IN.	100.000	LFT
62	715-05147 PIPE, TYPE 2, CIRCULAR, 8 IN.	86.000	LFT
63	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	421.000	LFT
64	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN.	269.000	LFT
65	715-05203 PIPE, TYPE 4, CIRCULAR, 4 IN.	400.000	LFT
66	715-46000 PIPE END SECTION, 12 IN.	3.000	EACH
67	715-46005 PIPE END SECTION, 15 IN.	7.000	EACH
68	720-02485 TRENCH DRAIN	18.000	EACH
69	720-45015 INLET, A8	2.000	EACH
70	720-45045 INLET, J10	3.000	EACH
71	720-45055 INLET, M10	5.000	EACH
72	720-45105 INLET, A2, MODIFIED	3.000	EACH
73	720-45410 MANHOLE, C4	1.000	EACH
74	720-98174 INLET, B15	3.000	EACH
75	732-03942 HYDRANT	5.000	EACH
76	732-91742 FIRE HYDRANT	1.000	EACH
77	732-94780 WATER SERVICE CONNECTION	4.000	EACH
78	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
79	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
80	805-96014 SAW CUT, FULL DEPTH	1,985.000	LFT
81	807-01603 SERVICE POINT, TYPE II	3.000	EACH
82	807-02819 LIGHTING RECEPTACLE, SINGLE, WATERPROOF	20.000	EACH
83	807-03738 LIGHT POLE ASSEMBLY, STREET	35.000	EACH
84	807-03738 LIGHT POLE ASSEMBLY, STREET	18.000	EACH
85	807-03965 CONDUIT, PVC, 2.50 IN., SCHEDULE 80, FOR ELECTRIC	2,405.000	LFT
86	807-03968 CONDUIT, PVC, 1 IN., SCHEDULE 80, FOR ELECTRIC	735.000	LFT
87	807-04651 WIRE	3,290.000	LFT
88	807-04651 WIRE	1,545.000	LFT
89	807-04651 WIRE	75.000	LFT
90	807-04651 WIRE	4,810.000	LFT
91	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	546.000	LFT

CALL ORDER : 401

CONTRACT ID : R -30921-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CURB AND SIDEWALK RECONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-02278 CURB, CONCRETE, REMOVE	6,681.000	LFT
8	202-52710 SIDEWALK, CONCRETE, REMOVE	1,672.000	SYS
9	203-02070 BORROW	30.000	CYS
10	304-07490 HMA PATCHING, TYPE B	1,000.000	TON
11	604-06070 SIDEWALK, CONCRETE	1,672.000	SYS
12	605-06120 CURB, CONCRETE	6,681.000	LFT
13	611-05330 CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS, 6 IN.	1,932.000	SYS
14	611-06497 MAILBOX ASSEMBLY, SINGLE	41.000	EACH
15	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
16	621-06574 SODDING	2,000.000	SYS
17	628-09402 FIELD OFFICE, B	5.000	MOS
18	720-44000 CASTING, ADJUST TO GRADE	19.000	EACH
19	720-45215 CATCH BASIN, A8	3.000	EACH
20	720-45610 STRUCTURE, CATCH BASIN, RECONSTRUCT	75.000	LFT
21	720-99315 CLEAN EXISTING CATCH BASINS	15.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
23	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 441

CONTRACT ID : RS-29500-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02241 GUARDRAIL, REMOVE	36.000	LFT
12	203-08607 LINEAR GRADING	150.000	LFT
13	303-07449 COMPACTED AGGREGATE, NO. 73	3,098.000	TON
14	304-07490 HMA PATCHING, TYPE B	352.000	TON
15	306-08034 MILLING, ASPHALT, 1 1/2 IN.	93,898.000	SYS
16	306-08043 MILLING, TRANSITION	210.000	SYS
17	306-08432 MILLING, APPROACH	5,443.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07339 QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	10,329.000	TON
20	406-05520 ASPHALT FOR TACK COAT	23.000	TON
21	506-06333 PCCP PATCHING, FULL DEPTH	2,130.000	SYS
22	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT. 3 IN. SPACING	16.000	LFT
23	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
24	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	1.000	EACH
25	610-07488 HMA FOR APPROACHES, TYPE C	449.000	TON
26	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
27	621-06559 MULCHED SEEDING, R	300.000	SYS
28	628-09402 FIELD OFFICE, B	6.000	MOS
29	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
30	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,683.000	LFT
31	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,683.000	LFT
32	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	35.000	LFT
35	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	53,766.000	LFT
36	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6,620.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,785.000	LFT
38	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	439.000	EACH
39	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	439.000	EACH

CALL ORDER : 451

CONTRACT ID : RS-30289-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	40.000	SYS
10	202-02278 CURB, CONCRETE, REMOVE	341.000	LFT
11	202-52710 SIDEWALK, CONCRETE, REMOVE	253.000	SYS
12	303-01180 COMPACTED AGGREGATE, NO. 53	200.000	TON
13	304-07783 HMA PATCHING, TYPE D	703.000	TON
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	50,360.000	SYS
15	306-08043 MILLING, TRANSITION	200.000	SYS
16	306-08432 MILLING, APPROACH	6,347.000	SYS
17	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	4,155.000	TON
18	406-05520 ASPHALT FOR TACK COAT	15.000	TON
19	604-06070 SIDEWALK, CONCRETE	253.000	SYS
20	604-06367 JOINT MATERIAL	500.000	LFT
21	604-07894 CURB RAMP, CONCRETE, A	289.000	SYS
22	604-07897 CURB RAMP, CONCRETE, C	85.000	SYS
23	604-07900 CURB RAMP, CONCRETE, F	47.000	SYS
24	604-07901 CURB RAMP, CONCRETE, G	18.000	SYS
25	604-07902 CURB RAMP, CONCRETE, H	15.000	SYS
26	605-06090 CURB, INTEGRAL, CONCRETE	93.000	LFT
27	605-06120 CURB, CONCRETE	248.000	LFT
28	610-07788 HMA FOR APPROACHES, TYPE D	524.000	TON
29	621-06574 SODDING	120.000	SYS
30	628-09402 FIELD OFFICE, B	7.000	MOS
31	720-01894 CASTING, FURNISH AND ADJUST TO GRADE	1.000	EACH
32	720-44000 CASTING, ADJUST TO GRADE	43.000	EACH
33	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
34	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,450.000	LFT
35	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,450.000	LFT
36	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	802-91122 SIGN, GROUND MOUNTED, RESET	4.000	EACH
39	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	19.000	EACH
40	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	8,625.000	LFT
41	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	863.000	LFT
42	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,760.000	LFT
43	808-02066 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID WHITE CROSSHATCH	400.000	LFT
44	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
45	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	1,360.000	LFT
46	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	27.000	LFT
47	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	105.000	LFT
48	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	16,271.000	LFT
49	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	914.000	LFT

CALL ORDER : 451

CONTRACT ID : RS-30289-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,136.000	LFT
51	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	60.000	LFT
52	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	200.000	LFT
53	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	428.000	LFT
54	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	23.000	EACH
55	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	8.000	EACH
56	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	114.000	EACH
57	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	124.000	EACH
58	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	748.000	LFT
59	808-94435 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (STOP)	1.000	EACH



CALL ORDER : 461

CONTRACT ID : RS-30925-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001    MICROSURFACING			
1	105-06845    CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359    LIQUIDATED DAMAGES	1.000	DOL
3	109-08360    CONTRACT LIENS	1.000	DOL
4	109-08443    QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444    QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001    MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	303-01180    COMPACTED AGGREGATE, NO. 53	150.000	TON
8	304-07490    HMA PATCHING, TYPE B	100.000	TON
9	406-05520    ASPHALT FOR TACK COAT	0.100	TON
10	411-08438    MICRO-SURFACING, WARRANTED	207,866.000	SYS
11	628-09402    FIELD OFFICE, B	5.000	MOS
12	628-09407    FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
13	801-03290    CONSTRUCTION SIGN, C	4.000	EACH
14	801-06207    TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,500.000	LFT
15	801-06640    CONSTRUCTION SIGN, A	48.000	EACH
16	801-06775    MAINTAINING TRAFFIC	LUMP	LUMP
17	808-02157    PAVEMENT MESSAGE MARKINGS, REMOVE	14.000	EACH
18	808-06368    TRANSVERSE MARKING, REMOVE	63.000	LFT
19	808-06712    LINE, PAINT, BROKEN, YELLOW, 4 IN.	13,187.000	LFT
20	808-06713    LINE, PAINT, SOLID, WHITE, 4 IN.	130,080.000	LFT
21	808-06714    LINE, PAINT, SOLID, YELLOW, 4 IN.	67,534.000	LFT
22	808-75278    TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	445.000	LFT
23	808-75297    TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	63.000	LFT
24	808-75320    PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	11.000	EACH
25	808-75325    PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	3.000	EACH
26	808-75996    SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,600.000	EACH
27	808-75998    SNOWPLOWABLE RAISED PAVEMENT MARKER	1,600.000	EACH
28	808-75998    SNOWPLOWABLE RAISED PAVEMENT MARKER	17.000	EACH
29	808-92027    LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,700.000	LFT

CALL ORDER : 471

CONTRACT ID : RS-30962-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PCCP PATCHING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-01180 COMPACTED AGGREGATE, NO. 53	2,988.000	TON
12	304-07489 HMA PATCHING, TYPE A	50.000	TON
13	501-03489 TIE BAR, RETROFIT	118.000	EACH
14	503-05240 D-1 CONTRACTION JOINT	300.000	LFT
15	506-06333 PCCP PATCHING, FULL DEPTH	9,053.000	SYS
16	507-07479 HMA PARTIAL DEPTH PATCH	87.890	TON
17	608-04395 AGGREGATE FOR SHOULDER DRAINS	50.000	TON
18	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	10.500	TON
19	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
20	612-60410 DRILLED HOLE FOR UNDERSEAL	174.000	EACH
21	628-09401 FIELD OFFICE, A	9.000	MOS
22	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
23	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
25	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,000.000	LFT
26	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
27	801-06710 FLASHING ARROW SIGN	200.000	DAY
28	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
29	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	420.000	LFT
30	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
31	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	180.000	LFT
32	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	2,065.000	LFT
33	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	2,705.000	LFT
34	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	3,956.000	LFT
35	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	60.000	LFT

CALL ORDER : 481

CONTRACT ID : RS-31018-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07783 HMA PATCHING, TYPE D	1,890.000	TON
12	305-07470 PCC BASE PATCHING, 14 IN.	700.000	SYS
13	306-08043 MILLING, TRANSITION	200.000	SYS
14	306-08432 MILLING, APPROACH	4,049.000	SYS
15	306-08563 MILLING ASPHALT, 1 1/4 IN.	214,020.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07363 QC/QA-HMA, 4, 70, INTERMEDIATE, 9.5 mm	17,700.000	TON
18	404-05512 SEAL COAT, 3	45,000.000	SYS
19	406-05520 ASPHALT FOR TACK COAT	55.000	TON
20	610-07788 HMA FOR APPROACHES, TYPE D	340.000	TON
21	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	200.000	TON
22	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
23	612-60410 DRILLED HOLE FOR UNDERSEAL	3,370.000	EACH
24	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
25	628-09402 FIELD OFFICE, B	6.000	MOS
26	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
27	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.000	EACH
28	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
29	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,100.000	LFT
30	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,100.000	LFT
31	801-06640 CONSTRUCTION SIGN, A	52.000	EACH
32	801-06710 FLASHING ARROW SIGN	90.000	DAY
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,070.000	LFT
35	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	690.000	LFT
36	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	14,440.000	LFT
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	68,042.000	LFT
38	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	57,736.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	345.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	8.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	6.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	980.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	980.000	EACH

CALL ORDER : 491

CONTRACT ID : RS-31019-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07783 HMA PATCHING, TYPE D	400.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	207,300.000	SYS
13	306-08432 MILLING, APPROACH	600.000	SYS
14	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
15	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	17,070.000	TON
16	406-05520 ASPHALT FOR TACK COAT	95.000	TON
17	610-07788 HMA FOR APPROACHES, TYPE D	50.000	TON
18	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	60.000	TON
19	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
20	612-60410 DRILLED HOLE FOR UNDERSEAL	950.000	EACH
21	615-06527 MONUMENT, SECTION CORNER	6.000	EACH
22	628-09402 FIELD OFFICE, B	6.000	MOS
23	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
26	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,100.000	LFT
27	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,100.000	LFT
28	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
29	801-06710 FLASHING ARROW SIGN	90.000	DAY
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
32	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	450.000	LFT
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	100.000	LFT
34	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	15,220.000	LFT
35	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	68,658.000	LFT
36	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	440.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	63,604.000	LFT
38	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	228.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	145.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	6.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	946.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	946.000	EACH

CALL ORDER : 501

CONTRACT ID : RS-31020-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-07449 COMPACTED AGGREGATE, NO. 73	1,000.000	TON
12	304-07489 HMA PATCHING, TYPE A	1,000.000	TON
13	304-07783 HMA PATCHING, TYPE D	2,500.000	TON
14	304-07783 HMA PATCHING, TYPE D	1,000.000	TON
15	306-08432 MILLING, APPROACH	3,264.000	SYS
16	306-08563 MILLING ASPHALT, 1 1/4 IN.	233,700.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	20,500.000	TON
19	406-05520 ASPHALT FOR TACK COAT	61.000	TON
20	606-07484 MILLED HMA SHOULDER CORRUGATIONS	133,216.000	LFT
21	610-07788 HMA FOR APPROACHES, TYPE D	270.000	TON
22	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	8.000	TON
23	612-05081 MOBILIZATION AND DEMOBILIZATION FOR UNDERSEAL	1.000	EACH
24	612-60410 DRILLED HOLE FOR UNDERSEAL	131.000	EACH
25	628-09402 FIELD OFFICE, B	4.000	MOS
26	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	4.000	MOS
27	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
28	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
29	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	7,000.000	LFT
30	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7,000.000	LFT
31	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
32	801-06710 FLASHING ARROW SIGN	90.000	DAY
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
35	804-06771 DELINEATOR POST, FLEXIBLE	250.000	EACH
36	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	16,040.000	LFT
37	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	75,220.000	LFT
38	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	68,640.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	60.000	LFT
40	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	967.000	EACH
41	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	967.000	EACH

CALL ORDER : 541

CONTRACT ID : B -28761-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	385.000	CYS
12	203-51223 EXCAVATION, WATERWAY	1,637.000	CYS
13	205-06937 TEMPORARY SILT FENCE	850.000	LFT
14	206-51220 EXCAVATION, WET	142.000	CYS
15	206-51235 COFFERDAM	LUMP	LUMP
16	207-08264 SUBGRADE TREATMENT, TYPE II	1,363.000	SYS
17	211-06467 AGGREGATE FOR END BENT BACKFILL	47.300	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	261.000	TON
19	302-07455 DENSE GRADED SUBBASE	37.200	CYS
20	303-07449 COMPACTED AGGREGATE, NO. 73	97.000	TON
21	402-07432 HMA SURFACE, TYPE A	99.000	TON
22	402-07435 HMA INTERMEDIATE, TYPE A	161.000	TON
23	402-07440 HMA BASE, TYPE A	260.000	TON
24	404-05514 SEAL COAT, 5	290.000	SYS
25	406-05521 ASPHALT FOR TACK COAT	2,289.000	SYS
26	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
27	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
28	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	50.000	LFT
29	602-06729 BARRIER DELINEATOR	8.000	EACH
30	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	223.200	SYS
31	615-06490 RIGHT OF WAY MARKER	17.000	EACH
32	616-02320 GEOTEXTILES	1,185.000	SYS
33	616-06405 RIPRAP, REVEIMENT	884.000	TON
34	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
35	621-06545 FERTILIZER	0.040	TON
36	621-06557 SEED MIXTURE, T	27.000	LBS
37	621-06559 MULCHED SEEDING, R	1,600.000	SYS
38	621-06565 MULCHING MATERIAL	0.700	TON
39	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
40	622-91786 SEEDLING	50.000	EACH
41	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
42	628-09402 FIELD OFFICE, B	8.000	MOS
43	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
44	701-51190 PILE, STEEL H, HP 10 X 42	635.000	LFT
45	701-51195 PILE, STEEL H, HP 12 X 53	912.000	LFT
46	701-91792 PILE TIP, STEEL H	26.000	EACH
47	702-51005 CONCRETE, A, SUBSTRUCTURE	97.600	CYS
48	702-51015 CONCRETE, B, FOOTINGS	8.800	CYS
49	703-06029 REINFORCING BARS, EPOXY COATED	81,037.000	LBS

CALL ORDER : 541

CONTRACT ID : B -28761-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	704-51002 CONCRETE, C, SUPERSTRUCTURE	202.300	CYS
51	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
52	706-51020 CONCRETE, C, RAILING	26.800	CYS
53	707-05983 STRUCTURAL MEMBERS, CONCRETE I-BEAM, II, 36 IN. X 12 IN.	670.000	LFT
54	709-51821 SURFACE SEAL	LUMP	LUMP
55	715-05407 PIPE, END BENT DRAIN, 6 IN.	120.000	LFT
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
57	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
58	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
59	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
60	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
61	801-07118 BARRICADE, III-A	48.000	LFT
62	801-07119 BARRICADE, III-B	120.000	LFT
63	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	8.000	LFT
64	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	6.250	SFT
65	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,200.000	LFT
66	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	1,200.000	LFT

CALL ORDER : 551

CONTRACT ID : B -29608-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-99187 FENCE, FARM FIELD, REMOVE	165.000	LFT
9	203-02000 EXCAVATION, COMMON	134.000	CYS
10	203-02070 BORROW	237.000	CYS
11	205-06932 TEMPORARY CHECK DAM, STRAW BALES	27.000	LFT
12	205-06937 TEMPORARY SILT FENCE	910.000	LFT
13	207-08262 SUBGRADE TREATMENT, TYPE I	550.000	SYS
14	210-05804 MISCELLANEOUS	LUMP	LUMP
15	304-07493 WIDENING WITH HMA, TYPE B	270.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	200.000	SYS
17	402-05494 HMA RUMBLE STRIPS	34.000	LFT
18	402-07433 HMA SURFACE, TYPE B	85.000	TON
19	402-07438 HMA INTERMEDIATE, TYPE B	10.000	TON
20	402-07441 HMA BASE, TYPE B	10.000	TON
21	402-07451 HMA WEDGE AND LEVEL, TYPE B	82.000	TON
22	406-05521 ASPHALT FOR TACK COAT	1,700.000	SYS
23	601-05399 GUARDRAIL	LUMP	LUMP
24	603-06040 FENCE, FARM FIELD, 47 IN.	250.000	LFT
25	615-06490 RIGHT OF WAY MARKER	12.000	EACH
26	615-06505 MONUMENT, B	10.000	EACH
27	616-02320 GEOTEXTILES	120.000	SYS
28	616-05688 RIPRAP, CLASS 1	165.000	TON
29	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
30	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
31	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
32	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
33	621-06545 FERTILIZER	1.000	TON
34	621-06553 SEED MIXTURE, R	91.000	LBS
35	621-06565 MULCHING MATERIAL	2.000	TON
36	621-06575 SODDING, NURSERY	112.000	SYS
37	628-09402 FIELD OFFICE, B	8.000	MOS
38	708-05394 REPAIR	LUMP	LUMP
39	708-05394 REPAIR	LUMP	LUMP
40	708-05394 REPAIR	LUMP	LUMP
41	708-05394 REPAIR	LUMP	LUMP
42	708-05394 REPAIR	LUMP	LUMP
43	708-05394 REPAIR	LUMP	LUMP
44	711-05396 REPLACE	LUMP	LUMP
45	711-05396 REPLACE	LUMP	LUMP
46	711-05396 REPLACE	LUMP	LUMP
47	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
48	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
49	801-06640 CONSTRUCTION SIGN, A	15.000	EACH



CALL ORDER : 551

CONTRACT ID : B -29608-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
50 801-07118	BARRICADE, III-A	48.000	LFT
51 801-07119	BARRICADE, III-B	48.000	LFT
52 802-07060	SIGN, SHEET, RELOCATE	1.000	EACH
53 802-76025	SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	20.250	SFT
54 802-76055	SIGN POST, A	25.000	LFT
55 808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	134.000	LFT
56 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	820.000	LFT
57 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	820.000	LFT
58 808-97323	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	96.000	LFT

CALL ORDER : 561

CONTRACT ID : B -29716-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	115.000	CYS
10	203-02070 BORROW	90.000	CYS
11	205-02770 EROSION CONTROL BLANKET	660.000	SYS
12	205-06937 TEMPORARY SILT FENCE	200.000	LFT
13	206-51220 EXCAVATION, WET	223.000	CYS
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	325.000	CYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	900.000	SYS
16	211-09265 STRUCTURE BACKFILL, TYPE 2	320.000	CYS
17	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	40.000	CYS
18	402-07433 HMA SURFACE, TYPE B	70.000	TON
19	402-07438 HMA INTERMEDIATE, TYPE B	118.000	TON
20	402-07441 HMA BASE, TYPE B	286.000	TON
21	406-05521 ASPHALT FOR TACK COAT	2,565.000	SYS
22	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
23	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
24	616-02320 GEOTEXTILES	118.000	SYS
25	616-05688 RIPRAP, CLASS 1	131.000	TON
26	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
27	621-06559 MULCHED SEEDING, R	830.000	SYS
28	628-09401 FIELD OFFICE, A	5.000	MOS
29	701-90386 TEMPORARY SHEET PILING	LUMP	LUMP
30	703-51032 REINFORCING STEEL, EPOXY COATED	3,082.000	LBS
31	706-51020 CONCRETE, C, RAILING	25.800	CYS
32	709-51821 SURFACE SEAL	LUMP	LUMP
33	714-08514 WINGWALL	1,087.000	SFT
34	723-06927 STRUCTURE, PRECAST THREE-SIDED,	31.000	LFT
35	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
36	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
37	801-07118 BARRICADE, III-A	48.000	LFT
38	805-02426 WIRE, THW, NO. 4 CU, IN PLASTIC DUCT, IN CONDUIT, 4 1C	30.000	LFT
39	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	30.000	LFT
40	807-02193 LIGHT STANDARD FOUNDATION, 3 FT. DIA. X 8 FT.	4.000	EACH
41	807-02603 LIGHT STANDARD, RELOCATE	4.000	EACH
42	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	201.000	LFT
43	807-08612 HANDHOLE, RECTANGULAR	2.000	EACH

CALL ORDER : 565

CONTRACT ID : B -31029-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 201-52370	CLEARING RIGHT OF WAY	LUMP	LUMP
7 628-09401	FIELD OFFICE, A	6.000	MOS
8 713-51820	TEMPORARY SUPPORT	LUMP	LUMP
9 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
10 801-06640	CONSTRUCTION SIGN, A	8.000	EACH
11 801-06710	FLASHING ARROW SIGN	2.000	DAY
12 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 571

CONTRACT ID : B -30241-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-01066 HYDRO DEMOLITION	1,588.000	SYS
12	202-02240 PAVEMENT REMOVAL	348.000	SYS
13	202-02241 GUARDRAIL, REMOVE	100.000	LFT
14	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
15	203-02000 EXCAVATION, COMMON	15.700	CYS
16	207-08268 SUBGRADE TREATMENT, TYPE IV	935.000	SYS
17	211-06467 AGGREGATE FOR END BENT BACKFILL	15.700	CYS
18	302-07455 DENSE GRADED SUBBASE	61.000	CYS
19	304-07494 WIDENING WITH HMA, TYPE C	1,093.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN.	792.000	SYS
21	406-05521 ASPHALT FOR TACK COAT	8,900.000	SYS
22	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
23	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
24	601-06035 GUARDRAIL, RESET	25.000	LFT
25	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	2.000	EACH
26	602-06729 BARRIER DELINEATOR	34.000	EACH
27	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	366.100	SYS
28	610-07488 HMA FOR APPROACHES, TYPE C	33.400	TON
29	616-02320 GEOTEXTILES	159.000	SYS
30	616-06405 RIPRAP, REVETMENT	35.000	TON
31	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
32	621-06560 MULCHED SEEDING, U	150.000	SYS
33	621-06567 WATER	0.200	KGAL
34	621-06574 SODDING	31.100	SYS
35	628-09402 FIELD OFFICE, B	6.000	MOS
36	702-51005 CONCRETE, A, SUBSTRUCTURE	3.500	CYS
37	702-51863 FIELD DRILLED HOLE IN CONCRETE	747.000	EACH
38	703-06029 REINFORCING BARS, EPOXY COATED	44,844.000	LBS
39	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	140.000	EACH
40	704-51002 CONCRETE, C, SUPERSTRUCTURE	20.200	CYS
41	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	4.000	EACH
42	706-51020 CONCRETE, C, RAILING	63.600	CYS
43	709-51821 SURFACE SEAL	LUMP	LUMP
44	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	430.000	SFT
45	722-51842 BRIDGE DECK OVERLAY	1,654.000	SYS
46	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	8.000	CYS
47	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	290.000	SFT
48	722-60824 SURFACE MILLING	1,588.000	SYS
49	724-51925 STRUCTURAL EXPANSION JOINT, SS	126.200	LFT

CALL ORDER : 571

CONTRACT ID : B -30241-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REHABILITATION			
50	728-98377 MASONRY COATING	LUMP	LUMP
51	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
53	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10,073.000	LFT
54	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
55	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
56	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
57	801-06710 FLASHING ARROW SIGN	180.000	DAY
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	75.000	LFT
60	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	620.000	LFT
61	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,320.000	LFT
62	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	161.000	LFT
63	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	322.000	LFT
64	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	322.000	LFT
65	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	914.000	LFT
66	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,828.000	LFT
67	808-06716 LINE, REMOVE	5,170.000	LFT
68	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	700.000	LFT
69	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,828.000	LFT
70	808-75994 PRISMATIC REFLECTOR	27.000	EACH
71	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	5.000	EACH
72	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	5.000	EACH

CALL ORDER : 581

CONTRACT ID : B -30536-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 109-08359	LIQUIDATED DAMAGES	1.000	DOL
5 109-08360	CONTRACT LIENS	1.000	DOL
6 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9 619-05926	ENVIRONMENTAL CONTROL	LUMP	LUMP
10 619-51859	PAINT STEEL BRIDGE	LUMP	LUMP
11 619-61000	CLEAN STEEL BRIDGE	LUMP	LUMP
12 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
13 628-09409	MOBILE INTERNET SERVICE	6.000	MOS
14 709-51821	SURFACE SEAL	LUMP	LUMP
15 801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
16 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
17 801-06640	CONSTRUCTION SIGN, A	10.000	EACH
18 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 591

CONTRACT ID : B -30537-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE PAINTING			
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
10	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
11	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
12	619-05926 ENVIRONMENTAL CONTROL	LUMP	LUMP
13	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
14	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
15	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
16	619-51859 PAINT STEEL BRIDGE	LUMP	LUMP
17	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
18	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
19	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
20	619-61000 CLEAN STEEL BRIDGE	LUMP	LUMP
21	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	12.000	MOS
22	628-09409 MOBILE INTERNET SERVICE	12.000	MOS
23	709-51821 SURFACE SEAL	LUMP	LUMP
24	709-51821 SURFACE SEAL	LUMP	LUMP
25	709-51821 SURFACE SEAL	LUMP	LUMP
26	709-51821 SURFACE SEAL	LUMP	LUMP
27	801-03290 CONSTRUCTION SIGN, C	11.000	EACH
28	801-06640 CONSTRUCTION SIGN, A	55.000	EACH
29	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 631

CONTRACT ID : M -30024-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	15.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	303-01180 COMPACTED AGGREGATE, NO. 53	200.000	TON
10	304-07491 HMA PATCHING, TYPE C	200.000	TON
11	306-08043 MILLING, TRANSITION	100.000	SYS
12	402-07434 HMA SURFACE, TYPE C	7,120.000	TON
13	402-07452 HMA WEDGE AND LEVEL, TYPE C	200.000	TON
14	406-05520 ASPHALT FOR TACK COAT	24.000	TON
15	615-97768 PARKING BARRIER, RESET	350.000	EACH
16	628-09402 FIELD OFFICE, B	5.000	MOS
17	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
18	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
20	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,000.000	LFT
21	801-06640 CONSTRUCTION SIGN, A	5.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	6,705.000	LFT
24	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	850.000	LFT
25	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN.	270.000	LFT
26	808-09358 PAVEMENT MESSAGE MARKING, PAINT, NO PARKING	10.000	EACH



CALL ORDER : 641

CONTRACT ID : M -30027-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-52710 SIDEWALK, CONCRETE, REMOVE	12.000	SYS
8	303-01180 COMPACTED AGGREGATE, NO. 53	100.000	TON
9	304-07491 HMA PATCHING, TYPE C	150.000	TON
10	306-08043 MILLING, TRANSITION	1,165.000	SYS
11	402-07434 HMA SURFACE, TYPE C	3,144.000	TON
12	402-07452 HMA WEDGE AND LEVEL, TYPE C	140.000	TON
13	406-05520 ASPHALT FOR TACK COAT	11.000	TON
14	615-06496 PARKING BARRIER	20.000	EACH
15	615-97768 PARKING BARRIER, RESET	427.000	EACH
16	628-09402 FIELD OFFICE, B	4.000	MOS
17	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	801-07118 BARRICADE, III-A	70.000	LFT
20	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	8,220.000	LFT
21	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	336.000	LFT
22	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN.	48.000	LFT
23	808-09358 PAVEMENT MESSAGE MARKING, PAINT, NO PARKING	2.000	EACH
24	808-09359 PAVEMENT MESSAGE MARKING, PAINT,	2.000	EACH

CALL ORDER : 651

CONTRACT ID : M -30119-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 DRAINAGE DITCH CORRECTION			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	711-91996 REPAIR EXISTING STRUCTURE	LUMP	LUMP
7	711-91996 REPAIR EXISTING STRUCTURE	LUMP	LUMP
8	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
9	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
10	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 671

CONTRACT ID : M -30205-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	303-01180 COMPACTED AGGREGATE, NO. 53	37.000	TON
7	304-07490 HMA PATCHING, TYPE B	60.000	TON
8	304-07493 WIDENING WITH HMA, TYPE B	9.000	TON
9	306-08043 MILLING, TRANSITION	400.000	SYS
10	402-07433 HMA SURFACE, TYPE B	411.000	TON
11	406-05520 ASPHALT FOR TACK COAT	1.500	TON
12	615-97768 PARKING BARRIER, RESET	32.000	EACH
13	628-09401 FIELD OFFICE, A	3.000	MOS
14	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	3.000	MOS
15	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
16	801-03290 CONSTRUCTION SIGN, C	1.000	EACH
17	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
19	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,200.000	LFT
20	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	4.000	EACH
21	808-09314 LINE, PAINT, SOLID, BLUE, 4 IN.	135.000	LFT

CALL ORDER : 681

CONTRACT ID : M -30215-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE DECK BARRIER WALL			
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	262.500	LFT
11	202-02446 BRIDGE RAILING, CONCRETE, REMOVE	74.000	LFT
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
13	203-02070 BORROW	15.000	CYS
14	203-08607 LINEAR GRADING	525.000	LFT
15	303-01180 COMPACTED AGGREGATE, NO. 53	40.000	TON
16	304-07491 HMA PATCHING, TYPE C	3.000	TON
17	601-02800 GUARDRAIL TRANSITION, TGT	3.000	EACH
18	601-06035 GUARDRAIL, RESET	50.000	LFT
19	601-07050 GUARDRAIL END TREATMENT, OS, RESET	1.000	EACH
20	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
21	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	175.000	LFT
22	615-06535 BENCH MARK POST, RESET	1.000	EACH
23	616-06451 RIPRAP, UNIFORM	9.000	TON
24	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
25	628-09409 MOBILE INTERNET SERVICE	5.000	MOS
26	702-51863 FIELD DRILLED HOLE IN CONCRETE	120.000	EACH
27	706-08352 RAILING, CF-1	80.000	LFT
28	729-51875 CONCRETE, A, PATCHING	379.000	SFT
29	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
30	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
31	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
32	801-06710 FLASHING ARROW SIGN	120.000	DAY
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	24.000	LFT
35	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	18.000	SFT

CALL ORDER : 691

CONTRACT ID : M -30238-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 206-51235	COFFERDAM	LUMP	LUMP
7 628-09402	FIELD OFFICE, B	4.000	MOS
8 725-06858	PIPE LINER, THERMOPLASTIC, 36 IN.	330.000	LFT
9 725-06859	PIPE LINER, THERMOPLASTIC, 48 IN.	167.000	LFT
10 801-03290	CONSTRUCTION SIGN, C	3.000	EACH
11 801-06640	CONSTRUCTION SIGN, A	17.000	EACH
12 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 701

CONTRACT ID : M -30391-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	210-05873 TESTING	LUMP	LUMP
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	729.000	TON
11	303-07449 COMPACTED AGGREGATE, NO. 73	972.000	TON
12	304-07490 HMA PATCHING, TYPE B	10.000	TON
13	304-07490 HMA PATCHING, TYPE B	110.000	TON
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,138.000	SYS
15	306-08043 MILLING, TRANSITION	19,480.000	SYS
16	306-08432 MILLING, APPROACH	1,164.000	SYS
17	402-07451 HMA WEDGE AND LEVEL, TYPE B	5,897.000	TON
18	406-05520 ASPHALT FOR TACK COAT	24.000	TON
19	610-07486 HMA FOR APPROACHES, TYPE A	478.000	TON
20	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
21	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
22	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
23	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,624.000	LFT
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,624.000	LFT
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	801-92448 CONSTRUCTION SIGNS, MOBILE	60.000	DAY
27	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,561.000	LFT
28	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	51,519.000	LFT
29	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	40,392.000	LFT
30	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	2.000	EACH
31	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	2.000	EACH
32	808-75140 PAVEMENT MESSAGE MARKINGS, PAINT, WORD RXR	2.000	EACH
33	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	306.000	EACH
34	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	306.000	EACH

CALL ORDER : 711

CONTRACT ID : M -30612-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT WEDGE AND LEVEL			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07491 HMA PATCHING, TYPE C	1,200.000	TON
12	306-08034 MILLING, ASPHALT, 1 1/2 IN.	44,000.000	SYS
13	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
14	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	3,750.000	TON
15	406-05520 ASPHALT FOR TACK COAT	11.500	TON
16	628-09402 FIELD OFFICE, B	5.000	MOS
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,300.000	LFT
19	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,300.000	LFT
20	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,000.000	LFT
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	27,000.000	LFT
24	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	6,000.000	LFT
25	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	249.000	EACH
26	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	250.000	EACH

CALL ORDER : 721

CONTRACT ID : M -30689-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT PATCHING			
1	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	15.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	304-07490 HMA PATCHING, TYPE B	978.000	TON
10	402-07451 HMA WEDGE AND LEVEL, TYPE B	815.000	TON
11	406-05520 ASPHALT FOR TACK COAT	3.000	TON
12	628-09401 FIELD OFFICE, A	5.000	MOS
13	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
15	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	500.000	LFT
16	801-06640 CONSTRUCTION SIGN, A	56.000	EACH
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	6,950.000	LFT
19	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	211,200.000	LFT
20	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	171,500.000	LFT
21	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	75.000	LFT
22	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
23	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	1.000	EACH
24	306-08033 MILLING, ASPHALT, 1 IN.	11,175.000	SYS



CALL ORDER : 731

CONTRACT ID : M -30829-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 303-07449	COMPACTED AGGREGATE, NO. 73	700.000	TON
7 304-07490	HMA PATCHING, TYPE B	100.000	TON
8 306-08034	MILLING, ASPHALT, 1 1/2 IN.	120.000	SYS
9 306-08042	MILLING, SCARIFICATION/PROFILE	33,470.000	SYS
10 306-08043	MILLING, TRANSITION	5,700.000	SYS
11 402-07451	HMA WEDGE AND LEVEL, TYPE B	3,700.000	TON
12 406-05520	ASPHALT FOR TACK COAT	12.000	TON
13 610-07487	HMA FOR APPROACHES, TYPE B	200.000	TON
14 628-09402	FIELD OFFICE, B	4.000	MOS
15 628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	4.000	MOS
16 801-03290	CONSTRUCTION SIGN, C	4.000	EACH
17 801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1,100.000	LFT
18 801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1,100.000	LFT
19 801-06640	CONSTRUCTION SIGN, A	19.000	EACH
20 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
21 808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	2,470.000	LFT
22 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	21,640.000	LFT
23 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5,040.000	LFT

CALL ORDER : 741

CONTRACT ID : M -30861-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	306-08037 MILLING, ASPHALT, 3 IN.	8,490.000	SYS
8	306-08042 MILLING, SCARIFICATION/PROFILE	4,533.000	SYS
9	306-08432 MILLING, APPROACH	2,042.000	SYS
10	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,093.000	TON
11	406-05520 ASPHALT FOR TACK COAT	3.150	TON
12	610-07488 HMA FOR APPROACHES, TYPE C	168.000	TON
13	720-44000 CASTING, ADJUST TO GRADE	15.000	EACH
14	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	4,530.000	LFT
18	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	100.000	LFT

CALL ORDER : 751

CONTRACT ID : M -30924-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEBRIS REMOVAL		
1 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	2.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 109-08359	LIQUIDATED DAMAGES	1.000	DOL
5 109-08360	CONTRACT LIENS	1.000	DOL
6 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8 201-90788	DEBRIS, REMOVE	LUMP	LUMP
9 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
10 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
11 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 761

CONTRACT ID : M -31010-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL REPAIR		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	202-02241 GUARDRAIL, REMOVE	1,000.000	LFT
7	202-02271 HEADWALL, REMOVE	4.000	EACH
8	202-74025 FENCE, REMOVE	300.000	LFT
9	203-02000 EXCAVATION, COMMON	30.000	CYS
10	203-02070 BORROW	20.000	CYS
11	303-01180 COMPACTED AGGREGATE, NO. 53	40.000	TON
12	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	6.000	EACH
13	601-02208 GUARDRAIL TERMINAL SECTION, GALVANIZED, 11 IN., INSTALLED	1.000	EACH
14	601-02209 GUARDRAIL, STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE,	1.000	EACH
15	601-02211 GUARDRAIL POST, 8.5 LBS PER LFT, 7 FT 0 IN LONG, GALVANIZED	250.000	EACH
16	601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12 FT. 6 IN.	10.000	EACH
17	601-03463 GUARDRAIL, STEEL CURVED TERMINAL END SECTION, LABOR ONLY	5.000	EACH
18	601-03469 W BEAM BACK UP PLATE, STEEL	200.000	EACH
19	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	20.000	EACH
20	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	5.000	EACH
21	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	5.000	EACH
22	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	5.000	EACH
23	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	10.000	EACH
24	601-03677 ANCHOR, TYPE 5	5.000	EACH
25	601-05856 CAT	2.000	EACH
26	601-05856 CAT	2.000	EACH
27	601-05856 CAT	5.000	EACH
28	601-05856 CAT	1.000	EACH
29	601-05856 CAT	5.000	EACH
30	601-05856 CAT	5.000	EACH
31	601-05856 CAT	10.000	EACH
32	601-05856 CAT	1.000	EACH
33	601-05856 CAT	1.000	EACH
34	601-05856 CAT	1.000	EACH
35	601-05856 CAT	1.000	EACH
36	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
37	601-06053 GUARDRAIL	250.000	EACH
38	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
39	601-06273 GUARDRAIL END TREATMENT, SKT-350	3.000	EACH
40	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
41	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
42	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
43	601-06854 GUARDRAIL, W-BEAM, NESTED	6.000	EACH
44	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
45	601-09238 HAND DIG GUARDRAIL POST HOLES	10.000	EACH
46	601-52540 GUARDRAIL TERMINAL SECTION, W BEAM	1.000	EACH
47	601-61320 CURVED SECTION, STEEL BEAM GUARDRAIL GALVANIZED, 12 GA.	400.000	LFT
48	601-61330 CHANNEL, 6.7 LBS PER LFT, 5 IN., GALVANIZED	300.000	LFT
49	601-61340 GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN.	60.000	EACH

CALL ORDER : 761

CONTRACT ID : M -31010-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL REPAIR		
50	601-61380 GUARDRAIL TERMINAL SECTION, FLATEND, GALVANIZED	1.000	EACH
51	601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	10.000	EACH
52	601-61410 GUARDRAIL TERMINAL SECTION, DOUBLE FACE, GALVANIZED	1.000	EACH
53	601-61550 GUARDRAIL TERMINAL END SECTION, ALUMINUM	1.000	EACH
54	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	5,000.000	LFT
55	601-62090 GUARDRAIL, STEEL BEAM, INSTALL	1,000.000	LFT
56	601-62100 GUARDRAIL POST, STEEL, INSTALL	10.000	EACH
57	601-62110 GUARDRAIL, CHANNEL, 6.7 LBS PER LFT., INSTALL	200.000	LFT
58	601-62120 GUARDRAIL POST BRACKET, INSTALL	10.000	EACH
59	601-62149 GUARDRAIL POST, 15.5 LBS PER LFT., GALVANIZED,	10.000	EACH
60	601-62297 GUARDRAIL STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE	1.000	EACH
61	601-62530 GUARDRAIL PIER CONNECTION, ES	1.000	EACH
62	601-62540 GUARDRAIL POST, PLUMB	700.000	EACH
63	601-62554 GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM, INSTALL	500.000	LFT
64	601-62570 GUARDRAIL DIAPHRAGM, ALUMINUM	1.000	EACH
65	601-62600 GUARDRAIL POST BRACKET, A, ALUMINUM	1.000	EACH
66	601-62720 GUARDRAIL, TUBING, 1, ALUMINUM	50.000	LFT
67	601-62770 GUARDRAIL ANCHOR, 0.75 IN. BOLT, GALVANIZED THRU CONCRETE	40.000	EACH
68	601-90382 GUARDRAIL POST, ALUMINUM, 7 FT.	20.000	EACH
69	601-90389 GUARDRAIL TERMINAL SECTION, GALVANIZED, 11 IN.	8.000	EACH
70	601-90677 DRILLED BRACKET, INSTALL	20.000	EACH
71	601-90678 CONCRETE, A, BURIED END SECTION	10.000	CYS
72	601-90960 GUARDRAIL, TUBE, ALUMINUM, III	40.000	LFT
73	601-90962 GUARDRAIL EXPANSION ANCHORS, REPLACEMENT	5.000	EACH
74	601-91423 GUARDRAIL SPLICE PLATE, C, LABOR ONLY	1.000	EACH
75	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	3.000	EACH
76	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	3.000	EACH
77	601-91512 GUARDRAIL ATTENUATING TERMINAL, WOOD BLOCK, MKA	12.000	EACH
78	601-91513 GUARDRAIL ATTENUATING TERMINAL, WOOD BLOCK, MKE	12.000	EACH
79	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	4.000	EACH
80	601-91576 GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	4.000	EACH
81	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	1.000	EACH
82	601-91650 GUARDRAIL THRIE BEAM EXPANSION RAIL, GALVANIZED	20.000	LFT
83	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	1.000	EACH
84	601-92973 GUARDRAIL END TREATMENT, LABOR ONLY	2.000	EACH
85	601-93346 GUARDRAIL CONNECTOR, AS	5.000	EACH
86	601-94689 GUARDRAIL END TREATMENT, OS	13.000	EACH
87	601-94689 GUARDRAIL END TREATMENT, OS	13.000	EACH
88	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
89	601-95342 GUARDRAIL SPLICE PLATE, C, GALVANIZED	1.000	EACH
90	601-95917 GUARDRAIL POST PADDLE, ALUMINUM, INSTALL	20.000	EACH
91	601-95924 GUARDRAIL TERMINAL PIECE, ALUMINUM, INSTALL	5.000	EACH
92	601-95927 GUARDRAIL TERMINAL SECTION, SINGLEFACE, BURIED END,	3.000	EACH
93	601-95928 GUARDRAIL TERMINAL SECTION, DOUBLEFACE, BURIED END,	3.000	EACH
94	601-95972 GUARDRAIL POST (CRT), 8 IN. X 6 IN. TREATED LUMBER,	15.000	EACH
95	601-98826 BREAKAWAY CABLE TERMINAL, A, BASE PADDLE POST OR ALTERNATE	1.000	EACH
96	601-98836 BREAKAWAY CABLE TERMINAL, A, TERMINAL TUBE POST OR POST 1 A	1.000	EACH
97	601-98837 BREAKAWAY CABLE TERMINAL, A, PUNCHED GUARD RAIL SECTION,	25.000	LFT
98	601-98838 BREAKAWAY CABLE TERMINAL, A, FOUNDATION POST, INCLUDING	3.000	EACH

CALL ORDER : 761

CONTRACT ID : M -31010-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 GUARDRAIL REPAIR			
99	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	3,000.000	LFT
100	601-99106 GUARDRAIL, W BEAM, 3 FT. 1.5 IN. SPACING	50.000	LFT
101	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	50.000	LFT
102	601-99109 GUARDRAIL, W BEAM, DOUBLE FACED, 3 FT. 1.5 IN. SPACING	50.000	LFT
103	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	1.000	EACH
104	601-99133 GUARDRAIL TRANSITION VH, 12 FT. 6 IN. SPACING	1.000	EACH
105	603-01932 FENCE, CHAIN LINK, 96 IN.	100.000	LFT
106	603-06040 FENCE, FARM FIELD, 47 IN.	2,800.000	LFT
107	603-06045 FENCE, CHAIN LINK, 48 IN.	1,000.000	LFT
108	603-06060 FENCE, FARM FIELD, RESET	200.000	LFT
109	603-06065 FENCE, CHAIN LINK, RESET	200.000	LFT
110	603-06065 FENCE, CHAIN LINK, RESET	100.000	LFT
111	603-06065 FENCE, CHAIN LINK, RESET	100.000	LFT
112	603-92636 FENCE, CHAIN LINK, 72 IN.	100.000	LFT
113	603-98840 FENCE, CHAIN LINK FABRIC, 9 GAUGE	1,000.000	LFT
114	603-98840 FENCE, CHAIN LINK FABRIC, 9 GAUGE	100.000	LFT
115	603-98840 FENCE, CHAIN LINK FABRIC, 9 GAUGE	100.000	LFT
116	603-98842 POST, LINE, 3.65 LBS PER LFT.	75.000	EACH
117	603-98842 POST, LINE, 3.65 LBS PER LFT.	10.000	EACH
118	603-98842 POST, LINE, 3.65 LBS PER LFT.	1.000	EACH
119	603-98848 POST, LINE, CHAIN LINK	75.000	EACH
120	603-98848 POST, LINE, CHAIN LINK	5.000	EACH
121	603-98848 POST, LINE, CHAIN LINK	5.000	EACH
122	603-98848 POST, LINE, CHAIN LINK	5.000	EACH
123	603-98849 POST, LINE, FARM FIELD	30.000	EACH
124	603-98849 POST, LINE, FARM FIELD	10.000	EACH
125	603-98850 WIRE, 4 POINT BARB, 12.5 GAUGE	1,000.000	LFT
126	603-98851 WIRE, TENSION, 7 GAUGE	1,000.000	LFT
127	603-98852 FENCE, 1.25 IN. DIAGONAL BRACE, 2.27 LBS/LFT	20.000	EACH
128	603-98853 FENCE, TRUSS ROD, .375 IN.	4.000	EACH
129	603-98855 FENCE, FLAT STRETCHER BAR, .1875 IN. X .75 IN.	4.000	EACH
130	616-02320 GEOTEXTILES	200.000	SYS
131	616-06405 RIPRAP, REVELMENT	20.000	TON
132	702-06850 SOUND BARRIER	10.000	EACH
133	702-06850 SOUND BARRIER	10.000	EACH
134	702-06850 SOUND BARRIER	10.000	EACH
135	702-06850 SOUND BARRIER	1.000	EACH
136	702-06850 SOUND BARRIER	15.000	EACH
137	702-06851 SOUND BARRIER	300.000	LFT
138	702-06851 SOUND BARRIER	250.000	LFT
139	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	1.000	EACH
140	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	1.000	EACH
141	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	1.000	EACH
142	706-05735 CONCRETE BRIDGE RAILING TRANSITION, WBT	1.000	EACH
143	706-62310 BRIDGE RAILING BRACKET A, GALVANIZED	1.000	EACH
144	706-62320 BRIDGE RAILING BRACKET B, GALVANIZED	1.000	EACH
145	706-62390 BRIDGE RAILING POST, 6	1.000	EACH
146	706-62400 BRIDGE RAILING POST, 7	1.000	EACH
147	706-90676 EXPANSION ANCHOR	1.000	EACH

CALL ORDER : 761

CONTRACT ID : M -31010-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL REPAIR		
148 706-95929	BRIDGE RAILING POST, 5, ALUMINUM, INSTALL	25.000	EACH
149 706-95930	BRIDGE RAILING POST, 5A, ALUMINUM, INSTALL	15.000	EACH
150 711-98839	ANCHOR ASSEMBLY AS1, REPAIR	10.000	EACH
151 807-06796	ELECTRIC	1.000	EACH

CALL ORDER : 811

CONTRACT ID : T -29890-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL INSTALLATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-01874 SHEET SIGN AND POST, REMOVE	4.000	EACH
11	628-09403 FIELD OFFICE, C	6.000	MOS
12	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
13	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
14	801-06710 FLASHING ARROW SIGN	20.000	DAY
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	90.000	SFT
17	802-76055 SIGN POST, A	124.000	LFT
18	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
19	805-01842 HANDHOLE, SIGNAL	7.000	EACH
20	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	1,423.000	LFT
21	805-78109 CONTROLLER AND CABINET, SECONDARY, MENU DRIVEN, 8 PHASE	1.000	EACH
22	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
23	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
24	805-78420 DISCONNECT HANGER	4.000	EACH
25	805-78445 SIGNAL SERVICE	1.000	EACH
26	805-78467 SIGNAL CABLE, 3C 8GA.	76.000	LFT
27	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,227.000	LFT
28	805-78485 SIGNAL CABLE, 5C 14GA.	251.000	LFT
29	805-78490 SIGNAL CABLE, 7C 14GA.	781.000	LFT
30	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,998.000	LFT
31	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
32	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	724.000	LFT
33	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
34	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT.	4.000	EACH
35	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	4.000	EACH
36	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	256.000	LFT
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,091.000	LFT
38	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,541.000	LFT
39	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	139.000	LFT
40	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
41	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH



CALL ORDER : 821

CONTRACT ID : T -29965-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
11	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
12	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
15	801-06710 FLASHING ARROW SIGN	30.000	DAY
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	20.000	LFT
18	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	10.000	SFT
19	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	18.000	SFT
20	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
21	805-01842 HANDHOLE, SIGNAL	8.000	EACH
22	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
23	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	1,890.000	LFT
24	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
25	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	8.000	EACH
26	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
27	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
28	805-78420 DISCONNECT HANGER	4.000	EACH
29	805-78445 SIGNAL SERVICE	1.000	EACH
30	805-78467 SIGNAL CABLE, 3C 8GA.	70.000	LFT
31	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	3,172.000	LFT
32	805-78480 SIGNAL CABLE, 3C 14GA.	210.000	LFT
33	805-78485 SIGNAL CABLE, 5C 14GA.	640.000	LFT
34	805-78490 SIGNAL CABLE, 7C 14GA.	545.000	LFT
35	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	3,559.000	LFT
36	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
37	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,144.000	LFT
38	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
39	805-79020 TRAFFIC SIGNAL INSTALLATION	LUMP	LUMP
40	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	26.000	EACH
41	805-95466 FLASHING BEACON WITH SIGNAL AHEAD SIGN, 6 IN. I BEAM AND	2.000	EACH
42	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	183.000	LFT
43	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	8.000	EACH
44	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH

CALL ORDER : 831

CONTRACT ID : T -30383-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
11	202-86946 HANDHOLE, REMOVE	1.000	EACH
12	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
13	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
14	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
16	801-06710 FLASHING ARROW SIGN	30.000	DAY
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	24.000	LFT
19	802-05702 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	104.000	LFT
20	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	10.000	SFT
21	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	82.000	SFT
22	805-01815 SIGNAL SUPPORT FOUNDATION, 3 FT. X 12 FT.	4.000	EACH
23	805-01842 HANDHOLE, SIGNAL	11.000	EACH
24	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
25	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	2,579.000	LFT
26	805-06834 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE, TS2, TYPE I	1.000	EACH
27	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	10.000	EACH
28	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	2.000	EACH
29	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
30	805-78420 DISCONNECT HANGER	3.000	EACH
31	805-78445 SIGNAL SERVICE	1.000	EACH
32	805-78467 SIGNAL CABLE, 3C 8GA.	70.000	LFT
33	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,928.000	LFT
34	805-78485 SIGNAL CABLE, 5C 14GA.	1,253.000	LFT
35	805-78490 SIGNAL CABLE, 7C 14GA.	1,008.000	LFT
36	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	4,860.000	LFT
37	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
38	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	1,056.000	LFT
39	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
40	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT.	4.000	EACH
41	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	24.000	EACH
42	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	14.300	SYS
43	808-06368 TRANSVERSE MARKING, REMOVE	56.000	LFT
44	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	105.000	LFT
45	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	4.000	EACH
46	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	3.000	EACH

CALL ORDER : 841

CONTRACT ID : T -30538-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	RAISED PAVEMENT MARKINGS		
1 105-08520	CELLULAR TELEPHONE/RADIO	2.000	EACH
2 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
3 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4 109-08359	LIQUIDATED DAMAGES	1.000	DOL
5 109-08360	CONTRACT LIENS	1.000	DOL
6 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
7 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
10 628-09409	MOBILE INTERNET SERVICE	3.000	MOS
11 801-06710	FLASHING ARROW SIGN	60.000	DAY
12 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
13 801-92448	CONSTRUCTION SIGNS, MOBILE	240.000	DAY
14 808-75994	PRISMATIC REFLECTOR	16,788.000	EACH
15 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	3,000.000	EACH

CALL ORDER : 851

CONTRACT ID : T -30706-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	RAISED PAVEMENT MARKERS, NEW		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
7 628-09409	MOBILE INTERNET SERVICE	5.000	MOS
8 801-03290	CONSTRUCTION SIGN, C	4.000	EACH
9 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
10 801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	1.000	EACH
11 808-75994	PRISMATIC REFLECTOR	34,024.000	EACH
12 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3,817.000	EACH
13 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4,144.000	EACH

CALL ORDER : 871

CONTRACT ID : TM-29776-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.000	EACH
8	306-08034 MILLING, ASPHALT, 1 1/2 IN.	279.670	SYS
9	402-07432 HMA SURFACE, TYPE A	29.560	TON
10	406-05521 ASPHALT FOR TACK COAT	279.670	SYS
11	628-09402 FIELD OFFICE, B	6.000	MOS
12	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
15	801-06710 FLASHING ARROW SIGN	50.000	DAY
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
17	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	88.000	SFT
18	802-76035 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.100 IN.	386.000	SFT
19	802-76045 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.125 IN.	108.000	SFT
20	805-01842 HANDHOLE, SIGNAL	43.000	EACH
21	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN., UNDERGROUND	4,922.000	LFT
22	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
23	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOLS, 18 IN.	2.000	EACH
24	805-03592 PAINT EXISTING SIGNAL STRUCTURE	4.000	EACH
25	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER, GREEN	53.000	EACH
26	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN. RED, AMBER ARROW, GREEN	10.000	EACH
27	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN. RED, AMBER, GREEN,	15.000	EACH
28	805-78370 PEDESTRIAN PUSH BUTTON	2.000	EACH
29	805-78415 SPAN, CATENARY, AND TETHER	28.000	EACH
30	805-78420 DISCONNECT HANGER	28.000	EACH
31	805-78445 SIGNAL SERVICE	7.000	EACH
32	805-78467 SIGNAL CABLE, 3C 8GA.	700.000	LFT
33	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	20,920.000	LFT
34	805-78480 SIGNAL CABLE, 3C 14GA.	345.000	LFT
35	805-78485 SIGNAL CABLE, 5C 14GA.	2,185.000	LFT
36	805-78490 SIGNAL CABLE, 7C 14GA.	5,820.000	LFT
37	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	38,276.000	LFT
38	805-78785 SIGNAL DETECTOR HOUSING	46.000	EACH
39	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	7,065.000	LFT
40	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	27.000	EACH
41	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	25.000	EACH
42	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	300.000	SYS
43	808-06368 TRANSVERSE MARKING, REMOVE	1,510.000	LFT
44	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	200.000	LFT
45	808-06716 LINE, REMOVE	560.000	LFT
46	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	140.000	LFT
47	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	1,510.000	LFT
48	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	360.000	LFT
49	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	89.000	EACH

CALL ORDER : 871

CONTRACT ID : TM-29776-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
50 808-75325	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	46.000	EACH

CALL ORDER : 881

CONTRACT ID : TM-30240-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNALS MODERNIZATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02241 GUARDRAIL, REMOVE	50.000	LFT
11	202-86946 HANDHOLE, REMOVE	2.000	EACH
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
13	202-95579 SERVICE POINT, REMOVE	1.000	EACH
14	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
15	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000	EACH
16	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
17	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	50.000	LFT
18	616-02320 GEOTEXTILES	360.000	SYS
19	616-05689 RIPRAP, CLASS 2	342.000	TON
20	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
21	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
22	801-06710 FLASHING ARROW SIGN	30.000	DAY
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
24	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
25	805-06592 CONDUIT, STEEL, GALVANIZED, 2 IN.	741.000	LFT
26	805-86890 POLE CIRCUIT CABLE, 1C NO. 10 THW OR TW STRANDED COPPER	975.000	LFT
27	805-87485 INSULATING LINK, FURNISH	14.000	EACH
28	805-87490 INSULATING LINK, WATER PROOFED, FURNISH	20.000	EACH
29	807-02191 HANDHOLE, LIGHTING	5.000	EACH
30	807-02428 CONCRETE FOUNDATION WITH GROUNDING, 30 IN. X 30 IN. X 96 IN.	7.000	EACH
31	807-03934 LIGHT STRUCTURE, REMOVE	7.000	EACH
32	807-07580 WIRE, NO.4, COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1,514.000	LFT
33	807-84764 LIGHT POLE, 40 FT. E.M.H., 16.0 FT. MAST ARM, TRANSFORMER	1.000	EACH
34	807-84768 LIGHT POLE, 40 FT. E.M.H., 18.0 FT. MAST ARM, TRANSFORMER	1.000	EACH
35	807-84816 LIGHT POLE, 42 FT. E.M.H., 16.0 FT. MAST ARM, TRANSFORMER	3.000	EACH
36	807-84820 LIGHT POLE, 42 FT. E.M.H., 18.0 FT. MAST ARM, BREAKAWAY BASE	2.000	EACH
37	807-86805 SERVICE POINT, I	1.000	EACH
38	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
39	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
40	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.000	EACH
41	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
42	807-86950 SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION	7.000	EACH
43	807-86955 CABLE DUCT MARKER	6.000	EACH
44	807-87205 LUMINAIRE ROADWAY, HIGH PRESSURE SODIUM, 400 WATT, FURNISH	7.000	EACH

CALL ORDER : 891

CONTRACT ID : TM-31079-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT MARKINGS			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
7	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
8	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
9	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
10	801-92448 CONSTRUCTION SIGNS, MOBILE	100.000	DAY
11	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	19,960.000	LFT
12	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	193,664.000	LFT
13	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	164,191.000	LFT
14	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	28,624.000	LFT
15	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	2,700.000	LFT
16	808-06716 LINE, REMOVE	148,796.000	LFT
17	808-06800 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW, CROSSHATCH LINE,	506.000	LFT
18	808-09038 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE,	2,083.000	LFT
19	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	1,790.000	LFT
20	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	63.000	EACH
21	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	37.000	EACH
22	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	32,900.000	LFT
23	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	1,529.000	LFT
24	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	2,231.000	LFT
25	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	106.000	EACH
26	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	77.000	EACH
27	808-94455 TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	2,883.000	LFT
28	808-95933 CURB PAINTING, YELLOW	11,836.000	LFT
29	808-98000 LINE, EPOXY, SOLID, YELLOW, 8 IN.	1,906.000	LFT



