

CALL ORDER : 121

CONTRACT ID : SR -27370-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	5.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
11	203-02000 EXCAVATION, COMMON	1,313.000	CYS
12	203-51223 EXCAVATION, WATERWAY	113.000	CYS
13	205-03371 SEDIMENT, REMOVE	110.000	CYS
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	80.000	LFT
15	205-06936 TEMPORARY SEDIMENT TRAP	220.000	TON
16	206-51220 EXCAVATION, WET	355.000	CYS
17	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	750.000	CYS
18	207-08263 SUBGRADE TREATMENT, TYPE IA	3,060.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	408.200	SYS
20	211-09264 STRUCTURE BACKFILL, TYPE 1	55.000	CYS
21	211-09268 STRUCTURE BACKFILL, TYPE 5	455.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	940.000	TON
23	306-08037 MILLING, ASPHALT, 3 IN.	1,667.000	SYS
24	306-08043 MILLING, TRANSITION	267.000	SYS
25	402-07432 HMA SURFACE, TYPE A	676.000	TON
26	402-07434 HMA SURFACE, TYPE C	220.000	TON
27	402-07435 HMA INTERMEDIATE, TYPE A	460.000	TON
28	402-07439 HMA INTERMEDIATE, TYPE C	460.000	TON
29	402-07442 HMA BASE, TYPE C	365.000	TON
30	406-05520 ASPHALT FOR TACK COAT	3.000	TON
31	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	1.000	EACH
32	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	2.000	EACH
33	601-02206 TEMPORARY GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	312.500	LFT
34	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	300.000	LFT
37	610-07487 HMA FOR APPROACHES, TYPE B	115.000	TON
38	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
39	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
40	615-06490 RIGHT OF WAY MARKER	19.000	EACH
41	615-06500 MONUMENT, A	2.000	EACH
42	616-02320 GEOTEXTILES	436.000	SYS
43	616-06405 RIPRAP, REVETMENT	471.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
45	621-06545 FERTILIZER	1.000	TON
46	621-06553 SEED MIXTURE, R	245.000	LBS
47	621-06557 SEED MIXTURE, T	115.000	LBS
48	621-06565 MULCHING MATERIAL	6.000	TON
49	621-06567 WATER	25.000	KGAL

CALL ORDER : 121

CONTRACT ID : SR -27370-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	621-06574 SODDING	527.000	SYS
51	628-09401 FIELD OFFICE, A	5.000	MOS
52	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	220.000	LFT
53	715-46005 PIPE END SECTION, 15 IN.	12.000	EACH
54	723-06660 WINGWALL	60.000	SYS
55	723-09069 STRUCTURE, PRECAST THREE-SIDED, 144 IN. X 96 IN.	58.000	LFT
56	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
57	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
58	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	1,500.000	LFT
59	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,180.000	LFT
60	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
61	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
62	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
63	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
64	801-07119 BARRICADE, III-B	24.000	LFT
65	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	875.000	LFT
66	808-01428 TEMPORARY TRANSVERSE MARKINGS, WHITE, STOP LINE, 24 IN.	24.000	LFT
67	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,100.000	LFT
68	808-06716 LINE, REMOVE	415.000	LFT
69	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	291.250	LFT
70	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.000	EACH
71	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	15.000	EACH

CALL ORDER : 131

CONTRACT ID : SR -29114-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	11.000	MOS
5	105-08523 RADIO SERVICE	11.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	64.400	SYS
16	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
17	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
20	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
22	203-02000 EXCAVATION, COMMON	5,156.600	CYS
23	203-02070 BORROW	123.700	CYS
24	205-03371 SEDIMENT, REMOVE	2,000.000	CYS
25	205-06932 TEMPORARY CHECK DAM, STRAW BALES	144.000	LFT
26	205-06936 TEMPORARY SEDIMENT TRAP	142.300	TON
27	205-06937 TEMPORARY SILT FENCE	1,014.000	LFT
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,400.000	SYS
29	207-08268 SUBGRADE TREATMENT, TYPE IV	10,120.000	SYS
30	211-09264 STRUCTURE BACKFILL, TYPE 1	114.400	CYS
31	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	200.300	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,191.500	TON
33	304-07491 HMA PATCHING, TYPE C	52.700	TON
34	306-08033 MILLING, ASPHALT, 1 IN.	66.700	SYS
35	306-08036 MILLING, ASPHALT, 2 IN.	6,098.000	SYS
36	306-08043 MILLING, TRANSITION	747.000	SYS
37	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
38	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	914.600	TON
39	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1,399.600	TON
40	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	1,296.200	TON
41	402-07432 HMA SURFACE, TYPE A	340.700	TON
42	402-07435 HMA INTERMEDIATE, TYPE A	291.300	TON
43	402-07440 HMA BASE, TYPE A	1,066.600	TON
44	406-05520 ASPHALT FOR TACK COAT	7.280	TON
45	601-91426 GUARDRAIL TERMINAL END SECTION, A	2.000	EACH
46	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	18.750	LFT
47	603-03398 FENCE, RELOCATE	1,115.000	LFT
48	603-03829 FENCE	130.000	LFT
49	610-07487 HMA FOR APPROACHES, TYPE B	586.600	TON

CALL ORDER : 131

CONTRACT ID : SR -29114-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH
51	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	9.480	TON
52	612-60410 DRILLED HOLE FOR UNDERSEAL	158.000	EACH
53	615-06490 RIGHT OF WAY MARKER	22.000	EACH
54	615-06500 MONUMENT, A	2.000	EACH
55	615-06505 MONUMENT, B	2.000	EACH
56	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
57	616-02320 GEOTEXTILES	366.000	SYS
58	616-06451 RIPRAP, UNIFORM	230.300	TON
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
60	621-06557 SEED MIXTURE, T	327.600	LBS
61	621-06560 MULCHED SEEDING, U	10,572.750	SYS
62	621-06575 SODDING, NURSERY	9,743.000	SYS
63	628-09402 FIELD OFFICE, B	11.000	MOS
64	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	11.000	MOS
65	714-06688 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 5 FT. X 2 FT.	32.000	LFT
66	714-26702 CULVERT, PRECAST BOX, REINFORCED CONCRETE, 6 FT. X 3 FT.	184.000	LFT
67	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN.	16.000	EACH
68	715-04830 GRATED BOX END SECTION	4.000	EACH
69	715-04830 GRATED BOX END SECTION	2.000	EACH
70	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	340.000	LFT
71	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	49.300	TON
72	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
73	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
74	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	9,050.000	LFT
75	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,800.000	LFT
76	801-06625 DETOUR ROUTE MARKER ASSEMBLY	54.000	EACH
77	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07118 BARRICADE, III-A	312.000	LFT
80	801-07119 BARRICADE, III-B	72.000	LFT
81	801-07120 BARRICADE, III, PERMANENT	12.000	LFT
82	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,160.000	LFT
83	802-04116 SIGN, PANEL, RESET	4.000	EACH
84	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	52.500	LFT
85	802-05705 SIGN POST, SQUARE, 2, UNREINFORCED ANCHOR BASE	61.000	LFT
86	802-09570 SIGN, SHEET, SHEETING TYPE IX, WITH	30.100	SFT
87	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
88	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6,919.000	LFT
89	808-06716 LINE, REMOVE	7,050.000	LFT
90	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7,540.000	LFT
91	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	24.000	LFT
92	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	12.000	EACH
93	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	33.000	EACH
94	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	164.000	EACH

CALL ORDER : 141

CONTRACT ID : SR -30221-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	203-02070 BORROW	10.000	CYS
11	205-06937 TEMPORARY SILT FENCE	400.000	LFT
12	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	5.000	CYS
13	303-01180 COMPACTED AGGREGATE, NO. 53	20.000	TON
14	603-06060 FENCE, FARM FIELD, RESET	60.000	LFT
15	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
16	621-06559 MULCHED SEEDING, R	2,000.000	SYS
17	628-09401 FIELD OFFICE, A	6.000	MOS
18	715-01662 PIPE CLEANING, 12 IN. TO 48 IN. DIA.	55.000	LFT
19	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN.	2.000	EACH
20	716-07632 PIPE INSTALLATION, TRENCHLESS, 18 IN.	54.000	LFT
21	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 161

CONTRACT ID : SR -30592-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08523 RADIO SERVICE	12.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	202-02241 GUARDRAIL, REMOVE	142.000	LFT
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	13.000	EACH
16	203-02070 BORROW	70.000	CYS
17	203-08607 LINEAR GRADING	64,000.000	LFT
18	303-01180 COMPACTED AGGREGATE, NO. 53	2,350.000	TON
19	304-07490 HMA PATCHING, TYPE B	9,286.000	TON
20	306-08033 MILLING, ASPHALT, 1 IN.	405,500.000	SYS
21	306-08043 MILLING, TRANSITION	750.000	SYS
22	306-08432 MILLING, APPROACH	29,600.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	33,600.000	TON
25	404-05511 SEAL COAT, 2	138,800.000	SYS
26	406-05520 ASPHALT FOR TACK COAT	105.000	TON
27	601-05999 CURVED TERMINAL END	1.000	EACH
28	601-94689 GUARDRAIL END TREATMENT, OS	14.000	EACH
29	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	50.000	LFT
30	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	13.000	EACH
31	610-07487 HMA FOR APPROACHES, TYPE B	2,440.000	TON
32	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	132.500	TON
33	612-60410 DRILLED HOLE FOR UNDERSEAL	2,208.000	EACH
34	628-09401 FIELD OFFICE, A	12.000	MOS
35	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
36	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
37	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	12,520.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12,520.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	47.000	EACH
41	801-06710 FLASHING ARROW SIGN	200.000	DAY
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	6.000	EACH
44	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	122.000	LFT
45	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	486.000	LFT
46	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	486.000	LFT
47	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	1.000	EACH
48	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	30,730.000	LFT
49	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	134,128.000	LFT

CALL ORDER : 161

CONTRACT ID : SR -30592-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50 808-06716	LINE, REMOVE	1,094.000	LFT
51 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	122,076.000	LFT
52 808-75297	TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	130.000	LFT
53 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,850.000	EACH
54 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1,850.000	EACH

CALL ORDER : 171

CONTRACT ID : SR -30903-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	203-08607 LINEAR GRADING	51,491.000	LFT
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,165.000	TON
14	304-07489 HMA PATCHING, TYPE A	2,500.000	TON
15	304-07783 HMA PATCHING, TYPE D	2,253.000	TON
16	306-08033 MILLING, ASPHALT, 1 IN.	338,315.000	SYS
17	306-08042 MILLING, SCARIFICATION/PROFILE	107,189.000	SYS
18	306-08043 MILLING, TRANSITION	2,030.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	9,010.000	TON
21	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	28,524.000	TON
22	406-05520 ASPHALT FOR TACK COAT	108.000	TON
23	606-07484 MILLED HMA SHOULDER CORRUGATIONS	201,084.000	LFT
24	628-09401 FIELD OFFICE, A	12.000	MOS
25	725-06878 PIPE LINER, THERMOPLASTIC, 84 IN.	240.000	LFT
26	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
27	801-03290 CONSTRUCTION SIGN, C	12.000	EACH
28	801-06204 TEMPORARY PAVEMENT MARKING, 5 IN.	5,149.000	LFT
29	801-06208 TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN	5,149.000	LFT
30	801-06640 CONSTRUCTION SIGN, A	38.000	EACH
31	801-06710 FLASHING ARROW SIGN	240.000	DAY
32	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
33	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
34	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	1,220.000	LFT
35	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	1,220.000	LFT
36	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	25,441.000	LFT
37	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	103,229.000	LFT
38	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	7,337.000	LFT
39	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	1,340.000	LFT
40	808-06716 LINE, REMOVE	2,745.000	LFT
41	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN.	305.000	LFT
42	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	101,762.000	LFT
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,492.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,492.000	EACH

CALL ORDER : 181

CONTRACT ID : SR -31056-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	303-01180 COMPACTED AGGREGATE, NO. 53	376.000	TON
7	503-03489 RETROFITTED TIE BARS	293.000	EACH
8	503-05240 D-1 CONTRACTION JOINT	552.000	LFT
9	506-06333 PCCP PATCHING, FULL DEPTH	1,657.000	SYS
10	506-06334 PCCP PATCHING, PARTIAL DEPTH	50.000	SYS
11	507-07482 CRACKS AND JOINTS IN PCCP, ROUT AND SEAL	100.000	LFT
12	628-09402 FIELD OFFICE, B	4.000	MOS
13	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
14	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	241.000	LFT
15	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
16	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	801-07119 BARRICADE, III-B	96.000	LFT
19	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
20	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	4,810.000	LFT
21	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	4,810.000	LFT
22	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	30.000	EACH

CALL ORDER : 221

CONTRACT ID : SRS-28667-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	25.000	LFT
13	202-02279 CURB AND GUTTER, REMOVE	2,810.000	LFT
14	202-52710 SIDEWALK, CONCRETE, REMOVE	1,325.000	SYS
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
16	304-07491 HMA PATCHING, TYPE C	740.000	TON
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	92,000.000	SYS
18	306-08432 MILLING, APPROACH	8,000.000	SYS
19	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7,600.000	TON
20	406-05520 ASPHALT FOR TACK COAT	26.000	TON
21	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
22	604-06069 CURB RAMP, CONCRETE	392.300	SYS
23	604-07894 CURB RAMP, CONCRETE, A	280.000	SYS
24	604-07896 CURB RAMP, CONCRETE, B	98.400	SYS
25	604-07898 CURB RAMP, CONCRETE, D	10.800	SYS
26	604-07900 CURB RAMP, CONCRETE, F	328.900	SYS
27	604-07901 CURB RAMP, CONCRETE, G	14.700	SYS
28	604-07902 CURB RAMP, CONCRETE, H	151.200	SYS
29	604-07903 CURB RAMP, CONCRETE, K	53.400	SYS
30	605-06140 CURB AND GUTTER, CONCRETE	2,810.000	LFT
31	610-07488 HMA FOR APPROACHES, TYPE C	660.000	TON
32	621-06575 SODDING, NURSERY	245.000	SYS
33	628-09402 FIELD OFFICE, B	12.000	MOS
34	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
35	720-44000 CASTING, ADJUST TO GRADE	9.000	EACH
36	801-01349 TEMPORARY STOP LINE, 24 IN	1,717.000	LFT
37	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	90.000	EACH
38	801-01505 TEMPORARY PAVEMENT MESSAGE MARKINGS, WORD (ONLY)	29.000	EACH
39	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
40	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	25,480.000	LFT
41	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	25,480.000	LFT
42	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (ONLY)	29.000	EACH
43	801-06213 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, WORD (RXR)	4.000	EACH
44	801-06640 CONSTRUCTION SIGN, A	62.000	EACH
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	7,686.000	LFT
47	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,772.000	LFT
48	808-01771 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW, CROSSHATCH LINE,	1,040.000	LFT
49	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	5,857.000	LFT

CALL ORDER : 221

CONTRACT ID : SRS-28667-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	16,182.000	LFT
51	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	2,281.000	LFT
52	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN.	212.000	LFT
53	808-05535 TRANSVERSE MARKINGS, EPOXY, SOLID, WHITE, CROSSHATCH LINE,	25.000	LFT
54	808-06680 TRANSVERSE MARKINGS, EPOXY	1,452.000	LFT
55	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	1,717.000	LFT
56	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	90.000	EACH
57	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	29.000	EACH
58	808-74809 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (R X R)	4.000	EACH
59	808-94455 TRANSVERSE MARKINGS, EPOXY, CROSSWALK, 6 IN.	6,596.000	LFT
60	808-98000 LINE, EPOXY, SOLID, YELLOW, 8 IN.	1,921.000	LFT

CALL ORDER : 231

CONTRACT ID : SRS-28719-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02241 GUARDRAIL, REMOVE	25.000	LFT
12	202-93741 GUARD RAIL END TREATMENT, REMOVE	11.000	EACH
13	203-02070 BORROW	55.000	CYS
14	203-08607 LINEAR GRADING	42,373.000	LFT
15	303-01180 COMPACTED AGGREGATE, NO. 53	600.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	76.340	TON
17	304-07491 HMA PATCHING, TYPE C	400.000	TON
18	304-07494 WIDENING WITH HMA, TYPE C	76.340	TON
19	306-08033 MILLING, ASPHALT, 1 IN.	101,060.100	SYS
20	306-08043 MILLING, TRANSITION	940.000	SYS
21	306-08432 MILLING, APPROACH	9,006.280	SYS
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	8,415.010	TON
24	406-05520 ASPHALT FOR TACK COAT	26.660	TON
25	601-94689 GUARDRAIL END TREATMENT, OS	11.000	EACH
26	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	450.000	LFT
27	610-07488 HMA FOR APPROACHES, TYPE C	635.210	TON
28	615-06505 MONUMENT, B	6.000	EACH
29	628-09402 FIELD OFFICE, B	9.000	MOS
30	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
31	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
32	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
33	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	4,038.000	LFT
34	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,038.000	LFT
35	801-06640 CONSTRUCTION SIGN, A	39.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	1,402.000	LFT
38	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	748.000	LFT
39	808-04896 LINE, EPOXY, BROKEN, YELLOW, 4 IN.	133.250	LFT
40	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	78,721.000	LFT
41	808-06716 LINE, REMOVE	2,283.000	LFT
42	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	5,100.000	LFT
43	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	52,359.000	LFT
44	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	911.000	EACH

CALL ORDER : 241

CONTRACT ID : SRS-28770-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07491 HMA PATCHING, TYPE C	400.000	TON
9	402-09282 ULTRATHIN BONDED WEARING COURSE SIZE 3/8 IN.	221,773.000	SYS
10	628-09401 FIELD OFFICE, A	3.000	MOS
11	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
12	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,300.000	LFT
13	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	4,933.000	LFT
16	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	5,112.000	LFT
17	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	126,711.000	LFT
18	808-06800 TRANSVERSE MARKINGS, EPOXY, SOLID, YELLOW, CROSSHATCH LINE,	216.000	LFT
19	808-74805 TRANSVERSE MARKINGS, EPOXY, STOP LINE, 24 IN.	48.000	LFT
20	808-74807 PAVEMENT MESSAGE MARKINGS, EPOXY, LANE INDICATIONS ARROWS	7.000	EACH
21	808-74808 PAVEMENT MESSAGE MARKINGS, EPOXY, WORD (ONLY)	7.000	EACH
22	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	84,756.000	LFT
23	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	12,136.000	LFT
24	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	47,425.000	LFT
25	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	295.000	LFT
26	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	48.000	LFT
27	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	4.000	EACH
28	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	2.000	EACH
29	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,215.000	EACH

CALL ORDER : 251

CONTRACT ID : SRS-29178-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	44.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	19.000	SYS
11	202-90277 DETECTOR HOUSING, REMOVE	61.000	EACH
12	304-07491 HMA PATCHING, TYPE C	502.000	TON
13	306-08036 MILLING, ASPHALT, 2 IN.	30,300.000	SYS
14	306-08043 MILLING, TRANSITION	1,400.000	SYS
15	306-08432 MILLING, APPROACH	3,114.000	SYS
16	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
17	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	3,333.000	TON
18	402-07452 HMA WEDGE AND LEVEL, TYPE C	50.000	TON
19	406-05520 ASPHALT FOR TACK COAT	9.000	TON
20	604-06070 SIDEWALK, CONCRETE	19.000	SYS
21	604-07897 CURB RAMP, CONCRETE, C	4.000	SYS
22	604-07900 CURB RAMP, CONCRETE, F	93.000	SYS
23	604-07901 CURB RAMP, CONCRETE, G	6.000	SYS
24	604-07902 CURB RAMP, CONCRETE, H	8.000	SYS
25	605-01870 CURB, CONCRETE, A	28.000	LFT
26	605-06090 CURB, INTEGRAL, CONCRETE	16.000	LFT
27	610-07488 HMA FOR APPROACHES, TYPE C	342.000	TON
28	621-06574 SODDING	50.000	SYS
29	628-09401 FIELD OFFICE, A	6.000	MOS
30	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
31	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	1.000	EACH
32	720-44000 CASTING, ADJUST TO GRADE	21.000	EACH
33	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
34	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	2,164.000	LFT
35	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,164.000	LFT
36	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
37	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
38	801-06710 FLASHING ARROW SIGN	120.000	DAY
39	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
40	805-02327 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	2.000	EACH
41	805-02503 CABLE, ROADWAY LOOP, 1C 14GA.	28,000.000	LFT
42	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	2,800.000	LFT
43	805-78785 SIGNAL DETECTOR HOUSING	61.000	EACH
44	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	8,960.000	LFT
45	808-06694 LINE, PAINT, SOLID, YELLOW, 8 IN.	320.000	LFT
46	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1,760.000	LFT
47	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,200.000	LFT
48	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN.	150.000	LFT
49	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,400.000	LFT

CALL ORDER : 251

CONTRACT ID : SRS-29178-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	365.000	LFT
51	808-06723 PAVEMENT MESSAGE MARKINGS, PAINT, LANE INDICATION ARROW	8.000	EACH
52	808-06724 PAVEMENT MESSAGE MARKINGS, PAINT, WORD ONLY	3.000	EACH
53	808-74815 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 12 IN.	800.000	LFT
54	808-75078 TRANSVERSE MARKINGS, PAINT, SOLID, YELLOW CROSSHATCH LINE,	160.000	LFT
55	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	150.000	LFT
56	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4,380.000	LFT
57	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	150.000	LFT
58	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	979.000	LFT
59	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	43.000	EACH
60	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	20.000	EACH
61	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	50.000	EACH
62	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	600.000	LFT

CALL ORDER : 271

CONTRACT ID : SRS-29809-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02278 CURB, CONCRETE, REMOVE	218.000	LFT
10	202-52710 SIDEWALK, CONCRETE, REMOVE	144.000	SYS
11	202-90277 DETECTOR HOUSING, REMOVE	2.000	EACH
12	303-01180 COMPACTED AGGREGATE, NO. 53	561.000	TON
13	304-07491 HMA PATCHING, TYPE C	1,383.000	TON
14	306-08034 MILLING, ASPHALT, 1 1/2 IN.	246,323.000	SYS
15	306-08043 MILLING, TRANSITION	2,610.000	SYS
16	306-08432 MILLING, APPROACH	19,109.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	20,322.000	TON
19	402-07452 HMA WEDGE AND LEVEL, TYPE C	100.000	TON
20	406-05520 ASPHALT FOR TACK COAT	54.000	TON
21	604-06070 SIDEWALK, CONCRETE	144.000	SYS
22	604-06367 JOINT MATERIAL	100.000	LFT
23	604-07896 CURB RAMP, CONCRETE, B	275.000	SYS
24	604-07897 CURB RAMP, CONCRETE, C	7.000	SYS
25	604-07901 CURB RAMP, CONCRETE, G	42.000	SYS
26	604-07902 CURB RAMP, CONCRETE, H	39.000	SYS
27	605-01870 CURB, CONCRETE, A	140.000	LFT
28	605-06090 CURB, INTEGRAL, CONCRETE	78.000	LFT
29	610-07488 HMA FOR APPROACHES, TYPE C	1,576.000	TON
30	612-04315 ASPHALT MATERIAL FOR UNDERSEAL	2.000	TON
31	612-60410 DRILLED HOLE FOR UNDERSEAL	32.000	EACH
32	621-06574 SODDING	60.000	SYS
33	628-09402 FIELD OFFICE, B	8.000	MOS
34	720-44000 CASTING, ADJUST TO GRADE	68.000	EACH
35	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
36	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	16,789.000	LFT
37	801-06209 TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	16,789.000	LFT
38	801-06640 CONSTRUCTION SIGN, A	144.000	EACH
39	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
40	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
41	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	6,500.000	LFT
42	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	650.000	LFT
43	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
44	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,080.000	LFT
45	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	14.000	EACH
46	808-01296 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORDS (STOP AHEAD)	1.000	EACH
47	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	486.000	LFT
48	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3,609.000	LFT
49	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	110,301.000	LFT

CALL ORDER : 271

CONTRACT ID : SRS-29809-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	11,547.000	LFT
51	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	52,429.000	LFT
52	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	249.000	LFT
53	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	295.000	LFT
54	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
55	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	4.000	EACH
56	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,207.000	EACH
57	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,207.000	EACH
58	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	21.000	EACH
59	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1,640.000	LFT

CALL ORDER : 281

CONTRACT ID : SRS-29811-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-90277 DETECTOR HOUSING, REMOVE	2.000	EACH
9	303-01180 COMPACTED AGGREGATE, NO. 53	30.000	TON
10	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
11	304-07491 HMA PATCHING, TYPE C	317.000	TON
12	306-08042 MILLING, SCARIFICATION/PROFILE	2,664.000	SYS
13	306-08043 MILLING, TRANSITION	403.000	SYS
14	306-08432 MILLING, APPROACH	10,087.000	SYS
15	402-07452 HMA WEDGE AND LEVEL, TYPE C	50.000	TON
16	402-09282 ULTRATHIN BONDED WEARING COURSE SIZE 3/8 IN.	120,325.000	SYS
17	406-05520 ASPHALT FOR TACK COAT	0.500	TON
18	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
19	628-09402 FIELD OFFICE, B	6.000	MOS
20	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
22	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4,600.000	LFT
23	801-06640 CONSTRUCTION SIGN, A	44.000	EACH
24	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
25	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,250.000	LFT
26	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	170.000	LFT
27	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
28	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	400.000	LFT
29	808-02157 PAVEMENT MESSAGE MARKINGS, REMOVE	3.000	EACH
30	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
31	808-05929 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 8 IN.	658.000	LFT
32	808-06368 TRANSVERSE MARKING, REMOVE	1,000.000	LFT
33	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	9,200.000	LFT
34	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	6,231.000	LFT
35	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	71,367.000	LFT
36	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	45,452.000	LFT
37	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	750.000	LFT
38	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	212.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	1.000	EACH

CALL ORDER : 291

CONTRACT ID : SRS-30033-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	670.000	LFT
13	202-02277 GUTTER, LIP, REMOVE	500.000	LFT
14	202-60815 CENTER CURB, REMOVE	779.000	LFT
15	202-93741 GUARD RAIL END TREATMENT, REMOVE	23.000	EACH
16	203-08607 LINEAR GRADING	1,215.000	LFT
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	530.000	TON
18	303-07449 COMPACTED AGGREGATE, NO. 73	200.000	TON
19	304-07492 WIDENING WITH HMA, TYPE A	982.000	TON
20	304-07783 HMA PATCHING, TYPE D	150.000	TON
21	306-08036 MILLING, ASPHALT, 2 IN.	105,230.000	SYS
22	306-08043 MILLING, TRANSITION	960.000	SYS
23	306-08432 MILLING, APPROACH	2,800.000	SYS
24	306-08595 MILLING ASPHALT, 3 1/2 IN.	29,860.000	SYS
25	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
26	401-07348 QC/QA-HMA, 4, 70, SURFACE, 12.5 mm	15,100.000	TON
27	406-05520 ASPHALT FOR TACK COAT	35.000	TON
28	601-06035 GUARDRAIL, RESET	1,500.000	LFT
29	601-94689 GUARDRAIL END TREATMENT, OS	19.000	EACH
30	601-94690 GUARDRAIL END TREATMENT, MS	4.000	EACH
31	605-04510 LIP GUTTER	3,750.000	LFT
32	605-06255 CENTER CURB, D, CONCRETE	780.000	SYS
33	605-52807 CURB AND GUTTER, COMBINED	450.000	LFT
34	621-06559 MULCHED SEEDING, R	1,180.000	SYS
35	628-09402 FIELD OFFICE, B	12.000	MOS
36	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
37	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	5.000	LFT
38	720-44000 CASTING, ADJUST TO GRADE	40.000	EACH
39	720-44296 CAP INLET	1.000	EACH
40	720-45042 INLET, HA5	1.000	EACH
41	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
43	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	3,886.000	LFT
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,886.000	LFT
45	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
46	801-06710 FLASHING ARROW SIGN	300.000	DAY
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
49	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN.	1,100.000	LFT

CALL ORDER : 291

CONTRACT ID : SRS-30033-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN.	4,375.000	LFT
51	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN.	4,375.000	LFT
52	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4,910.000	LFT
53	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	43,150.000	LFT
54	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	400.000	LFT
55	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	395.000	LFT
56	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	43,800.000	LFT
57	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	220.000	LFT
58	808-75278 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, YELLOW,	130.000	LFT
59	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	100.000	LFT
60	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	450.000	EACH
61	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	450.000	EACH
62	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	344.000	LFT
63	808-95933 CURB PAINTING, YELLOW	25,650.000	LFT

CALL ORDER : 301

CONTRACT ID : SRS-30057-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02278 CURB, CONCRETE, REMOVE	20.000	LFT
13	202-52710 SIDEWALK, CONCRETE, REMOVE	10.000	SYS
14	303-07449 COMPACTED AGGREGATE, NO. 73	365.000	TON
15	304-07490 HMA PATCHING, TYPE B	500.000	TON
16	306-08034 MILLING, ASPHALT, 1 1/2 IN.	155,885.000	SYS
17	306-08043 MILLING, TRANSITION	1,500.000	SYS
18	306-08432 MILLING, APPROACH	10,565.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	12,865.000	TON
21	402-07451 HMA WEDGE AND LEVEL, TYPE B	500.000	TON
22	406-05520 ASPHALT FOR TACK COAT	46.000	TON
23	604-06070 SIDEWALK, CONCRETE	10.000	SYS
24	604-07897 CURB RAMP, CONCRETE, C	56.000	SYS
25	605-01870 CURB, CONCRETE, A	20.000	LFT
26	610-07487 HMA FOR APPROACHES, TYPE B	875.000	TON
27	621-06574 SODDING	50.000	SYS
28	628-09402 FIELD OFFICE, B	6.000	MOS
29	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
30	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
31	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
32	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,235.000	LFT
33	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,235.000	LFT
34	801-06640 CONSTRUCTION SIGN, A	53.000	EACH
35	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	808-01226 SNOWPLOWABLE RAISED PAVEMENT MARKER CASTING, INSTALL	5.000	EACH
38	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	25,735.000	LFT
39	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	104,665.000	LFT
40	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	69,350.000	LFT
41	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,310.000	EACH
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,310.000	EACH

CALL ORDER : 311

CONTRACT ID : SRS-30073-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	303-07449 COMPACTED AGGREGATE, NO. 73	200.000	TON
13	304-07491 HMA PATCHING, TYPE C	10.000	TON
14	306-08033 MILLING, ASPHALT, 1 IN.	176,300.000	SYS
15	306-08041 MILLING, PCCP	830.000	SYS
16	306-08043 MILLING, TRANSITION	1,500.000	SYS
17	306-08432 MILLING, APPROACH	16,343.000	SYS
18	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
19	401-07347 QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	19,400.000	TON
20	406-05520 ASPHALT FOR TACK COAT	42.000	TON
21	610-07488 HMA FOR APPROACHES, TYPE C	1,800.000	TON
22	615-06527 MONUMENT, SECTION CORNER	13.000	EACH
23	628-09402 FIELD OFFICE, B	6.000	MOS
24	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
25	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
26	725-06866 PIPE LINER, THERMOPLASTIC, 15 IN.	45.000	LFT
27	725-06867 PIPE LINER, THERMOPLASTIC, 18 IN.	105.000	LFT
28	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
29	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
30	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,291.000	LFT
31	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,291.000	LFT
32	801-06640 CONSTRUCTION SIGN, A	28.000	EACH
33	801-06710 FLASHING ARROW SIGN	90.000	DAY
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
36	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	111,380.000	LFT
37	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	10,250.000	LFT
38	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	35,471.000	LFT
39	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	954.000	EACH
40	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	954.000	EACH

CALL ORDER : 321

CONTRACT ID : SRS-30082-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	18.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	303-07449 COMPACTED AGGREGATE, NO. 73	6,784.000	TON
13	304-07491 HMA PATCHING, TYPE C	1,081.000	TON
14	306-08033 MILLING, ASPHALT, 1 IN.	150,000.000	SYS
15	306-08043 MILLING, TRANSITION	800.000	SYS
16	306-08432 MILLING, APPROACH	15,200.000	SYS
17	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
18	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	11,730.000	TON
19	406-05520 ASPHALT FOR TACK COAT	72.000	TON
20	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	5.000	EACH
21	628-09402 FIELD OFFICE, B	6.000	MOS
22	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
23	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	18,501.000	LFT
24	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,250.000	LFT
25	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
26	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
27	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	6.000	EACH
28	805-02441 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,360.000	LFT
29	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	2,360.000	LFT
30	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
31	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	177.000	LFT
32	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	83,482.000	LFT
33	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	9,190.000	LFT
34	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	11,887.000	LFT
35	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	800.000	EACH
36	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	790.000	EACH

CALL ORDER : 331

CONTRACT ID : SRS-30472-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	605.000	LFT
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	8.000	EACH
14	203-02070 BORROW	81.000	CYS
15	303-01180 COMPACTED AGGREGATE, NO. 53	650.000	TON
16	304-07490 HMA PATCHING, TYPE B	2,450.000	TON
17	306-08042 MILLING, SCARIFICATION/PROFILE	82,300.000	SYS
18	306-08043 MILLING, TRANSITION	3,410.000	SYS
19	306-08432 MILLING, APPROACH	2,725.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	8,600.000	TON
22	402-07451 HMA WEDGE AND LEVEL, TYPE B	530.000	TON
23	406-05520 ASPHALT FOR TACK COAT	22.400	TON
24	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
25	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
26	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	255.000	LFT
27	610-07487 HMA FOR APPROACHES, TYPE B	250.000	TON
28	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
29	621-06559 MULCHED SEEDING, R	390.000	SYS
30	628-09402 FIELD OFFICE, B	6.000	MOS
31	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
32	706-08188 RAILING, TR	250.000	LFT
33	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
34	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	3,445.000	LFT
35	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,445.000	LFT
36	801-06640 CONSTRUCTION SIGN, A	33.000	EACH
37	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
38	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WORD (RR)	2.000	EACH
39	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	7,410.000	LFT
40	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	68,850.000	LFT
41	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	14,325.000	LFT
42	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	83.000	LFT
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	543.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	544.000	EACH

CALL ORDER : 341

CONTRACT ID : SRS-30568-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	20.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	263.000	LFT
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	28.000	EACH
14	203-02070 BORROW	7.000	CYS
15	303-07449 COMPACTED AGGREGATE, NO. 73	1,800.000	TON
16	304-07491 HMA PATCHING, TYPE C	1,625.000	TON
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	6,000.000	SYS
18	306-08042 MILLING, SCARIFICATION/PROFILE	153,750.000	SYS
19	306-08043 MILLING, TRANSITION	1,600.000	SYS
20	306-08432 MILLING, APPROACH	6,150.000	SYS
21	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
22	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	13,200.000	TON
23	402-07452 HMA WEDGE AND LEVEL, TYPE C	100.000	TON
24	406-05520 ASPHALT FOR TACK COAT	43.000	TON
25	506-06333 PCCP PATCHING, FULL DEPTH	170.000	SYS
26	506-06334 PCCP PATCHING, PARTIAL DEPTH	20.000	SYS
27	507-07482 CRACKS AND JOINTS IN PCCP, ROUT AND SEAL	6,300.000	LFT
28	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	3.000	EACH
29	601-01740 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 4	2.000	EACH
30	601-94689 GUARDRAIL END TREATMENT, OS	23.000	EACH
31	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	25.000	LFT
32	610-07488 HMA FOR APPROACHES, TYPE C	506.000	TON
33	621-06559 MULCHED SEEDING, R	20.000	SYS
34	628-09402 FIELD OFFICE, B	10.000	MOS
35	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
36	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
37	801-06198 PATROLLER	10.000	DAY
38	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	5,100.000	LFT
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5,100.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	41.000	EACH
41	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
42	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	3,650.000	LFT
43	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	103,350.000	LFT
44	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	84,350.000	LFT
45	808-06726 TRANSVERSE MARKINGS, PAINT, STOP LINE, 24 IN.	67.000	LFT
46	808-75008 LINE, PAINT, SOLID, WHITE, 8 IN.	850.000	LFT
47	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	39.000	LFT
48	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,115.000	EACH
49	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,118.000	EACH

CALL ORDER : 351

CONTRACT ID : SRS-30604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	35.000	LFT
13	202-90277 DETECTOR HOUSING, REMOVE	7.000	EACH
14	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	95.000	TON
16	303-07449 COMPACTED AGGREGATE, NO. 73	17.000	TON
17	304-07491 HMA PATCHING, TYPE C	75.000	TON
18	304-07783 HMA PATCHING, TYPE D	509.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN.	28,140.000	SYS
20	306-08432 MILLING, APPROACH	4,375.000	SYS
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	902.000	TON
22	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1,288.000	TON
23	402-07432 HMA SURFACE, TYPE A	141.000	TON
24	406-05520 ASPHALT FOR TACK COAT	9.000	TON
25	507-07479 HMA PARTIAL DEPTH PATCH	208.000	TON
26	507-07479 HMA PARTIAL DEPTH PATCH	604.000	TON
27	601-09238 HAND DIG GUARDRAIL POST HOLES	4.000	EACH
28	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
29	604-07894 CURB RAMP, CONCRETE, A	35.000	SYS
30	604-07900 CURB RAMP, CONCRETE, F	229.000	SYS
31	604-07900 CURB RAMP, CONCRETE, F	14.000	SYS
32	604-07901 CURB RAMP, CONCRETE, G	25.000	SYS
33	604-07901 CURB RAMP, CONCRETE, G	15.000	SYS
34	604-07902 CURB RAMP, CONCRETE, H	89.000	SYS
35	610-07486 HMA FOR APPROACHES, TYPE A	361.000	TON
36	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	1.000	EACH
37	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
38	628-09409 MOBILE INTERNET SERVICE	5.000	MOS
39	720-45615 STRUCTURE, INLET, RECONSTRUCT	3.000	LFT
40	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
41	720-45610 STRUCTURE, CATCH BASIN, RECONSTRUCT	4.000	LFT
42	720-99315 CLEAN EXISTING CATCH BASINS	1.000	EACH
43	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
44	801-05954 TEMPORARY PAVEMENT MESSAGE MARKING	12.000	EACH
45	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	710.000	LFT
46	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	710.000	LFT
47	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	5.000	EACH
48	801-06640 CONSTRUCTION SIGN, A	49.000	EACH
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 351

CONTRACT ID : SRS-30604-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	801-92448 CONSTRUCTION SIGNS, MOBILE	720.000	DAY
51	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	2,750.000	LFT
52	805-78785 SIGNAL DETECTOR HOUSING	7.000	EACH
53	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	860.000	LFT
54	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	50.000	LFT
55	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,060.000	LFT
56	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	663.000	LFT
57	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,070.000	LFT
58	808-75256 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	280.000	LFT
59	808-75260 TRANSVERSE MARKINGS, THERMOPLASTIC, SOLID, WHITE, CROSSHATCH	32.000	LFT
60	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	247.000	LFT
61	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	964.000	LFT
62	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	17.000	EACH
63	808-75325 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	12.000	EACH
64	808-75340 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
65	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	53.000	EACH

CALL ORDER : 361

CONTRACT ID : SRS-30605-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-93135 RAILROAD CROSSING, REMOVE	LUMP	LUMP
13	202-93741 GUARD RAIL END TREATMENT, REMOVE	1.000	EACH
14	203-02000 EXCAVATION, COMMON	142.000	CYS
15	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	284.000	TON
16	304-07490 HMA PATCHING, TYPE B	2,472.000	TON
17	306-08034 MILLING, ASPHALT, 1 1/2 IN.	35,644.000	SYS
18	306-08432 MILLING, APPROACH	3,131.000	SYS
19	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
20	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,943.000	TON
21	406-05520 ASPHALT FOR TACK COAT	12.200	TON
22	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
23	604-07897 CURB RAMP, CONCRETE, C	16.200	SYS
24	604-07898 CURB RAMP, CONCRETE, D	5.400	SYS
25	604-07899 CURB RAMP, CONCRETE, E	64.200	SYS
26	604-07901 CURB RAMP, CONCRETE, G	112.700	SYS
27	604-07902 CURB RAMP, CONCRETE, H	12.600	SYS
28	604-07903 CURB RAMP, CONCRETE, K	17.800	SYS
29	610-07487 HMA FOR APPROACHES, TYPE B	261.000	TON
30	615-06520 MONUMENT, RE-ESTABLISH	2.000	EACH
31	615-06525 CASTING ADJUSTED TO GRADE, MONUMENT	2.000	EACH
32	628-09402 FIELD OFFICE, B	6.000	MOS
33	720-44000 CASTING, ADJUST TO GRADE	18.000	EACH
34	720-44045 CASTING, 8, FURNISH AND ADJUST TO GRADE	2.000	EACH
35	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	1.000	EACH
36	720-45605 STRUCTURE, MANHOLE, RECONSTRUCT	8.000	LFT
37	720-45615 STRUCTURE, INLET, RECONSTRUCT	6.000	LFT
38	720-94840 CASTING, ADJUST TO GRADE, WATER VALVE	2.000	EACH
39	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
40	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	985.000	LFT
41	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	985.000	LFT
42	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-92448 CONSTRUCTION SIGNS, MOBILE	450.000	DAY
45	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7,616.000	LFT
46	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	205.000	LFT
47	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16,430.000	LFT
48	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	21.000	LFT
49	808-75300 TRANSVERSE MARKINGS, THERMOPLASTIC, CROSSWALK LINE, 6 IN.	174.000	LFT

CALL ORDER : 361

CONTRACT ID : SRS-30605-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
50 808-75340	PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD, RXR	2.000	EACH
51 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	122.000	EACH

CALL ORDER : 371

CONTRACT ID : SRS-30676-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CONCRETE PAEMENT CLEANING AND SEALING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	305-93342 SAW, CLEAN AND SEAL TRANSVERSE JOINTS	335.000	LFT
11	503-05240 D-1 CONTRACTION JOINT	210.000	LFT
12	506-06333 PCCP PATCHING, FULL DEPTH	725.000	SYS
13	506-06334 PCCP PATCHING, PARTIAL DEPTH	56.000	SYS
14	507-07482 CRACKS AND JOINTS IN PCCP, ROUT AND SEAL	222,000.000	LFT
15	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
16	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	3.000	EACH
17	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	36.000	EACH
20	801-06710 FLASHING ARROW SIGN	80.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA.	1,708.000	LFT
23	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALER	616.000	LFT

CALL ORDER : 381

CONTRACT ID : SRS-31545-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 MICROSURFACING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-01180 COMPACTED AGGREGATE, NO. 53	40.000	TON
12	304-07491 HMA PATCHING, TYPE C	175.000	TON
13	306-08043 MILLING, TRANSITION	216.000	SYS
14	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	12.000	TON
15	411-09521 MICRO-SURFACING, WARRANTED, MULTIPLE COURSE	79,830.000	SYS
16	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
17	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
18	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
19	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,600.000	LFT
20	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	49,551.000	LFT
23	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	5,395.000	LFT
24	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17,216.000	LFT
25	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	488.000	EACH
26	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	488.000	EACH

CALL ORDER : 391

CONTRACT ID : SRS-31795-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	304-07491 HMA PATCHING, TYPE C	200.000	TON
12	406-05520 ASPHALT FOR TACK COAT	0.500	TON
13	411-09520 MICRO-SURFACING, WARRANTED, MULTIPLE COURSE	142,200.000	SYS
14	628-09402 FIELD OFFICE, B	3.000	MOS
15	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
16	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	9.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	14,900.000	LFT
19	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	100.000	LFT
20	801-06640 CONSTRUCTION SIGN, A	49.000	EACH
21	801-06710 FLASHING ARROW SIGN	400.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-92448 CONSTRUCTION SIGNS, MOBILE	800.000	DAY
24	808-02157 PAVEMENT MESSAGE MARKINGS, REMOVE	9.000	EACH
25	808-06368 TRANSVERSE MARKING, REMOVE	100.000	LFT
26	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	11,200.000	LFT
27	808-06716 LINE, REMOVE	111,500.000	LFT
28	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	55,200.000	LFT
29	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	44,800.000	LFT
30	808-75297 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 24 IN.	100.000	LFT
31	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	9.000	EACH
32	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	861.000	EACH
33	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	861.000	EACH
34	808-97323 LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	290.000	LFT

CALL ORDER : 431

CONTRACT ID : SB -28077-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	202-74035 SIGN, REMOVE	10.000	EACH
13	203-02000 EXCAVATION, COMMON	6,690.700	CYS
14	203-02020 EXCAVATION, UNCLASSIFIED	18.600	CYS
15	203-51223 EXCAVATION, WATERWAY	211.200	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	134.420	TON
17	205-06932 TEMPORARY CHECK DAM, STRAW BALES	422.500	LFT
18	205-06937 TEMPORARY SILT FENCE	150.000	LFT
19	206-51220 EXCAVATION, WET	78.100	CYS
20	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,527.200	SYS
21	211-09264 STRUCTURE BACKFILL, TYPE 1	161.400	CYS
22	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	6.500	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	743.000	TON
24	302-07455 DENSE GRADED SUBBASE	111.200	CYS
25	306-08043 MILLING, TRANSITION	320.000	SYS
26	402-07433 HMA SURFACE, TYPE B	298.800	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	437.000	TON
28	402-07441 HMA BASE, TYPE B	1,386.900	TON
29	406-05520 ASPHALT FOR TACK COAT	2.600	TON
30	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
31	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
33	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	300.000	LFT
34	602-06729 BARRIER DELINEATOR	6.000	EACH
35	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	163.300	SYS
36	610-07486 HMA FOR APPROACHES, TYPE A	22.700	TON
37	615-06490 RIGHT OF WAY MARKER	12.000	EACH
38	615-06505 MONUMENT, B	3.000	EACH
39	616-02320 GEOTEXTILES	823.400	SYS
40	616-05688 RIPRAP, CLASS 1	414.000	TON
41	616-06405 RIPRAP, REVETMENT	282.300	TON
42	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
43	621-06545 FERTILIZER	0.500	TON
44	621-06553 SEED MIXTURE, R	192.000	LBS
45	621-06565 MULCHING MATERIAL	2.300	TON
46	621-06567 WATER	7.600	KGAL
47	621-06574 SODDING	1,901.500	SYS
48	628-09401 FIELD OFFICE, A	6.000	MOS
49	701-02938 CORED HOLE IN ROCK, 24 IN.	16.000	LFT

CALL ORDER : 431

CONTRACT ID : SB -28077-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	701-51195 PILE, STEEL H, HP 12" X 53	91.100	LFT
51	701-91792 PILE TIP, STEEL H	8.000	EACH
52	702-51010 CONCRETE, B, ABOVE FOOTINGS	38.000	CYS
53	702-51015 CONCRETE, B, FOOTINGS	26.000	CYS
54	703-51030 REINFORCING STEEL	19,260.000	LBS
55	703-51032 REINFORCING STEEL, EPOXY COATED	21,992.000	LBS
56	704-51002 CONCRETE, C, SUPERSTRUCTURE	150.400	CYS
57	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
58	706-51020 CONCRETE, C, RAILING	14.900	CYS
59	709-51821 SURFACE SEAL	LUMP	LUMP
60	711-51864 DRILLED HOLE	20.000	EACH
61	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN.	100.000	LFT
62	715-05049 PIPE, TYPE 4, CIRCULAR, 8 IN.	100.000	LFT
63	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	100.000	LFT
64	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN.	40.000	LFT
65	715-05248 PIPE, TYPE 1, DEFORMED, 16.6 SQ. FT.	84.000	LFT
66	715-05840 CONCRETE ANCHOR, MIN. AREA 14.7 SQ.FT.	2.000	EACH
67	715-46005 PIPE END SECTION, 15 IN.	2.000	EACH
68	715-91361 PIPE, PVC, 6 IN.	41.200	LFT
69	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
70	801-06625 DETOUR ROUTE MARKER ASSEMBLY	23.000	EACH
71	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-07118 BARRICADE, III-A	96.000	LFT
74	801-07119 BARRICADE, III-B	96.000	LFT
75	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	57.000	LFT
76	802-76025 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 0.080 IN.	29.900	SFT
77	804-06725 DELINEATOR WITH POST, D1, 3 IN. DIA.	10.000	EACH
78	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,735.000	LFT
79	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,670.000	LFT
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	36.000	EACH

CALL ORDER : 441

CONTRACT ID : SB -28428-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE DECK REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
5	105-08523 RADIO SERVICE	12.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-02240 PAVEMENT REMOVAL	136.000	SYS
15	202-02241 GUARDRAIL, REMOVE	712.500	LFT
16	202-02276 GUTTER TURNOUT, REINFORCED CONCRETE, REMOVE	4.000	EACH
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	205-06937 TEMPORARY SILT FENCE	200.000	LFT
19	205-09543 NO 2 STONE	100.000	TON
20	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	48.000	CYS
21	211-06467 AGGREGATE FOR END BENT BACKFILL	40.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	123.000	TON
23	302-07455 DENSE GRADED SUBBASE	34.000	CYS
24	306-08043 MILLING, TRANSITION	220.000	SYS
25	402-07432 HMA SURFACE, TYPE A	17.000	TON
26	406-05521 ASPHALT FOR TACK COAT	960.000	SYS
27	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
28	601-07050 GUARDRAIL END TREATMENT, OS, RESET	4.000	EACH
29	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	850.000	LFT
30	602-06729 BARRIER DELINEATOR	10.000	EACH
31	607-95754 PAVED SIDE DITCH, BREAK	72.000	LFT
32	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	254.000	SYS
33	610-07487 HMA FOR APPROACHES, TYPE B	70.000	TON
34	616-02320 GEOTEXTILES	733.000	SYS
35	616-06405 RIPRAP, REVETMENT	499.000	TON
36	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	6,287.000	SFT
37	619-09434 PAINT STEEL BRIDGE, TYPE 1	6,287.000	SFT
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
39	621-06559 MULCHED SEEDING, R	167.000	SYS
40	621-06567 WATER	1.000	KGAL
41	621-06574 SODDING	32.000	SYS
42	628-09401 FIELD OFFICE, A	12.000	MOS
43	702-51100 DRAIN PIPE, CAST IRON, 6 IN.	400.000	LBS
44	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	2,576.000	LBS
45	702-51863 FIELD DRILLED HOLE IN CONCRETE	298.000	EACH
46	702-92857 CONCRETE, C, SUBSTRUCTURE	19.400	CYS
47	703-51032 REINFORCING STEEL, EPOXY COATED	64,067.000	LBS
48	704-51002 CONCRETE, C, SUPERSTRUCTURE	189.500	CYS
49	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH

CALL ORDER : 441

CONTRACT ID : SB -28428-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT		
50	706-51020 CONCRETE, C, RAILING	33.800	CYS
51	709-51821 SURFACE SEAL	LUMP	LUMP
52	710-51864 FIELD DRILLED HOLE	76.000	EACH
53	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
54	711-96800 STUD SHEAR CONNECTORS	1,836.000	EACH
55	715-05407 PIPE, END BENT DRAIN, 6 IN.	120.000	LFT
56	726-93524 BEARING ASSEMBLY, I	12.000	EACH
57	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
58	801-06625 DETOUR ROUTE MARKER ASSEMBLY	17.000	EACH
59	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
60	801-07118 BARRICADE, III-A	64.000	LFT
61	802-05701 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	8.170	LFT
62	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
63	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN.	103.000	LFT
64	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	1,012.000	LFT
65	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	2,013.000	LFT
66	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.000	EACH
67	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	7.000	EACH

CALL ORDER : 451

CONTRACT ID : SB -28733-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	40.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02241 GUARDRAIL, REMOVE	625.000	LFT
13	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
14	202-93741 GUARD RAIL END TREATMENT, REMOVE	4.000	EACH
15	203-02000 EXCAVATION, COMMON	837.000	CYS
16	203-02070 BORROW	100.000	CYS
17	205-03371 SEDIMENT, REMOVE	50.000	CYS
18	205-06937 TEMPORARY SILT FENCE	1,100.000	LFT
19	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	133.100	CYS
20	207-08263 SUBGRADE TREATMENT, TYPE IA	950.000	SYS
21	207-08266 SUBGRADE TREATMENT, TYPE III	350.000	SYS
22	211-06467 AGGREGATE FOR END BENT BACKFILL	48.000	CYS
23	211-09265 STRUCTURE BACKFILL, TYPE 2	8.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	400.000	TON
25	302-07455 DENSE GRADED SUBBASE	50.000	CYS
26	303-02051 STONE, NO 2	100.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN.	1,280.000	SYS
28	402-07432 HMA SURFACE, TYPE A	30.000	TON
29	402-07433 HMA SURFACE, TYPE B	80.000	TON
30	402-07434 HMA SURFACE, TYPE C	115.000	TON
31	402-07435 HMA INTERMEDIATE, TYPE A	40.000	TON
32	402-07438 HMA INTERMEDIATE, TYPE B	205.000	TON
33	406-05521 ASPHALT FOR TACK COAT	2,600.000	SYS
34	501-05110 CEMENT CONCRETE PAVEMENT, HIGH EARLY STRENGTH, 8 IN.	58.800	SYS
35	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
37	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
38	601-97774 GUARDRAIL END TREATMENT, OS, SPARE PARTS PACKAGE	2.000	EACH
39	601-97803 GUARDRAIL END TREATMENT, MS, SPARE PARTS PACKAGE	2.000	EACH
40	601-98352 BICYCLE RAILING	538.000	LFT
41	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	218.750	LFT
42	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT. 3 IN. SPACING	237.500	LFT
43	602-06729 BARRIER DELINEATOR	32.000	EACH
44	609-06263 REINFORCED CONCRETE BRIDGE APPROACH, 15 IN.	287.200	SYS
45	616-02320 GEOTEXTILES	1,443.000	SYS
46	616-05689 RIPRAP, CLASS 2	160.000	TON
47	616-06405 RIPRAP, REVETMENT	865.000	TON
48	619-09429 CLEAN STEEL BRIDGE, PARTIAL, TYPE 1, QP-2	2,363.400	SFT
49	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	22,943.000	SFT

CALL ORDER : 451

CONTRACT ID : SB -28733-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
50	621-06545 FERTILIZER	0.800	TON
51	621-06553 SEED MIXTURE, R	164.000	LBS
52	621-06557 SEED MIXTURE, T	145.000	LBS
53	621-06565 MULCHING MATERIAL	3.800	TON
54	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
55	628-09402 FIELD OFFICE, B	20.000	MOS
56	701-04732 PILE	96.000	LFT
57	701-05779 FURNISHING DRILLED SHAFT DRILLING EQUIPMENT	LUMP	LUMP
58	701-05780 DRILLED SHAFT CONCRETE	591.500	CYS
59	701-05781 UNCLASSIFIED SHAFT EXCAVATION	472.900	CYS
60	701-05782 UNCLASSIFIED EXTRA DEPTH EXCAVATION	16.800	CYS
61	701-05783 OBSTRUCTIONS	36.000	HRS
62	701-05784 TRIAL SHAFT HOLES	30.000	LFT
63	701-05785 EXPLORATION (SHAFT EXCAVATION)	120.000	LFT
64	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
65	701-51195 PILE, STEEL H, HP 12" X 53	1,077.000	LFT
66	701-91792 PILE TIP, STEEL H	18.000	EACH
67	701-97874 PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP 12" X 53	36.000	LFT
68	702-51005 CONCRETE, A, SUBSTRUCTURE	272.600	CYS
69	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	9,016.000	LBS
70	702-51863 FIELD DRILLED HOLE IN CONCRETE	648.000	EACH
71	702-93722 CONCRETE, C	658.300	CYS
72	703-01540 THREADED TIE BAR ASSEMBLY	206.000	EACH
73	703-06028 REINFORCING BARS	101,169.000	LBS
74	703-06029 REINFORCING BARS, EPOXY COATED	237,756.000	LBS
75	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	2,260.000	EACH
76	706-06339 RAILING, PF-1	511.440	LFT
77	706-06339 RAILING, PF-1	511.440	LFT
78	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.000	EACH
79	706-51020 CONCRETE, C, RAILING	63.100	CYS
80	709-51821 SURFACE SEAL	LUMP	LUMP
81	711-51038 STRUCTURAL STEEL	LUMP	LUMP
82	711-51864 DRILLED HOLE	714.000	EACH
83	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
84	711-96800 STUD SHEAR CONNECTORS	3,528.000	EACH
85	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN.	50.000	LFT
86	715-05407 PIPE, END BENT DRAIN, 6 IN.	116.000	LFT
87	715-46020 PIPE END SECTION, 24 IN.	2.000	EACH
88	715-91361 PIPE, PVC, 6 IN.	84.000	LFT
89	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	526.500	SFT
90	724-51925 STRUCTURAL EXPANSION JOINT, SS	107.900	LFT
91	726-58789 BEARING ASSEMBLY, ELASTOMERIC, II	27.000	EACH
92	726-99095 BEARING ASSEMBLY, ELASTOMERIC, I	54.000	EACH
93	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
94	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
95	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16,200.000	LFT
96	801-06218 TEMPORARY TRANSVERSE PAVMENT MARKING, REMOVABLE, 24 IN.	24.000	LFT
97	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
98	801-06645 CONSTRUCTION SIGN, B	5.000	EACH

CALL ORDER : 451

CONTRACT ID : SB -28733-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REHABILITATION			
99	801-06646	2.000	LFT
100	801-06775	LUMP	LUMP
101	801-07023	4.000	EACH
102	801-08508	2,085.000	LFT
103	808-03631	1,142.000	LFT
104	808-04896	143.000	LFT
105	808-06712	180.000	LFT
106	808-06713	1,440.000	LFT
107	808-06716	2,528.000	LFT
108	808-75996	17.000	EACH
109	808-75998	17.000	EACH

CALL ORDER : 461

CONTRACT ID : SB -29495-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	353.000	SYS
13	202-02241 GUARDRAIL, REMOVE	2,785.000	LFT
14	202-02277 GUTTER, LIP, REMOVE	4,069.000	LFT
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	202-51822 BRIDGE DECK OVERLAY, REMOVE	542.000	SYS
19	203-02000 EXCAVATION, COMMON	40.000	CYS
20	203-02070 BORROW	600.000	CYS
21	203-08607 LINEAR GRADING	4,192.000	LFT
22	205-06934 TEMPORARY MULCHING	3.000	TON
23	205-09543 NO 2 STONE	308.000	TON
24	302-07455 DENSE GRADED SUBBASE	82.000	CYS
25	306-08034 MILLING, ASPHALT, 1 1/2 IN.	799.000	SYS
26	306-08043 MILLING, TRANSITION	400.000	SYS
27	406-05521 ASPHALT FOR TACK COAT	1,375.000	SYS
28	601-01522 GUARDRAIL TRANSITION TYPE TGB	12.000	EACH
29	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
30	601-06037 GUARDRAIL END TREATMENT, I	4.000	EACH
31	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
32	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	1,919.000	LFT
33	601-99123 GUARDRAIL TRANSITION, GP	8.000	EACH
34	601-99132 GUARDRAIL TRANSITION, VH, 6 FT. 3 IN. SPACING	12.000	EACH
35	602-06729 BARRIER DELINEATOR	38.000	EACH
36	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	162.000	SYS
37	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	322.000	SYS
38	610-07486 HMA FOR APPROACHES, TYPE A	274.000	TON
39	610-07487 HMA FOR APPROACHES, TYPE B	366.000	TON
40	616-02320 GEOTEXTILES	1,395.000	SYS
41	616-06405 RIPRAP, REVETMENT	983.000	TON
42	619-09429 CLEAN STEEL BRIDGE, PARTIAL, TYPE 1, QP-2	6,151.000	SFT
43	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	6,151.000	SFT
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
45	621-06559 MULCHED SEEDING, R	1,850.000	SYS
46	628-09402 FIELD OFFICE, B	6.000	MOS
47	702-51005 CONCRETE, A, SUBSTRUCTURE	5.000	CYS
48	702-51863 FIELD DRILLED HOLE IN CONCRETE	1,004.000	EACH
49	703-08247 EMBEDDED GALVANIC ANODE	40.000	EACH

CALL ORDER : 461

CONTRACT ID : SB -29495-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
50	703-51030 REINFORCING STEEL	606.000	LBS
51	703-51032 REINFORCING STEEL, EPOXY COATED	57,257.000	LBS
52	704-51001 CONCRETE, A, IN SUPERSTRUCTURE	15.100	CYS
53	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	12.000	EACH
54	706-51025 CONCRETE, C, RAILING	1,299.500	LFT
55	709-51821 SURFACE SEAL	LUMP	LUMP
56	709-51821 SURFACE SEAL	LUMP	LUMP
57	709-51821 SURFACE SEAL	LUMP	LUMP
58	710-09158 PATCHING CONCRETE STRUCTURES	220.000	SFT
59	720-44296 CAP INLET	16.000	EACH
60	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	1,410.000	SFT
61	722-51842 BRIDGE DECK OVERLAY	1,842.000	SYS
62	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	38.800	CYS
63	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	3,560.000	SFT
64	722-60824 SURFACE MILLING	1,597.000	SYS
65	724-51925 STRUCTURAL EXPANSION JOINT, SS	117.000	LFT
66	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
67	801-04308 ROAD CLOSURE SIGN ASSEMBLY	11.000	EACH
68	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
69	801-06640 CONSTRUCTION SIGN, A	66.000	EACH
70	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
71	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	8.000	EACH
72	801-07118 BARRICADE, III-A	288.000	LFT
73	801-07119 BARRICADE, III-B	120.000	LFT
74	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,060.000	LFT
75	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	1,280.000	LFT
76	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	6.000	EACH
77	802-02158 SIGN, PANEL, REMOVE AND REINSTALL	6.000	EACH

CALL ORDER : 471

CONTRACT ID : SB -29561-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	26.700	SYS
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	231.000	CYS
12	203-02070 BORROW	287.000	CYS
13	205-03371 SEDIMENT, REMOVE	3.000	CYS
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	50.000	LFT
15	205-06937 TEMPORARY SILT FENCE	885.000	LFT
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	342.200	SYS
17	207-08268 SUBGRADE TREATMENT, TYPE IV	668.600	SYS
18	211-06467 AGGREGATE FOR END BENT BACKFILL	71.500	CYS
19	211-09265 STRUCTURE BACKFILL, TYPE 2	49.900	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	341.700	TON
21	302-07455 DENSE GRADED SUBBASE	56.400	CYS
22	306-08036 MILLING, ASPHALT, 2 IN.	504.000	SYS
23	306-08043 MILLING, TRANSITION	533.300	SYS
24	402-07432 HMA SURFACE, TYPE A	48.400	TON
25	402-07434 HMA SURFACE, TYPE C	89.000	TON
26	402-07435 HMA INTERMEDIATE, TYPE A	149.700	TON
27	402-07439 HMA INTERMEDIATE, TYPE C	134.800	TON
28	402-07442 HMA BASE, TYPE C	16.100	TON
29	402-07453 HMA FOR TEMPORARY PAVEMENT	112.200	TON
30	406-05520 ASPHALT FOR TACK COAT	0.810	TON
31	601-01128 GUARDRAIL TRANSITION TYPE WGB	4.000	EACH
32	601-01625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 1	1.000	EACH
33	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
34	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
35	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
36	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	37.500	LFT
38	602-06729 BARRIER DELINEATOR	8.000	EACH
39	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	338.200	SYS
40	610-07487 HMA FOR APPROACHES, TYPE B	94.100	TON
41	615-06505 MONUMENT, B	2.000	EACH
42	616-02320 GEOTEXTILES	332.000	SYS
43	616-06405 RIPRAP, REVETMENT	570.000	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
45	621-06545 FERTILIZER	0.100	TON
46	621-06557 SEED MIXTURE, T	10.000	LBS
47	621-06560 MULCHED SEEDING, U	200.000	SYS
48	621-06565 MULCHING MATERIAL	0.100	TON
49	621-06567 WATER	2.800	KGAL

CALL ORDER : 471

CONTRACT ID : SB -29561-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06575 SODDING, NURSERY	785.000	SYS
51	628-09402 FIELD OFFICE, B	6.000	MOS
52	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
53	701-51195 PILE, STEEL H, HP 12" X 53	208.000	LFT
54	701-91792 PILE TIP, STEEL H	16.000	EACH
55	701-92043 CORED HOLE IN ROCK, 18 IN.	40.000	LFT
56	703-06029 REINFORCING BARS, EPOXY COATED	50,875.000	LBS
57	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	227.000	EACH
58	704-51002 CONCRETE, C, SUPERSTRUCTURE	255.100	CYS
59	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
60	706-51025 CONCRETE, C, RAILING	155.300	LFT
61	707-09311 STRUCTURAL MEMBERS, CONCRETE BOX BEAM,	606.000	LFT
62	709-51821 SURFACE SEAL	LUMP	LUMP
63	715-05051 PIPE, TYPE 4, CIRCULAR, 10 IN.	25.000	LFT
64	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN.	166.000	LFT
65	715-05407 PIPE, END BENT DRAIN, 6 IN.	130.000	LFT
66	715-09064 VIDEO INSPECTION FOR PIPE	321.000	LFT
67	715-46000 PIPE END SECTION, 12 IN.	1.000	EACH
68	720-45030 INLET, E7	1.000	EACH
69	720-45035 INLET, F7	1.000	EACH
70	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
71	801-02617 TEMPORARY POLE, WOOD, WITH DOWN GUYS AND ANCHORS	2.000	EACH
72	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
73	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,960.000	LFT
74	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	40.000	LFT
75	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
76	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
77	801-06710 FLASHING ARROW SIGN	60.000	DAY
78	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
79	801-07119 BARRICADE, III-B	60.000	LFT
80	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	360.000	LFT
81	808-06716 LINE, REMOVE	681.000	LFT
82	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	934.000	LFT
83	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	2,660.000	LFT
84	808-75063 LINE, PREFORMED PLASTIC, BROKEN, YELLOW, 4 IN.	751.000	LFT
85	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.000	EACH
86	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	12.000	EACH

CALL ORDER : 481

CONTRACT ID : SB -29950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	26.000	MOS
5	105-08523 RADIO SERVICE	13.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-02240 PAVEMENT REMOVAL	371.000	m2
16	202-02241 GUARDRAIL, REMOVE	79.240	m
17	202-02272 PAVED SIDE DITCH, REMOVE	91.500	m
18	202-03000 HOUSES AND BUILDINGS, REMOVE	LUMP	LUMP
19	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
20	202-74035 SIGN, REMOVE	12.000	EACH
21	202-90747 RETAINING WALL, REMOVE	71.000	m3
22	202-91385 INLET, REMOVE	2.000	EACH
23	203-02000 EXCAVATION, COMMON	1,142.000	m3
24	203-51223 EXCAVATION, WATERWAY	5,716.500	m3
25	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	68.200	Mg
26	205-06933 TEMPORARY DITCH INLET PROTECTION	7.000	EACH
27	205-06937 TEMPORARY SILT FENCE	445.000	m
28	206-51220 EXCAVATION, WET	227.000	m3
29	207-08267 SUBGRADE TREATMENT, TYPE IIIA	492.300	m2
30	207-08268 SUBGRADE TREATMENT, TYPE IV	1,218.000	m2
31	211-09194 B BORROW	165.500	Mg
32	211-09265 STRUCTURE BACKFILL, TYPE 2	102.200	m3
33	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	96.200	Mg
34	302-07455 DENSE GRADED SUBBASE	212.700	m3
35	306-08034 MILLING, ASPHALT, 38 mm	6,352.000	m2
36	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	684.300	Mg
37	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 MM	1,140.500	Mg
38	402-07432 HMA SURFACE, TYPE A	36.100	Mg
39	402-07435 HMA INTERMEDIATE, TYPE A	48.700	Mg
40	402-07786 HMA BASE, TYPE D	837.600	Mg
41	406-05520 ASPHALT FOR TACK COAT	4.660	Mg
42	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
43	601-03871 RAILING, WOOD, END TREATMENT	1.000	EACH
44	601-03970 RAILING, WOOD, 1.372 m	24.000	m
45	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
46	601-07009 IMPACT ATTENUATOR, LS, W1, TL-1	2.000	EACH
47	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
48	601-99105 GUARDRAIL, W BEAM, 1.905 m SPACING	76.200	m
49	602-06729 BARRIER DELINEATOR	18.000	EACH

CALL ORDER : 481

CONTRACT ID : SB -29950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	604-06070 SIDEWALK, CONCRETE	756.000	m2
51	604-07902 CURB RAMP, CONCRETE, H	64.800	m2
52	605-05523 CURB, HMA	75.000	m
53	605-06140 CURB AND GUTTER, CONCRETE	719.000	m
54	609-06259 REINFORCED CONCRETE BRIDGE APPROACH, 300 mm	598.800	m2
55	610-09108 PCCP FOR APPROACHES, 225 mm	424.700	m2
56	611-06497 MAILBOX ASSEMBLY, SINGLE	6.000	EACH
57	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
58	615-06490 RIGHT OF WAY MARKER	12.000	EACH
59	615-06500 MONUMENT, A	3.000	EACH
60	616-02320 GEOTEXTILES	1,971.300	m2
61	616-06405 RIPRAP, REVETMENT	1,666.500	Mg
62	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
63	621-01743 SEED MIXTURE, GRASS, 2	65.600	kg
64	621-06545 FERTILIZER	0.100	Mg
65	621-06553 SEED MIXTURE, R	81.000	kg
66	621-06565 MULCHING MATERIAL	1.900	Mg
67	621-06567 WATER	26.600	kL
68	621-06574 SODDING	798.500	m2
69	621-06575 SODDING, NURSERY	424.000	m2
70	628-09402 FIELD OFFICE, B	13.000	MOS
71	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	26.000	MOS
72	701-01814 MOBILIZATION FOR DYNAMIC PILE MONITORING AND EQUIPMENT	1.000	EACH
73	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
74	701-06012 TEST PILE, RESTRIKE	2.000	EACH
75	701-91792 PILE TIP, STEEL H	70.000	EACH
76	701-93575 PILE, STEEL H, HP 356mm X 108	1,091.000	m
77	701-99155 SHEET PILING, STEEL, TEMPORARY	LUMP	LUMP
78	702-51005 CONCRETE, A, SUBSTRUCTURE	78.000	m3
79	702-51010 CONCRETE, B, ABOVE FOOTINGS	268.000	m3
80	702-51015 CONCRETE, B, FOOTINGS	32.000	m3
81	702-51100 DRAIN PIPE, CAST IRON, 150 mm	211.800	kg
82	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	522.600	kg
83	703-51030 REINFORCING STEEL	10,684.000	kg
84	703-51032 REINFORCING STEEL, EPOXY COATED	101,812.000	kg
85	704-51002 CONCRETE, C, SUPERSTRUCTURE	578.700	m3
86	706-06349 RAILING, TX	145.800	m
87	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	2.000	EACH
88	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	2.000	EACH
89	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM, III, 1143 mm X 406 mm	864.000	m
90	709-51821 SURFACE SEAL	LUMP	LUMP
91	714-44240 CONCRETE, A, STRUCTURES	22.800	m3
92	715-05048 PIPE, TYPE 4, CIRCULAR, 150 mm	579.000	m
93	715-05049 PIPE, TYPE 4, CIRCULAR, 200 mm	30.000	m
94	715-05051 PIPE, TYPE 4, CIRCULAR, 250 mm	30.000	m
95	715-05053 PIPE, UNDERDRAIN OUTLET, 150 mm	22.400	m
96	715-05115 PIPE, TYPE 1, CIRCULAR, 150 mm	70.000	m
97	715-05149 PIPE, TYPE 2, CIRCULAR, 300 mm	13.000	m
98	715-05151 PIPE, TYPE 2, CIRCULAR, 375 mm	13.000	m

CALL ORDER : 481

CONTRACT ID : SB -29950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE REPLACEMENT			
99	715-05152 PIPE, TYPE 2, CIRCULAR, 450 mm	143.000	m
100	715-05154 PIPE, TYPE 2, CIRCULAR, 600 mm	34.000	m
101	715-05173 PIPE, TYPE 3, CIRCULAR, 600 mm	18.000	m
102	715-05175 PIPE, TYPE 3, CIRCULAR, 750 mm	11.000	m
103	715-46010 PIPE END SECTION, 450 mm	3.000	EACH
104	715-46020 PIPE END SECTION, 600 mm	3.000	EACH
105	715-46030 PIPE END SECTION, 750 mm	2.000	EACH
106	715-97122 PIPE, PVC, 50 mm	193.000	m
107	718-06528 OUTLET PROTECTOR, 1	1.000	EACH
108	718-52610 AGGREGATE FOR UNDERDRAINS	103.400	m3
109	718-99153 GEOTEXTILES FOR UNDERRAIN	1,157.000	m2
110	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
111	720-45015 INLET, A8	9.000	EACH
112	720-45030 INLET, E7	3.000	EACH
113	720-45035 INLET, F7	2.000	EACH
114	720-45205 CATCH BASIN, A2	3.000	EACH
115	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
116	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 100 mm	3,992.000	m
117	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 200 mm	844.000	m
118	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
119	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
120	801-06775 MAINTAINING TRAFFIC BARRICADE, III-B	LUMP	LUMP
121	801-07119 TEMPORARY TRAFFIC BARRIER, TYPE 2	7.200	m
122	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	62.000	m
123	801-08508 SIGN POST, SQUARE, 1, REINFORCED ANCHOR BASE	166.000	m
124	802-05701 SIGN POST, SQUARE, 2, REINFORCED ANCHOR BASE	24.800	m
125	802-05702 SIGN, SHEET, ENCAPSULATED LENS WITH LEGEND, 2.03 mm	21.700	m
126	802-76025 DELINEATOR WITH POST, D1, 75 mm	2.500	m2
127	804-06725 LOOP, RESEAL	6.000	EACH
128	805-01744 LINE, THERMOPLASTIC, BROKEN, WHITE, 100mm	2.000	EACH
129	808-06701 LINE, THERMOPLASTIC, SOLID, WHITE, 100mm	1,016.000	m
130	808-06703 LINE, THERMOPLASTIC, BROKEN, YELLOW, 100mm	1,108.000	m
131	808-75240 LINE, THERMOPLASTIC, SOLID, YELLOW, 100mm	985.000	m
132	808-75245 TRANSVERSE MARKINGS, THERMOPLASTIC, STOP LINE, 600 mm	1,102.000	m
133	808-75297 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, LANE INDICATION	5.300	m
134	808-75320 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC, WORD (ONLY)	8.000	EACH
135	808-75325 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.000	EACH
136	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER	63.000	EACH
137	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	209.000	EACH

CALL ORDER : 491

CONTRACT ID : SB -30220-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE DECK REPLACEMENT AND WIDENING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	1.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL	1.000	DOL
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02240 PAVEMENT REMOVAL	185.000	SYS
14	202-02241 GUARDRAIL, REMOVE	2,392.000	LFT
15	202-02279 CURB AND GUTTER, REMOVE	2,733.000	LFT
16	202-02772 CASTING, REMOVE	9.000	EACH
17	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
18	202-91385 INLET, REMOVE	4.000	EACH
19	202-96133 PIPE, REMOVE	104.000	LFT
20	203-02000 EXCAVATION, COMMON	831.000	CYS
21	203-02020 EXCAVATION, UNCLASSIFIED	48.000	CYS
22	205-09543 NO 2 STONE	100.000	TON
23	211-06467 AGGREGATE FOR END BENT BACKFILL	48.000	CYS
24	213-09269 FLOWABLE BACKFILL, NON-REMOVEABLE	31.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,557.000	TON
26	306-08043 MILLING, TRANSITION	480.000	SYS
27	402-07433 HMA SURFACE, TYPE B	223.000	TON
28	402-07438 HMA INTERMEDIATE, TYPE B	29.000	TON
29	406-05520 ASPHALT FOR TACK COAT	0.400	TON
30	502-06329 PCCP, 12 IN.	64.000	SYS
31	503-05240 D-1 CONTRACTION JOINT	48.000	LFT
32	503-05310 TERMINAL JOINT	48.000	LFT
33	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
34	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT. 3 IN. SPACING	2,325.000	LFT
37	602-06729 BARRIER DELINEATOR	26.000	EACH
38	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN.	162.000	SYS
39	616-02320 GEOTEXTILES	384.000	SYS
40	616-06405 RIPRAP, REVETMENT	173.000	TON
41	616-51367 SLOPEWALL, CONCRETE, 4 IN.	238.000	SYS
42	616-93772 INSPECTION HOLE	2.000	EACH
43	619-09422 CLEAN STEEL BRIDGE, TYPE 1, QP-1	7,236.000	SFT
44	619-09434 PAINT STEEL BRIDGE, TYPE 1	7,236.000	SFT
45	621-06559 MULCHED SEEDING, R	2,062.000	SYS
46	621-06567 WATER	0.600	KGAL
47	621-06574 SODDING	164.000	SYS
48	628-09402 FIELD OFFICE, B	8.000	MOS
49	702-51005 CONCRETE, A, SUBSTRUCTURE	78.000	CYS

CALL ORDER : 491

CONTRACT ID : SB -30220-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK REPLACEMENT AND WIDENING		
50	702-51863 FIELD DRILLED HOLE IN CONCRETE	48.000	EACH
51	703-51030 REINFORCING STEEL	9,474.000	LBS
52	703-51032 REINFORCING STEEL, EPOXY COATED	64,389.000	LBS
53	704-51002 CONCRETE, C, SUPERSTRUCTURE	204.000	CYS
54	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
55	706-51020 CONCRETE, C, RAILING	39.000	CYS
56	708-51813 PNEUMATICALLY PLACED MORTAR	16.000	SFT
57	708-51814 WELDED STEEL WIRE FABRIC	16.000	SFT
58	709-51821 SURFACE SEAL	LUMP	LUMP
59	711-51038 STRUCTURAL STEEL	LUMP	LUMP
60	711-51864 DRILLED HOLE	672.000	EACH
61	711-51877 JACKING AND SUPPORTING BEAMS	LUMP	LUMP
62	711-92500 ANCHOR ROD	8.000	EACH
63	711-96526 FIELD WELDED STUD, 0.875 IN. DIA.	2,058.000	EACH
64	715-05407 PIPE, END BENT DRAIN, 6 IN.	125.000	LFT
65	720-44296 CAP INLET	9.000	EACH
66	722-09456 POLYMERIC OVERLAY SYSTEM	737.000	SYS
67	726-92406 BEARING ASSEMBLY, ELASTOMERIC	14.000	EACH
68	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
69	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
70	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
71	801-06625 DETOUR ROUTE MARKER ASSEMBLY	46.000	EACH
72	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
73	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
74	801-06710 FLASHING ARROW SIGN	30.000	DAY
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
77	801-07118 BARRICADE, III-A	96.000	LFT
78	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	760.000	LFT
79	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	480.000	LFT
80	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
81	802-02475 SIGN, PANEL, REMOVE AND RELOCATE	2.000	EACH
82	802-04893 REFERENCE POST	2.000	EACH
83	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
84	802-76160 BRIDGE BRACKET ASSEMBLY	2.000	EACH
85	805-96014 SAW CUT, FULL DEPTH	1,696.000	LFT
86	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.	3,356.000	LFT
87	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.	3,356.000	LFT

